



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT McCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

February 11, 2015

SUBJECT: ADDENDUM ONE FOR DE00105 – U-5118EM, INTERSECTION
IMPROVEMENTS AT NC 97 AND SR 2329 (MARSHBURN RD/LIZARD
LICK RD) IN WAKE COUNTY, WBS ELEMENT: 42379.3.FR27

MEMORANDUM TO PROSPECTIVE BIDDERS

This addendum is being issued to add standard size junction boxes to the project.

Attached please find the attached revised bid sheets, with the new item added for bidding purposes. Please substitute the new bid sheets for the bid sheets in the original proposal and acknowledge receipt of this addendum in the proposal.

If you wish to use Expedite Entry in helping you prepare your bids, please note that an amendment file is provided on the website for your use in addition to the original EBS file.

If you have any questions, feel free to call me at (919) 220-4600.

Sincerely,

DocuSigned by:

A handwritten signature in black ink, appearing to read "MKneis".

5CDD3BA8BDE94C1...

Michael J. Kneis, PE

Division Project Manager

cc: D. Jernigan (w/proposal)
David B. Moore (w/proposal)
Civil Rights Office

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0043000000-N	226	GRADING	Lump Sum	L.S.	
0004	0057000000-E	226	UNDERCUT EXCAVATION	8.5 CY		
0005	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	1,500 SY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	5 TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	5 SY		
0008	0343000000-E	310	15" SIDE DRAIN PIPE	114 LF		
0009	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	27 LF		
0010	0995000000-E	340	PIPE REMOVAL	84 LF		
0011	0996000000-N	350	PIPE CLEAN-OUT	3 EA		
0012	1099500000-E	505	SHALLOW UNDERCUT	500 CY		
0013	1099700000-E	505	CLASS IV SUBGRADE STABILIZATION	1,010 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	200 TON		
0015	1297000000-E	607	MILLING ASPHALT PAVEMENT, **** DEPTH (2")	1,120 SY		
0016	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	1,100 TON		
0017	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	330 TON		
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	70 TON		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2022000000-E	815	SUBDRAIN EXCAVATION	20 CY		
0020	2033000000-E	815	SUBDRAIN FINE AGGREGATE	20 CY		
0021	2044000000-E	815	6" PERFORATED SUBDRAIN PIPE	100 LF		
0022	2070000000-N	815	SUBDRAIN PIPE OUTLET	1 EA		
0023	2077000000-E	815	6" OUTLET PIPE	6 LF		
0024	2253000000-E	840	PIPE COLLARS	0.45 CY		
0025	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0026	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (16)	2 EA		
0027	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0028	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	850 LF		
0029	2612000000-E	848	6" CONCRETE DRIVEWAY	19 SY		
0030	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	2 EA		
0031	4116100000-N	904	SIGN ERECTION, RELOCATE, TYPE **** (GROUND MOUNTED) E)	6 EA		
0032	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	128 SF		
0033	4435000000-N	1135	CONES	48 EA		
0034	4455000000-N	1150	FLAGGER	140 DAY		
0035	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,502 LF		
0036	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	4,389 LF		
0037	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	128 LF		

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	4710000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (24", 120 MILS)	132	LF	
0039	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	8	EA	
0040	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	4,000	LF	
0041	4870000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (24")	132	LF	
0042	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	64	EA	
0043	6000000000-E	1605	TEMPORARY SILT FENCE	100	LF	
0044	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75	TON	
0045	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	20	TON	
0046	6012000000-E	1610	SEDIMENT CONTROL STONE	35	TON	
0047	6015000000-E	1615	TEMPORARY MULCHING	1	ACR	
0048	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0049	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5	TON	
0050	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0051	6030000000-E	1630	SILT EXCAVATION	60	CY	
0052	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,175	SY	
0053	6071010000-E	SP	WATTLE	135	LF	
0054	6071020000-E	SP	POLYACRYLAMIDE (PAM)	10	LB	
0055	6084000000-E	1660	SEEDING & MULCHING	3	ACR	
0056	6087000000-E	1660	MOWING	3	ACR	

County : Wake

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0057	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0058	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0059	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0060	6108000000-E	1665	FERTILIZER TOPDRESSING	1	TON	
0061	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0062	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	7	EA	
0063	7060000000-E	1705	SIGNAL CABLE	450	LF	
0064	7120000000-E	1705	VEHICLE SIGNAL HEAD (12", 3 SECTION)	6	EA	
0065	7264000000-E	1710	MESSENGER CABLE (3/8")	100	LF	
0066	7288000000-E	1715	PAVED TRENCHING (*****) (1, 2")	75	LF	
0067	7300000000-E	1715	UNPAVED TRENCHING (*****) (1, 2")	700	LF	
0068	7360000000-N	1720	WOOD POLE	1	EA	
0069	7372000000-N	1721	GUY ASSEMBLY	4	EA	
0070	7420000000-E	1722	2" RISER WITH WEATHERHEAD	1	EA	
0071	7444000000-E	1725	INDUCTIVE LOOP SAWCUT	840	LF	
0072	7456000000-E	1726	LEAD-IN CABLE (*****) (14-2)	2,200	LF	
0073	7780000000-N	1751	DETECTOR CARD (TYPE 2070L)	1	EA	
0074	7324000000-N	1716	JUNCTION BOX (STANDARD SIZE)	10	EA	