

**North Carolina Department of Transportation  
PURCHASE ORDER CONTRACT BID FORM**

**Work Order:** 51215.01AA

**Description:** Pipe over Brier Creek Reservoir on SR 1642 (Nelson Rd.)

**County:** Wake

ITEM	SECT	DESCRIPTION	QTY	UNIT	UNIT PRICE (\$)	AMOUNT BID (\$)
1	800	Mobilization	1.00	LS		
2	801	Construction Surveying	1.00	LS		
3	225	Undercut Excavation	31.00	CY		
4	226	Supplementary Clearing & Grubbing	0.10	AC		
5	SP	Grading	1.00	LS		
6	270	Geotextile for Soil Stabilization	183.00	SY		
7	SP	Temporary Shoring	2880.00	SF		
8	SP	Generic Grading Item Installation of State Supplied Pipe Structure and Headwalls	1.00	LS		
9	SP	Select Material Class II Type I	490.00	TON		
10	SP	Select Material Class III	9298.00	TON		
11	SP	Select Material Class IV	60.00	TON		
12	SP	Geotextile for Pavement Stabilization	35.00	SY		
13	545	Incidental Stone Base	10.00	TON		
14	SP	Shoulder Reconstruction	0.10	SMI		
15	SP	Aggregate Shoulder Borrow	10.00	TON		
16	607	Milling Asphalt Pavement, 0" to 2"	340.00	SY		
17	610	Asphalt Conc. Base Course, Type B25.0C	98.00	TON		

18	610	Asphalt Conc. Surface Course, Type S9.5B	40.00	TON		
19	620	Asphalt Binder for Plant Mix	10.00	TON		
20	862	Steel Beam Guardrail	800.00	LF		
21	862	Additional Guardrail Post	5.00	EA		
22	863	Guardrail End Units Type TL-3	4.00	EA		
23	863	Remove Existing Guardrail	990.00	LF		
24	876	Class I Rip Rap	365.00	TON		
25	876	Geotextile for Drainage	1385.00	SY		
26	1205	Thermoplastic Pavement Marking Lines (4", 90 Mils)	804.00	LF		
27	1510	12" Water Line	120.00	LF		
28	1510	Ductile Iron Water Pipe Fittings	440.00	LBS		
29	1510	12" Valve	1.00	EA		
30	1515	Generic Utility Item ( Concrete Encasement)	5.60	LF		
31	1520	12" Sanitary Gravity Sewer	80.00	LF		
32	1530	Abandon 8" Utility Pipe	100.00	LF		
33	1530	Abandon 12" Utility Pipe	162.00	LF		
34	SP	Generic Utility Item ( Temporary Pump Around for SS)	1.00	LS		
35	1605	Temporary Silt Fence	180.00	LF		
36	1610	Erosion Control Stone, Class B	30.00	TON		
37	1610	Sediment Control Stone	15.00	TON		

38	1615	Temporary Mulching	0.25	ACRE		
39	1620	Seed for Temporary Seeding	100.00	LB		
40	1620	Fertilizer for Temporary Seeding	0.25	TON		
41	SP	Safety Fence	375.00	LF		
42	1630	Silt Excavation	20.00	CY		
43	1631	Matting For Erosion Control	890.00	SY		
44	1632	1/4" Hardware Cloth	50.00	LF		
45	1639	Special Stilling Basins	1.00	EA		
46	SP	Wattle	100.00	LF		
47	SP	Polyacrylamide (PAM)	25.00	LB		
48	1660	Seeding & Mulching	0.50	ACRE		
49	1665	Fertilizer Topdressing	0.25	TON		
50	SP	Impervious Dike	250.00	LF		
51	230	Borrow Excavation	35.00	CY		

**TOTAL BID FOR PROJECT:** \_\_\_\_\_