

# SP-1

17BP.5.R.79

Wake County

## GENERIC STRUCTURE ITEM – SIDEWALK ON BRIDGE

(SPECIAL)

### 1.0 DESCRIPTION

This special provision addresses sidewalk on bridge and sidewalk on approach slabs. Construct approach slabs following the applicable sections of the Standard Specifications, plans and this provision. Note that payment for bridge sidewalk and approach slab sidewalk are handled separately.

### 2.0 MATERIAL REQUIREMENTS

Materials shall be in conformance with plans and Standard Specifications.

### 3.0 BASIS OF PAYMENT

Payment for “GENERIC STRUCTURE ITEM – SIDEWALK ON BRIDGE” will be at the contract unit price for Class AA concrete per cubic yard and epoxy coated reinforcing steel per pound. Such payment will be full compensation for cost of materials, equipment, labor, placement, and any incidentals necessary to complete the sidewalk on the bridge.

No additional payment is made for sidewalk on approach slabs. The entire cost of sidewalk on approach slab, including materials, equipment, labor, placement, and any incidentals necessary to complete the approach slab sidewalk shall be included in the lump sum cost for “BRIDGE APPROACH SLAB”.



DocuSigned by:  
*David Ruggles*  
C462768DF412422...

6/29/2022