



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY  
GOVERNOR

ANTHONY J. TATA  
SECRETARY

February 4, 2015

**NOTICE TO PROSPECTIVE BIDDERS**

**Subject:** Invitation to Bid

**TIP No.:** W-5206Z

**Federal Aid:** HSIP-1103(28)

**WBS:** 45336.3.FD26

**County:** Cumberland

**Description:** Grading, Drainage, Paving, Signals & Pavement Markings

The North Carolina Department of Transportation is requesting bids for Grading, Drainage, Paving, Signals & Pavement Markings on SR 1102, SR 1103 & SR 1112 in Cumberland County. The project will include the approximate quantities as attached. The Contractor is to furnish labor, materials, equipment, and traffic control.

**The availability date for this project is April 6, 2015.**

**The completion date is October 6, 2015.**

Sealed bids must be received in the Division Proposals Engineer's Office at 558 Gillespie Street, Fayetteville, NC, 28301 by 10:00 AM on Wednesday, February 25, 2015. Bids must be submitted on the official bid sheet included in the proposal and display the following statements on the front of the sealed envelope:

- 1. QUOTATION FOR WORK ORDER 45336.3.26, FOR SR 1102, SR 1103 & SR 1112 IN CUMBERLAND COUNTY TO BE OPENED AT 10:00 AM ON WEDNESDAY, FEBRUARY 25, 2015.**
- 2. THE BIDDING CONTRACTOR'S NAME, ADDRESS & PHONE NUMBER.**

In accordance with NC General Statute G.S. 44A-26, a Performance Bond and a Payment Bond in the amount of one hundred percent (100%) of the contract amount, conditioned upon the faithful performance of the contract in accordance with the specifications and conditions of the contract, are required for construction contracts of \$500,000 or more. Such bond shall be solely for the protection of the North Carolina Department of Transportation and the State of North Carolina.

**MAILING ADDRESS:**  
NC DEPT. OF TRANSPORTATION  
DIVISION SIX  
PO Box 1150  
FAYETTEVILLE, NC 28302

PHONE: 910-486-1493  
FAX: 910-486-1959

**WEBSITE:** [WWW.NCDOT.ORG](http://WWW.NCDOT.ORG)

**LOCATION:**  
NC DEPT. OF TRANSPORTATION  
DIVISION SIX  
558 GILLESPIE ST.  
FAYETTEVILLE, NC 28301

The North Carolina Department of Transportation, in accordance with the provisions of Title VI of the Civil Rights of 1964 (78 Stat.252) and the Regulations of the Department of Transportation (49 C.F.R., Part 21), issued pursuant to such act, hereby notifies all bidders that it will affirmatively insure that the contract entered into pursuant to this notice will be awarded to the lowest responsible bidder without discrimination on the grounds of sex, race, color, or national origin.

Any firm that wishes to bid as a prime contractor shall be prequalified as a Bidder or PO Prime Contractor prior to submitting a bid. Information regarding prequalification can be found at:  
<https://connect.ncdot.gov/business/Prequal/Pages/default.aspx>

**Statements of Disadvantaged Business Enterprise (DBE) participation must be presented with the bids.**

Proposals may be obtained from the Division Six web site:

[https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let\\_type=6](https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=6)

Should you have questions, need additional information concerning this project, or need additional information pertaining to the bidding or bidding process, please contact Allen Waddell, Division Proposals Engineer at (910)-486-1493.

Sincerely,



R. Allen Waddell, P.E.  
Division Proposals Engineer

Attachment

cc: Greg Burns, P.E.  
Randy Wise, P.E.  
Richie Hines, P.E.  
Jason Salisbury  
Frank West

**Work Order Number:** 45336.3.FD26 (W-5206Z)

**Project Description:** Galatia Church Rd (SR1103), Gillis Hill (SR1102) & Stoney Point (SR1112)

**County:** Cumberland

LINE #	ITEM NUMBER	SEC #	DESCRIPTION	QTY	UNIT
1	0000100000-N	800	Mobilization	1	LS
2	0000400000-N	801	Construction Surveying	1	LS
3	0022000000-E	225	Unclassified Excavation	5,800	CY
4	0036000000-E	225	Undercut	100	CY
5	0043000000-N	226	Grading	1	LS
6	0156000000-E	250	Remove Existing Asphalt Pavement	3,020	SY
7	0318000000-E	300	Foundation Cond. Mat'l, Minor Strs.	30	TON
8	0320000000-E	300	Foundation Conditioning Geo-Textile	80	SY
9	0344000000-E	310	18" Side Drain Pipe	80	LF
10	0378000000-E	310	24" RC Pipe Culverts Class III	92	LF
11	0448300000-E	310	18" RCP CULV CLASS IV	60	LF
12	0995000000-E	340	Pipe Removal	80	LF
13	1220000000-E	545	Incidental Stone	200	TON
14	1308000000-E	607	Milling Existing Asphalt Pavement 0" to 1.5"	1,420	SY
15	1489000000-E	610	Asphalt Concrete Base Course, Type B25.0B	1,600	TON
16	1498000000-E	607	Asphalt Concrete Intermediate Course, Type 119.0B	1,000	TON
17	1519000000-E	610	Asphalt Concrete Surface Course, Type S9.5B	1,400	TON
18	1575000000-E	620	Asphalt Binder for Plant Mix	205	TON
19	1693000000-E	654	Asphalt Plant Mix, Pavement Repair	25	TON
20	2275000000-E	SP	Flowable Fill	3	CY
21	2845000000-N	858	Adj. of Meter Boxes or Valve Boxes	3	EA
22	4026000000-E	901	Department Furnished Type 'E' Sign	16	SF
23	4072000000-E	903	Supports 3LB U-Channel	257	LF
24	4102000000-N	904	Sign Erection Type 'E'	16	EA
25	4116100000-N	904	Sign Erection, Relocate Type 'E'	8	EA
26	4155000000-N	907	Disposal of Sign System, U-Channel	16	EA
27	4192000000-N	907	Disposal of Support, U-Channel	4	EA
28	4400000000-E	1110	Work Zone Signs (Stationary)	256	SF

29	4405000000-E	1110	Work Zone Signs (Portable)	488	SF
30	4410000000-E	1110	Work Zone Signs (Barricade Mounted)	70	SF
31	4430000000-N	1130	Drums	200	EA
32	4435000000-N	1135	Cones	50	EA
33	4450000000-N	1150	Flagger	370	HR
34	4480000000-N	1165	TMA	2	EA
35	4510000000-N	SP	Law Enforcement	32	HR
36	4516000000-N	1180	Skinny Drum	50	EA
37	4650000000-N	1251	Temporary Raised Pavement Markers	28	EA
38	4685000000-E	1205	Thermoplastic Pavement Marking Lines (4", 90 Mils)	6,013	LF
39	4686000000-E	1205	Thermoplastic Pavement Marking Lines (4", 120 Mils)	10,001	LF
40	4700000000-E	1205	Thermoplastic Pavement Marking Lines (12", 90 Mils)	189	LF
41	4710000000-E	1205	Thermoplastic (24", 120 Mils)	200	LF
42	4725000000-E	1205	Thermoplastic Pavement Marking Symbol (90 Mils)	24	EA
43	4810000000-E	1205	Paint Pavement Marking Lines (4")	3,447	LF
44	4900000000-N	1251	Permanent Raised Permanent Markers	165	EA
45	6000000000-E	1605	Temporary Silt Fence	9,645	LF
46	6006000000-E	1610	Erosion Control Stone, Class A	60	TON
47	6009000000-E	1610	Erosion Control Stone, Class B	290	TON
48	6012000000-E	1610	Sediment Control Stone	205	TON
49	6015000000-E	1615	Temporary Mulching	9	ACR
50	6018000000-E	1620	Seed for Temporary Seeding	600	LB
51	6021000000-E	1620	Fertilizer for Temporary Seeding	3	TON
52	6024000000-E	1622	Temporary Slope Drains	200	LF
53	6030000000-E	1630	Silt Excavation	340	CY
54	6036000000-E	1631	Matting for Erosion Control	14,990	SY
55	6042000000-E	1632	1/4" Hardware Cloth	540	LF
56	6071010000-E	SP	Coir Fiber Wattle	675	LF
57	6071020000-E	SP	Polyacrylamide (PAM)	230	LB
58	6084000000-E	1660	Seeding & Mulching	5	ACR
59	6090000000-E	1661	Seed for Repair Seeding	250	LB
60	6093000000-E	1661	Fertilizer for Repair Seeding	1.25	TON
61	6096000000-E	1662	Seed for Supplemental Seeding	25	LB

62	6108000000-E	1665	Fertilizer Topdressing	5.75	TON
63	6114500000-N	1667	Specialized Hand Mowing	10	MHR
64	6117000000-N	SP	Response for Erosion Control	25	EA
65	7060000000-E	1705	Signal Cable	1,600	LF
66	7120000000-E	1705	Vehicle Signal Head (12", 3 Section)	7	EA
67	7132000000-E	1705	Vehicle Signal Head (12", 4 Section)	4	EA
68	7144000000-E	1705	Vehicle Signal Head (12", 5 Section)	4	EA
69	7264000000-E	1710	Messenger Cable (3/8")	520	LF
70	7300000000-E	1715	Unpaved Trenching ( 1 Conduit, 2 inch)	1,400	LF
71	7300100000-E	1715	Unpaved Trenching for Temporary Lead-in	250	LF
72	7324000000-N	1716	Junction Box (Standard Size)	14	EA
73	7360000000-N	1720	Wood Pole	5	EA
74	7372000000-N	1721	Guy Assembly	8	EA
75	7444000000-E	1725	Inductive Loop Sawcut	3,300	LF
76	7456000000-E	1726	Lead-in Cable (14-2)	6,600	LF
77	7708000000-N	1751	Detector Card (Type 2070L)	3	EA