STATE PROJ. REFERENCE NO.	SHEET NO.
W-5206Z	PMP-1

APPROVED: [signature]

DATE: 1/26/2015

SEAL

NORTH CAROLINA PROFESSIONAL SEAL 033822 ENGINEER JONATHAN P. SOIKA

T.I.P.: W-5206Z

PROJECT: 45336.2.FD26

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAVEMENT MARKING PLAN
CUMBERLAND COUNTY

LOCATION: SR 1103 (Galatia Church Rd) at SR 1102 (Gillis Hill Rd)
SR 1103 (Galatia Church Rd) at SR 1112 (Stoney Point Rd)
and SR 1112 (Stoney Point Rd) at SR 1102 (Gillis Hill Rd)

INDEX

SHEET NO.	DESCRIPTION
PMP-1	PAVEMENT MARKING PLAN TITLE AND SCHEDULE SHEET
PMP-2-4	PAVEMENT MARKING DETAIL

PAVEMENT MARKING SCHEDULE

SYMBOL	DESCRIPTION	PAY ITEM QUANTITY	TOTAL
	THERMOPLASTIC (24", 120 MILS)		
T2	WHITE STOPBAR	200 LF	TOTAL 200 LF
	THERMOPLASTIC (4", 120 MILS)		
T8	2 FT. - 6 FT./SP WHITE MINISKIP	59 LF	
TD	3 FT. - 9 FT./SP WHITE MINISKIP	256 LF	
TE	WHITE SOLID LANE LINE	1538 LF	
TF	10 FT. YELLOW SKIP	86 LF	
TH	YELLOW SINGLE CENTER	342 LF	
TI	YELLOW DOUBLE CENTER	7720 LF	TOTAL 10001 LF
	THERMOPLASTIC (4", 90 MILS)		
TA	WHITE EDGELINE	6013 LF	TOTAL 6013 LF
	THERMOPLASTIC (12", 90 MILS)		
TV	YELLOW DIAGONAL	189 LF	TOTAL 189 LF
	THERMOPLASTIC PAVEMENT MARKING SYMBOLS (90 MILS)		
UA	LEFT TURN ARROW	8 EA	
UB	RIGHT TURN ARROW	8 EA	
UC	STRAIGHT ARROW	8 EA	TOTAL 24 EA
	PERMANENT RAISED PAVEMENT MARKERS		
MA	YELLOW & YELLOW		
MB	CRYSTAL & RED		TOTAL 165 EA

GENERAL NOTES

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT, EXCEPT WHEN OTHERWISE NOTED IN THE PLAN, OR DIRECTED BY THE ENGINEER.

A) INSTALL PAVEMENT MARKINGS AND PAVEMENT MARKERS ON THE FINAL SURFACE AS FOLLOWS:

ROAD NAME	MARKING	MARKER
GALATIA CHURCH RD AND -Y- LINES	THERMOPLASTIC	PERMANENT RAISED

B) TIE PROPOSED PAVEMENT MARKING LINES TO EXISTING PAVEMENT MARKING LINES.

C) REMOVE/REPLACE ANY CONFLICTING/DAMAGED PAVEMENT MARKINGS AND MARKERS.

D) MARKERS SHALL BE INSTALLED ACCORDING TO NCDOT ROADWAY STANDARD DRAWING NO. 1250.01.

E) REFER TO APPROVED TRAFFIC SIGNAL PLANS FOR STOP BAR PLACEMENT AT SIGNALIZED INTERSECTIONS.

ROADWAY STANDARD DRAWING

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN "ROADWAY STANDARD DRAWINGS" - PROJECT SERVICES UNIT - N.C. DEPARTMENT OF TRANSPORTATION - RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD. NO.	TITLE
1205.01	PAVEMENT MARKINGS - LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS - TWO-LANE AND MULTILANE ROADWAYS
1205.04	PAVEMENT MARKINGS - INTERSECTIONS
1205.05	PAVEMENT MARKINGS - TURN LANES
1205.08	PAVEMENT MARKINGS - SYMBOLS AND WORD MESSAGES
1205.09	PAVEMENT MARKINGS - PAINTED ISLANDS
1250.01	RAISED PAVEMENT MARKERS - INSTALLATION SPACING
1251.01	RAISED PAVEMENT MARKERS - PERMANENT AND TEMPORARY

PLAN PREPARED BY: VHB Engineering NC, P.C.

Jonathan P. Soika, PE PROJECT ENGINEER

vhb Engineers | Scientists | Planners | Designers
4000 WestChase Boulevard, Suite 530 Raleigh, NC 27607
NC License No. C-3705

V:\267295.W5206Z-TC_PMP_01.dgn