PROJ. REFERENCE NO.	SHEET NO.
U-5524	X-SUM

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CROSS-SECTION SUMMARY

NOTE: EMBANKMENT COLUMN DOES NOT INCLUDE BACKFILL FOR UNDERCUT

Quantities are approximate only. The Resident Engineer will recross-section the work accurately when the project is staked out. These cross-section notes will be used in computing the final quantities for which the contractor will be paid.

Station L	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
11+90.00000	0	0
12+00.00000	22	0
12+50.00000	111	0
13+00.00000	79	25
13+50.00000	59	45

Station DR1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+15.00000	0	0
10+25.00000	0	31
10+50.00000	0	38
10+75.00000	5	5

Station ROUND	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+00.00000	0	0
10+25.00000	5	149
10+50.00000	2	148
10+75.00000	6	136
11+00.00000	8	131
11+25.00000	9	185
11+50.00000	5	424
11+75.00000	0	539
12+00.00000	0	381
12+25.00000	0	291
12+50.00000	0	276
12+75.00000	0	250
13+00.00000	0	192
13+25.00000	2	142
13+50.00000	7	139

Station DR2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+25.00000	0	0
10+50.00000	4	13
10+64.00000	5	0

Station Y1	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+30.00000	0	0
10+50.00000	39	29
11+00.00000	112	27
11+50.00000	109	2
12+00.00000	91	1
12+12.00000	20	1

Station Y2	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+30.00000	0	0
10+50.00000	29	36
11+00.00000	138	18
11+50.00000	139	3
12+00.00000	111	2
12+50.00000	97	1
12+53.00000	6	0

Station Y3	Uncl. Exc. (cu. yd.)	Embt (cu. yd.)
10+50.00000	0	0
11+00.00000	0	141