




HIGHWAY LANDSCAPE DEVELOPMENT PROJECT







County Line. City or Town Line. Exist. Right of Way Line Marker... Prop. Right of Way Line Marker (By Others) Prop Right of Way Line Marker (By Contract) Exist. Control of Access Line Prop. Control of Access Line Property Line. Easement Line. Slope Stake Line. Exist. Fence. Prop. Woven Wire Fence. Prop. Chain Link Fence. Exist. Road Prop. Road Guardrail.. Survey Line. Denotes Line Equality Bridge. Culvert Woods Exist. Telephone Pole. Prop. Telephone Pole Tower Pole and Line. Exist. Power Pole Prop. Power Pole. Sanitary Sewer Line Water Line. Gas Line. Picnic Shelter Regeneration. Reforestation

CONVENTIONAL SYMBOLS

Summary of Quantities 1 year establishment

DES	SEC	QTY	UNIT	KEY	BOTANICAL NAME	COMMON NAME	SIZE	CALIPER	FURNISH	A.S.N.S.	REMARKS
					Trees						
L	1670	7	еа	JV	Juniperus virginiana	Eastern Red Cedar	8'		B&B	3.2.5	As Shown
L	1670	8	еа	MG	Magnolia grandiflora 'Kay Parris'	Kay Parris Magnolia	7'		B&B	1.2.4	As Shown
					Other						
L	1670	1	еа		Selective Tree Removal, 10"						
L	1670	0.2	acres		Wooded Area Clean-up						
L	1670	17	cuyd		Mulch						Depth of 4"
L	1670	5	m/g		Water for Plantings						
L	1670	581	sqyd		Pre emergence Herbicidal Treatment						
L	1670	581	sqyd		Post emergence Herbicidal Treatment						
L	1670	1	LS		Grading						
L	1670	1	LS		Existing Site Amenities Removal						
L	1670	12	sqyd		4" Concrete Pad						
L	1670	1	еа		8' Picnic Table						
L	1670	2	ea		Trash Receptacles						
		·									



L 1.0 - Title Sheet


L 2.0 - Planting Details

L 3.0 - Demolition Plan L 4.0 - Planting Plan

PREPARED BY: KC date: 09/2015

REVISIONS

DATE	DESCRIPTION



STATE OF NORTH CAROLINA DEPARTMENT OF TRANSPORTATION LOCATION: US 701 Tabor City

TYPE of WORK: Enhancement

COUNTY: Columbus County

2014 American Standard for Nursery Stock
2012 NCDOT STANDARD SPECIFICATIONS

PREPARED IN THE OFFICE OF:

NCDOT- ROADSIDE ENVIRONMENTAL UNIT


LANDSCAPE DESIGN & DEVELOPMENT SECTION

1557 MAIL SERVICE CENTER

RALEIGH NC 27699 919-707-2920

abor

600F



DO NOT PLACE MULCH WITHIN 2" -

MULCH DETAIL

SCHEDULE FOR PLANT HOLE SIZE: PLANT HOLE WIDTH (X) TO BE TWICE THE ROOT BALL SIZE OR CONTAINER

SEE STANDARD SPECIFICATIONS FOR PLANT BED FUMIGATION AND HERBICIDAL

APPLY FERTILIZER AT PLANTING TIME IN THE FORM OF A SLOW RELEASE PELLET OR TABLET. APPLY AT RATE RECOMMENDED BY MANUFACTURER. BOTH RATE AND FORMULATION MUST BE APPROVED BY FIELD ENGINEER PRIOR

REMOVE WIRE BASKET AND FOLD BURLAP BACK FROM TOP OF ROOT BALL BEFORE BACKFILLING IS COMPLETE.

ALL PRUNING TO FOLLOW STANDARD ARBORICULTURAL PRACTICES AS SPECIFIED BY INTERNATIONAL SOCIETY

DO NOT ATTEMPT TO STRAIGHTEN A TREE THAT HAS BEEN PLANTED AT AN ANGLE WITH THE USE OF STAKING OR GUYING. DIG TREE AND REPLANT TO UPRIGHT

Planting Details

Roadside

Transportation

Plans Drawn By Kyle Cooper

AS NOTED

09 / 08 / 15 Sheet Description

WBS # 46305.1.4 Sheet #

L-2

