



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY  
GOVERNOR

NICHOLAS J. TENNYSON  
SECRETARY

September 30, 2015

## **NOTICE TO PROSPECTIVE BIDDERS**

**Contract:** DF00095  
**TIP No.:** W-5206AJ  
**Federal Aid:** HSIP-0210(32)  
**WBS:** 45336.3.FR36  
**County:** Harnett  
**Description:** Grading, Paving, Drainage, Signals, Signing & Pavement Markings

The North Carolina Department of Transportation is requesting bids for grading, paving, drainage, signal installation and pavement markings on SR 2215 (Harnett Central Road) and NC 210 in Harnett County. The project will include the approximate quantities as attached. The Contractor is to furnish labor, materials, equipment, and traffic control.

**The availability date for this project is December 7, 2015.**

**The completion date is September 30, 2016.**

Sealed bids must be received in the Division Proposals Engineer's Office at 558 Gillespie Street, Fayetteville, NC, 28301 by **10:00 AM on Wednesday, October 21, 2015**. Bids must be submitted on the official bid sheet included in the proposal and display the following statements on the front of the sealed envelope:

- 1. QUOTATION FOR DF00095 – W-5206AJ  
GRADING, PAVING, DRAINAGE, SIGNALS, SIGNING &  
PAVEMENT MARKINGS  
TO BE OPENED AT 10:00 AM ON WEDNESDAY, OCTOBER 21, 2015**
- 2. THE BIDDING CONTRACTOR'S NAME, ADDRESS & PHONE NUMBER.**

The North Carolina Department of Transportation, in accordance with the provisions of Title VI of the Civil Rights of 1964 (78 Stat.252) and the Regulations of the Department of Transportation (49 C.F.R., Part 21), issued pursuant to such act, hereby notifies all bidders that it will affirmatively insure that the contract entered into pursuant to this notice will be awarded to the lowest responsible bidder without discrimination on the grounds of sex, race, color, or national origin.

**MAILING ADDRESS:**  
NC DEPT. OF TRANSPORTATION  
DIVISION SIX  
PO Box 1150  
FAYETTEVILLE, NC 28302

PHONE: 910-486-1493  
FAX: 910-486-1959  
WEBSITE: [WWW.NCDOT.ORG](http://WWW.NCDOT.ORG)

**LOCATION:**  
NC DEPT. OF TRANSPORTATION  
DIVISION SIX  
558 GILLESPIE ST.  
FAYETTEVILLE, NC 28301

Any firm that wishes to bid as a prime contractor shall be prequalified as a Bidder or PO Prime Contractor prior to submitting a bid. Information regarding prequalification can be found at:  
<https://connect.ncdot.gov/business/Prequal/Pages/default.aspx>.

In addition, the prime contractor and/or subcontractor(s) shall be prequalified in the work code(s) for which they identify as work items in the prime contractor's construction progress schedule that they will complete themselves. Any contractor identified as working outside their expertise may be considered in default of contract.

**Statements of Disadvantaged Business Enterprise (DBE) participation must be presented with the bids.**


Proposals may be obtained from the Division Six web site:

[https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let\\_type=6&let\\_status=Advertised](https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=6&let_status=Advertised)

Should you have questions, need additional information concerning this project, or need additional information pertaining to the bidding or bidding process, please contact Allen Waddell, Division Proposals Engineer at (910)-486-1493.

Sincerely,

DocuSigned by:



F06892B7CB3147E...

R. Allen Waddell, P.E.  
Division Proposals Engineer

Attachment

cc: Greg Burns, P.E.  
Ken Murphy, P.E.  
Randy Wise, P.E.  
Jerry Bradley, P.E.  
Scott Pridgen  
Richie Hines, P.E.

**PROJECT NUMBER:** 45336.3.FR36  
**COUNTY:** Harnett  
**DESCRIPTION:** Grading, Paving, Drainage, Signals, Signing & Pavement Markings  
**BID DATE:** October 21, 2015

LINE #	ITEM NUMBER	SEC #	DESCRIPTION	QTY	UNIT
1	0000100000-N	800	Mobilization	1	LS
2	0000400000-N	801	Construction Surveying	1	LS
3	0000995000-E	SP	Aggregate Shoulder Borrow	100	TON
4	0008000000-E	200	Supplementary Clearing and Grubbing	0.25	ACR
5	0057000000-E	226	Undercut Excavation (Incidental)	100	CY
6	0063000000-N	226	Grading	1	LS
7	0255000000-E	SP	Stockpiling Contaminated Soil	10	TON
8	0318000000-E	300	Foundation Conditioning Material, Minor Structures	260	TON
9	0320000000-E	300	Foundation Conditioning Geotextile	270	SY
10	0343000000-E	310	15" Side Drain Pipe	200	LF
11	0378000000-E	310	24" RC Pipe Culverts, Class III	24	LF
12	0448300000-E	310	18" RC Pipe Culverts, Class IV	80	LF
13	0448500000-E	310	30" RC Pipe Culverts, Class IV	170	LF
14	0448600000-E	310	36" RC Pipe Culverts, Class IV	184	LF
15	0995000000-E	340	Pipe Removal	240	LF
16	1220000000-E	545	Incidental Stone Base	200	TON
17	1330000000-E	607	Incidental Milling (Tie-ins)	450	SY
18	1489000000-E	610	Asphalt Conc Base Course, Type B25.0B	1000	TON
19	1498000000-E	610	Asphalt Conc Intermediate Course, Type I19.0B	865	TON
20	1519000000-E	610	Asphalt Conc Surface Course, Type S9.5B	2230	TON
21	1575000000-E	620	Asphalt Binder For Plant Mix	220	TON
22	1693000000-E	654	Asphalt Plant Mix, Pavement Repair	80	TON
23	2209000000-E	838	Endwalls (838.01)	12	CY
24	2253000000-E	840	Pipe Collars	1.50	CY
25	2264000000-E	840	Pipe Plugs	0.13	CY
26	2275000000-E	SP	Flowable Fill	100	CY
27	2535000000-E	846	9" x 18" Concrete Curb	30	LF
28	2549000000-E	846	2'-6" Concrete Curb & Gutter	51	LF
29	2570000000-N	SP	Modified Concrete Flume	1	EA
30	2830000000-N	858	Adjustment of Manholes	1	EA
31	2845000000-N	858	Adjust Meter or Valve Box	7	EA

32	3649000000-E	876	Rip Rap, Class B	50	TON
33	3656000000-E	876	Geotextile For Drainage	125	SYD
34	4399000000-N	1105	Temporary Traffic Control	1	LS
35	4510000000-N	SP	Law Enforcement	40	HR
36	4650000000-N	1251	Temporary Raised Pavement Markers	200	EA
37	4685000000-E	1205	Thermoplastic Pavement Marking lines (4", 90 Mils)	7,200	LF
38	4686000000-E	1205	Thermoplastic Pavement Marking Lines (4", 120 Mils)	9,775	LF
39	4695000000-E	1205	Thermoplastic Pavement Marking lines (8", 90 Mils)	250	LF
40	4710000000-E	1205	Thermoplastic Pavement Marking Lines (24", 120 Mils)	250	LF
41	4721000000-E	1205	Thermoplastic Pavement Marking Character (120 Mils)	6	EA
42	4725000000-E	1205	Thermoplastic Pavement Marking Symbol (90 Mils)	35	EA
43	4900000000-N	1251	Permanent Raised Pavement Markers	165	EA
44	5325000000-E	1510	*** Water Line (8" RJD Pipe)	215	LF
45	5325800000-E	1510	8" Water Line	1,700	LF
46	5546000000-E	1515	8" Gate Valve	3	EA
47	5572200000-E	1515	12" Tapping Valve (12"x8")	1	EA
48	5648000000-N	1515	Relocate Water Meter	7	EA
49	5672000000-N	1515	Relocate Fire Hydrant	2	EA
50	5709400000-E	1520	8" Force Main Sewer	75	LF
51	6000000000-E	1605	Temporary Silt Fence	1,800	LF
52	6009000000-E	1610	Stone For Erosion Control, Class B	30	TON
53	6012000000-E	1610	Sediment Control Stone	10	TON
54	6018000000-E	1620	Seed For Temporary Seeding	85	LB
55	6021000000-E	1620	Fertilizer For Temporary Seeding	0.50	TON
56	6029000000-E	SP	Safety Fence	250	LF
57	6036000000-E	1631	Matting For Erosion Control	800	SYD
58	6042000000-E	1632	1/4" Hardware Cloth	30	LF
59	6071010000-E	SP	Wattle	150	LF
60	6071020000-E	SP	Polyacrylamide (Pam)	20	LBS
61	6084000000-E	1660	Seeding & Mulching	2.00	ACR
62	6090000000-E	1661	Seed For Repair Seeding	85	LBS
63	6093000000-E	1661	Fertilizer For Repair Seeding	0.50	TON
64	6096000000-E	1662	Seed For Supplemental Seeding	85	LBS
65	6108000000-E	1665	Fertilizer For Topdressing	0.50	TON
66	6117000000-N	SP	Response For Erosion Control	10	EA
67	7060000000-E	1705	Signal Cable	1,550	LF
68	7120000000-E	1705	Vehicle Signal Head (12", 3 Section)	8	EA

69	7132000000-E	1705	Vehicle Signal Head (12", 4 Section)	2	EA
70	7144000000-E	1705	Vehicle Signal Head (12", 5 Section)	2	EA
71	7252000000-E	1710	Messenger Cable (1/4")	420	LF
72	7264000000-E	1710	Messenger Cable (3/8")	450	LF
73	7300000000-E	1715	Unpaved Trenching (1 Conduit,2")	460	LF
74	7300000000-E	1715	Unpaved Trenching (2 Conduit,2")	15	LF
75	7324000000-N	1716	Junction Box (Standard Size)	9	EA
76	7360000000-N	1720	Wood Pole	1	EA
77	7372000000-N	1721	Guy Assembly	8	EA
78	7408000000-E	1722	1" Riser With Weatherhead	1	EA
79	7420000000-E	1722	2" Riser With Weatherhead	6	EA
80	7444000000-E	1725	Inductive Loop Sawcut	1,350	LF
81	7456000000-E	1726	Lead-In Cable (14-2 Pair)	2,800	LF
82	7684000000-N	1750	Signal Cabinet Foundation	1	EA
83	7756000000-N	1751	Controller With Cabinet (Type 2070L, Base Mounted)	1	EA
84	7780000000-N	1751	Detector Card (Type 2070L)	8	EA
85	7901000000-N	1753	Cabinet Base Extender	1	EA