

FED AID NO HSIP-0024(076)

GRADING, PAVING, RESURFACING, SIGNALS REVISION & PVT MKS
FROM WEST OF CIRCLE ST TO SR 2022

HIGHLAND PAVING COMPANY LLC
FAYETTEVILLE, NC

BARNHILL CONTRACTING
COMPANY
ROCKY MOUNT, NC

ROADWAY ITEMS

0001	0000100000-N	800	MOBILIZATION	Lump Sum		10000.00		12050.00
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum		1000.00		785.00
0003	0063000000-N	SP	GRADING	Lump Sum		12000.00		18140.00
0004	1220000000-E	545	INCIDENTAL STONE BASE	25 TON	60.00	1500.00	50.00	1250.00
0005	1308000000-E	607	MILLN ASPHALT PVT ***** - ***** (0" - 1.5")	5,800 SY	4.00	23200.00	2.10	12180.00
0006	1330000000-E	607	INCIDENTAL MILLING	1,325 SY	12.00	15900.00	8.10	10732.50
0007	1489000000-E	610	ASP CONC BASE CRS B25.0B	70 TON	165.00	11550.00	159.30	11151.00
0008	1519000000-E	610	ASP CONC SURF CRS S9.5B	1,330 TON	57.00	75810.00	62.70	83391.00
0009	1575000000-E	620	ASP FOR PLANT MIX	85 TON	331.50	28177.50	308.00	26180.00
0010	2591000000-E	848	4" CONCRETE SIDEWALK	10 SY	65.00	650.00	65.00	650.00
0011	2830000000-N	858	ADJ MANHOLES	1 EA	750.00	750.00	1515.00	1515.00
0012	2845000000-N	858	ADJ METER OR VALVE BOXES	1 EA	750.00	750.00	1515.00	1515.00
0013	4399000000-N	1105	TEMP TRAFFIC CONTROL (1105)	Lump Sum		10800.00		21260.00
0014	4685000000-E	1205	THERMO PVT MKG LINES 4*90	1,700 LF	1.10	1870.00	1.10	1870.00
0015	4686000000-E	1205	THERMO PVT MKG LINES 4*120	7,800 LF	1.25	9750.00	1.25	9750.00
0016	4697000000-E	1205	THERMO PVT MKG LINE 8*120 MILS	700 LF	3.00	2100.00	3.00	2100.00
0017	4710000000-E	1205	24"WIDE THERMO 120 MILS	200 LF	9.00	1800.00	9.00	1800.00
0018	4721000000-E	1205	THERMO PVT MKG CHARACTER 120	12 EA	100.00	1200.00	100.00	1200.00
0019	4725000000-E	1205	THERMO PVT SYMBOL 90MILS	28 EA	100.00	2800.00	100.00	2800.00
0020	4810000000-E	1205	PAINT PVT MARKINGS 4"	10,000 LF	0.20	2000.00	0.20	2000.00
0021	4835000000-E	1205	PAINT PVT MKG LINES 24"	200 LF	3.00	600.00	3.00	600.00
0022	4840000000-N	1205	PAINT PVT MKG CHARACTER	12 EA	25.00	300.00	25.00	300.00
0023	4845000000-N	1205	PAINT PVT MKG SYMBOL	25 EA	25.00	625.00	25.00	625.00
0024	4870000000-E	1205	LINE REMOVAL 24" WIDE	30 LF	5.00	150.00	5.00	150.00
0025	4900000000-N	1251	PERM RAISED PVT MARKERS	100 EA	10.00	1000.00	10.00	1000.00
0026	6000000000-E	1605	TEMPORARY SILT FENCE	600 LF	2.50	1500.00	2.50	1500.00
0027	6015000000-E	1615	TEMPORARY MULCHING	0.14 ACR	4000.00	560.00	4000.00	560.00
0028	6018000000-E	1620	SEED FOR TEMP SEEDING	7 LB	5.00	35.00	5.00	35.00
0029	6021000000-E	1620	FERT FOR TEMP SEEDING	0.1 TON	1200.00	120.00	1200.00	120.00
0030	6084000000-E	1660	SEEDING AND MULCHING	0.14 ACR	8000.00	1120.00	8000.00	1120.00
0031	6090000000-E	1661	SEED FOR REPAIR SEEDING	7 LB	10.00	70.00	10.00	70.00
0032	6093000000-E	1661	FERT FOR REPAIR SEEDING	0.05 TON	1000.00	50.00	1000.00	50.00
0033	6096000000-E	1662	SEED FOR SUPP SEEDING	7 LB	10.00	70.00	10.00	70.00
0034	6108000000-E	1665	FERTILIZER TOPDRESSING	0.1 TON	1000.00	100.00	1000.00	100.00
0035	6117000000-N	SP	RESPONSE FOR EROS CONTROL	2 EA	350.00	700.00	350.00	700.00
0036	6132000000-N	SP	GENERIC EROSION CONTROL ITEM (EA) CONCRETE CLEANOUT STRUCTURE	1 EA	1.00	1.00	150.00	150.00
0037	7048500000-E	1705	16" PEDEST SIG HEAD 1 SEC W/CD	2 EA	700.00	1400.00	700.00	1400.00
0038	7060000000-E	1705	SIGNAL CABLE	400 LF	3.45	1380.00	3.45	1380.00
0039	7120000000-E	1705	VEHICLE SIGNAL HD (12", 3 SECT)	1 EA	700.00	700.00	700.00	700.00

NOV 17, 2016 09:57 AM

CUMBERLAND

TIP NO W-5601EP

50138.3.147

2:00 PM 2 / 2 002

NOV 16 2016 DF00143
0.578 MI

FED AID NO HSIP-0024(076)

GRADING, PAVING, RESURFACING, SIGNALS REVISION & PVT MKS
FROM WEST OF CIRCLE ST TO SR 2022

		HIGHLAND PAVING COMPANY LLC			BARNHILL CONTRACTING COMPANY		
		FAYETTEVILLE, NC			ROCKY MOUNT, NC		
0040	7288000000-E	1715 PAVED TRENCH (***** (2, 2")	15 LF	18.00	270.00	18.00	270.00
0041	7300000000-E	1715 UNPAVED TRENCH (***** (2, 2")	10 LF	18.00	180.00	18.00	180.00
0042	7420000000-E	1722 2" RISER WITH WEATHERHEAD	1 EA	375.00	375.00	375.00	375.00
0043	7444000000-E	1725 INDUCTIVE LOOP SAWCUT	670 LF	4.98	3336.60	5.00	3350.00
0044	7456000000-E	1726 LEAD-IN CABLE(***** (14-2)	800 LF	1.75	1400.00	1.75	1400.00
0045	7642200000-N	1743 TYPE II PED W/ FOUNDATION	2 EA	1450.00	2900.00	1450.00	2900.00
CONTRACT TOTAL				TOTAL	232550.10	TOTAL	241424.50
ROADWAY ITEMS				SUB-TOTAL	232550.10	SUB-TOTAL	241424.50
BIDDERS IN ORDER				CONTRACT TOTAL			
HIGHLAND PAVING COMPANY LLC			1	232550.10			
BARNHILL CONTRACTING COMPANY			2	241424.50			