



BID ADDENDUM

June 20, 2016

FAILURE TO RETURN THIS ENTIRE BID ADDENDUM IN ACCORDANCE WITH INSTRUCTIONS SHALL SUBJECT YOUR BID TO REJECTION ON THE AFFECTED ITEM(S):

Contract ID: -----
TIP No.: -----
Federal Aid: -----
WBS: 17BP.6.R.78
County: Cumberland
Description: Pipe Replacements

Addendum No.: 1 Letting Date: June 22, 2016
Time: 2:00 PM

- INSTRUCTIONS:**
1. Please make the following changes and adhere to the following clarifications on the bid referenced above.
 2. Sign & Return all the pages of this Addendum with the Bid Proposal, due at the Date & Time as listed above.

Proposed Amendments / Changes / Clarifications:

1. The Units in the original Contract Bid Form were incorrect for Item No. 12. It should be EA, instead of LS. The form has been corrected. Please delete the original Contract Bid Form, and insert the attached Revised Contract Bid Form.

North Carolina Department of Transportation
REVISED CONTRACT BID FORM

PROJECT NUMBER: 17BP.6.R.78
COUNTY: Cumberland
DESCRIPTION: Pipe Replacements

ROAD: SR 1722			PIPE NO.: 87		COUNTY: Cumberland		
LINE	ITEM NO.	SEC	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT BID
1	0001000000-N	800	Mobilization	1	LS		
2	0043000000-N	SP	Comprehensive Grading	1	LS		
3	0106000000-E	230	Borrow	50	CY		
4	1077000000-E	SP	#57 Stone / Backfill	920	TON		
5	0995000000-E	SP	Pipe Removal	100	LF		
6	1220000000-E	545	Aggregate Base Course	150	TON		
7	1498000000-E	610	ACIC, Type I19.0B	42	TON		
8	1525000000-E	610	ACSC, Type SF9.5A	52	TON		
9	1575000000-E	620	Asphalt Binder, Grade PG 64-22	6	TON		
10	2474000000-N	SP	Pipe & Headwall (20'-10" x 8'-1" Arch w/Headwalls)	1	LS		
11	3691000000-N	SP	Dewatering	1	EA		
12	5912000000-N	SP	Utility Relocations	1	EA		
13	6000000000-E	1605	Temporary Silt Fence	150	LF		
14	6000900000-E	1610	Stone for Erosion Control -Class B	100	TON		
15	6036000000-E	1631	Matting for Erosion Control	100	SY		
16	6071010000-E	SP	Wattle	48	LF		
17	6084000000-E	1660	Seeding and Mulching	0.3	AC		
SUBTOTAL:							

REVISED CONTRACT BID FORM

ROAD: SR 2249			PIPE NO.: 2028		COUNTY: Cumberland		
LINE	ITEM NO.	SEC	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT BID
1	0001000000-N	800	Mobilization	1	LS		
2	0043000000-N	SP	Comprehensive Grading	1	LS		
3	0106000000-E	230	Borrow	50	CY		
4	1077000000-E	SP	#57 Stone / Backfill	490	TON		
5	0995000000-E	SP	Pipe Removal	44	LF		
6	1220000000-E	545	Aggregate Base Course	42	TON		
7	1498000000-E	610	ACIC, Type I19.0B	26	TON		
8	1525000000-E	610	ACSC, Type SF9.5A	41	TON		
9	1575000000-E	620	Asphalt Binder, Grade PG 64-22	6	TON		
10	2474000000-N	SP	Pipe & Headwall (13'-7" x 4'-7" Arch w/Headwalls)	1	LS		
11	3691000000-N	SP	Dewatering	1	EA		
12	5912000000-N	SP	Utility Relocations	1	EA		
13	6000000000-E	1605	Temporary Silt Fence	150	LF		
14	6000900000-E	1610	Stone for Erosion Control -Class B	80	TON		
15	6036000000-E	1631	Matting for Erosion Control	50	SY		
16	6071010000-E	SP	Wattle	48	LF		
17	6084000000-E	1660	Seeding and Mulching	0.3	AC		
SUBTOTAL:							

REVISED CONTRACT BID FORM

ROAD: SR 2255			PIPE NO.: 2032		COUNTY: Cumberland		
LINE	ITEM NO.	SEC	DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT BID
1	0001000000-N	800	Mobilization	1	LS		
2	0043000000-N	SP	Comprehensive Grading	1	LS		
3	0106000000-E	230	Borrow	50	CY		
4	1077000000-E	SP	#57 Stone / Backfill	790	TON		
5	0995000000-E	SP	Pipe Removal	60	LF		
6	1220000000-E	545	Aggregate Base Course	100	TON		
7	1498000000-E	610	ACIC, Type I19.0B	30	TON		
8	1525000000-E	610	ACSC, Type SF9.5A	50	TON		
9	1575000000-E	620	Asphalt Binder, Grade PG 64-22	6	TON		
10	2474000000-N	SP	Pipe & Headwall (12'-11" x 7'-6" Arch w/Headwalls)	1	LS		
11	3691000000-N	SP	Dewatering	1	EA		
12	5912000000-N	SP	Utility Relocations	1	EA		
13	6000000000-E	1605	Temporary Silt Fence	150	LF		
14	6000900000-E	1610	Stone for Erosion Control -Class B	100	TON		
15	6036000000-E	1631	Matting for Erosion Control	100	SY		
16	6071010000-E	SP	Wattle	48	LF		
17	6084000000-E	1660	Seeding and Mulching	0.3	AC		
SUBTOTAL:							

TOTAL BID FOR PROJECT: _____