



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

December 14, 2022

BID OPENING: JANUARY 5, 2023, AT 2:00 P.M.
CONTRACT ID: DG00600
WBS ELEMENT NO.: 17BP.7. R.127
COUNTY: GUILFORD
LOCATION: SR1523/1538 (DEEP RIVER ROAD)
DESCRIPTION: REPLACE BRIDGE #67 OVER WEST FORK DEEP RIVER
TYPE OF WORK: GRADING, PAVING, DRAINAGE AND STRUCTURE
SUBJECT: INVITATION TO BID

This is to request quotations for replacing Bridge #67 over West Fork Deep River on SR 1523/1538 (Deep River Road) in Guilford County. The Contractor is to supply materials, equipment, and labor.

The bid opening will be January 5, 2023, at 2:00 p.m. The floating availability date is February 1, 2023, until May 1, 2023. The completion date is 360 consecutive calendar days from the start of construction.

Questions shall be emailed to Jennifer Sour at jsour@ncdot.gov prior to the bid opening. Contact with any other NCDOT personnel concerning this project is strictly prohibited and will result in bids being considered non-responsive

The public letting will be held via conference call. You may join the conference call just prior to 2pm on 1/5/2023. Please dial (919) 250-7881, announce name and company name when prompted.

Bid packages are now available on the NCDOT website at the following location: https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=7. Please download and print your bid package from the website.

This project shall be bid online. Contractors who wish to submit a bid and do not have a DIVISION ID from Bid Express should pursue obtaining the required ID as it may take several days for the ID to be issued.

Regards,

DocuSigned by:

Jennifer A. Sour

B213233052CA46B...

Jennifer A. Sour

DIVISION PROPOSAL ENGINEER

JAS/bcj

cc: file

cc: W. R. Archer, III, PE P. P. Eason, PE P. D. Wilson, PE C. B. Smitherman, PE
T. Powers, PE K. Lorenz, PE Plan Rooms Prospective Bidders

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS DIVISION 7
PO BOX 14996
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075
Fax: (336) 334-3637
Customer Service: 1-877-368-4968

Location:
1584 YANCEYVILLE STREET
GREENSBORO, NC 27405

Website: www.ncdot.gov

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** (15+33.00 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	15 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	10 TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	25 SY		
0008	0378000000-E	310	24" RC PIPE CULVERTS, CLASS III	44 LF		
0009	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	24 LF		
0010	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK (15", 0.064")	2 EA		
0011	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0012	1330000000-E	607	INCIDENTAL MILLING	495 SY		
0013	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	500 TON		
0014	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	775 TON		
0015	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	620 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	100 TON		
0017	2253000000-E	840	PIPE COLLARS	0.56 CY		

Dec 13, 2022 1:06 PM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00600

Page 2 of 6

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	1 EA		
0019	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	1 EA		
0020	2556000000-E	846	SHOULDER BERM GUTTER	20 LF		
0021	2830000000-N	858	ADJUSTMENT OF MANHOLES	2 EA		
0022	2845000000-N	858	ADJUSTMENT OF METER BOXES OR VALVE BOXES	3 EA		
0023	3030000000-E	862	STEEL BEAM GUARDRAIL	325 LF		
0024	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	37.5 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0027	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0028	3288000000-N	SP	GUARDRAIL END UNITS, TYPE TL-2	3 EA		
0029	3628000000-E	876	RIP RAP, CLASS I	36 TON		
0030	3649000000-E	876	RIP RAP, CLASS B	9 TON		
0031	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	956 SY		
0032	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	515 SF		
0033	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0034	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		

Dec 13, 2022 1:06 PM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00600

Page 3 of 6

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	5,125 LF		
0036	6000000000-E	1605	TEMPORARY SILT FENCE	2,020 LF		
0037	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	65 TON		
0038	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	175 TON		
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	370 TON		
0040	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5 TON		
0043	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0044	6029000000-E	SP	SAFETY FENCE	200 LF		
0045	6030000000-E	1630	SILT EXCAVATION	160 CY		
0046	6036000000-E	1631	MATTING FOR EROSION CONTROL	1,435 SY		
0047	6037000000-E	SP	COIR FIBER MAT	415 SY		
0048	6042000000-E	1632	1/4" HARDWARE CLOTH	485 LF		
0049	6070000000-N	1639	SPECIAL STILLING BASINS	12 EA		
0050	6071012000-E	SP	COIR FIBER WATTLE	130 LF		
0051	6071020000-E	SP	POLYACRYLAMIDE (PAM)	40 LB		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0053	6087000000-E	1660	MOWING	3 ACR		
0054	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0055	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0056	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0057	6108000000-E	1665	FERTILIZER TOPDRESSING	1 TON		
0058	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0059	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0060	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0061	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0062	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (15+33.00 -L-)	Lump Sum	L.S.	
0063	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0064	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	75 LF		
0065	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	57 LF		
0066	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	63.9 LF		
0067	8112730000-N	450	PDA TESTING	1 EA		

Dec 13, 2022 1:06 PM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00600

Page 5 of 6

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0068	8113000000-N	411	SID INSPECTIONS	2 EA		
0069	8115000000-N	411	CSL TESTING	2 EA		
0070	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (15+33.00 -L-)	Lump Sum	L.S.	
0071	8156000000-E	SP	CONCRETE WEARING SURFACE	5,485 SF		
0072	8161000000-E	420	GROOVING BRIDGE FLOORS	5,805 SF		
0073	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	91.5 CY		
0074	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (15-33.00 -L-)	Lump Sum	L.S.	
0075	8217000000-E	425	REINFORCING STEEL (BRIDGE)	27,563 LB		
0076	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	3,148 LB		
0077	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12X53 STEEL PILES)	14 EA		
0078	8364000000-E	450	HP 12 X 53 STEEL PILES	280 LF		
0079	8391000000-N	450	STEEL PILE POINTS	14 EA		
0080	8475000000-E	460	TWO BAR METAL RAIL	284.89 LF		
0081	8522000000-E	460	GENERIC STRUCTURE ITEM 1'-2"X2'-11 1/8" CONCRETE PARAPET	300.52 LF		
0082	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	440 TON		
0083	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	488 SY		
0084	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0085	8762000000-E	430	3'-0" X 1'-9" PRESTRESSED CONC CORED SLABS	1,040 LF		
0086	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	910 LF		

1306/Dec13/Q61868.22/D439077802000/E86

Total Amount Of Bid For Entire Project :