



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

December 14, 2022

BID OPENING: JANUARY 5, 2023, AT 2:00 P.M.  
CONTRACT ID: DG00605  
WBS ELEMENT NO.: 17BP.7. C.18  
COUNTY: ALAMANCE  
LOCATION: SR 2158 (DARRELL NEWTON ROAD)  
DESCRIPTION: CULVERT IMPROVEMENTS ON SR 2158 (DARRELL NEWTON ROAD)  
TYPE OF WORK: GRADING, DRAINAGE. AND CULVERT  
SUBJECT: INVITATION TO BID

This is to request quotations for culvert improvements on SR 2158 (Darrell Newton Road) in Alamance County. The Contractor is to supply materials, equipment, and labor.

The bid opening will be January 5, 2023, at 2:00 p.m. The floating availability date is March 1, 2023, until June 1, 2023. The completion date is 360 consecutive calendar days from the start of construction.

**Questions shall be emailed to Jennifer Sour at [jsour@ncdot.gov](mailto:jsour@ncdot.gov) prior to the bid opening. Contact with any other NCDOT personnel concerning this project is strictly prohibited and will result in bids being considered non-responsive**

**The public letting will be held via conference call.** You may join the conference call just prior to 2pm on 1/5/2023. Please dial (919) 250-7881, announce name and company name when prompted.

**Bid packages are now available on the NCDOT website at the following location: [https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let\\_type=7](https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=7). Please download and print your bid package from the website.**

This project shall be bid online. Contractors who wish to submit a bid and do not have a DIVISION ID from Bid Express should pursue obtaining the required ID as it may take several days for the ID to be issued.

Regards,

DocuSigned by:

*Jennifer A. Sour*

B213233052CA46B...

Jennifer A. Sour  
DIVISION PROPOSAL ENGINEER

JAS/bcj

cc: file

cc: W. R. Archer, III, PE      P. P. Eason, PE      P. D. Wilson, PE      C. B. Smitherman, PE  
T. Powers, PE      B. J. Howell      Plan Rooms      Prospective Bidders

Mailing Address:  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS DIVISION 7  
PO BOX 14996  
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075  
Fax: (336) 334-3637  
Customer Service: 1-877-368-4968

Location:  
1584 YANCEYVILLE STREET  
GREENSBORO, NC 27405

Website: [www.ncdot.gov](http://www.ncdot.gov)

| Line #               | Item Number  | Sec # | Description   | Quantity   | Unit Cost | Amount |
|----------------------|--------------|-------|---|------------|-----------|--------|
| <b>ROADWAY ITEMS</b> |              |       |   |            |           |        |
| 0001                 | 0000100000-N | 800   | MOBILIZATION  | Lump Sum   | L.S.      |        |
| 0002                 | 0043000000-N | 226   | GRADING   | Lump Sum   | L.S.      |        |
| 0003                 | 0223000000-E | 275   | ROCK PLATING  | 350<br>SY  |           |        |
| 0004                 | 0318000000-E | 300   | FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES  | 5<br>TON   |           |        |
| 0005                 | 0320000000-E | 300   | FOUNDATION CONDITIONING GEOTEXTILE  | 15<br>SY   |           |        |
| 0006                 | 0448700000-E | 310   | 42" RC PIPE CULVERTS, CLASS IV  | 12<br>LF   |           |        |
| 0007                 | 0576000000-E | 310   | *** CS PIPE CULVERTS, ***** THICK (72", 0.168")   | 20<br>LF   |           |        |
| 0008                 | 0973100000-E | 330   | *** WELDED STEEL PIPE, ***** THICK, GRADE B IN SOIL (72", 1.00")                            | 92<br>LF   |           |        |
| 0009                 | 0986000000-E | SP    | GENERIC PIPE ITEM<br>60" CENTRIFUGALLY CAST FIBERGLASS REINFORCED POLYMER MORTAR PIPE LINER | 88<br>LF   |           |        |
| 0010                 | 0992000000-E | SP    | GENERIC PIPE ITEM<br>CORRUGATED STEEL CONNECTING BAND                                       | 1<br>EA    |           |        |
| 0011                 | 0995000000-E | 340   | PIPE REMOVAL  | 28<br>LF   |           |        |
| 0012                 | 1077000000-E | SP    | #57 STONE   | 640<br>TON |           |        |
| 0013                 | 1491000000-E | 610   | ASPHALT CONC BASE COURSE, TYPE B25.0C   | 60<br>TON  |           |        |
| 0014                 | 1519000000-E | 610   | ASPHALT CONC SURFACE COURSE, TYPE S9.5B   | 40<br>TON  |           |        |
| 0015                 | 1575000000-E | 620   | ASPHALT BINDER FOR PLANT MIX  | 10<br>TON  |           |        |
| 0016                 | 2253000000-E | 840   | PIPE COLLARS  | 0.89<br>CY |           |        |

Dec 14, 2022 11:25 AM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00605

Page 2 of 5

| Line # | Item Number  | Sec # | Description  | Quantity   | Unit Cost | Amount |
|--------|--------------|-------|--|------------|-----------|--------|
| 0017   | 3030000000-E | 862   | STEEL BEAM GUARDRAIL                               | 175<br>LF  |           |        |
| 0018   | 3150000000-N | 862   | ADDITIONAL GUARDRAIL POSTS                         | 5<br>EA    |           |        |
| 0019   | 3195000000-N | 862   | GUARDRAIL END UNITS, TYPE AT-1                     | 1<br>EA    |           |        |
| 0020   | 3288000000-N | SP    | GUARDRAIL END UNITS, TYPE TL-2                     | 1<br>EA    |           |        |
| 0021   | 3628000000-E | 876   | RIP RAP, CLASS I                                   | 170<br>TON |           |        |
| 0022   | 3635000000-E | 876   | RIP RAP, CLASS II                                  | 40<br>TON  |           |        |
| 0023   | 3656000000-E | 876   | GEOTEXTILE FOR DRAINAGE                            | 700<br>SY  |           |        |
| 0024   | 4400000000-E | 1110  | WORK ZONE SIGNS (STATIONARY)                       | 489<br>SF  |           |        |
| 0025   | 4405000000-E | 1110  | WORK ZONE SIGNS (PORTABLE)                         | 96<br>SF   |           |        |
| 0026   | 4410000000-E | 1110  | WORK ZONE SIGNS (BARRICADE MOUNTED)                | 89<br>SF   |           |        |
| 0027   | 4422000000-N | 1120  | PORTABLE CHANGEABLE MESSAGE SIGN (SHORT TERM)      | 42<br>DAY  |           |        |
| 0028   | 4430000000-N | 1130  | DRUMS  | 20<br>EA   |           |        |
| 0029   | 4445000000-E | 1145  | BARRICADES (TYPE III)                              | 48<br>LF   |           |        |
| 0030   | 4455000000-N | 1150  | FLAGGER  | 20<br>DAY  |           |        |
| 0031   | 4510000000-N | 1190  | LAW ENFORCEMENT                                    | 28<br>HR   |           |        |
| 0032   | 4685000000-E | 1205  | THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS) | 143<br>LF  |           |        |
| 0033   | 4835000000-E | 1205  | PAINT PAVEMENT MARKING LINES (24")                 | 12<br>LF   |           |        |

Dec 14, 2022 11:25 AM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00605

Page 3 of 5

| Line # | Item Number  | Sec # | Description                           | Quantity   | Unit Cost | Amount |
|--------|--------------|-------|---------------------------------------|------------|-----------|--------|
| 0034   | 4900000000-N | 1251  | PERMANENT RAISED PAVEMENT MARKERS     | 2<br>EA    |           |        |
| 0035   | 5325800000-E | 1510  | 8" WATER LINE                         | 130<br>LF  |           |        |
| 0036   | 5329000000-E | 1510  | DUCTILE IRON WATER PIPE FITTINGS      | 750<br>LB  |           |        |
| 0037   | 5546000000-E | 1515  | 8" VALVE                              | 1<br>EA    |           |        |
| 0038   | 5801000000-E | 1530  | ABANDON 8" UTILITY PIPE               | 130<br>LF  |           |        |
| 0039   | 6000000000-E | 1605  | TEMPORARY SILT FENCE                  | 455<br>LF  |           |        |
| 0040   | 6006000000-E | 1610  | STONE FOR EROSION CONTROL,<br>CLASS A | 95<br>TON  |           |        |
| 0041   | 6009000000-E | 1610  | STONE FOR EROSION CONTROL,<br>CLASS B | 40<br>TON  |           |        |
| 0042   | 6012000000-E | 1610  | SEDIMENT CONTROL STONE                | 100<br>TON |           |        |
| 0043   | 6015000000-E | 1615  | TEMPORARY MULCHING                    | 0.5<br>ACR |           |        |
| 0044   | 6018000000-E | 1620  | SEED FOR TEMPORARY SEEDING            | 100<br>LB  |           |        |
| 0045   | 6021000000-E | 1620  | FERTILIZER FOR TEMPORARY<br>SEEDING   | 0.5<br>TON |           |        |
| 0046   | 6024000000-E | 1622  | TEMPORARY SLOPE DRAINS                | 200<br>LF  |           |        |
| 0047   | 6029000000-E | SP    | SAFETY FENCE                          | 980<br>LF  |           |        |
| 0048   | 6030000000-E | 1630  | SILT EXCAVATION                       | 40<br>CY   |           |        |
| 0049   | 6036000000-E | 1631  | MATTING FOR EROSION CONTROL           | 500<br>SY  |           |        |
| 0050   | 6037000000-E | SP    | COIR FIBER MAT                        | 100<br>SY  |           |        |

Dec 14, 2022 11:25 AM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00605

Page 4 of 5

| Line #               | Item Number  | Sec # | Description                   | Quantity    | Unit Cost | Amount |
|----------------------|--------------|-------|-------------------------------|-------------|-----------|--------|
| 0051                 | 6042000000-E | 1632  | 1/4" HARDWARE CLOTH           | 50<br>LF    |           |        |
| 0052                 | 6045000000-E | SP    | *** TEMPORARY PIPE<br>(48")   | 180<br>LF   |           |        |
| 0053                 | 6070000000-N | 1639  | SPECIAL STILLING BASINS       | 4<br>EA     |           |        |
| 0054                 | 6071020000-E | SP    | POLYACRYLAMIDE (PAM)          | 10<br>LB    |           |        |
| 0055                 | 6084000000-E | 1660  | SEEDING & MULCHING            | 0.5<br>ACR  |           |        |
| 0056                 | 6087000000-E | 1660  | MOWING                        | 0.5<br>ACR  |           |        |
| 0057                 | 6090000000-E | 1661  | SEED FOR REPAIR SEEDING       | 50<br>LB    |           |        |
| 0058                 | 6093000000-E | 1661  | FERTILIZER FOR REPAIR SEEDING | 0.25<br>TON |           |        |
| 0059                 | 6096000000-E | 1662  | SEED FOR SUPPLEMENTAL SEEDING | 50<br>LB    |           |        |
| 0060                 | 6108000000-E | 1665  | FERTILIZER TOPDRESSING        | 0.25<br>TON |           |        |
| 0061                 | 6111000000-E | SP    | IMPERVIOUS DIKE               | 55<br>LF    |           |        |
| 0062                 | 6114500000-N | 1667  | SPECIALIZED HAND MOWING       | 10<br>MHR   |           |        |
| 0063                 | 6117000000-N | SP    | RESPONSE FOR EROSION CONTROL  | 13<br>EA    |           |        |
| 0064                 | 6117500000-N | SP    | CONCRETE WASHOUT STRUCTURE    | 3<br>EA     |           |        |
| 0065                 | 6123000000-E | 1670  | REFORESTATION                 | 0.1<br>ACR  |           |        |
| <b>CULVERT ITEMS</b> |              |       |                               |             |           |        |
| 0066                 | 8140000000-E | 416   | CHANNEL EXCAVATION            | 130<br>CY   |           |        |

---

| Line # | Item Number | Sec # | Description | Quantity | Unit Cost | Amount |
|--------|-------------|-------|-------------|----------|-----------|--------|
|--------|-------------|-------|-------------|----------|-----------|--------|

---

1125/Dec14/Q7623.49/D281016720000/E66 Total Amount Of Bid For Entire Project :

---