



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

March 24, 2021

ADDENDUM #1

MEMO TO: Plan Holders

FROM: Chris Smitherman, PE
Project Team Lead

DocuSigned by:
Chris Smitherman
EA7926E3CDA446A...
3/24/2021

RE: Contract Id: DG00512
WBS No.: 2021CPT.07.07.20411
County: Guilford
Location: 43 Various Secondary Roads
Description: Sections of Various Secondary Routes and Ramp to
NC 68 (EB & WB) from SR 4464 (Cornerstone Dr.)
Type of Work: Milling, Widening, Resurfacing & Pavement Markings

To whom it may concern:

It has been brought to my attention that base index for the asphalt adjustment provision was not included in the proposal.

Page 32: Price Adjustment-Asphalt Binder for Plant Mix

Please replace this page in your proposal and acknowledge receipt of the addendum on the appropriate proposal sheet.

CBS/rts

ec: Plan Rooms
Website

CONSTRUCTION SEQUENCE:

(7-1-95) (Rev. 8-21-12)

560

SP1 R34R

Pave each section of roadway begun in a continuous operation. Do not begin work on another section of roadway unless satisfactory progress is being made toward completion of intersections and all other required incidental work by satisfactorily furnishing additional paving equipment and personnel, except for milling and patching operations.

PRICE ADJUSTMENT - ASPHALT BINDER FOR PLANT MIX:

(11-21-00)

620

SP6 R25

Price adjustments for asphalt binder for plant mix will be made in accordance with Section 620 of the *2018 Standard Specifications*.

The base price index for asphalt binder for plant mix is **450.38** per ton.

This base price index represents an average of F.O.B. selling prices of asphalt binder at supplier's terminals on **March 1, 2021**.

INCIDENTAL STONE BASE:

(7-1-95) (Rev.8-21-12)

545

SP5 R28R

Description

Place incidental stone base on driveways, mailboxes, etc. immediately after paving and do not have the paving operations exceed stone base placement by more than one week without written permission of the Engineer.

Materials and Construction

Provide and place incidental stone base in accordance with Section 545 of the *2018 Standard Specifications*.

Measurement and Payment

Incidental Stone Base will be measured and paid in accordance with Article 545-6 of the *2018 Standard Specifications*.

SHOULDER WEDGE:

(9-20-11) (Rev. 8-21-12)

610

SP6 R03R

Revise the *2018 Standard Specifications* as follows:

Page 6-21, Article 610-8, SPREADING AND FINISHING, add the following after line 39:

Attach a device, mounted on screed of paving equipment, capable of constructing a shoulder wedge with an angle of 30 degrees plus or minus 4 degrees along the outside edge of the roadway, measured from the horizontal plane in place after final compaction on the final surface course. Use an approved mechanical device which will form the asphalt mixture to produce a wedge with uniform texture, shape and density while automatically adjusting to varying heights.