



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

ROY COOPER  
GOVERNOR

J. ERIC BOYETTE  
SECRETARY

March 17, 2021

BID OPENING: APRIL 15, 2021 AT 2:00 P.M.  
CONTRACT ID: DG00514  
WBS ELEMENT NO.: 17BP.7.R.110  
COUNTY: CASWELL  
LOCATION: SR 1771 (DAVE SMITH ROAD)  
DESCRIPTION: REPLACE BRIDGE #19 OVER LYNCH CREEK ON SR 1771 (DAVE SMITH ROAD)  
TYPE OF WORK: GRADING, PAVING, SHOULDER CONSTRUCTION & CULVERT  
SUBJECT: INVITATION TO BID

This is to request quotations for replacing bridge #19 over Lynch Creek on SR 1771 (Dave Smith Road) in Caswell County. The Contractor is to supply materials, equipment, and labor.

The bid opening will be April 15, 2021 at 2:00 p.m. The availability date is June 21, 2021. The completion date is October 19, 2021.

**The public letting will be held via conference call.** You may join the conference call just prior to 2pm on 4/15/2021. Please dial 1-800-747-5150 and enter access code 3343192 when prompted.

**Bid packages are now available on the NCDOT website at the following location:** [https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let\\_type=7](https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=7). **Please download and print your bid package from the website.**

This project shall be bid online. Contractors who wish to submit a bid and do not have a DIVISION ID from Bid Express should pursue obtaining the required ID as it may take several days for the ID to be issued.

Regards,

DocuSigned by:

*Chris Smitherman*

EA7928E3CDA446A...  
C. B. Smitherman, PE  
PROJECT TEAM LEAD

CBS/rts

cc: file

cc: W. R Archer, III, PE    P. P. Eason, PE    P. D. Wilson, PE    T Powers, PE  
C. N. Edwards, PE    M. D. Hayes, PE    Prospective Bidders    Plan Rooms

Mailing Address:  
NC DEPARTMENT OF TRANSPORTATION  
DIVISION OF HIGHWAYS DIVISION 7  
PO BOX 14996  
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075  
Fax: (336) 334-3637  
Customer Service: 1-877-368-4968

Location:  
1584 YANCEYVILLE STREET  
GREENSBORO, NC 27405

Website: [www.ncdot.gov](http://www.ncdot.gov)

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
<b>ROADWAY ITEMS</b>						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** (STATION 15+64.00-L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	10 TON		
0006	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	30 SY		
0007	0335200000-E	305	15" DRAINAGE PIPE	20 LF		
0008	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	24 LF		
0009	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	32 LF		
0010	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK 15", 0.064"	2 EA		
0011	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0012	1330000000-E	607	INCIDENTAL MILLING	235 SY		
0013	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	150 TON		
0014	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	230 TON		
0015	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	330 TON		
0016	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	40 TON		
0017	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0018	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2556000000-E	846	SHOULDER BERM GUTTER	60		LF
0020	3030000000-E	862	STEEL BEAM GUARDRAIL	425		LF
0021	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4		EA
0022	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4		EA
0023	3649000000-E	876	RIP RAP, CLASS B	7		TON
0024	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	212		SY
0025	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	401		SF
0026	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94		SF
0027	4445000000-E	1145	BARRICADES (TYPE III)	80		LF
0028	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	1,100		LF
0029	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120 MILS)	1,100		LF
0030	6000000000-E	1605	TEMPORARY SILT FENCE	1,050		LF
0031	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	65		TON
0032	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	65		TON
0033	6012000000-E	1610	SEDIMENT CONTROL STONE	55		TON
0034	6015000000-E	1615	TEMPORARY MULCHING	0.5		ACR
0035	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100		LB
0036	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5		TON
0037	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200		LF

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6029000000-E	SP	SAFETY FENCE	400 LF		
0039	6030000000-E	1630	SILT EXCAVATION	80 CY		
0040	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,140 SY		
0041	6037000000-E	SP	COIR FIBER MAT	100 SY		
0042	6042000000-E	1632	1/4" HARDWARE CLOTH	185 LF		
0043	6071020000-E	SP	POLYACRYLAMIDE (PAM)	5 LB		
0044	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0045	6087000000-E	1660	MOWING	0.5 ACR		
0046	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0047	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0048	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0049	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0050	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0051	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13 EA		
0052	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		

---

**STRUCTURE ITEMS**


---

0053	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (STATION 15+64.00-L-)	Lump Sum	L.S.	
0054	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0055	8112730000-N	450	PDA TESTING	1 EA		

County : Caswell

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0056	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVATION AT STATION ***** (STATION 15+64.00-L-)	Lump Sum	L.S.	
0057	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	60 CY		
0058	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (STATION 15+64.00-L-)	Lump Sum	L.S.	
0059	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,426 LB		
0060	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES 12X53	10 EA		
0061	8364000000-E	450	HP12X53 STEEL PILES	325 LF		
0062	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	200 LF		
0063	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	395 TON		
0064	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	445 SY		
0065	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0066	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,000 LF		

1132/Feb11/Q26064.5/D314064050000/E66

Total Amount Of Bid For Entire Project :