



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

April 14, 2021

BID OPENING: MAY 6, 2021 AT 2:00 P.M.
CONTRACT ID: DG00521
WBS ELEMENT NO.: 17BP.7.R.106
COUNTY: ALAMANCE
LOCATION: SR 1113 (KIMESVILLE ROAD)
DESCRIPTION: REPLACE BRIDGE NO. 000164 OVER NORTH PRONG STINKING
QUARTER CREEK ON SR 1113 (KIMESVILLE ROAD)
TYPE OF WORK: GRADING, PAVING, DRAINAGE & CULVERT
SUBJECT: INVITATION TO BID

This is to request quotations for replacing bridge #000164 over North Prong Stinking Quarter Creek on SR 1113 (Kimesville Road) in Alamance County. The Contractor is to supply materials, equipment, and labor.

The bid opening will be May 6, 2021 at 2:00 p.m. The availability date is June 21, 2021. The completion date is November 18, 2021.

The public letting will be held via conference call. You may join the conference call just prior to 2pm on 5/6/2021. Please dial 1-800-747-5150 and enter access code 3343192 when prompted.

Bid packages are now available on the NCDOT website at the following location: https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=7. **Please download and print your bid package from the website.**

This project shall be bid online. Contractors who wish to submit a bid and do not have a DIVISION ID from Bid Express should pursue obtaining the required ID as it may take several days for the ID to be issued.

Regards,

DocuSigned by:

Jennifer A. Sour

B213233052CA46B...

J. A. Sour

Division Proposal Engineer

JAS/rts

cc: file

cc: W. R Archer, III, PE P. P. Eason, PE P. D. Wilson, PE C. B. Smitherman, PE
T Powers, PE C. N. Edwards, PE M. D. Hayes, PE Prospective Bidders
Plan Rooms

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS DIVISION 7
PO BOX 14996
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075
Fax: (336) 334-3637
Customer Service: 1-877-368-4968

Location:
1584 YANCEYVILLE STREET
GREENSBORO, NC 27405

Website: www.ncdot.gov

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** (STATION 15+79.50)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	40 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	15 TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	45 SY		
0008	0343000000-E	310	15" SIDE DRAIN PIPE	28 LF		
0009	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	44 LF		
0010	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	48 LF		
0011	0636000000-E	310	*** CS PIPE ELBOWS, ***** THICK 0.064 THICK	4 EA		
0012	0995000000-E	340	PIPE REMOVAL (STATION 15+52.00-L-)	28 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0014	1330000000-E	607	INCIDENTAL MILLING	240 SY		
0015	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	400 TON		
0016	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	460 TON		
0017	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	450 TON		
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	70 TON		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	3 EA		
0020	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	185 LF		
0022	3030000000-E	862	STEEL BEAM GUARDRAIL	487.5 LF		
0023	3045000000-E	862	STEEL BEAM GUARDRAIL, SHOP CURVED	12.5 LF		
0024	3195000000-N	862	GUARDRAIL END UNITS, TYPE AT-1	1 EA		
0025	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0026	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	3 EA		
0027	3635000000-E	876	RIP RAP, CLASS II	95 TON		
0028	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	307 SY		
0030	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	433 SF		
0031	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0032	4445000000-E	1145	BARRICADES (TYPE III)	80 LF		
0033	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	3,600 LF		
0034	6000000000-E	1605	TEMPORARY SILT FENCE	1,005 LF		
0035	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	65 TON		
0036	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	185 TON		
0037	6012000000-E	1610	SEDIMENT CONTROL STONE	90 TON		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6015000000-E	1615	TEMPORARY MULCHING	0.5	ACR	
0039	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100	LB	
0040	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	0.5	TON	
0041	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200	LF	
0042	6029000000-E	SP	SAFETY FENCE	400	LF	
0043	6030000000-E	1630	SILT EXCAVATION	130	CY	
0044	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,485	SY	
0045	6037000000-E	SP	COIR FIBER MAT	495	SY	
0046	6042000000-E	1632	1/4" HARDWARE CLOTH	245	LF	
0047	6048000000-E	SP	FLOATING TURBIDITY CURTAIN	20	SY	
0048	6071020000-E	SP	POLYACRYLAMIDE (PAM) 15", 0.064"	25	LB	
0049	6084000000-E	1660	SEEDING & MULCHING	0.5	ACR	
0050	6087000000-E	1660	MOWING	0.5	ACR	
0051	6090000000-E	1661	SEED FOR REPAIR SEEDING	50	LB	
0052	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25	TON	
0053	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50	LB	
0054	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25	TON	
0055	6111000000-E	SP	IMPERVIOUS DIKE	98	LF	
0056	6114500000-N	1667	SPECIALIZED HAND MOWING	10	MHR	
0057	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	13	EA	

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0058	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0059	6123000000-E	1670	REFORESTATION	0.1 ACR		
STRUCTURE ITEMS						
0060	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (STATION 15+79.50L)	Lump Sum	L.S.	
0061	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0062	8105520000-E	411	3'-0" DIA DRILLED PIERS IN SOIL	39.25 LF		
0063	8105620000-E	411	3'-0" DIA DRILLED PIERS NOT IN SOIL	25 LF		
0064	8111200000-E	411	PERMANENT STEEL CASING FOR 3'-0" DIA DRILLED PIER	46.25 LF		
0065	8113000000-N	411	SID INSPECTIONS	1 EA		
0066	8115000000-N	411	CSL TESTING	1 EA		
0067	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (STATION 15+79.50-L-)	Lump Sum	L.S.	
0068	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	85.5 CY		
0069	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (STATION 15+79.50-L-)	Lump Sum	L.S.	
0070	8217000000-E	425	REINFORCING STEEL (BRIDGE)	20,344 LB		
0071	8238000000-E	425	SPIRAL COLUMN REINFORCING STEEL (BRIDGE)	1,485 LB		
0072	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES 12X53	14 EA		

County : Alamance

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0073	8364000000-E	450	HP12X53 STEEL PILES	315		
				LF		
0074	8475000000-E	460	TWO BAR METAL RAIL	253.94		
				LF		
0075	8517000000-E	460	1'-***"X *****" CONCRETE PARA- PET 1'-2" X 2'-9 1/2"	270		
				LF		
0076	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK) (STATION 15+79.50L-)	355		
				TON		
0077	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	395		
				SY		
0078	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0079	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,485		
				LF		

1118/Apr07/Q43004.54/D387834460000/E79

Total Amount Of Bid For Entire Project :