



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

May 12, 2021

BID OPENING: JUNE 3, 2021 AT 2:00 P.M.
CONTRACT ID: DG00493
WBS ELEMENT NO.: 17BP.7.C.14
COUNTY: GUILFORD
LOCATION: SR 2835 (MCKNIGHT MILL ROAD)
DESCRIPTION: REPLACE NON-INVENTORY PIPE #40-2134 ON SR 2835
(MCKNIGHT MILL ROAD) APPROXIMATELY 0.1 MILES SOUTH
OF THE INTERSECTION WITH SR 2732 (HINES CHAPEL ROAD)
TYPE OF WORK: GRADING, PAVING, SHOULDER CONSTRUCTION & CULVERT
SUBJECT: INVITATION TO BID

This is to request quotations for replacing non-inventory Pipe #40-2134 on SR 2835 (McKnight Mill Road) in Guilford County. The Contractor is to supply materials, equipment, and labor.

The bid opening will be June 3, 2021 at 2:00 p.m. The availability date is July 8, 2021. The completion date is September 9, 2021.

The public letting will be held via conference call. You may join the conference call just prior to 2pm on 6/3/2021. Please dial 1-800-747-5150 and enter access code 3343192 when prompted.

Bid packages are now available on the NCDOT website at the following location: https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=7. **Please download and print your bid package from the website.**

This project shall be bid online. Contractors who wish to submit a bid and do not have a DIVISION ID from Bid Express should pursue obtaining the required ID as it may take several days for the ID to be issued.

Regards,

DocuSigned by:

Jennifer A. Sour

B213233052CA46B...

J. A. Sour

DIVISION PROPOSAL ENGINEER

JAS/rts

cc: file

cc: W. R Archer, III, PE P. P. Eason, PE P. D. Wilson, PE C. B. Smitherman, PE
T Powers, PE W. H. Snell, PE Plan Rooms Prospective Bidders

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS DIVISION 7
PO BOX 14996
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075
Fax: (336) 334-3637
Customer Service: 1-877-368-4968

Location:
1584 YANCEYVILLE STREET
GREENSBORO, NC 27405

Website: www.ncdot.gov

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0043000000-N	226	GRADING	Lump Sum	L.S.	
0003	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	40 TON		
0004	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	160 SY		
0005	1220000000-E	545	INCIDENTAL STONE BASE	50 TON		
0006	1330000000-E	607	INCIDENTAL MILLING	65 SY		
0007	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	50 TON		
0008	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	20 TON		
0009	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	40 TON		
0010	3628000000-E	876	RIP RAP, CLASS I	40 TON		
0011	3649000000-E	876	RIP RAP, CLASS B	5 TON		
0012	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	315 SY		
0013	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	614 SF		
0014	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	144 SF		
0015	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	2 EA		
0016	4445000000-E	1145	BARRICADES (TYPE III)	112 LF		
0017	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	220 LF		
0018	6000000000-E	1605	TEMPORARY SILT FENCE	1,400 LF		
0019	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	55 TON		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0020	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	70 TON		
0021	6012000000-E	1610	SEDIMENT CONTROL STONE	95 TON		
0022	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0023	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0024	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0025	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0026	6029000000-E	SP	SAFETY FENCE	200 LF		
0027	6030000000-E	1630	SILT EXCAVATION	10 CY		
0028	6036000000-E	1631	MATTING FOR EROSION CONTROL	800 SY		
0029	6037000000-E	SP	COIR FIBER MAT	100 SY		
0030	6042000000-E	1632	1/4" HARDWARE CLOTH	210 LF		
0031	6070000000-N	1639	SPECIAL STILLING BASINS	2 EA		
0032	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0033	6087000000-E	1660	MOWING	0.5 ACR		
0034	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0035	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0036	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0037	6108000000-E	1665	FERTILIZER TOPDRESSING	0.25 TON		
0038	6111000000-E	SP	IMPERVIOUS DIKE	34 LF		
0039	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		

County : Guilford

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0040	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	3 EA		
0041	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		
0042	8804000000-N	SP	GENERIC CULVERT ITEM 47' #5-L2(10'-6"SPAN X 5'-7" R ISE) ALUMN BOX CUL W FULL ALUM INVERT LRD G HL93	Lump Sum	L.S.	
			1120/May11/Q5273.5/D195278100000/E42			
			Total Amount Of Bid For Entire Project :			