



CONTRACT:




ROCKINGHAM COUNTY

TYPE OF WORK: GRADING, PAVING, DRAINAGE AND CULVERT

[illegible]

**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**



SUB REGIONAL TIER
LOCAL

TOTAL LENGTH TIP PROJECT = 0.085 MILES

NCDOT CONTACT:


TIM POWERS, PE
*DIVISION BRIDGE
PROGRAM MANAGER*

DocuSign Envelope ID: E14BC27398BE439

SIGNATURE:

PO Box 700
Fuquay-Varina, NC 27526
(919) 552-2253
(919) 552-2254 (Fax)
www.mottmac.com

LICENSE NO. F-0669



ICA
Engineering

5121 Kingdom Way
Suite 100
Raleigh, NC 27607
NC License No: F-0258

GENERAL NOTES:

2012 SPECIFICATIONS
EFFECTIVE: 01-17-2012
REVISED: 10-31-2014

GRADE LINE:

GRADING AND SURFACING:

THE GRADE LINES SHOWN DENOTE THE FINISHED ELEVATION OF THE PROPOSED SURFACING AT GRADE POINTS SHOWN ON THE TYPICAL SECTIONS. GRADE LINES MAY BE ADJUSTED AT THEIR BEGINNING AND ENDING AND AT STRUCTURES AS DIRECTED BY THE ENGINEER IN ORDER TO SECURE A PROPER TIE-IN.

CLEARING:

CLEARING ON THIS PROJECT SHALL BE PERFORMED TO THE LIMITS ESTABLISHED BY METHOD II.

SUPERELEVATION:

ALL CURVES ON THIS PROJECT SHALL BE SUPERELEVATED IN ACCORDANCE WITH STD. NO. 225.04 USING THE RATE OF SUPERELEVATION AND RUNOFF SHOWN ON THE PLANS. SUPERELEVATION IS TO BE REVOLVED ABOUT THE GRADE POINTS SHOWN ON THE TYPICAL SECTIONS.

SHOULDER CONSTRUCTION:

ASPHALT, EARTH, AND CONCRETE SHOULDER CONSTRUCTION ON THE HIGH SIDE OF SUPERELEVATED CURVES SHALL BE IN ACCORDANCE WITH STD. NO. 560.01

GUARDRAIL:

THE GUARDRAIL LOCATIONS SHOWN ON THE PLANS MAY BE ADJUSTED DURING CONSTRUCTION AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHOULD CONSULT WITH THE ENGINEER PRIOR TO ORDERING GUARDRAIL MATERIAL.




SUBSURFACE PLANS:

NO SUBSURFACE PLANS ARE AVAILABLE ON THIS PROJECT. THE CONTRACTOR SHOULD MAKE HIS OWN INVESTIGATION AS TO THE SUBSURFACE CONDITIONS.

UTILITIES:

UTILITY OWNERS ON THIS PROJECT ARE DUKE ENERGY, AT&T AND DAN RIVER WATER.

ANY RELOCATION OF EXISTING UTILITIES WILL BE ACCOMPLISHED BY OTHERS.

PROJECT REFERENCE		SHEET NO.
17BP.7.R.103 – ROCKINGHAM 248		1-A
ROADWAY DESIGN ENGINEER		
		
MOTT MACDONALD 1 & E, LLC LICENSE NO. E-0669		
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		
Prepared in the Office of:		 PO. Box 700 Fuquay-Varina, NC 27526 www.mottmac.com

	INDEX OF SHEETS
SHEET NUMBER	DESCRIPTION
1	TITLE SHEET
1-A	INDEX OF SHEETS, GENERAL NOTES, AND LIST OF STANDARD DRAWINGS
1-B	CONVENTIONAL SYMBOLS
2	PAVEMENT SCHEDULE AND TYPICAL SECTIONS
3	GUARDRAIL & EARTHWORK SUMMARY
4	PLAN SHEET AND PROFILE SHEET
TMP-1 THRU TMP-3	TRAFFIC MANAGEMENT PLANS
EC-1 THRU EC-5	EROSION CONTROL PLANS
UC-1 THRU UC-4	UTILITY CONSTRUCTION PLANS
UO-1	UTILITIES BY OTHERS PLAN
X-1 THRU X-2	CROSS-SECTIONS
C-1 THRU C-6	CULVERT PLANS
CN	STANDARD CULVERT NOTES

EFF. 01-17-2012
REV. 02-29-16

2012 ROADWAY ENGLISH STANDARD DRAWINGS

The following Roadway Standards as appear in “Roadway Standard Drawings” Highway Design Branch – N. C. Department of Transportation – Raleigh, N. C., Dated January, 2012 are applicable to this project and by reference hereby are considered a part of these plans:

STD.NO.	TITLE
DIVISION 2 – EARTHWORK	
200.02	Method of Clearing – Method II
225.02	Guide for Grading Subgrade – Secondary and Local
225.04	Method of Obtaining Superelevation – Two Lane Pavement
DIVISION 5 – SUBGRADE, BASES AND SHOULDERS	
560.01	Method of Shoulder Construction – High Side of Superelevated Curve – Method I
DIVISION 8 – INCIDENTALS	
862.01	Guardrail Placement
862.02	Guardrail Installation
876.01	Rip Rap in Channels
876.04	Drainage Ditches with Class ‘B’ Rip Rap

Note: Not to Scale

**S.U.E. = Subsurface Utility Engineering*

BOUNDARIES AND PROPERTY:

State Line	
County Line	
Township Line	
City Line	
Reservation Line	
Property Line	
Existing Iron Pin	
Property Corner	
Property Monument	
Parcel/Sequence Number	
Existing Fence Line	
Proposed Woven Wire Fence	
Proposed Chain Link Fence	
Proposed Barbed Wire Fence	
Existing Wetland Boundary	
Proposed Wetland Boundary	
Existing Endangered Animal Boundary	
Existing Endangered Plant Boundary	
Existing Historic Property Boundary	
Known Contamination Area: Soil	
Potential Contamination Area: Soil	
Known Contamination Area: Water	
Potential Contamination Area: Water	
Contaminated Site: Known or Potential	

BUILDINGS AND OTHER CULTURE:

Gas Pump Vent or U/G Tank Cap	
Sign	
Well	
Small Mine	
Foundation	
Area Outline	
Cemetery	
Building	
School	
Church	
Dam	

HYDROLOGY:

Stream or Body of Water	
Hydro, Pool or Reservoir	
Jurisdictional Stream	
Buffer Zone 1	
Buffer Zone 2	
Flow Arrow	
Disappearing Stream	
Spring	
Wetland	
Proposed Lateral, Tail, Head Ditch	
False Sump	

RAILROADS:

Standard Gauge	
RR Signal Milepost	
Switch	
RR Abandoned	
RR Dismantled	

RIGHT OF WAY:

Baseline Control Point	
Existing Right of Way Marker	
Existing Right of Way Line	
Proposed Right of Way Line	
Proposed Right of Way Line with Iron Pin and Cap Marker	
Proposed Right of Way Line with Concrete or Granite RW Marker	
Proposed Control of Access Line with Concrete C/A Marker	
Existing Control of Access	
Proposed Control of Access	
Existing Easement Line	
Proposed Temporary Construction Easement	
Proposed Temporary Drainage Easement	
Proposed Permanent Drainage Easement	
Proposed Permanent Drainage / Utility Easement	
Proposed Permanent Utility Easement	
Proposed Temporary Utility Easement	
Proposed Aerial Utility Easement	
Proposed Permanent Easement with Iron Pin and Cap Marker	

ROADS AND RELATED FEATURES:

Existing Edge of Pavement	
Existing Curb	
Proposed Slope Stakes Cut	
Proposed Slope Stakes Fill	
Proposed Curb Ramp	
Existing Metal Guardrail	
Proposed Guardrail	
Existing Cable Guiderail	
Proposed Cable Guiderail	
Equality Symbol	
Pavement Removal	
Single Tree	
Single Shrub	
Hedge	
Woods Line	

VEGETATION:

--	--

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

CONVENTIONAL PLAN SHEET SYMBOLS

Orchard	
Vineyard	

EXISTING STRUCTURES:

MAJOR:	
Bridge, Tunnel or Box Culvert	
Bridge Wing Wall, Head Wall and End Wall	
MINOR:	
Head and End Wall	
Pipe Culvert	
Footbridge	
Drainage Box: Catch Basin, DI or JB	
Paved Ditch Gutter	
Storm Sewer Manhole	
Storm Sewer	

UTILITIES:

POWER:	
Existing Power Pole	
Proposed Power Pole	
Existing Joint Use Pole	
Proposed Joint Use Pole	
Power Manhole	
Power Line Tower	
Power Transformer	
U/G Power Cable Hand Hole	
H-Frame Pole	
U/G Power Line LOS B (S.U.E.*)	
U/G Power Line LOS C (S.U.E.*)	
U/G Power Line LOS D (S.U.E.*)	

TELEPHONE:

Existing Telephone Pole	
Proposed Telephone Pole	
Telephone Manhole	
Telephone Pedestal	
Telephone Cell Tower	
U/G Telephone Cable Hand Hole	
U/G Telephone Cable LOS B (S.U.E.*)	
U/G Telephone Cable LOS C (S.U.E.*)	
U/G Telephone Cable LOS D (S.U.E.*)	
U/G Telephone Conduit LOS B (S.U.E.*)	
U/G Telephone Conduit LOS C (S.U.E.*)	
U/G Telephone Conduit LOS D (S.U.E.*)	
U/G Fiber Optics Cable LOS B (S.U.E.*)	
U/G Fiber Optics Cable LOS C (S.U.E.*)	
U/G Fiber Optics Cable LOS D (S.U.E.*)	

WATER:

Water Manhole	
Water Meter	
Water Valve	
Water Hydrant	
U/G Water Line LOS B (S.U.E.*)	
U/G Water Line LOS C (S.U.E.*)	
U/G Water Line LOS D (S.U.E.*)	
Above Ground Water Line	

TV:

TV Pedestal	
TV Tower	
U/G TV Cable Hand Hole	
U/G TV Cable LOS B (S.U.E.*)	
U/G TV Cable LOS C (S.U.E.*)	
U/G TV Cable LOS D (S.U.E.*)	
U/G Fiber Optic Cable LOS B (S.U.E.*)	
U/G Fiber Optic Cable LOS C (S.U.E.*)	
U/G Fiber Optic Cable LOS D (S.U.E.*)	

GAS:

Gas Valve	
Gas Meter	
U/G Gas Line LOS B (S.U.E.*)	
U/G Gas Line LOS C (S.U.E.*)	
U/G Gas Line LOS D (S.U.E.*)	
Above Ground Gas Line	

SANITARY SEWER:

Sanitary Sewer Manhole	
Sanitary Sewer Cleanout	
U/G Sanitary Sewer Line	
Above Ground Sanitary Sewer	
SS Forced Main Line LOS B (S.U.E.*)	
SS Forced Main Line LOS C (S.U.E.*)	
SS Forced Main Line LOS D (S.U.E.*)	

MISCELLANEOUS:

Utility Pole	
Utility Pole with Base	
Utility Located Object	
Utility Traffic Signal Box	
Utility Unknown U/G Line LOS B (S.U.E.*)	
U/G Tank; Water, Gas, Oil	
Underground Storage Tank, Approx. Loc.	
A/G Tank; Water, Gas, Oil	
Geoenvironmental Boring	
U/G Test Hole LOS A (S.U.E.*)	
Abandoned According to Utility Records	
End of Information	



-L- STA 10+50.00 TO 11+00.00

-L- STA 11+00.00 TO 11+90.00

-L- STA 13+80.00 TO 14+50.00

-L- STA 14+50.00 TO 15+00.00



—L— STA 11+90.00 TO 13+80.00



PAVEMENT SCHEDULE	
C1	PROP. APPROX. 1½" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD.
C2	PROP. APPROX. 3" ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 168 LBS. PER SQ. YD. IN EACH OF TWO LAYERS.
C3	PROP. VAR. DEPTH ASPHALT CONCRETE SURFACE COURSE, TYPE S9.5B, AT AN AVERAGE RATE OF 112 LBS. PER SQ. YD. PER 1" DEPTH. TO BE PLACED IN LAYERS NOT LESS THAN 1½" IN DEPTH OR GREATER THAN 2" IN DEPTH.
D1	PROP. APPROX. 2½" ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 285 LBS. PER SQ. YD.
D2	PROP. VAR. DEPTH ASPHALT CONCRETE INTERMEDIATE COURSE, TYPE I19.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH, TO BE PLACED IN LAYERS NOT LESS THAN 2½" IN DEPTH OR GREATER THAN 4" IN DEPTH.
E1	PROP. APPROX. 4" ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 456 LBS. PER SQ. YD.
E2	PROP. VAR. DEPTH ASPHALT CONCRETE BASE COURSE, TYPE B25.0B, AT AN AVERAGE RATE OF 114 LBS. PER SQ. YD. PER 1" DEPTH TO BE PLACED IN LAYERS NOT LESS THAN 3" IN DEPTH OR GREATER THAN 5½" IN DEPTH.
T	EARTH MATERIAL.
U	EXISTING PAVEMENT.
W	WEDGING (SEE DETAIL SHOWING METHOD OF WEDGING).

NOTE: PAVEMENT EDGE SLOPES ARE 1:1 UNLESS SHOWN OTHERWISE.

"N" = DISTANCE FROM EDGE OF LANE TO FACE OF GUARDRAIL.
TOTAL SHOULDER WIDTH = DISTANCE FROM EDGE OF TRAVEL LANE TO SHOULDER BREAK POINT.
FLARE LENGTH = DISTANCE FROM LAST SECTION OF PARALLEL GUARDRAIL TO END OF GUARDRAIL.
W = TOTAL WIDTH OF FLARE FROM BEGINNING OF TAPER TO END OF GUARDRAIL.
G = GATING IMPACT ATTENUATOR TYPE 350
NG = NON-GATING IMPACT ATTENUATOR TYPE 350


GUARDRAIL SUMMARY

SURVEY LINE	BEG. STA.	END STA.	LOCATION	LENGTH			WARRANT POINT		"N" DIST. FROM E.O.L.	TOTAL SHOULDER WIDTH	FLARE LENGTH		W		ANCHORS										IMPACT ATTENUATOR TYPE 350			REMARKS	
				STRAIGHT	SHOP CURVED	DOUBLE FACED	APPROACH END	TRAILING END			APPROACH END	TRAILING END	APPROACH END	TRAILING END	AT-1	GRAU 350 TL-2	TYPE III									PERMITTED			
																										NO.	G		NG
-L-	12+10 +/-	13+92.5 +/-	RT	187.50'			12+84.00 (CULVERT)	13+04.00 (CULVERT)	4'	7'						2													
-L-	12+09 +/-	13+46 +/-	LT	131.25'	12.50'		12+84.00 (CULVERT)	13+04.00 (CULVERT)	4'	7'					1	1													
		SUBTOTAL		318.75'	12.50'																								
		LESS ANCHOR DEDUCTIONS																											
		GRAU-350 TL-2 3 x 25.00' =		-75.00'																									
		AT-1 1 x 8.25' =		-8.25'																									
		TOTAL		237.50'	12.50'										1	3													

SUMMARY OF EARTHWORK IN CUBIC YARDS

LOCATION	UNCLASSIFIED EXCAVATION	UNDERCUT	EMBT + %	BORROW	WASTE
-L- 10+50.00 TO 15+00.00	14		859	845	
SUBTOTAL	14		859	845	
WASTE IN LIEU OF BORROW					
PROJECT TOTAL	14			845	
5% TO REPLACE BORROW				43	
GRAND TOTAL	14			888	
SAY	20			940	

NOTE: Approximate quantities only. Unclassified Excavation, Borrow Excavation, Fine Grading, Clearing and Grubbing and Removal of Existing Asphalt Pavement will be paid for at the contract Lump Sum price for "Grading".



TRACK HOE EXCAVATOR SHALL BE USED FOR CONSTRUCTION IN LIEU OF A CRANE DUE TO THE PROXIMITY OF OVERHEAD POWER LINES

DAN VALLEY BAPTIST ASSOCIATION, INC
DB 933 PG 1567

PROJECT REFERENCE
17BP.7.R.103 - ROCKINGHAM 248

SHEET NO.
4

ROADWAY DESIGN
ENGINEER

HYDRAULICS
ENGINEER

SEAL
21102

4/14/2016

SEAL
19732

4/14/2016

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED




Prepared in the
Office of:

M
MOTT
MACDONALD

PO Box 700
Fuquay-Varina, NC 27526
www.mottmac.com

ICA
Engineering

VERTICAL SCALE
5' 0 5 10'
HORIZONTAL SCALE
25' 0 25' 50'



4/14/2017 8:33:49 AM
R:\Roadway\Proj\780248_rdy.psh.dgn
ID=66165

THE FOLLOWING ROADWAY STANDARDS AS APPEAR IN “ROADWAY STANDARD DRAWINGS” – HIGHWAY DESIGN BRANCH– N.C. DEPARTMENT OF TRANSPORTATION – RALEIGH, N.C., DATED JANUARY 2012 ARE APPLICABLE TO THIS PROJECT AND BY REFERENCE HEREBY ARE CONSIDERED A PART OF THESE PLANS:

STD.	TITLE
1101.03	TEMPORARY ROAD CLOSURES
1110.01	STATIONARY WORK ZONE SIGNS
1145.01	BARRICADES
1205.01	PAVEMENT MARKINGS – LINE TYPES AND OFFSETS
1205.02	PAVEMENT MARKINGS – TWO-LANE AND MULTI-LANE ROADWAYS
1205.12	PAVEMENT MARKINGS – BRIDGES
1261.01	GUARDRAIL AND BARRIER DELINEATORS – INSTALLATION SPACING
1261.02	GUARDRAIL AND BARRIER DELINEATORS – TYPES AND MOUNTING
1262.01	GUARDRAIL END DELINEATION

GENERAL NOTES

CHANGES MAY BE REQUIRED WHEN PHYSICAL DIMENSIONS IN THE DETAIL DRAWINGS, STANDARD DETAILS, AND ROADWAY DETAILS ARE NOT ATTAINABLE TO MEET FIELD CONDITIONS OR RESULT IN DUPLICATE OR UNDESIRED OVERLAPPING OF DEVICES. MODIFICATION MAY INCLUDE: MOVING, SUPPLEMENTING, COVERING, OR REMOVAL OF DEVICES AS DIRECTED BY THE ENGINEER.

THE FOLLOWING GENERAL NOTES APPLY AT ALL TIMES FOR THE DURATION OF THE CONSTRUCTION PROJECT EXCEPT WHEN OTHERWISE NOTED IN THE PLAN OR DIRECTED BY THE ENGINEER.

TRAFFIC PATTERN ALTERATIONS

A) NOTIFY THE ENGINEER TWENTY ONE (21) CALENDAR DAYS PRIOR TO ANY TRAFFIC PATTERN ALTERATION.

SIGNING

- B) PROVIDE PERMANENT SIGNING.
- C) PROVIDE SIGNING AND DEVICES REQUIRED TO CLOSE THE ROAD ACCORDING TO THE ROADWAY STANDARD DRAWINGS AND TRAFFIC CONTROL PLANS.

PROVIDE SIGNING REQUIRED FOR THE OFF-SITE DETOUR ROUTE AS SHOWN IN THE TRAFFIC CONTROL PLANS.

D) COVER OR REMOVE ALL SIGNS AND DEVICES REQUIRED TO CLOSE THE ROAD WHEN ROAD CLOSURE IS NOT IN OPERATION.

COVER OR REMOVE ALL SIGNS REQUIRED FOR THE OFF-SITE DETOUR WHEN THE DETOUR IS NOT IN OPERATION.


E) ENSURE ALL NECESSARY SIGNING IS IN PLACE PRIOR TO ALTERING ANY TRAFFIC PATTERN.

TRAFFIC CONTROL DEVICES

F) PLACE TYPE III BARRICADES, WITH “ROAD CLOSED” SIGN R11-2 ATTACHED, OF SUFFICIENT LENGTH TO CLOSE ENTIRE ROADWAY.

PAVEMENT MARKINGS AND MARKERS

G) INSTALL PAVEMENT MARKINGS ON THE FINAL SURFACE.

PROJECT REFERENCE		SHEET NO.
17BP.7.R.103 – ROCKINGHAM 248		TMP-1
<div>ROADWAY DESIGN ENGINEER</div> <div></div> <div>MOTT MACDONALD 1 & E, LLC LICENSE NO. E-0669</div>		
DOCUMENT NOT CONSIDERED FINAL UNLESS ALL SIGNATURES COMPLETED		
Prepared in the Office of:		<div>M</div> <div>MOTT MACDONALD</div> <div>PO Box 700 Fuquay-Varina, NC 27526 www.mottmac.com</div>


PHASING

- STEP 1: USING ROADWAY STANDARD DRAWING NUMBER 1101.03, SHEET 1 OF 9, AND SHEET TMP-2, PERFORM THE FOLLOWING:
- INSTALL ALL ROAD CLOSURE AND DETOUR SIGNING INCLUDING BARRICADES
 - CLOSE SR 2009 (CAMP DAN VALLEY ROAD)
 - PLACE TRAFFIC ONTO OFF- SITE DETOUR
- STEP 2: REMOVE EXISTING BRIDGE #248 AND CONSTRUCT THE PROPOSED CULVERT AND APPROACHES AS SHOWN IN THE CONSTRUCTION PLANS.
- STEP 3: INSTALL FINAL PAVEMENT MARKINGS.
- STEP 4: REMOVE ALL TRAFFIC CONTROL SIGNING AND DEVICES AND RE-OPEN SR 2009 (CAMP DAN VALLEY ROAD) TO THE FINAL TRAFFIC PATTERN.








PAVEMENT MARKING

PAINT WHITE EDGELINE (4”) 1,800 LF
PAINT YELLOW DOUBLE CENTER (4”) 1,800 LF

NOTE: QUANTITY INCLUDES 2 APPLICATIONS OF EACH




* SEE SHEET TMP-3 FOR SPECIAL SIGN DESIGNS




TIP PROJECT: 17BP.7.R.103

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS
PLAN FOR PROPOSED
HIGHWAY EROSION CONTROL
ROCKINGHAM COUNTY

LOCATION: BRIDGE NO. 248 OVER CARROLL CREEK ON SR 2009 (CAMP DAN VALLEY ROAD)
TYPE OF WORK: GRADING, PAVING, DRAINAGE AND CULVERT



GRAPHIC SCALE



THESE EROSION AND SEDIMENT CONTROL PLANS COMPLY WITH THE REGULATIONS SET FORTH BY THE NCG-010000 GENERAL CONSTRUCTION PERMIT EFFECTIVE AUGUST 1, 2016 AND ISSUED BY THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENT AND NATURAL RESOURCES DIVISION OF WATER RESOURCES.

Prepared In the Office of:

ICA ENGINEERING
5121 KINGDOM WAY, SUITE 100
RALEIGH NC 27607
NC License No. F-0258

Designed by:

STACEY H. BAILEY, PE 3074
NAME LEVEL III CERTIFICATION NO.

Reviewed In the Office of:

ROADSIDE ENVIRONMENTAL UNIT
1 South Wilmington St.
Raleigh, NC 27611

2012 STANDARD SPECIFICATIONS

Reviewed by:

JEFF WALSTON, PE, CPESC, CPSWQ

Roadway Standard Drawings

The following roadway english standards as appear in "Roadway Standard Drawings"- Roadway Design Unit - N. C. Department of Transportation - Raleigh, N. C., dated January 2012 and the latest revision thereto are applicable to this project and by reference hereby are considered a part of these plans.


1604.01	Railroad Erosion Control Detail	1632.01	Rock Inlet Sediment Trap Type A
1605.01	Temporary Silt Fence	1632.02	Rock Inlet Sediment Trap Type B
1606.01	Special Sediment Control Fence	1632.03	Rock Inlet Sediment Trap Type C
1607.01	Gravel Construction Entrance	1633.01	Temporary Rock Silt Check Type A
1622.01	Temporary Berms and Slope Drains	1633.02	Temporary Rock Silt Check Type B
1630.01	Riser Basin	1634.01	Temporary Rock Sediment Dam Type A
1630.02	Silt Basin Type B	1634.02	Temporary Rock Sediment Dam Type B
1630.03	Temporary Silt Ditch	1635.01	Rock Pipe Inlet Sediment Trap Type A
1630.04	Stilling Basin	1635.02	Rock Pipe Inlet Sediment Trap Type B
1630.05	Temporary Diversion	1640.01	Coir Fiber Baffle
1630.06	Special Stilling Basin	1645.01	Temporary Stream Crossing
1631.01	Matting Installation		

STATE	STATE PROJECT REFERENCE NO.	SHEET NO.	TOTAL SHEETS
N.C.	17BP.7.R.103	EC-1	
STATE PROJ. NO.	F.A. PROJ. NO.	DESCRIPTION	




EROSION AND SEDIMENT CONTROL MEASURES

Std. #	Description	Symbol
1630.05	Temporary Silt Ditch	TD
1630.05	Temporary Diversion	TD
1605.01	Temporary Silt Fence	III
1606.01	Special Sediment Control Fence	III
1622.01	Temporary Berms and Slope Drains	TD
1630.02	Silt Basin Type B	TD
1633.01	Temporary Rock Silt Check Type-A	TD
	Temporary Rock Silt Check Type-A with Matting and Polyacrylamide (PAM)	TD
1633.02	Temporary Rock Silt Check Type-B	TD
	Wattle / Coir Fiber Wattle	TD
	Wattle / Coir Fiber Wattle with Polyacrylamide (PAM)	TD
1634.01	Temporary Rock Sediment Dam Type-A	TD
1634.02	Temporary Rock Sediment Dam Type-B	TD
1635.01	Rock Pipe Inlet Sediment Trap Type-A	TD
1635.02	Rock Pipe Inlet Sediment Trap Type-B	TD
1630.04	Stilling Basin	TD
1630.06	Special Stilling Basin	TD
	Rock Inlet Sediment Trap:	
1632.01	Type A	A
1632.02	Type B	B
1632.03	Type C	C
	Skimmer Basin	TD
	Tiered Skimmer Basin	TD
	Infiltration Basin	TD

THIS PROJECT CONTAINS EROSION CONTROL PLANS FOR CLEARING AND GRUBBING PHASE OF CONSTRUCTION.



COIR FIBER WATTLE WITH POLYACRYLAMIDE (PAM) DETAIL



NOTES:

USE MINIMUM 12 IN. DIAMETER COIR FIBER (COCONUT FIBER) WATTLE.

USE 2 FT. WOODEN STAKES WITH A 2 IN. BY 2 IN. NOMINAL CROSS SECTION.

ONLY INSTALL WATTLE(S) TO A HEIGHT IN DITCH SO FLOW WILL NOT WASH AROUND WATTLE AND SCOUR DITCH SLOPES AND AS DIRECTED.

INSTALL A MINIMUM OF 2 UPSLOPE STAKES AND 4 DOWNSLOPE STAKES AT AN ANGLE TO WEDGE WATTLE TO BOTTOM OF DITCH.



PROVIDE STAPLES MADE OF 0.125 IN. DIAMETER STEEL WIRE FORMED INTO A U SHAPE NOT LESS THAN 12" IN LENGTH.

INSTALL STAPLES APPROXIMATELY EVERY 1 LINEAR FOOT ON BOTH SIDES OF WATTLE AND AT EACH END TO SECURE IT TO THE SOIL.

INSTALL MATTING IN ACCORDANCE WITH SECTION 1631 OF THE STANDARD SPECIFICATIONS.

PRIOR TO POLYACRYLAMIDE (PAM) APPLICATION, OBTAIN A SOIL SAMPLE FROM PROJECT LOCATION, AND FROM OFFSITE MATERIAL, AND ANALYZE FOR APPROPRIATE PAM FLOCCULANT TO BE APPLIED TO EACH WATTLE.

INITIALLY APPLY 2 OUNCES OF ANIONIC OR NEUTRALLY CHARGED PAM OVER WATTLE WHERE WATER WILL FLOW AND 1 OUNCE OF PAM ON MATTING ON EACH SIDE OF WATTLE. REAPPLY PAM AFTER EVERY RAINFALL EVENT THAT IS EQUAL TO OR EXCEEDS 0.50 IN.



DIVISION OF HIGHWAYS
STATE OF NORTH CAROLINA




SOIL STABILIZATION TIMEFRAMES

SITE DESCRIPTION	STABILIZATION TIME	TIMEFRAME EXCEPTIONS
PERIMETER DIKES, SWALES, DITCHES AND SLOPES	7 DAYS	NONE
HIGH QUALITY WATER (HQW) ZONES	7 DAYS	NONE
SLOPES STEEPER THAN 3:1	7 DAYS	IF SLOPES ARE 10' OR LESS IN LENGTH AND ARE NOT STEEPER THAN 2:1, 14 DAYS ARE ALLOWED.
SLOPES 3:1 OR FLATTER	14 DAYS	7 DAYS FOR SLOPES GREATER THAN 50' IN LENGTH.
ALL OTHER AREAS WITH SLOPES FLATTER THAN 4:1	14 DAYS	NONE, EXCEPT FOR PERIMETERS AND HQW ZONES.

LEVEL III CERTIFIED BY:
STACEY H. BAILEY, PE
CERTIFICATION NUMBER: 3074
ISSUED: MARCH 14, 2017




CLEARING AND GRUBBING
EROSION CONTROL FOR
CONSTRUCTION SHEET 04



NAD 83/NA 2011

15+00



- NOTE: PLACE TEMPORARY ROCK SEDIMENT DAMS TYPE - B AND TEMPORARY ROCK SILT CHECKS TYPE - A AT DRAINAGE OUTLETS.
- NOTE: PERIMETER EROSION CONTROL MEASURES SHALL BE INSTALLED DURING CLEARING AND GRUBBING PHASE.
- NOTE: ALL EROSION CONTROL DEVICES SHOWN ARE LOCATED WITHIN EXISTING R/W OR EASEMENT.

5/14/99
4/17/2017
C:\Users\erossion\Control\cadd\780248_hyd.ec.construction_sequence.dgn
EC-4A/CONST.4

CONSTRUCTION SEQUENCE

GRAPHIC SCALE

3000

0


3000

6000

PROJECT REFERENCE NO.	SHEET NO.
17BP.7.R.103	EC-4A/CONST.4
RW SHEET NO.	

BRIDGE NO. 248 OVER CARROLL CREEK ON SR 2009
(CAMP DAN VALLEY ROAD)
ROCKINGHAM COUNTY, NC





- CULVERT PHASING
SF-780248
- PHASE 1
- 1.) INSTALL ALL TEMPORARY SEDIMENT CONTROL DEVICES NECESSARY FOR CULVERT CONSTRUCTION.
 - 2.) INSTALL SPECIAL STILLING BASIN WITHIN PROJECT RIGHT-OF-WAY. PUMP ALL EFFLUENT INTO SPECIAL STILLING BASIN.
 - 3.) INSTALL IMPERVIOUS DIKES AND INSTALL 24" TEMP. PIPE.
 - 4.) DE-WATER EFFLUENT FROM WORK SITE INTO SPECIAL STILLING BASIN.
 - 5.) CONSTRUCT PROPOSED 2 @ 10'x9' RCBC CHANNEL IMPROVEMENTS AND FLOOD BENCH PER PLANS.
- PHASE 2
- 6.) REMOVE TEMPORARY IMPERVIOUS DIKES AND TEMPORARY PIPE TO ALLOW FLOW THROUGH NEWLY CONSTRUCTED CULVERT.
 - 7.) UPON STABILIZATION OF ALL DISTURBED AREAS, REMOVE ALL TEMPORARY SEDIMENT CONTROL DEVICES.



LEVEL III CERTIFIED BY:
STACEY H. BAILEY, PE
CERTIFICATION NUMBER: 3074
ISSUED: MARCH 14, 2017




FINAL EROSION CONTROL
FOR CONSTRUCTION
SHEET 04



09/28/09


TIP PROJECT: 17BP.7.R.103




STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

UTILITY CONSTRUCTION PLANS
ROCKINGHAM COUNTY

LOCATION: BRIDGE NO. 248 CARROLL CREEK ON
SR 2009 (CAMP DAN VALLEY ROAD)
TYPE OF WORK: UTILITY RELOCATION OF WATER MAIN



DOCUMENT NOT CONSIDERED FINAL
UNTIL ALL SIGNATURES ARE COMPLETED



INDEX OF SHEETS	
SHEET NO.:	DESCRIPTION:
UC-1	TITLE SHEET
UC-2	UTILITY SYMBOLOGY
UC-3	NOTES
UC-3A	DETAILS
UC-4	UTILITY PLAN AND PROFILE SHEET

WATER AND SEWER
OWNERS ON PROJECT

(A) WATER - DAN RIVER WATER, INC.

PREPARED IN THE OFFICE OF




THE WOOTEN COMPANY

120 North Boylan Avenue Raleigh, NC 27603-1423
919.828.0531 Fax 919.834.3589
License Number: F-0115

James R. Gregg	CONSULTANT CONTACT #1
	CONSULTANT CONTACT #2
	CONSULTANT CONTACT #3

SEAL



DIVISION OF HIGHWAYS
UTILITIES UNIT
1555 MAIL SERVICES CENTER
RALEIGH, NC 27699-1555
PHONE (919) 707-6690
FAX (919) 250-4151









	UTILITIES REGIONAL ENGINEER
	UTILITIES ENGINEER
	UTILITIES AREA COORDINATOR
	UTILITIES COORDINATOR

STATE OF NORTH CAROLINA DIVISION OF HIGHWAYS

UTILITIES PLAN SHEET SYMBOLS



















PROPOSED MISCELLANEOUS UTILITIES SYMBOLS

Water Line (Sized as Shown)	
11 1/4 Degree Bend	
22 1/2 Degree Bend	
45 Degree Bend	
90 Degree Bend	
Plug	
Tee	
Cross	
Reducer	
Gate Valve	
Butterfly Valve	
Tapping Valve	
Line Stop	
Line Stop with Bypass	
Blow Off	
Fire Hydrant	
Relocate Fire Hydrant	
Remove Fire Hydrant	
Water Meter	
Relocate Water Meter	
Remove Water Meter	
Water Pump Station	
RPZ Backflow Preventer	
DCV Backflow Preventer	
Relocate RPZ Backflow Preventer	
Relocate DCV Backflow Preventer	

Power Pole	
Telephone Pole	
Joint Use Pole	
Telephone Pedestal	
Utility Line by Others (Type as Shown)	
Trenchless Installation	
Encasement by Open Cut	
Encasement	

Thrust Block		
Air Release Valve		
Utility Vault		
Concrete Pier		
Steel Pier		
Plan Note		NOTE
Pay Item Note		

EXISTING UTILITIES SYMBOLS

Power Pole.....	
Telephone Pole.....	
Joint Use Pole.....	
Utility Pole.....	
Utility Pole with Base.....	
H-Frame Pole.....	
Power Transmission Line Tower.....	
Water Manhole.....	
Power Manhole.....	
Telephone Manhole.....	
Sanitary Sewer Manhole.....	
Hand Hole for Cable.....	
Power Transformer.....	
Telephone Pedestal.....	
CATV Pedestal.....	
Gas Valve.....	
Gas Meter.....	
Located Miscellaneous Utility Object.....	
Abandoned According to Utility Records.....	AATUR
End of Information.....	E.O.I.

Underground Power Line	P
*Underground Telephone Cable	T
*Underground Telephone Conduit	TC
*Underground Fiber Optics Telephone Cable	T FO
*Underground TV Cable	TV
*Underground Fiber Optics TV Cable	TV FO
*Underground Gas Pipeline	G
Aboveground Gas Pipeline	A/G Gas
*Underground Water Line	W
Aboveground Water Line	A/G Water
*Underground Gravity Sanitary Sewer Line	SS
Aboveground Gravity Sanitary Sewer Line	A/G Sanitary Sewer
*Underground SS Forced Main Line	FSS
Underground Unknown Utility Line	?UTL
SUE Test Hole	⊗
Water Meter	⊠
Water Valve	⊗
Fire Hydrant	⊕
Sanitary Sewer Cleanout	⊕

PROPOSED SEWER SYMBOLS

Gravity Sewer Line 12" SS
(Sized as Shown)

Force Main Sewer Line 12" FSS
(Sized as Shown)

Manhole •
(Sized per Note)

Sewer Pump Station PS(SS)

*For Existing Utilities

Utility Line Drawn from Recordw.....
(Type as Shown)

Designated Utility Linew.....
(Type as Shown)

8/17/99

REVISIONS

\$\$\$DATE\$\$\$
\$\$\$SYTIME\$\$\$
\$\$\$DON\$\$\$
\$\$\$USERNAME\$\$\$

GENERAL NOTES:

1. THE PROPOSED UTILITY CONSTRUCTION SHALL MEET THE APPLICABLE REQUIREMENTS OF THE NC DEPARTMENT OF TRANSPORTATION'S "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" DATED JANUARY 2012.
2. THE EXISTING UTILITIES BELONG TO DAN RIVER WATER, INC .
3. ALL WATER LINES TO BE INSTALLED WITHIN COMPLIANCE OF THE RULES AND REGULATIONS OF THE NORTH CAROLINA DEPARTMENT OF ENVIRONMENTAL AND NATURAL RESOURCES, DIVISION OF WATER RESOURCES, PUBLIC WATER SUPPLY SECTION.
4. THE UTILITY OWNER OWNS THE EXISTING UTILITY FACILITIES AND WILL OWN THE NEW UTILITY FACILITIES AFTER ACCEPTANCE BY THE DEPARTMENT. THE DEPARTMENT OWNS THE CONSTRUCTION CONTRACT AND HAS ADMINISTRATIVE AUTHORITY. COMMUNICATIONS AND DECISIONS BETWEEN THE CONTRACTOR AND UTILITY OWNER ARE NOT BINDING UPON THE DEPARTMENT OR THIS CONTRACT UNLESS AUTHORIZED BY THE ENGINEER. AGREEMENTS BETWEEN THE UTILITY OWNER AND CONTRACTOR FOR THE WORK THAT IS NOT PART OF THIS CONTRACT OR IS SECONDARY TO THIS CONTRACT ARE ALLOWED, BUT ARE NOT BINDING UPON THE DEPARTMENT.
5. PROVIDE ACCESS FOR THE DEPARTMENT PERSONNEL AND THE OWNER'S REPRESENTATIVES TO ALL PHASES OF CONSTRUCTION. NOTIFY DEPARTMENT PERSONNEL AND THE UTILITY OWNER TWO WEEKS PRIOR TO COMMENCEMENT OF ANY WORK AND ONE WEEK PRIOR TO SERVICE INTERRUPTION. KEEP UTILITY OWNERS' REPRESENTATIVES INFORMED OF WORK PROGRESS AND PROVIDE OPPROTUNITY FOR INSPECTION OF CONSTRUCTION AND TESTING.

6. THE PLANS DEPICT THE BEST AVAILABLE INFORMATION FOR THE LOCATION, SIZE, AND TYPE OF MATERIAL FOR ALL EXISTING UTILITIES. MAKE INVESTIGATIONS FOR DETERMINING THE EXACT LOCATION, SIZE, AND TYPE MATERIAL OF THE EXISTING FACILITIES AS NECESSARY FOR THE CONSTRUCTION OF THE PROPOSED UTILITIES AND FOR AVOIDING DAMAGE TO EXISTING FACILITIES. REPAIR ANY DAMAGE INCURRED TO EXISTING FACILITIES TO THE ORIGINAL OR BETTER CONDITION AT NO ADDITONAL COST TO THE DEPARTMENT.
7. MAKE FINAL CONNECTIONS OF THE NEW WORK TO THE EXISTING SYSTEM WHERE INDICATED ON THE PLANS, AS REQUIRED TO FIT THE ACTUAL CONDITIONS, OR AS DIRECTED.
8. MAKE CONNECTIONS BETWEEN EXISTING AND PROPOSED UTILITIES AT TIMES MOST CONVENIENT TO THE PUBLIC, WITHOUT ENDANGERING THE UTILITY SERVICE, AND IN ACCORDANCE WITH THE UTILITY OWNER'S REQUIREMENTS. MAKE CONNECTIONS ON WEEKENDS, AT NIGHT, AND ON HOLIDAYS IF NECESSARY.
9. ALL UTILITY MATERIALS SHALL BE APPROVED PRIOR TO DELIVERY TO THE PROJECT. SEE 1500-7, " SUBMITTALS AND RECORDS" IN SECTION 1500 OF THE STANDARD SPECIFICATIONS.

UTILITY CONSTRUCTION

PROJECT SPECIFIC NOTES:

1. PROPOSED WATER LINE FROM -L- LINE STATION 11+05 TO -L- LINE STATION 12+43 AND FROM -L- LINE STATION 13+94 TO -L- LINE STATION 15+34 SHALL BE D.I.R.J. (DUCTILE IRON RESTRAINED JOINT) PIPE. PROPOSED WATER LINE FROM -L- LINE STATION 12+43 TO -L- LINE STATION 13+94 SHALL BE F.P.V.C. (FUSIBLE POLYVINYL CHLORIDE) PIPE.
2. CONTRACTOR'S ATTENTION IS DIRECTED TO SECTIONS 102, 107, AND 1550 OF THE STANDARD SPECIFICATIONS CONCERNING TRENCHLESS INSTALLATION. IT IS CONTRACTOR'S RESPONSIBILITY TO HAVE BORE DESIGNED AND SEALED BY A LICENSED NORTH CAROLINA PROFESSIONAL ENGINEER. NO DAMAGE IS ALLOWED TO RIVER, WETLANDS, OR BUFFER ZONES.
4. TRACER WIRE AND WARNING TAPE SHALL BE INSTALLED WITH ALL PLASTIC PIPE UTILITIES. WIRE, TAPE, AND PIPE SHALL BE COLOR CODED ACCORDING TO UTILITY (BLUE FOR WATER) AND SHALL BE IN ACCORDANCE WITH NCDOT SPECIFICATIONS.
5. FUSED PVC PIPE LENGTHS THAT HAVE BEEN INSTALLED IN THE TRENCH SHALL NOT BE BENT OR JOCKEYED INTO POSITION WITH HEAVY EQUIPMENT IN ORDER TO CONNECT TO FITTINGS. ALL ALIGNMENTS CORRECTIONS SHALL TAKE PLACE IN THE DIP FITTINGS.

PROJECT REFERENCE NO.		SHEET NO.	
17BP.7.R.103 -- ROCKINGHAM 248		UC-3	
DESIGNED BY:		<div><div><div>NORTH CAROLINA PROFESSIONAL ENGINEER</div><div>2020/2017</div><div>SEAL</div><div>Witnessed by</div><div>James R. Grier</div><div>ENGINEER</div></div></div>	
DRAWN BY:			
CHECKED BY:			
APPROVED BY:			
REVISED:			
NORTH CAROLINA DEPARTMENT OF TRANSPORTATION		Document Not Considered Final Unless All Signatures Completed UTILITY CONSTRUCTION PLANS ONLY	
UTILITIES ENGINEERING SEC. PHONE: (919) 707-6690 FAX: (919) 250-4151			
Prepared in the Office of:			
<div><div><div>W</div></div><div><div>THE WOOTEN COMPANY</div><div>120 North Baylan Avenue Raleigh NC 27603-1423</div><div>919.828.0531 fax 919.834.3589</div><div>License Number: F-0115</div></div></div>			
VERTICAL SCALE 5' 0 10'		HORIZONTAL SCALE 25' 0 25' 50'	

UTILITY CONSTRUCTION


8/17/99

REVISIONS

\$\$\$\$\$SYTIME\$\$\$\$\$
\$\$\$\$\$USERNAME\$\$\$\$\$
\$\$\$\$\$DATE\$\$\$\$\$

PROJECT TYPICAL DETAILS

NODOT STANDARD DETAILS:
1. 300.01 (SHEETS 1,2, AND 3)



NOTES:

USE MINIMUM 12 IN. DIAMETER COIR FIBER (COCONUT FIBER) WATTLE AND LENGTH OF 10 FT.

EXCAVATE A 1 TO 2 INCH TRENCH FOR WATTLE TO BE PLACED.

DO NOT PLACE WATTLE ON TOE OF SLOPE.

USE 2 FT. WOODEN STAKES WITH A 2 IN. BY 2 IN. NOMINAL CROSS SECTION.

INSTALL A MINIMUM OF 2 UPSLOPE STAKES AND 4 DOWNSLOPE STAKES AT AN ANGLE TO WEDGE WATTLE TO GROUND.


PROVIDE STAPLES MADE OF 0.125 IN. DIAMETER STEEL WIRE FORMED INTO A U SHAPE NOT LESS THAN 12" IN LENGTH.

INSTALL STAPLES APPROXIMATELY EVERY 1 LINEAR FOOT ON BOTH SIDES OF WATTLE AND AT EACH END TO SECURE IT TO THE SOIL.


WATTLE INSTALLATION CAN BE ON OUTSIDE OF THE SILT FENCE AS DIRECTED.

INSTALL TEMPORARY SILT FENCE IN ACCORDANCE WITH SECTION 1605 OF THE STANDARD SPECIFICATIONS.


2 COIR LOG WATTLE SILT FENCE OUTLET
3A NOT TO SCALE




5 SILT FENCE
3A NOT TO SCALE




6 AIR RELEASE ASSEMBLY
3A NOT TO SCALE




7 VALVE BOX INSTALLATION
3A NOT TO SCALE




8 STANDARD 2" BLOW-OFF ASSEMBLY
3A NOT TO SCALE



10 NEW VALVE AND PIPE BEND WITH THRUST COLLAR CUT INTO EXISTING WATER LINE
3A NOT TO SCALE



11 THRUST COLLAR INSTALLATION
3A NOT TO SCALE



12 STANDARD REACTION BLOCKING
3A NOT TO SCALE

PROJECT REFERENCE NO.
17BP.7.R.103 – ROCKINGHAM 248

SHEET NO.
UC-4

DESIGNED BY:
DRAWN BY:
CHECKED BY:
APPROVED BY:
REVISED:

NORTH CAROLINA
PROFESSIONAL
ENGINEER
2020/2017
SEAL
James R. Grier
JAMES R. GRIER

Document Not Considered Final
Unless All Signatures Completed
UTILITY CONSTRUCTION
PLANS ONLY

NORTH CAROLINA
DEPARTMENT OF
TRANSPORTATION

UTILITIES ENGINEERING SEC.
PHONE: (919) 707-6690
FAX: (919) 250-4151

Prepared in the Office of:

THE WOOTEN COMPANY

120 North Baylan Avenue Raleigh NC 27603-1423
919.828.0531 fax 919.834.3589
License Number: F-0115

VERTICAL SCALE
5' 0 5' 10'

HORIZONTAL SCALE
25' 0 25' 50'

UTILITY CONSTRUCTION

DATUM DESCRIPTION
THE LOCALIZED COORDINATE SYSTEM DEVELOPED FOR THIS PROJECT IS BASED ON THE STATE PLANE COORDINATES ESTABLISHED BY NCOS FOR MONUMENT "780248-1" WITH NAD 83/NA 2011 STATE PLANE GRID COORDINATES OF NORTHING: 964990.742(±ft) EASTING: 1785805.195(±ft) ELEVATION: 759.76(±ft) THE AVERAGE COMBINED GRID FACTOR USED ON THIS PROJECT (GROUND TO GRID) IS: 1.0000419618 THE N.C. LAMBERT GRID BEARING AND LOCALIZED HORIZONTAL GROUND DISTANCE FROM "780248-1" TO -L- STATION 10+00.00 IS S 9° 04' 25.9" E Distance 283.97(±FT) ALL LINEAR DIMENSIONS ARE LOCALIZED HORIZONTAL DISTANCES VERTICAL DATUM USED IS NAVD 88

PROPOSED BRIDGE REPLACEMENT SHOWN IN BACKGROUND FOR REFERENCE PURPOSES ONLY

GPS 780248-1

1
MARTHA DRAPER ONTJES
WESLEY LEE DRAPER &
JOSEPH C. DRAPER
DB 986 PG 179

2
CANDACE S. BURNETTE
DB 1288 PG 253

3
LEON HYLER &
LINDA J. HYLER
DB 877 PG 2173
PB 22 PG 29

4
VIRGINIA BRANTLEY
DB 789 PG 1698

5
DAN VALLEY BAPTIST ASSOCIATION, INC
DB 933 PG 1567

6
DONALD R. WILLIAMS &
BONNIE M. WILLIAMS
DB 736 PG 926

7
FANNIE L. DAMERON
DB 692 PG 632
PB 22 PG 29

8
CARROLL CREEK

9
ASHLEY LOOP

10
CAMP DAN VALLEY RD SR 2009

11
TO CAMP RD

12
TO CAMP RD

13
TO CAMP RD

14
TO CAMP RD

15
TO CAMP RD

16
TO CAMP RD

17
TO CAMP RD

18
TO CAMP RD

19
TO CAMP RD

20
TO CAMP RD

21
TO CAMP RD

22
TO CAMP RD

23
TO CAMP RD

24
TO CAMP RD

25
TO CAMP RD

26
TO CAMP RD

27
TO CAMP RD

28
TO CAMP RD

29
TO CAMP RD

30
TO CAMP RD

31
TO CAMP RD

32
TO CAMP RD

33
TO CAMP RD

34
TO CAMP RD

35
TO CAMP RD

36
TO CAMP RD

37
TO CAMP RD

38
TO CAMP RD

39
TO CAMP RD

40
TO CAMP RD

41
TO CAMP RD

42
TO CAMP RD

43
TO CAMP RD

44
TO CAMP RD

45
TO CAMP RD

46
TO CAMP RD

47
TO CAMP RD

48
TO CAMP RD

49
TO CAMP RD

50
TO CAMP RD

51
TO CAMP RD

52
TO CAMP RD

53
TO CAMP RD

54
TO CAMP RD

55
TO CAMP RD

56
TO CAMP RD

57
TO CAMP RD

58
TO CAMP RD

59
TO CAMP RD

60
TO CAMP RD

61
TO CAMP RD

62
TO CAMP RD

63
TO CAMP RD

64
TO CAMP RD

65
TO CAMP RD

66
TO CAMP RD

67
TO CAMP RD

68
TO CAMP RD

69
TO CAMP RD

70
TO CAMP RD

71
TO CAMP RD

72
TO CAMP RD

73
TO CAMP RD

74
TO CAMP RD

75
TO CAMP RD

76
TO CAMP RD

77
TO CAMP RD

78
TO CAMP RD

79
TO CAMP RD

80
TO CAMP RD

81
TO CAMP RD

82
TO CAMP RD

83
TO CAMP RD

84
TO CAMP RD

85
TO CAMP RD

86
TO CAMP RD

87
TO CAMP RD

88
TO CAMP RD

89
TO CAMP RD

90
TO CAMP RD

91
TO CAMP RD

92
TO CAMP RD

93
TO CAMP RD

94
TO CAMP RD

95
TO CAMP RD

96
TO CAMP RD

97
TO CAMP RD

98
TO CAMP RD

99
TO CAMP RD

100
TO CAMP RD

101
TO CAMP RD

102
TO CAMP RD

103
TO CAMP RD

104
TO CAMP RD

105
TO CAMP RD

106
TO CAMP RD

107
TO CAMP RD

108
TO CAMP RD

109
TO CAMP RD

110
TO CAMP RD

111
TO CAMP RD

112
TO CAMP RD

113
TO CAMP RD

114
TO CAMP RD

115
TO CAMP RD

116
TO CAMP RD

117
TO CAMP RD

118
TO CAMP RD

119
TO CAMP RD

120
TO CAMP RD

121
TO CAMP RD

122
TO CAMP RD

123
TO CAMP RD

124
TO CAMP RD

125
TO CAMP RD

126
TO CAMP RD

127
TO CAMP RD

128
TO CAMP RD

129
TO CAMP RD

130
TO CAMP RD

131
TO CAMP RD

132
TO CAMP RD

133
TO CAMP RD

134
TO CAMP RD

135
TO CAMP RD

136
TO CAMP RD

137
TO CAMP RD

138
TO CAMP RD

139
TO CAMP RD

140
TO CAMP RD

141
TO CAMP RD

142
TO CAMP RD

143
TO CAMP RD

144
TO CAMP RD

145
TO CAMP RD

146
TO CAMP RD

147
TO CAMP RD

148
TO CAMP RD

149
TO CAMP RD

150
TO CAMP RD

151
TO CAMP RD

152
TO CAMP RD

153
TO CAMP RD

154
TO CAMP RD

155
TO CAMP RD

156
TO CAMP RD

157
TO CAMP RD

158
TO CAMP RD

159
TO CAMP RD

160
TO CAMP RD

161
TO CAMP RD

162
TO CAMP RD

163
TO CAMP RD

164
TO CAMP RD

165
TO CAMP RD

166
TO CAMP RD

167
TO CAMP RD

168
TO CAMP RD

169
TO CAMP RD

170
TO CAMP RD

171
TO CAMP RD

172
TO CAMP RD

173
TO CAMP RD

174
TO CAMP RD

175
TO CAMP RD

176
TO CAMP RD

177
TO CAMP RD

178
TO CAMP RD

179
TO CAMP RD

180
TO CAMP RD

181
TO CAMP RD

182
TO CAMP RD

183
TO CAMP RD

184
TO CAMP RD

185
TO CAMP RD

186
TO CAMP RD

187
TO CAMP RD

188
TO CAMP RD

189
TO CAMP RD

190
TO CAMP RD

191
TO CAMP RD

192
TO CAMP RD

193
TO CAMP RD

194
TO CAMP RD

195
TO CAMP RD

196
TO CAMP RD

197
TO CAMP RD

198
TO CAMP RD

199
TO CAMP RD

200
TO CAMP RD

201
TO CAMP RD

202
TO CAMP RD

203
TO CAMP RD

204
TO CAMP RD

205
TO CAMP RD

206
TO CAMP RD

207
TO CAMP RD

208
TO CAMP RD

209
TO CAMP RD

210
TO CAMP RD

211
TO CAMP RD

212
TO CAMP RD

213
TO CAMP RD

214
TO CAMP RD

215
TO CAMP RD

216
TO CAMP RD

217
TO CAMP RD

218
TO CAMP RD

219
TO CAMP RD

220
TO CAMP RD

221
TO CAMP RD

222
TO CAMP RD

223
TO CAMP RD

224
TO CAMP RD

225
TO CAMP RD

226
TO CAMP RD

227
TO CAMP RD

228
TO CAMP RD

229
TO CAMP RD

230
TO CAMP RD

231
TO CAMP RD

232
TO CAMP RD

233
TO CAMP RD

234
TO CAMP RD

235
TO CAMP RD

236
TO CAMP RD

237
TO CAMP RD

238
TO CAMP RD

239
TO CAMP RD

240
TO CAMP RD

241
TO CAMP RD

242
TO CAMP RD

243
TO CAMP RD

244
TO CAMP RD

245
TO CAMP RD

246
TO CAMP RD

247
TO CAMP RD

248
TO CAMP RD

249
TO CAMP RD

250
TO CAMP RD

251
TO CAMP RD

252
TO CAMP RD

253
TO CAMP RD

254
TO CAMP RD

255
TO CAMP RD

256
TO CAMP RD

257
TO CAMP RD

258
TO CAMP RD

259
TO CAMP RD

260
TO CAMP RD

261
TO CAMP RD

262
TO CAMP RD

263
TO CAMP RD

264
TO CAMP RD

265
TO CAMP RD

266
TO CAMP RD

267
TO CAMP RD

268
TO CAMP RD

269
TO CAMP RD

270
TO CAMP RD

271
TO CAMP RD

272
TO CAMP RD

273
TO CAMP RD

274
TO CAMP RD

275
TO CAMP RD

276
TO CAMP RD

277
TO CAMP RD

278
TO CAMP RD

279
TO CAMP RD

280
TO CAMP RD

281
TO CAMP RD

282
TO CAMP RD

283
TO CAMP RD

284
TO CAMP RD

285
TO CAMP RD

286
TO CAMP RD

287
TO CAMP RD

288
TO CAMP RD

289
TO CAMP RD

290
TO CAMP RD

291
TO CAMP RD

292
TO CAMP RD

293
TO CAMP RD

294
TO CAMP RD

295
TO CAMP RD

296
TO CAMP RD

297
TO CAMP RD

298
TO CAMP RD

299
TO CAMP RD

300
TO CAMP RD

301
TO CAMP RD

302
TO CAMP RD

303
TO CAMP RD

304
TO CAMP RD

305
TO CAMP RD

306
TO CAMP RD

307
TO CAMP RD

308
TO CAMP RD

309
TO CAMP RD

310
TO CAMP RD

311
TO CAMP RD

312
TO CAMP RD

313
TO CAMP RD

314
TO CAMP RD

315
TO CAMP RD

316
TO CAMP RD

317
TO CAMP RD

318
TO CAMP RD

319
TO CAMP RD

320
TO CAMP RD

321
TO CAMP RD

322
TO CAMP RD

323
TO CAMP RD

324
TO CAMP RD

325
TO CAMP RD

326
TO CAMP RD

327
TO CAMP RD

328
TO CAMP RD

329
TO CAMP RD

330
TO CAMP RD

331
TO CAMP RD

332
TO CAMP RD

333
TO CAMP RD

334
TO CAMP RD

335
TO CAMP RD

336
TO CAMP RD

337
TO CAMP RD

338
TO CAMP RD

339
TO CAMP RD

340
TO CAMP RD

341
TO CAMP RD

342
TO CAMP RD

343
TO CAMP RD

344
TO CAMP RD

345
TO CAMP RD

346
TO CAMP RD

347
TO CAMP RD

348
TO CAMP RD

349
TO CAMP RD

350
TO CAMP RD

351
TO CAMP RD

352
TO CAMP RD

353
TO CAMP RD

354
TO CAMP RD

355
TO CAMP RD

356
TO CAMP RD

357
TO CAMP RD

358
TO CAMP RD

359
TO CAMP RD

360
TO CAMP RD

361
TO CAMP RD

362
TO CAMP RD

363
TO CAMP RD

364
TO CAMP RD

365
TO CAMP RD

366
TO CAMP RD

367
TO CAMP RD

368
TO CAMP RD

369
TO CAMP RD

370
TO CAMP RD

371
TO CAMP RD

372
TO CAMP RD

373
TO CAMP RD

374
TO CAMP RD

375
TO CAMP RD

376
TO CAMP RD

377
TO CAMP RD

378
TO CAMP RD

379
TO CAMP RD

380
TO CAMP RD

381
TO CAMP RD

382
TO CAMP RD

383
TO CAMP RD

384
TO CAMP RD

385
TO CAMP RD

386
TO CAMP RD

387
TO CAMP RD

388
TO CAMP RD

389
TO CAMP RD

390
TO CAMP RD

391
TO CAMP RD

392
TO CAMP RD

393
TO CAMP RD

394
TO CAMP RD

395
TO CAMP RD

396
TO CAMP RD

397
TO CAMP RD

398
TO CAMP RD

399
TO CAMP RD

400
TO CAMP RD

401
TO CAMP RD

402
TO CAMP RD

403
TO CAMP RD

404
TO CAMP RD

405
TO CAMP RD

406
TO CAMP RD

407
TO CAMP RD

408
TO CAMP RD

409
TO CAMP RD

410
TO CAMP RD

411
TO CAMP RD

412
TO CAMP RD

413
TO CAMP RD

414
TO CAMP RD

415
TO CAMP RD

416
TO CAMP RD

417
TO CAMP RD

418
TO CAMP RD

419
TO CAMP RD

420
TO CAMP RD

421
TO CAMP RD

422
TO CAMP RD

423
TO CAMP RD

424
TO CAMP RD

425
TO CAMP RD

426
TO CAMP RD

427
TO CAMP RD

428
TO CAMP RD

429
TO CAMP RD

430
TO CAMP RD

431
TO CAMP RD

432
TO CAMP RD

433
TO CAMP RD

434
TO CAMP RD

435
TO CAMP RD

436
TO CAMP RD

437
TO CAMP RD

438
TO CAMP RD

439
TO CAMP RD

440
TO CAMP RD

441
TO CAMP RD

442
TO CAMP RD

443
TO CAMP RD

444
TO CAMP RD

445
TO CAMP RD

446
TO CAMP RD

447
TO CAMP RD

448
TO CAMP RD

449
TO CAMP RD

450
TO CAMP RD

451
TO CAMP RD

452
TO CAMP RD

453
TO CAMP RD

454
TO CAMP RD

455
TO CAMP RD

456
TO CAMP RD

457
TO CAMP RD

458
TO CAMP RD

459
TO CAMP RD

460
TO CAMP RD

461
TO CAMP RD

462
TO CAMP RD

463
TO CAMP RD

464
TO CAMP RD

465
TO CAMP RD

466
TO CAMP RD

467
TO CAMP RD

468
TO CAMP RD

469
TO CAMP RD

470
TO CAMP RD

471
TO CAMP RD

472
TO CAMP RD

473
TO CAMP RD

474
TO CAMP RD

475
TO CAMP RD

476
TO CAMP RD

477
TO CAMP RD

478
TO CAMP RD

479
TO CAMP RD

480
TO CAMP RD

481
TO CAMP RD

482
TO CAMP RD

483
TO CAMP RD

484
TO CAMP RD

485
TO CAMP RD

486
TO CAMP RD

487
TO CAMP RD

488
TO CAMP RD

489
TO CAMP RD

490
TO CAMP RD

491
TO CAMP RD

492
TO CAMP RD

493
TO CAMP RD

494
TO CAMP RD

495
TO CAMP RD

496
TO CAMP RD

497
TO CAMP RD

498
TO CAMP RD

499
TO CAMP RD

500
TO CAMP RD

501
TO CAMP RD

502
TO CAMP RD

503
TO CAMP RD

504
TO CAMP RD

505
TO CAMP RD

506
TO CAMP RD

507
TO CAMP RD

508
TO CAMP RD

509
TO CAMP RD

510
TO CAMP RD

511
TO CAMP RD

512
TO CAMP RD

513
TO CAMP RD

514
TO CAMP RD

515
TO CAMP RD

516
TO CAMP RD

517
TO CAMP RD

518
TO CAMP RD

519
TO CAMP RD

520
TO CAMP RD

521
TO CAMP RD

522
TO CAMP RD

523
TO CAMP RD

524
TO CAMP RD

525
TO CAMP RD

526
TO CAMP RD

527
TO CAMP RD

528
TO CAMP RD

529
TO CAMP RD

530
TO CAMP RD

531
TO CAMP RD

532
TO CAMP RD

533
TO CAMP RD

534
TO CAMP RD

535
TO CAMP RD

536
TO CAMP RD

537
TO CAMP RD

538
TO CAMP RD

539
TO CAMP RD

540
TO CAMP RD

541
TO CAMP RD

542
TO CAMP RD

543
TO CAMP RD

544
TO CAMP RD

545
TO CAMP RD

546
TO CAMP RD

547
TO CAMP RD

548
TO CAMP RD

549
TO CAMP RD

550
TO CAMP RD

551
TO CAMP RD

552
TO CAMP RD

553
TO CAMP RD

554
TO CAMP RD

555
TO CAMP RD

556
TO CAMP RD

557
TO CAMP RD

558
TO CAMP RD

559
TO CAMP RD

560
TO CAMP RD

561
TO CAMP RD

562
TO CAMP RD

563
TO CAMP RD

564
TO CAMP RD

565
TO CAMP RD

566
TO CAMP RD

567
TO CAMP RD

568
TO CAMP RD

569
TO CAMP RD

570
TO CAMP RD

571
TO CAMP RD

572
TO CAMP RD

573
TO CAMP RD

574
TO CAMP RD

575
TO CAMP RD

576
TO CAMP RD

577
TO CAMP RD

578
TO CAMP RD

579
TO CAMP RD

580
TO CAMP RD

581
TO CAMP RD

582
TO CAMP RD

583
TO CAMP RD

584
TO CAMP RD

585
TO CAMP RD

586
TO CAMP RD

587
TO CAMP RD

588
TO CAMP RD

589
TO CAMP RD

590
TO CAMP RD

591
TO CAMP RD

592
TO CAMP RD

593
TO CAMP RD

594
TO CAMP RD

595
TO CAMP RD

596
TO CAMP RD

597
TO CAMP RD

598
TO CAMP RD

599
TO CAMP RD

600
TO CAMP RD

601
TO CAMP RD

602
TO CAMP RD

603
TO CAMP RD

604
TO CAMP RD

605
TO CAMP RD

606
TO CAMP RD

607
TO CAMP RD

608
TO CAMP RD

609
TO CAMP RD

610
TO CAMP RD

611
TO CAMP RD

612
TO CAMP RD

613
TO CAMP RD

614
TO CAMP RD

615
TO CAMP RD

616
TO CAMP RD

617
TO CAMP RD

618
TO CAMP RD

619
TO CAMP RD

620
TO CAMP RD

621
TO CAMP RD

622
TO CAMP RD

623
TO CAMP RD

624
TO CAMP RD

625
TO CAMP RD

626
TO CAMP RD

627
TO CAMP RD

628
TO CAMP RD

629
TO CAMP RD

630
TO CAMP RD

631
TO CAMP RD

632
TO CAMP RD

633
TO CAMP RD

634
TO CAMP RD

635
TO CAMP RD

636
TO CAMP RD

637
TO CAMP RD

638
TO CAMP RD

639
TO CAMP RD

640
TO CAMP RD

641
TO CAMP RD

642
TO CAMP RD

643
TO CAMP RD

644
TO CAMP RD

645
TO CAMP RD

646
TO CAMP RD

647
TO CAMP RD

648
TO CAMP RD

649
TO CAMP RD

650
TO CAMP RD

651
TO CAMP RD

652
TO CAMP RD

653
TO CAMP RD

654
TO CAMP RD

655
TO CAMP RD

656
TO CAMP RD

657
TO CAMP RD

658
TO CAMP RD

659
TO CAMP RD

660
TO CAMP RD

661
TO CAMP RD

662
TO CAMP RD

663
TO CAMP RD

664
TO CAMP RD

665
TO CAMP RD

666
TO CAMP RD

667
TO CAMP RD

668
TO CAMP RD

669
TO CAMP RD

670
TO CAMP RD

671
TO CAMP RD

672
TO CAMP RD

673
TO CAMP RD

674
TO CAMP RD

675
TO CAMP RD

676
TO CAMP RD

677
TO CAMP RD

678
TO CAMP RD

679
TO CAMP RD

680
TO CAMP RD

681
TO CAMP RD

682
TO CAMP RD

683
TO CAMP RD

684
TO CAMP RD

685
TO CAMP RD

686
TO CAMP RD

687
TO CAMP RD

688
TO CAMP RD

689
TO CAMP RD

690
TO CAMP RD

691
TO CAMP RD

692
TO CAMP RD

693
TO CAMP RD

694
TO CAMP RD

695
TO CAMP RD

696
TO CAMP RD

697
TO CAMP RD

698
TO CAMP RD

699
TO CAMP RD

700
TO CAMP RD

701
TO CAMP RD

702
TO CAMP RD

703
TO CAMP RD

704
TO CAMP RD

705
TO CAMP RD

706
TO CAMP RD

707
TO CAMP RD

708
TO CAMP RD

709
TO CAMP RD

710
TO CAMP RD

711
TO CAMP RD

712
TO CAMP RD

713
TO CAMP RD

714
TO CAMP RD

715
TO CAMP RD

716
TO CAMP RD

717
TO CAMP RD

718
TO CAMP RD

719
TO CAMP RD

720
TO CAMP RD

721
TO CAMP RD

722
TO CAMP RD

723
TO CAMP RD

724
TO CAMP RD

725
TO CAMP RD

726
TO CAMP RD

727
TO CAMP RD

728
TO CAMP RD

729
TO CAMP RD

730
TO CAMP RD

731
TO CAMP RD

732
TO CAMP RD

733
TO CAMP RD

734
TO CAMP RD

735
TO CAMP RD

736
TO CAMP RD

737
TO CAMP RD

738
TO CAMP RD

739
TO CAMP RD

740
TO CAMP RD

741
TO CAMP RD

742
TO CAMP RD

743
TO CAMP RD

744
TO CAMP RD

745
TO CAMP RD

746
TO CAMP RD

747
TO CAMP RD

748
TO CAMP RD

749
TO CAMP RD

750
TO CAMP RD

751
TO CAMP RD

752
TO CAMP RD

753
TO CAMP RD

754
TO CAMP RD

755
TO CAMP RD

756
TO CAMP RD

757
TO CAMP RD

758
TO CAMP RD

759
TO CAMP RD

760
TO CAMP RD

761
TO CAMP RD

762
TO CAMP RD

763
TO CAMP RD

764
TO CAMP RD

765
TO CAMP RD

766
TO CAMP RD

767
TO CAMP RD

768
TO CAMP RD

769
TO CAMP RD

770
TO CAMP RD

771
TO CAMP RD

772
TO CAMP RD

773
TO CAMP RD

774
TO CAMP RD

775
TO CAMP RD

776
TO CAMP RD

777
TO CAMP RD

778
TO CAMP RD

779
TO CAMP RD

780
TO CAMP RD

781
TO CAMP RD

782
TO CAMP RD

783
TO CAMP RD

784
TO CAMP RD

785
TO CAMP RD

786
TO CAMP RD

787
TO CAMP RD

788
TO CAMP RD

789
TO CAMP RD

790
TO CAMP RD

791
TO CAMP RD

792
TO CAMP RD

793
TO CAMP RD

794
TO CAMP RD

795
TO CAMP RD

796
TO CAMP RD

797
TO CAMP RD

798
TO CAMP RD

799
TO CAMP RD

800
TO CAMP RD

801
TO CAMP RD

802
TO CAMP RD

803
TO CAMP RD

804
TO CAMP RD

805
TO CAMP RD

806
TO CAMP RD

807
TO CAMP RD

808
TO CAMP RD

809
TO CAMP RD

810
TO CAMP RD

811
TO CAMP RD

812
TO CAMP RD

813
TO CAMP RD

814
TO CAMP RD

815
TO CAMP RD

816
TO CAMP RD

817
TO CAMP RD

818
TO CAMP RD

819
TO CAMP RD

820
TO CAMP RD

821
TO CAMP RD

822
TO CAMP RD

823
TO CAMP RD

824
TO CAMP RD

825
TO CAMP RD

826
TO CAMP RD

827
TO CAMP RD

828
TO CAMP RD

829
TO CAMP RD

830
TO CAMP RD

831
TO CAMP RD

832
TO CAMP RD

833
TO CAMP RD

834
TO CAMP RD

835
TO CAMP RD

836
TO CAMP RD

837
TO CAMP RD

838
TO CAMP RD

839
TO CAMP RD

840
TO CAMP RD

841
TO CAMP RD

842
TO CAMP RD

843
TO CAMP RD

844
TO CAMP RD

845
TO CAMP RD

846
TO CAMP RD

847
TO CAMP RD

848
TO CAMP RD

849
TO CAMP RD

850
TO CAMP RD

851
TO CAMP RD

852
TO CAMP RD

853
TO CAMP RD

854
TO CAMP RD

855
TO CAMP RD

856
TO CAMP RD

857
TO CAMP RD

858
TO CAMP RD

859
TO CAMP RD

860
TO CAMP RD

861
TO CAMP RD

862
TO CAMP RD

863
TO CAMP RD

864
TO CAMP RD

865
TO CAMP RD

866
TO CAMP RD

867
TO CAMP RD

868
TO CAMP RD

869
TO CAMP RD

870
TO CAMP RD

871
TO CAMP RD

872
TO CAMP RD

873
TO CAMP RD

874
TO CAMP RD

875
TO CAMP RD

876
TO CAMP RD

877
TO CAMP RD

878
TO CAMP RD

879
TO CAMP RD

880
TO CAMP RD


881
TO CAMP RD

882
TO CAMP RD

883
TO CAMP RD

884
TO CAMP RD

885
TO CAMP




PROJECT REFERENCE

17BP.7.R.103 - ROCKINGHAM 248


SHEET NO.

UO-1

Prepared in the Office of:




THE WOOTEN COMPANY
120 North Boylan Avenue Raleigh, NC 27603-1423
919.828.0531 fax 919.834.3589
License Number: F-0115

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED


GRAPHIC SCALE
25' 0 25' 50'


UTILITIES BY OTHERS

NOTE:
ALL PROPOSED UTILITY WORK
SHOWN ON THIS SHEET WILL
BE DONE BY OTHERS




OVERHEAD POWER HAS BEEN DISCONNECTED
TO DE-ENERGIZE THE PRIMARIES AND WILL
BE PLACED BACK INTO SERVICE AFTER
PROJECT HAS BEEN COMPLETED.


BL	POINT	DESC.	NORTH	EAST	ELEVATION	BL STATION
2		780248-2	965638.8480	1785505.4870	807.41	5+00.00
1		780248-1	964990.7420	1785805.1950	759.76	12+14.05
3		BL-3	964357.8403	1785906.6456	734.95	18+55.03



4/14/2017 8:14:49 AM
R:\Projects\Xsc\Xpl\780248_rdu_xpl.dgn
DWG0003

0	5	10	PROJECT REFERENCE	SHEET NO.
■	■	■	17BP.7.R.103 - ROCKINGHAM 248	X-2





<p><u>GRADE DATA:</u></p> <p>GRADE POINT EL. @ STA. 12+94.00 -L- = EL. 733.80</p> <p>BED EL. @ STA. 12+94.00 -L- = EL. 720.84</p> <p>ROADWAY SLOPE 2:1</p>
--

FOUNDATION NOTES:

NOTES:

INASMUCH AS THE PAINT SYSTEM ON THE EXISTING STRUCTURAL STEEL CONTAINS LEAD, THE CONTRACTOR'S ATTENTION IS DIRECTED TO ARTICLE 107-1 OF THE STANDARD SPECIFICATIONS. ANY COST RESULTING FROM COMPLIANCE WITH APPLICABLE STATE OR FEDERAL REGULATIONS PERTAINING TO HANDLING OF MATERIALS CONTAINING LEAD BASED PAINT SHALL BE INCLUDED IN THE BID PRICE FOR REMOVAL OF EXISTING STRUCTURE AT STATION 12+94.00 -L-.

90° SKEW


REVISIONS						SHEET NO. C-1
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 6
2			4			

PLANS PREPARED BY:


SLIMPSON
SE ENGINEERS
& A ASSOCIATES

5640 Dillard Drive
Suite 200
Cary, NC 27518
(919) 852-0468
(919) 852-0598 (Fax)
www.slimpsonengr.com

LICENSURE NO. C-2521



**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**



END ELEVATION - LOOKING DOWNSTREAM
(UPSTREAM END SHOWN, DOWNSTREAM END SIMILAR)



PROJECT NO. 17BP.7.R.103
ROCKINGHAM COUNTY
 STATION: 12+94.00 -L-

SHEET 2 OF 6

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

DOUBLE 10 FT. X 9 FT.
CONCRETE BOX CULVERT


90° SKEW

REVISIONS						SHEET NO. C-2
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 6
2			4			


**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

DRAWN BY: <u>D.G. VESTER</u>	DATE: <u>7-16</u>
CHECKED BY: <u>B.S. COX</u>	DATE: <u>7-16</u>
DESIGN ENGINEER OF RECORD: <u>B.S. COX</u>	DATE: <u>7-16</u>

4/14/2017 8:26:29 AM G:\Projects\2015\Division 7 (Hatch Mot+)\17BP7R103 (Rockingham 248) ID10X9 Culvert\Structures\Drawings\Final\410_17BP7R103_SMJ_CU.dgn




SECTION OF BARREL
(THERE ARE 83 "C" BARS IN SECTION OF BARREL)



FLOOR PLAN
(SHOWING PLACEMENT OF SILLS)


CULVERT SILL DETAILS

BACKFILL BARREL 1 WITH 2'-0" OF NATIVE MATERIALS
BACKFILL BARREL 2 WITH 1'-0" OF NATIVE MATERIALS
(SEE CULVERT SURVEY AND HYDRAULIC DESIGN REPORT FOR DESCRIPTION OF AND PLACEMENT OF NATIVE MATERIALS.)




SPLICE CHART	
*4 B1 SPLICE LENGTH = 1'-9"	
*4 B3 SPLICE LENGTH = 1'-9"	
*4 C1 SPLICE LENGTH = 1'-11"	
*5 A200 SPLICE LENGTH = 2'-2"	
*7 A400 SPLICE LENGTH = 3'-9"	

BILL OF MATERIAL					
BAR	NO.	SIZE	TYPE	LENGTH	WEIGHT
A1	108	6	4	7'-1"	1149
A2	108	6	4	6'-6"	1054
A100	67	5	STR	21'-7"	1508
A200	54	5	STR	21'-7"	1216
A300	54	6	STR	21'-7"	1751
A400	54	7	STR	21'-7"	2382
B1	118	4	STR	10'-8"	841
B2	108	4	STR	8'-4"	601
B3	90	4	STR	10'-8"	641
C1	166	4	STR	23'-0"	2550
D1	6	6	STR	1'-6"	14
D2	6	6	STR	2'-6"	23
G1	8	5	STR	21'-8"	181
TOTAL REINFORCING STEEL					13911 LB
CLASS A CONCRETE BREAKDOWN					
BARREL					108.0 CY
HEADWALLS					2.0 CY
SILLS					2.2 CY



ELEVATION - LOOKING DOWNSTREAM



SECTION THROUGH SILL

** DOWELS MAY BE PUSHED INTO GREEN CONCRETE AFTER SLAB HAS BEEN FLOAT FINISHED.

PLANS PREPARED BY:

SE & A
IMPSON
ENGINEERS
ASSOCIATES
5640 Dillard Drive
Suite 200
Cary, NC 27518
(919) 852-0468
(919) 852-0598 (Fax)
www.simpsonengr.com
LICENSURE NO. C-2521



PROJECT NO. 17BP.7.R.103
ROCKINGHAM COUNTY
STATION: 12+94.00 -L-

SHEET 3 OF 6


STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

DOUBLE 10 FT. X 9 FT.
CONCRETE BOX CULVERT

90° SKEW

REVISIONS					SHEET NO. C-3
NO.	BY:	DATE:	NO.	BY:	
1			3		TOTAL SHEETS 6
2			4		

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED



REINFORCING STEEL FOR 4 WINGS	1803 LBS
CLASS A CONCRETE	
4 WINGS	26.2 CY
2 END CURTAIN WALLS	2.3 CY
TOTAL	28.5 CY

PROJECT NO. 17BP.7.R.103
ROCKINGHAM COUNTY
 STATION: 12+94.00 -L-

SHEET 4 OF 6

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

WINGS FOR
CONCRETE BOX CULVERT
H = 9'-0" SLOPE = 2:1
90° SKEW


REVISIONS						SHEET NO. C-4
NO.	BY:	DATE:	NO.	BY:	DATE:	
1			3			TOTAL SHEETS 6
2			4			

PLANS PREPARED BY:

**SIMPSON
& SE ENGINEERS
& A ASSOCIATES**


5640 Dillard Drive
Suite 200
Cary, NC 27518
(919) 852-0468
(919) 852-0598 (Fax)
www.simpsonengr.com

ENCLOSURE NO. C-252




**DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED**

4/14/2017 8:26:29 AM G:\Projects\2015\Division 7 (Hatch Mot)\17BP7R103 (Rockingham 248) ID10X9 Culvert\Structures\Drawings\Final\410_17BP7R103_SMJ_CU.dgn




PLAN
(SHOWING GUARDRAIL ANCHOR ASSEMBLY SPACING)




SECTION A-A

SECTION B-B




ELEVATION

THIS SUPPORT SHALL MEET THE REQUIREMENTS AS SPECIFIED FOR SUPPORTS FOR REINFORCING STEEL. SEE SPECIFICATIONS.



PLAN



SIDE VIEW

GUARDRAIL ANCHOR ASSEMBLY FOR CULVERTS

NOTES:

THE GUARDRAIL ANCHOR ASSEMBLY FOR CULVERTS SHALL CONSIST OF THE FOLLOWING COMPONENTS :

- FERRULES SHALL BE MADE FROM STEEL MEETING THE REQUIREMENTS OF AASHTO M169, GRADE 12L14 AND SHALL HAVE A MINIMUM LENGTH OF THREADS OF 2 1/2".
- 4 - 1" Ø X 2 1/4" BOLTS WITH WASHERS, BOLTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM A307. BOLTS AND WASHERS SHALL BE GALVANIZED. (AT THE CONTRACTOR'S OPTION, STAINLESS STEEL BOLTS AND WASHERS MAY BE USED AS AN ALTERNATE FOR THE 1" Ø X 2 1/4" GALVANIZED BOLTS AND WASHERS. THEY SHALL CONFORM TO OR EXCEED THE MECHANICAL REQUIREMENTS OF ASTM A307. THE USE OF THIS ALTERNATE SHALL BE APPROVED BY THE ENGINEER.)
- WIRE STRUTS SHOWN IN THE GUARDRAIL ANCHOR ASSEMBLY FOR CULVERTS DETAIL ARE MINIMUM ALLOWABLE SIZE AND SHALL HAVE A MINIMUM TENSILE STRENGTH OF 100,000 P.S.I. AS AN OPTION, A 1/16" Ø WIRE STRUT WITH A MINIMUM TENSILE STRENGTH OF 90,000 PSI IS ACCEPTABLE.

GUARDRAIL ANCHOR ASSEMBLY WITH BOLTS SHALL BE ASSEMBLED IN THE SHOP. BOLT THREADS MAY BE RECUT AS NECESSARY TO INSURE FIT.

THE COST OF THE GUARDRAIL ANCHOR ASSEMBLY FOR CULVERTS COMPLETE IN PLACE, SHALL BE INCLUDED IN THE UNIT CONTRACT PRICE BID FOR CLASS "A" CONCRETE.

FERRULES TO BE PLUGGED DURING POURING OF SLAB AS RECOMMENDED BY THE MANUFACTURER.

AT THE CONTRACTOR'S OPTION, FERRULES WITH OPEN OR CLOSED ENDS MAY BE USED.

PAYMENT FOR GUARDRAIL, POSTS, AND POST BASE PLATES IS INCLUDED IN ROADWAY PAY ITEMS.

SLAB REINFORCING STEEL MAY BE SHIFTED AS NECESSARY TO CLEAR GUARDRAIL ANCHOR ASSEMBLY. CARE SHOULD BE TAKEN TO KEEP THE SHIFTING OF REINFORCING STEEL TO A MINIMUM.

THE CONTRACTOR MAY USE ADHESIVELY ANCHORED ANCHOR BOLTS IN PLACE OF GUARDRAIL ANCHOR ASSEMBLY. LEVEL TWO FIELD TESTING IS REQUIRED, AND THE YIELD LOAD OF THE 1" Ø BOLT IS 21.8 KIPS. FOR ADHESIVELY ANCHORED ANCHOR BOLTS OR DOWELS, SEE STANDARD SPECIFICATIONS.

PROJECT NO. 17BP.7.R.103
ROCKINGHAM COUNTY
STATION: 12+94.00 -L-

SHEET 5 OF 6

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

ANCHORAGE DETAILS
FOR GUARDRAIL
ANCHOR ASSEMBLY
FOR CULVERTS

REVISIONS

NO.	BY:	DATE:	NO.	BY:	DATE:	SHEET NO.
1			3			C-5
2			4			TOTAL SHEETS 6

PLANS PREPARED BY:

SEA
ENGINEERS
& ASSOCIATES
5640 Dillard Drive
Suite 200
Cary, NC 27518
(919) 852-0468
(919) 852-0598 (Fax)
www.simpsonengr.com


LICENSURE NO. C-2521

4/17/2017

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

4/14/2017 8:26:29 AM G:\Projects\2015\Division 7 (Hatch Mot+)\17BP7R103 (Rockingham 248) (D10X9 Culvert+)\Structures\Drawings\Final\410_17BP7R103_SMJ_CU.dgn

LOAD AND RESISTANCE FACTOR RATING (LRFR) SUMMARY FOR REINFORCED CONCRETE BOX CULVERTS																
LEVEL	VEHICLE	WEIGHT (W) (TONS)	CONTROLLING LOAD RATING ⬡	MINIMUM RATING FACTORS (RF)	TONS = W × RF	STRENGTH I LIMIT STATE									COMMENT NUMBER	
						LIVE-LOAD FACTORS (γ _{LL})	MOMENT				SHEAR					
							RATING FACTOR	BOX NO.	ELEMENT TYPE	DISTANCE FROM LEFT END OF ELEMENT (ft)	RATING FACTOR	BOX NO.	ELEMENT TYPE	DISTANCE FROM LEFT END OF ELEMENT (ft)		
DESIGN LOAD RATING	HL-93 (INVENTORY)	N/A	⬡1	1.32	- -	1.75	1.32	1	TOP SLAB - MID	4.27	1.62	1	TOP SLAB - RT END	9.47		
	HL-93 (OPERATING)	N/A		1.71	- -	1.35	1.71	1	TOP SLAB - MID	4.27	2.10	1	TOP SLAB - RT END	9.47		
	HS-20 (INVENTORY)	36.000	⬡2	1.48	53.3	1.75	1.48	1	TOP SLAB - MID	4.27	1.94	1	TOP SLAB - RT END	9.47		
	HS-20 (OPERATING)	36.000		1.92	69.1	1.35	1.92	1	TOP SLAB - MID	4.27	2.51	1	TOP SLAB - RT END	9.47		
LEGAL LOAD RATING	SINGLE VEHICLE (SV)	SNSH	13.500		2.08	28.1	1.40	2.08	1	TOP SLAB - MID	4.27	2.77	1	TOP SLAB - RT END	9.47	
		SNGARBS2	20.000		1.95	39.0	1.40	1.95	1	TOP SLAB - MID	4.27	2.57	1	TOP SLAB - RT END	9.47	
		SNAGRIS2	22.000		2.08	45.8	1.40	2.08	1	TOP SLAB - MID	4.27	2.73	1	TOP SLAB - RT END	9.47	
		SNCOTTS3	27.250	⬡3	1.33	36.2	1.40	1.33	1	TOP SLAB - MID	4.27	1.54	1	TOP SLAB - RT END	9.47	
		SNAGGRS4	34.925		1.66	58.0	1.40	1.66	1	TOP SLAB - MID	4.27	1.75	1	BOT SLAB - RT END	9.61	
		SNS5A	35.550		1.58	56.2	1.40	1.58	1	TOP SLAB - MID	4.27	1.77	1	TOP SLAB - RT END	9.47	
		SNS6A	39.950		1.58	63.1	1.40	1.58	1	TOP SLAB - MID	4.27	1.72	1	TOP SLAB - RT END	9.47	
		SNS7B	42.000		1.66	69.7	1.40	1.66	1	TOP SLAB - MID	4.27	1.69	1	BOT SLAB - RT END	9.61	
	TRUCK TRACTOR SEMI-TRAILER (TTST)	TNAGRIT3	33.000		1.87	61.7	1.40	2.08	1	TOP SLAB - MID	4.27	1.87	1	BOT SLAB - RT END	9.61	
		TNT4A	33.075		1.59	52.6	1.40	1.59	1	TOP SLAB - MID	4.27	1.76	1	TOP SLAB - RT END	9.47	
		TNT6A	41.600		1.62	67.4	1.40	1.62	1	TOP SLAB - MID	4.27	1.73	1	TOP SLAB - RT END	9.47	
		TNT7A	42.000		1.60	67.2	1.40	1.60	1	TOP SLAB - MID	4.27	1.74	1	TOP SLAB - RT END	9.47	
		TNT7B	42.000		1.56	65.5	1.40	1.56	1	TOP SLAB - MID	4.27	1.75	1	TOP SLAB - RT END	9.47	
		TNAGRIT4	43.000		1.59	68.4	1.40	1.59	1	TOP SLAB - MID	4.27	1.70	1	TOP SLAB - RT END	9.47	
		TNAGT5A	45.000		1.70	76.5	1.40	1.70	1	TOP SLAB - MID	4.27	1.70	1	TOP SLAB - RT END	9.47	
		TNAGT5B	45.000		1.46	65.7	1.40	1.59	1	TOP SLAB - MID	4.27	1.46	1	BOT SLAB - RT END	9.61	



LRFR SUMMARY
(LOOKING DOWNSTREAM)

DRAWN BY: <u>D.G. VESTER</u>	DATE: <u>7-16</u>
CHECKED BY: <u>B.S. COX</u>	DATE: <u>7-16</u>
DESIGN ENGINEER OF RECORD: <u>B.S. COX</u>	DATE: <u>7-16</u>

PLANS PREPARED BY:

SIMPSON & ASSOCIATES
ENGINEERS
5640 Dillard Drive
Suite 200
Cary, NC 27518
(919) 852-0468
(919) 852-0598 (Fax)
www.simpsonengr.com
[LICENSURE NO. C-2521]



PROJECT NO. 17BP.7.R.103
ROCKINGHAM COUNTY
STATION: 12+94.00 -L-

SHEET 6 OF 6

STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION
RALEIGH

LRFR SUMMARY FOR
REINFORCED CONCRETE
BOX CULVERTS
(NON-INTERSTATE TRAFFIC)

REVISIONS						SHEET NO.
NO.	BY:	DATE:	NO.	BY:	DATE:	C-6
1			3			TOTAL SHEETS 6
2			4			

DOCUMENT NOT CONSIDERED FINAL
UNLESS ALL SIGNATURES COMPLETED

LOAD FACTORS:

DESIGN LOAD RATING FACTORS

LOAD TYPE	MAX FACTOR	MIN FACTOR
DC	1.25	0.90
DW	1.50	0.65
EV	1.30	0.90
EH	1.35	0.90
ES	1.35	0.90
LS	1.75	--
WA	1.00	--

NOTE:

RATING FACTORS ARE BASED ON THE STRENGTH I LIMIT STATE.

⬡ CONTROLLING LOAD RATING
⬡1 DESIGN LOAD RATING (HL-93)
⬡2 DESIGN LOAD RATING (HS-20)
⬡3 LEGAL LOAD RATING **
** SEE CHART FOR VEHICLE TYPE

4/14/2017 8:26:30 AM G:\Projects\2015\Division 7 (Hatch Mot+)\17BPTRI03 (Rockingham 248) (D10X9 Culvert+)\Structures\Final\410_17BPTRI03_SML_SN.dgn

STANDARD NOTES

DESIGN DATA:

SPECIFICATIONS	- - - - -	A.A.S.H.T.O. (CURRENT)
LIVE LOAD	- - - - -	SEE PLANS
IMPACT ALLOWANCE	- - - - -	SEE A.A.S.H.T.O.
STRESS IN EXTREME FIBER OF		
STRUCTURAL STEEL - AASHTO M270 GRADE 36	-	20,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50W	-	27,000 LBS. PER SQ. IN.
- AASHTO M270 GRADE 50	-	27,000 LBS. PER SQ. IN.
REINFORCING STEEL IN TENSION		
GRADE 60	- -	24,000 LBS. PER SQ. IN.
CONCRETE IN COMPRESSION	- - - - -	1,200 LBS. PER SQ. IN.
CONCRETE IN SHEAR	- - - - -	SEE A.A.S.H.T.O.
STRUCTURAL TIMBER - TREATED OR		
UNTREATED - EXTREME FIBER STRESS	- - - - -	1,800 LBS. PER SQ. IN.
COMPRESSION PERPENDICULAR TO GRAIN OF TIMBER	- - - -	375 LBS. PER SQ. IN.
EQUIVALENT FLUID PRESSURE OF EARTH	- - - - -	30 LBS. PER CU. FT.
		(MINIMUM)

MATERIAL AND WORKMANSHIP:

EXCEPT AS MAY OTHERWISE BE SPECIFIED ON PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIAL AND WORKMANSHIP SHALL BE IN ACCORDANCE WITH THE 2012 "STANDARD SPECIFICATIONS FOR ROADS AND STRUCTURES" OF THE N. C. DEPARTMENT OF TRANSPORTATION.

STEEL SHEET PILING FOR PERMANENT OR TEMPORARY APPLICATIONS SHALL BE HOT ROLLED.

CONCRETE:

UNLESS OTHERWISE REQUIRED ON PLANS, CLASS A CONCRETE SHALL BE USED FOR ALL PORTIONS OF ALL STRUCTURES WITH THE EXCEPTION THAT: CLASS AA CONCRETE SHALL BE USED IN BRIDGE SUPERSTRUCTURES, ABUTMENT BACKWALLS, AND APPROACH SLABS; AND CLASS B CONCRETE SHALL BE USED FOR SLOPE PROTECTION AND RIP RAP.

CONCRETE CHAMFERS:

UNLESS OTHERWISE NOTED ON THE PLANS, ALL EXPOSED CORNERS ON STRUCTURES SHALL BE CHAMFERED 3/4" WITH THE FOLLOWING EXCEPTIONS: TOP CORNERS OF CURBS MAY BE ROUNDED TO 1-1/2" RADIUS WHICH IS BUILT INTO CURB FORMS; CORNERS OF TRANSVERSE FLOOR EXPANSION JOINTS SHALL BE ROUNDED WITH A 1/4" FINISHING TOOL UNLESS OTHERWISE REQUIRED ON PLANS; AND CORNERS OF EXPANSION JOINTS IN THE ROADWAY FACES AND TOPS OF CURBS AND SIDEWALKS SHALL BE ROUNDED TO A 1/4" RADIUS WITH A FINISHING STONE OR TOOL UNLESS OTHERWISE REQUIRED ON PLANS.

DOWELS:

DOWELS WHEN INDICATED ON PLANS AS FOR CULVERT EXTENSIONS, SHALL BE EMBEDDED AT LEAST 12" INTO THE OLD CONCRETE AND GROUTED INTO PLACE WITH 1:2 CEMENT MORTAR.

ALLOWANCE FOR DEAD LOAD DEFLECTION, SETTLEMENT:

ETC. IN CASTING SUPERSTRUCTURES:

BRIDGES SHALL BE BUILT ON THE GRADE OR VERTICAL CURVE SHOWN ON PLANS. SLABS, CURBS AND PARAPETS SHALL CONFORM TO THE GRADE OR CURVE. ALL DIMENSIONS WHICH ARE GIVEN IN SECTION AND ARE AFFECTED BY DEAD LOAD DEFLECTIONS ARE DIMENSIONS AT CENTER LINE OF BEARING UNLESS OTHERWISE NOTED ON PLANS. IN SETTING FORMS FOR STEEL BEAM BRIDGES AND PRESTRESSED CONCRETE GIRDER BRIDGES, ADJUSTMENTS SHALL BE MADE DUE TO THE DEAD LOAD DEFLECTIONS FOR THE ELEVATIONS SHOWN. WHERE BLOCKS ARE SHOWN OVER BEAMS FOR BUILDING UP TO THE SLAB, THE VERTICAL DIMENSIONS OF THE BLOCKS SHALL BE ADJUSTED BETWEEN BEARINGS TO COMPENSATE FOR DEAD LOAD DEFLECTIONS, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. WHERE BOTTOM OF SLAB IS IN LINE WITH BOTTOM OF TOP FLANGES, DEPTH OF SLAB BETWEEN BEARINGS SHALL BE ADJUSTED TO COMPENSATE FOR DEAD LOAD DEFLECTION, VERTICAL CURVE ORDINATE, AND ACTUAL BEAM CAMBER. IN SETTING FALSEWORK AND FORMS FOR REINFORCED CONCRETE SPANS, AN ALLOWANCE SHALL BE MADE FOR DEAD LOAD DEFLECTIONS, SETTLEMENT OF FALSEWORK, AND PERMANENT CAMBER WHICH SHALL BE PROVIDED FOR IN ADDITION TO THE ELEVATIONS SHOWN. AFTER REMOVAL OF THE FALSEWORK, THE FINISHED STRUCTURES SHALL CONFORM TO THE PROFILE AND ELEVATIONS SHOWN ON THE PLANS AND CONSTRUCTION ELEVATIONS FURNISHED BY THE ENGINEER. DETAILED DRAWINGS FOR FALSEWORK OR FORMS FOR BRIDGE SUPERSTRUCTURE AND ANY STRUCTURE OR PARTS OF A STRUCTURE AS NOTED ON THE PLANS SHALL BE SUBMITTED TO THE ENGINEER FOR APPROVAL BEFORE CONSTRUCTION OF THE FALSEWORK OR FORMS IS STARTED.

REINFORCING STEEL:

ALL REINFORCING STEEL SHALL BE DEFORMED. DIMENSIONS RELATIVE TO PLACEMENT OF REINFORCING ARE TO CENTERS OF BARS UNLESS OTHERWISE INDICATED IN THE PLANS. DIMENSIONS ON BAR DETAILS ARE TO CENTERS OF BARS OR ARE OUT TO OUT AS INDICATED ON PLANS. WIRE BAR SUPPORTS SHALL BE PROVIDED FOR REINFORCING STEEL WHERE INDICATED ON THE PLANS. WHEN BAR SUPPORT PIECES ARE PLACED IN CONTINUOUS LINES, THEY SHALL BE SO PLACED THAT THE ENDS OF THE SUPPORTING WIRES SHALL BE LAPPED TO LOCK LEGS ON ADJOINING PIECES.

STRUCTURAL STEEL:

AT THE CONTRACTOR'S OPTION, HE MAY SUBSTITUTE 7/8"Ø SHEAR STUDS FOR THE 3/4"Ø STUDS SPECIFIED ON THE PLANS. THIS SUBSTITUTION SHALL BE MADE AT THE RATE OF 3 - 7/8"Ø STUDS FOR 4 - 3/4"Ø STUDS, AND STUD SPACING CHANGES SHALL BE MADE AS NECESSARY TO PROVIDE THE SAME EQUIVALENT NUMBER OF 7/8"Ø STUDS ALONG THE BEAM AS SHOWN FOR 3/4"Ø STUDS BASED ON THE RATIO OF 3 - 7/8"Ø STUDS FOR 4 - 3/4"Ø STUDS. STUDS OF THE LENGTH SPECIFIED ON THE PLANS MUST BE PROVIDED. THE MAXIMUM SPACING SHALL BE 2'-0". EXCEPT AT THE INTERIOR SUPPORTS OF CONTINUOUS BEAMS WHERE THE COVER PLATE IS IN CONTACT WITH BEARING PLATE, THE CONTRACTOR MAY, AT HIS OPTION, SUBSTITUTE FOR THE COVER PLATES DESIGNATED ON THE PLANS COVER PLATES OF THE EQUIVALENT AREA PROVIDED THESE PLATES ARE AT LEAST 5/16" IN THICKNESS AND DO NOT EXCEED A WIDTH EQUAL TO THE FLANGE WIDTH LESS 2" OR A THICKNESS EQUAL TO 2 TIMES THE FLANGE THICKNESS. THE SIZE OF FILLET WELDS SHALL CONFORM TO THE REQUIREMENTS OF THE CURRENT ANSI/AASHTO/AWS "BRIDGE WELDING CODE". ELECTROSLAG WELDING WILL NOT BE PERMITTED. WITH THE SOLE EXCEPTION OF EDGES AT SURFACES WHICH BEAR ON OTHER SURFACES, ALL SHARP EDGES AND ENDS OF SHAPES AND PLATES SHALL BE SLIGHTLY ROUNDED BY SUITABLE MEANS TO A RADIUS OF APPROXIMATELY 1/16 INCH OR EQUIVALENT FLAT SURFACE AT A SUITABLE ANGLE PRIOR TO PAINTING, GALVANIZING, OR METALLIZING.

HANDRAILS AND POSTS:

METAL STANDARDS AND FACES OF THE CONCRETE END POSTS FOR THE METAL RAIL SHALL BE SET NORMAL TO THE GRADE OF THE CURB, UNLESS OTHERWISE SHOWN ON PLANS. THE METAL RAIL AND TOPS OF CONCRETE POSTS USED WITH THE ALUMINUM RAIL SHALL BE BUILT PARALLEL TO THE GRADE OF THE CURB. METAL HANDRAILS SHALL BE IN ACCORDANCE WITH THE PLANS. RAILS SHALL BE AS MANUFACTURED FOR BRIDGE RAILING. CASTINGS SHALL BE OF A UNIFORM APPEARANCE. FINIS AND OTHER DEFORMATIONS RESULTING FROM CASTING OR OTHERWISE SHALL BE REMOVED IN A MANNER SO THAT A UNIFORM COLORING OF THE COMPLETED CASTING SHALL BE OBTAINED. CASTINGS WITH DISCOLORATIONS OR OF NON-UNIFORM COLORING WILL NOT BE ACCEPTED. CERTIFIED MILL REPORTS ARE REQUIRED FOR METAL RAILS AND POSTS.

SPECIAL NOTES:

GENERALLY, IN CASE OF DISCREPANCY, THIS STANDARD SHEET OF NOTES SHALL GOVERN OVER THE SPECIFICATIONS, BUT THE REMAINDER OF THE PLANS SHALL GOVERN OVER NOTES HEREON, AND SPECIAL PROVISIONS SHALL GOVERN OVER ALL. SEE SPECIFICATIONS ARTICLE 105-4.