



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

November 23, 2022

BID OPENING: DECEMBER 15, 2022, AT 2:00 P.M.
CONTRACT ID: DG00599
WBS ELEMENT NO.: 17BP.7. R.138
COUNTY: GUILFORD
LOCATION: SR 3412 (TABERNACKLE CHURCH ROAD)
DESCRIPTION: REPLACE BRIDGE #584 OVER BIG ALAMANCE CREEK
TYPE OF WORK: GRADING, PAVING, DRAINAGE AND STRUCTURE
SUBJECT: INVITATION TO BID

This is to request quotations for replacing Bridge #584 over Big Alamance Creek on SR 3412 (Tabernacle Church Road) in Guilford County. The Contractor is to supply materials, equipment, and labor.

The bid opening will be December 15, 2022, at 2:00 p.m. The floating availability date is February 1, 2023, until May 1, 2023. The completion date is 360 consecutive calendar days from the start of construction.

Questions shall be emailed to Jennifer Sour at jsour@ncdot.gov prior to the bid opening. Contact with any other NCDOT personnel concerning this project is strictly prohibited and will result in bids being considered non-responsive

The public letting will be held via conference call. You may join the conference call just prior to 2pm on 12/15/2022. Please dial (919) 250-7881, announce name and company name when prompted.

Bid packages are now available on the NCDOT website at the following location: https://connect.ncdot.gov/letting/Pages/Letting-List.aspx?let_type=7. Please download and print your bid package from the website.

This project shall be bid online. Contractors who wish to submit a bid and do not have a DIVISION ID from Bid Express should pursue obtaining the required ID as it may take several days for the ID to be issued.

Regards,

DocuSigned by:

Jennifer A. Sour

B213233052CA46B...

Jennifer A. Sour

DIVISION PROPOSAL ENGINEER

JAS/bcj

cc: file

cc: W. R. Archer, III, PE P. P. Eason, PE P. D. Wilson, PE C. B. Smitherman, PE
T. Powers, PE M. D. Hayes, PE Plan Rooms Prospective Bidders

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS DIVISION 7
PO BOX 14996
GREENSBORO, NC 27415-4996

Telephone: (336) 487-0075
Fax: (336) 334-3637
Customer Service: 1-877-368-4968

Location:
1584 YANCEYVILLE STREET
GREENSBORO, NC 27405

Website: www.ncdot.gov

Nov 23, 2022 8:25 AM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00599

Page 1 of 5

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** (14+25 -L-)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0134000000-E	240	DRAINAGE DITCH EXCAVATION	10 CY		
0006	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	25 TON		
0007	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	80 SY		
0008	0335200000-E	305	15" DRAINAGE PIPE	52 LF		
0009	0335850000-E	305	*** DRAINAGE PIPE ELBOWS (15")	4 EA		
0010	0344000000-E	310	18" SIDE DRAIN PIPE	132 LF		
0011	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	40 LF		
0012	0995000000-E	340	PIPE REMOVAL	112 LF		
0013	1220000000-E	545	INCIDENTAL STONE BASE	25 TON		
0014	1330000000-E	607	INCIDENTAL MILLING	235 SY		
0015	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	195 TON		
0016	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	300 TON		
0017	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	475 TON		

Nov 23, 2022 8:25 AM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00599

Page 2 of 5

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0018	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	55 TON		
0019	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	4 EA		
0020	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	4 EA		
0021	2556000000-E	846	SHOULDER BERM GUTTER	70 LF		
0022	2612000000-E	848	6" CONCRETE DRIVEWAY	60 SY		
0023	2619000000-E	850	4" CONCRETE PAVED DITCH	100 SY		
0024	3030000000-E	862	STEEL BEAM GUARDRAIL	362.5 LF		
0025	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0026	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0027	3288000000-N	SP	GUARDRAIL END UNITS, TYPE TL-2	4 EA		
0028	3628000000-E	876	RIP RAP, CLASS I	100 TON		
0029	3649000000-E	876	RIP RAP, CLASS B	126 TON		
0030	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	829 SY		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	274 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0033	4445000000-E	1145	BARRICADES (TYPE III)	48 LF		
0034	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	2,600 LF		

Nov 23, 2022 8:25 AM

ITEMIZED PROPOSAL FOR CONTRACT NO. DG00599

Page 3 of 5

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0035	4900000000-N	1251	PERMANENT RAISED PAVEMENT MARKERS	8 EA		
0036	6000000000-E	1605	TEMPORARY SILT FENCE	755 LF		
0037	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	135 TON		
0038	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	120 TON		
0039	6012000000-E	1610	SEDIMENT CONTROL STONE	90 TON		
0040	6015000000-E	1615	TEMPORARY MULCHING	1.5 ACR		
0041	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	200 LB		
0042	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEEDING	1 TON		
0043	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0044	6029000000-E	SP	SAFETY FENCE	200 LF		
0045	6030000000-E	1630	SILT EXCAVATION	170 CY		
0046	6036000000-E	1631	MATTING FOR EROSION CONTROL	5,660 SY		
0047	6037000000-E	SP	COIR FIBER MAT	100 SY		
0048	6042000000-E	1632	1/4" HARDWARE CLOTH	145 LF		
0049	6071020000-E	SP	POLYACRYLAMIDE (PAM)	25 LB		
0050	6084000000-E	1660	SEEDING & MULCHING	3 ACR		
0051	6087000000-E	1660	MOWING	3 ACR		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0052	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0053	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0054	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0055	6108000000-E	1665	FERTILIZER TOPDRESSING	1.5 TON		
0056	6111000000-E	SP	IMPERVIOUS DIKE	41 LF		
0057	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0058	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	7 EA		
0059	6123000000-E	1670	REFORESTATION	0.1 ACR		
0060	6132000000-N	SP	GENERIC EROSION CONTROL ITEM CONCRETE WASHOUT STRUCTURE	2 EA		
STRUCTURE ITEMS						
0061	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (14+25.00 -L-)	Lump Sum	L.S.	
0062	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0063	8112730000-N	450	PDA TESTING	1 EA		
0064	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	58 CY		
0065	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (14+25.00 -L-)	Lump Sum	L.S.	
0066	8217000000-E	425	REINFORCING STEEL (BRIDGE)	9,224 LB		
0067	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (14)	14 EA		

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0068	8364000000-E	450	HP 12 X 53 STEEL PILES	280 LF		
0069	8391000000-N	450	STEEL PILE POINTS	14 EA		
0070	8517000000-E	460	1'-*** X ***** CONCRETE PARAPET (1'-2" X 2'-9-1/2")	200 LF		
0071	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	260 TON		
0072	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	290 SY		
0073	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0074	8753200000-E	430	3'-0" X 3'-3" PRESTRESSED CONC BOX BEAMS	1,100 LF		

0825/Nov23/Q25851.85/D339409400000/E74

Total Amount Of Bid For Entire Project :