STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

January 23, 2022

NOTICE TO PROSPECTIVE BIDDERS

Contract Number:	DH00304
TIP Number:	W-5708A
WBS Number:	44854.3.1
Fed Aid No:	HSIP-0015(055)
County:	Hoke
Description:	Construct Roundabout on US 15-501 and SR 1225 (Ashemont Road)

Subject: **Addendum #1**

The following revisions have been made to the project proposal associated with the above referenced project:

- Please replace Bid Form on page 114 thru 118 in the proposal with the attached Contract Item Sheets.

If this office can provide additional information, please contact me at (910) 773-8034 or cgbrown1@ncdot.gov.

Sincerely,

DocuSigned by:
Chad G. Brown
15C686F6ED674C5...

Chad G. Brown
Division Proposal Engineer

cc: Mr. J. A. Dietrich
Mr. M. W. Kitchen, PE
File

Mailing Address:
NC DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS, DIVISION 8
121 DOT DRIVE
CARTHAGE, NC 28327

Telephone: (910) 773-8000
Fax: (910) 947-3873
Customer Service: 1-877-368-4968

Website: www.ncdot.gov

Location:
121 DOT DRIVE
CARTHAGE, NC 28327

Contract Item Sheets For DH00304

Line #	ItemNumber	Sec #	Description	Quantity Unit	Unit Bid Price	Amount Bid
			ROADWAY ITEMS			
0001	0000100000-N	800	MOBILIZATION	Lump Sum LS		
0002	0036000000-E	225	UNDERCUT EXCAVATION	300 CY		
0003	0043000000-N	226	GRADING	Lump Sum LS		
0004	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUBBING	1 ACR		
0005	0113000000-E	SP	SELECT BORROW MATERIAL	370 CY		
0006	0134000000-E	240	DRAINAGE DITCH EXCAVATION	60 CY		
0007	0195000000-E	265	SELECT GRANULAR MATERIAL	300 CY		
0008	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZATION	1,000 SY		
0009	0255000000-E	SP	GENERIC GRADING ITEM HAULING AND DISPOSAL OF PETROLEUM CONTAMINATED SOIL	415 TON		
0010	0318000000-E	300	FOUNDATION CONDITIONING MATERIAL, MINOR STRUCTURES	140 TON		
0011	0320000000-E	300	FOUNDATION CONDITIONING GEOTEXTILE	420 SY		
0012	0343000000-E	310	15" SIDE DRAIN PIPE	68 LF		
0013	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	276 LF		
0014	0448300000-E	310	18" RC PIPE CULVERTS, CLASS IV	404 LF		
0015	0448400000-E	310	24" RC PIPE CULVERTS, CLASS IV	440 LF		
0016	0448500000-E	310	30" RC PIPE CULVERTS, CLASS IV	104 LF		
0017	0995000000-E	340	PIPE REMOVAL	205 LF		
0018	1121000000-E	520	AGGREGATE BASE COURSE	410 TON		
0019	1220000000-E	545	INCIDENTAL STONE BASE	170 TON		

Contract Item Sheets For DH00304

Line #	ItemNumber	Sec #	Description	Quantity Unit	Unit Bid Price	Amount Bid
0020	1297000000-E	607	MILLING ASPHALT PAVEMENT, ***" DEPTH 1.5" MILLING	880 SY		
0021	1330000000-E	607	INCIDENTAL MILLING	710 SY		
0022	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	2,170 TON		
0023	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	1,250 TON		
0024	1523000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5C	1,420 TON		
0025	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	243 TON		
0026	1693000000-E	654	ASPHALT PLANT MIX, PAVEMENT REPAIR	50 TON		
0027	1840000000-E	665	MILLED RUMBLE STRIPS (ASPHALT CONCRETE)	280 LF		
0028	2000000000-N	806	RIGHT-OF-WAY MARKERS	18 EA		
0029	2253000000-E	840	PIPE COLLARS	0.6 CY		
0030	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	18 EA		
0031	2308000000-E	840	MASONRY DRAINAGE STRUCTURES	5 LF		
0032	2364000000-N	840	FRAME WITH TWO GRATES, STD 840.16	2 EA		
0033	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	3 EA		
0034	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** FRAME WITH GRATE & HOOD, STD 840.03, TY PE E	3 EA		
0035	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** FRAME WITH GRATE & HOOD, STD 840.03, TY PE F	4 EA		

Contract Item Sheets For DH00304

Line #	ItemNumber	Sec #	Description	Quantity Unit	Unit Bid Price	Amount Bid
0036	2374000000-N	840	FRAME WITH GRATE & HOOD, STD 840.03, TYPE ** FRAME WITH GRATE & HOOD, STD 840.03, TY PE G	5 EA		
0037	2396000000-N	840	FRAME WITH COVER, STD 840.54	1 EA		
0038	2451000000-N	852	CONCRETE TRANSITIONAL SECTION FOR DROP INLET	2 EA		
0039	2542000000-E	846	1'-6" CONCRETE CURB & GUTTER	300 LF		
0040	2549000000-E	846	2'-6" CONCRETE CURB & GUTTER	1,320 LF		
0041	2577000000-E	846	CONCRETE EXPRESSWAY GUTTER	375 LF		
0042	2627000000-E	852	4" CONCRETE ISLAND COVER	730 SY		
0043	2655000000-E	852	5" MONOLITHIC CONCRETE ISLANDS (KEYED IN)	340 SY		
0044	2738000000-E	SP	GENERIC PAVING ITEM 7" CONCRETE TRUCK APRON	370 SY		
0045	3649000000-E	876	RIP RAP, CLASS B	13 TON		
0046	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	263 SY		
0047	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	484 SF		
0048	4405000000-E	1110	WORK ZONE SIGNS (PORTABLE)	176 SF		
0049	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	186 SF		
0050	4420000000-N	1120	PORTABLE CHANGEABLE MESSAGE SIGN	4 EA		
0051	4430000000-N	1130	DRUMS	80 EA		
0052	4435000000-N	1135	CONES	60 EA		
0053	4445000000-E	1145	BARRICADES (TYPE III)	136 LF		
0054	4455000000-N	1150	FLAGGER	70 DAY		

Contract Item Sheets For DH00304

Line #	ItemNumber	Sec #	Description	Quantity Unit	Unit Bid Price	Amount Bid
0055	4516000000-N	1180	SKINNY DRUM	50 EA		
0056	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90 MILS)	9,817 LF		
0057	4695000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (8", 90 MILS)	357 LF		
0058	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	25 EA		
0059	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	9,817 LF		
0060	4820000000-E	1205	PAINT PAVEMENT MARKING LINES (8")	357 LF		
0061	4845000000-N	1205	PAINT PAVEMENT MARKING SYMBOL	12 EA		
0062	4850000000-E	1205	REMOVAL OF PAVEMENT MARKING LINES (4")	1,200 LF		
0063	4895000000-N	SP	GENERIC PAVEMENT MARKING ITEM NON-CAST IRON SNOWPLOWABLE (Y& Y)	65 EA		
0064	5325600000-E	1510	6" WATER LINE	567 LF		
0065	5325800000-E	1510	8" WATER LINE	580 LF		
0066	5329000000-E	1510	DUCTILE IRON WATER PIPE FITTINGS	1,940 LB		
0067	5540000000-E	1515	6" VALVE	2 EA		
0068	5546000000-E	1515	8" VALVE	3 EA		
0069	5689000000-E	1515	GENERIC UTILITY ITEM RECONNECT WATER SERVICE	2 EA		
0070	5800000000-E	1530	ABANDON 6" UTILITY PIPE	462 LF		
0071	5801000000-E	1530	ABANDON 8" UTILITY PIPE	708 LF		
0072	5835600000-E	1540	12" ENCASEMENT PIPE	82 LF		
0073	5835700000-E	1540	16" ENCASEMENT PIPE	52 LF		

Contract Item Sheets For DH00304

Line #	ItemNumber	Sec #	Description	Quantity Unit	Unit Bid Price	Amount Bid
0074	5872500000-E	1550	BORE AND JACK OF **" BORE AND JACK OF 12"	64 LF		
0075	5872500000-E	1550	BORE AND JACK OF **" BORE AND JACK OF 16"	52 LF		
0076	6000000000-E	1605	TEMPORARY SILT FENCE	3,220 LF		
0077	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	105 TON		
0078	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	400 TON		
0079	6012000000-E	1610	SEDIMENT CONTROL STONE	285 TON		
0080	6015000000-E	1615	TEMPORARY MULCHING	4 ACR		
0081	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	300 LB		
0082	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED-ING	1.5 TON		
0083	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0084	6030000000-E	1630	SILT EXCAVATION	190 CY		
0085	6036000000-E	1631	MATTING FOR EROSION CONTROL	8,640 SY		
0086	6038000000-E	SP	PERMANENT SOIL REINFORCEMENT MAT	305 SY		
0087	6042000000-E	1632	1/4" HARDWARE CLOTH	790 LF		
0088	6071010000-E	SP	WATTLE	410 LF		
0089	6071020000-E	SP	POLYACRYLAMIDE (PAM)	205 LB		
0090	6071030000-E	1640	COIR FIBER BAFFLE	45 LF		
0091	6084000000-E	1660	SEEDING & MULCHING	6 ACR		
0092	6087000000-E	1660	MOWING	3 ACR		
0093	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		

Contract Item Sheets For DH00304

Line #	ItemNumber	Sec #	Description	Quantity Unit	Unit Bid Price	Amount Bid
0094	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0095	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	100 LB		
0096	6108000000-E	1665	FERTILIZER TOPDRESSING	2.75 TON		
0097	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0098	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	25 EA		
0099	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		

TOTAL AMOUNT OF BID FOR ENTIRE PROJECT **$0.00**

1104/Jan12/Q58570.1/D359309260000/E99