




STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

ROY COOPER
GOVERNOR

J. ERIC BOYETTE
SECRETARY

March 4, 2021

TO: Prospective Bidders

FROM: Jeff Turner, Division Proposals Engineer 
DocuSigned by:
B47701BDF119489...

SUBJECT: **Addendum #1**
Contract: DI00226 – 17BP.9.R.87
SR 1503 (Grace Church Road) – Bridge No. 790255 over Grant's Creek in
Rowan County

The subject contract proposal contains the following addendum:

1. Revised bid form.
There was a discrepancy between the bid form and plans.

This addendum officially becomes part of the contract.

Mar 04, 2021 11:23 am

ITEMIZED PROPOSAL FOR CONTRACT NO. DI00226

Page 1 of 4

County: Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
ROADWAY ITEMS						
0001	0000100000-N	800	MOBILIZATION	Lump Sum	L.S.	
0002	0000400000-N	801	CONSTRUCTION SURVEYING	Lump Sum	L.S.	
0003	0030000000-N	SP	TYPE II MODIFIED APPROACH FILL, STATION ***** (STA13+08)	Lump Sum	L.S.	
0004	0043000000-N	226	GRADING	Lump Sum	L.S.	
0005	0050000000-E	226	SUPPLEMENTARY CLEARING & GRUB- BING	1 ACR		
0006	0196000000-E	270	GEOTEXTILE FOR SOIL STABILIZA- TION	200 SY		
0007	0318000000-E	300	FOUNDATION CONDITIONING MATE- RIAL, MINOR STRUCTURES	10 TON		
0008	0320000000-E	300	FOUNDATION CONDITIONING GEO- TEXTILE	30 SY		
0009	0343000000-E	310	15" SIDE DRAIN PIPE	36 LF		
0010	0448200000-E	310	15" RC PIPE CULVERTS, CLASS IV	32 LF		
0011	0582000000-E	310	15" CS PIPE CULVERTS, 0.064" THICK	16 LF		
0012	1099500000-E	505	SHALLOW UNDERCUT	50 CY		
0013	1099700000-E	505	CLASS IV SUBGRADE STABILIZA- TION	150 TON		
0014	1220000000-E	545	INCIDENTAL STONE BASE	100 TON		
0015	1330000000-E	607	INCIDENTAL MILLING	250 SY		
0016	1491000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0C	280 TON		
0017	1503000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0C	280 TON		
0018	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	230 TON		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0019	1575000000-E	620	ASPHALT BINDER FOR PLANT MIX	40 TON		
0020	2000000000-N	806	RIGHT-OF-WAY MARKERS	11 EA		
0021	2286000000-N	840	MASONRY DRAINAGE STRUCTURES	2 EA		
0022	2352000000-N	840	FRAME WITH GRATE, STD 840.**** (840.35)	2 EA		
0023	2367000000-N	840	FRAME WITH TWO GRATES, STD 840.29	2 EA		
0024	2556000000-E	846	SHOULDER BERM GUTTER	130 LF		
0025	3030000000-E	862	STEEL BEAM GUARDRAIL	350 LF		
0026	3150000000-N	862	ADDITIONAL GUARDRAIL POSTS	5 EA		
0027	3215000000-N	SP	GUARDRAIL ANCHOR UNITS, TYPE III	4 EA		
0028	3287000000-N	SP	GUARDRAIL END UNITS, TYPE TL-3	4 EA		
0029	3656000000-E	876	GEOTEXTILE FOR DRAINAGE	230 SY		
0030	4155000000-N	907	DISPOSAL OF SIGN SYSTEM, U- CHANNEL	4 EA		
0031	4400000000-E	1110	WORK ZONE SIGNS (STATIONARY)	442 SF		
0032	4410000000-E	1110	WORK ZONE SIGNS (BARRICADE MOUNTED)	94 SF		
0033	4445000000-E	1145	BARRICADES (TYPE III)	32 LF		
0034	4810000000-E	1205	PAINT PAVEMENT MARKING LINES (4")	4,400 LF		
0035	6000000000-E	1605	TEMPORARY SILT FENCE	345 LF		
0036	6006000000-E	1610	STONE FOR EROSION CONTROL, CLASS A	75 TON		
0037	6009000000-E	1610	STONE FOR EROSION CONTROL, CLASS B	150 TON		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0038	6012000000-E	1610	SEDIMENT CONTROL STONE	45 TON		
0039	6015000000-E	1615	TEMPORARY MULCHING	0.5 ACR		
0040	6018000000-E	1620	SEED FOR TEMPORARY SEEDING	100 LB		
0041	6021000000-E	1620	FERTILIZER FOR TEMPORARY SEED- ING	0.5 TON		
0042	6024000000-E	1622	TEMPORARY SLOPE DRAINS	200 LF		
0043	6029000000-E	SP	SAFETY FENCE	200 LF		
0044	6030000000-E	1630	SILT EXCAVATION	120 CY		
0045	6036000000-E	1631	MATTING FOR EROSION CONTROL	7,980 SY		
0046	6037000000-E	SP	COIR FIBER MAT	100 SY		
0047	6042000000-E	1632	1/4" HARDWARE CLOTH	60 LF		
0048	6071014000-E	SP	COIR FIBER WATTLE BARRIER	450 LF		
0049	6071020000-E	SP	POLYACRYLAMIDE (PAM)	20 LB		
0050	6084000000-E	1660	SEEDING & MULCHING	0.5 ACR		
0051	6087000000-E	1660	MOWING	0.5 ACR		
0052	6090000000-E	1661	SEED FOR REPAIR SEEDING	50 LB		
0053	6093000000-E	1661	FERTILIZER FOR REPAIR SEEDING	0.25 TON		
0054	6096000000-E	1662	SEED FOR SUPPLEMENTAL SEEDING	50 LB		
0055	6108000000-E	1665	FERTILIZER TOPDRESSING	0.5 TON		
0056	6114500000-N	1667	SPECIALIZED HAND MOWING	10 MHR		
0057	6117000000-N	SP	RESPONSE FOR EROSION CONTROL	15 EA		
0058	6117500000-N	SP	CONCRETE WASHOUT STRUCTURE	2 EA		

County : Rowan

Line #	Item Number	Sec #	Description	Quantity	Unit Cost	Amount
0059	8035000000-N	402	REMOVAL OF EXISTING STRUCTURE AT STATION ***** (STA 13+08)	Lump Sum	L.S.	
0060	8065000000-N	SP	ASBESTOS ASSESSMENT	Lump Sum	L.S.	
0061	8121000000-N	412	UNCLASSIFIED STRUCTURE EXCAVA- TION AT STATION ***** (STA 13+08)	Lump Sum	L.S.	
0062	8182000000-E	420	CLASS A CONCRETE (BRIDGE)	54.2 CY		
0063	8210000000-N	422	BRIDGE APPROACH SLABS, STATION ***** (STA 13+08)	Lump Sum	L.S.	
0064	8217000000-E	425	REINFORCING STEEL (BRIDGE)	6,586 LB		
0065	8328200000-E	450	PILE DRIVING EQUIPMENT SETUP FOR *** STEEL PILES (HP 12X53)	14 EA		
0066	8364000000-E	450	HP12X53 STEEL PILES	210 LF		
0067	8391000000-N	450	STEEL PILE POINTS	7 EA		
0068	8505000000-E	460	VERTICAL CONCRETE BARRIER RAIL	140.29 LF		
0069	8608000000-E	876	RIP RAP CLASS II (2'-0" THICK)	140 TON		
0070	8622000000-E	876	GEOTEXTILE FOR DRAINAGE	190 SY		
0071	8657000000-N	430	ELASTOMERIC BEARINGS	Lump Sum	L.S.	
0072	8763000000-E	430	3'-0" X 2'-0" PRESTRESSED CONC CORED SLABS	910 LF		

1123/Mar04/Q25652.24/D325683134000/E72

Total Amount Of Bid For Entire Project :