



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY
GOVERNOR

ANTHONY J. TATA
SECRETARY

September 22, 2014

TO: Prospective Bidders

FROM: W. Jeff Turner, ^{WJT} Division Proposals Engineer

SUBJECT: Contract DI00072 - "U-4742 NB"
Addendum #1 -
Grading, Drainage, Paving, and Thermoplastic Markings of a Right Turn Lane on SR 1001 (Country Club Road) to SR 1314 (Meadowlark Drive) in Forsyth County

This letter is to advise all prospective bidders of the following contract addendum.

- Replacement of Bid Form

This addendum officially becomes part of the contract.

North Carolina Department of Transportation BID FORM

CONTRACT NO.: DI00072

DESCRIPTION: GRADING, DRAINAGE, PAVING, AND THERMOPLASTIC MARKINGS OF A RIGHT TURN LANE ON SR 1001 (COUNTRY CLUB RD) TO SR 1314 (MEADOWLARK DR) IN FORSYTH COUNTY

LINE	ITEM #	SECT	ITEM DESCRIPTION	QTY*	UNIT	UNIT PRICE	PRICE
1	0000100000-N	800	MOBILIZATION	1	LS		
2	0106000000-E	230	BORROW EXCAVATION	120	CY		
3	0195000000-E	265	SELECT GRANULAR MATERIAL	10	TON		
4	0372000000-E	310	18" RC PIPE CULVERTS, CLASS III	466	LF		
5	0536000000-E	310	HDPE PIPE, 15"	30	LF		
6	0995000000-E	340	PIPE REMOVAL	435	LF		
7	1220000000-E	545	INCIDENTAL STONE BASE	30	TON		
8	1297000000-E	607	MILLING ASPHALT PAVEMENT, 1 ½" DEPTH	100	SY		
9	1489000000-E	610	ASPHALT CONC BASE COURSE, TYPE B25.0B	115	TON		
10	1498000000-E	610	ASPHALT CONC INTERMEDIATE COURSE, TYPE I19.0B	65	TON		
11	1519000000-E	610	ASPHALT CONC SURFACE COURSE, TYPE S9.5B	65	TON		
12	2275000000-E	SP	FLOWABLE FILL	140	CY		
13	2286000000-E	840	MASONRY DRAINAGE STRUCTURES	5	EA		
14	2366000000-E	840	FRAME WITH TWO GRATES, STD 840.24	2	EA		
15	2374000000-E	840	FRAME WITH GRATE & HOOD, STD 840.03, <i>F</i>	3	EA		
16	2472000000-N	840	TRAFFIC BEARING JUNCTION BOX W/MANHOLE	2	EA		
17	2549000000-E	846	2' 6" CONCRETE CURB & GUTTER	300	LF		
18	2591000000-E	848	4" CONCRETE SIDEWALK	25	SY		
19	2605000000-E	848	CONCRETE CURB RAMP	1	EA		
20	2612000000-E	848	6" CONCRETE DRIVEWAY	76	SY		
21	2800000000-N	858	ADJUSTMENT OF CATCH BASIN	1	EA		
22	2815000000-N	858	ADJUSTMENT OF DROP INLETS	1	EA		
23	4457000000-N	SP	TEMPORARY TRAFFIC CONTROL	1	LS		
24	4685000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 90MIL)	70	LF		

North Carolina Department of Transportation BID FORM

CONTRACT NO.: DI00072
DESCRIPTION: GRADING, DRAINAGE, PAVING, AND THERMOPLASTIC MARKINGS OF A RIGHT TURN LANE ON SR 1001 (COUNTRY CLUB RD) TO SR 1314 (MEADOWLARK DR) IN FORSYTH COUNTY

LINE	ITEM #	SECT	ITEM DESCRIPTION	QTY*	UNIT	UNIT PRICE	PRICE
25	4686000000-E	1205	THERMOPLASTIC PAVEMENT MARKING LINES (4", 120MIL)	130	LF		
26	4710000000-E	1205	TERMOPLASTIC PAVEMENT MARKING LINES (24", 120MIL)	30	LF		
27	4725000000-E	1205	THERMOPLASTIC PAVEMENT MARKING SYMBOL (90 MILS)	1	EA		
28	6000000000-E	1605	TEMPORARY SILT FENCE	300	LF		
29	6071010000-E	SP	WATTLE	25	LF		
30	6071020000-E	SP	POLYACRYLAMIDE (PAM)	2	LB		
31	6084000000-E	1660	SEEDING & MULCHING	0.5	ACR		
32	8594000000-E	876	RIP RAP, CLASS B	10	TON		

*The Contractor shall note that all quantities are used only for figuring the lowest responsible bidder. The quantities may vary based on the amount of work needed as directed by the Engineer.

TOTAL BID FOR PROJECT: _____

CONTRACTOR _____
 ADDRESS _____

Federal Identification Number _____	Contractor's License Number _____
Authorized Agent _____	Title _____
Signature _____	Date _____
Witness _____	Title _____
Signature _____	Date _____

THIS SECTION TO BE COMPLETED BY NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
 This bid has been reviewed in accordance with Article 103-1 of the Standard Specifications for Roads and Structures 2012.

Reviewed by _____ (date)
 Accepted by NCDOT _____ Engineer _____ (date)