

Contract #: DI00067

WBS: 17BP.9.R.29

Description: Replace Bridge #119 in Stokes County on SR 1636 over Beaver Island Creek

To all Prospective Bidders:

It has been brought to our attention that there is clarification needed on two items for the above referenced project currently scheduled for the December 10, 2014 bid opening in Division 9.

1. On sheet 3 of the Roadway plans, the Summary of Earthwork quantities included the estimated 435 (-L- Station 13+04.99 to 13+52) and 970 (-L- Station 13+97 to 14+45.53) cubic yards of Unclassified Structure Excavation under Unclassified Excavation. These 1,405 cubic yards should be included in the lump sum bid price for Unclassified Structure Excavation as indicated on Sheet 4 of the roadway plans and Sheet S-1 of the structure plans and not included in the lump sum bid price for Grading.
2. Sheets S-23 and S-24 include a "Section thru Slab" view that indicates a "Reinforced Bridge Approach Fill" as opposed to a "Bridge Approach Fill - Sub Regional Tier". This item will be bid as indicated by Line Item # 3, "Bridge Approach Fill – Sub Regional Tier, Station 13+81.00".

If you should have any questions or concerns related to this clarification, please contact either Mr. Jeff Turner or myself, at 336-747-7800.

Sincerely,

Matthew W. Jones  
Division 9 Bridge Program Manager