

RESTRICTIONS ON CONSTRUCTION OF EMBANKMENT:

(2-17-04) (Rev. 7-18-06)

235

SP2 R65

The Contractor shall construct the embankments to the finished graded roadway section for a minimum distance of 100 feet from the listed end bents, and shall not begin any work on the bridge end bents as listed below until the prescribed waiting periods have elapsed, or until notified by the Engineer that the settlement rate has stabilized and work on the end bents may proceed.

Bridge Description and Affected Bent	Waiting Period
[Description]	[months]

The Contractor will be required to maintain the embankments at finished graded roadway section during the waiting period. Additional earth material required to maintain embankment of finished graded roadway section will be paid at the contract unit price per cubic yard for *Borrow Excavation* or *Unclassified Excavation* depending on the source of the material. Where there is no pay item for *Borrow* or *Unclassified Excavation*, the furnishing of additional material will be paid as extra work.