COMPUTED BY: RWP / KSH DATE: MAY 2013
CHECKED BY: DBE DATE: JAN. 2014

STATE OF NORTH CAROLINA
DIVISION OF HIGHWAYS

PROJECT REFERENCE NO.	SHEET NO.
U-0071	3-X

M A Engineering Consultants, Inc.
598 East Chatham Street Suite 137 Cary, NC 27511
Phone: 919.297.0220 Fax: 919.297.0221

SUMMARY OF WOVEN WIRE FENCE, 47" FABRIC

IN LINEAR FEET AND EACH

STATION TO STATION	LT. or RT.	FABRIC LF	4" POSTS EA	5" POSTS EA
-Y1- 30+10.00 RT to -Y7RPC- 18+26.66 RT	RT	2,597	159	49
-Y7RPC- 18+98.90 RT to -Y7- 26+30.00 RT	RT	2,002	123	37
-Y7- 26+30.00 LT to -L- 124+90.16 RT	RT	3,676	230	61
-L- 126+27.16 RT to -LDFEB- 137+72.57 RT	RT	1,521	92	31
-L- 80+93.20 LT to -Y7- 15+25.00 RT	LT	786	50	13
-Y7RPA- 20+47.55 RT to -Y7RPA- 29+45.91 RT	LT	921	58	16
-Y7RPA- 20+24.23 RT to -US70FLY- 45+16.08 LT	LT	2,322	146	37
-EEC70E- 31+05.58 RT to -L- 125+66.48 LT	LT	2,336	147	37
-L- 127+03.48 LT to -DFLW- 17+17.17 LT	LT	1,406	86	28
-EEC70E- 31+30.22 RT to -Y3- 47+45.00 RT	RT	1,229	76	22
-Y3- 48+65.00 RT to -Y3- 63+90.00 RT	RT	1,526	99	19
-US70FLY- 45+53.23 LT to -Y3- 64+45.00 LT	LT	3,199	207	40
NOTE: LT. OR RT. INDICATES LEFT OR RIGHT OF THE MAIN LINE.	TOTAL	23,521	1,473	390
	SAY	23,600	1,510	400

SUMMARY OF CHAIN LINK FENCE, 48" FABRIC

IN LINEAR FEET AND EACH

STATION TO STATION	LT. or RT.	FABRIC LF	FABRIC, VINYL COATED LF	LINE POSTS EA	TERMINAL POSTS EA
-L- 15+18.44 RT to -Y1- 27+81.57 LT	RT	3,074		258	13
-RAMPB- 17+40.08 LT to -Y1- 38+14.39 LT	LT	1,133		95	7
-Y1- 37+51.98 RT to -RAMPA- 13+99.77 RT	LT	1,532		129	8
-Y1- 24+00.00 to -Y1- 27+40.00	RT		342	29	2
-Y1- 27+45.00 to -Y1- 30+10.00	RT	279		24	5
NOTE: LT. OR RT. INDICATES LEFT OR RIGHT OF THE MAIN LINE.	TOTAL	6,018	342	535	35
	SAY	6,100	350	550	40

SUMMARY OF CHAIN LINK FENCE, 60" FABRIC

IN LINEAR FEET AND EACH

STATION TO STATION	LT. or RT.	FABRIC LF	LINE POSTS EA	TERMINAL POSTS EA
-DFFLY- 11+11.76 LT to -DFFLY- 18+99.85 LT	LT	837	71	7
-LDFWB- 11+26.63 RT to -LDFWB- 18+19.96 RT	RT	729	62	5
-DFWB- 20+18.34 LT to -DFWB- 22+13.96 LT	LT	208	18	2
-DFWB- 24+72.22 LT to -DFWB- 25+44.64 LT	LT	130	11	2
-DFWB- 28+38.72 LT to -DFWB- 30+12.92 LT	LT	175	15	2
-DFWB- 35+06.28 LT to -DFWB- 35+59.36 LT	LT	113	10	2
-DFWB- 36+80.73 LT to -DFWB- 37+11.43 LT	LT	52	5	2
-DFEB- 35+86.40 RT to -DFFLY- 40+67.10 LT	RT	148	13	3
-DFFLY- 29+71.43 LT to -DFFLY- 37+64.52 LT	RT	860	73	7
-DFEB- 59+12.78 RT to -DFEB- 59+65.00 RT	RT	53	5	2
-DFEB- 72+80.00 RT to -DFEB- 74+80.00 RT	RT	201	18	3
-LDFEB- 181+00.00 RT to -LDFEB- 182+85.00 RT	RT	185	16	3
-LDFEB- 199+50.00 RT to -LDFEB- 202+00.00 RT	RT	263	23	3
-LDFEB- 206+50.00 RT to -LDFEB- 207+49.00 RT	RT	114	10	3
NOTE: LT. OR RT. INDICATES LEFT OR RIGHT OF THE MAIN LINE.	TOTAL	4,068	350	46
	SAY	4,100	360	50

SUMMARY OF CONCRETE BARRIER

IN LINEAR FEET AND EACH

LINE	BEG STATION	END STATION	LOC.	SINGLE FACED BARRIER (LF)	DOUBLE FACED BARRIER TYPE II (VAR. HEIGHT) (LF)	DOUBLE FACED BARRIER TYPE III (VAR. HEIGHT) (LF)	DOUBLE FACED BARRIER TYPE IV (LF)	CONC. BARRIER TRANSITION SECTION (EA)	MEDIAN HAZARD PROTECTION (LF) (SEE DETAIL SHT. 2-BL)	CONCRETE BARRIER w/MOMENT SLAB (LF) (STRUCT. PAY ITEM)
-L-	14+25.00	21+57.00	LT.							734
-SR1-	9+12.90	16+44.82	RT.	734						
-L-	21+57.00	25+28.00	LT.		372					
-L-	25+28.00	28+72.14	LT.	345						
-RAMPB-	10+00.00	15+79.85	LT.	579						
-SR1-	20+15.84	29+36.03	RT.							924
-SR1-	29+36.03	30+92.73	RT.		162					
-L-	35+85.00	42+86.20	RT.	50						658
-L-	38+35.00	43+51.39	LT.							512
-RAMPC-	18+82.70	26+23.14	LT.	739						
-Y1-	31+74.56	33+43.53	LT.	169						
-RAMPB-	19+59.19	25+02.76	RT.	545						
-L-	42+93.45	43+18.45	MED.				25			
-L-	43+18.45	44+99.24	MED.				181' (STRUCT. PAYITEM)			
-L-	44+99.24	45+24.24	MED.				25			
-L-	44+64.92	52+40.00	RT.							783
-L-	45+34.30	53+26.98	LT.	57						729
-RAMPD-	19+19.95	27+40.95	RT.	817						
-Y1-	32+22.81	33+92.97	RT.	170						
-RAMPA-	19+65.43	27+80.12	LT.	816						
-RAMPA-	14+00.00	10+75.00	RT.			323		1		
-RAMPA- /-L-	10+75.00 RT	64+20.00 LT	-						191	
-L- /-SR2-	64+20.00 LT.	34+20.00 RT.	-			1,657		1		
-L-	64+38.00	65+13.00	MED.						75	
-Y7RPC- /-L-	12+50.00 LT.	65+10.00 RT.	-			335	105	2		
-L-	65+10.00	65+80.00	RT.						70	
-L-	65+80.00	70+50.00	RT.			475		1		
-L-	84+35.00	84+82.00	MED.					1		
-L-	84+82.00	85+52.00	MED.						70	
-Y7RPA-	10+07.86	10+87.86	RT.	80						
-L-	106+24.48	107+85.35	RT.	155						
-WBL-	107+95.00	109+20.00	LT.	130						
-US70FLY-	10+20.03	16+70.77	LT.	640						
-L- /-LDFEB-	126+51.06	130+94.92	RT.	445						
-DFEB-	46+46.95	47+47.19	RT.	100						
-DFLW-	37+69.86	38+09.16	RT.	40						
-DFWB-	54+16.53	58+07.49	RT.	386						
-DFWB-	54+20.40	58+02.55	LT.	387						
			TOTAL	7,384	534	2,790	155	6	406	4,340
			SAY	7,400	540	2,800	160	6	410	STRUCT. PAY ITEM

SUMMARY OF CHAIN LINK FENCE, 96" FABRIC

IN LINEAR FEET AND EACH

STATION TO STATION	LT. or RT.	FABRIC LF	LINE POSTS EA	TERMINAL POSTS EA
-DFEB- 56+30.00 RT to -DFEB- 59+12.78 RT	RT	289	25	3
NOTE: LT. OR RT. INDICATES LEFT OR RIGHT OF THE MAIN LINE.	TOTAL	289	25	3
	SAY	300	30	4

1/6/2014
r:\roadway\proj\U0071_Rdy_psh03X_sum.dgn
12:02:43 PM