Section 1636

1 1635-4 MAINTENANCE AND REMOVAL

- 2 Maintain the rock pipe inlet sediment traps, remove and dispose of silt accumulations at the
- 3 pipe inlet sediment traps as directed in accordance with Section 1630.
- 4 Remove rock pipe inlet sediment traps as the project nears completion, or as directed. Prepare
- 5 a seed bed to blend with existing contours and seed and mulch in accordance with
- 6 Section 1660.

7

14

1635-5 MEASUREMENT AND PAYMENT

- 8 Payment for temporary rock pipe inlet sediment traps will be as follows:
- 9 Stone for Erosion Control, Class ____ will be measured and paid in accordance with
- 10 Section 1610.
- 11 Sediment Control Stone will be measured and paid in accordance with Section 1610.
- 12 Silt Excavations will be measured and paid in accordance with Section 1630.

13 **SECTION 1636**

TEMPORARY STREAM CROSSING

15 1636-1 DESCRIPTION

- 16 Construct and maintain culverted temporary stream crossings. Temporary stream crossings
- are not shown in the plan sheets and shall be determined as directed.
- 18 The quantity of stream crossings to be installed will be affected by the actual conditions that
- occur during the construction of the project. The quantity of stream crossings may be
- 20 increased, decreased or eliminated entirely as directed. Such variations in quantity will not be
- 21 considered as alterations in the details of construction or a change in the character of the
- 22 work.

23 **1636-2 MATERIALS**

24 Refer to Division 10.

Item	Section
Sediment Control Stone, No. 5 or 57	1005
Stone for Erosion Control, Class B	1042
Geotextile for Drainage, Type 2	1056

25 1636-3 CONSTRUCTION METHODS

- 26 Construct stream crossings according to Roadway Standard Drawings No. 1645.01 or as
- 27 directed.
- 28 The Contractor shall determine the diameter of pipe(s) that will pass the peak or bankfull
- 29 flow, whichever is less, from a 2-year peak storm, without overtopping. Place the geotextile
- 30 on natural ground, on streambanks and in streambed beneath the temporary pipe(s) and stone
- according to the detail. Install Class B stone around the pipe(s), in the stream channel and on
- 32 the crossing road sideslopes. Place sediment control stone on top of Class B stone according
- 33 to Roadway Standard Drawings No. 1645.01.

34 1636-4 MEASUREMENT AND PAYMENT

- 35 Sediment Control Stone will be measured and paid in accordance with Section 1610.
- 36 Stone for Erosion Control, Class __ will be measured and paid in accordance with
- 37 Article 1610-4.
- 38 Geotextile for Drainage will be measured and paid in accordance with Article 876-4.

- 1 Temporary Pipe for Stream Crossing will be measured and paid at the contract unit price per
- 2 linear foot of temporary pipe approved by the Engineer and measured in place from end to
- 3 end
- 4 Article 104-5, pertaining to revised contract prices, will not apply to this item. No revision in
- 5 the contract unit price will be allowed because of any overrun or underrun.
- 6 Such price and payment will be full compensation for all work covered by this section,
- 7 including, but not limited to, furnishing all materials, labor, equipment and incidentals
- 8 necessary to construct the stream crossings.
- 9 Payment will be made under:

Pay ItemPay UnitTemporary Pipe for Stream CrossingLinear Foot

10 SECTION 1637 11 RISER BASIN

12 1637-1 DESCRIPTION

- 13 Construct, maintain and remove riser basin devices to reduce water velocity and contain
- 14 sediment.
- 15 The actual conditions which occur during the construction of the project will determine the
- quantity of riser basin devices constructed. The quantity of riser basins may be increased,
- 17 decreased or eliminated entirely as directed. Such variations in quantity will not be
- considered as alterations in the details of construction or a change in the character of the
- 19 work.

23

20 **1637-2 MATERIALS**

21 Refer to Divisions 3 and 10.

Item	Section
C.S. Pipe Tee riser	1032-3(C)
Stone for Erosion Control, Class A or Class B	1042-1
Coir Fiber Mat	1060-14

Use a skimmer of solid Schedule 40 PVC pipe that meets the contract.

1637-3 CONSTRUCTION METHODS

- Work includes constructing earth embankments and overflow spillways, and installing outlet
- 25 pipe, tee-riser sections, trash racks, anti-flotation devices, coir fiber baffles, skimmer and
- 26 stone energy dissipater in silt basins in accordance with Roadway Standard Drawings
- No. 1630.01 and 1630.02. Use either anti-flotation method shown in the plans.
- 28 Construct earth embankments with 2:1 side slopes with material meeting roadway
- 29 embankment specifications in accordance with Section 1018. The maximum height of earth
- 30 embankments is 12 ft. Compact embankment to at least 90% of AASHTO T 99 as modified
- 31 by the Department and as directed. Excavate when required to provide minimum surface area
- 32 and minimum storage volume area measured below the top of the principal spillway (top of
- 33 the riser pipe).
- Install a C.S. pipe tee riser as specified in the plans. Additional C.S. pipe may be required to
- 35 obtain the required riser pipe height (crest elevation) as indicated in the plans. Construct
- 36 a trash rack and an anti-flotation device on the riser pipe. Attach skimmer to riser pipe one
- foot above bottom elevation of basin.
- 38 Install coir fiber baffles in the basin in accordance with Section 1640 and as directed.