1 2	SECTION 350 PIPE CLEAN OUT	
3	350-1 DESCRIPTION	
4 5	Clean out silt accumulations and other debris from existing drainage pipes at locations shown in the plans and as directed.	
6	350-2 CONSTRUCTION METHODS	
7	Use a pipe clean out method that does not damage the existing pipe.	
8	350-3 MEASUREMENT AND PAYMENT	
9 10 11 12 13	<i>Pipe Clean Out</i> will be measured and paid as the actual number of existing pipes, structure to structure, cleaned out and accepted, except where the work of cleaning out the pipe was made necessary by the Contractor's negligence in taking appropriate erosion control measures. Such price and payment will be full compensation for cleaning out existing pipe and disposing of all silt and debris.	
14	Payment will be made under:	
		ay Unit ach

3-10