

DIVISION 8 INCIDENTALS

SECTION 800 MOBILIZATION

800-1 DESCRIPTION

This work consists of preparatory work and operations to mobilize personnel, materials and equipment to the project site.

800-2 MEASUREMENT AND PAYMENT

Mobilization will be paid as contract lump sum price.

Partial payments for *Mobilization* will be made with the first and second partial pay estimates paid on the contract and will be made at the rate of 50% lump sum price on each of these partial pay estimates, provided the amount bid for *Mobilization* does not exceed 5% of the total amount bid for the contract. Where the amount bid for *Mobilization* exceeds 5% of the total amount bid for the contract, 2.5% of the total amount bid will be paid on each of the first 2 partial pay estimates. That portion exceeding 5% will be paid on the last partial pay estimate.

As an exception to the above, where the work covered by the contract is limited exclusively to the resurfacing of an existing pavement, payment of the entire lump sum price for *Mobilization* will be made with the first partial pay estimate paid on the contract, provided the amount bid does not exceed 5% of the total amount bid for the contract. Where the amount bid for *Mobilization* exceeds 5% of the total amount bid for the contract, 5% of the total amount bid will be paid on the first partial pay estimate. That portion exceeding 5% will be paid on the last partial pay estimate.

Such price and payment includes, but is not limited to, the movement of personnel, equipment, supplies and incidentals to the project site, for the establishment of offices, buildings and other facilities necessary for work on the project; the removal and disbandment of those personnel, equipment, supplies, incidentals or other facilities that were established for the prosecution of work on the project; and for all other work and operations that shall be performed for costs incurred before beginning work on the various items on the project site.

Payment will be made under:

Pay Item	Pay Unit
Mobilization	Lump Sum

SECTION 801 CONSTRUCTION STAKES, LINES AND GRADE

801-1 DESCRIPTION

When required by the contract, provide all construction layout, surveying, stakeout, supplemental surveying and engineering necessary for the proper control of construction operations in accordance with this section and the *Manual for Construction Layout*. Provide a stakeout of areas where an environmental permit is required before performing any construction in or adjacent to these areas. Stake out limits of the permitted work areas according to the approved permit drawings. Provide clear delineation by use of highly visible flagging. Insure construction limits do not exceed approved permitted work areas. Immediately notify the Engineer of any variations of the stakeout limits when compared to the approved permit drawings.