

## SECTION 850 CONCRETE PAVED DITCH

### 850-1 DESCRIPTION

Construct Portland cement concrete paved ditches as shown in the plans for the various types of ditches. Work includes, but is not limited to, all excavating and backfilling, furnishing and placing concrete, constructing curtain walls and constructing and sealing joints.

### 850-2 MATERIALS

Refer to Division 10.

Item	Section
Curing Agents	1026
Joint Fillers	1028-1
Joint Sealers	1028-2, 1028-3
Portland Cement Concrete, Class B	1000

### 850-3 CONSTRUCTION METHODS

Construct concrete in accordance with Section 825 and give a sidewalk finish, except as otherwise provided herein.

Broom the concrete surface transverse to the longitudinal centerline of the paved ditch. Make joint spacing no less than 5 ft.

Do not place backfill adjacent to the paved ditch until at least 3 curing days have elapsed, unless otherwise approved. Compact backfill to a degree comparable to the adjacent undisturbed material.

### 850-4 MEASUREMENT AND PAYMENT

\_\_\_" *Concrete Paved Ditch* will be measured and paid in square yards that is completed and accepted. Longitudinal measurements will be made along the surface of the pavement at the centerline of the ditch and transverse measurements will be made along the surface of the pavement at right angles to the centerline. No measurement will be made of curtain walls at the beginning or ends of the paved ditches.

Payment will be made under:

Pay Item	Pay Unit
___" Concrete Paved Ditch	Square Yard

## SECTION 852 TRAFFIC ISLANDS AND MEDIANS

### 852-1 DESCRIPTION

Construct traffic islands and medians of the type required by the plans. Perform the work in accordance with the contract.

### 852-2 MATERIALS

Refer to Division 10.

Item	Section
Curing Agents	1026
Herbicide	1060-13
Joint Fillers	1028-1
Joint Sealers	1028-2, 1028-3
Portland Cement Concrete, Class B	1000