

PAY RECORD BOOK ENTRY EXAMPLE

Line Code #260 Changeable Message Signs

3 Ea. @ \$22,000.00

68

<i>Locations</i>	<i>Total</i>	<i>Date</i>	<i>Initials</i>	<i>Remarks</i>
<i>NBL and SBL at ends of project and -1/2-</i>	<i>3.0</i>	<i>7-25-07</i>	<i>MLT</i>	<i>Maximum number of CMS operating on the project at one time.</i>
<i>Project Total:</i>	<i>3.0 Ea.</i>	<i>8-3-07</i>	<i>JRL</i>	

The Contractor is only paid for the total quantity of CMS in place and operating at any one time during the project. In this example, the Contractor has placed 3 CMS in operation at the same time.

Note: The method of measurement for traffic control items such as drums, cones, barricades, portable work zone signs, barricade mounted work zone signs, Type C flashing arrow panels, changeable message signs, warning flags, warning lights and truck mounted impact attenuators is the maximum number operating or in use at any one time during the life of the project.

Note: Percentages for payment are determined by the Standard Specifications. See Section 1125. See EWB examples for additional information.

Checked By: MLT

Date: 1-19-08