PAY RECORD BOOK ENTRY EXAMPLE

Line Code #260 Drums *422 Ea. @ $45.00* *58*

Station	Station	Locations	Total	Date	Initials	Remarks
12+00+/-		SBL Closures for Median Work	428	6-29-07	MKT	Maximum number of drums on the project at one time.
			428 Ea.	6-29-07	MKT	

The Contractor is only paid for the maximun quantity of Drums in use at any one time during the life of the project. In this example, the Contractor has placed 428 Drums in operation at the same time.

Note: The method of measurement for traffic control items such as drums, cones, barricades, portable work zone signs, barricade mounted work zone signs, Type C flashing arrow panels, changeable message signs, warning flags, warning lights and truck mounted impact attenuators is the maximum number operating or in use at any one time during the life of the project.

Checked By: MLF

Date: 1-19-00