

**PAY RECORD BOOK ENTRY EXAMPLE**

*Line Code #258 Truck Mounted Impact Attenuator*

*2 Ea. @ \$11,850.00*

*64*

<i>Station</i>	<i>Loc.</i>	<i>Lt./Rt.</i>			<i>Total</i>	<i>Date</i>	<i>Initials</i>	<i>Remarks</i>
<i>435+60</i>	<i>-L Rev. -</i>	<i>Rt.</i>			<i>1</i>	<i>8-24-98</i>	<i>GTP</i>	<i>Approach end of barrier - Phase 1</i>
<i>23+85</i>	<i>-14-</i>	<i>Rt.</i>			<i>1</i>	<i>9-3-98</i>	<i>GTP</i>	<i>Approach end of barrier - Phase 1</i>
								<i>Added to project.</i>
			<i>Page &amp;</i>	<i>Project</i>	<i>Total:</i>	<i>2 Ea.</i>	<i>10-2-99</i>	<i>MCK7</i>

The Contractor is only paid for the maximum quantity of TMIA's in use at any one time during the life of the project. In this example, the Contractor has placed 2 TIMAs in operation at the same time.

Note: The method of measurement for traffic control items such as drums, cones, barricades, portable work zone signs, barricade mounted work zone signs, Type C flashing arrow panels, changeable message signs, warning flags, warning lights and truck mounted impact attenuators is the maximum number operating or in use at any one time during the life of the project.

*Checked By: ML7*

*Date: 1-19-00*