

## **NCDOT Prioritization 3.0 Project Summary**

**SPOT ID:** H141917 Mode: Highway Status: Submitted

## **NC-127**

From/Cross Street: SR-1146 (Bethlehem School

Road)

To:

Length: 0.5

Specific Improvement Type: 10 - Improve Intersection

**Project Category: Regional Impact** 

Cost to NCDOT: \$233,000

TIP#:

**Fully Funded in Draft STIP?** 

MPOS(s)/RPO(s): Greater Hickory MPO

**Description:** 

Add right turn lane on NC 127.

Division(s): Division 12

County(s): ALEXANDER

### **Project Location**



09/23/2014 02:22 PM Highway 1/4 NC-127 SPOT ID H141917

## **Statewide Mobility Total Score: 0**

Quantitative Score	Division Engineer Local Input Points	MPO/RPO Local Input Points
	N/A	N/A
Totals: Weight: 0% Weighted Score: 0		

### **Regional Impact Total Score: 28.39**

Quantitative Score		Division Engineer Local Input Points	MPO/RPO Local Input Points
Congestion (V/C) (25%) Safety (10%) [Travel Time] Benefit/Cost (25%) Accessibility / Connectivity (10%)  Totals: Weight: 70% Weighted Score	50.82 16.65 0.00 18.67	Percent: 15% Points: 0	Percent: 15% Points: 81

### **Division Needs Total Score: 11.83**

Quantitative Score		Division Engineer Local Input Points	MPO/RPO Local Input Points
Congestion (V/C) (20%) Safety (10%) [Travel Time] Benefit/Cost (20%)  Totals: Weight: 50% Weighted Scor	50.82 16.65 0.00	Percent: 25% Points: 0	Percent: 25% Points: 0

09/23/2014 02:22 PM Highway **2/4** 

### Project Data \*

#### **Existing Conditions**

#### **Existing Cross-Section:** Speed Limit: 55 0.5 Length (miles); Arterial Facility Type: Access Control: None Functional Classification: Minor Arterial Terrain Type: Rolling Lane Width: 12 Paved Shoulder Width: 0 Roadway has Curb & Gutter? No 22000 Volume (AADT): Capacity: 31412.6 Volume/Capacity Ratio: 0.7 % Autos: 96% % Trucks: 4% Truck Volume: 960 0 Crash Density: 0 Crash Severity: 0 Critical Crash Rate: Crash Frequency: 33.3 0 Severity Index: 2 County Tier Designation: Non-Interstate STRAHNET No Route? Average Commuting Time: 22 Existing Median Type (for Undivided Cost Estimation): Pavement Condition Rating: 89 Actual Congested Speed: 0

Travel Time Index:

#### **Project Benefits**

Project Cross-Section:	
Speed Limit:	55
Length (miles):	0.5
Facility Type:	Two Lane Highway
Access Control:	None
Functional Classification:	Minor Arterial
TerrainType:	Rolling
DOT Design Lane Width:	12
DOT Design Paved Shoulder Width:	4
Travel Time Savings for 30 Years (Total):	0
Travel Time Savings for 30 Years (Autos):	0
Travel Time Savings for 30 Years (Trucks):	0
Long-Term Employment:	
% Change in Economy:	
Provides Direct Connection to Transportation Terminal?	No
Does project upgrade how the roadway functions?	No
In CTP or LRTP?	Yes
CTP/LRTP Name:	Alexander County Transportation Plan
CTP/LRTP Completion Year:	1995
Submitted by:	Division 12

09/23/2014 02:22 PM Highway **3/4** 

<sup>\*</sup> Data reflects calculations which include weighted averages (where applicable) and represent raw output from the Department's SPOT On!ine tool and associated databases.

NC-127 SPOT ID H141917

## **Project Ownership**

#### **Division**

Division	Percent	Regional Impact	Division Needs
Division 12	100%	0	0
	0%	0	0
	0%	0	0
TOTAL Division Points		0	0

### MPO/RPO

MPO/RPO	Percent	Regional Impact	Division Needs
Greater Hickory MPO	100%	81	0
	0%	0	0
	0%	0	0
TOTAL MPO/RPO Points		81	0

# **Project Cost and Source**

Construction Cost:	\$188,000	Cost Estimation Tool
Right-of-Way Cost:	\$45,000	Cost Estimation Tool
Utilities Cost:	\$0	Cost Estimation Tool
Total Project Cost:	\$233,000	
Other Funding:	\$0	None
Cost to NCDOT :	\$233,000	

09/23/2014 02:22 PM Highway **4/4**