

NCDOT Prioritization 3.0 Project Summary

SPOT ID: H142192 Mode: Highway Status: Submitted

SR-1303 (Hickman Road)

From/Cross Street: US 17 Specific Improvement Type: 1 - Widen Existing Roadway

To: South Carolina State Line **Project Category:** Division Needs

Length: 3.66 TIP#:

Fully Funded in Draft STIP?

Cost to NCDOT: \$35,043,000


Description:

Widen existing SR 1303 to a 4-lane divided facility

Division(s): Division 3 County(s): BRUNSWICK

MPOS(s)/RPO(s): Grand Strand Transportation Study Area

Project Location



05/29/2014 12:57 PM Highway 1/4

Quanitative Score	Division Engineer Local Input Points	MPO/RPO Local Input Points
	N/A	N/A
Totals: Weight: 0% Weighted Score: 0		

Regional Impact To	otal Score: ()
--------------------	---------------	---

Quanitative Score	Division Engineer Local Input Points	MPO/RPO Local Input Points
	Percent: 15% Points:	Percent: 15% Points:
Totals: Weight: 0% Weighted Score: 0		

Division Needs Total Score: 0

Quantitative Score		Division Engineer Local Input Points	MPO/RPO Local Input Points
Congestion (V/C) (20%) Safety (20%) Multimodal + [Freight & Military] (10%)	20.39 48.39 0.00	Percent: 25% Points:	Percent: 25% Points:
Totals: Weight: 50% Weighted Score:	13.76		

05/29/2014 12:57 PM Highway **2/4**

Project Data *

Existing Conditions

Existing Cross-Section: 55 Speed Limit: Length (miles); 3.66 Two Lane Highway Facility Type: Access Control: None Functional Classification: Major Collector Terrain Type: Level Lane Width: 11 Paved Shoulder Width: Roadway has Curb & Gutter? No Volume (AADT): 4800 15592.94 Capacity: Volume/Capacity Ratio: 0.31 % Autos: 100% % Trucks: 0% Truck Volume: 0 95.26 Crash Density: 22.7 Crash Severity: Critical Crash Rate: 27.23 Crash Frequency: 0 0 Severity Index: County Tier Designation: 3 Non-Interstate STRAHNET No Route? Average Commuting Time: 24 Existing Median Type (for Undivided Cost Estimation): Pavement Condition Rating: 100 Actual Congested Speed: 0 Travel Time Index:

Project Benefits

Project Cross-Section:	4B - 4 Lane Divided (23' Raised Median) with Paved Shoulders and Sidewalks
Speed Limit:	55
Length (miles):	3.66
Facility Type:	Superstreet
Access Control:	None
Functional Classification:	Major Collector
TerrainType:	Level
DOT Design Lane Width:	12
DOT Design Paved Shoulder Width:	2
Travel Time Savings for 30 Years (Total):	-390352.16
Travel Time Savings for 30 Years (Autos):	-390352.16
Travel Time Savings for 30 Years (Trucks):	0
Long-Term Employment:	
% Change in Economy:	
Provides Direct Connection to Transportation Terminal?	No
Does project upgrade how the roadway functions?	Yes
In CTP or LRTP?	No
CTP/LRTP Name:	
CTP/LRTP Completion Year:	
Submitted by:	Division 3

05/29/2014 12:57 PM Highway **3/4**

^{*} Data reflects calculations which include weighted averages (where applicable) and represent raw output from the Department's SPOT Online tool and associated databases.

SR-1303 (Hickman Road) SPOT ID H142192

Project Ownership

Division

Division	Percent	Regional Impact	Division Needs
Division 3	100%	0	0
	0%	0	0
	0%	0	0
TOTAL Division Points		0	0

MPO/RPO

MPO/RPO	Percent	Regional Impact	Division Needs
Grand Strand Transportation Study Area	100%	0	0
	0%	0	0
	0%	0	0
TOTAL MPO/RPO Points		0	0

Project Cost and Source

Construction Cost:	\$30,601,000	Cost Estimation Tool
Right-of-Way Cost:	\$3,966,000	Cost Estimation Tool
Utilities Cost:	\$476,000	Cost Estimation Tool
Total Project Cost:	\$35,043,000	
Other Funding:	\$0	None
Cost to NCDOT :	\$35,043,000	

05/29/2014 12:57 PM Highway **4/4**