



Chapel Hill BRT Study

Transit Planning using FTA STOPS Model

presented to

North Carolina Model User Group Meeting

presented by

Cambridge Systematics, Inc.

Jay Evans, P.E., AICP Dilya Askaroff, Ph.<mark>D</mark>.

04/26/2017

Presentation Outline

Overview of the Project

Ridership Forecasting –

- » Overview of Federal Transit Administration (FTA) Simplified Trips-on-Project Software (STOPS)
- » Key Inputs and Approaches
- » Results and Sensitivities

Next Steps



Project Overview – Study Area



- 8-mile long corridor
- Runs along Martin Luther King Jr. Blvd./ Columbia St./ US 15-501 South from Eubanks Road park-andride lot to the Southern Village park-and-ride lot
- Direct Connections to UNC Hospitals campus and planned Durham-Orange LRT
- Substantial growth is forecast in the corridor (e.g., +54% in employment from 2010 to 2040)



Project Overview – Partners

- North-South Corridor Study is a 30-month project
- Led by Chapel Hill Transit Partners, which includes:
 - » Town of Chapel Hill
 - » Town of Carrboro
 - » University of North Carolina Chapel Hill
- Funded through combination of Federal (FTA) and local funds
- CS part of a consultant team led by AECOM



Project Overview – Goals

- Make transit more efficient and attractive
- Support planned land uses
- Contribute to regional equity, sustainability, and quality of life

- Improve connectivity along the corridor
- Improve connectivity of the corridor to the region
- Develop a communitysupported project



Photo Source: Chapel Hill Transit: http://nscstudy.org/



Project Overview – Evaluation

- A multi-step alternative development and evaluation process was used
- Included input from project advisory committees and members of the public over the course of the study
- The recommended Bus Rapid Transit (BRT) project (called the Locally-Preferred Alternative, or LPA) includes three possible combinations of running way types along the northern end of the corridor.



Project Overview – Locally-Preferred Alternative



Source: North-South Corridor Study: Executive Summary



Project Overview – LPA – Key Differences



Source: North-South Corridor Study: Executive Summary



Project Overview – LPA Characteristics

Service frequency

» 7.5 min (peak); 10-20 min (off-peak)

End-to-end travel time

» 33 min

- Hours of Operation
 - » 7 days a week
 - » 5:00 am 11:00 pm during the week
 - » 8:00 am 11:00 pm on the weekend



Ridership Forecasting – STOPS Overview

- Quantifies FTA's trips-on-project evaluation measures for FTA major capital funding
- Takes advantage of data that are generally available "off the shelf" to permit a user to develop transit project demand forecasts with relatively modest effort
- Produces reporting which permits straightforward review and interpretation of the likely beneficiaries of the proposed transit improvement



Ridership Forecasting – STOPS Overview (continued)

- Simplified implementation of a conventional "four-step" trip-based model
- Major focus is forecasting trips on major-capital fixed guideway projects (e.g., BRT, streetcar, light rail)
- Nationally calibrated, with adjustments made for local transit and fixed guideway systems



Ridership Forecasting – STOPS Components



-- Development of Non-Home-Based flows from HB transit trip ends

CAMBRIDGE SYSTEMATICS

Ridership Forecasting – Inputs for STOPS, Generally

- State-specific census shape file and 2010 block-boundary file
- CTPP 2000 Parts I, II, & III files
- General Transit Feed Specification (GTFS) time tables to represent current and project transit services
- Locations of project stations
- Definition of planning districts for the project corridor
- MPO data
 - » Year 2000 population and employment by TAZ
 - » Current year (2013) and horizon (2040) year population and employment by TAZ
 - » TAZ-to-TAZ peak period highway impedances from the regional travel model for current and horizon years



Ridership Forecasting – STOPS User Interface

Select GIS Executable C:\Program Files (x86)\ArcGIS\De Select Python Executable* C:\Python27\ArcGIS10.2\pythone * - Only used for ArcGIS	esktop10.2\bin\ w.exe	STOR
Scenario Set-up Steps 1. Select/Create Parameter File		STOPS Batch Steps
2. Specify Station Locations 3. Edit Parameter File	Files Not Found Files Not Found	● Current Yea ⊂ Opening Year ⊂ 10 Year Not Defined Not Defined Not Defined
4. List and Check TAZ and CTPP Files 5. List and Check GTFS Files 5a. EXST GTFS Test 5b. NOBL GTFS Test 6. Define Forecast Years Data Preparation Steps 7. Create Station Buffers	Files Not Found Files Not Found Optional Files Not Found Files Not Found	11. Run Batch Steps Not Complete Image: CTPP Extract
8. Define Districts and Zonal Data 9. Create MPO-TAZ Equivalency and Generate Zonal SE Forecasts 10. Prepare Pedestrian Environment Data	Files Not Found Files Not Found Files Not Found	12. Report STOPS Results 13. Map STOPS Results 14. Z2Z Query From Zone To
Messages Manual Steps		Automatic Steps

Ridership Forecasting – STOPS 1.5 Visibility Factor

- "Visibility factor" influenced mode-specific constants that determine the choice of path-type and access mode and nesting constants
- In STOPS version 1.5 only those BRTs that exclusively operate on dedicated right-of-way can use a maximum visibility factor of 1.0
- BRTs that at least partially operate in mixed traffic are coded with a visibility factor less than 1.0
- After sensitivity testing runs and consultation with FTA, the visibility factor = 0.25 was used
- Since the project completion date, newer STOPS versions 2.0 and 2.01 were released that incorporate an updated approach for setting visibility factors



Ridership Forecasting – Inputs for STOPS, North-South Corridor

General Inputs

» Automobile travel time skims from the Triangle Regional Model

» 2000, 2013 and 2040 MPO socioeconomic data files

Transit Inputs

- » GTFS data for transit agencies in Chapel Hill area
- » Locally reported region-wide ridership
- Project Inputs
 - » Detailed coding information about the proposed project
 - » Custom planning district system
 - » Visibility factor set to represent type of service = 0.25
 - » Route type set to represent type of service "3" for bus/premium bus, route type "0" – for fixed guideway



Ridership Forecasting – Districts Developed for Project Modeling



Ridership Forecasting – STOPS Outputs, Generally

Main STOPS Report

- » Calibration Summary
- » District-to-district and station-to-station flows
 - Total linked transit trips
 - Incremental linked transit trips: Build minus No-build
 - Linked transit trips that use the Project (BRT)
- » Station Volumes
 - >By mode of access at the production end of the trip
- » District-to-district changes in person-miles of travel



Ridership Forecasting – Project Outputs

- Ridership was forecast for several different alternative combinations of dedicated right of way segments.
- The three final LPA variations do not differ in terms of project travel time.
- We developed the report ridership forecast of 8,575 daily riders based on a blending of project forecasts using more and less conservative assumptions about likely market perceptions of the quality of the service.



Ridership Forecasts – Key Sensitivities

- Incorporating dedicated lanes tended to attract the highest ridership levels and produce the greatest VMT reductions
- The proportion of trips by different trip purpose, accessibility, and market share were consistent among the alternatives
- The majority of riders across all the evaluated alternatives used the project for commuter purposes. The second-most prevalent trip purpose was home-based other.
- Stations with PnR facilities, as well as stations near the University area had the highest boardings on the route



Some Lessons Learned from STOPS Application

- Written guidance on STOPS is limited largely because the model and the guidelines are still emerging
- STOPS users must be experienced enough to recognize anomalies as potential problems
- STOPS applications need understanding and care with key inputs:
 - Classification of the project BRT versus Bus
 - Regional Unlinked Trips
 - Station Groupings
 - District Definitions
 - Visibility Factor



Next Steps

- In November 2016, FTA notified Chapel Hill Transit that the North-South Corridor BRT Project was formally accepted into the FTA's Small Starts Project Development program.
- This acceptance into the FTA program will mean that the BRT project can move forward into further engineering analysis and environmental impact review.



Acknowledgments

Chapel Hill Transit

» Project Manager: Mila Vega

AECOM

» Dan Meyers, Julia Suprock, Gavin Poindexter

Cambridge Systematics, Inc.

» Nikhil Puri, Feng Liu, Xuemei Liu



Contact Information

Jay Evans
 jevans@camsys.com
 +1.301.347.9100

Dilya Askaroff

» daskaroff@camsys.com

» +1.301.347.9100

CS Raleigh Office
 1201 Edwards Mill Road, Suite 130
 Raleigh, NC 27607
 +1.919.741.7698

