2025

Highway Maintenance Improvement Program FY 2026-2030 and Needs Assessment

Required by GS 136-44.3

North Carolina Department of Transportation

Division of Highways

Background

Pursuant to N.C.G.S. § 143B-350(f), the Board of Transportation must approve a five-year schedule of state highway maintenance projects and their anticipated costs. This Highway Maintenance Improvement Program (HMIP) is to be published on the Department's website by June 1st of each year. Funding sources for each project in the HMIP, any changes from the previous year's plan, and the reasons for the changes are required.

Section 136-44.3A.(c) charges each highway division to determine and report to the Chief Engineer on the need for rehabilitation, resurfacing, and pavement preservation treatments. Effective January 1, 2020, the HMIP was expanded to include bridge and general maintenance. From these submissions, the Chief Engineer shall establish a five-year priority list and schedule for each highway division based on need based upon the preceding fiscal year's appropriation.

Highway Maintenance Improvement Plans and Needs

The Highway Maintenance Improvement Program, or HMIP, is the Department's primary tool for planning asset level investments across the North Carolina highway system. With focus areas including pavements, bridges and other roadway assets, the current 5-year HMIP covers fiscal years 2025-2029. Each highway division has a schedule by county for each plan year within the 5-year plan. The first year is expected to be "firm," reflecting what will be delivered that year.

The HMIP is submitted annually with modifications to adjust years two through five (which will become years one through four) based on changing conditions such as needs and appropriation levels. The process is managed through the Department's Asset Management System (AMS) which is composed of three subsystems: Pavement Management System (PMS); Bridge Management System (BMS); and the Maintenance Management System (MMS). AMS is used to identify potential areas which meet the treatment and funding requirements for inclusion in HMIP. Highway divisions use this data to develop and refine their work plans. Engineers use data from routine condition surveys on all assets to assist in developing their plans.

The HIMP is organized by:

- Pavements
- Routine Maintenance
- Bridges

PAVEMENTS - HMIP

Statewide - Lane Miles to be Treated in 5 Year HMIP

Division	Budget Group	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	5-Year Total
1	Preservation	136	152	185	230	134	837
	Resurfacing	398	400	399	378	386	1,960
2	Preservation	181	83	90	82	203	639
	Rehabilitation	48	15	3	4	10	80
	Resurfacing	254	311	350	322	322	1,559
3	Preservation	179	132	134	142	150	737
	Rehabilitation	3	10	1	2	-	15
	Resurfacing	413	388	363	387	363	1,913
4	Preservation	278	274	260	272	235	1,320
	Resurfacing	602	591	532	610	578	2,913
5	Preservation	104	101	104	113	96	517
	Rehabilitation		2				2
	Resurfacing	419	442	459	451	445	2,216
6	Preservation	324	307	336	375	363	1,705
	Resurfacing	375	361	341	348	365	1,789
7	Preservation	319	247	322	245	262	1,395
	Resurfacing	352	301	303	301	377	1,634
8	Preservation	301	352	418	343	337	1,752
	Resurfacing	564	553	584	562	633	2,896

Statewide - Lane Miles to be Treated in 5 Year HMIP

Division	Budget Group	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	5-Year Total
9	Preservation	189	193	198	204	158	944
	Resurfacing	277	297	270	250	264	1,358
10	Preservation	204	226	243	215	186	1,074
	Rehabilitation	9	3	4	4	4	25
	Resurfacing	238	349	312	322	289	1,512
11	Preservation	173	168	156	156	172	825
	Rehabilitation	8					8
	Resurfacing	168	174	159	159	168	827
12	Preservation	252	259	253	236	250	1,249
	Resurfacing	488	468	476	458	409	2,299
13	Preservation	162	171	153	152	161	799
	Resurfacing	358	318	301	228	249	1,454
14	Preservation	209	154	153	164	150	829
	Resurfacing	191	169	208	196	192	956
Statewide Totals	Preservation	3,011	2,821	3,004	2,929	2,857	14,623
	Rehabilitation	67	31	8	10	14	130
	Resurfacing	5,097	5,122	5,055	4,972	5,039	25,286

Statewide - Estimated Costs in 5 Year HMIP

Division	Budget Group	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	5-Year Total
1	Preservation	$4,692,000	$4,720,739	$4,882,000	$4,800,000	$4,734,000	$23,828,739
	Resurfacing	$48,272,000	$48,073,000	$48,475,000	$47,870,000	$48,092,000	$240,782,000
2	Preservation	$8,592,142	$5,717,857	$5,717,857	$5,717,857	$5,717,857	$31,463,570
	Rehabilitation	$10,141,850	$3,000,450	$607,750	$913,750	$1,466,750	$16,130,550
	Resurfacing	$32,692,376	$39,833,776	$42,226,476	$40,684,176	$41,367,476	$196,804,280
3	Preservation	$7,152,990	$6,264,810	$6,249,771	$6,295,380	$6,262,475	$32,225,426
	Rehabilitation	$215,750	$1,383,020	$75,075	$199,000		$1,872,845
	Resurfacing	$54,975,389	$52,817,665	$54,326,772	$55,069,107	$55,139,825	$272,328,758
4	Preservation	$7,005,908	$7,000,081	$7,007,599	$7,002,066	$7,037,117	$35,052,771
	Resurfacing	$51,407,453	$51,306,893	$51,408,690	$51,378,351	$51,461,448	$256,962,835
5	Preservation	$6,100,000	$6,559,000	$6,512,000	$6,711,795	$6,576,795	$32,459,590
	Rehabilitation		$888,000				$888,000
	Resurfacing	$54,279,000	$57,515,000	$58,228,000	$58,650,500	$58,830,000	$287,502,500
6	Preservation	$5,864,650	$5,889,920	$6,084,260	$5,758,770	$5,504,650	$29,102,250
	Resurfacing	$40,100,520	$38,935,155	$39,072,995	$39,302,282	$39,439,200	$196,850,152
7	Preservation	$5,863,960	$4,125,704	$6,543,463	$5,873,152	$6,002,358	$28,408,638
	Resurfacing	$44,854,469	$43,249,818	$45,349,081	$42,617,062	$46,175,230	$222,245,660
8	Preservation	$7,257,503	$7,238,478	$7,234,385	$7,241,176	$7,235,039	$36,206,580
	Resurfacing	$51,992,168	$51,747,984	$51,838,247	$51,986,327	$51,626,196	$259,190,922
9	Preservation	$5,350,793	$5,299,668	$5,583,754	$5,258,148	$5,193,239	$26,685,602
	Resurfacing	$41,010,266	$41,142,941	$41,039,774	$41,174,834	$40,919,456	$205,287,271
10	Preservation	$5,208,317	$5,205,420	$4,991,373	$4,716,612	$4,648,204	$24,769,926
	Rehabilitation	$3,355,000	$443,822	$850,956	$910,000	$996,500	$6,556,278
	Resurfacing	$50,047,300	$49,005,319	$48,779,034	$49,086,013	$49,041,705	$245,959,371
11	Preservation	$7,311,980	$7,325,030	$7,342,181	$7,307,124	$7,300,123	$36,586,438
	Rehabilitation	$1,150,000					$1,150,000
	Resurfacing	$30,836,153	$31,986,153	$31,910,294	$32,021,901	$31,908,739	$158,663,240
12	Preservation	$6,576,435	$6,854,995	$6,935,487	$6,761,371	$6,766,081	$33,894,369
	Resurfacing	$44,896,901	$46,102,158	$45,506,016	$45,808,750	$45,551,952	$227,865,777

Statewide - Estimated Costs in 5 Year HMIP

Division	Budget Group	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	5-Year Total
13	Preservation	$6,405,835	$6,401,727	$6,402,558	$6,401,951	$6,401,955	$32,014,026
	Resurfacing	$33,462,352	$33,460,805	$33,461,565	$33,465,317	$33,460,956	$167,310,995
14	Preservation	$5,322,282	$5,387,410	$5,340,510	$5,514,040	$5,256,540	$26,820,782
	Resurfacing	$35,236,700	$35,429,825	$35,158,625	$35,400,250	$35,479,930	$176,705,330
Statewide Totals	Preservation	$88,704,795	$83,990,840	$86,827,198	$85,359,442	$84,636,433	$429,518,707
	Rehabilitation	$14,862,600	$5,715,292	$1,533,781	$2,022,750	$2,463,250	$26,597,673
	Resurfacing	$614,063,047	$620,606,492	$626,780,569	$624,514,870	$628,494,114	$3,114,459,093

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	1	008-Bertie	Resurfacing	NC 11	NC 305	Hertford Co	1.82	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$675,000
2026	1	008-Bertie	Resurfacing	NC 11 Bus.	NC 11	NC 305	3.75	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$880,000
2026	1	008-Bertie	Resurfacing	SR 1112 (Cow Track Rd.)	SR 1260	NC 308	1.57	Full Depth Patching and 1.5" S9.5B	$439,000
2026	1	008-Bertie	Resurfacing	SR 1200 (Connaritsa Rd.)	SR 1221	Dead End	2.79	Full Depth Patching and 1.5" S9.5B	$557,000
2026	1	008-Bertie	Resurfacing	SR 1203 (Moore Rd.)	SR 1200	NC 11	0.19	Full Depth Patching and 1.5" S9.5B	$40,000
2026	1	008-Bertie	Resurfacing	SR 1301 (Hoggard Mill Rd.)	US 13	SR 1301	1.37	Full Depth Patching and 1.5" S9.5B	$274,000
2026	1	008-Bertie	Resurfacing	SR 1303 (Hoggard Mill Rd.)	SR 1301	US 13	0.88	Full Depth Patching and 1.5" S9.5B	$176,000
2026	1	008-Bertie	Resurfacing	SR 1304 (Askewville Rd.)	From SR 1307 (Elm Grove Rd.)	US 13	3.56	Full Depth Patching and 1.5" S9.5B	$711,000
2026	1	008-Bertie	Resurfacing	SR 1320 (Rockpile Rd.)	NC 42	SR 1321	1.81	Full Depth Patching and 1.5" S9.5B	$362,000
2026	1	008-Bertie	Resurfacing	SR 1521 (Cedar Landing Rd.)	SR 1523	SR 1500	3.68	Full Depth Patching and 1.5" S9.5B	$735,000
2026	1	008-Bertie	Preservation	SR 1100 (Grabtown Rd.)	SR 1101 (Madre Rd.)	US 13	1.19	1.25" S9.5B	$145,000
2026	1	008-Bertie	Preservation	SR 1100 (Grabtown Rd.)	US 13	Windsor CL	0.38	1.25" S9.5B	$47,000
2026	1	008-Bertie	Preservation	SR 1100 (Grabtown Rd.)	Windsor CL	NC 308	0.33	1.25" S9.5B	$72,000
2026	1	008-Bertie	Preservation	SR 1246 (Sheriff Garrett Rd.)	SR 1228 (Early Station Rd.)	SR 1200 (Hexlena Rd.)	3.27	Seal - Double	$155,000
2026	1	008-Bertie	Preservation	SR 1260 (Republican Rd.)	NC 308	SR 1257 (School Rd.)	2.31	Seal - Double	$127,000
2026	1	015-Camden	Resurfacing	SR 1129 (S. Mill Dam Rd.)	NC 343	NC 343	0.88	Full Depth Patching and 1.5" S9.5B	$175,000
2026	1	015-Camden	Resurfacing	SR 1135 (N. River Rd.)	SR 1121 (Trotman Rd.)	US 158	3.69	Full Depth Patching and 1.5" S9.5B	$737,000
2026	1	015-Camden	Resurfacing	SR 1148 (Hawkins Ln.)	NC 343	NC 343	0.31	Full Depth Patching and 1.5" S9.5B	$50,000
2026	1	015-Camden	Resurfacing	SR 1206 (Herman Arnold Rd.)	SR 1207 (Bourbon St.)	NC 34	1.02	Full Depth Patching and 1.5" S9.5B	$204,000
2026	1	015-Camden	Preservation	SR 1252 (Cool Breeze Place)	SR 1219 (Horseshoe Rd.)	Dead End	0.35	Microsurface	$19,000
2026	1	015-Camden	Preservation	SR 1292 (Deerfield Dr.)	SR 1219 (Horsehoe Rd.)	Dead End	0.20	Microsurface	$12,000
2026	1	015-Camden	Preservation	SR 1293 (Buck Run)	SR 1292 (Deerfield Dr.)	SR 1292 (Deerfield Dr.)	0.28	Microsurface	$17,000
2026	1	015-Camden	Preservation	SR 1294 (Whitetail Rd.)	SR 1292 (Deerfield Dr.)	Dead End	0.12	Microsurface	$7,000
2026	1	021-Chowan	Resurfacing	SR 1238 (Parrish Rd.)	SR 1225 (Nixon Rd.)	SR 1225 (Nixon Rd.)	0.61	#67 Mat Seal and 1.5" S9.5B	$144,000
2026	1	021-Chowan	Resurfacing	SR 1301 (Bunch Rd.)	Gates County Line	SR 1002 (County Line Rd.)	0.55	Full Depth Patching and 1.5" S9.5B	$110,000
2026	1	021-Chowan	Resurfacing	SR 1312 (Center Hill Rd.)	SR 1002 (County Line Rd.)	Perquimans County Line	1.92	Full Depth Patching and 1.5" S9.5B	$384,000
2026	1	021-Chowan	Resurfacing	SR 1319 (Paradise Rd.)	SR 1316 (Greenhall Rd.)	Begin 3 Lane	4.37	Full Depth Patching and 1.5" S9.5B	$871,000
2026	1	021-Chowan	Resurfacing	SR 1319 (Paradise Rd.)	Begin 3 Lane	Begin C&G	0.40	Full Depth Patching and 1.5" S9.5B	$96,000
2026	1	021-Chowan	Resurfacing	SR 1319 (Paradise Rd.)	Begin C&G	US 17	0.50	Full Depth Patching and 1.5" S9.5B	$180,000
2026	1	021-Chowan	Preservation	SR 1220 (Dye Plant Rd.)	SR 1222 (Rocky Hock Rd.)	End of Maintenance	0.21	Seal - Double	$11,000
2026	1	021-Chowan	Preservation	SR 1222 (Rocky Hock Rd.)	NC 32	SR 1221 (Brandon Rd.)	6.69	Seal - Double	$334,000
2026	1	027-Currituck	Resurfacing	SR 1222 (Tulls Creek Rd.)	NC 168	SR 1214 (Guinea Rd.)	7.53	1.5" S9.5B	$1,879,000
2026	1	027-Currituck	Preservation	SR 1243 (Knapp Dr.)	NC 168	Dead End	0.12	Microsurface	$8,000
2026	1	027-Currituck	Preservation	SR 1244 (JP Knapp School Rd.)	NC 168	SR 1243-Knapp Dr.	0.07	Microsurface	$5,000
2026	1	027-Currituck	Preservation	SR 1399 (Brumsey Landing Rd.)	SR 1264-Brumsey Rd.	SR 1500-Elizabeth Cir.	0.33	1.25" S9.5B	$41,000
2026	1	027-Currituck	Preservation	SR 1500 (Elizabeth Cir.)	SR 1399-Brumsey Landing Rd.	SR 1399-Brumsey Landing Rd.	0.57	1.25" S9.5B	$69,000
2026	1	027-Currituck	Preservation	SR 1505 (Armstead Ct.)	CDS	SR 1500	0.07	Microsurface	$5,000
2026	1	027-Currituck	Preservation	SR 1510 (Riversedge Dr.)	SR 1222	SR 1513	0.18	1.25" S9.5B	$22,000
2026	1	027-Currituck	Preservation	SR 1510 (Riversedge Dr.)	SR 1513	SR 1513	0.25	1.25" S9.5B	$31,000
2026	1	027-Currituck	Preservation	SR 1511 (King Fisher Cove)	Dead End	SR 1510	0.04	1.25" S9.5B	$5,000
2026	1	027-Currituck	Preservation	SR 1512 (Egret Cove)	CDS	SR 1510	0.03	1.25" S9.5B	$4,000
2026	1	027-Currituck	Preservation	SR 1513 (Mariners Way)	CDS	SR 1510	1.09	1.25" S9.5B	$133,000
2026	1	027-Currituck	Preservation	SR 1514 (Blue Heron Cove Rd.)	SR 1513	SR 1513	0.14	Microsurface	$9,000
2026	1	027-Currituck	Preservation	SR 1515 (Bayside Dr.)	SR 1513	SR 1513	0.31	1.25" S9.5B	$38,000
2026	1	028-Dare	Resurfacing	NC 12	SR 1246 (Austin Rd.)	Osprey Way	1.93	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$635,000
2026	1	028-Dare	Resurfacing	NC 12	Osprey Way	SR 1482 (Buccaneer Dr.)	4.12	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,304,000
2026	1	028-Dare	Resurfacing	NC 12	Hatteras Ferry Dock	SR 1246 (Austin Rd.)	2.57	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$925,000
2026	1	028-Dare	Resurfacing	SR 1236-C. Deering Ridge Rd.	Dead End	NC 12	0.38	Full Depth Patching and 1.5" S9.5B	$69,000
2026	1	028-Dare	Resurfacing	SR 1237-Kohler Dr.	End Maint	NC 12	0.90	Full Depth Patching and 1.5" S9.5B	$145,000
2026	1	028-Dare	Resurfacing	SR 1238-Altona Lane	Dead End	SR 1237-Kohler Dr.	0.21	Full Depth Patching and 1.5" S9.5B	$26,000
2026	1	028-Dare	Resurfacing	SR 1239-Kohler Dr.	SR 1237-Kohler Dr.	NC 12	0.02	Full Depth Patching and 1.5" S9.5B	$5,000
2026	1	028-Dare	Resurfacing	SR 1248-Islington Rd.	Dead End	NC 12	0.15	Full Depth Patching and 1.5" S9.5B	$18,000
2026	1	028-Dare	Resurfacing	SR 1253-Pricilla Curve Rd.	Dead End	SR 1237-Kohler Rd.	0.18	Full Depth Patching and 1.5" S9.5B	$30,000
2026	1	028-Dare	Resurfacing	SR 1254-Stowe Landing Rd.	SR 1237-Kohler Rd.	SR 1255-MV Australia Lane	0.08	Full Depth Patching and 1.5" S9.5B	$13,000
2026	1	028-Dare	Resurfacing	SR 1255-MV Australia Lane	Dead End	SR 1238-Altona Lane	0.15	Full Depth Patching and 1.5" S9.5B	$22,000
2026	1	028-Dare	Resurfacing	SR 1258-Fulcher Rd.	Dead End	NC 12	0.23	Full Depth Patching and 1.5" S9.5B	$47,000
2026	1	028-Dare	Resurfacing	SR 1266-Waltham Rd.	Dead End	NC 12	0.11	Full Depth Patching and 1.5" S9.5B	$20,000
2026	1	028-Dare	Resurfacing	SR 1276-Woodall Way	SR 1511-Sea View Dr.	NC 12	0.31	1.25" S9.5B	$34,000
2026	1	028-Dare	Resurfacing	SR 1294-Bayside Court	Dead End	SR 1295-Paradise Drive	0.18	Full Depth Patching and 1.5" S9.5B	$32,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	1	028-Dare	Resurfacing	SR 1295-Paradise Dr.	Sr 1296-Utopia Lane	NC 12	0.15	Full Depth Patching and 1.5" S9.5B	$30,000
2026	1	028-Dare	Resurfacing	SR 1296-Utopia Lane	Dead End	SR 1293-Seabreeze Drive	0.04	Full Depth Patching and 1.5" S9.5B	$7,000
2026	1	028-Dare	Resurfacing	SR 1298-Lassiter Lane	Dead End	NC 12	0.19	Full Depth Patching and 1.5" S9.5B	$34,000
2026	1	028-Dare	Resurfacing	SR 1310-Flambeau Rd.	SR 1241-Eagle Pass Rd.	SR 1311-Lighthouse Rd.	0.29	Full Depth Patching and 1.5" S9.5B	$58,000
2026	1	028-Dare	Resurfacing	SR 1311-Lighthouse Rd.	SR 1310-Flambeau Rd.	SR 1312-Sea Scape Rd.	0.06	Full Depth Patching and 1.5" S9.5B	$12,000
2026	1	028-Dare	Resurfacing	SR 1312-Sea Scape Rd.	Dead End	SR 1311-Lighthouse Rd.	0.12	Full Depth Patching and 1.5" S9.5B	$25,000
2026	1	028-Dare	Resurfacing	SR 1340-Saxon Cut Dr.	Marlin Club	SR 1237-Kohler Rd.	0.15	Full Depth Patching and 1.5" S9.5B	$30,000
2026	1	028-Dare	Resurfacing	SR 1400-Buccaneer Dr.	Dead End	NC 12	0.43	Full Depth Patching and 1.5" S9.5B	$85,000
2026	1	028-Dare	Resurfacing	SR 1401-Snug Harbor Dr.	SR 1402-Kings Point Dr.	SR 1400-Buccaneer Dr.	0.34	1.25" S9.5B	$42,000
2026	1	028-Dare	Resurfacing	SR 1402-Kings Point Rd.	CDS	SR 1401-Snug Harbor Rd.	0.32	Full Depth Patching and 1.5" S9.5B	$58,000
2026	1	028-Dare	Resurfacing	SR 1426-Freebooter Ct.	CDS	SR 1400-Buccaneer Dr.	0.26	Full Depth Patching and 1.5" S9.5B	$46,000
2026	1	028-Dare	Resurfacing	SR 1451-Blackbeards Ct.	CDS	SR 1400-Buccaneer Dr.	0.27	Full Depth Patching and 1.5" S9.5B	$49,000
2026	1	028-Dare	Resurfacing	SR 1468-Runboat Rd.	NC 12	NC 12	0.46	1.25" S9.5B	$51,000
2026	1	028-Dare	Resurfacing	SR 1489-Spencer Lane	Dead End	NC 12	0.62	Full Depth Patching and 1.5" S9.5B	$124,000
2026	1	028-Dare	Resurfacing	SR 1538-Timber Trail	Dead End	NC 12	0.95	Full Depth Patching and 1.5" S9.5B	$161,000
2026	1	028-Dare	Resurfacing	SR1272-Elizabeth Ave.	Dead End	NC 12	0.42	1.25" S9.5B	$52,000
2026	1	028-Dare	Resurfacing	SR1273-Shoal Dr.	CDS	SR 1272-Elizabeth Ave.	0.10	1.25" S9.5B	$13,000
2026	1	028-Dare	Preservation	SR 1401-Snug Harbor Dr.	SR 1401-Snug Harbor Dr.	SR 1401-Snug Harbor Dr.	0.20	1.0" S9.5B	$14,000
2026	1	028-Dare	Preservation	SR 1403-Captains Court	Dead End	SR 1400-Buccaneer Dr.	0.26	1.0" S9.5B	$29,000
2026	1	028-Dare	Preservation	SR 1404-Treasure Court	Dead End	SR 1402-Kings Point Dr.	0.27	1.0" S9.5B	$30,000
2026	1	028-Dare	Preservation	SR 1430-Pamlico Dr.	CDS	SR 1272-Elizabeth Ave.	0.09	1.0" S9.5B	$11,000
2026	1	028-Dare	Preservation	SR 1487-Cape Hatteras Dr.	Dead End	NC 12	0.20	1.0" S9.5B	$22,000
2026	1	028-Dare	Preservation	SR 1499-Coast Guard Access Rd.	EOM	EOM	0.16	1.0" S9.5B	$31,000
2026	1	028-Dare	Preservation	SR 1505-Sutton Place	Dead End	SR 1276-Woodall Way	0.11	1.0" S9.5B	$14,000
2026	1	028-Dare	Preservation	SR 1521-Liberator Way	Dead End	SR 1276 Woodall Way	0.12	1.0" S9.5B	$15,000
2026	1	028-Dare	Preservation	SR 1526-Cedar Ct.	NC 12	CDS	0.07	1.0" S9.5B	$8,000
2026	1	028-Dare	Preservation	SR 1536-Sand Rd.	SR 1276-Woodall Lane	Dead End	0.12	1.0" S9.5B	$14,000
2026	1	028-Dare	Preservation	SR 1546-Summer Place Dr.	CDS	NC 12	0.24	1.0" S9.5B	$30,000
2026	1	028-Dare	Preservation	SR 1554-Empire Gem Lane	Dead End	SR 1276-Woodall Way	0.12	1.0" S9.5B	$15,000
2026	1	028-Dare	Preservation	SR1447-Queen St.	Dead End	SR 1272-Elizabeth Ave.	0.13	1.0" S9.5B	$14,000
2026	1	037-Gates	Resurfacing	NC 137	US 13	SR 1126 (Corner High Rd.)	2.49	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$702,000
2026	1	037-Gates	Resurfacing	SR 1100 (Carters Rd.)	SR 1103 (Indian Neck Rd.)	NC 32	2.13	Full Depth Patching and 1.5" S9.5B	$425,000
2026	1	037-Gates	Resurfacing	SR 1202 (Gatlington Rd.)	SR 1200-Sand Banks Rd.	SR 1208 (Saunders Rd.)	2.80	Full Depth Patching and 1.5" S9.5B	$503,000
2026	1	037-Gates	Resurfacing	SR 1315 (Cotton Gin Rd.)	SR 1316 (Will Ln.)	US 158	1.05	Full Depth Patching and 1.5" S9.5B	$209,000
2026	1	037-Gates	Resurfacing	SR 1316 (Will Ln.)	SR 1315 (Cotton Gin Rd.)	End of Maintenance	0.24	Full Depth Patching and 1.5" S9.5B	$44,000
2026	1	037-Gates	Resurfacing	SR 1326 (Thicket Rd.)	SR 1327 (Parkers Fork Rd.)	NC 32	2.21	Full Depth Patching and 1.5" S9.5B	$441,000
2026	1	037-Gates	Resurfacing	SR 1418 (Spivey Rd.)	SR 1417 (Selwing Rd.)	Chowan Co.	1.11	Full Depth Patching and 1.5" S9.5B	$222,000
2026	1	037-Gates	Resurfacing	SR 1422 (Mike Bunch Rd.)	SR 1418 (Spivey Rd.)	Chowan Co.	0.18	Full Depth Patching and 1.5" S9.5B	$37,000
2026	1	037-Gates	Resurfacing	US 158	US 158 Bus.	SR 1300 (Medical Center Rd.)	4.48	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,325,000
2026	1	037-Gates	Preservation	SR 1132 (B Parker Ln.)	NC 137	End of Maintenance	0.10	1.25" S9.5B	$11,000
2026	1	037-Gates	Preservation	SR 1404 (Silver Springs Rd.)	SR 1400 (Millpond Rd.)	SR 1407 (Gatling Rd.)	4.41	Seal - Double	$220,000
2026	1	037-Gates	Preservation	SR 1407 (Gatling Rd.)	SR 1409 (Gray Rd.)	SR 1404 (Silver Springs Rd.)	1.41	Seal - Double	$74,000
2026	1	037-Gates	Preservation	SR 1407 (Gatling Rd.)	SR 1411 (Water Swamp Rd.)	SR 1409 (Gray Rd.)	0.77	Seal - Double	$39,000
2026	1	046-Hertford	Resurfacing	NC 11	SR 1108 (Bonner Bridge Rd.)	Overpass @ SR 1130 (Modlin Rd.)	1.90	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$620,000
2026	1	046-Hertford	Resurfacing	NC 305	NC 561	Northampton Co	0.70	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$206,000
2026	1	046-Hertford	Resurfacing	NC 561	NC 305	NC 461	5.47	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,640,000
2026	1	046-Hertford	Resurfacing	SR 1114 (Hortons Church Rd.)	NC 305	SR 1118 (Mill Branch Church Rd.)	3.74	Full Depth Patching and 1.5" S9.5B	$709,000
2026	1	046-Hertford	Resurfacing	SR 1131 (West Saluda Hall Rd.)	NC 11	US 13	1.01	Full Depth Patching and 1.5" S9.5B	$182,000
2026	1	046-Hertford	Resurfacing	SR 1134 (Sears Rd.)	Dead End	NC 461	0.55	Full Depth Patching and 1.5" S9.5B	$105,000
2026	1	046-Hertford	Resurfacing	SR 1135 (Chet Rogerson Rd.)	SR 1108 (Boone Farm Rd.)	NC 461	0.44	Full Depth Patching and 1.5" S9.5B	$79,000
2026	1	046-Hertford	Resurfacing	SR 1308 (Gatling Rd.)	SR 1310 (Statesville Rd.)	US 258	1.03	#67 Mat Seal and 1.5" S9.5B	$242,000
2026	1	046-Hertford	Resurfacing	SR 1418 (Arrow Rd.)	SR 1419 (DT Road)	US 13	0.64	Full Depth Patching and 1.5" S9.5B	$128,000
2026	1	046-Hertford	Resurfacing	SR 1427 (South Moore Town Rd.)	Bertie Co	NC 561	2.67	Full Depth Patching and 1.5" S9.5B	$533,000
2026	1	046-Hertford	Resurfacing	US 158 Bus. (Main St.)	US 158	US 158	4.06	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,735,000
2026	1	046-Hertford	Resurfacing	US 158 EBL	SR 1179 (Chowan College Rd.)	Northampton Co	2.02	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$712,000
2026	1	046-Hertford	Resurfacing	US 158 WBL	Northampton Co	SR 1179 (Chowan College Rd.)	2.02	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$712,000
2026	1	046-Hertford	Resurfacing	US 258	SR 1319 (Mill Neck Rd.)	Virginia State Line	2.50	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$640,000
2026	1	046-Hertford	Resurfacing	US 258	SR 1306 (Parkers Ferry Rd.)	SR 1319 (Mill Neck Rd.)	2.39	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$617,000
2026	1	046-Hertford	Resurfacing	US 258	US 158	Bridge #9 (Meherrin River)	1.75	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$453,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	1	046-Hertford	Preservation	SR 1138 (Peele Rd.)	Dead End	SR 1137 (Liverman Mill Rd.)	0.38	1.0" S9.5B	$42,000
2026	1	046-Hertford	Preservation	SR 1157 (Powell Rd.)	Northampton Co	US 158	0.56	1.0" S9.5B	$68,000
2026	1	046-Hertford	Preservation	SR 1157 (Powell Rd.)	SR 1160 (Spring Avenue)	US 158	0.43	1.0" S9.5B	$53,000
2026	1	046-Hertford	Preservation	SR 1166 (Storey Rd.)	US 158 Bus	SR 1157 (Powell Rd.)	0.33	1.0" S9.5B	$41,000
2026	1	046-Hertford	Preservation	SR 1441 (Swains Mill Rd.)	400' NW of Bridge #42	Bertie Co	5.40	Seal - Double	$297,000
2026	1	048-Hyde	Resurfacing	NC 45	SR 1128 (Oyster Creek Rd.)	Ferry Ramp	0.32	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$133,000
2026	1	048-Hyde	Resurfacing	NC 45	Ferry Ramp	SR 1128 (Oyster Creek Rd.)	0.39	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$69,000
2026	1	048-Hyde	Resurfacing	SR 1143 (Sladesville Credle Rd.)	SR 1141 (Swindel Rd.)	SR 1154 (Old US 264)	8.21	Full Depth Patching and 1.5" S9.5B	$1,637,000
2026	1	048-Hyde	Resurfacing	US 264	NC 94 (Main St.)	SR 1304 (Turnpike Rd.)	2.34	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$659,000
2026	1	048-Hyde	Resurfacing	US 264	SR 1311 (North Lake Rd.)	Bridge #54	2.13	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$530,000
2026	1	048-Hyde	Preservation	SR 1149 (Montgomery Rd.)	SR 1143 (Sladesville Credle Rd.)	SR 1150 (Lowe Rd.)	2.82	Seal - Double	$141,000
2026	1	048-Hyde	Preservation	SR 1306 (Newlands Rd.)	SR 1305 (Piney Woods Rd.)	End of Maintenance	2.37	Seal - Double	$107,000
2026	1	058-Martin	Resurfacing	NC 125	End of 3 Lane	NC 125 Bypass	0.26	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$74,000
2026	1	058-Martin	Resurfacing	NC 125	US 17 Bus. (W. Main St.)	End of 3 Lane	0.89	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$441,000
2026	1	058-Martin	Resurfacing	SR 1116 (Rodgers School Rd.)	SR 1117 (White Rd.)	US 17	0.90	Full Depth Patching and 1.5" S9.5B	$181,000
2026	1	058-Martin	Resurfacing	SR 1162 (Jones St.)	SR 1160 (Roberson St.)	SR 1164 (Main St.)	0.21	Full Depth Patching and 1.5" S9.5B	$40,000
2026	1	058-Martin	Resurfacing	SR 1164 (Main St.)	Pitt County Line	SR 1303 (Dixon Rd.)	1.39	Full Depth Patching and 1.5" S9.5B	$278,000
2026	1	058-Martin	Resurfacing	SR 1446 (Jamesville Rd.)	US 17 Bus.	US 64 Alt. West	0.31	Mill 1.5" and 1.5" S9.5B	$144,000
2026	1	058-Martin	Resurfacing	SR 1450 (River Rd.)	US 17 Bus.	US 17 Bus.	0.58	Full Depth Patching and 1.5" S9.5B	$145,000
2026	1	058-Martin	Resurfacing	SR 1500 (Holly Springs Church Rd.)	NC 171	US 64	3.05	Full Depth Patching and 1.5" S9.5B	$609,000
2026	1	058-Martin	Resurfacing	SR 1516 (Fire Dept. Road)	SR 1114 (Grand Canyon Rd.)	SR 1535 (Hollow Pond Rd.)	4.79	Full Depth Patching and 1.5" S9.5B	$956,000
2026	1	058-Martin	Resurfacing	SR 1521 (Mill Inn Rd.)	SR 1516 (Kader Lilley Rd.)	US 17	1.23	Full Depth Patching and 1.5" S9.5B	$246,000
2026	1	058-Martin	Resurfacing	SR 1541 (Dymond City Rd.)	SR 1538 (E.H. Williams Rd.)	NC 171	1.09	Full Depth Patching and 1.5" S9.5B	$218,000
2026	1	058-Martin	Resurfacing	SR 1598 (East Boulevard)	US 13	US 64 Alt. West	0.25	Full Depth Patching and 1.5" S9.5B	$104,000
2026	1	058-Martin	Resurfacing	SR 1598 (East Boulevard)	US 13	US 64 Alt. West	0.25	Full Depth Patching and 1.5" S9.5B	$103,000
2026	1	058-Martin	Resurfacing	US 17 Bus. (S. Elm St.)	NC 125 (N. Haughton St.)	US 17 Bus. (Washington St.)	0.32	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$61,000
2026	1	058-Martin	Resurfacing	US 17 Bus. (S. Haughton St.)	US 17 Bus. (S. Elm St.)	NC 125 (N. Haughton St.)	0.27	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$78,000
2026	1	058-Martin	Resurfacing	US 17 Bus. (W. Main St.)	NC 125 (N. Haughton St.)	US 13 Bypass (East Blvd.)	1.04	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$292,000
2026	1	058-Martin	Resurfacing	US 17 Bus. (Washington St.)	US 64 Alt. (West/East Blvd.)	US 17 Bus. (S. Elm St.)	0.70	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$372,000
2026	1	058-Martin	Resurfacing	US 64 Alt.	US 17 Bus. (Washington St.0	SR 1446 (Jamesville Rd.)	0.48	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$90,000
2026	1	058-Martin	Preservation	SR 1117 (Green Acres Rd.)	SR SR 1114 (Grand Canyon Rd.)	SR SR 1116 (Rodgers School Rd.)	1.10	1.25" S9.5B	$141,000
2026	1	058-Martin	Preservation	SR 1120 (Hickory Grove Rd.)	SR 1117 (Bear Trap Rd.)	SR 1119 (Ralph Taylor Rd.)	0.99	1.25" S9.5B	$121,000
2026	1	058-Martin	Preservation	SR 1189 (Rawls Rd.)	SR 1159 (Third St.)	US 64 Alt	0.27	1.25" S9.5B	$33,000
2026	1	058-Martin	Preservation	SR 1321 (Hines Rd.)	NC 125	SR 1002 (Hassel Rd.)	0.75	1.25" S9.5B	$92,000
2026	1	058-Martin	Preservation	SR 1540 (Sim Daniel Rd.)	SR 1539 (Evan Perry Rd.)	NC 171	0.57	1.25" S9.5B	$70,000
2026	1	058-Martin	Preservation	SR 1601 (Brezze Woods Ave.)	SR 1501 (Big Mill Rd.)	CDS	0.21	1.25" S9.5B	$28,000
2026	1	066-Northampton	Resurfacing	NC 35	SR 1341 (Deberrys Mill Rd.)	SR 1337 (Britton Rd.)	2.24	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$526,000
2026	1	066-Northampton	Resurfacing	NC 35	SR 1337 (Britton Rd.)	Virginia State Line	5.75	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,350,000
2026	1	066-Northampton	Resurfacing	SR 1109 (Bryantown Rd.)	SR 1108 (Chapel Hill Church Rd.)	US 258	4.44	#67 Mat Seal and 1.5" S9.5B	$1,042,000
2026	1	066-Northampton	Resurfacing	SR 1113 (Ash Town Rd.)	SR 1109 (Bryantown Rd.)	Dead End	1.49	Full Depth Patching and 1.5" S9.5B	$268,000
2026	1	066-Northampton	Resurfacing	SR 1114 (Ash Town Rd.)	SR 1113 (Ash Town Rd.)	Dead End	0.77	Full Depth Patching and 1.5" S9.5B	$139,000
2026	1	066-Northampton	Resurfacing	SR 1504 (Creeksville Rd.)	SR 1501 (Dusty Hill Rd.)	SR 1500 (Zion Church Rd.)	3.05	Full Depth Patching and 1.5" S9.5B	$645,000
2026	1	066-Northampton	Resurfacing	SR 1522 (Eagletown Rd.)	NC 305	US 258	3.47	Full Depth Patching and 1.5" S9.5B	$693,000
2026	1	066-Northampton	Resurfacing	SR 1523 (Joe Brown Rd.)	SR 1522-Eagletown Rd.	US 258	0.87	Full Depth Patching and 1.5" S9.5B	$174,000
2026	1	066-Northampton	Resurfacing	US 158 Bus. (Main St.)	US 158	US 158	0.34	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$144,000
2026	1	066-Northampton	Preservation	SR 1301 (Cornwallis St.)	US 301	NC 186	5.13	Seal - Double	$256,000
2026	1	066-Northampton	Preservation	SR 1341 (Deberry's Mill Rd)	SR 1344 (Galatia Rd.)	NC 35	5.32	Seal - Double	$266,000
2026	1	070-Pasquotank	Resurfacing	SR 1340 (Davis Rd.)	SR 1416 (Northside Rd.)	End of Maintenance	0.31	Full Depth Patching and 1.5" S9.5B	$56,000
2026	1	070-Pasquotank	Resurfacing	SR 1352 (Brothers Ln.)	End Pavement	SR 1354 (Mill Pond Rd.)	0.30	Full Depth Patching and 1.5" S9.5B	$60,000
2026	1	070-Pasquotank	Resurfacing	SR 1356 (Newland Rd.)	US 158	SR 1360 (Upriver Rd.)	1.53	Full Depth Patching and 1.5" S9.5B and Widening	$432,000
2026	1	070-Pasquotank	Resurfacing	SR 1360 (Upriver Rd.)	SR 1367	Dead End	1.01	Full Depth Patching and 1.5" S9.5B	$182,000
2026	1	070-Pasquotank	Resurfacing	SR 1361 (Stafford Rd.)	SR 1360 (Upriver Rd.)	End of Maintenance	0.39	Full Depth Patching and 1.5" S9.5B	$78,000
2026	1	070-Pasquotank	Resurfacing	SR 1363 (School House Rd.)	SR 1361 (Drive Rd.)	SR 1360 (Upriver Rd.)	0.96	Full Depth Patching and 1.5" S9.5B	$191,000
2026	1	070-Pasquotank	Resurfacing	SR 1363 (School House Rd.)	US 158	SR 1361 (Drive Rd.)	0.95	Full Depth Patching and 1.5" S9.5B	$190,000
2026	1	070-Pasquotank	Resurfacing	SR 1367 (Tadmore Rd.)	US 158	End of Pavement	0.60	Full Depth Patching and 1.5" S9.5B	$120,000
2026	1	070-Pasquotank	Preservation	SR 1270 (Small Dr.)	SR 1622 (Blimpview Dr.)	Dead End	1.24	1.25" S9.5B	$151,000
2026	1	070-Pasquotank	Preservation	SR 1506 (Maggie Ln.)	SR 1270 (Small Dr.)	SR 1509 (Broomfield Trl.)	0.41	Microsurface	$24,000
2026	1	070-Pasquotank	Preservation	SR 1507 (Courthouse Ln.)	SR 1506 (Maggie Ln.)	CDS	0.10	Microsurface	$6,000
2026	1	070-Pasquotank	Preservation	SR 1508 (Cister Chase Rd.)	SR 1506 (Maggie Ln.)	CDS	0.11	Microsurface	$7,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	1	070-Pasquotank	Preservation	SR 1509 (Broomfield Trl.)	SR 1270 (Small Dr.)	SR 1622 (Airship Dr)	0.37	1.25" S9.5B	$45,000
2026	1	070-Pasquotank	Preservation	SR 1600 (Eyrie Dr.)	SR 1270 (Small Dr.)	Dead End	0.14	Microsurface	$8,000
2026	1	070-Pasquotank	Preservation	SR 1620 (Enfield Ct.)	SR 1506 (Maggie Ln.)	Dead End	0.07	Microsurface	$5,000
2026	1	070-Pasquotank	Preservation	SR 1621 (Airship Dr.)	SR 1270 (Small Dr.)	SR 1509 (Broomfield Trl.)	0.22	1.25" S9.5B	$27,000
2026	1	070-Pasquotank	Preservation	SR 1622 (Blimpview Dr.)	SR 1270 (Small Dr.)	Dead End	0.24	1.25" S9.5B	$29,000
2026	1	070-Pasquotank	Preservation	SR 1623 (William Dr.)	SR 1270 (Small Dr.)	SR 1624 (Beverly Dr.)	0.26	1.25" S9.5B	$32,000
2026	1	070-Pasquotank	Preservation	SR 1624 (Beverly Dr.)	SR 1623 (William Dr.)	SR 1625 (Gaston Dr.)	0.12	Microsurface	$7,000
2026	1	070-Pasquotank	Preservation	SR 1625 (Gaston Dr.)	SR 1270 (Small Dr.)	SR 1624 (Beverly Dr.)	0.19	1.25" S9.5B	$24,000
2026	1	072-Perquimans	Resurfacing	SR 1101 (Bear Swamp Rd.)	RR	US 17	2.02	Full Depth Patching and 1.5" S9.5B	$403,000
2026	1	072-Perquimans	Resurfacing	SR 1101 (Bear Swamp Rd.)	Chowan Co	RR	4.04	Full Depth Patching and 1.5" S9.5B	$806,000
2026	1	072-Perquimans	Preservation	SR 1001 (Sandy Cross Rd.)	SR 1214 (Bay Branch Rd.)	NC 37	1.76	Seal - Double	$84,000
2026	1	072-Perquimans	Preservation	SR 1002 (County Line Rd.)	SR 1117 (Beech Springs Rd.)	SR 1115 (Poplar Neck Rd.)	1.74	Seal - Double	$78,000
2026	1	089-Tyrrell	Resurfacing	NC 94	SR 1102 (Jones Rd.)	SR 1103 (Burton Shell Rd)	7.03	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,350,000
2026	1	089-Tyrrell	Resurfacing	SR 1211 (Riverneck Road)	SR 1209 (Soundside Rd.)	Dead End)	1.90	Full Depth Patching and 1.5" S9.5B	$379,000
2026	1	089-Tyrrell	Preservation	SR 1113	SR 1206 (Cut Off Rd)	SR-1110 (Old Columbia Rd)	1.49	Microsurface	$98,000
2026	1	089-Tyrrell	Preservation	SR 1212 (Rhodes Rd. / Rhodes Haven Dr.)	SR 1211 (Riverneck Rd.)	Dead End	1.74	Microsurface	$103,000
2026	1	089-Tyrrell	Preservation	SR 1234 (Taylors Beach Rd.)	SR 1212 (Rhodes Rd. / Rhodes Haven Dr.)	End of Pavement	0.65	Microsurface	$39,000
2026	1	094-Washington	Resurfacing	NC 32	NC 99	Beaufort Co	6.62	Mill 1.5" and 1.5" S9.5C	$1,850,000
2026	1	094-Washington	Resurfacing	NC 45	NC 32	Bertie County	3.27	Full Depth Patching and 1.5" S9.5C	$1,050,000
2026	1	094-Washington	Resurfacing	SR 1300 (Mackeys Rd.)	NC 45	SR 1325 (E. Main St.)	2.22	Full Depth Patching and 1.5" S9.5B	$488,000
2026	1	094-Washington	Resurfacing	SR 1322 (Mackeys Ferry Rd.)	NC 45	Dead End	0.47	Full Depth Patching and 1.5" S9.5B	$94,000
2026	1	094-Washington	Preservation	SR 1113 (Old Roper Loop)	NC 45	NC 45	0.42	Microsurface	$25,000
2026	1	094-Washington	Preservation	SR 1184 (Sitterson Loop)	NC 32	NC 32	0.17	Microsurface	$10,000
2026	1	094-Washington	Preservation	SR 1221 (Gee St.)	NC 45	End Of Pavement	0.10	Microsurface	$6,000
2026	1	094-Washington	Preservation	SR 1335 (Wilson St.)	US 64	Springwood Dr.	2.16	Microsurface	$178,000
2026	1	094-Washington	Preservation	SR 1342 (Rankin Rd.)	US 64	SR 1325 (East Main Street)	0.61	Microsurface	$43,000
2026	2	007-Beaufort	Resurfacing	SR 1328	SR 1327	NC 32	0.92	1.5" S9.5B	$160,000
2026	2	007-Beaufort	Resurfacing	SR 1530	RR TRACKS	SR 1528	0.92	1.5" S9.5B	$184,000
2026	2	007-Beaufort	Resurfacing	SR 1531	SR 1530	DEAD END	0.13	1.5" S9.5B	$26,600
2026	2	007-Beaufort	Resurfacing	SR 1700	US 264	SR 1709	2.83	1.5" S9.5B	$560,000
2026	2	007-Beaufort	Resurfacing	SR 1708	US 264 BUS	END MAINTENANCE	0.30	1.25" S9.5B	$60,000
2026	2	007-Beaufort	Resurfacing	SR 1709	US 264	SR 1700	0.90	1.5" S9.5B	$200,000
2026	2	007-Beaufort	Resurfacing	SR 1710	US 264	SR 1779	1.75	1.5" S9.5B	$350,000
2026	2	007-Beaufort	Resurfacing	SR 1711	US 264	DEAD END	0.80	1.5" S9.5B	$160,000
2026	2	007-Beaufort	Resurfacing	SR 1712	US 264	DEAD END	2.34	1.5" S9.5B	$468,000
2026	2	007-Beaufort	Resurfacing	SR 1712	US 264	DEAD END	0.07	1.5" S9.5B	$14,000
2026	2	007-Beaufort	Resurfacing	SR 1730	SR 1725	DEAD END	1.90	1.5" S9.5B	$380,000
2026	2	007-Beaufort	Resurfacing	SR 1741	SR 1742	BEGIN C&G	1.41	1.5" S9.5B and Widen	$420,000
2026	2	007-Beaufort	Resurfacing	SR 1741	BEGIN C&G	SR 1756	0.33	Mill 1.5" and 1.5" S9.5B	$107,250
2026	2	007-Beaufort	Resurfacing	SR 1756	END C&G	NC 92	0.22	1.5" S9.5B	$44,000
2026	2	007-Beaufort	Resurfacing	SR 1756	SR 1741	END C&G	0.17	Mill 1.5" and 1.5" S9.5B	$55,250
2026	2	007-Beaufort	Resurfacing	SR 1779	SR 1710	DEAD END	0.56	1.25" S9.5B	$112,000
2026	2	007-Beaufort	Resurfacing	SR 1780	SR 1779	END MAINTENANCE	0.05	1.5" S9.5B	$10,000
2026	2	016-Carteret	Resurfacing	SR 1168	SR 1165	NC 101	0.29	1.5" S9.5B	$58,000
2026	2	016-Carteret	Resurfacing	SR 1169	NC 101	END MAINTENANCE	0.50	1.5" S9.5B	$100,000
2026	2	016-Carteret	Resurfacing	SR 1230	NC 101	END MAINTENANCE	0.32	1.5" S9.5B	$63,000
2026	2	016-Carteret	Resurfacing	SR 1231	SR 1230	SR 1232	0.09	1.5" S9.5B	$17,000
2026	2	016-Carteret	Resurfacing	SR 1232	SR 1231	END MAINTENANCE	0.10	1.5" S9.5B	$20,000
2026	2	016-Carteret	Resurfacing	SR 1246	NC 101	DEAD END	0.36	1.5" S9.5B	$72,000
2026	2	016-Carteret	Resurfacing	SR 1301	US 70	SR 1302	0.43	1.5" S9.5B	$86,400
2026	2	016-Carteret	Resurfacing	SR 1302	BEGIN MAINTENANCE	END MAINTENANCE	0.20	1.5" S9.5B	$40,000
2026	2	016-Carteret	Resurfacing	SR 1303	SR 1493	END MAINTENANCE	0.89	1.5" S9.5B	$178,400
2026	2	016-Carteret	Resurfacing	SR 1304	US 70	END MAINTENANCE	0.83	1.5" S9.5B	$166,800
2026	2	016-Carteret	Resurfacing	SR 1426	SR 1303	SR 1427	0.15	1.5" S9.5B	$29,000
2026	2	016-Carteret	Resurfacing	SR 1427	SR 1480	DEAD END	0.38	1.5" S9.5B	$75,200
2026	2	016-Carteret	Resurfacing	SR 1428	SR 1303	SR 1427	0.13	1.5" S9.5B	$25,200
2026	2	016-Carteret	Resurfacing	SR 1429	US 70	SR 1430	0.40	1.5" S9.5B	$80,600
2026	2	016-Carteret	Resurfacing	SR 1430	SR 1429	SR 1431	0.10	1.5" S9.5B	$20,600
2026	2	016-Carteret	Resurfacing	SR 1431	SR 1430	SR 1432	0.07	1.5" S9.5B	$13,800

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	2	016-Carteret	Resurfacing	SR 1432	SR 1429	SR 1431	0.13	1.5" S9.5B	$25,200
2026	2	016-Carteret	Resurfacing	SR 1433	SR 1429	SR 1458	0.12	1.5" S9.5B	$23,000
2026	2	016-Carteret	Resurfacing	SR 1434	SR 1301	DEAD END	0.28	1.5" S9.5B	$55,000
2026	2	016-Carteret	Resurfacing	SR 1446	NC 101	END MAINTENANCE	0.49	1.5" S9.5B	$97,200
2026	2	016-Carteret	Resurfacing	SR 1449	US 70	DEAD END	0.24	1.5" S9.5B	$48,000
2026	2	016-Carteret	Resurfacing	SR 1458	SR 1429	SR 1433	0.17	1.5" S9.5B	$34,000
2026	2	016-Carteret	Resurfacing	SR 1459	US 70	DEAD END	0.36	2.0" S9.5C	$50,000
2026	2	016-Carteret	Resurfacing	SR 1460	SR 1446	DEAD END	0.05	1.5" S9.5B	$10,000
2026	2	016-Carteret	Resurfacing	SR 1462	SR 1301	DEAD END	0.11	1.5" S9.5B	$22,000
2026	2	016-Carteret	Resurfacing	SR 1464	US 70	DEAD END	0.38	1.5" S9.5B	$76,800
2026	2	016-Carteret	Resurfacing	SR 1468	SR 1464	DEAD END	0.08	1.5" S9.5B	$16,000
2026	2	016-Carteret	Resurfacing	SR 1479	SR 1426	SR 1480	0.16	1.5" S9.5B	$32,600
2026	2	016-Carteret	Resurfacing	SR 1480	SR 1479	SR 1427	0.08	1.5" S9.5B	$16,600
2026	2	016-Carteret	Resurfacing	SR 1631	NC 101	SR 1775	0.38	1.5" S9.5B	$76,000
2026	2	016-Carteret	Resurfacing	SR 1644	NC 101	END MAINTENANCE	0.15	1.5" S9.5B	$30,000
2026	2	016-Carteret	Resurfacing	SR 1683	SR 1125	END MAINTENANCE	0.42	2.0" S9.5C	$70,000
2026	2	016-Carteret	Resurfacing	SR 1775	CUL DE SAC	CUL DE SAC	0.06	1.5" S9.5B	$10,000
2026	2	016-Carteret	Preservation	SR 1459	US 70	DEAD END	0.36	FDR and Double Seal	$307,192
2026	2	016-Carteret	Preservation	SR 1683	SR 1125	SR 1786	0.42	FDR and Double Seal	$370,000
2026	2	025-Craven	Resurfacing	NC 55	BLUEBERRY LANE	PAMLICO COUNTY	1.98	Mill 1.5" and 2.0" S9.5C	$1,500,000
2026	2	025-Craven	Resurfacing	SR 1131	US 70	DEAD END	0.60	1.5" S9.5B	$120,000
2026	2	025-Craven	Resurfacing	SR 1169	SR 1131	DEAD END	0.33	1.5" S9.5B	$66,200
2026	2	025-Craven	Resurfacing	SR 1214	SR 1213	US 17	1.10	1.5" S9.5B	$220,000
2026	2	025-Craven	Resurfacing	SR 1257	SR 1005	SR 1256	1.15	1.5" S9.5B	$230,000
2026	2	025-Craven	Resurfacing	SR 1290	SR 1278	SR 1216	0.36	1.5" S9.5B	$72,000
2026	2	025-Craven	Resurfacing	SR 1301	SR 1290	SR 1302	0.18	1.5" S9.5B	$36,000
2026	2	025-Craven	Resurfacing	SR 1302	SR 1301	SR 1303	0.08	1.5" S9.5B	$16,000
2026	2	025-Craven	Resurfacing	SR 1307	US 17	SHORE LINE	1.12	1.5" S9.5B	$224,000
2026	2	025-Craven	Resurfacing	SR 1310	SR 1200	SR 1311	0.24	1.5" S9.5B	$48,000
2026	2	025-Craven	Resurfacing	SR 1311	SR 1310	SR 1312	0.09	1.5" S9.5B	$18,000
2026	2	025-Craven	Resurfacing	SR 1312	SR 1311	SR 1313	0.26	1.5" S9.5B	$52,000
2026	2	025-Craven	Resurfacing	SR 1313	BEGIN MAINTENANCE	SR 1310	0.10	1.5" S9.5B	$20,000
2026	2	025-Craven	Resurfacing	SR 1339	SR 1338	DEAD END	0.03	1.5" S9.5B	$6,000
2026	2	025-Craven	Resurfacing	SR 1422	SR 1421	SR 1423	1.20	1.5" S9.5B	$240,000
2026	2	025-Craven	Resurfacing	SR 1498	SR 1401	DEAD END	0.23	1.5" S9.5B	$46,000
2026	2	025-Craven	Resurfacing	SR 1502	SR 1401	DEAD END	0.17	1.5" S9.5B	$34,000
2026	2	025-Craven	Resurfacing	SR 1506	SR 1401	END MAINTENANCE	0.09	1.5" S9.5B	$18,000
2026	2	025-Craven	Resurfacing	SR 1507	SR 1506	SR 1502	0.25	1.5" S9.5B	$50,000
2026	2	025-Craven	Resurfacing	SR 1620	SR 1611	SR 1615	1.03	1.5" S9.5B	$205,200
2026	2	025-Craven	Resurfacing	US 70 EB	MC COTTER ROAD	CARTERET COUNTY	1.01	Mill 1.5" and 1.5" S9.5C	$420,000
2026	2	025-Craven	Resurfacing	US 70 EB	SLOCUM GATE PROJECT LIMITS	MC COTTER ROAD	4.98	Mill 1.5" and 1.5" S9.5C	$1,925,000
2026	2	025-Craven	Resurfacing	US 70 WB	CARTERET COUNTY	MC COTTER ROAD	1.02	Mill 1.5" and 1.5" S9.5C	$420,000
2026	2	025-Craven	Resurfacing	US 70 WB	MC COTTER ROAD	SLOCUM GATE PROJECT LIMITS	4.98	Mill 1.5" and 1.5" S9.5C	$1,925,000
2026	2	025-Craven	Rehabilitation	SR 1303	SR 1290	SR 1302	0.23	2.5" I19.0C and 1.5" S9.5B	$97,750
2026	2	025-Craven	Rehabilitation	SR 1338	SR 1299	SR 1216	0.66	2.5" I19.0C and 1.5" S9.5B	$282,200
2026	2	025-Craven	Rehabilitation	SR 1626	SR 1003	SR 1611	2.39	2.5" I19.0C and 1.5" S9.5B	$1,014,900
2026	2	025-Craven	Preservation	SR 1441	SR 1440	SR 1440	1.30	Seal - Double	$65,000
2026	2	040-Greene	Resurfacing	SR 1110	SR 1109	NC 58	1.60	1.5" S9.5B	$320,000
2026	2	040-Greene	Resurfacing	SR 1335	NC 123	SR 1336	6.57	1.5" S9.5B	$1,314,000
2026	2	040-Greene	Resurfacing	SR 1336	SR 1335	NC 903	2.39	1.5" S9.5B	$478,000
2026	2	040-Greene	Preservation	SR 1102	NC 58	LENOIR CO	4.95	Seal - Double	$247,250
2026	2	040-Greene	Preservation	SR 1103	US 258	SR 1104	2.10	Seal - Double	$104,850
2026	2	040-Greene	Preservation	SR 1147	SR 1146	NC 903	1.54	Seal - Double	$77,000
2026	2	040-Greene	Preservation	SR 1337	SR 1336	NC 903	1.93	Seal - Double	$96,500
2026	2	040-Greene	Preservation	SR 1355	NC 123	SR 1335	0.84	Seal - Double	$42,000
2026	2	040-Greene	Preservation	SR 1405	SR 1400	SR 1004	3.50	Seal - Double	$175,000
2026	2	040-Greene	Preservation	SR 1413	SR 1400	NC 903	3.01	Seal - Double	$150,450
2026	2	052-Jones	Resurfacing	SR 1146	LENOIR CO	ONSLOW CO	4.16	1.5" S9.5B	$830,000
2026	2	052-Jones	Resurfacing	SR 1148	DUPLIN CO	LENOIR CO	1.21	1.5" S9.5B	$240,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	2	052-Jones	Preservation	SR 1129	SR 1300	NC 41	5.79	Seal - Double	$289,000
2026	2	052-Jones	Preservation	SR 1130	SR 1129	LENOIR COUNTY	9.01	Seal - Double	$450,650
2026	2	052-Jones	Preservation	SR 1153	SR 1130	LENOIR COUNTY	2.19	Seal - Double	$109,350
2026	2	052-Jones	Preservation	SR 1154	SR 1153	NS-99960	0.70	Seal - Double	$35,000
2026	2	052-Jones	Preservation	SR 1158	SR 1157	NC 58	2.17	Seal - Double	$108,400
2026	2	052-Jones	Preservation	SR 1159	SR 1301 + 1.29 miles	SR 1158	0.99	Seal - Double	$47,500
2026	2	054-Lenoir	Resurfacing	SR 1102	NC 241	DUPLIN COUNTY	1.78	1.5" S9.5B	$356,000
2026	2	054-Lenoir	Resurfacing	SR 1103	JONES COUNTY	BEGIN C&G	3.17	1.5" S9.5B	$634,600
2026	2	054-Lenoir	Resurfacing	SR 1109	SR 1103	SR 1113	1.11	1.5" S9.5B	$222,000
2026	2	054-Lenoir	Resurfacing	SR 1710	SR 1711	SR 1004	0.74	1.5" S9.5B	$148,000
2026	2	054-Lenoir	Resurfacing	SR 1711	SR 1004	SR 1091	1.90	1.5" S9.5B	$380,000
2026	2	054-Lenoir	Rehabilitation	SR 1709	NC 11	SR 1004	4.34	2.5" I19.0B and 1.5" S9.5B and Widen	$2,247,000
2026	2	054-Lenoir	Preservation	SR 1342	NC 11	NC 58	3.80	Seal - Double	$190,200
2026	2	054-Lenoir	Preservation	SR 1343	NC 11	SR 1342	0.61	Seal - Double	$30,500
2026	2	054-Lenoir	Preservation	SR 1504	NC 903	SR 1001	3.29	Seal - Double	$164,450
2026	2	054-Lenoir	Preservation	SR 1700	NC 58	SR 1004	3.69	Seal - Double	$184,600
2026	2	054-Lenoir	Preservation	SR 1701	SR 1700	GREENE COUNTY	0.83	Seal - Double	$41,500
2026	2	054-Lenoir	Preservation	SR 1729	SR 1703	SR 1004	1.31	Seal - Double	$65,550
2026	2	054-Lenoir	Preservation	SR 1729	SR 1703	SR 1004	0.38	Seal - Double	$18,950
2026	2	054-Lenoir	Preservation	SR 1810	NC 55	MCCASKILL	2.60	Seal - Double	$129,950
2026	2	054-Lenoir	Preservation	SR 1811	SR 1810	NC 11	1.48	Seal - Double	$74,000
2026	2	054-Lenoir	Preservation	SR 1812	SR 1811	CARR LYLES	0.94	Seal - Double	$47,000
2026	2	054-Lenoir	Preservation	SR 1906	SR 1342	US 258	1.67	Seal - Double	$83,500
2026	2	054-Lenoir	Preservation	SR 1907	US 258	US 258	1.87	Seal - Double	$93,500
2026	2	054-Lenoir	Preservation	SR 1911	SR 1912	SR 1909	2.29	Seal - Double	$114,500
2026	2	054-Lenoir	Preservation	SR 1923	JONES COUNTY	US 258	3.47	Seal - Double	$173,350
2026	2	054-Lenoir	Preservation	SR 1924	SR 1925	SR 1923	3.57	Seal - Double	$178,500
2026	2	054-Lenoir	Preservation	SR 1926	SR 1925	SR 1923	3.78	Seal - Double	$189,000
2026	2	069-Pamlico	Resurfacing	NC 55	CRAVEN COUNTY	NC 306	7.83	Mill 1.5" and 1.5" S9.5C	$5,400,000
2026	2	069-Pamlico	Resurfacing	SR 1311	SR 1005	END MAINTENANCE	1.29	1.5" S9.5B	$257,000
2026	2	069-Pamlico	Resurfacing	SR 1326	SR 1327	DEAD END	0.33	1.5" S9.5B	$70,000
2026	2	069-Pamlico	Resurfacing	SR 1328	SR 1327	DEAD END	1.31	1.5" S9.5B	$230,000
2026	2	069-Pamlico	Resurfacing	SR 1361	SR 1311	CUL-DE-SAC	0.43	1.5" S9.5B	$85,800
2026	2	069-Pamlico	Resurfacing	SR 1362	SR 1361	CUL-DE-SAC	0.27	1.5" S9.5B	$54,200
2026	2	069-Pamlico	Resurfacing	SR 1369	SR 1302	END MAINTENANCE	0.58	1.5" S9.5B	$116,800
2026	2	069-Pamlico	Resurfacing	SR 1370	SR 1361	SR 1362	0.28	1.5" S9.5B	$55,200
2026	2	069-Pamlico	Resurfacing	SR 1373	SR 1311	CUL-DE-SAC	0.34	1.5" S9.5B	$68,200
2026	2	069-Pamlico	Resurfacing	SR 1382	SR 1311	SR 1388	0.43	1.5" S9.5B	$85,600
2026	2	069-Pamlico	Resurfacing	SR 1385	BEGIN MAINTENANCE	CUL-DE-SAC	0.51	1.5" S9.5B	$102,000
2026	2	069-Pamlico	Resurfacing	SR 1388	CUL-DE-SAC	END MAINTENANCE	0.18	1.5" S9.5B	$36,800
2026	2	069-Pamlico	Resurfacing	SR 1389	SR 1388	CUL-DE-SAC	0.04	1.5" S9.5B	$8,800
2026	2	069-Pamlico	Rehabilitation	SR 1324	NC 55	SR 1327	9.17	2.5" I19.0B and 1.5" S9.5B and Widen	$3,800,000
2026	2	069-Pamlico	Rehabilitation	SR 1325	SR 1324	SR 1326	3.77	2.5" I19.0B and 1.5" S9.5B and Widen	$1,500,000
2026	2	069-Pamlico	Rehabilitation	SR 1327	SR 1325	SR 1326	2.79	2.5" I19.0B and 1.5" S9.5B and Widen	$1,200,000
2026	2	074-Pitt	Resurfacing	NC 121	US 258 BUSINESS	BRIDGE 446	1.07	Mill 1.75" and 1.75" S9.5B	$540,000
2026	2	074-Pitt	Resurfacing	SR 1108	SR 1900	SR 1110	2.29	1.5" S9.5B and Widen	$687,900
2026	2	074-Pitt	Resurfacing	SR 1216	SR 1217	SR 1206	0.71	1.5" S9.5B	$141,600
2026	2	074-Pitt	Resurfacing	SR 1217	SR 1218	SR 1138	2.64	1.5" S9.5B	$527,800
2026	2	074-Pitt	Resurfacing	SR 1258	SR 1247	NC 121	1.07	1.5" S9.5B	$214,000
2026	2	074-Pitt	Resurfacing	SR 1263	SR 1206	SR 1216	0.21	1.5" S9.5B	$41,000
2026	2	074-Pitt	Resurfacing	SR 1270	SR 1206	END PAVEMENT	0.10	1.5" S9.5B	$19,600
2026	2	074-Pitt	Resurfacing	SR 1725	PAVEMENT JOINT	NC 102	6.25	1.5" S9.5B	$1,250,000
2026	2	074-Pitt	Resurfacing	SR 1755	NC 43	NC 33	11.36	2.0" S9.5C	$2,800,000
2026	2	074-Pitt	Resurfacing	SR 1900	SR 1110	NC 102	4.85	1.5" S9.5B and Widen	$1,455,600
2026	2	074-Pitt	Resurfacing	US 258 BUSINESS	US 258	NC 121	1.17	Mill 1.5" and 1.5" S9.5B	$560,976
2026	2	074-Pitt	Preservation	SR 1755	NC 43	NC 33	11.36	FDR and Double Seal	$4,000,000
2026	2	074-Pitt	Preservation	SR 1912	SR 1110	SR 1911	0.73	Seal - Double	$36,350
2026	2	074-Pitt	Preservation	SR 1915	SR 2227	CRAVEN COUNTY	1.02	Seal - Double	$51,100
2026	2	074-Pitt	Preservation	SR 1916	SR 1915	NC 118	1.01	Seal - Double	$50,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	3	010-Brunswick	Resurfacing	NC 133	Rabon Way - 0.64mi	Morecamble Blvd + 0.07mi	4.00	1.5" S9.5C	$1,404,000
2026	3	010-Brunswick	Resurfacing	NC 179	SR 1163	US 17BUS	2.31	1.5" S9.5C	$581,607
2026	3	010-Brunswick	Resurfacing	SR 1120	SR 1122	NC 130	2.02	Full Depth Patching and 1.5" S9.5B and Widening	$556,325
2026	3	010-Brunswick	Resurfacing	SR 1124	SR 1119	NC 130	2.85	Full Depth Patching and 1.5" S9.5B and Widening	$784,850
2026	3	010-Brunswick	Resurfacing	SR 1125	SR 1115	SR 1130	2.84	1.5" S9.5B and Widen	$1,092,630
2026	3	010-Brunswick	Resurfacing	SR 1147	SR 1151	NC 179	1.47	Full Depth Patching and 1.5" S9.5B and Widening	$404,250
2026	3	010-Brunswick	Resurfacing	SR 1151	SR 1145	DEAD END	1.31	Full Depth Patching and 1.5" S9.5B and Widening	$360,250
2026	3	010-Brunswick	Resurfacing	SR 1152	NC 179	S 1145	1.97	Full Depth Patching and 1.5" S9.5B and Widening	$759,605
2026	3	010-Brunswick	Resurfacing	SR 1173	NC 179	US 17BUS	0.27	1.5" S9.5C	$95,500
2026	3	010-Brunswick	Resurfacing	SR 1181	SR 1125	SR 1124	1.21	Full Depth Patching and 1.5" S9.5B and Widening	$332,750
2026	3	010-Brunswick	Resurfacing	SR 1300	SR 1303	US 17	2.33	Full Depth Patching and 1.5" S9.5B	$640,750
2026	3	010-Brunswick	Resurfacing	SR 1313	NC 904	SR 1315	0.98	Full Depth Patching and 1.5" S9.5B	$251,808
2026	3	010-Brunswick	Resurfacing	SR 1340	SR 1342	NC 211	5.93	Full Depth Patching and 1.5" S9.5B	$1,374,000
2026	3	010-Brunswick	Resurfacing	SR 1502	US 17	SR 1501	2.22	Full Depth Patching and 1.25" S9.5B	$225,600
2026	3	010-Brunswick	Resurfacing	SR 1522	US 17	END PVMT	0.80	Full Depth Patching and 1.5" S9.5B and Widening	$273,735
2026	3	010-Brunswick	Preservation	SR 1155	SR 1154	NC 179	0.72	1.25" S9.5B	$79,530
2026	3	010-Brunswick	Preservation	SR 1157	NC 179	SR 1274	0.70	1.25" S9.5B	$76,780
2026	3	010-Brunswick	Preservation	SR 1158	SR 1157	Dead End	0.09	1.25" S9.5B	$5,000
2026	3	010-Brunswick	Preservation	SR 1159	NC 179	DEAD END	0.40	1.25" S9.5B	$43,560
2026	3	010-Brunswick	Preservation	SR 1171	NC 179	DEAD END	0.46	1.25" S9.5B	$50,050
2026	3	010-Brunswick	Preservation	SR 1183	NC 904	DEAD END	0.54	1.25" S9.5B	$58,850
2026	3	010-Brunswick	Preservation	SR 1185	NC 904	DEAD END	0.46	1.25" S9.5B	$50,160
2026	3	010-Brunswick	Preservation	SR 1212	NC 179	DEAD END	0.15	1.25" S9.5B	$16,390
2026	3	010-Brunswick	Preservation	SR 1213	SR 1159	SR 1212	0.13	1.25" S9.5B	$13,860
2026	3	010-Brunswick	Preservation	SR 1232	NC 179	DEAD END	0.57	1.25" S9.5B	$62,810
2026	3	010-Brunswick	Preservation	SR 1247	NC 904	DEAD END	0.56	1.25" S9.5B	$61,930
2026	3	010-Brunswick	Preservation	SR 1257	NC 904	DEAD END	0.52	1.25" S9.5B	$56,870
2026	3	010-Brunswick	Preservation	SR 1258	SR 1257	SR 1259	0.06	1.25" S9.5B	$6,600
2026	3	010-Brunswick	Preservation	SR 1259	NC 904	DEAD END	0.53	1.25" S9.5B	$57,970
2026	3	010-Brunswick	Preservation	SR 1260	NC 904	DEAD END	0.58	1.25" S9.5B	$63,360
2026	3	010-Brunswick	Preservation	SR 1294	NC 904	END MAINT	0.15	1.25" S9.5B	$16,280
2026	3	010-Brunswick	Preservation	SR 1295	SR 1155	DEAD END	0.31	1.25" S9.5B	$34,100
2026	3	010-Brunswick	Preservation	SR 1296	SR 1295	SR 1297	0.05	1.25" S9.5B	$5,500
2026	3	010-Brunswick	Preservation	SR 1297	SR 1155	DEAD END	0.31	1.25" S9.5B	$34,320
2026	3	010-Brunswick	Preservation	SR 1403	US 17 BUS.	DEAD END	0.49	1.25" S9.5B	$54,230
2026	3	010-Brunswick	Preservation	SR 1449	SR 1402	DEAD END	0.42	1.25" S9.5B	$46,200
2026	3	010-Brunswick	Preservation	SR 1456	SR 1426	DEAD END	0.21	1.25" S9.5B	$22,880
2026	3	010-Brunswick	Preservation	SR 1493	SR 1402	DEAD END	0.28	1.25" S9.5B	$30,800
2026	3	010-Brunswick	Preservation	SR 1534	SR 1528	EOM	0.73	1.25" S9.5B	$80,300
2026	3	010-Brunswick	Preservation	SR 1572	SR 1506	EOM	0.22	1.25" S9.5B	$24,200
2026	3	031-Duplin	Resurfacing	NC 41	SR 1964 bridge approach	SR 1966	4.96	Mill 1.5" and 1.5" S9.5C	$1,598,215
2026	3	031-Duplin	Resurfacing	NC 41	SR 1966	NC 24	3.50	Mill 1.5" and 1.5" S9.5C	$1,125,823
2026	3	031-Duplin	Resurfacing	SR 1105	SR 1114	SR 1104	2.44	#67 Mat Seal and 1.5" S9.5B	$670,450
2026	3	031-Duplin	Resurfacing	SR 1123	SR 1103	SR 1122	1.62	1.5" S9.5B	$445,500
2026	3	031-Duplin	Resurfacing	SR 1162	SR 1172	US 117	0.17	1.5" S9.5B	$46,750
2026	3	031-Duplin	Resurfacing	SR 1179	SR 1172	SR 1162	0.18	1.5" S9.5B	$40,000
2026	3	031-Duplin	Resurfacing	SR 1320	US 117	NC 403	1.75	1.5" S9.5B	$480,425
2026	3	031-Duplin	Resurfacing	SR 1372	SR 1559	SR 1004	0.70	1.5" S9.5B	$192,500
2026	3	031-Duplin	Resurfacing	SR 1378	NC 11	SR 1380	2.74	1.5" S9.5B	$753,500
2026	3	031-Duplin	Resurfacing	SR 1546	NC 111	SR 1555	5.38	1.5" S9.5B	$968,000
2026	3	031-Duplin	Resurfacing	SR 1711	NC 241	NC 41	3.63	1.5" S9.5B	$998,250
2026	3	031-Duplin	Resurfacing	SR 1824	SR 1715	SR 1715	0.83	1.5" S9.5B	$228,250
2026	3	031-Duplin	Resurfacing	SR 1909	SR 1912	NC 903	1.63	1.5" S9.5B	$448,250
2026	3	031-Duplin	Resurfacing	SR 1922	NC 11	SR 1909	2.27	1.5" S9.5B	$622,875
2026	3	031-Duplin	Resurfacing	US 421	Sampson County	Sampson County	0.21	1.5" S9.5C	$79,380
2026	3	031-Duplin	Preservation	SR 1112	SR 1105	SR 1192	1.18	Seal - Double and Fog Seal	$106,200
2026	3	031-Duplin	Preservation	SR 1150	US 117	SR 1101	2.27	Crack Seal	$12,000
2026	3	031-Duplin	Preservation	SR 1301	SR 1377	SR 1398	1.41	Patching	$150,900
2026	3	031-Duplin	Preservation	SR 1301	SR 1351	SR 1305	1.03	Patching	$175,400

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	3	031-Duplin	Preservation	SR 1311	SR 1006	SR 1302	1.61	Patching	$313,950
2026	3	031-Duplin	Preservation	SR 1345	Begin Maint	NC 24 Bus	0.22	1.0" S4.75A	$42,900
2026	3	031-Duplin	Preservation	SR 1416	SR 1345	Dead End	0.13	1.0" S4.75A	$30,000
2026	3	031-Duplin	Preservation	SR 1561	SR 1004	SR 1505	0.60	Seal - Double and Fog Seal	$54,000
2026	3	031-Duplin	Preservation	SR 1741	NC 41	Deer Run	0.09	1.0" Sand Asphalt	$17,550
2026	3	031-Duplin	Preservation	SR 1973	SR 1974	Dead End	0.51	Seal - Double and Fog Seal	$45,900
2026	3	031-Duplin	Preservation	SR 1975	SR 1974	SR 1827	0.93	Seal - Double and Fog Seal	$83,700
2026	3	065-New Hanover	Resurfacing	NC 133	SR 1310	SR 1332	3.71	1.5" S9.5C	$1,202,364
2026	3	065-New Hanover	Resurfacing	SR 1140	US 421	End Maintenance	0.35	Full Depth Patching and 1.5" S9.5C	$113,000
2026	3	065-New Hanover	Resurfacing	SR 1216	US 17 Bus	SR 1371	0.21	Mill 1.5" and 1.5" S9.5B	$33,000
2026	3	065-New Hanover	Resurfacing	SR 1217	US 17 Bus	SR 1371	0.23	Mill 1.5" and 1.5" S9.5B	$44,000
2026	3	065-New Hanover	Resurfacing	SR 1301	SR 1217	US 17 Bus	2.10	Mill 1.5" and 1.5" S9.5C	$500,000
2026	3	065-New Hanover	Resurfacing	SR 1302	US 17 Bus	US 74 + 0.12	1.70	Mill 1.5" and 1.5" S9.5C	$734,000
2026	3	065-New Hanover	Resurfacing	SR 1322	SR 1175	US 117	0.44	Mill 1.5" and 1.5" S9.5C	$202,000
2026	3	065-New Hanover	Resurfacing	SR 1322	US 117	SR 2234	2.55	Mill 1.5" and 1.5" S9.5B	$757,000
2026	3	065-New Hanover	Resurfacing	SR 1363	US 17	SR 1393	0.08	Full Depth Patching and 1.25" S9.5B	$20,000
2026	3	065-New Hanover	Resurfacing	SR 1371	SR 1216	SR 1217	0.08	Mill 1.5" and 1.5" S9.5B	$28,000
2026	3	065-New Hanover	Resurfacing	SR 1492	NA	SR 1688	1.75	Full Depth Patching and 1.5" S9.5B	$473,000
2026	3	065-New Hanover	Resurfacing	SR 1520	SR 1492	SR 1520	0.36	1.5" S9.5B	$100,000
2026	3	065-New Hanover	Resurfacing	SR 1527	US 421	Dead End	0.56	Mill 1.5" and 1.5" S9.5B	$151,000
2026	3	065-New Hanover	Resurfacing	SR 2117	SR 2711	SR 2633	1.13	Mill 1.25" and 1.25" S9.5B	$274,000
2026	3	065-New Hanover	Resurfacing	SR 2290	US 17	End Maintenance	0.49	Full Depth Patching and 1.25" S9.5B	$134,750
2026	3	065-New Hanover	Resurfacing	SR 2617	SR 1322	Cul-De-Sac	0.15	Full Depth Patching and 1.25" S9.5B	$41,000
2026	3	065-New Hanover	Resurfacing	SR 2782	US 76	US 74	0.87	Full Depth Patching and 1.5" S9.5C	$704,000
2026	3	065-New Hanover	Resurfacing	SR 3306	CDS	CDS	0.13	1.5" S9.5B	$50,000
2026	3	065-New Hanover	Resurfacing	SR 3307	US 117	SR 3306	0.03	1.5" S9.5B	$10,000
2026	3	065-New Hanover	Resurfacing	US 117	I-40 Ramps	Pender Line	5.91	1.5" S9.5C	$2,313,000
2026	3	065-New Hanover	Resurfacing	US 117	Entrance of Roundabout	Exit of Roundabout	0.01	1.5" S9.5C	$5,500
2026	3	065-New Hanover	Resurfacing	US 117 S	Begin divided	Gordon Rd	0.88	1.5" S9.5C	$533,000
2026	3	065-New Hanover	Resurfacing	US 117 S	Entrance of Roundabout	Exit of Roundabout	0.27	1.5" S9.5C	$106,500
2026	3	065-New Hanover	Preservation	SR 1209	RANDALL PARKWAY (CITY STREET)	US 76	0.86	Microsurface	$71,000
2026	3	065-New Hanover	Preservation	SR 1209	US 76	RANDALL PARKWAY (CITY STREET)	0.85	Microsurface	$71,000
2026	3	065-New Hanover	Preservation	SR 1216	US 76	US 17 + 1.198	1.29	Microsurface	$97,000
2026	3	065-New Hanover	Preservation	SR 1216	Savanah	US 117	1.08	Microsurface	$85,000
2026	3	065-New Hanover	Preservation	SR 1217	US 117	US 117 + 1.068 mile	1.08	Microsurface	$84,000
2026	3	065-New Hanover	Preservation	SR 1217	Savanah	US 17	1.20	Microsurface	$92,000
2026	3	065-New Hanover	Preservation	SR 1345	US 17	US 17	0.56	.75" Sand Asphalt	$45,000
2026	3	065-New Hanover	Preservation	SR 1688	SR 1492	SR 1643	0.28	1.25" S9.5B	$20,000
2026	3	065-New Hanover	Preservation	SR 1704	SR 1492	NC 132 S	1.21	1.0" S4.75A	$95,000
2026	3	065-New Hanover	Preservation	SR 1707	SR 1706	CDS	0.05	1.25" S9.5B	$4,000
2026	3	065-New Hanover	Preservation	SR 1719	SR 1688	CDS	0.13	1.25" S9.5B	$9,000
2026	3	065-New Hanover	Preservation	SR 1721	SR 1720	CDS	0.07	1.25" S9.5B	$7,000
2026	3	065-New Hanover	Preservation	SR 2146	SR 1345	END MAINT	0.29	.75" Sand Asphalt	$23,000
2026	3	065-New Hanover	Preservation	SR 2147	SR 2146	END MAINT	0.12	.75" Sand Asphalt	$10,000
2026	3	065-New Hanover	Preservation	SR 2535	SR 1720	CDS	0.06	1.25" S9.5B	$4,000
2026	3	065-New Hanover	Preservation	SR 2536	SR 1720	CDS	0.08	1.25" S9.5B	$6,000
2026	3	065-New Hanover	Preservation	SR 2537	SR 1720	CDS	0.06	1.25" S9.5B	$4,000
2026	3	065-New Hanover	Preservation	SR 2573	NC 132	SR 1492	1.17	1.0" S4.75A	$112,000
2026	3	065-New Hanover	Preservation	SR 2574	SR 2573	CDS	0.03	1.0" S4.75A	$2,000
2026	3	065-New Hanover	Preservation	SR 2575	SR 2573	CDS	0.03	1.0" S4.75A	$2,000
2026	3	065-New Hanover	Preservation	SR 2576	SR 2574	CDS	0.05	1.0" S4.75A	$4,000
2026	3	065-New Hanover	Preservation	SR 2577	SR 2575	CDS	0.07	1.0" S4.75A	$5,000
2026	3	065-New Hanover	Preservation	SR 2578	SR 2573	SR 1704	0.13	1.0" S4.75A	$10,000
2026	3	065-New Hanover	Preservation	SR 2579	CDS	CDS	0.12	1.0" S4.75A	$9,000
2026	3	065-New Hanover	Preservation	SR 2580	SR 2579	CDS	0.02	1.0" S4.75A	$1,000
2026	3	065-New Hanover	Preservation	SR 2582	SR 2573	SR 1704	0.07	1.0" S4.75A	$6,000
2026	3	065-New Hanover	Preservation	SR 2631	SR 2632	CUL-DE-SAC	0.19	1.0" S4.75A	$16,000
2026	3	065-New Hanover	Preservation	SR 2632	CUL-DE-SAC	CUL-DE-SAC	0.32	1.0" S4.75A	$21,000
2026	3	065-New Hanover	Preservation	SR 2633	SR 2117	SR 2630	0.26	1.0" S4.75A	$19,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	3	065-New Hanover	Preservation	SR 2634	SR 2633	CUL-DE-SAC	0.06	1.0" S4.75A	$5,500
2026	3	065-New Hanover	Preservation	SR 2635	SR 2191	DEAD END	0.08	.75" Sand Asphalt	$6,000
2026	3	065-New Hanover	Preservation	SR 2638	SR 2146	CUL-DE-SAC	0.07	.75" Sand Asphalt	$6,000
2026	3	065-New Hanover	Preservation	SR 2739	SR 2117	SR 1328	0.41	1.0" S4.75A	$36,000
2026	3	065-New Hanover	Preservation	SR 2740	SR 1739	CDS	0.05	1.0" S4.75A	$4,000
2026	3	065-New Hanover	Preservation	SR 2741	SR 1739	CDS	0.05	1.0" S4.75A	$4,000
2026	3	065-New Hanover	Preservation	SR 2742	SR 1739	CDS	0.09	1.0" S4.75A	$7,000
2026	3	065-New Hanover	Preservation	SR 2743	SR 2742	CDS	0.04	1.0" S4.75A	$3,000
2026	3	065-New Hanover	Preservation	SR 2744	SR 1739	CDS	0.05	1.0" S4.75A	$4,000
2026	3	065-New Hanover	Preservation	SR 2745	SR 1739	CDS	0.05	1.0" S4.75A	$4,000
2026	3	065-New Hanover	Preservation	SR 2746	SR 1739	CDS	0.07	1.0" S4.75A	$5,000
2026	3	065-New Hanover	Preservation	SR 2835	SR 2633	CDS	0.03	1.0" S4.75A	$2,000
2026	3	065-New Hanover	Preservation	SR 2856	SR 2146	CUL-DE-SAC	0.05	.75" Sand Asphalt	$4,000
2026	3	065-New Hanover	Preservation	SR 2865	SR 2633	CDS	0.06	1.0" S4.75A	$4,000
2026	3	065-New Hanover	Preservation	SR 3120	SR 1706	CDS	0.05	1.25" S9.5B	$4,000
2026	3	067-Onslow	Resurfacing	Birch Ct	SR 1152	CDS	0.04	1.5" S9.5B	$9,000
2026	3	067-Onslow	Resurfacing	Briarneck Rd	US 258	SR 1316	0.42	1.5" S9.5B	$94,500
2026	3	067-Onslow	Resurfacing	Clayton James	SR 1105	CDS	0.71	1.5" S9.5B	$159,750
2026	3	067-Onslow	Resurfacing	Duffyfield Rd	SR 1222	Quarry Entrance	0.80	1.5" S9.5B	$91,000
2026	3	067-Onslow	Resurfacing	Evergreen Dr	SR 1689	EOM	0.07	1.5" S9.5B	$15,750
2026	3	067-Onslow	Resurfacing	Folkstone Rd	US 17	SR 1531	1.58	1.5" S9.5B	$350,000
2026	3	067-Onslow	Resurfacing	Futrell Loop	SR 1209	SR 1209	1.32	1.5" S9.5B	$250,000
2026	3	067-Onslow	Resurfacing	Futrell Rd	SR 1209	EOM	1.40	1.5" S9.5B	$315,000
2026	3	067-Onslow	Resurfacing	Hadley Collins	SR 1437	SR 1439	1.44	1.5" S9.5B	$324,000
2026	3	067-Onslow	Resurfacing	Heritage Ct	SR 1150	CDS	0.08	1.5" S9.5B	$18,000
2026	3	067-Onslow	Resurfacing	Heritage Dr	SR 1152	SR 1138	0.16	1.5" S9.5B	$36,000
2026	3	067-Onslow	Resurfacing	Jones Rd	SR 1509	Dead End	0.43	1.5" S9.5B	$96,750
2026	3	067-Onslow	Resurfacing	Kenwood Dr	SR 1213	SR 1285	0.64	1.5" S9.5B	$57,600
2026	3	067-Onslow	Resurfacing	Lake St	Rail Road Tracks	NC 24W	0.49	1.5" S9.5B	$112,000
2026	3	067-Onslow	Resurfacing	Lindsey Dr	SR 1130	SR 1145	0.27	1.5" S9.5B	$60,750
2026	3	067-Onslow	Resurfacing	Maple Ave	SR 1144	SR 1164	0.08	1.5" S9.5B	$18,000
2026	3	067-Onslow	Resurfacing	Maplehurst Dr	SR 1140	SR 1138	0.43	1.5" S9.5B	$96,750
2026	3	067-Onslow	Resurfacing	Meadow Trl	SR 1386 (N. Bryan)	CDS	0.22	1.25" S9.5B	$40,000
2026	3	067-Onslow	Resurfacing	Melody Ln	SR 1130	SR 1145	0.32	1.5" S9.5B	$72,000
2026	3	067-Onslow	Resurfacing	Mike Loop Rd	SR 1406	SR 1406	0.42	Full Depth Patching and 1.25" S9.5B	$110,000
2026	3	067-Onslow	Resurfacing	N Bryan	SR 1308 (Gum Branch)	CDS	1.35	1.5" S9.5B	$309,920
2026	3	067-Onslow	Resurfacing	NC 111	US 258	Airport project joint	5.00	1.5" S9.5C	$1,355,062
2026	3	067-Onslow	Resurfacing	NC 111	Airport project joint	Duplin County	3.41	1.5" S9.5C	$980,000
2026	3	067-Onslow	Resurfacing	Pine Needle Dr	SR 1501	EOM	0.26	1.5" S9.5B	$58,500
2026	3	067-Onslow	Resurfacing	Pony Express	SR 1386 (N Bryan)	CDS	0.10	1.25" S9.5B	$18,600
2026	3	067-Onslow	Resurfacing	Shamrock Dr	SR 1903	SR 1971	0.59	1.5" S9.5B	$133,000
2026	3	067-Onslow	Resurfacing	Shamrock Dr	SR 1308	SR 1903	0.39	1.5" S9.5B	$87,750
2026	3	067-Onslow	Resurfacing	Spanish Trl	SR 1386 (N. Bryan)	CDS	0.15	1.25" S9.5B	$27,900
2026	3	067-Onslow	Resurfacing	Swan Point Rd	SR 1515	EOM	0.75	1.5" S9.5B	$170,000
2026	3	067-Onslow	Resurfacing	Turtle Shell	SR 1229	SR 1238	1.30	1.5" S9.5B	$292,000
2026	3	067-Onslow	Resurfacing	US 258	NC 111	SR 2086	5.52	1.5" S9.5C	$2,349,000
2026	3	067-Onslow	Resurfacing	White St	SR 1308	MP 0.621	0.62	1.5" S9.5B	$139,000
2026	3	067-Onslow	Resurfacing	Wildwood Ct	SR 1501	CDS	0.08	1.5" S9.5B	$18,000
2026	3	067-Onslow	Resurfacing	William Gurganus	SR 1105	NC 53	3.94	1.5" S9.5B	$885,825
2026	3	067-Onslow	Rehabilitation	Hogans	SR 1503	EOM	1.28	2.5" I19.0B and 1.5" S9.5B	$215,750
2026	3	067-Onslow	Preservation	Ben Williams	SR 1205	SR 1213	5.37	Microsurface	$249,971
2026	3	067-Onslow	Preservation	Clayton Rd	SR 1406	SR 1471	0.16	1.25" S9.5B	$36,625
2026	3	067-Onslow	Preservation	Davis Rd	SR 1203	SR 1203	1.90	Microsurface	$101,625
2026	3	067-Onslow	Preservation	Dressler Dr	SR 1251	End Maint.	0.14	1.25" S9.5B	$31,625
2026	3	067-Onslow	Preservation	Earl Pl	SR 1853	Dead End	0.06	1.25" S9.5B	$18,529
2026	3	067-Onslow	Preservation	Hewitt Rd	SR 1203	SR 1201	1.90	Microsurface	$106,625
2026	3	067-Onslow	Preservation	Linda Dr	SR 1406	SR 1802	0.22	Patching and 1.25" S9.5A	$50,625
2026	3	067-Onslow	Preservation	Morningside Dr	NC 53	NC 24	0.17	1.25" S9.5B	$38,625
2026	3	067-Onslow	Preservation	Nine Mile Rd	NC 53	SR 1205	5.12	Microsurface	$231,625

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	3	067-Onslow	Preservation	Padgett Rd	NC 50	SR 1105	3.21	Microsurface	$166,625
2026	3	071-Pender	Resurfacing	SR 1100	SR 1201	NC 53	3.50	Full Depth Patching and 1.5" S9.5B	$770,000
2026	3	071-Pender	Resurfacing	SR 1101	Begin Pavement	NC 210	1.38	Full Depth Patching and 1.5" S9.5B	$305,000
2026	3	071-Pender	Resurfacing	SR 1113	NC 210	US 421	0.86	1.5" S9.5C and Widen	$225,000
2026	3	071-Pender	Resurfacing	SR 1121	SR 1120	NC 53	4.00	Full Depth Patching and 1.5" S9.5B	$990,000
2026	3	071-Pender	Resurfacing	SR 1128	SR 1126	NC 53	2.00	Full Depth Patching and 1.5" S9.5B	$440,000
2026	3	071-Pender	Resurfacing	SR 1216	SR 1336	SR 1343	3.40	Full Depth Patching and 1.5" S9.5B	$730,000
2026	3	071-Pender	Resurfacing	SR 1324	SR 1300	SR 1332	3.74	Full Depth Patching and 1.5" S9.5B	$825,000
2026	3	071-Pender	Resurfacing	SR 1411	SR 1409	US 117	4.00	Full Depth Patching and 1.5" S9.5B	$880,000
2026	3	071-Pender	Resurfacing	SR 1433	SR 1433	SR 1411	0.85	Full Depth Patching and 1.5" S9.5B	$190,000
2026	3	071-Pender	Resurfacing	SR 1433	US 117	SR 1433	0.60	Full Depth Patching and 1.5" S9.5B	$135,000
2026	3	071-Pender	Resurfacing	SR 1437	NC 133	EOM	1.80	Full Depth Patching and 1.5" S9.5B	$400,000
2026	3	071-Pender	Resurfacing	US 421 N	SR 1114	End Divided Section	4.44	1.5" S9.5C	$1,438,560
2026	3	071-Pender	Resurfacing	US 421 S	Begin Divided Section	SR 1114	4.44	1.5" S9.5C	$1,438,560
2026	3	071-Pender	Preservation	SR 1134	SR 1121	End of Pavement	0.34	Full Depth Patching and 1.0" S4.75A	$163,125
2026	3	071-Pender	Preservation	SR 1219	SR 1218	End of Pavement	0.10	Full Depth Patching and 1.0" S4.75A	$138,125
2026	3	071-Pender	Preservation	SR 1411	SR 1412	SR 1411	3.57	Full Depth Patching and 1.0" S4.75A	$523,125
2026	3	071-Pender	Preservation	SR 1412	SR 1411	US 117	2.93	Full Depth Patching and 1.0" S4.75A	$453,125
2026	3	071-Pender	Preservation	SR 1423	US 117	EOM	0.22	Full Depth Patching and 1.0" S4.75A	$153,125
2026	3	071-Pender	Preservation	SR 1510	US 117	EOM	0.90	Full Depth Patching and 1.0" S4.75A	$223,125
2026	3	071-Pender	Preservation	SR 1514	SR 1411	End of Pavement	0.29	Full Depth Patching and 1.0" S4.75A	$158,125
2026	3	071-Pender	Preservation	SR 1672	SR 1411	End of Pavement	0.30	Full Depth Patching and 1.0" S4.75A	$158,125
2026	3	082-Sampson	Resurfacing	SR 1215	Begin	NC 411	1.63	1.5" S9.5B	$0
2026	3	082-Sampson	Resurfacing	SR 1277	SR 2008	SR 1214	0.37	1.5" S9.5B	$101,750
2026	3	082-Sampson	Resurfacing	SR 1289	SR 1214	SR 1227	0.71	1.5" S9.5B	$195,250
2026	3	082-Sampson	Resurfacing	SR 1296	US 421	SR 1839	0.78	Mill Curb and 1.5" S9.5B	$234,000
2026	3	082-Sampson	Resurfacing	SR 1356	US 421	SR 1838	1.03	Mill Curb and 1.5" S9.5B	$550,000
2026	3	082-Sampson	Resurfacing	SR 1643	NC 55	US 13	2.93	1.5" S9.5B	$0
2026	3	082-Sampson	Resurfacing	SR 1644	SR1643	US 13	1.75	1.5" S9.5B	$0
2026	3	082-Sampson	Resurfacing	SR 1711	SR 1845	SR 1722	2.92	1.5" S9.5B	$0
2026	3	082-Sampson	Resurfacing	SR 1749	US 701	SR 1748	4.86	1.5" S9.5B	$1,336,500
2026	3	082-Sampson	Resurfacing	SR 1933	US421	SR 1924	3.36	1.5" S9.5B	$0
2026	3	082-Sampson	Resurfacing	US 421	Pender County	Duplin County	4.78	1.5" S9.5C	$1,807,218
2026	3	082-Sampson	Resurfacing	US 421	Duplin County	Begin Divided Section	17.11	1.5" S9.5C	$6,467,202
2026	3	082-Sampson	Preservation	SR 1135	US 701	NC 411	2.02	Seal - Double and Fog Seal	$75,000
2026	3	082-Sampson	Preservation	SR 1256	NC 24	SR 1406	2.45	Seal - Double and Fog Seal	$90,000
2026	3	082-Sampson	Preservation	SR 1403	SR 1405	SR 1515	1.37	Seal - Double and Fog Seal	$56,000
2026	3	082-Sampson	Preservation	SR 1404	SR 1403	NC 24	0.57	Seal - Double and Fog Seal	$23,000
2026	3	082-Sampson	Preservation	SR 1405	NC 24	SR 1002	2.31	Seal - Double and Fog Seal	$85,000
2026	3	082-Sampson	Preservation	SR 1475	US 421	SR 1636	0.70	Seal - Double and Fog Seal	$28,000
2026	3	082-Sampson	Preservation	SR 1476	SR 1475	US13	1.65	Seal - Double and Fog Seal	$65,960
2026	3	082-Sampson	Preservation	SR 1636	SR 1843	SR 1477	7.14	Seal - Double and Fog Seal	$260,000
2026	3	082-Sampson	Preservation	SR 1703	US 421	US 13	9.69	Seal - Double and Fog Seal	$350,000
2026	4	033-Edgecombe	Resurfacing	NC 122	Pinetops City Limits	NC-111	1.67	Mill 1.5" and 1.5" S9.5B	$308,950
2026	4	033-Edgecombe	Resurfacing	NC 33	US 258	Tar River Bridge / Bell Bridge	2.91	Mill 1.5" and 1.5" S9.5B	$840,450
2026	4	033-Edgecombe	Resurfacing	NC-111	Town Creek Bridge	SR 1003	0.56	1.5" S9.5B	$92,400
2026	4	033-Edgecombe	Resurfacing	NC-111	NC-43	NC-122	1.14	Mill 1.5" and 1.5" S9.5B	$228,000
2026	4	033-Edgecombe	Resurfacing	SR 1141	NC 43	SR 1006	3.22	1.5" S9.5B	$434,700
2026	4	033-Edgecombe	Resurfacing	SR 1200	NC 42	SR 1003	3.26	1.5" S9.5B	$471,975
2026	4	033-Edgecombe	Resurfacing	SR 1230	NC 43	SR 1232	1.58	1.5" S9.5B	$213,300
2026	4	033-Edgecombe	Resurfacing	SR 1309	SR 1230	SR 1232	0.26	1.5" S9.5B	$35,100
2026	4	033-Edgecombe	Resurfacing	SR 1344	US 258	NC 111	1.92	1.5" S9.5B	$316,800
2026	4	033-Edgecombe	Resurfacing	SR 1350	US 64A	NC 33 (Main St)	0.96	Mill 1.5" and 1.5" S9.5B	$378,015
2026	4	033-Edgecombe	Resurfacing	SR 1403	SR 1402	Dead End	0.74	1.5" S9.5B	$107,300
2026	4	033-Edgecombe	Resurfacing	SR 1409	NC-33	US-301	2.74	1.5" S9.5B	$397,300
2026	4	033-Edgecombe	Resurfacing	SR 1420	BEGIN PVMT	SR 1409	0.20	1.5" S9.5B	$27,000
2026	4	033-Edgecombe	Resurfacing	SR 1421	SR 1409	Nash County Line	0.86	1.5" S9.5B	$116,100
2026	4	033-Edgecombe	Resurfacing	SR 1518	NC 33	Tarboro County Line	3.20	1.5" S9.5B	$432,000
2026	4	033-Edgecombe	Resurfacing	SR 1527	NC-111	US-13	6.49	1.5" S9.5B	$941,050

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	4	033-Edgecombe	Resurfacing	SR 1537	SR 1520	NC 258	3.23	1.5" S9.5B	$532,455
2026	4	033-Edgecombe	Resurfacing	US-258	Bridge Joint	US-64A	0.35	Mill 1.5" and 1.5" S9.5B	$70,000
2026	4	033-Edgecombe	Preservation	NC 43	NC 43	RR Tracks	1.05	Crack Seal	$6,563
2026	4	033-Edgecombe	Preservation	SR 1117	NC 111	NC 122	1.61	Microsurface	$104,650
2026	4	033-Edgecombe	Preservation	SR 1134	SR 1124	SR 1135	0.99	Microsurface	$64,350
2026	4	033-Edgecombe	Preservation	SR 1218	SR 1337	SR 1208	2.13	Crack Seal	$13,313
2026	4	033-Edgecombe	Preservation	SR 1301	SR 1200	Dead End	0.33	1.25" S9.5B	$43,725
2026	4	033-Edgecombe	Preservation	SR 1302	SR 1301	SR 1301	0.25	1.25" S9.5B	$33,125
2026	4	033-Edgecombe	Preservation	SR 1336	US 64A	US 64A	1.95	Crack Seal	$12,188
2026	4	033-Edgecombe	Preservation	SR 1353	NC 111	SR 1354	0.09	1.25" S9.5B	$10,125
2026	4	033-Edgecombe	Preservation	SR 1354	Dead End	Dead End	0.23	1.25" S9.5B	$29,250
2026	4	033-Edgecombe	Preservation	SR 1400	NC 97	SR 1412	4.54	Crack Seal	$28,375
2026	4	033-Edgecombe	Preservation	SR 1504	US 258	SR 1505	0.96	Microsurface	$62,400
2026	4	033-Edgecombe	Preservation	SR 1506	SR 1504	NC 122	2.96	Microsurface	$175,335
2026	4	033-Edgecombe	Preservation	SR 1513	SR 1506	US 258	2.32	Microsurface	$130,865
2026	4	042-Halifax	Resurfacing	NC 48	NC 4	SR 1310	5.58	Mill 1.5" and 1.5" S9.5C	$1,185,750
2026	4	042-Halifax	Resurfacing	NC 48	NC 903	SR 1683	4.66	Mill 1.5" and 1.5" S9.5C	$941,625
2026	4	042-Halifax	Resurfacing	NC 481	SR 1117	NC 561	1.12	Mill 1.5" and 1.5" S9.5C	$238,000
2026	4	042-Halifax	Resurfacing	NC 561	US 301	SR 1149	2.20	Mill 1.5" and 1.5" S9.5C	$467,500
2026	4	042-Halifax	Resurfacing	SR 1002	I95	NC-481	4.86	1.5" S9.5B	$658,800
2026	4	042-Halifax	Resurfacing	SR 1103	SR 1003	SR 1114	2.85	1.5" S9.5B	$384,750
2026	4	042-Halifax	Resurfacing	SR 1105	SR 1103	SR 1102	3.69	1.5" S9.5B	$535,050
2026	4	042-Halifax	Resurfacing	SR 1210	NC 561	I-95	2.67	1.5" S9.5B and Widen	$440,550
2026	4	042-Halifax	Resurfacing	SR 1433	SR 1434	NC 48	2.03	1.5" S9.5B	$268,975
2026	4	042-Halifax	Resurfacing	SR 1621	NC 125	US 301	2.92	1.5" S9.5B	$392,850
2026	4	042-Halifax	Resurfacing	SR 1624	NC 125	SR 1657	2.07	1.5" S9.5B	$279,450
2026	4	042-Halifax	Resurfacing	SR 1626	SR 1627	NC 48	1.66	1.25" S9.5B	$307,100
2026	4	042-Halifax	Resurfacing	SR 1801	SR 1800	End of Pavement	0.49	1.5" S9.5B	$71,050
2026	4	042-Halifax	Resurfacing	SR 1806	US 258	End Maint	1.01	1.5" S9.5B	$136,350
2026	4	042-Halifax	Preservation	NC 125	SR 1629	NC 48	1.79	Crack Seal	$11,188
2026	4	042-Halifax	Preservation	NC 561	SR 1003	US 258	2.57	Crack Seal	$14,188
2026	4	042-Halifax	Preservation	NC-561	SR 1133	SR 1003	4.22	Crack Seal	$26,350
2026	4	042-Halifax	Preservation	SR 1002	SR 1214	I-95	3.36	Crack Seal	$21,000
2026	4	042-Halifax	Preservation	SR 1105	NC 125	SR 1103	3.47	Seal - Double	$164,825
2026	4	042-Halifax	Preservation	SR 1123	SR 1117	Dead End	0.80	Seal - Double and Fog Seal	$31,550
2026	4	042-Halifax	Preservation	SR 1143	SR 1142	SR 1144	1.05	Seal - Double and Fog Seal	$49,875
2026	4	042-Halifax	Preservation	SR 1144	NC-561	End Of Pavement	1.65	Seal - Double and Fog Seal	$69,300
2026	4	042-Halifax	Preservation	SR 1145	SR 1146	SR 1144	1.52	Seal - Double and Fog Seal	$72,200
2026	4	042-Halifax	Preservation	SR 1146	SR 1145	SR 1144	0.61	Seal - Double and Fog Seal	$28,975
2026	4	042-Halifax	Preservation	SR 1147	NC 561	Dead End	0.38	Seal - Double and Fog Seal	$17,500
2026	4	042-Halifax	Preservation	SR 1431	NC 48	SR 1432	1.06	Microsurface	$68,900
2026	4	042-Halifax	Preservation	SR 1604	SR 1602	SR 1615	1.39	Crack Seal	$8,656
2026	4	042-Halifax	Preservation	SR 1686	NC 48	NC 125	1.11	Crack Seal	$6,938
2026	4	042-Halifax	Preservation	SR 1695	SR 1615	Dead End	0.78	Seal - Double and Fog Seal	$50,700
2026	4	042-Halifax	Preservation	SR 1804	SR 1827	SR 1118	4.63	Seal - Double and Fog Seal	$219,925
2026	4	042-Halifax	Preservation	SR 1827	SR 1804	Dead End	1.01	Microsurface	$65,650
2026	4	051-Johnston	Resurfacing	SR 1100	US 301	SR 1204 + .4 Mi	0.99	1.5" S9.5B	$133,785
2026	4	051-Johnston	Resurfacing	SR 1145	SR 1140	SR 1144	2.10	1.5" S9.5B	$283,635
2026	4	051-Johnston	Resurfacing	SR 1161	SR 1162	NC 96	0.76	1.5" S9.5B	$102,195
2026	4	051-Johnston	Resurfacing	SR 1166	Harnett County Line	Wake County Line	1.84	1.5" S9.5B	$248,400
2026	4	051-Johnston	Resurfacing	SR 1204	NC 50	END PAVEMENT	1.13	1.5" S9.5B	$152,010
2026	4	051-Johnston	Resurfacing	SR 1232	NC 50	SR 1233	0.18	1.5" S9.5B	$24,705
2026	4	051-Johnston	Resurfacing	SR 1233	NC 50	SR 1232	0.10	1.5" S9.5B	$13,500
2026	4	051-Johnston	Resurfacing	SR 1313	NC 210	Harnett County Line	1.61	1.5" S9.5B	$217,215
2026	4	051-Johnston	Resurfacing	SR 1330	SR 1354	US 301	1.32	Mill 1.5" and 1.5" S9.5C	$257,400
2026	4	051-Johnston	Resurfacing	SR 1509	SR 1010	SR 1330	2.84	1.5" S9.5B	$383,400
2026	4	051-Johnston	Resurfacing	SR 1525	SR 3354	SR 1010	0.88	Mill 1.5" and 1.5" S9.5C	$259,600
2026	4	051-Johnston	Resurfacing	SR 1525	SR 1524	SR 3354	1.90	Mill 1.5" and 1.5" S9.5C	$403,750
2026	4	051-Johnston	Resurfacing	SR 1525	SR 1010	SR 2944	0.86	Mill 1.5" and 1.5" S9.5C	$167,700

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	4	051-Johnston	Resurfacing	SR 1531	Wake County Line	NC 210	5.07	1.5" S9.5B	$684,450
2026	4	051-Johnston	Resurfacing	SR 1534	SR 1533	SR 1536	1.39	1.5" S9.5B	$187,650
2026	4	051-Johnston	Resurfacing	SR 1535	SR 1534	End of State Maintenance	0.30	1.5" S9.5B	$40,500
2026	4	051-Johnston	Resurfacing	SR 1541	Wake County Line	SR 1531	1.24	1.5" S9.5B	$166,995
2026	4	051-Johnston	Resurfacing	SR 1542	Harnett County Line	SR 1006	0.87	1.5" S9.5B	$117,450
2026	4	051-Johnston	Resurfacing	SR 1545	Wake CL	NC 50	0.57	1.5" S9.5B	$81,000
2026	4	051-Johnston	Resurfacing	SR 1553	US 70 Bus W	SR 1700	1.20	Mill 1.5" and 1.5" S9.5B	$354,000
2026	4	051-Johnston	Resurfacing	SR 1560	SR 1561	SR 1563	2.95	1.5" S9.5B	$398,250
2026	4	051-Johnston	Resurfacing	SR 1571	Dead End	SR 1563	2.43	1.5" S9.5B	$328,050
2026	4	051-Johnston	Resurfacing	SR 1574	SR 1573	SR 1563	0.96	1.5" S9.5B	$129,600
2026	4	051-Johnston	Resurfacing	SR 1756	SR 1004	US 70 Bus W	0.47	Mill 1.5" and 1.5" S9.5B	$138,650
2026	4	051-Johnston	Resurfacing	SR 1913	SR 1907	SR 1923	4.98	1.5" S9.5B	$803,050
2026	4	051-Johnston	Resurfacing	SR 1934	SR 2127	SR 1003	9.90	1.5" S9.5B	$1,435,500
2026	4	051-Johnston	Resurfacing	SR 2177	US 301	End of State Maintenance	0.07	1.5" S9.5B	$20,650
2026	4	051-Johnston	Resurfacing	SR 2305	US 70	SR 1927	2.01	1.5" S9.5B	$271,620
2026	4	051-Johnston	Resurfacing	SR 2310	SR 1007	US 70 Alt	5.65	1.5" S9.5B	$762,615
2026	4	051-Johnston	Resurfacing	SR 2335	SR 1001	SR 2339	2.67	1.5" S9.5B	$360,450
2026	4	051-Johnston	Resurfacing	SR 2347	NC 222	Wilson County Line	0.73	1.5" S9.5B	$98,550
2026	4	051-Johnston	Resurfacing	SR 2379	SR 2347	Dead End	0.46	1.5" S9.5B	$62,100
2026	4	051-Johnston	Resurfacing	SR 2381	RR Tracks	SR 2330	0.23	1.5" S9.5B	$31,050
2026	4	051-Johnston	Resurfacing	SR 2517	SR 2310	SR 2516	0.40	1.5" S9.5B	$54,000
2026	4	051-Johnston	Resurfacing	SR 2520	SR 2519	SR 2521	0.69	1.5" S9.5B	$93,150
2026	4	051-Johnston	Resurfacing	SR 2526	SR 2523	SR 1007	3.23	1.5" S9.5B	$436,050
2026	4	051-Johnston	Resurfacing	SR 2556	US 70	US 70	1.50	Mill 1.5" and 1.5" S9.5B	$442,500
2026	4	051-Johnston	Resurfacing	US 301	SR 1007	US 70 Bus	0.85	Mill 1.5" and 1.5" S9.5B	$408,000
2026	4	051-Johnston	Resurfacing	US 70 Bus	US 301	SR 2560	0.64	1.5" S9.5B	$188,800
2026	4	051-Johnston	Resurfacing	US 70 Bus	NC 210	US 301	1.10	1.5" S9.5C	$522,750
2026	4	051-Johnston	Resurfacing	US-301	Harnett County Line	I-40 Bridge	3.40	Mill 1.5" and 1.5" S9.5B	$722,500
2026	4	051-Johnston	Preservation	SR 1173	SR 1705	Cul-De-Sac	0.29	1.25" S9.5B	$32,625
2026	4	051-Johnston	Preservation	SR 1312	SR 1313	Harnett County Line	1.92	1.25" S9.5B	$216,000
2026	4	051-Johnston	Preservation	SR 1396	SR 1311	Cul-De-Sac	0.20	1.25" S9.5B	$22,500
2026	4	051-Johnston	Preservation	SR 1657	SR 1554	Cul-De-Sac	0.33	1.25" S9.5B	$37,125
2026	4	051-Johnston	Preservation	SR 1658	SR 1657	Cul-De-Sac	0.11	1.25" S9.5B	$12,375
2026	4	051-Johnston	Preservation	SR 1659	SR 1554	Cul-De-Sac	0.41	1.25" S9.5B	$46,125
2026	4	051-Johnston	Preservation	SR 1779	SR 1553	Cul-De-Sac	0.18	1.25" S9.5B	$20,250
2026	4	051-Johnston	Preservation	SR 1780	SR 1179	Cul-De-Sac	0.02	1.25" S9.5B	$2,250
2026	4	051-Johnston	Preservation	SR 1781	SR 1553	Cul-De-Sac	0.15	1.25" S9.5B	$16,875
2026	4	051-Johnston	Preservation	SR 1782	SR 1781	Cul-De-Sac	0.03	1.25" S9.5B	$3,375
2026	4	051-Johnston	Preservation	SR 1786	SR 1004	SR 1787	0.15	1.25" S9.5B	$16,875
2026	4	051-Johnston	Preservation	SR 1787	SR 1786	Cul-De-Sac	0.31	1.25" S9.5B	$34,875
2026	4	051-Johnston	Preservation	SR 1788	SR 1787	SR 1787	0.32	1.25" S9.5B	$36,000
2026	4	051-Johnston	Preservation	SR 1838	SR 1586	Cul-De-Sac	0.21	1.25" S9.5B	$23,625
2026	4	051-Johnston	Preservation	SR 1847	NC 50	Cul-De-Sac	0.30	1.25" S9.5B	$33,750
2026	4	051-Johnston	Preservation	SR 1848	SR 1847	Cul-De-Sac	0.07	1.25" S9.5B	$7,875
2026	4	051-Johnston	Preservation	SR 2005	SR 1901	SR 2006	0.21	1.25" S9.5B	$23,625
2026	4	051-Johnston	Preservation	SR 2006	SR 2007	Cul-De-Sac	0.19	1.25" S9.5B	$21,375
2026	4	051-Johnston	Preservation	SR 2007	Cul-De-Sac	Dead End	0.15	1.25" S9.5B	$16,875
2026	4	051-Johnston	Preservation	SR 2013	SR 1901	Dead End	0.48	1.25" S9.5B	$54,000
2026	4	051-Johnston	Preservation	SR 2014	Dead End	Dead End	0.25	1.25" S9.5B	$28,125
2026	4	051-Johnston	Preservation	SR 2049	SR 1903	Cul-De-Sac	0.63	1.25" S9.5B	$70,875
2026	4	051-Johnston	Preservation	SR 2050	SR 2049	Cul-De-Sac	0.17	1.25" S9.5B	$19,125
2026	4	051-Johnston	Preservation	SR 2051	SR 2050	Cul-De-Sac	0.10	1.25" S9.5B	$11,250
2026	4	051-Johnston	Preservation	SR 2085	SR 1561	Cul-De-Sac	0.07	1.25" S9.5B	$7,875
2026	4	051-Johnston	Preservation	SR 2086	SR 1567	Cul-De-Sac	0.17	1.25" S9.5B	$19,125
2026	4	051-Johnston	Preservation	SR 2087	SR 1561	Cul-De-Sac	0.59	1.25" S9.5B	$66,375
2026	4	051-Johnston	Preservation	SR 2200	SR 2200	Cul-De-Sac	0.96	1.25" S9.5B	$108,000
2026	4	051-Johnston	Preservation	SR 2201	SR 2200	Cul-De-Sac	0.12	1.25" S9.5B	$13,500
2026	4	051-Johnston	Preservation	SR 2202	SR 2200	Cul-De-Sac	0.19	1.25" S9.5B	$21,375
2026	4	051-Johnston	Preservation	SR 2203	SR 2200	Cul-De-Sac	0.07	1.25" S9.5B	$9,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	4	051-Johnston	Preservation	SR 2242	SR 1512	Dead End	0.09	1.25" S9.5B	$10,125
2026	4	051-Johnston	Preservation	SR 2262	SR 2200	Cul-De-Sac	0.04	1.25" S9.5B	$4,500
2026	4	051-Johnston	Preservation	SR 2263	SR 2200	Cul-De-Sac	0.06	1.25" S9.5B	$6,750
2026	4	051-Johnston	Preservation	SR 2264	SR 2200	Cul-De-Sac	0.10	1.25" S9.5B	$11,250
2026	4	051-Johnston	Preservation	SR 2800	SR 1901	SR 2801	0.56	1.25" S9.5B	$63,000
2026	4	051-Johnston	Preservation	SR 2801	Cul-De-Sac	Cul-De-Sac	0.13	1.25" S9.5B	$14,625
2026	4	051-Johnston	Preservation	SR 2922	SR 1509	CDS	0.49	1.25" S9.5B	$55,125
2026	4	051-Johnston	Preservation	SR 2923	SR 2922	CDS	0.31	1.25" S9.5B	$34,875
2026	4	051-Johnston	Preservation	SR 3178	SR 1010	SR 3180	0.71	1.25" S9.5B	$94,075
2026	4	051-Johnston	Preservation	SR 3179	SR 3178	SR 2200	0.09	1.25" S9.5B	$11,925
2026	4	051-Johnston	Preservation	SR 3180	SR 2200	SR 2200	0.37	1.25" S9.5B	$41,625
2026	4	051-Johnston	Preservation	SR 3181	SR 3180	Cul-De-Sac	0.07	1.25" S9.5B	$7,875
2026	4	051-Johnston	Preservation	SR 3182	SR 3184	SR 3184	0.80	1.25" S9.5B	$106,000
2026	4	051-Johnston	Preservation	SR 3183	SR 3178	Cul-De-Sac	0.04	1.25" S9.5B	$4,500
2026	4	051-Johnston	Preservation	SR 3184	SR 3178	SR 3316	0.56	1.25" S9.5B	$74,200
2026	4	051-Johnston	Preservation	SR 3220	SR 1514	Cul-De-Sac	1.06	1.25" S9.5B	$119,250
2026	4	051-Johnston	Preservation	SR 3316	SR 1010	CUL-DE-SAC	0.78	1.25" S9.5B	$103,350
2026	4	051-Johnston	Preservation	SR 3317	SR 3316	CUL-DE-SAC	0.17	1.25" S9.5B	$19,125
2026	4	051-Johnston	Preservation	SR 3318	SR 3316	CUL-DE-SAC	0.04	1.25" S9.5B	$4,500
2026	4	051-Johnston	Preservation	SR 3321	SR 3320	Cul-De-Sac	0.46	1.25" S9.5B	$51,750
2026	4	051-Johnston	Preservation	SR 3322	SR 3320	End Maintenance	0.21	1.25" S9.5B	$23,625
2026	4	051-Johnston	Preservation	SR 3323	SR 3321	Cul-De-Sac	0.05	1.25" S9.5B	$5,625
2026	4	051-Johnston	Preservation	SR 3357	SR 3178	CUL-DE-SAC	0.06	1.25" S9.5B	$6,750
2026	4	051-Johnston	Preservation	SR 3494	SR 3182	CUL-DE-SAC	0.49	1.25" S9.5B	$64,925
2026	4	051-Johnston	Preservation	SR 3495	SR 3494	CUL-DE-SAC	0.03	1.25" S9.5B	$3,975
2026	4	051-Johnston	Preservation	SR 3496	SR 3494	Cul-De-Sac	0.04	1.25" S9.5B	$4,900
2026	4	051-Johnston	Preservation	SR 3497	SR 3182	CUL-DE-SAC	0.11	1.25" S9.5B	$13,475
2026	4	051-Johnston	Preservation	SR 3498	SR 3494	CUL-DE-SAC	0.05	1.25" S9.5B	$6,125
2026	4	051-Johnston	Preservation	SR 3499	SR 3494	CUL-DE-SAC	0.05	1.25" S9.5B	$5,625
2026	4	064-Nash	Resurfacing	NC 58	Barnes Street	South First Street	0.48	1.5" S9.5B	$86,400
2026	4	064-Nash	Resurfacing	NC 58	Boddie Mill Pond Road	Nashville County Line	4.03	Mill 1.5" and 1.5" S9.5B	$1,934,400
2026	4	064-Nash	Resurfacing	SR 1110	US 264 Alt	SR 1105	0.54	1.25" S9.5B	$60,750
2026	4	064-Nash	Resurfacing	SR 1114	NC 231	Wilson County Line	0.95	1.25" S9.5B	$106,875
2026	4	064-Nash	Resurfacing	SR 1117	SR 1116	SR 1115	1.19	1.5" S9.5B	$145,775
2026	4	064-Nash	Resurfacing	SR 1144	US 64 Alt	SR 1145	1.14	Mill 1.5" and 1.5" S9.5B	$450,300
2026	4	064-Nash	Resurfacing	SR 1305	US 64 Alt	SR 1301	2.21	1.25" S9.5B	$248,625
2026	4	064-Nash	Resurfacing	SR 1314	SR 1002	SR 1312	1.12	1.25" S9.5B	$126,000
2026	4	064-Nash	Resurfacing	SR 1603	SR 1717	NC 97	4.17	1.5" S9.5B	$688,050
2026	4	064-Nash	Resurfacing	SR 1603	NC 43	SR 1601	3.12	1.5" S9.5B	$514,635
2026	4	064-Nash	Resurfacing	SR 1670	SR 1003	NC 58/US 64 Bus	1.76	1.5" S9.5B	$255,200
2026	4	064-Nash	Resurfacing	SR 1700	US 64 Bus	SR 1544	5.04	1.5" S9.5B	$830,940
2026	4	064-Nash	Resurfacing	SR 1710	SR 1544	SR 1709	1.45	1.25" S9.5B	$163,125
2026	4	064-Nash	Resurfacing	SR 1741	NC 97	Wilson County Line	0.61	1.25" S9.5B	$68,625
2026	4	064-Nash	Resurfacing	SR 1900	SR 1306	US 64 Alt	4.93	1.5" S9.5B and Widen	$912,050
2026	4	064-Nash	Resurfacing	SR 1918	SR 1919	SR 1717	0.87	1.25" S9.5B	$97,875
2026	4	064-Nash	Resurfacing	SR 1950	NC 97	NC 97	2.08	1.25" S9.5B	$234,000
2026	4	064-Nash	Resurfacing	SR 1955	SR 1941	SR 1941	2.21	1.25" S9.5B	$248,625
2026	4	064-Nash	Resurfacing	SR 1976	SR 1900	SR 1145	0.26	1.25" S9.5B	$29,250
2026	4	064-Nash	Resurfacing	SR 1983	SR 1745	Dead End	0.31	1.25" S9.5B	$34,875
2026	4	064-Nash	Resurfacing	SR 2340	SR 1539	SR 1541	1.31	1.5" S9.5B	$147,375
2026	4	064-Nash	Resurfacing	US 301	US 301	NC 97	10.08	Mill 1.5" and 1.5" S9.5C	$2,500,000
2026	4	064-Nash	Resurfacing	US 301	US 301	NC 97	10.05	Mill 1.5" and 1.5" S9.5C	$2,500,000
2026	4	064-Nash	Resurfacing	US 64 Alt.	SR 1335+.067	NC 581 + .604	2.18	Mill 1.5" and 1.5" S9.5B	$861,100
2026	4	064-Nash	Preservation	SR 1112	SR 1101	NC 231	2.65	Microsurface	$172,250
2026	4	064-Nash	Preservation	SR 1113	NC 231	Wilson County Line	1.39	Microsurface	$90,350
2026	4	064-Nash	Preservation	SR 1162	NC 97	NC 231	1.30	Microsurface	$84,500
2026	4	064-Nash	Preservation	SR 1514	NC 48	SR 1500	1.92	Microsurface	$124,800
2026	4	064-Nash	Preservation	SR 1516	SR 1515	US 301	3.94	Seal - Double and Fog Seal	$206,400
2026	4	064-Nash	Preservation	SR 1517	SR 1516	NC 33	1.05	Seal - Double and Fog Seal	$53,125

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	4	064-Nash	Preservation	SR 1520	SR 1510	SR 1519	1.59	Seal - Double and Fog Seal	$79,475
2026	4	064-Nash	Preservation	SR 1525	NC 4	NC 48	1.11	Seal - Double and Fog Seal	$58,725
2026	4	064-Nash	Preservation	SR 1735	SR1544	US 301	1.05	Seal - Double and Fog Seal	$55,125
2026	4	064-Nash	Preservation	SR 1747	NC 97	SR 1544	1.55	Seal - Double and Fog Seal	$81,375
2026	4	064-Nash	Preservation	SR 1820	SR 1703	End Maint	0.28	Seal - Double and Fog Seal	$14,700
2026	4	064-Nash	Preservation	SR 1863	SR 1745	SR 1864	0.26	1.0" S4.75A	$29,250
2026	4	064-Nash	Preservation	SR 1864	Dead End	Dead End	0.17	1.0" S4.75A	$19,125
2026	4	064-Nash	Preservation	SR 1901	SR 1900	SR 1001	1.23	Seal - Double and Fog Seal	$63,575
2026	4	064-Nash	Preservation	SR 1910	SR 1909	SR 1909	1.28	Seal - Double and Fog Seal	$67,200
2026	4	096-Wayne	Resurfacing	NC 111	SR 1547	US 117 Bus	3.20	Mill 1.5" and 1.5" S9.5C	$592,000
2026	4	096-Wayne	Resurfacing	NC 581	NC 111	US 13	6.06	1.5" S9.5C	$999,900
2026	4	096-Wayne	Resurfacing	SR 1002	Johnston Co	NC 581	3.60	1.5" S9.5B	$486,000
2026	4	096-Wayne	Resurfacing	SR 1006	US 13	SR 1008	3.39	1.25" S9.5B	$381,375
2026	4	096-Wayne	Resurfacing	SR 1234	US-70	SR 1227	2.66	1.5" S9.5B	$359,100
2026	4	096-Wayne	Resurfacing	SR 1300	SR 1320	SR 1304	5.24	1.5" S9.5B	$707,130
2026	4	096-Wayne	Resurfacing	SR 1326	NC 581	US 70	3.63	1.5" S9.5B and Widen	$1,004,750
2026	4	096-Wayne	Resurfacing	SR 1331	US 70	Johnston County Line	1.96	1.5" S9.5B	$264,600
2026	4	096-Wayne	Resurfacing	SR 1333	Johnston CL	SR 1332	5.03	1.25" S9.5B	$565,875
2026	4	096-Wayne	Resurfacing	SR 1334	SR 1333	SR 1335	1.74	1.25" S9.5B	$195,750
2026	4	096-Wayne	Resurfacing	SR 1335	SR 1336	SR 1334	1.00	1.25" S9.5B	$112,050
2026	4	096-Wayne	Resurfacing	SR 1342	Johnston Co	NC 222	6.46	1.25" S9.5B	$726,750
2026	4	096-Wayne	Resurfacing	SR 1353	NC 222	SR 1336	2.96	1.5" S9.5B	$399,465
2026	4	096-Wayne	Resurfacing	SR 1485	SR 1336	Cul-De-Sac	0.70	1.25" S9.5B	$78,750
2026	4	096-Wayne	Resurfacing	SR 1486	SR 1336	Cul-De-Sac	0.43	1.25" S9.5B	$48,375
2026	4	096-Wayne	Resurfacing	SR 1502	SR 1503	Wilson County Line	1.20	1.25" S9.5B	$135,000
2026	4	096-Wayne	Resurfacing	SR 1508	SR 1505	SR 1506	1.80	1.25" S9.5B	$202,500
2026	4	096-Wayne	Resurfacing	SR 1510	SR 1508	Wilson County Line	1.07	1.25" S9.5B	$120,263
2026	4	096-Wayne	Resurfacing	SR 1575	SR 1556	SR 1535	2.30	1.25" S9.5B	$258,750
2026	4	096-Wayne	Resurfacing	SR 1941	SR 1938	SR 1744	1.79	1.5" S9.5B	$241,650
2026	4	096-Wayne	Resurfacing	SR 1941	SR 1938	US 117 Alt	0.55	1.5" S9.5B and Widen	$117,250
2026	4	096-Wayne	Preservation	SR 1101	Sampson County Line	SR 1106	4.76	Microsurface	$214,200
2026	4	096-Wayne	Preservation	SR 1122	US 13	SR 1120	3.89	Seal - Double and Fog Seal	$155,050
2026	4	096-Wayne	Preservation	SR 1124	SR 1122	SR 1120	0.89	1.25" S9.5B	$100,125
2026	4	096-Wayne	Preservation	SR 1264	US 70	SR 1264	0.33	1.5" S9.5B	$33,150
2026	4	096-Wayne	Preservation	SR 1265	SR 1264	Dead End	0.15	Microsurface	$9,750
2026	4	096-Wayne	Preservation	SR 1278	SR 1264	SR 1243	0.07	Microsurface	$4,550
2026	4	096-Wayne	Preservation	SR 1303	SR 1300	SR 1305	0.68	Microsurface	$44,200
2026	4	096-Wayne	Preservation	SR 1734	1731	Lenoir County Line	1.58	1.25" S9.5B	$177,750
2026	4	096-Wayne	Preservation	SR 1737	SR 1731	Lenoir Co	1.03	1.25" S9.5B	$115,875
2026	4	096-Wayne	Preservation	SR 1933	SR 1744	SR 1120	3.11	Seal - Double and Fog Seal	$132,550
2026	4	096-Wayne	Preservation	SR 1957	NC-111	SR 1574	0.90	1.25" S9.5B	$101,250
2026	4	096-Wayne	Preservation	SR 2154	Dead End	Dead End	0.63	1.25" S9.5B	$70,875
2026	4	096-Wayne	Preservation	SR 2165	SR 1236	Dead End	0.23	1.25" S9.5B	$25,313
2026	4	096-Wayne	Preservation	SR 2165	SR 2165	Cul-De-Sac	0.09	1.25" S9.5B	$10,125
2026	4	096-Wayne	Preservation	SR 2206	SR 1726	Dead End	0.84	1.25" S9.5B	$94,500
2026	4	098-Wilson	Resurfacing	NC 58	Ward Blvd	Joint Near Country Club Road	1.90	Mill 1.5" and 1.5" S9.5B	$560,500
2026	4	098-Wilson	Resurfacing	NC 581	SR 1118	Nash County Line	7.23	Mill 1.5" and 1.5" S9.5B	$1,446,000
2026	4	098-Wilson	Resurfacing	NC 581	Wayne County Line	SR 1118	5.94	Mill 1.5" and 1.5" S9.5C	$1,188,000
2026	4	098-Wilson	Resurfacing	SR 1195	Johnston County Line	Dead End	3.56	1.5" S9.5B and Widen	$930,000
2026	4	098-Wilson	Resurfacing	SR 1339	SR 1368	SR 1340	1.60	1.5" S9.5B	$216,000
2026	4	098-Wilson	Resurfacing	SR 1512	NC 42	Edgecombe County Line	1.22	1.25" S9.5B	$137,250
2026	4	098-Wilson	Resurfacing	SR 1516	SR1359 Joint near Raleigh Rd Pwky East	US 264A Raleigh Rd Pkwy W	3.67	Mill 1.5" and 1.5" S9.5B	$1,449,650
2026	4	098-Wilson	Preservation	NC 42	Johnston County Line	SR 1116	5.54	Crack Seal	$34,625
2026	4	098-Wilson	Preservation	SR 1108	SR 1100	SR 1111	1.89	Crack Seal	$11,812
2026	4	098-Wilson	Preservation	SR 1119	SR 1159	Dead End	0.66	.75" S4.75A	$57,750
2026	4	098-Wilson	Preservation	SR 1163	SR 1162	SR 1165	2.36	Crack Seal	$14,750
2026	4	098-Wilson	Preservation	SR 1175	SR 1103	SR 1100	1.04	Crack Seal	$6,500
2026	4	098-Wilson	Preservation	SR 1307	SR 1306	Dead End in Nash County	0.07	1.0" S4.75A	$40,425
2026	4	098-Wilson	Preservation	SR 1327	RR XING	COUNTY LINE	6.45	Microsurface	$415,250

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	4	098-Wilson	Preservation	SR 1329	SR 1327	SR 1330	2.40	Crack Seal	$14,987
2026	4	098-Wilson	Preservation	SR 1337	SR 1003	SR 1340	1.52	Crack Seal	$9,550
2026	4	098-Wilson	Preservation	SR 1433	SR 1432	Dead End	0.68	Crack Seal	$4,250
2026	4	098-Wilson	Preservation	SR 1522	US 264 ALT	SR 1514	1.21	Microsurface	$78,650
2026	4	098-Wilson	Preservation	SR 1572	NC 222	Dead End	0.55	Microsurface	$35,750
2026	4	098-Wilson	Preservation	SR 1619	US 117	SR 1621	1.51	Crack Seal	$9,437
2026	4	098-Wilson	Preservation	SR 1661	US 301	SR 1658	0.84	1.0" S4.75A	$95,750
2026	4	098-Wilson	Preservation	US 264 Alt.	Nash County Line	joint at Chip Mill	3.00	Crack Seal	$18,750
2026	5	032-Durham	Resurfacing	Bahama Rd.	US 501	SR 1607	3.71	Full Depth Patching and 1.5" S9.5B	$808,000
2026	5	032-Durham	Resurfacing	Bahama Rd.	SR 1616	Person County	4.63	Full Depth Patching and 1.5" S9.5B	$1,010,000
2026	5	032-Durham	Resurfacing	Broach Rd	SR 1911	SR 2006	0.30	Full Depth Patching and 1.5" S9.5B	$65,000
2026	5	032-Durham	Resurfacing	Broach Rd	SR 2091	Dead End	0.16	Full Depth Patching and 1.5" S9.5B	$31,000
2026	5	032-Durham	Resurfacing	Carpenter Pond Rd.	Wake County	SR 1906	4.56	Full Depth Patching and 1.5" S9.5B	$979,000
2026	5	032-Durham	Resurfacing	Mockingbird Lane	Begin Maintenance	Dead End	0.42	Full Depth Patching and 1.5" S9.5B	$83,000
2026	5	032-Durham	Resurfacing	Oakview St	SR 1912	End Maintenance	0.20	Full Depth Patching and 1.5" S9.5B	$40,000
2026	5	032-Durham	Resurfacing	Panoramic Dr.	SR 1906	Dead End	0.33	Full Depth Patching and 1.5" S9.5B	$71,000
2026	5	032-Durham	Resurfacing	Pennock Rd	SR 2006	High Fox Dr	0.54	Full Depth Patching and 1.5" S9.5B	$106,000
2026	5	032-Durham	Resurfacing	Pennock Rd.	SR 1912	End Maintenance	0.09	Full Depth Patching and 1.5" S9.5B	$18,000
2026	5	032-Durham	Resurfacing	Sterling Dr.	SR 1449	Cul-de-sac	0.42	Full Depth Patching and 1.25" S9.5B	$82,000
2026	5	032-Durham	Resurfacing	Summer Rose Ln.	SR 2089	Dead End	0.19	Full Depth Patching and 1.5" S9.5B	$42,000
2026	5	032-Durham	Resurfacing	US 15 Bus	US 70 Bus	US 15 Bus	0.48	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$128,000
2026	5	032-Durham	Resurfacing	US 15 Bus	E Forest Hills Blvd	E Main St	1.09	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$353,000
2026	5	032-Durham	Resurfacing	US 70 Bus	SR 1380	US 70 Bus	0.50	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$155,000
2026	5	032-Durham	Resurfacing	US 70 Bus	S Buchanan Blvd	SR 1380	0.54	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$289,000
2026	5	032-Durham	Resurfacing	Wayward Dr	SR 2426	End Maintenance	0.13	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$23,000
2026	5	032-Durham	Resurfacing	Wentz Dr	SR 1807	End Maintenance	0.31	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$55,000
2026	5	032-Durham	Preservation	Barbours Creek Rd	SR 1798	SR 2600	0.18	1.0" S9.5B	$23,000
2026	5	032-Durham	Preservation	Beck Rd	SR 1670	SR 1819	0.38	1.0" S9.5B	$47,000
2026	5	032-Durham	Preservation	Bent Creek Rd	SR 2601	Cul de sac	0.16	1.0" S9.5B	$20,000
2026	5	032-Durham	Preservation	Broughton Dr	SR 1670	SR 2539	0.22	1.0" S9.5B	$25,000
2026	5	032-Durham	Preservation	Broughton Dr	SR 1868	End Pavement	0.05	1.0" S9.5B	$6,000
2026	5	032-Durham	Preservation	Chambers Rd	SR 1470	SR 1471	0.85	1.0" S9.5B	$105,000
2026	5	032-Durham	Preservation	Chambers Rd	SR 1471	US 501	1.09	1.0" S9.5B	$135,000
2026	5	032-Durham	Preservation	Chantilly Pl	SR 2600	Cul-de-sac	0.08	1.0" S9.5B	$10,000
2026	5	032-Durham	Preservation	Converse Rd	SR 1883	Dead End	0.09	1.0" S9.5B	$11,000
2026	5	032-Durham	Preservation	Cross Creek Rd	SR 1751	SR 1799	0.07	1.0" S9.5B	$9,000
2026	5	032-Durham	Preservation	Fiesta Rd	SR 1815	SR 1883	0.09	1.0" S9.5B	$11,000
2026	5	032-Durham	Preservation	Glenda Rd	SR 1637	End Maintenance	0.23	1.0" S9.5B	$37,000
2026	5	032-Durham	Preservation	Grimes Ave	SR 1815	End Maintenance	0.27	1.0" S9.5B	$33,000
2026	5	032-Durham	Preservation	Iron Gate Dr	SR 1628	Dead End	0.35	1.0" S9.5B	$43,000
2026	5	032-Durham	Preservation	Loftin Dr	SR 1800	SR 1815	0.16	1.0" S9.5B	$20,000
2026	5	032-Durham	Preservation	Penrod Rd	SR 1813	SR 1882	0.19	1.0" S9.5B	$24,000
2026	5	032-Durham	Preservation	Riverside Dr	SR 1004	END MAINT	0.10	1.0" S9.5B	$12,000
2026	5	035-Franklin	Resurfacing	Barnhill Ln	SR 4581	Cul-de-sac	0.86	Full Depth Patching and 1.25" S9.5B	$151,000
2026	5	035-Franklin	Resurfacing	Brantleytown Road/Old Halifax	NC 39	WAKE CO	5.97	Full Depth Patching and 1.25" S9.5B	$1,103,000
2026	5	035-Franklin	Resurfacing	Briarwood Pl	Cul-de-sac	Dead End	0.23	Full Depth Patching and 1.25" S9.5B	$40,000
2026	5	035-Franklin	Resurfacing	Bud Winstead	SR 1607	Dead End	0.66	Full Depth Patching and 1.25" S9.5B	$128,000
2026	5	035-Franklin	Resurfacing	Camping Creek Rd	SR 1109	Cul-de-sac	0.80	Full Depth Patching and 1.5" S9.5B	$175,000
2026	5	035-Franklin	Resurfacing	Cottrell Dr	US 401	END MAINT	0.47	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$93,000
2026	5	035-Franklin	Resurfacing	Dorsey Rd	SR 1455	SR 1425	0.67	Full Depth Patching and 1.5" S9.5B	$146,000
2026	5	035-Franklin	Resurfacing	Dunstan	SR 1228	Dead End	0.03	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$9,000
2026	5	035-Franklin	Resurfacing	Epping Forest Way	SR 1925	Cul-de-sac	0.04	Full Depth Patching and 1.25" S9.5B	$7,000
2026	5	035-Franklin	Resurfacing	Grant/Chestnut/Hayes	SR 1229	SR 1229	0.48	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$95,000
2026	5	035-Franklin	Resurfacing	Grifford Dr	NC 561	SR 1489	0.34	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$67,000
2026	5	035-Franklin	Resurfacing	Guernsey Ct	SR 1971	Cul-de-sac	0.15	Full Depth Patching and 1.25" S9.5B	$26,000
2026	5	035-Franklin	Resurfacing	Halifax Rd	US 401	NC 561	0.30	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$66,000
2026	5	035-Franklin	Resurfacing	Jeffress Dr	SR 1232	SR 1257	0.21	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$42,000
2026	5	035-Franklin	Resurfacing	Jeffress Dr	SR 1256	SR 1258	0.24	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$48,000
2026	5	035-Franklin	Resurfacing	Keighley Forest Dr	WAKE CO	Dead End	0.20	Full Depth Patching and 1.25" S9.5B	$34,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	5	035-Franklin	Resurfacing	Meadow Glenn	GRANVILLE CO	Cul-de-sac	0.54	Full Depth Patching and 1.25" S9.5B	$95,000
2026	5	035-Franklin	Resurfacing	NC 561	US 401	Pavement Joint	11.28	Full Depth Patching and 1.5" S9.5B	$2,760,000
2026	5	035-Franklin	Resurfacing	Perry Ln	SR 1103	Dead End	0.30	Full Depth Patching and 1.5" S9.5B	$65,000
2026	5	035-Franklin	Resurfacing	S. Cross St	NC 96	Wake County	1.89	Full Depth Patching and 1.5" S9.5B	$413,000
2026	5	035-Franklin	Resurfacing	Santorini Way	SR 1945	Cul-de-sac	0.11	Full Depth Patching and 1.25" S9.5B	$19,000
2026	5	035-Franklin	Resurfacing	Scotts Pine Cir	Dead End	Dead End	0.34	Full Depth Patching and 1.25" S9.5B	$51,000
2026	5	035-Franklin	Resurfacing	Silo Glen	SR 1137	SR 1971	0.04	Full Depth Patching and 1.25" S9.5B	$7,000
2026	5	035-Franklin	Resurfacing	Stratford Dr	SR 1256	SR 1490	0.30	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$60,000
2026	5	035-Franklin	Resurfacing	Traylee Dr	SR 1961	GRANVILLE CO	0.47	Full Depth Patching and 1.25" S9.5B	$82,000
2026	5	035-Franklin	Resurfacing	US 1 Alt	NC 96	US 1	2.18	Full Depth Patching and 1.5" S9.5B	$664,000
2026	5	035-Franklin	Resurfacing	Vaiden Rd	SR 1407	NC 58	2.81	Full Depth Patching and 1.25" S9.5B	$547,000
2026	5	035-Franklin	Preservation	Bibby Rd	SR 1211	Cul-de-sac	0.59	Full Depth Patching and Double Seal and Fog Seal	$53,000
2026	5	035-Franklin	Preservation	Ja Rogers Rd	SR 1239	Cul-de-sac	1.74	Full Depth Patching and Double Seal and Fog Seal	$172,000
2026	5	035-Franklin	Preservation	Moores Pond	SR 1100	SR 1103	1.85	Full Depth Patching and Double Seal and Fog Seal	$174,000
2026	5	035-Franklin	Preservation	Possum Rd	SR 1003	SR 1211	1.18	Full Depth Patching and Double Seal and Fog Seal	$117,000
2026	5	035-Franklin	Preservation	Trinity Church Rd	US 401	SR 1412	2.08	Full Depth Patching and Triple Seal and Fog Seal	$307,000
2026	5	035-Franklin	Preservation	Wiley Hawkins	SR 1243	SR 1244	1.56	Full Depth Patching and Double Seal	$141,000
2026	5	039-Granville	Resurfacing	Baynam Pond Dr	WAKE CO	FRANKLIN CO	0.09	Full Depth Patching and 1.25" S9.5B	$18,000
2026	5	039-Granville	Resurfacing	Brinkley Rd/Thad Carey Rd	SR 1004	Dead End	1.08	Full Depth Patching and 1.5" S9.5B	$235,000
2026	5	039-Granville	Resurfacing	Lawrence Rd	WAKE CO	SR 1709	3.92	Full Depth Patching and 1.25" S9.5B	$944,000
2026	5	039-Granville	Resurfacing	NC 56	SR 1103	Pavement Joint	4.82	Full Depth Patching and 1.5" S9.5B	$1,209,000
2026	5	039-Granville	Resurfacing	Old NC 75	Ledge Creek	RR Tracks	7.85	Full Depth Patching and 1.5" S9.5B	$2,167,000
2026	5	039-Granville	Resurfacing	Sunflower Meadows Ln	SR 1734	WAKE CO	0.28	Full Depth Patching and 1.25" S9.5B	$54,000
2026	5	039-Granville	Resurfacing	Traylee Dr	SR 1794	FRANKLIN CO	0.06	Full Depth Patching and 1.25" S9.5B	$11,000
2026	5	039-Granville	Preservation	Bodie Currin	SR 1303	SR 1300	2.27	Full Depth Patching and 1.25" S9.5B	$442,000
2026	5	039-Granville	Preservation	Cornwall Rd	SR 1301	US 158	0.56	Full Depth Patching and 1.25" S9.5B	$120,000
2026	5	039-Granville	Preservation	Joe Pruitt Rd	SR 1300	SR 1303	2.26	Full Depth Patching and 1.25" S9.5B	$440,000
2026	5	039-Granville	Preservation	John Watkins Rd	SR 1410	SR 1300	0.67	Full Depth Patching and 1.25" S9.5B	$130,000
2026	5	073-Person	Resurfacing	Cunningham Rd	CASWELL CO	VIRGINIA	5.03	Full Depth Patching and 1.5" S9.5B	$1,098,000
2026	5	073-Person	Resurfacing	Graves Rd	Begin Pvmt	End Pvmt	0.22	Full Depth Patching and 1.5" S9.5B	$37,000
2026	5	073-Person	Resurfacing	Harrington Ln	SR 1363	Dead End	0.15	Full Depth Patching and 1.5" S9.5B	$32,000
2026	5	073-Person	Resurfacing	Hassel Clayton Rd	SR 1337	End Maintenance	0.10	Full Depth Patching and 1.5" S9.5B	$68,000
2026	5	073-Person	Resurfacing	Henderson Rd	SR 1534	US 501	0.48	Full Depth Patching and 1.5" S9.5B	$106,000
2026	5	073-Person	Resurfacing	Lindsey Carver Rd	NC 157	SR 1220	0.09	Full Depth Patching and 1.5" S9.5B	$18,000
2026	5	073-Person	Resurfacing	Morton Pulliam	SR 1340	SR 1339	1.15	Full Depth Patching and 1.5" S9.5B	$251,000
2026	5	073-Person	Resurfacing	Shady Hill Cir	SR 1605	SR 1580	0.29	Full Depth Patching and 1.5" S9.5B	$57,000
2026	5	073-Person	Resurfacing	Tanglewood Cir	SR 1391	SR 1415	0.87	Full Depth Patching and 1.5" S9.5B	$190,000
2026	5	073-Person	Preservation	Al Gray Rd	Orange County	SR 1121	0.49	Full Depth Patching and Double Seal	$44,000
2026	5	073-Person	Preservation	Charlie Jay Rd	SR 1333	End Maintenance	0.44	Full Depth Patching and Double Seal	$32,000
2026	5	073-Person	Preservation	Enos Slaughter Rd	SR 1556	Dead End	0.63	Full Depth Patching and Double Seal	$57,000
2026	5	073-Person	Preservation	Harold Gill Rd	SR 1565	SR 1536	1.10	Full Depth Patching and Double Seal	$99,000
2026	5	073-Person	Preservation	Jack Hambrick Rd	SR 1336	SR 1337	0.92	Full Depth Patching and Double Seal	$83,000
2026	5	073-Person	Preservation	Ruff Davis Rd	SR 1541	SR 1542	1.03	Full Depth Patching and Double Seal	$93,000
2026	5	073-Person	Preservation	Seamster Rd	SR 1337	Cul-de-sac	0.30	Full Depth Patching and Double Seal	$27,000
2026	5	073-Person	Preservation	Talley Loop Rd	SR 1547	SR 1547	0.29	Full Depth Patching and Double Seal	$23,000
2026	5	073-Person	Preservation	Willie Gray Rd	SR 1123	SR 1120	1.98	Full Depth Patching and Double Seal	$179,000
2026	5	091-Vance	Resurfacing	Dr. Finch Road	SR 1519	End Maintenance	0.93	Full Depth Patching and 1.25" S9.5B	$162,000
2026	5	091-Vance	Resurfacing	Foster Rd Ext	SR 1559	End Maintenance	0.91	Full Depth Patching and 1.25" S9.5B	$176,000
2026	5	091-Vance	Resurfacing	Haywood Wright Rd	SR 1310	NC 39	0.79	1.0" S9.5B	$98,000
2026	5	091-Vance	Resurfacing	Nutbush/Glebe	SR 1306	SR 1319	7.66	Full Depth Patching and 1.25" S9.5B	$1,639,000
2026	5	091-Vance	Resurfacing	Pine Crest Rd	SR 1312	SR 1407	0.27	1.25" S9.5B	$34,000
2026	5	091-Vance	Resurfacing	Sandy Point Road	SR 1363	End Maintenance	0.28	1.0" S9.5B	$30,000
2026	5	091-Vance	Resurfacing	Skipper's Landing	SR 1459	Cul De Sac	0.16	1.0" S9.5B	$18,000
2026	5	091-Vance	Resurfacing	Tharrington Ln	SR 1399	SR 1407	0.11	1.25" S9.5B	$14,000
2026	5	091-Vance	Resurfacing	Tucker Lumber Rd.	US 1	End of Maint.	0.04	Full Depth Patching and 1.5" S9.5C	$10,000
2026	5	091-Vance	Resurfacing	US 1 Bus / US 158	US 1 NB	Warren County	4.99	Full Depth Patching and 1.5" S9.5C	$1,320,000
2026	5	091-Vance	Resurfacing	US 1 Bus / US 158	Pavement Joint	US 1	1.01	Full Depth Patching and 1.5" S9.5C	$256,000
2026	5	091-Vance	Resurfacing	US 1 Bus / US 158	US 1 NB	US 1 SB	0.04	Full Depth Patching and 1.5" S9.5C	$10,000
2026	5	091-Vance	Resurfacing	Wesley Dr	SR 1312	END MAINT	0.18	1.25" S9.5B	$22,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	5	091-Vance	Resurfacing	Williams Rd	SR 1329	Cul-de-sac	0.38	1.0" S9.5B	$42,000
2026	5	091-Vance	Resurfacing	Wrenn Rd	SR 1110	Granville County	0.30	1.0" S9.5B	$38,000
2026	5	091-Vance	Preservation	Cedar Cove Rd	SR 1369	Cul-de-sac	1.20	Full Depth Patching and Double Seal and Fog Seal	$119,000
2026	5	091-Vance	Preservation	Clements Rd	US 158	End Maintenance	0.40	Full Depth Patching and Double Seal and Fog Seal	$48,000
2026	5	091-Vance	Preservation	Oakridge Church	SR 1551	US 1	2.44	Full Depth Patching and Double Seal and Fog Seal	$241,000
2026	5	091-Vance	Preservation	S Hawkins Ave	SR 1501	End Maintenance	0.22	Full Depth Patching and Double Seal and Fog Seal	$19,000
2026	5	091-Vance	Preservation	Twisdale	SR 1348	End Maintenance	0.69	Full Depth Patching and Double Seal and Fog Seal	$68,000
2026	5	091-Vance	Preservation	Woodlief/Moss Stock	SR 1555	Cul-de-sac	0.96	Full Depth Patching and Double Seal and Fog Seal	$95,000
2026	5	092-Wake	Resurfacing	Adona Ln	SR 1912	Cul-de-sac	0.14	Full Depth Patching and 1.5" S9.5B	$31,000
2026	5	092-Wake	Resurfacing	Air Park Rd	US 401	End Maintenance	1.01	Full Depth Patching and 1.5" S9.5B	$220,000
2026	5	092-Wake	Resurfacing	Aldershot Dr	SR 1979	Dead End	0.09	Full Depth Patching and 1.5" S9.5B	$17,000
2026	5	092-Wake	Resurfacing	Alveston Ct	SR 5719	Cul-de-sac	0.06	Full Depth Patching and 1.25" S9.5B	$13,000
2026	5	092-Wake	Resurfacing	Andersonwood Dr	Cul-de-sac	Dead End	0.91	Full Depth Patching and 1.5" S9.5B	$198,000
2026	5	092-Wake	Resurfacing	Applecross Cir	SR 3900	Cul-de-sac	0.37	Full Depth Patching and 1.5" S9.5B	$81,000
2026	5	092-Wake	Resurfacing	April Wind Dr	Dead End	Cul-de-sac	0.22	Full Depth Patching and 1.25" S9.5B	$43,000
2026	5	092-Wake	Resurfacing	Baker Rd	SR 1001	Pvmt Jt	0.33	Full Depth Patching and 1.5" S9.5B	$65,000
2026	5	092-Wake	Resurfacing	Bare Creek Ln	SR 2849	Cul-de-sac	0.14	Full Depth Patching and 1.25" S9.5B	$27,000
2026	5	092-Wake	Resurfacing	Birchfalls Dr	SR 2002	SR 3614	0.63	Full Depth Patching and 1.25" S9.5B	$123,000
2026	5	092-Wake	Resurfacing	Blue Ravine Rd	Begin Maintenance	END MAINT	0.16	Full Depth Patching and 1.25" S9.5B	$31,000
2026	5	092-Wake	Resurfacing	Brassfield Rd	SR 2008	SR 2002	0.37	Full Depth Patching and 1.5" S9.5B	$81,000
2026	5	092-Wake	Resurfacing	Brothers Way	SR 2728	SR 5376	0.19	Full Depth Patching and 1.25" S9.5B	$37,000
2026	5	092-Wake	Resurfacing	Brushy Meadows Dr	SR 1393	SR 5090	0.66	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$82,000
2026	5	092-Wake	Resurfacing	Buckboard Ln	SR 3855	Cul-de-sac	0.16	Full Depth Patching and 1.5" S9.5B	$36,000
2026	5	092-Wake	Resurfacing	Bud Smith Rd	SR 4519	GRANVILLE CO	0.53	Full Depth Patching and 1.5" S9.5B	$95,000
2026	5	092-Wake	Resurfacing	Bud Smith Rd	SR 1909	SR 4519	0.37	Full Depth Patching and 1.5" S9.5B	$89,000
2026	5	092-Wake	Resurfacing	Burchblind Dr	SR 4540	END MAINT	0.08	1.5" S9.5B	$18,000
2026	5	092-Wake	Resurfacing	Burnside Dr	SR 1404	SR 3901	0.09	Full Depth Patching and 1.5" S9.5B	$19,000
2026	5	092-Wake	Resurfacing	Canonbie Ln	END MAINT	Cul-de-sac	0.38	Full Depth Patching and 1.5" S9.5B	$74,000
2026	5	092-Wake	Resurfacing	Carrier Way	SR 3764	Cul-de-sac	0.20	Full Depth Patching and 1.5" S9.5B	$44,000
2026	5	092-Wake	Resurfacing	Catrush Way	SR 4540	END MAINT	0.10	1.5" S9.5B	$24,000
2026	5	092-Wake	Resurfacing	Chelsea Dr	SR 2724	SR 3864	0.23	Full Depth Patching and 1.25" S9.5B	$45,000
2026	5	092-Wake	Resurfacing	Cotesworth Dr	SR 1923	SR 4581	0.45	Full Depth Patching and 1.5" S9.5B	$98,000
2026	5	092-Wake	Resurfacing	Darmstadt Ct	SR 4519	Cul-de-sac	0.07	Full Depth Patching and 1.25" S9.5B	$13,000
2026	5	092-Wake	Resurfacing	Debenham Dr	SR 5151	Cul-de-sac	0.10	Full Depth Patching and 1.5" S9.5B	$19,000
2026	5	092-Wake	Resurfacing	Deer Forest Trl	SR 2005	SR 2007	0.66	Full Depth Patching and 1.5" S9.5B	$144,000
2026	5	092-Wake	Resurfacing	Dolphin Pl	SR 3864	Cul-de-sac	0.07	Full Depth Patching and 1.25" S9.5B	$14,000
2026	5	092-Wake	Resurfacing	Donlin Dr	SR 4597	END MAINT	0.15	Full Depth Patching and 1.25" S9.5B	$29,000
2026	5	092-Wake	Resurfacing	Dun Loring Dr	SR 4576	SR 5719	0.24	Full Depth Patching and 1.25" S9.5B	$47,000
2026	5	092-Wake	Resurfacing	Dunallie Dr	SR 2752	Cul-de-sac	0.26	Full Depth Patching and 1.25" S9.5B	$51,000
2026	5	092-Wake	Resurfacing	Ebenezer Church Rd	SR 1647	SR 1664	4.05	Full Depth Patching and 1.5" S9.5B	$1,102,000
2026	5	092-Wake	Resurfacing	Elsbeth Ct	SR 1979	Cul-de-sac	0.09	Full Depth Patching and 1.5" S9.5B	$17,000
2026	5	092-Wake	Resurfacing	Eric St	SR 1006	End Maintenance	0.11	Full Depth Patching and 1.5" S9.5B	$22,000
2026	5	092-Wake	Resurfacing	Falkirk Ridge Ct	SR 4519	Cul-de-sac	0.27	Full Depth Patching and 1.25" S9.5B	$53,000
2026	5	092-Wake	Resurfacing	Farmingdale Rd	SR 2770	SR 3772	0.24	Full Depth Patching and 1.5" S9.5B	$52,000
2026	5	092-Wake	Resurfacing	Farrier Ct	SR 3855	Cul-de-sac	0.03	Full Depth Patching and 1.5" S9.5B	$7,000
2026	5	092-Wake	Resurfacing	Forestville Rd	SR 5113	SR 2052	0.12	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$30,000
2026	5	092-Wake	Resurfacing	Forestville Rd	SR 5115	END MAINT	0.20	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$45,000
2026	5	092-Wake	Resurfacing	Fullard Dr	SR 1926	SR 4513	0.25	Full Depth Patching and 1.5" S9.5B	$54,000
2026	5	092-Wake	Resurfacing	Girth Ln	SR 3855	Cul-de-sac	0.10	Full Depth Patching and 1.5" S9.5B	$22,000
2026	5	092-Wake	Resurfacing	Glen Arbor Dr	SR 1390	Cul-de-sac	0.11	Full Depth Patching and 1.5" S9.5B	$22,000
2026	5	092-Wake	Resurfacing	Globe Rd	I-540	Dead End	0.71	Full Depth Patching and 1.5" S9.5B	$251,000
2026	5	092-Wake	Resurfacing	Harvey Johnson Rd	SR 2727	SR 2725	0.71	Full Depth Patching and 1.5" S9.5B	$155,000
2026	5	092-Wake	Resurfacing	Highgate Rd	SR 2849	Cul-de-sac	0.39	Full Depth Patching and 1.25" S9.5B	$76,000
2026	5	092-Wake	Resurfacing	Hillsborough St	Pavement Joint	U-4437 West Limits	0.42	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$174,000
2026	5	092-Wake	Resurfacing	Homestead Dr	SR 1652	END MAINT	0.48	Full Depth Patching and 1.5" S9.5B	$135,000
2026	5	092-Wake	Resurfacing	Horse Buggy Dr	SR 4810	Cul-de-sac	0.04	Full Depth Patching and 1.5" S9.5B	$7,000
2026	5	092-Wake	Resurfacing	Keighley Forest Dr	SR 1935	FRANKLIN CO	0.33	Full Depth Patching and 1.25" S9.5B	$58,000
2026	5	092-Wake	Resurfacing	Kendall Hill Rd	SR 1006	Dead End	0.24	Full Depth Patching and 1.5" S9.5B	$52,000
2026	5	092-Wake	Resurfacing	Kensington Manor Ln	SR 1926	Dead End	0.61	Full Depth Patching and 1.25" S9.5B	$119,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	5	092-Wake	Resurfacing	Kimmon Way	SR 1923	SR 4519	0.29	Full Depth Patching and 1.25" S9.5B	$56,000
2026	5	092-Wake	Resurfacing	Kingsbridge Ct	SR 4555	Cul-de-sac	0.07	Full Depth Patching and 1.25" S9.5B	$14,000
2026	5	092-Wake	Resurfacing	Laura Ashley Cir	Cul-de-sac	Cul-de-sac	0.25	Full Depth Patching and 1.25" S9.5B	$49,000
2026	5	092-Wake	Resurfacing	Laurel Field Cir	SR 5719	Cul-de-sac	0.07	Full Depth Patching and 1.25" S9.5B	$13,000
2026	5	092-Wake	Resurfacing	Laurelford Ln	Cul-de-sac	Cul-de-sac	0.53	Full Depth Patching and 1.5" S9.5B	$105,000
2026	5	092-Wake	Resurfacing	Livery Way	Cul-de-sac	Cul-de-sac	0.20	Full Depth Patching and 1.5" S9.5B	$38,000
2026	5	092-Wake	Resurfacing	Lorena Lynn Ct	Cul-de-sac	Cul-de-sac	0.20	Full Depth Patching and 1.25" S9.5B	$39,000
2026	5	092-Wake	Resurfacing	Lynn Rd	SR 1820	SR 1005	1.68	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,168,000
2026	5	092-Wake	Resurfacing	Matherly Dr	SR 1926	Cul-de-sac	0.46	Full Depth Patching and 1.5" S9.5B	$99,000
2026	5	092-Wake	Resurfacing	Matherly Dr	SR 1926	END MAINT	0.53	Full Depth Patching and 1.25" S9.5B	$104,000
2026	5	092-Wake	Resurfacing	Melcombe Way	SR 5719	Cul-de-sac	0.08	Full Depth Patching and 1.25" S9.5B	$16,000
2026	5	092-Wake	Resurfacing	Melcombe Way	SR 1926	SR 5719	0.32	Full Depth Patching and 1.5" S9.5B	$69,000
2026	5	092-Wake	Resurfacing	Melody Ln	SR 1650	SR 1652	0.22	Full Depth Patching and 1.5" S9.5B	$49,000
2026	5	092-Wake	Resurfacing	Meyerswood Dr	SR 1404	SR 1532	0.35	Full Depth Patching and 1.5" S9.5B	$76,000
2026	5	092-Wake	Resurfacing	Mid Pines Rd	Begin Pavement	SR 1009	1.10	Full Depth Patching and 1.5" S9.5B	$240,000
2026	5	092-Wake	Resurfacing	Mitchell Mill Rd	Pvmt. Jt. east of SR 2049	SR 2308	4.82	Full Depth Patching and 1.5" S9.5C	$1,170,000
2026	5	092-Wake	Resurfacing	N White St	Begin Maintenance	Franklin County	0.28	Full Depth Patching and 1.5" S9.5B	$61,000
2026	5	092-Wake	Resurfacing	NC 42	Harnett County	US 401	3.42	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$987,000
2026	5	092-Wake	Resurfacing	NC 42	SR 1006	NC 55	3.97	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,064,000
2026	5	092-Wake	Resurfacing	NC 50	Westerham Dr	Granville County	5.93	Full Depth Patching and 1.5" S9.5C	$1,670,000
2026	5	092-Wake	Resurfacing	New Brighton Dr	SR 1390	Cul-de-sac	0.29	Full Depth Patching and 1.5" S9.5B	$63,000
2026	5	092-Wake	Resurfacing	New Brighton Dr	SR 1390	Cul-de-sac	0.16	Full Depth Patching and 1.5" S9.5B	$35,000
2026	5	092-Wake	Resurfacing	New Forest Ln	SR 1923	Cul-de-sac	0.84	Full Depth Patching and 1.5" S9.5B	$165,000
2026	5	092-Wake	Resurfacing	New Oxford Dr	SR 1404	SR 3963	0.30	Full Depth Patching and 1.5" S9.5B	$66,000
2026	5	092-Wake	Resurfacing	Old Apex Rd	SR 3977	SR 1614	0.59	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$247,000
2026	5	092-Wake	Resurfacing	Old Stagecoach Ln	SR 1006	SR 3855	0.07	Full Depth Patching and 1.5" S9.5B	$15,000
2026	5	092-Wake	Resurfacing	Old US 1	Beg Div Hwy	End Divided	0.27	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$83,000
2026	5	092-Wake	Resurfacing	Old US 1	Beg Div Hwy	End Divided	0.23	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$71,000
2026	5	092-Wake	Resurfacing	Old US 1	NC 55	CHATHAM CO	8.70	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$2,110,000
2026	5	092-Wake	Resurfacing	Pageland Ct	SR 1912	Cul-de-sac	0.15	Full Depth Patching and 1.5" S9.5B	$28,000
2026	5	092-Wake	Resurfacing	Pamplona Dr	SR 1909	SR 1912	0.39	Full Depth Patching and 1.5" S9.5B	$86,000
2026	5	092-Wake	Resurfacing	Passenger Pl	Cul-de-sac	Cul-de-sac	0.64	Full Depth Patching and 1.5" S9.5B	$140,000
2026	5	092-Wake	Resurfacing	Penfold Ln	SR 1927	End Maintenance	0.13	Full Depth Patching and 1.5" S9.5B	$27,000
2026	5	092-Wake	Resurfacing	Pinecrest Rd	US 70	SR 1836	1.77	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$625,000
2026	5	092-Wake	Resurfacing	Powell Dr	NC 54	RR Tracks	0.06	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$16,000
2026	5	092-Wake	Resurfacing	Prather Pl	SR 1979	Cul-de-sac	0.08	Full Depth Patching and 1.5" S9.5B	$18,000
2026	5	092-Wake	Resurfacing	Quail Grove St	SR 2754	SR 4804	0.41	Full Depth Patching and 1.5" S9.5B	$80,000
2026	5	092-Wake	Resurfacing	Quail Point Dr	SR 1006	Cul-de-sac	0.12	Full Depth Patching and 1.5" S9.5B	$24,000
2026	5	092-Wake	Resurfacing	Ransdell Rd	Bengal Blvd	SR 1401	0.35	Full Depth Patching and 1.25" S9.5B	$74,000
2026	5	092-Wake	Resurfacing	Ransdell Rd	NC 55	North St	0.07	Full Depth Patching and 1.25" S9.5B	$14,000
2026	5	092-Wake	Resurfacing	Relay Way	SR 3764	Dead End	0.09	Full Depth Patching and 1.5" S9.5B	$18,000
2026	5	092-Wake	Resurfacing	Richland Dr	SR 1649	END MAINT	0.27	Full Depth Patching and 1.25" S9.5B	$47,000
2026	5	092-Wake	Resurfacing	Sentimental Ln	SR 1390	SR 4092	0.08	Full Depth Patching and 1.5" S9.5B	$17,000
2026	5	092-Wake	Resurfacing	Shield Cir	SR 2724	SR 2724	0.43	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$84,000
2026	5	092-Wake	Resurfacing	Shorrey Pl	SR 5719	Cul-de-sac	0.07	Full Depth Patching and 1.25" S9.5B	$13,000
2026	5	092-Wake	Resurfacing	Six Forks Rd	SR 1829	SR 2015	2.61	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$1,881,000
2026	5	092-Wake	Resurfacing	Six Forks Rd	SR 1847	SR 2002	1.53	Full Depth Patching and 1.5" S9.5C	$337,000
2026	5	092-Wake	Resurfacing	Soft Wind Dr	SR 2752	SR 3757	0.61	Full Depth Patching and 1.25" S9.5B	$119,000
2026	5	092-Wake	Resurfacing	South Meadow Rd	SR 2727	Dead End	0.89	Full Depth Patching and 1.5" S9.5B	$194,000
2026	5	092-Wake	Resurfacing	Southern Oaks Dr	Cul-de-sac	Cul-de-sac	0.33	Full Depth Patching and 1.5" S9.5B	$72,000
2026	5	092-Wake	Resurfacing	SR 1127 to US 1 N Ramp	SR 1127	US 1 North	0.20	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$54,000
2026	5	092-Wake	Resurfacing	SR 1127 to US 1 S Ramp	Chatham Co	US 1 South	0.17	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$45,000
2026	5	092-Wake	Resurfacing	Stageline Dr	SR 1006	SR 3855	0.38	Full Depth Patching and 1.5" S9.5B	$83,000
2026	5	092-Wake	Resurfacing	Star Rd	US 1 Alt	End Maintenance	1.17	Full Depth Patching and 1.5" S9.5B	$281,000
2026	5	092-Wake	Resurfacing	Stonecrest Ct	SR 3106	Cul-de-sac	0.06	Full Depth Patching and 1.25" S9.5B	$11,000
2026	5	092-Wake	Resurfacing	Stoneridge Dr	SR 1649	Dead End	0.48	Full Depth Patching and 1.25" S9.5B	$93,000
2026	5	092-Wake	Resurfacing	Stuarts Ridge Rd	E Whiter St	SR 2434	0.75	Full Depth Patching and 1.25" S9.5B	$145,000
2026	5	092-Wake	Resurfacing	Sunflower Meadows Ln	Cul-de-sac	GRANVILLE CO	0.25	Full Depth Patching and 1.25" S9.5B	$48,000
2026	5	092-Wake	Resurfacing	Surry Ridge Cir	SR 1152	Cul-de-sac	0.50	Full Depth Patching and 1.5" S9.5B	$98,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	5	092-Wake	Resurfacing	Theberton Way	SR 5151	Cul-de-sac	0.06	Full Depth Patching and 1.5" S9.5B	$12,000
2026	5	092-Wake	Resurfacing	Thornburg Dr	SR 2300	Cul-de-sac	0.48	Full Depth Patching and 1.25" S9.5B	$94,000
2026	5	092-Wake	Resurfacing	US 1 N to SR 1127 Ramp	US 1 North	SR 1127	0.16	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$42,000
2026	5	092-Wake	Resurfacing	US 1 North	SR 1134	Pavement Joint	6.47	Mill 2.0" and 2.0" S9.5C	$3,823,000
2026	5	092-Wake	Resurfacing	US 1 S to SR 1127 Ramp	US 1 South	SR 1127	0.15	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$41,000
2026	5	092-Wake	Resurfacing	US 1 South	Pavement Joint	Chatham Co	6.10	Mill 2.0" and 2.0" S9.5C	$3,818,000
2026	5	092-Wake	Resurfacing	Watkins Rd	SR 2224	SR 2217	1.99	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5B	$900,000
2026	5	092-Wake	Resurfacing	Wickershire Ct	SR 3533	Cul-de-sac	0.17	Full Depth Patching and 1.25" S9.5B	$33,000
2026	5	092-Wake	Resurfacing	Wild Duck Ct	SR 5722	Cul-de-sac	0.28	1.5" S9.5B	$67,000
2026	5	092-Wake	Resurfacing	Wind Haven Dr	SR 2752	SR 3717	0.21	Full Depth Patching and 1.25" S9.5B	$41,000
2026	5	092-Wake	Resurfacing	Windsong Valley Dr	SR 4598	Dead End	0.37	Full Depth Patching and 1.25" S9.5B	$72,000
2026	5	092-Wake	Resurfacing	Woodland Church Rd	GRANVILLE CO	GRANVILLE CO	0.24	Full Depth Patching and 1.5" S9.5B	$51,000
2026	5	092-Wake	Resurfacing	Wycombe Ridge Way	Cul-de-sac	FRANKLIN CO	0.26	Full Depth Patching and 1.25" S9.5B	$50,000
2026	5	092-Wake	Preservation	Baneberry Ct	SR 5514	Cul-de-sac	0.03	1.0" S9.5B	$4,000
2026	5	092-Wake	Preservation	Bent Branch Dr	Cul-de-sac	Cul-de-sac	0.31	1.0" S9.5B	$35,000
2026	5	092-Wake	Preservation	Bentcreek Dr	SR 1393	Cul-de-sac	0.46	1.0" S9.5B	$57,000
2026	5	092-Wake	Preservation	Birch Field St	SR 3818	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2026	5	092-Wake	Preservation	Bracken Ct	SR 2044	Cul-de-sac	0.08	1.0" S9.5B	$10,000
2026	5	092-Wake	Preservation	Bradleywood Dr	SR 5520	Cul-de-sac	0.09	1.0" S9.5B	$12,000
2026	5	092-Wake	Preservation	Bridgestone Ct	SR 3772	Cul-de-sac	0.03	1.0" S9.5B	$4,000
2026	5	092-Wake	Preservation	Brierley Hill Ct	SR 5240	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2026	5	092-Wake	Preservation	Care Free Cv	SR 1204	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2026	5	092-Wake	Preservation	Cavatina Ct	SR 3939	Cul-de-sac	0.09	1.0" S9.5B	$10,000
2026	5	092-Wake	Preservation	Chesters Hollow Dr	SR 5379	Dead End	0.26	1.0" S9.5B	$29,000
2026	5	092-Wake	Preservation	Clarincarde Ct	SR 4582	Cul-de-sac	0.27	1.0" S9.5B	$33,000
2026	5	092-Wake	Preservation	Cornerstone Ridge Dr	SR 4091	SR 4093	0.16	1.0" S9.5B	$20,000
2026	5	092-Wake	Preservation	Deer Brook St	NC 42	Cul-de-sac	0.33	1.0" S9.5B	$41,000
2026	5	092-Wake	Preservation	Dunn Rd	Falls Landing Dr	Begin Curb and Gutter	0.27	1.0" S9.5B	$61,000
2026	5	092-Wake	Preservation	Farm Meadow Rd	SR 3745	Dead End	0.10	1.0" S9.5B	$11,000
2026	5	092-Wake	Preservation	Full Meadow Pl	SR 3745	Cul-de-sac	0.03	1.0" S9.5B	$3,000
2026	5	092-Wake	Preservation	Gomar Ln	SR 4058	Cul-de-sac	0.12	1.0" S9.5B	$15,000
2026	5	092-Wake	Preservation	Green Tap Ct	SR 5376	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2026	5	092-Wake	Preservation	Greenhow Ln	SR 2044	Cul-de-sac	0.12	1.0" S9.5B	$15,000
2026	5	092-Wake	Preservation	Greenlea Dr	SR 1101	SR 1204	0.08	1.0" S9.5B	$10,000
2026	5	092-Wake	Preservation	Grren Knob Ct	SR 4058	Cul-de-sac	0.03	1.0" S9.5B	$4,000
2026	5	092-Wake	Preservation	GW Ct	SR 5379	Cul-de-sac	0.08	1.0" S9.5B	$9,000
2026	5	092-Wake	Preservation	Hay Meadow Ct	SR 3745	Cul-de-sac	0.10	1.0" S9.5B	$11,000
2026	5	092-Wake	Preservation	Haystack Cir	SR 3772	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2026	5	092-Wake	Preservation	Heritage Ct	SR 3046	Cul-de-sac	0.07	1.0" S9.5B	$16,000
2026	5	092-Wake	Preservation	Hilltop Rd	SR 2773	SR 2715	0.09	1.0" S9.5B	$10,000
2026	5	092-Wake	Preservation	Honeymoon Ct	SR 5520	Cul-de-sac	0.09	1.0" S9.5B	$12,000
2026	5	092-Wake	Preservation	Hubo Ct	SR 5379	Cul-de-sac	0.03	1.0" S9.5B	$3,000
2026	5	092-Wake	Preservation	Irene Way	SR 5376	Dead End	0.93	1.0" S9.5B	$104,000
2026	5	092-Wake	Preservation	Karen Dr	SR 1006	Cul-de-sac	0.17	1.0" S9.5B	$21,000
2026	5	092-Wake	Preservation	Kristiwood Ct	SR 5514	Cul-de-sac	0.11	1.0" S9.5B	$14,000
2026	5	092-Wake	Preservation	Lakeside Trl	SR 2773	SR 2831	0.25	1.0" S9.5B	$28,000
2026	5	092-Wake	Preservation	Light Falls Dr	SR 1907	Cul-de-sac	0.20	1.0" S9.5B	$24,000
2026	5	092-Wake	Preservation	Lightfoot Ct	SR 2044	Cul-de-sac	0.13	1.0" S9.5B	$16,000
2026	5	092-Wake	Preservation	Marsha Gayle Ct	Cul-de-sac	Cul-de-sac	0.12	1.0" S9.5B	$15,000
2026	5	092-Wake	Preservation	Meadow Rue Pl	SR 3745	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2026	5	092-Wake	Preservation	Meadow Sweet Ct	SR 3745	Cul-de-sac	0.04	1.0" S9.5B	$4,000
2026	5	092-Wake	Preservation	Micah Ln	SR 3741	Cul-de-sac	0.12	1.0" S9.5B	$15,000
2026	5	092-Wake	Preservation	Minnie Dr	Dead End	Dead End	0.61	1.0" S9.5B	$68,000
2026	5	092-Wake	Preservation	Oak Twig Dr	SR 3845	Cul-de-sac	0.11	1.0" S9.5B	$12,000
2026	5	092-Wake	Preservation	Old Clayton Rd	SR 1006	Cul-de-sac	0.15	1.0" S9.5B	$19,000
2026	5	092-Wake	Preservation	Overhill St	SR 2720	SR 2798	0.10	1.0" S9.5B	$12,000
2026	5	092-Wake	Preservation	Peak Ct	SR 4092	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2026	5	092-Wake	Preservation	Pine Ave	SR 2835	Hickory Ln	0.22	1.0" S9.5B	$25,000
2026	5	092-Wake	Preservation	Pinedale Rd	SR 1203	Cul-de-sac	0.18	1.0" S9.5B	$20,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	5	092-Wake	Preservation	Poplar Dr	SR 2774	SR 2832	0.27	1.0" S9.5B	$30,000
2026	5	092-Wake	Preservation	Red Inn Ct	SR 5376	Cul-de-sac	0.12	1.0" S9.5B	$14,000
2026	5	092-Wake	Preservation	River Park Dr	SR 4517	SR 4561	0.30	1.0" S9.5B	$37,000
2026	5	092-Wake	Preservation	Rocktree Ct	SR 3770	Cul-de-sac	0.04	1.0" S9.5B	$4,000
2026	5	092-Wake	Preservation	Sage Ct	SR 3772	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2026	5	092-Wake	Preservation	Sarahwood Ct	SR 5519	SR 5518	0.48	1.0" S9.5B	$59,000
2026	5	092-Wake	Preservation	Settlers Cir	SR 3046	Cul-de-sac	0.06	1.0" S9.5B	$14,000
2026	5	092-Wake	Preservation	Shanna Hills Dr	SR 5519	Dead End	0.20	1.0" S9.5B	$25,000
2026	5	092-Wake	Preservation	Silver Maple St	SR 3818	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2026	5	092-Wake	Preservation	Sloping Hill Ln	SR 3772	Cul-de-sac	0.15	1.0" S9.5B	$19,000
2026	5	092-Wake	Preservation	Spring Crest Ct	SR 4058	Cul-de-sac	0.13	1.0" S9.5B	$16,000
2026	5	092-Wake	Preservation	St Edmunds Ln	SR 1389	Cul-de-sac	0.18	1.0" S9.5B	$20,000
2026	5	092-Wake	Preservation	Sunray Ct	SR 3772	Cul-de-sac	0.03	1.0" S9.5B	$4,000
2026	5	092-Wake	Preservation	Sweet Chestnut Ln	SR 2510	Cul-de-sac	0.27	1.0" S9.5B	$30,000
2026	5	092-Wake	Preservation	Tallgrass Rd	SR 3745	Cul-de-sac	0.13	1.0" S9.5B	$15,000
2026	5	092-Wake	Preservation	Tee Box Ct	SR 4058	Cul-de-sac	0.03	1.0" S9.5B	$4,000
2026	5	092-Wake	Preservation	Tree Meadow Ln	SR 3745	Cul-de-sac	0.03	1.0" S9.5B	$3,000
2026	5	092-Wake	Preservation	Trevorwood Dr	SR 5516	Dead End	0.27	1.0" S9.5B	$33,000
2026	5	092-Wake	Preservation	Trouville Ct	SR 4501	Cul-de-sac	0.08	1.0" S9.5B	$10,000
2026	5	092-Wake	Preservation	Tynewind Dr	SR 4517	SR 4568	0.64	1.0" S9.5B	$80,000
2026	5	092-Wake	Preservation	Walking Trl	SR 3779	Cul-de-sac	0.09	1.0" S9.5B	$10,000
2026	5	092-Wake	Preservation	Walnut Green St	SR 4804	Cul-de-sac	0.06	1.0" S9.5B	$7,000
2026	5	092-Wake	Preservation	Welcome Dr	SR 1986	Cul-de-sac	0.22	1.0" S9.5B	$27,000
2026	5	092-Wake	Preservation	Winfree Ln	SR 2435	Cul-de-sac	0.16	1.0" S9.5B	$20,000
2026	5	092-Wake	Preservation	Wisley Way	SR 4568	Cul-de-sac	0.12	1.0" S9.5B	$13,000
2026	5	092-Wake	Preservation	Woodman Dr	SR 3772	Cul-de-sac	0.22	1.0" S9.5B	$27,000
2026	5	092-Wake	Preservation	Woodrose Lan	SR 2044	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2026	5	093-Warren	Resurfacing	Clark	SR 1703	Cul-de-sac	0.17	1.0" S9.5B	$19,000
2026	5	093-Warren	Resurfacing	Cove Drive	Cul-de-sac	Cul-de-sac	0.43	1.0" S9.5B	$48,000
2026	5	093-Warren	Resurfacing	Crosswinds	SR 1703	SR 1703	0.05	1.0" S9.5B	$6,000
2026	5	093-Warren	Resurfacing	East/West Oak Grove	Cul-de-sac	Cul-de-sac	0.24	1.0" S9.5B	$26,000
2026	5	093-Warren	Resurfacing	Hickory Ridge	SR 1373	Cul-de-sac	0.16	1.0" S9.5B	$17,000
2026	5	093-Warren	Resurfacing	Mariners Cove	SR 1336	SR 1498	0.17	1.0" S9.5B	$19,000
2026	5	093-Warren	Resurfacing	NC 58	NC 43	US 158 Bus	4.15	Full Depth Patching and 1.5" S9.5B	$904,000
2026	5	093-Warren	Resurfacing	Pine Ridge	SR 1373	SR 1399	0.11	1.0" S9.5B	$13,000
2026	5	093-Warren	Resurfacing	Quail Ridge	SR 1362	Cul-de-sac	1.33	1.0" S9.5B	$165,000
2026	5	093-Warren	Resurfacing	Quail Shores	SR 1373	Cul-de-sac	0.15	1.0" S9.5B	$17,000
2026	5	093-Warren	Resurfacing	Ridge Shore	SR 1336	Cul-de-sac	0.09	1.0" S9.5B	$10,000
2026	5	093-Warren	Resurfacing	Tower	SR 1123	Vance County	4.02	1.0" S9.5B	$449,000
2026	5	093-Warren	Resurfacing	US 1 Bus / US 158	Vance County	US 158 / 401	6.14	Full Depth Patching and 1.5" S9.5C	$1,559,000
2026	5	093-Warren	Resurfacing	US 158 Bus	End Curb and Gutter	158 Byp	4.13	Full Depth Patching and 1.5" S9.5B	$1,036,000
2026	5	093-Warren	Resurfacing	US 158 Bus	US 401	End Curb and Gutter	0.24	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$61,000
2026	5	093-Warren	Resurfacing	West Winds	SR 1336	Cul-de-sac	1.04	1.0" S9.5B	$116,000
2026	5	093-Warren	Preservation	Carroll Town	SR 1500	SR 1507	2.37	Full Depth Patching and Double Seal and Fog Seal	$234,000
2026	5	093-Warren	Preservation	Hester	SR 1305	US 158	0.91	Full Depth Patching and Double Seal and Fog Seal	$81,000
2026	5	093-Warren	Preservation	John Skinner	SR 1357	Cul-de-sac	2.33	Full Depth Patching and Double Seal and Fog Seal	$231,000
2026	5	093-Warren	Preservation	Occoneechee	SR 1636	Cul-de-sac	0.75	Full Depth Patching and Double Seal and Fog Seal	$67,000
2026	5	093-Warren	Preservation	Pritchett	US 401	Cul-de-sac	1.53	Full Depth Patching and Double Seal and Fog Seal	$168,000
2026	5	093-Warren	Preservation	White Rock Church	SR 1519	Cul-de-sac	0.14	Full Depth Patching and Double Seal and Fog Seal	$12,000
2026	6	009-Bladen	Resurfacing	NC 131	Columbus Co	SCL Bladenboro	4.77	Mill 1.5" and 1.5" S9.5C	$1,908,000
2026	6	009-Bladen	Resurfacing	NC 87	Columbus County	SR 1725	10.42	Mill 1.5" and 1.5" S9.5C	$4,168,000
2026	6	009-Bladen	Preservation	SR 1003	NC 242	NC 410	7.51	Seal - Double	$287,000
2026	6	009-Bladen	Preservation	SR 1100	NC 41	NC 131	11.29	Seal - Double	$450,000
2026	6	009-Bladen	Preservation	SR 1107	NC 410	NC 410	2.44	Seal - Double	$87,500
2026	6	009-Bladen	Preservation	SR 1109	SR 1107	Cul-De-Sac	0.60	Seal - Double	$18,500
2026	6	009-Bladen	Preservation	SR 1110	SR 1107	Cul-De-Sac	0.56	Seal - Double	$18,500
2026	6	009-Bladen	Preservation	SR 1111	SR 1003	Cul-De-Sac	0.50	Seal - Double	$17,500
2026	6	009-Bladen	Preservation	SR 1112	SR 1114	Dead End	0.74	Seal - Double	$26,200
2026	6	009-Bladen	Preservation	SR 1113	SR 1114	Dead End	0.59	Seal - Double	$18,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	6	009-Bladen	Preservation	SR 1114	NC 242	NC 131	3.57	Seal - Double	$125,000
2026	6	009-Bladen	Preservation	SR 1115	SR 1114	NC 242	1.76	Seal - Double	$62,500
2026	6	009-Bladen	Preservation	SR 1116	SR 1114	SR 1114	3.36	Seal - Double	$118,500
2026	6	009-Bladen	Preservation	SR 1117	NC 242	NC 410	1.51	Seal - Double	$53,000
2026	6	009-Bladen	Preservation	SR 1118	NC 410	SR 1117	1.01	Seal - Double	$36,200
2026	6	009-Bladen	Preservation	SR 1148	SR 1150	SR 1145	0.68	Seal - Double	$22,500
2026	6	009-Bladen	Preservation	SR 1150	NC 87	SR 1003	2.27	Seal - Double	$94,000
2026	6	009-Bladen	Preservation	SR 1151	SR 1150	NC 242	0.43	Seal - Double	$13,700
2026	6	009-Bladen	Preservation	SR 1153	SR 1150	SR 1155	0.88	Seal - Double	$28,700
2026	6	009-Bladen	Preservation	SR 1173	Columbus Co.	Columbus Co.	0.76	Seal - Double	$27,000
2026	6	009-Bladen	Preservation	SR 1196	NC 131	Dead End	0.60	Seal - Double	$22,000
2026	6	009-Bladen	Preservation	SR 1200	SR 1150	Dead End	0.36	Seal - Double	$12,500
2026	6	009-Bladen	Preservation	SR 1207	SR 1114	End Pavement	0.30	Seal - Double	$10,000
2026	6	009-Bladen	Preservation	SR 1209	NC 242	End Maint	0.62	Seal - Double	$23,000
2026	6	009-Bladen	Preservation	SR 1212	SR 1150	SR 1145	0.74	Seal - Cape	$43,500
2026	6	009-Bladen	Preservation	SR 1221	SR 1107	Dead End	0.18	Seal - Double	$5,250
2026	6	009-Bladen	Preservation	SR 1224	SR 1145	Dead End	0.22	Seal - Double	$7,500
2026	6	009-Bladen	Preservation	SR 1230	SR 1150	Cul De Sac	0.65	Seal - Double	$21,250
2026	6	009-Bladen	Preservation	SR 1231	SR 1200	Dead End	0.14	Seal - Double	$5,000
2026	6	009-Bladen	Preservation	SR 1233	SR 1145	US 701	0.50	Seal - Double	$16,250
2026	6	009-Bladen	Preservation	SR 1238	SR 1237	Dead End	0.19	Seal - Double	$6,250
2026	6	009-Bladen	Preservation	SR 1338	SR 1339	SR 1336	1.90	Seal - Double	$62,500
2026	6	009-Bladen	Preservation	SR 1339	SR 1336	NC 87	2.69	Seal - Double	$100,000
2026	6	009-Bladen	Preservation	SR 1359	SR 1338	Dead End	0.29	Seal - Double	$10,000
2026	6	024-Columbus	Resurfacing	NC 131	US 701	Bladen Co	4.18	1.5" S9.5C	$1,672,000
2026	6	024-Columbus	Resurfacing	NC 211	NC 214	Bladen Co.	4.95	1.5" S9.5C	$1,980,000
2026	6	024-Columbus	Resurfacing	NC 410	SC Line	US 701 Bus	0.52	Mill 1.5" and 1.5" S9.5B	$208,000
2026	6	024-Columbus	Resurfacing	SR 1005	SR 1125	NC 904	0.14	1.5" S9.5B	$28,000
2026	6	024-Columbus	Resurfacing	SR 1125	SC LINE	SR 1005	0.82	1.5" S9.5B	$164,000
2026	6	024-Columbus	Resurfacing	SR 1166	SR 1170	US 701	1.30	1.5" S9.5B	$260,000
2026	6	024-Columbus	Resurfacing	SR 1170	US 701	SR 1166	0.81	1.5" S9.5B	$162,000
2026	6	024-Columbus	Resurfacing	SR 1170	SR 1166	NC 130	1.70	1.5" S9.5B	$340,000
2026	6	024-Columbus	Resurfacing	SR 1301	SC Line	NC 410	1.09	1.5" S9.5B	$272,500
2026	6	024-Columbus	Resurfacing	SR 1302	SR 1301	SR 1303	0.45	1.5" S9.5B	$112,500
2026	6	024-Columbus	Resurfacing	SR 1303	SC Line	NC 904	1.26	1.5" S9.5B	$315,000
2026	6	024-Columbus	Resurfacing	SR 1540	NC 131	SR 1003	1.58	1.5" S9.5B	$316,000
2026	6	024-Columbus	Resurfacing	SR 1549	SR 1585	US 701	1.61	1.5" S9.5B	$322,000
2026	6	024-Columbus	Resurfacing	SR 1551	US 701	SR 1549	0.73	1.5" S9.5B	$146,000
2026	6	024-Columbus	Resurfacing	SR 1567	US 74 Bus	SR 1552	0.38	1.5" S9.5B	$76,000
2026	6	024-Columbus	Resurfacing	SR 1585	US 74 Bus	SR 1552	1.77	1.5" S9.5B	$354,000
2026	6	024-Columbus	Resurfacing	SR 1754	SR 1550	Dead End	0.13	1.5" S9.5B	$26,000
2026	6	024-Columbus	Preservation	SR 1317	SR 1004	NC 410	2.44	Seal - Double	$75,000
2026	6	024-Columbus	Preservation	SR 1356	SR 1004	US 76	1.51	Seal - Double	$56,200
2026	6	024-Columbus	Preservation	SR 1401	SR 1352	SR 1405	2.64	Seal - Double	$93,700
2026	6	024-Columbus	Preservation	SR 1402	SR 1403	SR 1401	0.99	Seal - Double	$37,500
2026	6	024-Columbus	Preservation	SR 1403	SR 1356	WCL Cerro Gordo	1.97	Seal - Double	$68,700
2026	6	024-Columbus	Preservation	SR 1404	SR 1403	US 76	0.67	Seal - Double	$23,700
2026	6	024-Columbus	Preservation	SR 1405	SR 1401	Cul De Sac	0.60	Seal - Double	$21,250
2026	6	024-Columbus	Preservation	SR 1406	SR 1407	US 76	0.12	Seal - Double	$3,750
2026	6	024-Columbus	Preservation	SR 1408	SR 1407	SR 1410	0.07	Seal - Double	$2,500
2026	6	024-Columbus	Preservation	SR 1410	SR 1408	SR 1004	4.11	Seal - Double	$131,000
2026	6	024-Columbus	Preservation	SR 1411	SR 1452	SR 1410	0.82	Seal - Double	$27,500
2026	6	024-Columbus	Preservation	SR 1412	SR 1300	SR 1415	4.35	Seal - Double	$156,180
2026	6	024-Columbus	Preservation	SR 1413	SR 1412	SR 1410	1.75	Seal - Double	$62,480
2026	6	024-Columbus	Preservation	SR 1414	US 76	NC 410	5.01	Seal - Double	$281,000
2026	6	024-Columbus	Preservation	SR 1415	US 76	SR 1410	2.69	Seal - Double	$106,000
2026	6	024-Columbus	Preservation	SR 1416	SR 1414	SR 1414	1.69	Seal - Double	$62,500
2026	6	024-Columbus	Preservation	SR 1417	SR 1412	SR 1004	1.61	Seal - Double	$62,500
2026	6	024-Columbus	Preservation	SR 1418	SR 1300	SR 1004	1.28	Seal - Double	$46,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	6	024-Columbus	Preservation	SR 1420	SR 1300	SR 1317	1.35	Seal - Double	$47,000
2026	6	024-Columbus	Preservation	SR 1421	SR 1317	SR 1422	1.97	Seal - Double	$68,700
2026	6	024-Columbus	Preservation	SR 1422	SR 1300	SR 1421	1.56	Seal - Split	$56,000
2026	6	024-Columbus	Preservation	SR 1423	Collins St	Dead End	0.56	Seal - Double	$20,000
2026	6	024-Columbus	Preservation	SR 1442	Dead End	SR 1317	1.07	Seal - Double	$37,500
2026	6	024-Columbus	Preservation	SR 1448	SR 1422	Dead End	0.42	Seal - Double	$16,000
2026	6	026-Cumberland	Resurfacing	NC 24	HARNETT CO	NC 210	3.59	Mill 1.5" and 1.5" S9.5C	$1,800,000
2026	6	026-Cumberland	Resurfacing	SR 1006	SR 2842	SAMPSON CO	5.65	1.5" S9.5B	$875,000
2026	6	026-Cumberland	Resurfacing	SR 1108	Hoke Co	SR 1112	1.84	1.5" S9.5B	$280,250
2026	6	026-Cumberland	Resurfacing	SR 1110	SR 1109	SR 1112	0.91	1.5" S9.5B	$125,150
2026	6	026-Cumberland	Resurfacing	SR 1116	SR 1117	SR 1288	1.19	1.5" S9.5B	$171,350
2026	6	026-Cumberland	Resurfacing	SR 1288	SR 1116	DEAD END	1.82	1.5" S9.5B	$240,000
2026	6	026-Cumberland	Resurfacing	SR 1344	SR 1141	US 301 / I95 BUS	1.67	Mill 1.5" and 1.5" S9.5B	$800,000
2026	6	026-Cumberland	Resurfacing	SR 1414	US 401 BUS	SR 1404	1.49	Mill 1.5" and 1.5" S9.5B	$384,750
2026	6	026-Cumberland	Resurfacing	SR 1606	SR 1605	SR 1607	1.73	1.5" S9.5B	$260,450
2026	6	026-Cumberland	Resurfacing	SR 1607	US 401	Harnett Co	2.62	1.5" S9.5B	$375,000
2026	6	026-Cumberland	Resurfacing	SR 1609	HARNETT CO	US 401	1.27	1.5" S9.5B	$229,000
2026	6	026-Cumberland	Resurfacing	SR 1798	SR 1600	HARNETT CO	0.09	1.5" S9.5B	$14,850
2026	6	026-Cumberland	Resurfacing	SR 1863	SR 1933	DEADEND	0.20	1.5" S9.5B	$33,000
2026	6	026-Cumberland	Resurfacing	SR 1933	US 13	US 301	0.84	1.5" S9.5B	$138,600
2026	6	026-Cumberland	Resurfacing	SR 2212	NC 87	SR 2308	3.44	1.5" S9.5B	$450,000
2026	6	026-Cumberland	Resurfacing	SR 2244	ROBESON CO	SR 2252	2.04	5.0" B25.0B	$224,400
2026	6	026-Cumberland	Resurfacing	SR 2245	NC 87	NC 87	2.27	5.0" B25.0B	$249,700
2026	6	026-Cumberland	Resurfacing	SR 2252	SR 3947	BLADEN CO	6.67	1.5" S9.5B	$1,200,000
2026	6	026-Cumberland	Resurfacing	SR 2333	SR 2252	DEAD END	2.31	1.5" S9.5B	$365,985
2026	6	026-Cumberland	Resurfacing	SR 2378	SR 2333	SR 3935	0.40	1.5" S9.5C	$65,505
2026	6	026-Cumberland	Resurfacing	SR 3915	SR 2333	DEAD END	0.50	1.5" S9.5C	$82,500
2026	6	026-Cumberland	Resurfacing	SR 3935	SR 2378	SR 2220	0.45	1.5" S9.5C	$74,250
2026	6	026-Cumberland	Resurfacing	SR 3948	SR 2333	DEAD END	0.18	1.5" S9.5C	$29,700
2026	6	026-Cumberland	Resurfacing	SR 4626	SR 1141	US 301 / 95 BUS	0.37	Mill 1.5" and 1.5" S9.5B	$122,430
2026	6	026-Cumberland	Resurfacing	US 401	OUTER LOOP	SR 3589	0.74	Mill 1.5" and 1.5" S9.5C	$137,800
2026	6	026-Cumberland	Resurfacing	US 401	SR 3589	OUTER LOOP	0.73	Mill 1.5" and 1.5" S9.5C	$135,600
2026	6	026-Cumberland	Resurfacing	US 401 Byp	NC 24	NC 210	2.23	Mill 2.0" and 2.0" S9.5C	$1,100,000
2026	6	026-Cumberland	Preservation	SR 1709	SR 1802	DEAD END	0.45	Seal - Split	$15,000
2026	6	026-Cumberland	Preservation	SR 1732	US 301	CUL DE SAC	0.61	Seal - Split	$21,200
2026	6	026-Cumberland	Preservation	SR 1800	HARNETT CO	NC 82	2.64	Seal - Split	$81,000
2026	6	026-Cumberland	Preservation	SR 1801	SR 1800	NC 82	0.46	Seal - Split	$12,500
2026	6	026-Cumberland	Preservation	SR 1803	SR 1800	US 301	0.89	Seal - Split	$25,000
2026	6	026-Cumberland	Preservation	SR 1804	US 301	HARNETT CO.	2.36	Seal - Split	$76,200
2026	6	026-Cumberland	Preservation	SR 1805	SR 1804	HARNETT CO.	0.29	Seal - Split	$8,500
2026	6	026-Cumberland	Preservation	SR 1806	US 301	NC 82	4.12	Seal - Split	$150,000
2026	6	026-Cumberland	Preservation	SR 1807	SR 1806	DEAD END	1.10	Seal - Split	$37,500
2026	6	026-Cumberland	Preservation	SR 1811	US 13	SR 1806	2.38	Seal - Split	$81,000
2026	6	026-Cumberland	Preservation	SR 1812	SR 1802	NC 82	0.88	Seal - Split	$25,000
2026	6	026-Cumberland	Preservation	SR 1813	US 301	SR 1819	2.93	Seal - Split	$107,500
2026	6	026-Cumberland	Preservation	SR 1814	SR 1813	SR 1815	1.50	Seal - Split	$52,500
2026	6	026-Cumberland	Preservation	SR 1817	SR 1005	SR 1819	0.87	Seal - Split	$27,500
2026	6	026-Cumberland	Preservation	SR 1818	US 13	SR 1005	1.69	Seal - Split	$56,000
2026	6	026-Cumberland	Preservation	SR 1856	BEG PVMT	SR 1815	0.50	Seal - Split	$15,000
2026	6	026-Cumberland	Preservation	SR 1857	SR 1815	DEAD END	0.69	Seal - Split	$18,500
2026	6	026-Cumberland	Preservation	SR 1858	SR 1806	CUL DE SAC	0.30	Seal - Split	$10,000
2026	6	026-Cumberland	Preservation	SR 1859	NC 82	SR 1806	1.36	Seal - Split	$50,000
2026	6	026-Cumberland	Preservation	SR 1860	I 95 Off Ramp	End Maint	1.02	Seal - Split	$38,730
2026	6	026-Cumberland	Preservation	SR 1875	NC 82	Dead End	0.41	Seal - Split	$13,700
2026	6	026-Cumberland	Preservation	SR 1902	US 301	Dead End	0.33	Seal - Split	$10,000
2026	6	026-Cumberland	Preservation	SR 1936	US 13	DEAD END	0.06	Seal - Split	$3,000
2026	6	043-Harnett	Resurfacing	NC 217	BRIDGE	NC 82	0.77	Mill 1.5" and 1.5" S9.5B	$169,400
2026	6	043-Harnett	Resurfacing	NC 82	NC 217	US 421	1.38	Mill 1.5" and 1.5" S9.5B	$285,500
2026	6	043-Harnett	Resurfacing	SR 1121	Beginning of Project	SR 1117	1.79	1.5" S9.5B	$267,900

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	6	043-Harnett	Resurfacing	SR 1281	SR 1291	SR 1291	1.16	1.5" S9.5B	$174,150
2026	6	043-Harnett	Resurfacing	SR 1319	US 421	US 401	0.52	2.5" I19.0B and 1.5" S9.5B	$200,000
2026	6	043-Harnett	Resurfacing	SR 1542	NC 55	SR 1516	4.69	1.5" S9.5B	$660,000
2026	6	043-Harnett	Resurfacing	SR 1542	SR 1516	US 421	1.91	1.5" S9.5B and Widen	$410,000
2026	6	043-Harnett	Resurfacing	SR 1700	Coats CL	NC 55	1.64	1.5" S9.5B	$245,850
2026	6	043-Harnett	Resurfacing	SR 1735	NC 82	SR 1718	2.00	Mill 1.5" and 1.5" S9.5B	$370,000
2026	6	043-Harnett	Resurfacing	SR 1740	RAIFORD RD	SR 1735	0.64	1.5" S9.5B	$105,600
2026	6	043-Harnett	Resurfacing	SR 1815	US 421	SR 1735	0.41	1.5" S9.5B	$67,650
2026	6	043-Harnett	Resurfacing	SR 2024	SR 2027	SR 2026	3.57	1.5" S9.5B	$510,000
2026	6	043-Harnett	Resurfacing	SR 2027	US 401	NC 217	1.05	1.5" S9.5B	$173,250
2026	6	043-Harnett	Resurfacing	SR 2030	US 401	SR 2045	5.77	5.0" B25.0B	$575,000
2026	6	043-Harnett	Resurfacing	SR 2036	SR 2030	SR 2072	3.54	1.5" S9.5B	$530,000
2026	6	043-Harnett	Resurfacing	SR 2067	NC 210	SR 2030	2.65	1.5" S9.5B	$345,000
2026	6	043-Harnett	Resurfacing	SR 2084	PVMNT CHG	NC 27	1.19	1.5" S9.5B	$196,350
2026	6	078-Robeson	Resurfacing	NC 710	NC 711	SR 1345	4.91	1.5" S9.5C	$982,000
2026	6	078-Robeson	Resurfacing	NC 711	Nc 710	SR 1561	1.37	1.5" S9.5B	$280,000
2026	6	078-Robeson	Resurfacing	SR 1003	SR 1155	NC 211	10.54	1.5" S9.5B	$2,000,000
2026	6	078-Robeson	Resurfacing	SR 1104	SCOTLAND CO.	SR 1101	3.96	1.5" S9.5B	$720,000
2026	6	078-Robeson	Resurfacing	SR 1170	SR 1153	NC 130	4.01	1.5" S9.5B	$720,000
2026	6	078-Robeson	Resurfacing	SR 1506	NC 72	NC 211	1.70	1.5" S9.5B	$340,000
2026	6	078-Robeson	Resurfacing	SR 1509	SR 1318	SR 1318	2.45	1.5" S9.5B	$480,000
2026	6	078-Robeson	Resurfacing	SR 1521	SR 1318	NC 72	6.19	1.5" S9.5B and Widen	$1,240,000
2026	6	078-Robeson	Resurfacing	SR 1672	SR 1528	DEAD END	0.13	1.0" S9.5B	$15,600
2026	6	078-Robeson	Resurfacing	SR 1714	SR 1712	SR 1731	2.27	1.5" S9.5B	$440,000
2026	6	078-Robeson	Resurfacing	SR 1725	NC 71	SR 1727	3.51	1.5" S9.5A	$600,000
2026	6	078-Robeson	Resurfacing	SR 2208	NC 41	NC130	8.74	1.5" S9.5B	$1,740,000
2026	6	078-Robeson	Resurfacing	SR 2218	SR 2214	SR 2220	0.98	1.5" S9.5B	$195,000
2026	6	078-Robeson	Resurfacing	SR 2236	SR 1003	NC 41	0.76	1.5" S9.5B	$152,000
2026	6	078-Robeson	Resurfacing	SR 2280	DEAD END	SR 2277	0.95	1.5" S9.5B	$180,000
2026	6	078-Robeson	Resurfacing	SR 2282	NC 904	SC LINE	2.95	1.5" S9.5B	$540,000
2026	6	078-Robeson	Resurfacing	SR 2283	SR 2282	SR 2282	2.55	1.5" S9.5A	$500,000
2026	6	078-Robeson	Resurfacing	SR 2285	NC 904	SR 2282	0.84	1.5" S9.5B	$160,000
2026	6	078-Robeson	Resurfacing	SR 2327	SR 2218	Dead End	0.10	1.0" S9.5B	$15,000
2026	6	078-Robeson	Resurfacing	SR 2448	SR 2449	SR 2453	1.87	1.5" S9.5B	$350,000
2026	6	078-Robeson	Resurfacing	SR 2466	SR 2455	SR 2435	1.85	1.5" S9.5A	$370,000
2026	6	078-Robeson	Preservation	SR 1107	SCOTLND CO	US 501	4.74	Seal - Split	$172,000
2026	6	078-Robeson	Preservation	SR 1155	SR 2435	US 301	3.11	Seal - Split	$112,500
2026	6	078-Robeson	Preservation	SR 2435	SR 2464	NC 130	0.94	Seal - Split	$37,500
2026	6	078-Robeson	Preservation	SR 2435	SR 2466	SR 2464	2.22	Seal - Triple	$81,200
2026	6	078-Robeson	Preservation	SR 2459	SR 2519	SR 2435	1.85	Seal - Split	$68,500
2026	6	078-Robeson	Preservation	SR 2460	US 301	SR 2519	2.12	Seal - Split	$62,500
2026	6	078-Robeson	Preservation	SR 2462	SR 2489	SR 2463	3.44	Seal - Split	$127,000
2026	6	078-Robeson	Preservation	SR 2464	NC 130	SR 2435	1.12	Seal - Split	$37,400
2026	6	078-Robeson	Preservation	SR 2465	NC 130	SC SL	6.68	Seal - Split	$245,000
2026	6	078-Robeson	Preservation	SR 2466	SR 2455	SR 2435	1.85	Seal - Split	$62,500
2026	6	078-Robeson	Preservation	SR 2468	NC 130	SR 2465	1.01	Seal - Split	$3,100
2026	6	078-Robeson	Preservation	SR 2490	S 2489	SR 2491	0.60	Seal - Split	$18,500
2026	6	078-Robeson	Preservation	SR 2491	SR 2492	SR 2462	1.56	Seal - Split	$56,200
2026	6	078-Robeson	Preservation	SR 2492	SC SL	NC 130	2.75	Seal - Triple	$87,460
2026	6	078-Robeson	Preservation	SR 2493	SR 2465	SR 2494	1.01	Seal - Split	$37,500
2026	6	078-Robeson	Preservation	SR 2494	SC SL	NC 130	2.30	Seal - Split	$81,200
2026	6	078-Robeson	Preservation	SR 2495	US 301	DE	0.90	Seal - Split	$31,000
2026	6	078-Robeson	Preservation	SR 2504	SR 2460	DE	0.60	Seal - Split	$21,000
2026	6	078-Robeson	Preservation	SR 2517	US 301	DE	0.44	Seal - Triple	$25,000
2026	6	078-Robeson	Preservation	SR 2518	NC 130	END PVMT	0.11	Seal - Split	$6,200
2026	6	078-Robeson	Preservation	SR 2519	US 301	SR 1155	3.63	Seal - Split	$143,600
2026	7	001-Alamance	Resurfacing	Baker Bell farm Rd.	SR 1584	SR 1002	1.44	#78 Mat Seal and 1.5" S9.5B	$381,630
2026	7	001-Alamance	Resurfacing	Barrington Rd.	Elon Ossipee Rd.	DEAD END	0.14	#78 Mat Seal and 1.5" S9.5B	$37,200
2026	7	001-Alamance	Resurfacing	Barton Ct.	Wimbeley Dr.	Dead End	0.05	#78 Mat Seal and 1.5" S9.5B	$13,300

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	7	001-Alamance	Resurfacing	Byers Ct.	SR 2627	CUL-DE-SAC	0.06	#78 Mat Seal and 1.5" S9.5B	$15,901
2026	7	001-Alamance	Resurfacing	Carlton Ave.	Dead End	Dead End	0.26	#78 Mat Seal and 1.5" S9.5B	$68,900
2026	7	001-Alamance	Resurfacing	Cook St.	SR 2131	OCL	1.21	#78 Mat Seal and 1.5" S9.5B	$320,670
2026	7	001-Alamance	Resurfacing	Dogwood St.	Dead End	Dead End	0.35	#78 Mat Seal and 1.5" S9.5B	$92,800
2026	7	001-Alamance	Resurfacing	E. Haggard Ave.	University Dr.	C & G	0.84	#78 Mat Seal and 1.5" S9.5B	$222,612
2026	7	001-Alamance	Resurfacing	E. Haggard Ave.	C & G	Oak Ave.	0.48	Mill 1.5" and 1.5" S9.5B	$253,795
2026	7	001-Alamance	Resurfacing	Elon Court	Springfield Dr.	Dead End	0.02	#78 Mat Seal and 1.5" S9.5B	$5,300
2026	7	001-Alamance	Resurfacing	Garner Rd.	SR 1005	NC 49	1.19	#78 Mat Seal and 1.5" S9.5B	$315,377
2026	7	001-Alamance	Resurfacing	Gibson Rd.	SR 1928	US 70	3.85	#78 Mat Seal and 1.5" S9.5B	$1,020,305
2026	7	001-Alamance	Resurfacing	Golden Oaks Dr.	SR 2121	CUL-DE-SAC	0.30	#78 Mat Seal and 1.5" S9.5B	$79,600
2026	7	001-Alamance	Resurfacing	Gordon St.	Riverview Rd.	Burch Bridge Rd.	0.32	#78 Mat Seal and 1.5" S9.5B	$84,850
2026	7	001-Alamance	Resurfacing	Hamilton Rd.	Greenwood Dr.	Rockledge Dr.	0.23	#78 Mat Seal and 1.5" S9.5B	$60,960
2026	7	001-Alamance	Resurfacing	Hiawatha Ct.	Indian Valley Dr.	Dead End	0.08	#78 Mat Seal and 1.5" S9.5B	$21,200
2026	7	001-Alamance	Resurfacing	Hiawatha Place	SR 1677	DEAD END	0.08	#78 Mat Seal and 1.5" S9.5B	$26,501
2026	7	001-Alamance	Resurfacing	Indian Valley Dr.	Greenwood Dr..	Greenwood Dr.	1.13	#78 Mat Seal and 1.5" S9.5B	$299,500
2026	7	001-Alamance	Resurfacing	Isley Lane	SR 1146	DEAD END	0.10	#78 Mat Seal and 1.5" S9.5B	$26,502
2026	7	001-Alamance	Resurfacing	Judge Sharpe Rd.	NC 87	DEAD END	0.81	#78 Mat Seal and 1.5" S9.5B	$214,700
2026	7	001-Alamance	Resurfacing	Lacy Ncole Dr.	SR 2287	CUL-DE-SAC	0.28	#78 Mat Seal and 1.5" S9.5B	$74,250
2026	7	001-Alamance	Resurfacing	Lazy Lane	SR 2627	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$18,550
2026	7	001-Alamance	Resurfacing	Major Hill Rd.	SR 2356	SR 1003	2.86	#78 Mat Seal and 1.5" S9.5B	$757,940
2026	7	001-Alamance	Resurfacing	Mattie Florence Dr.	CUL-DE-SAC	CUL-DE-SAC	0.84	#78 Mat Seal and 1.5" S9.5B	$222,611
2026	7	001-Alamance	Resurfacing	McCray Rd.	SR 1001	NC 49	5.08	#78 Mat Seal and 1.5" S9.5B	$1,351,572
2026	7	001-Alamance	Resurfacing	Mineral Springs Rd.	NC 54	SR 2142	2.55	#78 Mat Seal and 1.5" S9.5B	$680,000
2026	7	001-Alamance	Resurfacing	Misty Hollow Ct.	SR 2610	CUL-DE-SAC	0.12	#78 Mat Seal and 1.5" S9.5B	$31,900
2026	7	001-Alamance	Resurfacing	Misty Hollow Lane	SR 2121	SR 2610	0.09	#78 Mat Seal and 1.5" S9.5B	$23,900
2026	7	001-Alamance	Resurfacing	Oakridge Dr.	SR 2231	SR 2231	0.22	#78 Mat Seal and 1.5" S9.5B	$55,652
2026	7	001-Alamance	Resurfacing	Pincroft Dr.	St. Regis Dr.	Pollard Ave.	0.38	#78 Mat Seal and 1.5" S9.5B	$100,720
2026	7	001-Alamance	Resurfacing	Pollard Ave.	Burch Bridge Rd.	Durham St.	0.37	#78 Mat Seal and 1.5" S9.5B	$98,100
2026	7	001-Alamance	Resurfacing	Riverview Dr.	Gordon St.	Durham St.	0.25	#78 Mat Seal and 1.5" S9.5B	$66,250
2026	7	001-Alamance	Resurfacing	Shelley Graham Rd.	SR 2116	CUL-DE-SAC	0.68	#78 Mat Seal and 1.5" S9.5B	$180,210
2026	7	001-Alamance	Resurfacing	Snug Harbor Rd.	Greenwood Dr.	Isley School Rd.	0.28	#78 Mat Seal and 1.5" S9.5B	$74,200
2026	7	001-Alamance	Resurfacing	Springfield Dr.	Elon ossipee Rd.	Dead End	0.28	#78 Mat Seal and 1.5" S9.5B	$74,250
2026	7	001-Alamance	Resurfacing	St. Regis Dr.	Riverview Dr.	Burch Bridge Rd.	0.32	#78 Mat Seal and 1.5" S9.5B	$84,850
2026	7	001-Alamance	Resurfacing	Stanton Ct.	SR 2632	CUL-DE-SAC	0.13	#78 Mat Seal and 1.5" S9.5B	$34,500
2026	7	001-Alamance	Resurfacing	Stockard Rd.	NC 87	CUL-DE-SAC	3.36	#78 Mat Seal and 1.5" S9.5B	$890,550
2026	7	001-Alamance	Resurfacing	Varnals Ct.	SR 2632	CUL-DE-SAC	0.09	#78 Mat Seal and 1.5" S9.5B	$23,860
2026	7	001-Alamance	Resurfacing	Whispering Winds Rd.	Indian Valley Dr.	Indian Valley Dr.	0.25	#78 Mat Seal and 1.5" S9.5B	$66,250
2026	7	001-Alamance	Resurfacing	Widow Foster Rd.	SR 1002	SR 1583	1.47	#78 Mat Seal and 1.5" S9.5B	$389,600
2026	7	001-Alamance	Resurfacing	William Newlin Dr.	SR 2627	SR 2632	0.30	#78 Mat Seal and 1.5" S9.5B	$79,550
2026	7	001-Alamance	Resurfacing	Wimbeley Dr.	Springfield Dr.	Barrington Rd.	0.13	#78 Mat Seal and 1.5" S9.5B	$34,500
2026	7	001-Alamance	Resurfacing	Woodside Ave.	SR 2158	CUL-DE-SAC	0.82	#78 Mat Seal and 1.5" S9.5B	$220,000
2026	7	001-Alamance	Resurfacing	Workman Rd.	SR 1004	SR 2356	1.62	#78 Mat Seal and 1.5" S9.5B	$429,330
2026	7	001-Alamance	Resurfacing	Yamota Dr.	Snug Harbor Rd.	DEAD END	0.24	#78 Mat Seal and 1.5" S9.5B	$63,650
2026	7	001-Alamance	Preservation	Atwater Dt.	SR 1601	SR 1632	0.45	Seal - Double and Fog Seal	$13,500
2026	7	001-Alamance	Preservation	Aunt Mary's Rd.	SR 1605	CUL-DE-SAC	0.20	Seal - Double and Fog Seal	$6,000
2026	7	001-Alamance	Preservation	Baker Bell Farm Rd.	SR 1584	SR 1002	1.44	Seal - Double and Fog Seal	$43,500
2026	7	001-Alamance	Preservation	Barclay Ln.	SR 1684	END MAINT	0.05	Seal - Double and Fog Seal	$2,000
2026	7	001-Alamance	Preservation	Basin Creek Rd.	SR 1593	SR 1002	1.71	Seal - Double and Fog Seal	$52,000
2026	7	001-Alamance	Preservation	Bethel Methodist Church Rd.	SR 1602	DEAD END	1.13	Seal - Double and Fog Seal	$34,000
2026	7	001-Alamance	Preservation	Bill Aldridge Rd.	SR 1001	END MAINT	0.30	Seal - Double and Fog Seal	$9,600
2026	7	001-Alamance	Preservation	Birchwood Dr.	SR 1593	SR 1685	0.09	Seal - Double and Fog Seal	$2,700
2026	7	001-Alamance	Preservation	Birchwood Dr.	SR 1593	CUL-DE-SAC	0.61	Seal - Double and Fog Seal	$19,000
2026	7	001-Alamance	Preservation	Carl Madren Rd.	SR 1584	END MAINT	1.09	Seal - Double and Fog Seal	$32,900
2026	7	001-Alamance	Preservation	Choyce St.	SR 1598	SR 1601	0.31	Seal - Double and Fog Seal	$10,000
2026	7	001-Alamance	Preservation	Claude Simpson Rd.	SR 1649	SR 1002	1.02	Seal - Double and Fog Seal	$30,600
2026	7	001-Alamance	Preservation	Darrel Davis Rd.	SR 1001	DEAD END	0.88	Seal - Double and Fog Seal	$26,500
2026	7	001-Alamance	Preservation	David Moore/Gwynn Rd.	CCL	SR 1587	4.08	Seal - Double and Fog Seal	$123,000
2026	7	001-Alamance	Preservation	Dodd Rd.	BEG PVMT	SR 1590	0.45	Seal - Double and Fog Seal	$14,000
2026	7	001-Alamance	Preservation	Earl Kimber Rd.	SR 1001	END MAINT	0.32	Seal - Double and Fog Seal	$9,600

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	7	001-Alamance	Preservation	Elva Dr.	SR 1522	END MAINT	0.11	Seal - Double and Fog Seal	$3,300
2026	7	001-Alamance	Preservation	Fleeman Ln.	SR 1547	DEAD END	0.10	Seal - Double and Fog Seal	$3,000
2026	7	001-Alamance	Preservation	Furguson Rd.	SR 1605	DEAD END	0.20	Seal - Double and Fog Seal	$6,000
2026	7	001-Alamance	Preservation	Gordon St.	SR 1520	SR 1530	0.32	Seal - Double and Fog Seal	$9,600
2026	7	001-Alamance	Preservation	Gwyn Rd.	SR 1582	SR 1571	1.00	Seal - Double and Fog Seal	$58,000
2026	7	001-Alamance	Preservation	Hollywood Dr.	SR 1632	SR 1661	0.38	Seal - Double and Fog Seal	$11,500
2026	7	001-Alamance	Preservation	Holyfield Rd.	SR 1565	END MAINT	0.05	Seal - Double and Fog Seal	$1,500
2026	7	001-Alamance	Preservation	Hub Mill Rd.	SR 1002	NC 87	0.90	Seal - Double and Fog Seal	$27,200
2026	7	001-Alamance	Preservation	Huffines Dr.	SR 1598	SR 1602	1.07	Seal - Double and Fog Seal	$32,500
2026	7	001-Alamance	Preservation	Hutchings Rd.	SR 1609	END MAINT	0.20	Seal - Double and Fog Seal	$6,000
2026	7	001-Alamance	Preservation	Jimmy Bowles Rd.	SR 1581	SR 1583	1.59	Seal - Double and Fog Seal	$48,000
2026	7	001-Alamance	Preservation	Johnson Ln.	SR 1603	END MAINT	0.20	Seal - Double and Fog Seal	$6,000
2026	7	001-Alamance	Preservation	Jughouse Rd.	GCL	NC 87	1.10	Seal - Double and Fog Seal	$34,110
2026	7	001-Alamance	Preservation	Juston Dr.	SR 1597	CUL-DE-SAC	0.35	Seal - Double and Fog Seal	$11,000
2026	7	001-Alamance	Preservation	Kernodle Circle Rd.	SR 1530	END MAINT	0.21	Seal - Double and Fog Seal	$6,300
2026	7	001-Alamance	Preservation	Lake Dr.	SR 1632	SR 1641	0.09	Seal - Double and Fog Seal	$3,000
2026	7	001-Alamance	Preservation	Lake Dr.	BEG MAINT	SR 1651	0.20	Seal - Double and Fog Seal	$6,000
2026	7	001-Alamance	Preservation	Leath Rd.	SR 1561	CUL-DE-SAC	0.61	Seal - Double and Fog Seal	$22,000
2026	7	001-Alamance	Preservation	Lee Lewis Rd.	SR 1576	SR 1578	1.24	Seal - Double and Fog Seal	$37,200
2026	7	001-Alamance	Preservation	Lenore Dr.	SR 1002	DEAD END	0.34	Seal - Double and Fog Seal	$10,500
2026	7	001-Alamance	Preservation	Mansfield Rd.	SR 1598	SR 1597	1.00	Seal - Double and Fog Seal	$30,000
2026	7	001-Alamance	Preservation	McIntyre Rd.	SR 1571	DEAD END	0.23	Seal - Double and Fog Seal	$6,900
2026	7	001-Alamance	Preservation	Melrose Dr.	SR 1515	SR 1629	0.43	Seal - Double and Fog Seal	$13,000
2026	7	001-Alamance	Preservation	Minor Rd.	SR 1002	CUL-DE-SAC	0.10	Seal - Double and Fog Seal	$3,000
2026	7	001-Alamance	Preservation	Mitchell St.	SR 1530	SR 1529	0.48	Seal - Double and Fog Seal	$15,000
2026	7	001-Alamance	Preservation	Motley St.	SR 1515	DEAD END	0.21	Seal - Double and Fog Seal	$6,500
2026	7	001-Alamance	Preservation	Mountain Side Lane	SR 1609	DEAD END	0.55	Seal - Double and Fog Seal	$16,500
2026	7	001-Alamance	Preservation	Mt. Vernon Rd.	SR 1002	SR 1611	2.72	Seal - Double and Fog Seal	$82,000
2026	7	001-Alamance	Preservation	Paschal Rd.	SR 1584	END MAINT	0.48	Seal - Double and Fog Seal	$14,500
2026	7	001-Alamance	Preservation	Pinecroft Dr.	SR 1521	SR 1516	0.38	Seal - Double and Fog Seal	$11,500
2026	7	001-Alamance	Preservation	Pollard Ave.	SR 1530	SR 1689	0.65	Seal - Double and Fog Seal	$20,000
2026	7	001-Alamance	Preservation	Pride Ave./Troendly St.	SR 1529	SR 1515	0.48	Seal - Double and Fog Seal	$15,000
2026	7	001-Alamance	Preservation	Rascoe Rd.	SR 1001	END MAINT	1.32	Seal - Double and Fog Seal	$40,000
2026	7	001-Alamance	Preservation	Reid Rd.	SR 1581	SR 1580	1.26	Seal - Double and Fog Seal	$38,000
2026	7	001-Alamance	Preservation	Riverview Dr.	SR 1529	SR 1518	0.06	Seal - Double and Fog Seal	$2,000
2026	7	001-Alamance	Preservation	Riverview Dr.	SR 1529	SR 2701	0.26	Seal - Double and Fog Seal	$8,000
2026	7	001-Alamance	Preservation	Roberta Dr.	SR 1001	END MAINT	0.17	Seal - Double and Fog Seal	$5,100
2026	7	001-Alamance	Preservation	Saddle Club Ln.	SR 1001	DEAD END	0.50	Seal - Double and Fog Seal	$15,000
2026	7	001-Alamance	Preservation	Sartin Rd.	SR 1581	CCL	2.83	Seal - Double and Fog Seal	$85,000
2026	7	001-Alamance	Preservation	Saul Loop Rd.	SR 1571	SR 1571	0.27	Seal - Double and Fog Seal	$8,500
2026	7	001-Alamance	Preservation	Saunders Rd.	SR 1602	DEAD END	0.20	Seal - Double and Fog Seal	$6,000
2026	7	001-Alamance	Preservation	Saw Mill Dr.	BEG MAINT	DEAD END	0.51	Seal - Double and Fog Seal	$15,500
2026	7	001-Alamance	Preservation	St. Regis Rd.	SR 1520	SR 1530	0.34	Seal - Double and Fog Seal	$10,500
2026	7	001-Alamance	Preservation	Stoney Mountain Rd.	SR 1001	SR 1614	1.70	Seal - Double and Fog Seal	$51,000
2026	7	001-Alamance	Preservation	Stoney Mountain Rd.	SR 1613	CCL	0.50	Seal - Double and Fog Seal	$17,600
2026	7	001-Alamance	Preservation	Troxler Mill Rd.	GCL	NC 87	0.72	Seal - Double and Fog Seal	$21,720
2026	7	001-Alamance	Preservation	W.L.Lane Rd.	SR 1547	END MAINT	0.13	Seal - Double and Fog Seal	$4,000
2026	7	001-Alamance	Preservation	Whitesell Brothers Rd.	SR 1581	CCL	2.20	Seal - Double and Fog Seal	$66,210
2026	7	001-Alamance	Preservation	Widow Foster Rd.	SR 1002	SR 1583	1.47	Seal - Double and Fog Seal	$44,100
2026	7	017-Caswell	Resurfacing	Allison Rd.	SR 1300	US 158	7.77	Microsurface	$2,040,608
2026	7	017-Caswell	Resurfacing	Ashland Rd.	Us 158	NC 150	4.40	Microsurface	$1,166,063
2026	7	017-Caswell	Resurfacing	Camp Springs Rd.	NC 150	SR 1133	2.79	Microsurface	$742,100
2026	7	017-Caswell	Resurfacing	NC 119 (N)	NC 57	VSL	3.04	#67 Mat Seal and 1.5" S9.5B	$814,942
2026	7	017-Caswell	Preservation	Brooks Rd.	SR 1771	DEAD END	0.49	Seal - Double and Fog Seal	$14,800
2026	7	017-Caswell	Preservation	Byrd Rd.	ACL	SR 1765	0.69	Seal - Double and Fog Seal	$20,800
2026	7	017-Caswell	Preservation	Dave Smith Rd.	NC 86	SR 1004	2.84	Seal - Double and Fog Seal	$85,500
2026	7	017-Caswell	Preservation	Gunn-Poole Rd.	NC 119	SR 1004	1.08	Seal - Double and Fog Seal	$137,500
2026	7	017-Caswell	Preservation	Hightowers Rd.	NC 119	SR 1004	5.48	Seal - Double and Fog Seal	$165,500
2026	7	017-Caswell	Preservation	Hooper Rd.	SR 1767	ACL	1.57	Seal - Double and Fog Seal	$47,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	7	017-Caswell	Preservation	Nicks Rd.	ACL	END MAINT	1.10	Seal - Double and Fog Seal	$33,500
2026	7	017-Caswell	Preservation	Oscar Gammon Rd.	ACL	EN MAINT	0.60	Seal - Double and Fog Seal	$18,500
2026	7	017-Caswell	Preservation	Smith Loop Rd.	SR 1765	SR 1765	1.31	Seal - Double and Fog Seal	$40,000
2026	7	017-Caswell	Preservation	Wade Hooker Rd.	NC 119	END MAINT	0.52	Seal - Double and Fog Seal	$15,800
2026	7	041-Guilford	Resurfacing	Arundell Ct.	SR 3765	CUL-DE-SAC	0.08	#78 Mat Seal and 1.5" S9.5B	$22,000
2026	7	041-Guilford	Resurfacing	Autumn Ridge Ct.	SR 4384	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$18,550
2026	7	041-Guilford	Resurfacing	Baggage Master Ct.	SR 4377	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$18,550
2026	7	041-Guilford	Resurfacing	Bar-Mot-Dr.	NC 150	CUL-DE-SAC	0.68	#78 Mat Seal and 1.5" S9.5B	$180,200
2026	7	041-Guilford	Resurfacing	Blazer Rd.	SR 1113	SR 4015	0.36	#78 Mat Seal and 1.5" S9.5B	$96,300
2026	7	041-Guilford	Resurfacing	Brush Arbor Ct.	SR 4377	CUL-DE-SAC	0.23	#78 Mat Seal and 1.5" S9.5B	$60,953
2026	7	041-Guilford	Resurfacing	Buffalo Tom Dr.	SR 4378	SR 4384	0.24	#78 Mat Seal and 1.5" S9.5B	$63,603
2026	7	041-Guilford	Resurfacing	Cedar Chase Dr.	NC 150	CUL-DE-SAC	0.31	#78 Mat Seal and 1.5" S9.5B	$82,155
2026	7	041-Guilford	Resurfacing	Center Grove Ct.	NC150	CUL-DE-SAC	0.12	#78 Mat Seal and 1.5" S9.5B	$31,800
2026	7	041-Guilford	Resurfacing	Centre Camp Ct.	SR 4385	CUL-DE-SAC	0.20	#78 Mat Seal and 1.5" S9.5B	$53,000
2026	7	041-Guilford	Resurfacing	Chesterbrooke Dr.	NC 150	DEAD END	0.59	#78 Mat Seal and 1.5" S9.5B	$156,360
2026	7	041-Guilford	Resurfacing	Chestnut Hill Ct.	SR 4378	CUL-DE-SAC	0.22	#78 Mat Seal and 1.5" S9.5B	$58,303
2026	7	041-Guilford	Resurfacing	Cornus Ct.	SR 2444	CUL-DE-SAC	0.04	#78 Mat Seal and 1.5" S9.5B	$11,400
2026	7	041-Guilford	Resurfacing	Crabtree Valley Ct.	NC 150	CUL-DE-SAC	0.38	#78 Mat Seal and 1.5" S9.5B	$100,705
2026	7	041-Guilford	Resurfacing	Cragganmore Dr.	SR3143	CUL-DE-SAC	0.55	Mill 1.5" and 1.5" S9.5B	$145,402
2026	7	041-Guilford	Resurfacing	Crossroads Dr.	SR4393	CUL-DE-SAC	0.25	#78 Mat Seal and 1.5" S9.5B	$66,253
2026	7	041-Guilford	Resurfacing	Crosswinds Rd.	Covered Wagon Rd	SR 5431	0.21	Mill 1.5" and 1.5" S9.5B	$55,517
2026	7	041-Guilford	Resurfacing	Devonmille Ct.	SR 4939	CUL-DE-SAC	0.06	#78 Mat Seal and 1.5" S9.5B	$15,900
2026	7	041-Guilford	Resurfacing	Dickenben Dr.	SR 2444	PVMT CHG	0.31	#78 Mat Seal and 1.5" S9.5B	$124,100
2026	7	041-Guilford	Resurfacing	Dow Dr.	SR 3060	DEAD END	0.51	#78 Mat Seal and 1.5" S9.5B	$135,200
2026	7	041-Guilford	Resurfacing	Emmacyn Dr.	SR 2446	DEAD END	0.25	#78 Mat Seal and 1.5" S9.5B	$65,200
2026	7	041-Guilford	Resurfacing	Emsley Rd.	SR 1113	DEAD END	0.41	#78 Mat Seal and 1.5" S9.5B	$108,700
2026	7	041-Guilford	Resurfacing	Filton Dr.	SR 3765	CUL-DE-SAC	0.23	#78 Mat Seal and 1.5" S9.5B	$62,100
2026	7	041-Guilford	Resurfacing	Fox Grove Trail	SR3765	END MAINT	0.10	#78 Mat Seal and 1.5" S9.5B	$26,500
2026	7	041-Guilford	Resurfacing	Guiness Dr.	SR 5431	SR 5431	0.29	Mill 1.5" and 1.5" S9.5B	$76,666
2026	7	041-Guilford	Resurfacing	Henfree Dr.	SR 2444	CUL-DE-SAC	0.15	#78 Mat Seal and 1.5" S9.5B	$40,100
2026	7	041-Guilford	Resurfacing	Hepatica Ct.	SR 2464	CUL-DE-SAC	0.13	#78 Mat Seal and 1.5" S9.5B	$34,500
2026	7	041-Guilford	Resurfacing	Hepatical Lane	SR 2444	SR 2461	0.45	#78 Mat Seal and 1.5" S9.5B	$119,000
2026	7	041-Guilford	Resurfacing	Hilltop Rd.	SR 1546	SR 4121	3.03	#78 Mat Seal and 1.5" S9.5B	$844,100
2026	7	041-Guilford	Resurfacing	Hugh Patrick Ct.	SR 2326	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$18,551
2026	7	041-Guilford	Resurfacing	James Doak Prkwy	SR 2347	SR 4937	1.82	#78 Mat Seal and 1.5" S9.5B	$482,325
2026	7	041-Guilford	Resurfacing	Joseph Hoskins Rd.	US 220	END MAINT	0.85	#78 Mat Seal and 1.5" S9.5B	$228,200
2026	7	041-Guilford	Resurfacing	Kivett Dr.	ECL High Point	SR 1104	7.13	#78 Mat Seal and 1.5" S9.5B	$1,265,051
2026	7	041-Guilford	Resurfacing	Lager Ct.	SR 5431	CUL-DE-SAC	0.07	Mill 1.5" and 1.5" S9.5B	$18,505
2026	7	041-Guilford	Resurfacing	Lashley Ct.	SR 2333	CUL-DE-SAC	0.10	#78 Mat Seal and 1.5" S9.5B	$26,501
2026	7	041-Guilford	Resurfacing	Longhorn Ct.	SR 4397	CUL-DE-SAC	0.10	#78 Mat Seal and 1.5" S9.5B	$26,501
2026	7	041-Guilford	Resurfacing	Longhorn Dr.	SR 4378	SR 2333	0.18	#78 Mat Seal and 1.5" S9.5B	$47,702
2026	7	041-Guilford	Resurfacing	McLeansville Rd.	NC 150	SR 2565	4.27	#78 Mat Seal and 1.25" S9.5A and Widen	$2,088,744
2026	7	041-Guilford	Resurfacing	McLeansville rd.	NC 150	SR 2565	4.27	#78 Mat Seal and 1.25" S9.5A and Widen	$2,088,745
2026	7	041-Guilford	Resurfacing	Minion Ct.	SR 5429	CUL-DE-SAC	0.11	Mill 1.5" and 1.5" S9.5B	$29,080
2026	7	041-Guilford	Resurfacing	Mountain Brook Rd.	DEAD END	DEAD END	0.65	#78 Mat Seal and 1.5" S9.5B	$167,000
2026	7	041-Guilford	Resurfacing	NC 150	SR 2514	RCL	4.94	#67 Mat Seal and 1.5" S9.5B	$1,324,281
2026	7	041-Guilford	Resurfacing	NC 610	SR 1009	NC 62	2.10	#78 Mat Seal and 1.5" S9.5B	$580,000
2026	7	041-Guilford	Resurfacing	NC 62	NC 62	RCL	1.80	#78 Mat Seal and 1.5" S9.5B	$725,000
2026	7	041-Guilford	Resurfacing	North Scamper Grey Ct.	SR 4395	DEAD END	0.06	#78 Mat Seal and 1.5" S9.5B	$16,200
2026	7	041-Guilford	Resurfacing	Old Brick Store Rd.	SR 4377	CUL-DE-SAC	0.42	#78 Mat Seal and 1.5" S9.5B	$111,305
2026	7	041-Guilford	Resurfacing	Old Iron Ct.	SR 4382	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$18,550
2026	7	041-Guilford	Resurfacing	Old Ironworks Rd.	NC 150	SR 4377	0.36	#78 Mat Seal and 1.5" S9.5B	$95,404
2026	7	041-Guilford	Resurfacing	Pauline Ct.	SR 2445	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$18,100
2026	7	041-Guilford	Resurfacing	Pebble Ridge Ct.	SR 4937	CUL-DE-SAC	0.10	#78 Mat Seal and 1.5" S9.5B	$26,501
2026	7	041-Guilford	Resurfacing	Penn-Lo-Dr.	US 70	SR 2924	0.36	#78 Mat Seal and 1.5" S9.5B	$95,500
2026	7	041-Guilford	Resurfacing	Pleasant Field Dr.	SR 4377	CUL-DE-SAC	0.18	#78 Mat Seal and 1.5" S9.5B	$47,702
2026	7	041-Guilford	Resurfacing	Pondside Ct.	SR 4963	DEAD END	0.08	#78 Mat Seal and 1.5" S9.5B	$21,200
2026	7	041-Guilford	Resurfacing	Preakness Parkway	US 70	5306	0.60	#78 Mat Seal and 1.5" S9.5B	$135,350
2026	7	041-Guilford	Resurfacing	Preakness Parkway	Sr 5306	SR 2758	0.47	#78 Mat Seal and 1.5" S9.5B	$135,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	7	041-Guilford	Resurfacing	Rachel Smothers Dr.	SR 2326	DEAD ENd	0.10	#78 Mat Seal and 1.5" S9.5B	$26,502
2026	7	041-Guilford	Resurfacing	Richardson Village Way	SR2950	END MAINT	0.22	#78 Mat Seal and 1.5" S9.5B	$58,303
2026	7	041-Guilford	Resurfacing	Ritter's Lake Rd.	SR 3505	SR 3738	1.60	#78 Mat Seal and 1.5" S9.5B	$424,100
2026	7	041-Guilford	Resurfacing	Royster Rd.	DEAD END	DEAD END	0.40	#78 Mat Seal and 1.5" S9.5B	$106,005
2026	7	041-Guilford	Resurfacing	Rygate Drive	SR 3738	SR 3505	0.63	#78 Mat Seal and 1.5" S9.5B	$166,700
2026	7	041-Guilford	Resurfacing	S. Main St.	Project Limts	SR 1300	3.00	Mill 1.5" and 1.5" S9.5B	$1,300,000
2026	7	041-Guilford	Resurfacing	Sarah Marie Dr.	Bailey Rd.	END MAINT	0.24	#78 Mat Seal and 1.5" S9.5B	$64,700
2026	7	041-Guilford	Resurfacing	Sarelma Dr.	SR 2444	END MAINT	0.21	#78 Mat Seal and 1.5" S9.5B	$56,000
2026	7	041-Guilford	Resurfacing	Smith St.	SR 2748	Railroad Ave.	0.89	#78 Mat Seal and 1.5" S9.5B	$235,862
2026	7	041-Guilford	Resurfacing	Soldier Retreat Ct.	SR 4377	CUL-DE-SAC	0.11	#78 Mat Seal and 1.5" S9.5B	$29,151
2026	7	041-Guilford	Resurfacing	South Scamper Grey Ct.	SR 4395	DEAD END	0.09	#78 Mat Seal and 1.5" S9.5B	$24,700
2026	7	041-Guilford	Resurfacing	Spencer Dixon Rd.	SR 4300	NC 150	2.25	#78 Mat Seal and 1.5" S9.5B	$296,281
2026	7	041-Guilford	Resurfacing	Springberry Ct.	SR 4963	CUL-DE-SAC	0.08	#78 Mat Seal and 1.5" S9.5B	$21,200
2026	7	041-Guilford	Resurfacing	Springwood Ave.	US 70	NC 100	1.87	#78 Mat Seal and 1.25" S9.5A	$495,600
2026	7	041-Guilford	Resurfacing	Springwood Ave.	US 70	NC 100	2.06	#78 Mat Seal and 1.5" S9.5B	$545,930
2026	7	041-Guilford	Resurfacing	Squirrel Chase Dr.	SR 2347	END MAINT	0.26	#78 Mat Seal and 1.5" S9.5B	$68,900
2026	7	041-Guilford	Resurfacing	Stella Dr.	SR 3060	SR 2923	0.32	#78 Mat Seal and 1.5" S9.5B	$84,900
2026	7	041-Guilford	Resurfacing	Sutter Rd.	NC 150	END MAINT	0.46	#78 Mat Seal and 1.5" S9.5B	$121,910
2026	7	041-Guilford	Resurfacing	Tiarella Ct.	SR 2462	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$18,900
2026	7	041-Guilford	Resurfacing	Tiarella Dr.	SR 2461	SR 2464	0.28	#78 Mat Seal and 1.5" S9.5B	$75,000
2026	7	041-Guilford	Resurfacing	Tillie Scott Ct.	SR 2326	CUL-DE-SAC	0.05	#78 Mat Seal and 1.5" S9.5B	$13,251
2026	7	041-Guilford	Resurfacing	Treford Ct.	SR 3765	END MAINT	0.05	#78 Mat Seal and 1.5" S9.5B	$12,000
2026	7	041-Guilford	Resurfacing	Troublesome Creek Dr.	SR 4380	CUL-DE-SAC	0.43	#78 Mat Seal and 1.5" S9.5B	$114,000
2026	7	041-Guilford	Resurfacing	W. Market St.	NC68	SR 2147	1.00	#78 Mat Seal and 1.5" S9.5B	$506,924
2026	7	041-Guilford	Resurfacing	Weitzel Dr.	SR 2444	SR 2464	0.54	#78 Mat Seal and 1.5" S9.5B	$142,600
2026	7	041-Guilford	Resurfacing	William Bailey Rd.	SR 2444	DEAD END	0.24	#78 Mat Seal and 1.5" S9.5B	$63,900
2026	7	041-Guilford	Resurfacing	Winterale Ct.	SR5431	CUL-DE-SAC	0.07	Mill 1.5" and 1.5" S9.5B	$18,505
2026	7	041-Guilford	Resurfacing	Worthing Chase Dr.	SR3330	SR 3330	0.47	#78 Mat Seal and 1.5" S9.5B	$124,300
2026	7	041-Guilford	Preservation	Amick Rd.	SR 1005	SR 3336	1.91	Seal - Double and Fog Seal	$85,500
2026	7	041-Guilford	Preservation	Annie Ave.	SR 3589	SR 3591	0.07	Seal - Double and Fog Seal	$3,100
2026	7	041-Guilford	Preservation	Arborlinda Dr.	SR 2565	DEAD END	0.20	Seal - Double and Fog Seal	$6,600
2026	7	041-Guilford	Preservation	Arrington Rd.	SR 3377	SR 3370	0.84	Seal - Double and Fog Seal	$37,700
2026	7	041-Guilford	Preservation	Bales Chapel Rd.	SR 1334	SR 1355	0.90	Seal - Double and Fog Seal	$94,770
2026	7	041-Guilford	Preservation	Bali Rd.	SR 3361	SR 3366	0.48	Seal - Double and Fog Seal	$21,400
2026	7	041-Guilford	Preservation	Baptist Assembly Rd.	SR 1005	X-Cross	0.90	Seal - Double and Fog Seal	$40,500
2026	7	041-Guilford	Preservation	Barkwood Rd.	SR 1005	SR 3321	0.15	Seal - Double and Fog Seal	$6,600
2026	7	041-Guilford	Preservation	Batten Rd.	SR3549	DEAD END	0.14	#78 Mat Seal and 1.5" S9.5B	$6,217
2026	7	041-Guilford	Preservation	Batten Rd.	SR 3549	DEAD END	0.14	Seal - Double and Fog Seal	$6,300
2026	7	041-Guilford	Preservation	Bedrock Rd.	SR 3093	SR 3459	1.07	Seal - Double and Fog Seal	$47,800
2026	7	041-Guilford	Preservation	Beth Rd.	SR 1005	DEAD END	0.23	Seal - Double and Fog Seal	$10,100
2026	7	041-Guilford	Preservation	Blakeshire Rd.	SR 1005	SR 3330	2.16	Seal - Double and Fog Seal	$96,700
2026	7	041-Guilford	Preservation	Bora Dr.	SR 3549	DEAD END	0.23	Seal - Double and Fog Seal	$10,200
2026	7	041-Guilford	Preservation	Boxer Lane	SR 1007	DEAD END	0.18	Seal - Double and Fog Seal	$7,830
2026	7	041-Guilford	Preservation	Boxford Rd.	SR 3330	DEAD END	0.36	Seal - Double and Fog Seal	$16,200
2026	7	041-Guilford	Preservation	Brill Rd.	SR 3549	DEAD END	0.10	Seal - Double and Fog Seal	$4,700
2026	7	041-Guilford	Preservation	Burns St.	SR 3322	SR 3325	0.17	Seal - Double and Fog Seal	$15,200
2026	7	041-Guilford	Preservation	Cade Rd.	CUL-DE-SAC	DEAD END	0.53	Seal - Double and Fog Seal	$23,700
2026	7	041-Guilford	Preservation	Canova Rd.	DEAD END	DEAD END	0.33	Seal - Double and Fog Seal	$14,600
2026	7	041-Guilford	Preservation	Chapparal Dr.	SR 3549	END MAINT	0.40	Seal - Double and Fog Seal	$18,800
2026	7	041-Guilford	Preservation	Chuck Rd.	SR 3330	DEAD END	0.33	Seal - Double and Fog Seal	$14,900
2026	7	041-Guilford	Preservation	Circle T Trail	SR 3549	CUL-DE-SAC	0.51	Seal - Double and Fog Seal	$22,900
2026	7	041-Guilford	Preservation	Cloud Rd.	SR 3368	DEAD END	0.65	Seal - Double and Fog Seal	$28,900
2026	7	041-Guilford	Preservation	Coble Church Rd.	SR 3346	SR 3360	2.65	Seal - Double and Fog Seal	$118,600
2026	7	041-Guilford	Preservation	Cocoa Dr.	SR 3526	DEAD END	0.23	Seal - Double and Fog Seal	$10,200
2026	7	041-Guilford	Preservation	Colonial Trading Path	SR 3374	RCL	0.04	Seal - Double and Fog Seal	$1,900
2026	7	041-Guilford	Preservation	Comanche Trail	SR 1005	DEAD END	0.55	Seal - Double and Fog Seal	$24,700
2026	7	041-Guilford	Preservation	Connie Rd.	SR 3381	DEAD END	0.77	Seal - Double and Fog Seal	$34,300
2026	7	041-Guilford	Preservation	Crest Rd.	SR 1005	NS-98165	0.07	Seal - Double and Fog Seal	$3,100
2026	7	041-Guilford	Preservation	Creston St.	SR 3300	DEAD END	0.28	Seal - Double and Fog Seal	$8,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	7	041-Guilford	Preservation	Cynthia Rd.	SR 3433	END MAINT	0.38	Seal - Double and Fog Seal	$42,120
2026	7	041-Guilford	Preservation	Dolphin Rd.	SR 3612	END PVMT	0.09	Seal - Double and Fog Seal	$4,200
2026	7	041-Guilford	Preservation	Dona Rd.	NC 62	SR 3093	0.98	Seal - Double and Fog Seal	$43,850
2026	7	041-Guilford	Preservation	Folger Rd.	RCL	NC 62	0.95	Seal - Double and Fog Seal	$42,600
2026	7	041-Guilford	Preservation	Folger Rd.	RCL	SR 3093	0.90	Seal - Double and Fog Seal	$30,000
2026	7	041-Guilford	Preservation	Forest Acres Circle	END MAINT	END MAINT	0.79	Seal - Double and Fog Seal	$35,300
2026	7	041-Guilford	Preservation	Foxburrow Rd.	SR 3389	SR 3334	1.04	Seal - Double and Fog Seal	$46,320
2026	7	041-Guilford	Preservation	Garwin Rd.	SR 3506	END MAINT	0.19	Seal - Double and Fog Seal	$8,500
2026	7	041-Guilford	Preservation	Girard Rd.	SR 3314	DEAD END	0.26	Seal - Double and Fog Seal	$11,800
2026	7	041-Guilford	Preservation	Glass Rd.	SR 1005	DEAD END	0.06	Seal - Double and Fog Seal	$2,700
2026	7	041-Guilford	Preservation	Greenland Ave.	SR3585	DEAD END	0.07	Seal - Double and Fog Seal	$3,200
2026	7	041-Guilford	Preservation	Jaylee Place Rd.	SR 3093	NC 62	0.25	Seal - Double and Fog Seal	$11,000
2026	7	041-Guilford	Preservation	Jidemi Rd.	SR 3329	DEAD END	0.59	Seal - Double and Fog Seal	$26,300
2026	7	041-Guilford	Preservation	Kincaid Dr.	SR 3330	END MAINT	0.36	Seal - Double and Fog Seal	$16,100
2026	7	041-Guilford	Preservation	Landsbury Rd.	SR 3325	DEAD END	0.19	Seal - Double and Fog Seal	$8,500
2026	7	041-Guilford	Preservation	Ledbetter Rd.	NC 62	RCL	0.60	Seal - Double and Fog Seal	$19,000
2026	7	041-Guilford	Preservation	Logandale Rd.	SR 3505	END MAINT	0.30	Seal - Double and Fog Seal	$42,120
2026	7	041-Guilford	Preservation	Mabel Lane	SR 3362	SR 3361	1.06	Seal - Double and Fog Seal	$47,500
2026	7	041-Guilford	Preservation	Methodist Rd.	SR 3389	DEAD END	0.33	Seal - Double and Fog Seal	$15,000
2026	7	041-Guilford	Preservation	Mossdale Rd.	SR 3506	END MAINT	0.01	Seal - Double and Fog Seal	$3,000
2026	7	041-Guilford	Preservation	Mossdale Rd.	SR 3506	END MAINT	0.10	Seal - Double and Fog Seal	$4,400
2026	7	041-Guilford	Preservation	Nat Rd.	NC 62	SR 3361	0.84	Seal - Double and Fog Seal	$37,300
2026	7	041-Guilford	Preservation	Nelson Farm Rd.	SR 1005	END PVMT	0.17	Seal - Double and Fog Seal	$7,700
2026	7	041-Guilford	Preservation	Nesbit Rd.	SR 3738	SR 3505	1.09	Seal - Double and Fog Seal	$32,800
2026	7	041-Guilford	Preservation	Old Julian Rd.	SR 3374	NC 62	0.43	Seal - Double and Fog Seal	$19,300
2026	7	041-Guilford	Preservation	Oliver Hills Rd.	SR 3314	DEAD END	0.50	Seal - Double and Fog Seal	$22,300
2026	7	041-Guilford	Preservation	Pearl Rd.	SR 3515	DEAD END	0.16	Seal - Double and Fog Seal	$7,400
2026	7	041-Guilford	Preservation	Phillippi Rd.	SR 3336	NC 62	2.46	Seal - Double and Fog Seal	$110,080
2026	7	041-Guilford	Preservation	Plaza Dr.	SR 3606	NC-93523	0.31	Seal - Double and Fog Seal	$13,900
2026	7	041-Guilford	Preservation	Rolling Hills Ave.	SR 3549	DEAD END	0.12	Seal - Double and Fog Seal	$5,300
2026	7	041-Guilford	Preservation	Rosemary Dr.	SR 3330	END PAVEMENT	0.42	Seal - Double and Fog Seal	$18,900
2026	7	041-Guilford	Preservation	Schoolway Dr.	SR 3330	SR 3613	0.11	Seal - Double and Fog Seal	$5,000
2026	7	041-Guilford	Preservation	Service Rd. off Monnett	SR 3381	DEAD END	0.10	Seal - Double and Fog Seal	$4,300
2026	7	041-Guilford	Preservation	Sherrilwood Dr.	SR 3505	END MAINT	0.30	Seal - Double and Fog Seal	$42,120
2026	7	041-Guilford	Preservation	Spur Rd.	SR 1007	SR 3505	1.50	Seal - Double and Fog Seal	$157,950
2026	7	041-Guilford	Preservation	Stanhope Rd.	SR 3314	SR 3563	0.09	Seal - Double and Fog Seal	$4,000
2026	7	041-Guilford	Preservation	Stoney Hill Circle	SR 3433	DEAD END	0.23	Seal - Double and Fog Seal	$10,400
2026	7	041-Guilford	Preservation	Stoney Hill Circle	SR 3433	SR 3439	0.39	Seal - Double and Fog Seal	$42,120
2026	7	041-Guilford	Preservation	Stoney Hill Circle	SR 3430	SR 3433	0.39	Seal - Double and Fog Seal	$17,600
2026	7	041-Guilford	Preservation	Thorny Rd.	SR 1005	SR 3334	0.77	Seal - Double and Fog Seal	$34,275
2026	7	041-Guilford	Preservation	Tryone Loop Rd.	SR 1005	MP 0.093	0.09	Seal - Double and Fog Seal	$4,200
2026	7	041-Guilford	Preservation	Twinning Rd.	SR 3505	END MAINT	0.52	Seal - Double and Fog Seal	$15,600
2026	7	041-Guilford	Preservation	Valhalla Cr.	SR 3329	SR 3493	0.20	Seal - Double and Fog Seal	$8,900
2026	7	041-Guilford	Preservation	Valhalla Cr.	SR 3492	SR 3492	0.34	Seal - Double and Fog Seal	$15,200
2026	7	041-Guilford	Preservation	Vivian Lane	BEG MAINT	DEAD END	0.32	Seal - Double and Fog Seal	$9,600
2026	7	041-Guilford	Preservation	Watchtower Rd.	SR 3336	SR 3381	2.49	Seal - Double and Fog Seal	$111,400
2026	7	041-Guilford	Preservation	Windsong Rd.	SR 1005	NS-92215	0.22	Seal - Double and Fog Seal	$9,800
2026	7	041-Guilford	Preservation	Woodledge Dr.	SR3325	END MAINT	0.22	Seal - Double and Fog Seal	$9,850
2026	7	041-Guilford	Preservation	Woodwind Rd.	SR 3571	DEAD END	0.11	Seal - Double and Fog Seal	$4,900
2026	7	041-Guilford	Preservation	Woody Lane	SR 3336	SR 3389	1.29	Seal - Double and Fog Seal	$57,588
2026	7	068-Orange	Resurfacing	Alice Miller Ct.	SR 1442	END MAINT	0.19	#78 Mat Seal and 1.5" S9.5B	$50,352
2026	7	068-Orange	Resurfacing	Berwick Place	DCL	SR 1690	0.05	#78 Mat Seal and 1.5" S9.5B	$13,300
2026	7	068-Orange	Resurfacing	Boundbrook Dr.	SR 1443	END MAINT	0.29	#78 Mat Seal and 1.5" S9.5B	$76,900
2026	7	068-Orange	Resurfacing	Bridgeton Pl.	SR 2281	CUL-DE-SAC	0.08	#78 Mat Seal and 1.5" S9.5B	$21,200
2026	7	068-Orange	Resurfacing	Buckwalter Lane	SR 1312	SR 1453	0.11	#78 Mat Seal and 1.5" S9.5B	$29,200
2026	7	068-Orange	Resurfacing	Caprea Ct.	SR 1863	CUL-DE-SAC	0.04	#78 Mat Seal and 1.5" S9.5B	$10,600
2026	7	068-Orange	Resurfacing	Churton Grove Blvd.	SR 1002	SR 2300	0.85	Mill 1.5" and 1.5" S9.5B	$206,490
2026	7	068-Orange	Resurfacing	Craftsmen St.	SR 1269	CUL-DE-SAC	0.21	#78 Mat Seal and 1.5" S9.5B	$65,670
2026	7	068-Orange	Resurfacing	Creek Ridge Ln.	SR 2281	CUL-DE-SAC	0.40	#78 Mat Seal and 1.5" S9.5B	$106,001

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	7	068-Orange	Resurfacing	Creekrun Ct.	SR 2281	CUL-DE-SAC	0.10	#78 Mat Seal and 1.5" S9.5B	$26,600
2026	7	068-Orange	Resurfacing	CreekWood Dr	SR 1731	SR 1730	0.90	#78 Mat Seal and 1.5" S9.5B	$238,513
2026	7	068-Orange	Resurfacing	Crown Ct.	SR 1563	END MAINT	0.30	#78 Mat Seal and 1.5" S9.5B	$79,600
2026	7	068-Orange	Resurfacing	Dunn Place	SR 1653	CUL-DE-SAC	0.07	Mill 1.5" and 1.5" S9.5B	$17,000
2026	7	068-Orange	Resurfacing	Estes Dr.	Joint (Caswell Rd.)	Sr 1010	0.63	Mill 1.5" and 1.5" S9.5B	$230,515
2026	7	068-Orange	Resurfacing	Ezekiel Peppers Trail	SR 1729	SR 2288	0.04	Mill 1.5" and 1.5" S9.5B	$10,000
2026	7	068-Orange	Resurfacing	Foreman St.	SR 1653	CUL-DE-SAC	0.10	#78 Mat Seal and 1.5" S9.5B	$24,300
2026	7	068-Orange	Resurfacing	Galax Ct.	SR 1259	CUL-DE-SAC	0.08	#78 Mat Seal and 1.5" S9.5B	$29,200
2026	7	068-Orange	Resurfacing	Highland Farm Rd.	SR 1004	SR 1334	4.29	#78 Mat Seal and 1.5" S9.5A	$1,136,911
2026	7	068-Orange	Resurfacing	Homestead Rd.	NC 86	SR 1009	3.20	#78 Mat Seal and 1.5" S9.5B	$848,100
2026	7	068-Orange	Resurfacing	James Madison Place	SR 1655	CUL-DE-SAC	0.11	Mill 1.5" and 1.5" S9.5B	$26,800
2026	7	068-Orange	Resurfacing	Jubilee Dr.	SR 2287	CUL-DE-SAC	0.11	Mill 1.5" and 1.5" S9.5B	$26,800
2026	7	068-Orange	Resurfacing	Maggie Lane	SR 1671	CUL-DE-SAC	0.10	#78 Mat Seal and 1.5" S9.5B	$26,600
2026	7	068-Orange	Resurfacing	Mayo St.	SR 1006	SR 1009	0.03	#78 Mat Seal and 1.5" S9.5B	$79,550
2026	7	068-Orange	Resurfacing	McRae Rd.	SR 1653	CUL-DE-SAC	0.07	Mill 1.5" and 1.5" S9.5B	$17,100
2026	7	068-Orange	Resurfacing	Monnlight Dr.	SR 1948	CUL-DE-SAC	0.35	#78 Mat Seal and 1.5" S9.5B	$92,800
2026	7	068-Orange	Resurfacing	Montvale Rd.	SR 1717	DCL	0.03	#78 Mat Seal and 1.5" S9.5B	$8,000
2026	7	068-Orange	Resurfacing	N. Greensboro St.	SR 1780	ROUNDABOUT	0.80	Mill 1.25" and 1.25" S9.5B	$365,600
2026	7	068-Orange	Resurfacing	N. Scotswood Blvd.	US 70	SR 1679	0.73	#78 Mat Seal and 1.5" S9.5B	$325,400
2026	7	068-Orange	Resurfacing	Nichols Dr.	NC 57	CUL-DE-SAC	0.24	#78 Mat Seal and 1.5" S9.5B	$63,700
2026	7	068-Orange	Resurfacing	Northridge Lane	SR 1732	CUL-DE-SAC	0.15	#78 Mat Seal and 1.5" S9.5B	$39,800
2026	7	068-Orange	Resurfacing	Oak Point Ct.	SR 1244	CUL-DE-SAC	0.05	#78 Mat Seal and 1.5" S9.5B	$13,300
2026	7	068-Orange	Resurfacing	Oak Point Lane	SR 1138	CUL-DE-SAC	0.11	#78 Mat Seal and 1.5" S9.5B	$13,300
2026	7	068-Orange	Resurfacing	Oakwood St. Ext.	SR 1301	SR 1381	0.60	#78 Mat Seal and 1.5" S9.5B	$159,100
2026	7	068-Orange	Resurfacing	Oakwood St. Ext.	SR 1144	SR 1300	0.70	#78 Mat Seal and 1.5" S9.5B	$185,600
2026	7	068-Orange	Resurfacing	Oconee Ct.	SR 1259	CUL-DE-SAC	0.08	#78 Mat Seal and 1.5" S9.5B	$21,200
2026	7	068-Orange	Resurfacing	Old Heritage Ct.	Old NC 86	CUL-DE-SAC	0.14	#78 Mat Seal and 1.5" S9.5B	$37,200
2026	7	068-Orange	Resurfacing	Oxbow Crossing Rd.	SR 1104	CUL-DE-SAC	0.44	#78 Mat Seal and 1.5" S9.5B	$116,200
2026	7	068-Orange	Resurfacing	Pascal Way	SR 1717	DCL	0.04	#78 Mat Seal and 1.5" S9.5B	$10,700
2026	7	068-Orange	Resurfacing	Patrick Henry Lane	SR 1653	CUL-DE-SAC	0.20	#78 Mat Seal and 1.5" S9.5B	$46,200
2026	7	068-Orange	Resurfacing	Pine Tree Lane	SR 1732	CUL-DE-SAC	0.11	#78 Mat Seal and 1.5" S9.5B	$29,200
2026	7	068-Orange	Resurfacing	Poplar Dr.	SR 1340	END PVMT	0.35	#78 Mat Seal and 1.5" S9.5B	$48,900
2026	7	068-Orange	Resurfacing	Preston Loop	SR 1144	SR 1144	0.46	#78 Mat Seal and 1.5" S9.5B	$121,900
2026	7	068-Orange	Resurfacing	Red Roof Inn Dr.	SR 1653	DCL	0.08	#78 Mat Seal and 1.5" S9.5B	$21,200
2026	7	068-Orange	Resurfacing	Rex Rd.	SR 1727	END MAINT	0.05	#78 Mat Seal and 1.5" S9.5B	$13,300
2026	7	068-Orange	Resurfacing	Rippy Lane	SR 1009	END MAINT	0.20	#78 Mat Seal and 1.5" S9.5B	$53,100
2026	7	068-Orange	Resurfacing	Salem Lane	SR 1005	CUL-DE-SAC	0.27	#78 Mat Seal and 1.5" S9.5B	$71,600
2026	7	068-Orange	Resurfacing	Stacy Ct.	SR 1460	CUL-DE-SAC	0.16	#78 Mat Seal and 1.5" S9.5B	$42,500
2026	7	068-Orange	Resurfacing	Strouds Creek Rd.	NC 57	END MAINT	0.33	#78 Mat Seal and 1.5" S9.5B	$87,500
2026	7	068-Orange	Resurfacing	Sunglow Ct.	SR 1460	CUL-DE-SAC	0.09	#78 Mat Seal and 1.5" S9.5B	$23,900
2026	7	068-Orange	Resurfacing	Trail Dr.	SR 1415	END MAINT	0.14	#78 Mat Seal and 1.5" S9.5B	$19,530
2026	7	068-Orange	Resurfacing	Trinity Lane	NC 57	CUL-DE-SAC	0.11	#78 Mat Seal and 1.5" S9.5B	$29,200
2026	7	068-Orange	Resurfacing	Tuscany Dr.	SR 1115	CUL-DE-SAC	0.47	#78 Mat Seal and 1.5" S9.5B	$124,700
2026	7	068-Orange	Resurfacing	University Lake Rd.	SR 1005	END MAINT	0.61	#78 Mat Seal and 1.5" S9.5B	$161,700
2026	7	068-Orange	Resurfacing	US 15-501	SR 1742	DCL	1.68	Mill 1.5" and 1.5" S9.5B	$459,000
2026	7	068-Orange	Resurfacing	Vallie Hi Lane	SR 1723	END MAINT	0.24	#78 Mat Seal and 1.5" S9.5B	$63,700
2026	7	068-Orange	Resurfacing	Virginia Lee Lane	SR 1340	SR 1343	0.53	#78 Mat Seal and 1.5" S9.5B	$140,500
2026	7	068-Orange	Resurfacing	Wagon Farm Rd.	SR 1414	END MAINT	0.39	#78 Mat Seal and 1.5" S9.5B	$54,500
2026	7	068-Orange	Preservation	Bumphus Rd.	SR 1723	END PVMT	0.39	Seal - Double and Fog Seal	$13,650
2026	7	068-Orange	Preservation	Couch Mountain Rd.	SR 1841	SR 1714	0.53	Seal - Double and Fog Seal	$18,550
2026	7	068-Orange	Preservation	Dove Creek Rd.	SR 1710	SR 1716	0.35	Seal - Double and Fog Seal	$12,250
2026	7	068-Orange	Preservation	Mt. Herman Church Rd.	SR 1710	SR 1841	0.91	Seal - Double and Fog Seal	$31,850
2026	7	068-Orange	Preservation	Murphy School Rd.	SR 1716	END PVMT	0.51	Seal - Double and Fog Seal	$17,850
2026	7	068-Orange	Preservation	Murphy School Rd.	SR 1714	SR 1778	1.69	Seal - Double and Fog Seal	$59,150
2026	7	068-Orange	Preservation	Murphy School Rd.	SR 1710	SR 1716	0.44	Seal - Double and Fog Seal	$15,400
2026	7	068-Orange	Preservation	New Hope Church Rd.	NC 86	SR 1710	1.83	Seal - Double and Fog Seal	$64,050
2026	7	068-Orange	Preservation	Oak Hill Rd.	SR 1732	SR 1732	1.00	Seal - Double and Fog Seal	$44,500
2026	7	068-Orange	Preservation	Station Rd.	SR 1817	END PVMT	0.21	Seal - Double and Fog Seal	$7,350
2026	7	068-Orange	Preservation	Turkey Farm Rd.	SR 1718	SR 1731	1.87	Seal - Double and Fog Seal	$68,250

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	7	068-Orange	Preservation	University Station Rd.	SR 1710	SR 1718	2.31	Seal - Double and Fog Seal	$80,850
2026	7	079-Rockingham	Resurfacing	Alley Farm Rd.	NC 65	DEAD END	0.19	#78 Mat Seal and 1.5" S9.5B	$26,000
2026	7	079-Rockingham	Resurfacing	Autumn Gate Dr.	SR 2953	SR 2976	0.30	#78 Mat Seal and 1.5" S9.5B	$45,100
2026	7	079-Rockingham	Resurfacing	Ayersville Rd.	NC 770	SR 1321	2.60	#78 Mat Seal and 1.5" S9.5B	$423,124
2026	7	079-Rockingham	Resurfacing	Azalea Rd.	SR 1605	SR 1705	0.06	#78 Mat Seal and 1.5" S9.5B	$8,195
2026	7	079-Rockingham	Resurfacing	Bald Hill Loop	NC 704	SR 2319	1.88	#78 Mat Seal and 1.5" S9.5B	$320,000
2026	7	079-Rockingham	Resurfacing	Battle Creek Rd.	SR 2406	CUL-DE-SAC	0.27	#78 Mat Seal and 1.5" S9.5B	$36,879
2026	7	079-Rockingham	Resurfacing	Bethlehem Church Rd.	NC 14	SR 2282	3.94	#78 Mat Seal and 1.5" S9.5B	$1,914,651
2026	7	079-Rockingham	Resurfacing	Church/Woolen St. Rd.	GCL	SR 2405	5.61	#78 Mat Seal and 1.5" S9.5B	$1,162,000
2026	7	079-Rockingham	Resurfacing	Club House Dr.	SR 1987	END MAINT	0.07	#78 Mat Seal and 1.5" S9.5B	$9,561
2026	7	079-Rockingham	Resurfacing	Commerce Dr.	NC 135	CUL-DE-SAC	0.16	#78 Mat Seal and 1.5" S9.5B	$45,888
2026	7	079-Rockingham	Resurfacing	Cottonwood Dr.	US 158	SR 2972	0.27	#78 Mat Seal and 1.5" S9.5B	$36,879
2026	7	079-Rockingham	Resurfacing	E. Plantation Circle	SR 2827	CDS Loop	0.28	#78 Mat Seal and 1.5" S9.5B	$38,245
2026	7	079-Rockingham	Resurfacing	Fisher Hill Rd.	SR 3004	VSL	1.02	#78 Mat Seal and 1.5" S9.5B	$158,090
2026	7	079-Rockingham	Resurfacing	Friends Farm Way	SR 1110	CUL-DE-SAC	0.27	#78 Mat Seal and 1.5" S9.5B	$37,000
2026	7	079-Rockingham	Resurfacing	Gallent Rd.	CUL-DE-SAC	END MAINT	0.32	#78 Mat Seal and 1.5" S9.5B	$43,709
2026	7	079-Rockingham	Resurfacing	Glenmoor Dr.	SR 1974	CUL-DE-SAC	0.15	#78 Mat Seal and 1.5" S9.5B	$20,489
2026	7	079-Rockingham	Resurfacing	Glenridge Dr.	SR 2813	CUL-DE-SAC	0.15	#78 Mat Seal and 1.5" S9.5B	$20,489
2026	7	079-Rockingham	Resurfacing	Glenwood Rd.	SR 1974	CUL-DE-SAC	0.16	#78 Mat Seal and 1.5" S9.5B	$21,854
2026	7	079-Rockingham	Resurfacing	Hampton Rd.	SR 1980	NC 700	3.63	#78 Mat Seal and 1.5" S9.5B	$562,614
2026	7	079-Rockingham	Resurfacing	Laurel Ridge Ct.	SR 2974	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$9,600
2026	7	079-Rockingham	Resurfacing	Madison St.	SR 2670	US 29 BUS	1.24	#78 Mat Seal and 1.5" S9.5B	$225,928
2026	7	079-Rockingham	Resurfacing	Meadow Bluff Ct.	SR 2974	CUL-DE-SAC	0.15	#78 Mat Seal and 1.5" S9.5B	$21,000
2026	7	079-Rockingham	Resurfacing	Mebane Bridge Rd.	END PVMT	NC 14	0.59	#78 Mat Seal and 1.5" S9.5B	$91,444
2026	7	079-Rockingham	Resurfacing	Merrigold Rd.	CUL-DE-SAC	DEAD END	0.10	#78 Mat Seal and 1.5" S9.5B	$14,000
2026	7	079-Rockingham	Resurfacing	Midway Rd.	US 158	END MAINT	0.19	#78 Mat Seal and 1.5" S9.5B	$25,952
2026	7	079-Rockingham	Resurfacing	Mountain Laurel Trail	SR 2282	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$9,600
2026	7	079-Rockingham	Resurfacing	Murphy Lane	SR 1605	DEAD END	0.23	#78 Mat Seal and 1.5" S9.5B	$31,416
2026	7	079-Rockingham	Resurfacing	Nance St.	SR 1704	SR 1605	0.33	#78 Mat Seal and 1.5" S9.5B	$45,075
2026	7	079-Rockingham	Resurfacing	Penn Lake Dr.	SR 2549	DEAD END	0.40	#78 Mat Seal and 1.5" S9.5B	$55,000
2026	7	079-Rockingham	Resurfacing	Picnic Place	SR 1230	CUL-DE-SAC	0.08	#78 Mat Seal and 1.5" S9.5B	$11,000
2026	7	079-Rockingham	Resurfacing	Priddy Dr.	NC 770	END MAINT	0.17	#78 Mat Seal and 1.5" S9.5B	$23,220
2026	7	079-Rockingham	Resurfacing	Redwing Dr.	SR 2310	CUL-DE-SAC	0.09	#78 Mat Seal and 1.5" S9.5B	$12,293
2026	7	079-Rockingham	Resurfacing	Rock Spring Dr.	SR 1001	CUL-DE-SAC	0.23	#78 Mat Seal and 1.5" S9.5B	$31,416
2026	7	079-Rockingham	Resurfacing	Shagbark Dr.	US 158	CUL-DE-SAC	0.27	#78 Mat Seal and 1.5" S9.5B	$36,879
2026	7	079-Rockingham	Resurfacing	Sone Haven Ct.	SR 2953	DEAD END	0.14	#78 Mat Seal and 1.5" S9.5B	$19,123
2026	7	079-Rockingham	Resurfacing	Spring Garden Rd.	SR 2410	END MAINT	0.26	#78 Mat Seal and 1.5" S9.5B	$35,513
2026	7	079-Rockingham	Resurfacing	Stillwater Lane	SR 2953	CUL-DE-SAC	0.42	#78 Mat Seal and 1.5" S9.5B	$58,000
2026	7	079-Rockingham	Resurfacing	Stonegate Ct.	SR 2974	CUL-DE-SAC	0.04	#78 Mat Seal and 1.5" S9.5B	$5,500
2026	7	079-Rockingham	Resurfacing	Tinderbox Rd.	NC 14	SR 2095	0.16	#78 Mat Seal and 1.5" S9.5B	$22,000
2026	7	079-Rockingham	Resurfacing	Town Creek Rd.	SR 2039	NC 14	0.55	#78 Mat Seal and 1.5" S9.5B	$86,000
2026	7	079-Rockingham	Resurfacing	Walker St.	Uhless St.	END MAINT	0.49	#78 Mat Seal and 1.5" S9.5B	$67,000
2026	7	079-Rockingham	Resurfacing	Waynor Dr.	SR 2480	END PVMT	0.14	#78 Mat Seal and 1.5" S9.5B	$19,123
2026	7	079-Rockingham	Resurfacing	Wilbert Rd.	US 220 Bus.	END MAINT	0.12	#78 Mat Seal and 1.5" S9.5B	$16,500
2026	7	079-Rockingham	Resurfacing	Wild Fern Lane	DEAD END	SR 2987	0.66	#78 Mat Seal and 1.5" S9.5B	$91,000
2026	7	079-Rockingham	Resurfacing	Woodford Lane	SR 1110	DEAD END	0.15	#78 Mat Seal and 1.5" S9.5B	$20,489
2026	7	079-Rockingham	Preservation	Auction Rd.	SR 1312	DEAD END	0.30	Seal - Double and Fog Seal	$9,000
2026	7	079-Rockingham	Preservation	Beaver Creek Rd.	SR 1321	SR 1300	2.58	Seal - Double and Fog Seal	$77,400
2026	7	079-Rockingham	Preservation	Brewer Rd.	SR 1336	END MAINT	0.61	Seal - Double and Fog Seal	$18,900
2026	7	079-Rockingham	Preservation	Brushy Mountain Rd.	NC 770	END MAINT	1.31	Seal - Double	$39,300
2026	7	079-Rockingham	Preservation	Camden Rd.	SR 2208	US 220	0.10	Seal - Double and Fog Seal	$9,900
2026	7	079-Rockingham	Preservation	Can Rd.	SR 1352	DEAD END	0.42	Seal - Double and Fog Seal	$12,600
2026	7	079-Rockingham	Preservation	Cedar Mountain Rd.	NC 135	DEAD END	1.53	Seal - Double and Fog Seal	$45,900
2026	7	079-Rockingham	Preservation	Chaney Loop	SR 1395	SR 1395	1.03	Seal - Double and Fog Seal	$30,900
2026	7	079-Rockingham	Preservation	Chapel Rd.	SR 1395	DEAD END	0.40	Seal - Double and Fog Seal	$12,000
2026	7	079-Rockingham	Preservation	Community Baptist Ch. Rd	SR 1321	SCL	0.86	Seal - Double and Fog Seal	$25,800
2026	7	079-Rockingham	Preservation	Ellis Rd.	SR 1321	END MAINT	0.20	Seal - Double and Fog Seal	$6,000
2026	7	079-Rockingham	Preservation	Glenn Chapel Rd.	NC 770	SR 1348	1.38	Seal - Double and Fog Seal	$41,400
2026	7	079-Rockingham	Preservation	Hall Rd.	SR 1335	END MAINT	0.48	Seal - Double and Fog Seal	$14,400

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	7	079-Rockingham	Preservation	Hamlin Ford Rd.	SR 1348	END MAINT	0.60	Seal - Double and Fog Seal	$18,000
2026	7	079-Rockingham	Preservation	Harry Rd.	SR 1341	DEAD END	0.30	Seal - Double and Fog Seal	$9,000
2026	7	079-Rockingham	Preservation	Hen Rd.	NC 770	END MAINT	0.40	Seal - Double	$12,000
2026	7	079-Rockingham	Preservation	Hopper Rd.	NC 770	END MAINT	1.22	Seal - Double and Fog Seal	$36,600
2026	7	079-Rockingham	Preservation	Joyce School Rd.	SR 1330	DEAD END	0.30	Seal - Double and Fog Seal	$9,000
2026	7	079-Rockingham	Preservation	Ledbetter Rd.	SR 1395	SR 1300	2.50	Seal - Double and Fog Seal	$75,000
2026	7	079-Rockingham	Preservation	Local Rd.	NC 770	SR 1348	0.82	Seal - Double and Fog Seal	$24,600
2026	7	079-Rockingham	Preservation	Manual Rd.	SR 1300	SR 1336	1.30	Seal - Double and Fog Seal	$39,000
2026	7	079-Rockingham	Preservation	Martin Rd.	SR 1312	END MAINT	0.40	Seal - Double and Fog Seal	$12,000
2026	7	079-Rockingham	Preservation	Mayo Mountain Rd.	US 220 Bus.	END MAINT.	0.22	Seal - Double and Fog Seal	$6,600
2026	7	079-Rockingham	Preservation	Means Creek Rd.	SR 1348	SR 1347	1.37	Seal - Double and Fog Seal	$41,100
2026	7	079-Rockingham	Preservation	Missouri Lane	NC 704	END MAINT	0.07	Seal - Double and Fog Seal	$2,100
2026	7	079-Rockingham	Preservation	Mockingbird Rd.	SR 1300	END MAINT	0.90	Seal - Double and Fog Seal	$27,000
2026	7	079-Rockingham	Preservation	Mountain Rd.	SR 2208	US 220	0.10	Seal - Double and Fog Seal	$3,300
2026	7	079-Rockingham	Preservation	Nick Rd.	NC 770	END MAINT	0.70	Seal - Double and Fog Seal	$21,000
2026	7	079-Rockingham	Preservation	Oak Rd.	SR 1326	END MAINT	0.36	Seal - Double and Fog Seal	$10,800
2026	7	079-Rockingham	Preservation	Odell Rd.	SR 1300	DEAD END	1.06	Seal - Double and Fog Seal	$31,800
2026	7	079-Rockingham	Preservation	Orchard Rd.	SR 1336	END MAINT.	0.40	Seal - Double and Fog Seal	$12,000
2026	7	079-Rockingham	Preservation	Park Rd.	SR 1300	NC 770	5.69	Seal - Double and Fog Seal	$166,800
2026	7	079-Rockingham	Preservation	Peach Orchard Rd.	SR 1404	DEAD END	1.19	Seal - Double and Fog Seal	$35,700
2026	7	079-Rockingham	Preservation	Reddie Rd.	SR 1395	DEAD END	0.50	Seal - Double and Fog Seal	$15,000
2026	7	079-Rockingham	Preservation	Reginald Rd.	SR 1300	DEAD END	0.42	Seal - Double and Fog Seal	$12,600
2026	7	079-Rockingham	Preservation	Rink St.	SR 1300	END PVMT	0.17	Seal - Double and Fog Seal	$5,100
2026	7	079-Rockingham	Preservation	Squire Loop Rd.	SR 1300	SR 1300	0.18	Seal - Double and Fog Seal	$5,400
2026	7	079-Rockingham	Preservation	Station Rd.	SR 1300	DEAD END	0.69	Seal - Double and Fog Seal	$20,700
2026	7	079-Rockingham	Preservation	Steve Rd.	NC 770	END MAINT	0.21	Seal - Double and Fog Seal	$7,500
2026	7	079-Rockingham	Preservation	Thornton Rd.	NC 770	SR 1321	2.53	Seal - Double and Fog Seal	$65,700
2026	7	079-Rockingham	Preservation	Twin Springs Rd.	BEG PVMT	DEAD END	0.74	Seal - Double and Fog Seal	$20,700
2026	7	079-Rockingham	Preservation	Van Buren Rd.	NC 770	END MAINT	0.80	Seal - Double and Fog Seal	$24,000
2026	7	079-Rockingham	Preservation	Victory Hill Church Rd.	SR 1353	NC 770	4.57	Seal - Double and Fog Seal	$137,100
2026	7	079-Rockingham	Preservation	Wall Rd.	NC 135	END MAINT	0.20	Seal - Double and Fog Seal	$7,200
2026	7	079-Rockingham	Preservation	Washington Mills Rd.	SR 2168	DEAD END	0.10	Seal - Double and Fog Seal	$3,410
2026	8	019-Chatham	Resurfacing	NC 87	US 64 WB	ALAMANCE CO	8.00	#67 Mat Seal and 1.5" S9.5B	$1,750,000
2026	8	019-Chatham	Resurfacing	SR 1525	SR 1539	SR 1532	1.50	1.25" S9.5B	$260,000
2026	8	019-Chatham	Resurfacing	SR 1532	PVMT CHG	END MAINT	1.22	1.25" SF9.5A	$200,000
2026	8	019-Chatham	Resurfacing	SR 1532	US 501	SR 1525	5.22	2.0" S9.5B	$1,800,000
2026	8	019-Chatham	Resurfacing	SR 1700	US 64	END MAINT	2.35	1.25" S9.5B	$352,500
2026	8	019-Chatham	Resurfacing	SR 1711	SR 1713	SR 1700	2.44	1.25" S9.5B	$366,000
2026	8	019-Chatham	Resurfacing	SR 1716	US 64	SR 1717	6.37	1.25" S9.5B	$956,000
2026	8	019-Chatham	Resurfacing	SR 1726	SR 1008	DURHAM CO	1.66	1.25" S9.5B	$249,000
2026	8	019-Chatham	Resurfacing	SR 1736	SR 1738	SR 1733	1.32	1.25" S9.5B	$199,000
2026	8	019-Chatham	Resurfacing	SR 1809	RUSSET RD.	END MAINT	1.71	1.25" SF9.5A	$165,000
2026	8	019-Chatham	Resurfacing	SR 1814	SR 1812	SR 1814	0.29	1.5" S9.5B	$60,000
2026	8	019-Chatham	Resurfacing	SR 1818	SR 1817	CUL DE SAC	0.28	1.25" SF9.5A	$35,000
2026	8	019-Chatham	Resurfacing	SR 1916	SR 1011	NC 42	5.06	1.25" S9.5B	$759,000
2026	8	019-Chatham	Resurfacing	SR 1941	US 64	SR 1700	1.99	1.25" S9.5B	$298,500
2026	8	019-Chatham	Resurfacing	SR 1941	SR 1700	END MAINT	0.89	1.25" S9.5B	$133,500
2026	8	019-Chatham	Resurfacing	SR 1943	PVMT JT	SR 1012	5.05	1.25" S9.5B	$757,500
2026	8	019-Chatham	Resurfacing	SR 2111	SR 2113	SR 2110	1.47	1.5" S9.5B	$265,000
2026	8	019-Chatham	Resurfacing	SR 2114	SR 1176	SR 2113	1.36	1.5" S9.5B	$247,000
2026	8	019-Chatham	Resurfacing	SR 2306	EARLS RETREAT	SR 2303	2.23	1.5" S9.5B	$401,000
2026	8	019-Chatham	Resurfacing	SR 2312	SR 1009	SR 2331	1.55	1.5" S9.5B	$279,000
2026	8	019-Chatham	Resurfacing	US 15/501	LEE CO	SR 1989	5.62	1.5" S9.5C	$1,167,800
2026	8	019-Chatham	Resurfacing	US 64 BUS	US 64 WEST	US 501	3.52	1.5" S9.5B	$675,000
2026	8	019-Chatham	Resurfacing	US 64 WB	SR 1578	SR 1511	2.78	Mill 1.5" and 2.0" S9.5C	$750,000
2026	8	019-Chatham	Preservation	SR 1103	SR 1107	SR 1102	1.24	Seal - Double	$65,000
2026	8	019-Chatham	Preservation	SR 1127	SR 1102	SR 1128	2.02	Seal - Double	$105,000
2026	8	019-Chatham	Preservation	SR 1128	SR 112	RANDOLPH CO	0.12	Seal - Double	$6,000
2026	8	019-Chatham	Preservation	SR 1705	SR 1713	SR 1871	0.21	Seal - Double	$10,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	8	019-Chatham	Preservation	SR 1724	US 501	ORANGE CO	1.83	Crack Seal	$11,000
2026	8	019-Chatham	Preservation	SR 1727	SR 1726	DEAD END	1.29	Seal - Double	$39,000
2026	8	019-Chatham	Preservation	SR 1730	DURHAM CO	WAKE CO	0.71	Crack Seal	$5,000
2026	8	019-Chatham	Preservation	SR 1733	SR 1008	SR 1974	2.91	Crack Seal	$18,000
2026	8	019-Chatham	Preservation	SR 1752	NC 751	SR 1008	2.82	Seal - Double	$85,000
2026	8	019-Chatham	Preservation	SR 1752	NC 751	SR 1764	0.90	Seal - Double	$25,000
2026	8	019-Chatham	Preservation	SR 1755	BEGIN MAINT	NC 751	0.69	Seal - Double	$21,000
2026	8	019-Chatham	Preservation	SR 1795	SR 1764	CUL DE SAC	0.32	Seal - Double	$10,000
2026	8	019-Chatham	Preservation	SR 1907	SR 1972	END MAINT	0.80	Seal - Double and Fog Seal	$24,000
2026	8	019-Chatham	Preservation	SR 1908	SR 1910	END MAINT	0.36	Seal - Double and Fog Seal	$11,000
2026	8	019-Chatham	Preservation	SR 1909	SR 1910	DEAD END	0.39	Seal - Double and Fog Seal	$12,000
2026	8	019-Chatham	Preservation	SR 1911	END PVMT	SR 1912	0.54	Seal - Double	$16,000
2026	8	019-Chatham	Preservation	SR 1917	NC 42	END MAINT	0.73	Seal - Double	$22,000
2026	8	019-Chatham	Preservation	SR 1927	SR 1011	SR 1928	0.32	Seal - Double and Fog Seal	$10,000
2026	8	019-Chatham	Preservation	SR 1928	SR 1927	SR 1927	0.55	Seal - Double and Fog Seal	$17,000
2026	8	019-Chatham	Preservation	SR 1930	SR 1011	END MAINT	0.30	Seal - Double and Fog Seal	$9,000
2026	8	019-Chatham	Preservation	SR 1932	SR 1011	DEAD END	0.30	Seal - Double and Fog Seal	$9,000
2026	8	019-Chatham	Preservation	SR 1934	SR 1011	DEAD END	0.20	Seal - Double and Fog Seal	$6,000
2026	8	019-Chatham	Preservation	SR 1935	SR 1932	SR 1934	0.09	Seal - Double and Fog Seal	$3,000
2026	8	019-Chatham	Preservation	SR 1936	SR 1011	END MAINT	0.28	Seal - Double and Fog Seal	$9,000
2026	8	019-Chatham	Preservation	SR 1952	SR 1012	END PVMT	0.71	Seal - Double	$25,000
2026	8	019-Chatham	Preservation	SR 1952	BEG PVMT	CUL DE SAC	0.68	Seal - Double	$20,000
2026	8	019-Chatham	Preservation	SR 1968	SR 1967	SR 1967	0.11	Crack Seal	$14,000
2026	8	019-Chatham	Preservation	SR 1972	SR 1008	SR 1974	2.27	Crack Seal	$14,000
2026	8	019-Chatham	Preservation	SR 1974	SR 1972	END MAINT	0.52	Seal - Double and Fog Seal	$16,000
2026	8	019-Chatham	Preservation	SR 1980	SR 1011	END MAINT	0.19	Seal - Double and Fog Seal	$6,000
2026	8	019-Chatham	Preservation	SR 1992	SR 1991	END MAINT	0.32	Seal - Double	$10,000
2026	8	019-Chatham	Preservation	SR 1994	SR 1907	END MAINT	0.21	Seal - Double and Fog Seal	$7,000
2026	8	019-Chatham	Preservation	SR 2140	US 421	END PVMT	0.17	Seal - Double	$7,000
2026	8	019-Chatham	Preservation	SR 2159	SR 2160	SR 2163	4.97	Seal - Double	$150,000
2026	8	019-Chatham	Preservation	SR 2167	BRIDGE	SR 2165	0.69	Seal - Double	$28,000
2026	8	019-Chatham	Preservation	SR 2218	BEGIN MAINT	END MAINT	1.10	Seal - Double	$46,200
2026	8	019-Chatham	Preservation	SR 2219	SR 1953	US 15/501	1.80	Seal - Double	$75,600
2026	8	019-Chatham	Preservation	SR 2220	SR 2218	US 15/501	0.15	Seal - Double	$8,400
2026	8	019-Chatham	Preservation	SR 2222	SR 1953	SR 2218	1.50	Seal - Double	$63,000
2026	8	047-Hoke	Resurfacing	SR1003	SR1441	SR1439	3.39	1.5" S9.5B	$554,000
2026	8	047-Hoke	Resurfacing	SR1406	SR1412	SR1003	6.36	1.5" S9.5B	$1,146,600
2026	8	047-Hoke	Resurfacing	US401 N	650 N OF SR1794	SR1588	1.01	Mill 1.5" and 1.5" S9.5C	$253,000
2026	8	047-Hoke	Resurfacing	US401 S	SR1588	PVMNT JT 650'N SR1794	0.91	Mill 1.5" and 1.5" S9.5C	$253,000
2026	8	047-Hoke	Preservation	SR1101	US401	MP 1	1.00	Full Depth Patching and Double Seal and Fog Seal	$45,000
2026	8	047-Hoke	Preservation	SR1200	US401	SR1203	4.41	Full Depth Patching and Double Seal and Fog Seal	$221,000
2026	8	047-Hoke	Preservation	SR1246	SR1235	DEAD END	0.79	Full Depth Patching and Double Seal and Fog Seal	$75,000
2026	8	047-Hoke	Preservation	SR1376	SR1305	DEAD END	0.22	Full Depth Patching and Double Seal and Fog Seal	$25,000
2026	8	047-Hoke	Preservation	SR1377	SR1376	DEAD END	0.03	Full Depth Patching and Double Seal and Fog Seal	$15,000
2026	8	047-Hoke	Preservation	SR1498	SR1003	SR1499	0.40	Full Depth Patching and Double Seal and Fog Seal	$25,000
2026	8	047-Hoke	Preservation	SR1499	DEAD END	END STATE MAINT.	0.23	Full Depth Patching and Double Seal and Fog Seal	$15,000
2026	8	047-Hoke	Preservation	SR1503	SR1498	DEAD END	0.38	Full Depth Patching and Double Seal and Fog Seal	$24,000
2026	8	047-Hoke	Preservation	SR1504	SR1503	DEAD END	0.15	Full Depth Patching and Double Seal and Fog Seal	$10,000
2026	8	047-Hoke	Preservation	SR1509	SR1424	SR1510	0.06	Full Depth Patching and Double Seal and Fog Seal	$10,000
2026	8	047-Hoke	Preservation	SR1510	DEAD END	DEAD END	0.18	Full Depth Patching and Double Seal and Fog Seal	$20,000
2026	8	047-Hoke	Preservation	SR1515	SR1510	DEAD END	0.60	Full Depth Patching and Double Seal and Fog Seal	$30,500
2026	8	047-Hoke	Preservation	SR1516	SR1515	DEAD END	0.09	Full Depth Patching and Double Seal and Fog Seal	$13,000
2026	8	047-Hoke	Preservation	SR1521	SR 1424	DEAD END	0.13	Full Depth Patching and Double Seal and Fog Seal	$12,000
2026	8	053-Lee	Resurfacing	NC Hwy 42	Pvt. Joint at SR 1319 Pickard Rd	. Joint at SR 1322 Tempting Church	1.49	1.5" S9.5B	$259,875
2026	8	053-Lee	Resurfacing	SR 1007 S Plank Rd	Existing Pvt Joint	NC Hwy 15	5.97	1.5" S9.5B	$706,125
2026	8	053-Lee	Resurfacing	SR 1152 Fire Tower Rd	New Pvt Joint SR 1152 Fire Tower Rd	isting Pvt Joint SR 1152 Fire Tower	0.16	Mill 1.5" and 1.5" S9.5B	$32,800
2026	8	053-Lee	Resurfacing	SR 1171 Black Rd	SR 1172 County Line Rd	SR 1170 Blacks Chapel Rd	1.65	1.5" S9.5B	$287,875
2026	8	053-Lee	Resurfacing	SR 1180 Wildlife	US Hwy 1	SR 1179 Rocky Fork Church Rd	1.08	1.5" S9.5B	$188,125
2026	8	053-Lee	Resurfacing	SR 1301 Henley Rd	SR 1300 Chris Cole Rd	SR 1303 Center Church Rd	0.95	1.5" S9.5B	$172,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	8	053-Lee	Resurfacing	SR 1305 Henley Rd	SR 1303 Center Church Rd	SR 1303 Center Church Rd	4.15	1.5" S9.5B	$725,375
2026	8	053-Lee	Resurfacing	SR 1319 Pickard Rd	SR 1318 Steel Bridge Rd	NC Hwy 42	3.38	1.5" S9.5B	$591,500
2026	8	053-Lee	Resurfacing	SR 1335 Bridges Rd	SR 1318 Steel Bridge Rd	SR 1332 S Franklin Dr	0.86	1.5" S9.5B	$150,325
2026	8	053-Lee	Resurfacing	SR 1505 Gunther Rd	SR 1500 Lower River Rd	SR 1537 Poplar Springs Church Rd	0.86	1.5" S9.5B	$150,325
2026	8	053-Lee	Resurfacing	SR 1546 Copeland rd	SR 1535 Berke Thomas Rd	SR 1547 salem Church rd	1.60	1.5" S9.5B	$175,000
2026	8	053-Lee	Resurfacing	SR 1738 Villanow Pl	SR 130 Chris Cole Rd	End of Maintenance Dead End	1.93	1.5" S9.5B	$337,750
2026	8	053-Lee	Resurfacing	SR 1740 Harrington Pl	SR 1738 Villanow Pl	End Of Maintenance	0.10	1.5" S9.5B	$17,500
2026	8	053-Lee	Resurfacing	SR 1748 Holly Pond Rd	SR 1738 Villanow Pl	End Of Maintenance	0.11	1.5" S9.5B	$19,250
2026	8	053-Lee	Resurfacing	SR 1749 Sugar Creek Rd	Sr 1738 Villanow Pl	End of Maintenance	0.12	1.5" S9.5B	$21,000
2026	8	053-Lee	Resurfacing	SR 1751 Twin Bridge Rd	SR 1738 Villanow Pl	End Of Maintenance	0.07	1.5" S9.5B	$12,250
2026	8	053-Lee	Resurfacing	SR 1756 Persimmon Path	SR 1738 Villanow Pl	End Of Maintenance	0.11	1.5" S9.5B	$19,250
2026	8	053-Lee	Resurfacing	us 421	Bridge Joint	Pav Joint at MP3.775	3.72	1.5" S9.5B	$651,000
2026	8	053-Lee	Resurfacing	Us 421	us 421 Pav Joint	21 bridge approach joint MP 14.97	2.83	1.5" S9.5B	$636,125
2026	8	053-Lee	Resurfacing	US Hwy 15	t Joint at SR 1007 S Plank Rd County Line Moore	New Pvt Joint on NC Hwy 15	3.26	1.5" S9.5B	$570,500
2026	8	053-Lee	Preservation	SR 1001 Edwards Rd	SR 1166 Nicholson Rd	Jwards Rd at the County Line Harn	3.17	Seal - Double and Fog Seal	$164,840
2026	8	053-Lee	Preservation	SR 1152 Fire Tower Rd	SR 1237 Carthage St	Pvt Joint Sr 1152 Fire Tower Rd	1.52	Seal - Double and Fog Seal	$78,780
2026	8	053-Lee	Preservation	SR 1416 Riddle Rd	SR 1415 Colon Rd	SR 1002 Lower Moncure Rd	2.48	Seal - Double	$128,960
2026	8	053-Lee	Preservation	SR 1538 Buckhorn Rd	Existing Pvt Joint SR 1538 Buckhorn Rd	isting Pvt Joint SR 1538 BuckHorn I	0.87	Seal - Double	$33,449
2026	8	053-Lee	Preservation	SR 1538 Buckhorn Rd	US Hwy 42	Pvt Joint	1.00	Seal - Double	$22,000
2026	8	053-Lee	Preservation	SR 1543 Thomas Kelly Rd	543 Thomas Kelly Rd At County Line Harnett Co	SR 1538 Buckhorn Rd	1.71	Seal - Double	$56,005
2026	8	062-Montgomery	Resurfacing	NC 109	SR 1121 (Williams St) + .07 miles	SR 1127	1.06	Full Depth Patching and 1.5" S9.5B	$232,500
2026	8	062-Montgomery	Resurfacing	NC 109	NC 73	SR 1121 (Williams St) + .07 miles	0.80	Mill 1.5" and 1.5" S9.5B	$300,000
2026	8	062-Montgomery	Resurfacing	NC 134	SR 1377 (Atkins Dairy Rd)	RANDOLPH COUNTY + .271 miles	4.90	Full Depth Patching and 1.5" S9.5B	$838,800
2026	8	062-Montgomery	Resurfacing	NC 731	SR 1534 (Thickety Creek Rd)	Sr 1005 (Pekin Rd)	5.05	Full Depth Patching and 1.5" S9.5B	$800,000
2026	8	062-Montgomery	Resurfacing	SR 1226	NC 109	Dead End	0.26	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$80,000
2026	8	062-Montgomery	Resurfacing	SR 1524	SR 1003	SR1626	2.97	Full Depth Patching and 1.5" S9.5B	$397,950
2026	8	062-Montgomery	Resurfacing	SR 1549	NC 109	SR 1547	1.00	Full Depth Patching and 1.5" S9.5B	$181,500
2026	8	062-Montgomery	Resurfacing	SR 1565	SR 1543	Little River	0.48	Full Depth Patching and 1.5" S9.5C	$89,300
2026	8	062-Montgomery	Resurfacing	SR 1638	Richmond Co	Richmond Co	0.48	1.5" S9.5B	$81,338
2026	8	062-Montgomery	Preservation	SR 1306	SR 1307	SR 1310	1.90	Full Depth Patching and Double Seal	$94,245
2026	8	062-Montgomery	Preservation	SR 1343	SR 1340	Bridge	3.26	Seal - Double	$156,000
2026	8	062-Montgomery	Preservation	SR 1353	US 220 ALT	Dead End	0.30	Seal - Double and Fog Seal	$20,000
2026	8	062-Montgomery	Preservation	SR 1508	NC 211	DEAD END	0.40	Seal - Double	$20,000
2026	8	062-Montgomery	Preservation	SR 1520	Moore County	I-73	1.41	Seal - Double	$73,000
2026	8	062-Montgomery	Preservation	SR 1533	SR 1534	SR 1535	1.52	Seal - Double	$78,000
2026	8	062-Montgomery	Preservation	SR 1538	SR 1533	End Maintenance	1.09	Seal - Double	$55,000
2026	8	062-Montgomery	Preservation	SR 1647	SR 1332	End Maintenance	0.25	Crack Seal	$8,000
2026	8	063-Moore	Resurfacing	NC 211	PEE DEE Rd	NC 15	0.94	1.5" S9.5B	$164,500
2026	8	063-Moore	Resurfacing	NC 24	Pvt Joint 650' East of NC 705	County Line (Montgomery)	9.65	1.5" S9.5B	$1,688,750
2026	8	063-Moore	Resurfacing	NC 73	Hwy 211	Hwy 15/501	7.48	1.5" S9.5B	$1,312,500
2026	8	063-Moore	Resurfacing	SR 1007 S. Plank Rd.	Hwy 24 (Main St.)	NC 15	4.31	1.5" S9.5B	$745,250
2026	8	063-Moore	Resurfacing	SR 1105 Pinebluff Lake Rd	NC Hwy 15	SR 1103 Currant St	2.82	1.5" S9.5B	$493,325
2026	8	063-Moore	Resurfacing	SR 1146 Spicewood Rd	NC Hwy 211	SR 1143 Samarcand Rd	1.16	1.5" S9.5B	$202,825
2026	8	063-Moore	Resurfacing	SR 1148 Chappell Rd	SR 1146 Spicewood Rd	SR 1145 Candor Rd	0.93	1.5" S9.5B	$162,575
2026	8	063-Moore	Resurfacing	SR 1203 Johnson St	NC Hwy 15/501	SR 1326 Mike Pl	0.39	1.5" S9.5B	$67,375
2026	8	063-Moore	Resurfacing	SR 1216 Juniper Lake Rd	SR 1209 Murdocksville Rd	NC Hwy 211	2.05	1.5" S9.5B	$357,875
2026	8	063-Moore	Resurfacing	SR 1416 Meadow Springs Rd	Hwy 705	County L:ine Randolph	0.62	1.5" S9.5B	$110,250
2026	8	063-Moore	Resurfacing	SR 1419 Cedar Hill Rd	Needham Grove Rd	Reynolds Mill Rd	2.82	1.5" S9.5B	$492,700
2026	8	063-Moore	Resurfacing	SR 1802 Niagara-Carthage Rd	SR Vass-Carthage Rd	Pvt. Joint at Holly Circle Dr	1.35	1.5" S9.5B	$236,250
2026	8	063-Moore	Resurfacing	SR 1802 Niagara-Carthage Rd	SR 1843 Airport Rd	SR 1853 Camp Easter Rd	1.29	1.5" S9.5B	$225,750
2026	8	063-Moore	Resurfacing	SR 1803 Vass-Carthage Rd	South Approach of Bridge joint over NC 15/501	SR 1831 Farm Life School Rd	3.01	1.5" S9.5B	$526,750
2026	8	063-Moore	Resurfacing	SR 1833 Joel Rd	NC Hwy 15/501	SR 1803 Vass-Carthage Rd	1.02	1.5" S9.5B	$178,500
2026	8	063-Moore	Resurfacing	SR 1836 River Daniel Rd	SR 1835 Blue Siding Rd	NC Hwy 22	0.72	1.5" S9.5B	$125,650
2026	8	063-Moore	Resurfacing	SR 1893 Brown Rd	SR 1834 Star Ridge Rd	SR 1803 Vass-Carthage Rd	0.71	1.5" S9.5B	$124,075
2026	8	063-Moore	Resurfacing	SR 2063 PEE DEE Rd	NC Hwy 211	Existing Pvt. Joint	0.46	1.5" S9.5B	$80,500
2026	8	063-Moore	Preservation	SR 1210 Mt Carmel Church Rd	Pvt Joint North of Fire lane rd	NC Hwy 24/27	2.21	Seal - Double	$114,920
2026	8	063-Moore	Preservation	SR 1241 Holly Grove School Rd	NC Hwy 211	SR 1240 Dowd Rd	3.83	Seal - Double	$202,280
2026	8	063-Moore	Preservation	SR 1427 Westside Rd.	NC 705	SR 1428 Dan Rd	0.70	Seal - Double	$36,400
2026	8	063-Moore	Preservation	SR 1432 Browns Chapel Church Rd	SR 1002 Spies Rd	End of Maintenance Dead End	0.68	Seal - Double	$35,984

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	8	063-Moore	Preservation	SR 1461 George P. Rd	NC 22	SR 1456 N Howards Mill Rd	3.35	Seal - Double and Fog Seal	$174,200
2026	8	063-Moore	Preservation	SR 1466 Bernard Purvis Farm Rd	County Line (Chatham)	SR 1461 George P. Rd	0.81	Seal - Double	$42,120
2026	8	063-Moore	Preservation	SR 1600 Wilson Rd	SR 1606 River Rd	NC 22	3.90	Seal - Double	$202,800
2026	8	063-Moore	Preservation	SR 1661 Stanton Hill Rd.	SR 1814 Red Hill Rd.	NC 15	3.67	Seal - Double	$190,840
2026	8	063-Moore	Preservation	SR 1838 McCaskill Rd	NC Hwy 15	SR 1831 Farm life School	1.63	Seal - Double	$84,760
2026	8	063-Moore	Preservation	SR 1843 Airport Rd	SR 1853 Camp Easter	SR 1802 Niagara-Carthage Rd	3.09	Seal - Double and Fog Seal	$160,680
2026	8	063-Moore	Preservation	SR 2017 McGill Rd	NC Hwy 690	SR 2017 Morrison Bridge Rd	1.32	Seal - Double	$68,380
2026	8	063-Moore	Preservation	SR 2021 Morrison Bridge Rd	SR 2017 McGill Rd	NC 690	1.68	Seal - Double	$87,568
2026	8	076-Randolph	Resurfacing	NC 22	SR 2138 Mack Lineberry Rd.	SR 2443 Randolph Ch. Rd.	2.26	1.5" S9.5C and Widen	$320,000
2026	8	076-Randolph	Resurfacing	SR 1175	SR 1143	SR 1174	4.16	1.5" S9.5B	$600,000
2026	8	076-Randolph	Resurfacing	SR 1182	NC 49	SR 1183	1.14	Full Depth Patching and 1.25" S9.5B	$170,550
2026	8	076-Randolph	Resurfacing	SR 1401	DAVIDSON COUNTY	SR 1344	5.06	1.5" S9.5B	$725,000
2026	8	076-Randolph	Resurfacing	SR 1415	SR 1416	SR 1004	1.01	1.5" S9.5B	$151,000
2026	8	076-Randolph	Resurfacing	SR 1502	US 220 BUS	SR 1504	0.98	1.5" S9.5B	$147,000
2026	8	076-Randolph	Resurfacing	SR 1524	B750078	SR 1525	1.45	Full Depth Patching and 1.5" S9.5B	$217,350
2026	8	076-Randolph	Resurfacing	SR 1526	SR 1525 BEESON FARM RD.	US HWY 311	4.08	1.5" S9.5B	$612,000
2026	8	076-Randolph	Resurfacing	SR 1922	SR 1978	SR 1928	2.71	1.5" S9.5B	$370,000
2026	8	076-Randolph	Resurfacing	SR 1928	END DIV	SR 1927 + .051 MILES	1.27	Seal - Single and 1.5" S9.5B	$178,000
2026	8	076-Randolph	Resurfacing	SR 2111	SR 2132 Bethany Ch. Rd.	SR 2116 New Salem Rd.	2.03	Seal - Single and 1.25" S9.5A	$350,000
2026	8	076-Randolph	Resurfacing	SR 2149	US 220 BUS	SR 2261 Old Liberty Rd.	1.76	Full Depth Patching and 1.5" S9.5B	$290,000
2026	8	076-Randolph	Resurfacing	SR 2159	SR 2261	SR 2183	0.44	1.5" S9.5B	$66,000
2026	8	076-Randolph	Resurfacing	SR 2167	US 220 Bus	SR 2261	0.44	1.5" S9.5C	$66,150
2026	8	076-Randolph	Resurfacing	SR 2442	SR 2459	NC 49	5.54	Full Depth Patching and 1.5" S9.5B	$990,000
2026	8	076-Randolph	Resurfacing	SR 2442	SR 2407 Shiloh Rd.	SR 2459	4.20	Full Depth Patching and 1.5" S9.5B	$750,000
2026	8	076-Randolph	Resurfacing	SR 2476	SR 2472 Shady Grove Ch. Rd.	US 64	1.57	Full Depth Patching and 1.5" S9.5B	$210,000
2026	8	076-Randolph	Resurfacing	SR 2481	SR 2455	US 64	4.28	1.5" S9.5B	$642,000
2026	8	076-Randolph	Resurfacing	SR 2481	SR 2455	US 64	0.56	1.5" S9.5B	$69,580
2026	8	076-Randolph	Resurfacing	SR 2611	SR 2610	SR 2614	1.67	1.5" S9.5B	$201,000
2026	8	076-Randolph	Resurfacing	SR 2621	NC 22	SR 2628 Parks Crossroads Ch. Rd.	3.09	Full Depth Patching and 1.5" S9.5B	$525,000
2026	8	076-Randolph	Resurfacing	SR 2625	SR 2621 Foushee Rd.	SR 2642 Old Siler City Rd.	1.15	Full Depth Patching and 1.5" S9.5B	$210,000
2026	8	076-Randolph	Resurfacing	SR 2631	US 64	SR 2629 Burgess Kivett Rd.	1.39	Full Depth Patching and 1.5" S9.5B	$250,000
2026	8	076-Randolph	Resurfacing	SR 2634	Chatham Co. Line	NC 22	7.01	Full Depth Patching and 1.5" S9.5B	$1,200,000
2026	8	076-Randolph	Resurfacing	SR 2642	NC 22	SR 2634 Old Coleridge Rd.	4.77	Full Depth Patching and 1.5" S9.5B	$800,000
2026	8	076-Randolph	Resurfacing	SR 2662	SR 2634 Old Coleridge Rd.	SR 2642 Old Siler City Rd.	3.39	1.5" S9.5B	$500,000
2026	8	076-Randolph	Resurfacing	SR 2717	SR 2611	CUL DE SAC	0.28	1.5" S9.5B	$33,000
2026	8	076-Randolph	Resurfacing	SR 2820	US 220 BUS	NC 159	1.93	Full Depth Patching and 1.5" S9.5B	$350,000
2026	8	076-Randolph	Resurfacing	SR 2824	SR 2826	SR 2834	1.56	Full Depth Patching and 1.25" S9.5B	$206,000
2026	8	076-Randolph	Resurfacing	SR 2826	SR 2824	US 64	1.74	1.5" S9.5B	$200,000
2026	8	076-Randolph	Resurfacing	SR 2839	US 220 BUS	SR 2975	2.45	Mill 1.25" and 1.25" S9.5B	$600,000
2026	8	076-Randolph	Resurfacing	US 64	Davidson County	MM 10.7	10.70	Mill 1.5" and 1.5" S9.5C	$3,300,000
2026	8	076-Randolph	Preservation	SR 1533	SR 1526 Edgar Rd.	SR 1534 Roy Farlow Rd.	1.28	Full Depth Patching and Double Seal and Fog Seal	$90,000
2026	8	076-Randolph	Preservation	SR 1535	SR 1858 Old Marlboro Rd.	SR 1536 Mt. Olive Ch. Rd.	0.91	Full Depth Patching and Double Seal and Fog Seal	$65,000
2026	8	076-Randolph	Preservation	SR 1536	SR 1526 Edgar Rd.	Dead End	1.02	Full Depth Patching and Double Seal and Fog Seal	$72,000
2026	8	076-Randolph	Preservation	SR 1546	SR 3106 Kennedy Rd.	SR 1545 Millers Mill Rd.	0.54	Full Depth Patching and Double Seal and Fog Seal	$40,000
2026	8	076-Randolph	Preservation	SR 1567	SR 1804 Riverview Dr.	SR 1004 Archdale Rd.	0.48	Full Depth Patching and Double Seal and Fog Seal	$50,000
2026	8	076-Randolph	Preservation	SR 1606	SR 1564 Meadowbrook Dr.	Dead End	0.47	Full Depth Patching and Double Seal and Fog Seal	$35,000
2026	8	076-Randolph	Preservation	SR 1640	SR 1564 Meadowbrook Dr.	Younts View Dr.	0.39	Full Depth Patching and Double Seal and Fog Seal	$30,000
2026	8	076-Randolph	Preservation	SR 1656	SR 1606 Trinity Blvd.	SR 1565 Ronniedale Rd.	0.52	Full Depth Patching and Double Seal and Fog Seal	$39,000
2026	8	076-Randolph	Preservation	SR 1703	SR 1606 Trinity Blvd.	End of Maint.	0.12	Full Depth Patching and Double Seal and Fog Seal	$11,000
2026	8	076-Randolph	Preservation	SR 1724	SR 1606 Hilltop Ave.	SR 3212 Albertson View St.	0.14	Full Depth Patching and Double Seal and Fog Seal	$14,000
2026	8	076-Randolph	Preservation	SR 1729	SR 1858 Old Marlboro Rd.	Dead End	0.54	Full Depth Patching and Double Seal and Fog Seal	$41,000
2026	8	076-Randolph	Preservation	SR 1730	SR 1729 Clover Dr.	Dead End	0.30	Full Depth Patching and Double Seal and Fog Seal	$25,000
2026	8	076-Randolph	Preservation	SR 1746	SR 1004 Archdale Rd.	Dead End	0.30	Full Depth Patching and Double Seal and Fog Seal	$25,000
2026	8	076-Randolph	Preservation	SR 1759	SR 1760 Broken Oak Rd.	Dead End	0.45	Full Depth Patching and Double Seal and Fog Seal	$36,000
2026	8	076-Randolph	Preservation	SR 1760	SR 3106 Kennedy Rd.	Dead End	0.49	Full Depth Patching and Double Seal and Fog Seal	$36,000
2026	8	076-Randolph	Preservation	SR 1778	SR 1858 Old Marlboro Rd.	Dead End	0.49	Full Depth Patching and Double Seal and Fog Seal	$37,000
2026	8	076-Randolph	Preservation	SR 1779	SR 1778 Beaumont Dr.	Dead End	0.28	Full Depth Patching and Double Seal and Fog Seal	$21,000
2026	8	076-Randolph	Preservation	SR 1799	SR 1004 Archdale Rd.	SR 1800 Kay Lynn Dr.	0.07	Full Depth Patching and Double Seal and Fog Seal	$10,000
2026	8	076-Randolph	Preservation	SR 1800	SR 1799 Woodlyn Way	SR 1566 Fairview Ch. Rd.	0.18	Full Depth Patching and Double Seal and Fog Seal	$17,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	8	076-Randolph	Preservation	SR 1801	SR 1567 Village Dr.	SR 1806 Creekview Dr.	0.25	Full Depth Patching and Double Seal and Fog Seal	$25,000
2026	8	076-Randolph	Preservation	SR 1802	SR 1567 Village Dr.	SR 1805 Kynwood Dr.	0.16	Full Depth Patching and Double Seal and Fog Seal	$15,000
2026	8	076-Randolph	Preservation	SR 1803	SR 1567 Village Dr.	SR 1805 Kynwood Dr.	0.12	Full Depth Patching and Double Seal and Fog Seal	$12,000
2026	8	076-Randolph	Preservation	SR 1804	SR 1567 Village Dr.	Dead End	0.33	Full Depth Patching and Double Seal and Fog Seal	$25,000
2026	8	076-Randolph	Preservation	SR 1805	SR 1004 Archdale Rd.	SR 1806 Creekview Dr.	0.47	Full Depth Patching and Double Seal and Fog Seal	$35,000
2026	8	076-Randolph	Preservation	SR 1806	SR 1801 Parkway Dr.	SR 1863 Beech Cir.	0.79	Full Depth Patching and Double Seal and Fog Seal	$65,000
2026	8	076-Randolph	Preservation	SR 1812	SR 1004 Archdale Rd.	SR 1813 Redding Ct.	0.30	Full Depth Patching and Double Seal and Fog Seal	$25,000
2026	8	076-Randolph	Preservation	SR 1813	Dead End	Dead End	0.13	Full Depth Patching and Double Seal and Fog Seal	$11,000
2026	8	076-Randolph	Preservation	SR 1814	SR 1858 Old Marlboro Rd.	SR 1818 Meadow Lark Ln.	0.27	Full Depth Patching and Double Seal and Fog Seal	$21,000
2026	8	076-Randolph	Preservation	SR 1815	SR 1817 Quail Meadow Dr.	SR 1814 Pheasant Ridge Dr.	0.11	Full Depth Patching and Double Seal and Fog Seal	$11,000
2026	8	076-Randolph	Preservation	SR 1816	SR 1814 Pheasant Ridge Dr.	Dead End	0.34	Full Depth Patching and Double Seal and Fog Seal	$27,500
2026	8	076-Randolph	Preservation	SR 1817	SR 1858 Old Marlboro Rd.	SR 1816 Loblolly Dr.	0.19	Full Depth Patching and Double Seal and Fog Seal	$18,500
2026	8	076-Randolph	Preservation	SR 1818	Dead End	SR 3271 Pointer Ln.	0.23	Full Depth Patching and Double Seal and Fog Seal	$20,000
2026	8	076-Randolph	Preservation	SR 1832	SR 1858 Old Marlboro Rd.	SR 1838 Carlton Dr.	0.26	Full Depth Patching and Double Seal and Fog Seal	$21,000
2026	8	076-Randolph	Preservation	SR 1833	SR 1858 Old Marlboro Rd.	SR 1837 Pearl Ave.	0.34	Full Depth Patching and Double Seal and Fog Seal	$27,500
2026	8	076-Randolph	Preservation	SR 1834	SR 1858 Old Marlboro Rd.	SR 1837 Pearl Ave.	0.35	Full Depth Patching and Double Seal and Fog Seal	$30,000
2026	8	076-Randolph	Preservation	SR 1835	SR 1858 Old Marlboro Rd.	SR 1837 Pearl Ave.	0.37	Full Depth Patching and Double Seal and Fog Seal	$30,000
2026	8	076-Randolph	Preservation	SR 1836	SR 1858 Old Marlboro Rd.	Dead End	0.44	Full Depth Patching and Double Seal and Fog Seal	$35,000
2026	8	076-Randolph	Preservation	SR 1837	SR 1004 Hillsville Rd.	SR 1836 Grey Dr.	0.81	Full Depth Patching and Double Seal and Fog Seal	$58,000
2026	8	076-Randolph	Preservation	SR 1838	SR 1004 Hillsville Rd.	SR 1837 Pearl Ave.	0.36	Full Depth Patching and Double Seal and Fog Seal	$30,000
2026	8	076-Randolph	Preservation	SR 1844	SR 1004 Hillsville Rd.	Dead End	0.36	Full Depth Patching and Double Seal and Fog Seal	$30,000
2026	8	076-Randolph	Preservation	SR 1845	SR 1004 Hillsville Rd.	Dead End	0.34	Full Depth Patching and Double Seal and Fog Seal	$28,500
2026	8	076-Randolph	Preservation	SR 1849	SR 1004 Hillsville Rd.	Dead End	0.21	Full Depth Patching and Double Seal and Fog Seal	$20,000
2026	8	076-Randolph	Preservation	SR 1850	SR 1849 Valley Ridge Dr.	SR 1004 Hillsville Rd.	0.53	Full Depth Patching and Double Seal and Fog Seal	$40,000
2026	8	076-Randolph	Preservation	SR 1851	SR 1850 Rollingwood Dr.	Dead End	0.07	Full Depth Patching and Double Seal and Fog Seal	$10,000
2026	8	076-Randolph	Preservation	SR 1852	SR 1850 Rollingwood Dr.	Dead End	0.07	Full Depth Patching and Double Seal and Fog Seal	$10,000
2026	8	076-Randolph	Preservation	SR 1853	SR 1850 Rollingwood Dr.	Dead End	0.07	Full Depth Patching and Double Seal and Fog Seal	$10,000
2026	8	076-Randolph	Preservation	SR 1861	Dead End	SR 3230 Wood Village Dr.	0.49	Full Depth Patching and Double Seal and Fog Seal	$38,000
2026	8	076-Randolph	Preservation	SR 1862	SR 1861 Oakview Dr.	SR 3188 Lynn Oaks Dr.	0.33	Full Depth Patching and Double Seal and Fog Seal	$28,000
2026	8	076-Randolph	Preservation	SR 1863	SR 1862 Pineview Dr.	SR 3238 Jill Dr.	0.24	Full Depth Patching and Double Seal and Fog Seal	$20,000
2026	8	076-Randolph	Preservation	SR 1880	SR 1564 Meadowbrook Dr.	End of Maintenance	0.08	Full Depth Patching and Double Seal and Fog Seal	$11,000
2026	8	076-Randolph	Preservation	SR 1881	NC 62	Dead End	0.07	Full Depth Patching and Double Seal and Fog Seal	$10,000
2026	8	076-Randolph	Preservation	SR 1888	SR 1564 Meadowbrook Dr.	Dead End	0.22	Full Depth Patching and Double Seal and Fog Seal	$18,000
2026	8	076-Randolph	Preservation	SR 1896	SR 1858 Old Marlboro Rd.	Eugene Estate Dr.	0.23	Full Depth Patching and Double Seal and Fog Seal	$20,000
2026	8	076-Randolph	Preservation	SR 1897	SR 3106 Kennedy Rd.	Dead End	0.38	Full Depth Patching and Double Seal and Fog Seal	$30,000
2026	8	076-Randolph	Preservation	SR 1898	SR 1897 Alamo Dr.	Dead End	0.05	Full Depth Patching and Double Seal and Fog Seal	$5,500
2026	8	076-Randolph	Preservation	SR 2062	SR 1804 Riverview Dr.	Dead End	0.03	Full Depth Patching and Double Seal and Fog Seal	$5,000
2026	8	076-Randolph	Preservation	SR 3103	SR 1656 Elmwood St.	SR 3104 James Ave.	0.17	Full Depth Patching and Double Seal and Fog Seal	$16,000
2026	8	076-Randolph	Preservation	SR 3104	SR 1656 Elmwood St.	SR 3103 Tony Dr.	0.08	Full Depth Patching and Double Seal and Fog Seal	$10,000
2026	8	076-Randolph	Preservation	SR 3110	SR 1564 Meadowbrook Dr.	Dead End	0.15	Full Depth Patching and Double Seal and Fog Seal	$12,000
2026	8	076-Randolph	Preservation	SR 3121	SR 1849 Valley Ridge Dr.	Dead End	0.07	Full Depth Patching and Double Seal and Fog Seal	$10,000
2026	8	076-Randolph	Preservation	SR 3124	SR 1534 Roy Farlow Rd.	SR 3125 Sparky Ln.	0.08	Full Depth Patching and Double Seal and Fog Seal	$11,000
2026	8	076-Randolph	Preservation	SR 3125	SR 3126 Creek Dr.	SR 3124 Cedar Dr.	0.25	Full Depth Patching and Double Seal and Fog Seal	$22,000
2026	8	076-Randolph	Preservation	SR 3126	SR 1534 Roy Farlow Rd.	SR 3125 Sparky Ln.	0.08	Full Depth Patching and Double Seal and Fog Seal	$11,000
2026	8	076-Randolph	Preservation	SR 3146	SR 1858 Old Marlboro Rd.	Dead End	0.11	Full Depth Patching and Double Seal and Fog Seal	$12,000
2026	8	076-Randolph	Preservation	SR 3181	SR 1812 Redding Country Rd.	Dead End	0.04	Full Depth Patching and Double Seal and Fog Seal	$5,000
2026	8	076-Randolph	Preservation	SR 3188	SR 1862 Pineview Dr.	SR 3239 Tallwood Dr.	0.20	Full Depth Patching and Double Seal and Fog Seal	$20,000
2026	8	076-Randolph	Preservation	SR 3212	SR 1656 Elmwood St.	SR 1724 Brookdale Dr.	0.04	Full Depth Patching and Double Seal and Fog Seal	$7,500
2026	8	076-Randolph	Preservation	SR 3221	SR 1844 Hillsdale Park Dr.	SR 1845 Valley Dr.	0.08	Full Depth Patching and Double Seal and Fog Seal	$10,000
2026	8	076-Randolph	Preservation	SR 3230	Dead End	Dead End	0.27	Full Depth Patching and Double Seal and Fog Seal	$22,000
2026	8	076-Randolph	Preservation	SR 3231	SR 3230 Wood Village Dr.	Dead End	0.22	Full Depth Patching and Double Seal and Fog Seal	$20,000
2026	8	076-Randolph	Preservation	SR 3238	SR 1862 Pineview Dr.	SR 3239 Tallwood Dr.	0.19	Full Depth Patching and Double Seal and Fog Seal	$19,000
2026	8	076-Randolph	Preservation	SR 3239	SR 1806 Creekview Dr.	SR 3188 Lynn Oaks Dr.	0.44	Full Depth Patching and Double Seal and Fog Seal	$33,000
2026	8	076-Randolph	Preservation	SR 3271	SR 1816 Loblolly Dr.	SR 1818 Meadow Lark Ln.	0.08	Full Depth Patching and Double Seal and Fog Seal	$11,000
2026	8	077-Richmond	Resurfacing	74 BYP E	SR1900 overpass	NC 177	3.90	Mill 1.5" and 1.5" S9.5C	$1,500,000
2026	8	077-Richmond	Resurfacing	74 BYP W	NC 177	SR1900 overpass	3.90	Mill 1.5" and 1.5" S9.5B	$1,500,000
2026	8	077-Richmond	Resurfacing	EB off ramp	74 byp	NC 177	0.30	Mill 1.5" and 1.5" S9.5B	$50,000
2026	8	077-Richmond	Resurfacing	EB on ramp	NC177	74 byp	0.25	Mill 1.5" and 1.5" S9.5B	$50,000
2026	8	077-Richmond	Resurfacing	SR 1003	1473	SR 1473+2.65MILES	2.65	1.5" S9.5B	$440,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	8	077-Richmond	Resurfacing	SR 1162	SR 1159	SR 1164	2.27	1.5" S9.5B	$425,000
2026	8	077-Richmond	Resurfacing	SR 1230	Sr 1139	Dead End	0.50	5.0" B25.0B	$180,000
2026	8	077-Richmond	Resurfacing	SR 1324	SR 1153	SR 1321	1.60	1.5" S9.5B	$180,000
2026	8	077-Richmond	Resurfacing	SR 1608	Scot co line	SR 1613	2.90	1.5" S9.5B	$405,000
2026	8	077-Richmond	Resurfacing	SR 1903	Alexander	SR 1909	1.09	1.5" S9.5B	$190,000
2026	8	077-Richmond	Resurfacing	SR1903	NC 177	Alexander	0.65	Mill 1.5" and 1.5" S9.5B	$166,000
2026	8	077-Richmond	Resurfacing	WB off ramp	74 byp	NC177	0.30	Mill 1.5" and 1.5" S9.5B	$50,000
2026	8	077-Richmond	Resurfacing	WB on ramp	NC177	74 byp	0.30	Mill 1.5" and 1.5" S9.5B	$50,000
2026	8	077-Richmond	Preservation	SR 1117	SR 1109	SR1118	0.79	Seal - Double and Fog Seal	$26,000
2026	8	077-Richmond	Preservation	SR 1138	SR 1005	SR 1184	0.25	Seal - Double and Fog Seal	$8,000
2026	8	077-Richmond	Preservation	SR 1153	NC 73	SR 1005	2.42	Seal - Double	$101,700
2026	8	077-Richmond	Preservation	SR 1154	NC 73	NC 73 +1.09	1.09	Seal - Double	$46,000
2026	8	077-Richmond	Preservation	SR 1160	NC 73	Montgomery County	0.50	Seal - Double	$14,000
2026	8	077-Richmond	Preservation	SR 1168	SR 1148	NC 109	2.33	Seal - Double	$56,000
2026	8	077-Richmond	Preservation	SR 1212	SR 1156	End PVMT	0.20	Seal - Double	$6,000
2026	8	077-Richmond	Preservation	SR 1217	SR 1124	SR1218	0.14	Seal - Double and Fog Seal	$5,500
2026	8	077-Richmond	Preservation	SR 1218	SR1217	DEAD END	0.12	Seal - Double and Fog Seal	$5,000
2026	8	077-Richmond	Preservation	SR 1224	SR 1200	DEAD END	0.09	Seal - Double and Fog Seal	$5,200
2026	8	077-Richmond	Preservation	SR 1314	SR 1309	SR 1310	3.88	Seal - Double	$95,000
2026	8	077-Richmond	Preservation	SR 1326	US 220	End PVMT	0.30	Seal - Double	$12,292
2026	8	077-Richmond	Preservation	SR 1337	SR 1321	End Maint	0.35	Seal - Double	$14,700
2026	8	077-Richmond	Preservation	SR 1338	US 220	END MAINT	0.11	Seal - Double and Fog Seal	$4,000
2026	8	077-Richmond	Preservation	SR 1339	SR 1307	End PVMT	0.58	Seal - Double	$16,000
2026	8	077-Richmond	Preservation	SR 1470	SR 1465	Moore County	0.47	Seal - Double	$15,000
2026	8	077-Richmond	Preservation	SR 1615	NC 177	NC 38	1.19	Seal - Double	$50,000
2026	8	077-Richmond	Preservation	SR 1666	US 1	SR 1683	0.21	Seal - Double	$6,000
2026	8	077-Richmond	Preservation	SR 1800	NC 381	SCOTLAND COUNTY	2.46	Seal - Double	$103,000
2026	8	077-Richmond	Preservation	SR 1914	SR 1900	SR 1915	1.16	Seal - Double	$38,000
2026	8	077-Richmond	Preservation	SR 1915	SR 1903	SR 1966	1.09	Seal - Double	$28,000
2026	8	077-Richmond	Preservation	SR 1966	SR 1108	SR 1979	1.97	Seal - Double	$51,000
2026	8	077-Richmond	Preservation	SR 2033	SR 2031	SR 2039	0.25	Seal - Double and Fog Seal	$8,000
2026	8	077-Richmond	Preservation	SR 2037	SR 1241	DEAD END	0.48	Seal - Double and Fog Seal	$18,000
2026	8	077-Richmond	Preservation	SR 2039	SR 2031	SR 2040	0.15	Seal - Double and Fog Seal	$5,000
2026	8	077-Richmond	Preservation	SR1332	SR 1317	End PVMT	0.79	Seal - Double	$33,200
2026	8	083-Scotland	Resurfacing	NC 79	SR1132	SR 1128	2.43	Mill 1.5" and 1.5" S9.5C	$410,000
2026	8	083-Scotland	Resurfacing	SR1324	NC144	SR1328	1.17	1.5" S9.5B	$210,600
2026	8	083-Scotland	Resurfacing	SR1324	SR1345	SR1328	1.96	1.5" S9.5B	$352,800
2026	8	083-Scotland	Resurfacing	SR1400	SR1403	MP1.0	1.00	1.5" S9.5B	$180,000
2026	8	083-Scotland	Preservation	SR1105	NC 144	US 74 BUS	4.03	Seal - Double and Fog Seal	$201,500
2026	8	083-Scotland	Preservation	SR1403	SR1406	SR1412	3.04	Seal - Double	$152,000
2026	8	083-Scotland	Preservation	SR1611	SR1639	ROBESON CO LINE	2.78	Seal - Double and Fog Seal	$147,000
2026	8	083-Scotland	Preservation	SR1615	ROBESON CO LINE	SR1621	3.92	Seal - Double and Fog Seal	$196,000
2026	9	029-Davidson	Resurfacing	BUS 85 NBL	SR 1798	RANDOLPH CO LINE	6.20	Mill 1.5" and 1.5" S9.5C	$2,182,048
2026	9	029-Davidson	Resurfacing	BUS 85 SBL	RANDOLPH CO LINE	SR 2004	6.21	Mill 1.5" and 1.5" S9.5C	$2,185,568
2026	9	029-Davidson	Resurfacing	SR 1118	NC 8	SR 1272	1.56	1.5" S9.5B	$347,776
2026	9	029-Davidson	Resurfacing	SR 1272	SR 1396	NC 8	3.06	1.5" S9.5B	$750,394
2026	9	029-Davidson	Resurfacing	SR 1319	SR 1120	SR 1272	1.16	1.5" S9.5B	$369,178
2026	9	029-Davidson	Resurfacing	SR 1323	NC 47	SR 1319	0.91	1.5" S9.5B	$243,443
2026	9	029-Davidson	Resurfacing	SR 1485	NC 150	FORSYTH CO	5.31	Mill 1.5" and 1.5" S9.5C	$1,872,640
2026	9	029-Davidson	Resurfacing	SR 1496	NC 150	NC 150	0.76	1.5" S9.5B	$186,372
2026	9	029-Davidson	Resurfacing	SR 1757	SR 1756	GUILFORD CO	3.03	1.5" S9.5B	$810,586
2026	9	029-Davidson	Resurfacing	SR 1761	SR 1761	SR 1757	0.38	1.5" S9.5B	$101,658
2026	9	029-Davidson	Resurfacing	SR 1762	SR 1761	SR 1763	0.60	1.5" S9.5B	$160,512
2026	9	029-Davidson	Resurfacing	SR 1769	US 70	GUILFORD CO LINE	0.73	Mill 1.5" and 1.5" S9.5B	$214,133
2026	9	029-Davidson	Resurfacing	SR 1776	SR 1772	SR 1763	1.24	1.5" S9.5B	$331,725
2026	9	029-Davidson	Resurfacing	SR 1841	SR 1813	NC 8	3.12	#67 Mat Seal and 1.5" S9.5B	$1,098,240
2026	9	029-Davidson	Resurfacing	SR 2020	END PVMT	SR 2024	3.00	1.5" S9.5B	$528,352
2026	9	029-Davidson	Resurfacing	SR 2066	RANDOLPH CO LINE	SR 2055	4.84	1.5" S9.5B	$1,132,947
2026	9	029-Davidson	Resurfacing	SR 2087	SR 2082	SR 2085	0.70	Mill 1.5" and 1.5" S9.5B	$290,259

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	9	029-Davidson	Resurfacing	SR 2087	SR 2085	SR 2031	0.92	Mill 1.5" and 1.5" S9.5B	$215,424
2026	9	029-Davidson	Preservation	SR 1573	SR 1643	EOM	0.12	Seal - Double and Fog Seal	$10,138
2026	9	029-Davidson	Preservation	SR 1643	SR 1508	EOM	0.24	Seal - Double and Fog Seal	$22,528
2026	9	029-Davidson	Preservation	SR 1716	SR 1800	SR 1802	1.26	Seal - Double and Fog Seal	$106,445
2026	9	029-Davidson	Preservation	SR 1722	SR 1716	EOM	0.87	Seal - Double and Fog Seal	$81,664
2026	9	029-Davidson	Preservation	SR 1761	SR 1755	SR 1762	0.51	Seal - Double and Fog Seal	$47,872
2026	9	029-Davidson	Preservation	SR 1768	SR 1769	EOM	0.25	Seal - Double and Fog Seal	$21,120
2026	9	029-Davidson	Preservation	SR 1782	SR 1783	EOM	0.26	Seal - Double and Fog Seal	$21,965
2026	9	029-Davidson	Preservation	SR 1788	SR 1800	SR 1785	0.79	Seal - Double and Fog Seal	$74,155
2026	9	029-Davidson	Preservation	SR 1789	SR 1800	EOM	0.82	Seal - Double and Fog Seal	$76,971
2026	9	029-Davidson	Preservation	SR 1804	SR 1805	EOM	0.19	Seal - Double and Fog Seal	$16,220
2026	9	029-Davidson	Preservation	SR 1814	SR 1810	SR 1813	1.42	Seal - Double and Fog Seal	$132,821
2026	9	029-Davidson	Preservation	SR 1860	SR 1755	SR 1763	0.90	Seal - Double and Fog Seal	$84,480
2026	9	029-Davidson	Preservation	SR 1865	NC 109	EOM	0.14	Seal - Double and Fog Seal	$11,827
2026	9	029-Davidson	Preservation	SR 1883	SR 1787	SR 1794	0.30	Seal - Double and Fog Seal	$28,160
2026	9	029-Davidson	Preservation	SR 1884	SR 1794	MP .22	0.22	Seal - Double and Fog Seal	$19,618
2026	9	029-Davidson	Preservation	SR 1898	SR 1798	EOM	0.54	Seal - Double and Fog Seal	$50,688
2026	9	029-Davidson	Preservation	SR 1906	SR 1813	EOM	0.25	Seal - Double and Fog Seal	$22,997
2026	9	029-Davidson	Preservation	SR 1963	US 29	SR 2980	0.22	Seal - Double and Fog Seal	$18,586
2026	9	029-Davidson	Preservation	SR 2029	SR 2024	CUL DE SAC	0.40	Seal - Double and Fog Seal	$37,547
2026	9	029-Davidson	Preservation	SR 2310	NC 47	NC 8	5.01	Crack Seal	$32,331
2026	9	029-Davidson	Preservation	SR 2576	SR 1721	EOM	0.20	Seal - Double and Fog Seal	$18,679
2026	9	029-Davidson	Preservation	SR 2709	SR 1722	EOM	0.11	Seal - Double and Fog Seal	$10,325
2026	9	029-Davidson	Preservation	SR 2900	SR 3056	SR 2900	0.55	Seal - Double and Fog Seal	$51,157
2026	9	029-Davidson	Preservation	SR 2901	SR 2900	SR 2900	0.11	Seal - Double and Fog Seal	$10,325
2026	9	029-Davidson	Preservation	SR 2903	SR 1813	EOM	0.17	Seal - Double and Fog Seal	$14,277
2026	9	029-Davidson	Preservation	SR 2920	SR 1722	EOM	0.32	Seal - Double and Fog Seal	$30,037
2026	9	029-Davidson	Preservation	SR 2929	SR 2916	CUL DE SAC	0.40	Seal - Double and Fog Seal	$37,547
2026	9	029-Davidson	Preservation	SR 2937	SR 1802	EOM	0.27	Seal - Double and Fog Seal	$25,344
2026	9	029-Davidson	Preservation	SR 2967	SR 1775	SR 2968	0.20	Seal - Double and Fog Seal	$18,773
2026	9	029-Davidson	Preservation	SR 2968	SR 1775	EOM	0.21	Seal - Double and Fog Seal	$17,741
2026	9	029-Davidson	Preservation	SR 2980	SR 1963	SR 2981	0.21	Seal - Double and Fog Seal	$19,712
2026	9	029-Davidson	Preservation	SR 2981	SR 2980	EOM	0.27	Seal - Double and Fog Seal	$25,344
2026	9	029-Davidson	Preservation	SR 3071	SR 1716	EOM	0.26	Seal - Double and Fog Seal	$24,030
2026	9	029-Davidson	Preservation	SR 3072	SR 3071	EOM	0.08	Seal - Double and Fog Seal	$7,134
2026	9	029-Davidson	Preservation	SR 3073	SR 3071	EOM	0.28	Seal - Double and Fog Seal	$53,316
2026	9	029-Davidson	Preservation	SR 3251	SR 2937	SR 3252	0.09	Seal - Double and Fog Seal	$8,354
2026	9	029-Davidson	Preservation	SR 3252	SR 3251	EOM	0.21	Seal - Double and Fog Seal	$19,994
2026	9	029-Davidson	Preservation	SR 3600	S 1652	EOM	0.23	Seal - Double and Fog Seal	$25,626
2026	9	029-Davidson	Preservation	SR 3601	SR 3600	EOM	0.07	Seal - Double and Fog Seal	$6,571
2026	9	029-Davidson	Preservation	SR 3602	SR 3600	EOM	0.07	Seal - Double and Fog Seal	$15,957
2026	9	029-Davidson	Preservation	US 64	SR 2774	RANDOLPH CO	4.45	Crack Seal	$31,328
2026	9	030-Davie	Resurfacing	NC 801	BRG 13	US 64	3.12	Mill 1.5" and 1.5" S9.5C	$626,053
2026	9	030-Davie	Resurfacing	NC 801	US 601	BRG 13	4.08	Mill 1.5" and 1.5" S9.5C	$1,434,752
2026	9	030-Davie	Resurfacing	NC 801	ROWAN CO	SR 1602	2.34	Mill 1.5" and 1.5" S9.5C	$892,320
2026	9	030-Davie	Resurfacing	SR 1630	SR 1606	US 158	3.59	1.5" S9.5C	$1,007,365
2026	9	030-Davie	Resurfacing	SR 1731	NC 801	SR 1754	1.24	Mill 1.5" and 1.5" S9.5C	$331,190
2026	9	030-Davie	Preservation	SR 1307	US 601	SR 1306	2.36	Crack Seal	$30,486
2026	9	030-Davie	Preservation	SR 1412	US 601	US 601	2.16	Crack Seal	$25,309
2026	9	030-Davie	Preservation	SR 1731	SR 1754	EOM	0.27	Seal - Double and Fog Seal	$25,438
2026	9	030-Davie	Preservation	SR 1732	SR 1731	EOM	0.18	Seal - Double and Fog Seal	$16,896
2026	9	030-Davie	Preservation	SR 1733	SR 1731	EOM	0.15	Seal - Double and Fog Seal	$13,986
2026	9	030-Davie	Preservation	SR 1734	SR 1731	EOM	0.13	Seal - Double and Fog Seal	$12,109
2026	9	030-Davie	Preservation	SR 1735	SR 1734	EOM	0.10	Seal - Double and Fog Seal	$9,481
2026	9	030-Davie	Preservation	SR 1736	SR 1731	EOM	0.30	Seal - Double and Fog Seal	$28,160
2026	9	030-Davie	Preservation	SR 1737	S 1736	EOM	0.04	Seal - Double and Fog Seal	$3,849
2026	9	030-Davie	Preservation	SR 1738	SR 1731	EOM	0.91	Seal - Double and Fog Seal	$85,513
2026	9	030-Davie	Preservation	SR 1739	SR 1738	EOM	0.22	Seal - Double and Fog Seal	$20,182
2026	9	030-Davie	Preservation	SR 1740	SR 1739	EOM	0.08	Seal - Double and Fog Seal	$7,603

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	9	030-Davie	Preservation	SR 1741	SR 1738	EOM	0.07	Seal - Double and Fog Seal	$6,758
2026	9	030-Davie	Preservation	SR 1742	SR 1738	EOM	0.05	Seal - Double and Fog Seal	$4,787
2026	9	030-Davie	Preservation	SR 1743	EOM	EOM	0.25	Seal - Double and Fog Seal	$23,373
2026	9	030-Davie	Preservation	SR 1744	SR 1743	EOM	0.03	Seal - Double and Fog Seal	$3,191
2026	9	030-Davie	Preservation	SR 1747	SR 1731	EOM	0.07	Seal - Double and Fog Seal	$6,101
2026	9	030-Davie	Preservation	SR 1748	SR 1731	SR 1797	0.48	Seal - Double and Fog Seal	$44,681
2026	9	030-Davie	Preservation	SR 1749	SR 1748	SR 1626	0.40	Seal - Double and Fog Seal	$37,640
2026	9	030-Davie	Preservation	SR 1750	SR 1749	EOM	0.40	Seal - Double and Fog Seal	$37,922
2026	9	030-Davie	Preservation	SR 1752	SR 1736	EOM	0.05	Seal - Double and Fog Seal	$4,693
2026	9	030-Davie	Preservation	SR 1753	SR 1735	EOM	0.04	Seal - Double and Fog Seal	$3,285
2026	9	030-Davie	Preservation	SR 1754	SR 1731	SR 1755	0.16	Seal - Double and Fog Seal	$14,550
2026	9	030-Davie	Preservation	SR 1755	EOM	EOM	1.26	Seal - Double and Fog Seal	$118,554
2026	9	030-Davie	Preservation	SR 1756	SR 1750	EOM	0.07	Seal - Double and Fog Seal	$6,665
2026	9	030-Davie	Preservation	SR 1757	SR 1738	EOM	0.06	Seal - Double and Fog Seal	$6,008
2026	9	030-Davie	Preservation	SR 1758	SR 1750	EOM	0.06	Seal - Double and Fog Seal	$5,163
2026	9	030-Davie	Preservation	SR 1759	SR 1731	EOM	0.13	Seal - Double and Fog Seal	$12,390
2026	9	030-Davie	Preservation	SR 1790	SR 1731	EOM	0.04	Seal - Double and Fog Seal	$3,285
2026	9	030-Davie	Preservation	SR 1791	SR 1906	EOM	0.03	Seal - Double and Fog Seal	$2,816
2026	9	030-Davie	Preservation	SR 1792	SR 1731	EOM	0.03	Seal - Double and Fog Seal	$3,192
2026	9	030-Davie	Preservation	SR 1793	SR 1755	EOM	0.06	Seal - Double and Fog Seal	$5,163
2026	9	030-Davie	Preservation	SR 1794	SR 1755	EOM	0.04	Seal - Double and Fog Seal	$3,942
2026	9	030-Davie	Preservation	SR 1795	SR 1755	SR 1799	0.07	Seal - Double and Fog Seal	$6,665
2026	9	030-Davie	Preservation	SR 1796	SR 1795	EOM	0.05	Seal - Double and Fog Seal	$4,506
2026	9	030-Davie	Preservation	SR 1797	SR 1748	EOM	0.09	Seal - Double and Fog Seal	$8,542
2026	9	030-Davie	Preservation	SR 1798	SR 1748	EOM	0.08	Seal - Double and Fog Seal	$7,791
2026	9	030-Davie	Preservation	SR 1799	SR 1795	EOM	0.05	Seal - Double and Fog Seal	$5,069
2026	9	030-Davie	Preservation	SR 1900	SR 1748	EOM	0.05	Seal - Double and Fog Seal	$4,881
2026	9	030-Davie	Preservation	SR 1901	SR 1748	EOM	0.15	Seal - Double and Fog Seal	$13,798
2026	9	030-Davie	Preservation	SR 1902	SR 1906	EOM	0.10	Seal - Double and Fog Seal	$9,293
2026	9	030-Davie	Preservation	SR 1903	SR 1748	EOM	0.24	Seal - Double and Fog Seal	$22,528
2026	9	030-Davie	Preservation	SR 1904	SR 1755	EOM	0.07	Seal - Double and Fog Seal	$6,946
2026	9	030-Davie	Preservation	SR 1905	SR 1798	EOM	0.09	Seal - Double and Fog Seal	$8,448
2026	9	030-Davie	Preservation	SR 1906	SR 1748	SR 1791	0.07	Seal - Double and Fog Seal	$6,477
2026	9	030-Davie	Preservation	SR 1928	SR 1621	SR 1929	0.15	Seal - Double and Fog Seal	$14,174
2026	9	030-Davie	Preservation	SR 1929	SR 1933	EOM	0.38	Seal - Double and Fog Seal	$35,951
2026	9	030-Davie	Preservation	SR 1930	SR 1933	EOM	0.11	Seal - Double and Fog Seal	$10,325
2026	9	030-Davie	Preservation	SR 1931	SR 1731	EOM	0.19	Seal - Double and Fog Seal	$17,741
2026	9	030-Davie	Preservation	SR 1933	SR 1748	SR 1929	0.10	Seal - Double and Fog Seal	$9,668
2026	9	034-Forsyth	Resurfacing	NC 150	SR 4315	GUILFORD CO	1.45	Mill 1.5" and 1.5" S9.5C	$479,659
2026	9	034-Forsyth	Resurfacing	SR 1001	EOM	SR 1103	4.48	Mill 1.5" and 1.5" S9.5C	$1,890,240
2026	9	034-Forsyth	Resurfacing	SR 1001	SR 1171	YADKIN CO	5.71	Mill 1.5" and 1.5" S9.5C	$1,605,120
2026	9	034-Forsyth	Resurfacing	SR 1152	SR 1103	SR 1001	1.42	Mill 1.5" and 1.5" S9.5B	$399,872
2026	9	034-Forsyth	Resurfacing	SR 1528	Bethabara RD	SR 4463	0.53	Mill 1.5" and 1.5" S9.5C	$217,653
2026	9	034-Forsyth	Resurfacing	SR 2030	SR 2021	SR 1969	0.69	1.5" S9.5B	$182,160
2026	9	034-Forsyth	Resurfacing	SR 3153	NC 67	PVMTJT	0.61	Mill 1.5" and 1.5" S9.5C	$769,413
2026	9	034-Forsyth	Resurfacing	SR 4278	SR 4315	SR 4315	1.14	Mill 1.5" and #67 Mat Seal and 1.5" S9.5A	$481,536
2026	9	034-Forsyth	Resurfacing	SR 4315	Harmon Creek Rd (NS)	US 421	0.66	Mill 1.5" and 1.5" S9.5C	$462,528
2026	9	034-Forsyth	Resurfacing	US 158	DAVIE CO	SR 1101	2.14	Mill 1.5" and 1.5" S9.5C	$903,936
2026	9	034-Forsyth	Preservation	NC 67	NC 150	US 421	3.27	Crack Seal	$46,042
2026	9	034-Forsyth	Preservation	SR 1467	NC 67	EOM	0.82	Seal - Double and Fog Seal	$76,971
2026	9	034-Forsyth	Preservation	SR 1474	SR 1473	EOM	1.34	Seal - Double and Fog Seal	$113,203
2026	9	034-Forsyth	Preservation	SR 1474	SR 1475	SR 1473	0.84	Seal - Double and Fog Seal	$78,566
2026	9	034-Forsyth	Preservation	SR 1475	NC 67	EOM	0.51	Seal - Double and Fog Seal	$47,497
2026	9	034-Forsyth	Preservation	SR 1476	SR 1475	EOM	0.40	Seal - Double and Fog Seal	$30,338
2026	9	034-Forsyth	Preservation	SR 1477	SR 1476	EOM	0.39	Seal - Double and Fog Seal	$29,512
2026	9	034-Forsyth	Preservation	SR 1614	SR 1619	EOM	0.88	Seal - Double and Fog Seal	$73,920
2026	9	034-Forsyth	Preservation	SR 1615	SR 1616	EOM	0.20	Seal - Double and Fog Seal	$18,586
2026	9	034-Forsyth	Preservation	SR 1616	SR 1619	SR 1620	1.42	Seal - Double and Fog Seal	$120,215
2026	9	034-Forsyth	Preservation	SR 1617	SR 1616	EOM	0.11	Seal - Double and Fog Seal	$9,546

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	9	034-Forsyth	Preservation	SR 1618	SR 1616	EOM	0.59	Seal - Double and Fog Seal	$50,181
2026	9	034-Forsyth	Preservation	SR 1899	SR 1619	EOM	0.11	Seal - Double and Fog Seal	$10,138
2026	9	034-Forsyth	Preservation	SR 3948	NC 67	EOM	0.35	Seal - Double and Fog Seal	$32,853
2026	9	034-Forsyth	Preservation	SR 3977	SR 1616	EOM	0.05	Seal - Double and Fog Seal	$4,787
2026	9	034-Forsyth	Preservation	SR 3999	S 3948	EOM	0.12	Seal - Double and Fog Seal	$11,264
2026	9	034-Forsyth	Preservation	SR 4036	SR 1641	EOM	0.20	Crack Seal	$2,700
2026	9	034-Forsyth	Preservation	SR 4037	SR 4036	EOM	0.15	Crack Seal	$1,500
2026	9	080-Rowan	Resurfacing	SR 1243	SR 1337	US 29	2.67	1.5" S9.5B	$654,755
2026	9	080-Rowan	Resurfacing	SR 1308	SR 1221	SR 1238	2.66	1.5" S9.5B	$593,003
2026	9	080-Rowan	Resurfacing	SR 1337	SR 1339	SR 1221	0.92	1.5" S9.5B	$205,099
2026	9	080-Rowan	Resurfacing	SR 2140	US 52	SR 1004	4.27	#67 Mat Seal and 1.5" S9.5B	$1,377,787
2026	9	080-Rowan	Resurfacing	SR 2319	SR 1006	US 52	2.51	1.5" S9.5B	$616,500
2026	9	080-Rowan	Resurfacing	SR 2337	US 52	SR 2335	0.34	Mill 1.5" and 1.5" S9.5B	$120,032
2026	9	080-Rowan	Resurfacing	SR 2339	US 52	SR 2340	0.91	1.5" S9.5B	$221,930
2026	9	080-Rowan	Resurfacing	SR 2340	SR 2344	US 52	2.49	1.5" S9.5B	$554,881
2026	9	080-Rowan	Resurfacing	SR 2344	US 52	US 52	2.37	1.5" S9.5B	$580,942
2026	9	080-Rowan	Resurfacing	SR 2370	SR 1004	SR 2375	1.20	1.5" S9.5B	$240,768
2026	9	080-Rowan	Resurfacing	SR 2370	SR 2375	SR 2343	0.59	1.5" S9.5B	$118,378
2026	9	080-Rowan	Resurfacing	SR 2375	SR 2344	SR 2370	2.75	1.5" S9.5B	$673,392
2026	9	080-Rowan	Resurfacing	SR 2380	US 52	SR 2379	1.59	1.5" S9.5B	$389,665
2026	9	080-Rowan	Resurfacing	SR 2561	SR 2562	NC 152	1.94	1.5" S9.5B	$431,822
2026	9	080-Rowan	Resurfacing	SR 2562	SR 1006	SR 2561	0.10	1.5" S9.5B	$21,625
2026	9	080-Rowan	Resurfacing	SR 2570	SR 1221	SR 1002	1.15	1.5" S9.5B	$256,150
2026	9	080-Rowan	Resurfacing	SR 2783	US 29	EOM	2.04	1.5" S9.5B	$408,302
2026	9	080-Rowan	Resurfacing	US 29	NC 152 - .27MI	SR 1221 - .1MI	2.71	Mill 1.5" and 1.5" S9.5C	$1,033,413
2026	9	080-Rowan	Resurfacing	US 29	SR 1221 +0.06MI	NC 152 +0.4 MI	2.86	Mill 1.5" and 1.5" S9.5C	$1,090,613
2026	9	080-Rowan	Preservation	SR 1002	BRG # 103	SR 2136	2.26	Crack Seal	$4,381
2026	9	080-Rowan	Preservation	SR 1002	SR 2200	SR 1007	1.73	Crack Seal	$5,465
2026	9	080-Rowan	Preservation	SR 1004	BRG# 146	US 52	1.06	Crack Seal	$2,239
2026	9	080-Rowan	Preservation	SR 1007	SR 1002	SR 1004	1.34	Crack Seal	$7,075
2026	9	080-Rowan	Preservation	SR 1710	SR 1526	US 601	2.19	Crack Seal	$4,619
2026	9	080-Rowan	Preservation	SR 1740	SR 1741	US 70	0.76	Seal - Fog	$11,107
2026	9	080-Rowan	Preservation	SR 1741	SR 1743	US 70	1.94	Seal - Double and Fog Seal	$182,170
2026	9	080-Rowan	Preservation	SR 1741	SR 1957	MP 4	1.36	Seal - Double and Fog Seal	$102,166
2026	9	080-Rowan	Preservation	SR 1741	MP 4	WIDTH CHG	1.20	Seal - Double and Fog Seal	$90,146
2026	9	080-Rowan	Preservation	SR 1741	U S70	SR 1957	0.70	Seal - Fog	$10,271
2026	9	080-Rowan	Preservation	SR 1741	WIDTH CHG	SR 1970	1.08	Seal - Double and Fog Seal	$101,602
2026	9	080-Rowan	Preservation	SR 1742	SR 1741	US 70	0.67	Seal - Fog	$9,757
2026	9	080-Rowan	Preservation	SR 1981	SR 1983	SR 1984	1.59	Seal - Double and Fog Seal	$148,929
2026	9	080-Rowan	Preservation	SR 1985	SR 1984	SR 1003	1.52	Seal - Double and Fog Seal	$156,591
2026	9	080-Rowan	Preservation	SR 2019	SR 1984	END MAINT	1.14	Seal - Double and Fog Seal	$107,330
2026	9	080-Rowan	Preservation	SR 2074	SR 2019	EOM	0.18	Seal - Fog	$2,113
2026	9	080-Rowan	Preservation	SR 2085	SR 1984	EOM	0.11	Seal - Double and Fog Seal	$10,611
2026	9	080-Rowan	Preservation	SR 2279	SR 2019	EOM	0.14	Seal - Fog	$2,069
2026	9	080-Rowan	Preservation	SR 2707	CABARUS CO	EOM	0.50	Seal - Double and Fog Seal	$47,139
2026	9	080-Rowan	Preservation	SR 2801	SR 2019	EOM	0.12	Seal - Fog	$1,746
2026	9	080-Rowan	Preservation	SR 2818	SR 1972	SR 1973	0.35	Seal - Double and Fog Seal	$33,241
2026	9	080-Rowan	Preservation	SR 2819	SR 2818	EOM	0.10	Seal - Double and Fog Seal	$9,015
2026	9	080-Rowan	Preservation	SR 2820	SR 2818	EOM	0.13	Seal - Double and Fog Seal	$12,583
2026	9	080-Rowan	Preservation	US 52	CABARRUS CO	SR 2143	1.97	Crack Seal	$5,201
2026	9	080-Rowan	Preservation	US 52	SR 2143	SR 2433	1.95	Crack Seal	$4,118
2026	9	085-Stokes	Resurfacing	NC 268	NC 66	NC 89	3.85	1.5" S9.5B	$956,384
2026	9	085-Stokes	Resurfacing	NC 268	SURRY CO	NC 66	7.96	1.5" S9.5C	$2,905,936
2026	9	085-Stokes	Resurfacing	NC 66	NC 268	NC 268	0.04	1.5" S9.5C	$9,809
2026	9	085-Stokes	Resurfacing	SR 1179	NC 268	SURRY CO	0.74	1.5" S9.5B	$148,474
2026	9	085-Stokes	Resurfacing	SR 1195	NC 268	SR 1210	2.45	1.5" S9.5B	$490,966
2026	9	085-Stokes	Resurfacing	SR 1236	SURRY COUNTY	FORSYTH COUNTY	8.99	1.5" S9.5B	$2,204,588
2026	9	085-Stokes	Preservation	SR 1413	SR 1432	NC 89	0.70	Crack Seal	$4,107
2026	9	085-Stokes	Preservation	SR 1455	NC 704	NC 89	1.29	Crack Seal	$7,568

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	9	085-Stokes	Preservation	SR 1649	NC 704	SR 1652	3.42	Seal - Double and Fog Seal	$321,306
2026	9	085-Stokes	Preservation	SR 1652	SR 1674	NC 704	5.43	Seal - Double and Fog Seal	$509,884
2026	9	085-Stokes	Preservation	SR 1696	NC 772	SR 1697	3.68	Seal - Double and Fog Seal	$345,617
2026	9	085-Stokes	Preservation	SR 1699	SR 1697	EOM	0.07	Seal - Double and Fog Seal	$58,291
2026	9	085-Stokes	Preservation	SR 1700	SR 1676	EOM	0.41	Seal - Double and Fog Seal	$34,721
2026	9	085-Stokes	Preservation	SR 2018	NC 8	SR 2019	4.11	Crack Seal	$24,118
2026	10	004-Anson	Resurfacing	SR 1110 Mayesville Rd	SR 1003	SC line	4.55	1.5" S9.5C and Widen	$1,920,000
2026	10	004-Anson	Resurfacing	SR 1205 White Store Rd	SR 1259 Anson High School Rd	Pvmt Jt Wadesboro City Liimit	0.58	Full Depth Patching and 1.5" S9.5C	$235,000
2026	10	004-Anson	Resurfacing	US 52 N	SR 1634 Grassy Island Rd	Firehouse Ave	0.69	#78 Mat Seal and 2.0" S9.5C	$525,000
2026	10	004-Anson	Resurfacing	US 52 N	RR Bridge north of Dennis Rd	SR 1634 Grassy Island Rd	3.60	#78 Mat Seal and 2.0" S9.5C	$1,800,000
2026	10	004-Anson	Resurfacing	US 74 W	SR 1846 Gravel Plant Rd	ridge west of SR 1801 Hailey's Ferr	2.10	#78 Mat Seal and 2.0" S9.5C	$1,300,000
2026	10	004-Anson	Preservation	SR 1431 Winfield Rd	SR 1432	NC 742 N	2.94	Seal - Double	$111,720
2026	10	004-Anson	Preservation	SR 1614 Red Hill - Mt Vernon Road	SR 1619 Randall Road	NC 742 North	5.26	Seal - Double	$199,880
2026	10	004-Anson	Preservation	SR 1619 Little Creek Road	SR 1621 Plank Road	SR 1619 Randall Road	2.61	Seal - Double	$99,332
2026	10	004-Anson	Preservation	SR 1619 Randall Road	SR 1619 little Creek Road	SR 1621 plank Road	2.76	Seal - Double	$105,100
2026	10	004-Anson	Preservation	SR 1623 Concord Church	SR 1621	SR 1627	1.79	Seal - Double	$68,020
2026	10	004-Anson	Preservation	SR 1624 Woodall	SR 1621	SR 1625	0.80	Seal - Double	$30,400
2026	10	004-Anson	Preservation	SR 1625 Howell Road	SR 1624 Woodall Road	SR 1621 Plank Road	0.64	Seal - Double	$24,320
2026	10	004-Anson	Preservation	SR 1626 Kendall Road	SR 1621 Plank Road	Sr 1624 Woodall Road	0.91	Seal - Double	$34,580
2026	10	004-Anson	Preservation	SR 1628 Springer	SR 1627	SR 1623	1.14	Seal - Double	$43,320
2026	10	004-Anson	Preservation	SR 1631 Buffalo Creek Rd	US 52	SR 1627 Pinkston River Rd	1.49	Seal - Double	$56,620
2026	10	004-Anson	Preservation	SR 1632 Dunlap Rd	US 52	SR 1627 Pinkston River Rd	1.25	Seal - Double	$47,500
2026	10	004-Anson	Preservation	SR 1634 Grassy Island	US 52	NC 109	6.62	Seal - Double	$251,560
2026	10	004-Anson	Preservation	SR 1635 McBride	SR 1634 Grassy Island	SR 1636	0.90	Seal - Double	$34,200
2026	10	004-Anson	Preservation	SR 1651 General Smith	SR 1650	SR 1634	0.46	Seal - Double	$17,480
2026	10	013-Cabarrus	Resurfacing	SR 1132 Flowes Store Rd	SR 1135 Morrison Rd	NC 24/27	1.01	2.0" S9.5C	$350,000
2026	10	013-Cabarrus	Resurfacing	SR 1132 Flowes Store Rd	Pvmt Jt before SR 1147 Flowes Store Rd E	SR 1135 Morrison Rd	3.42	2.0" S9.5C	$1,121,000
2026	10	013-Cabarrus	Resurfacing	SR 1132 Flowes Store Rd	US 601	SR 1147 (Flowes Store Rd East)	4.66	2.0" S9.5C	$1,800,000
2026	10	013-Cabarrus	Resurfacing	SR 1132 Miami Church Rd	SR 2630 Cold Springs Rd	NC 601	1.97	2.0" S9.5C	$655,000
2026	10	013-Cabarrus	Resurfacing	SR 1132 Miami Church Rd	SR 2627 Joe Bost Rd	SR 2630 Cold Springs Rd	1.92	2.0" S9.5C	$602,000
2026	10	013-Cabarrus	Resurfacing	SR 1132 Miami Church Rd	SR 1006 Mt Pleasant Rd S	SR 2627 Joe Bost Rd	1.46	2.0" S9.5C	$535,000
2026	10	013-Cabarrus	Resurfacing	SR 1430 Kannapolis Pkwy EB	NC 3	Professional Park Dr	0.94	2.0" S9.5C	$325,000
2026	10	013-Cabarrus	Resurfacing	SR 1430 Kannapolis Pkwy WB	SR 1622 Trinity Church Rd	Kellswater Bridges Blvd	0.90	2.0" S9.5C	$475,000
2026	10	013-Cabarrus	Resurfacing	SR 1600 Shiloh Ch Rd	Kingsview Dr	SR 1601 Odell School Rd	0.68	1.5" S9.5C	$230,000
2026	10	013-Cabarrus	Resurfacing	SR 1600 Shiloh Ch Rd	Mecklenburg County line	SR 1818 (Placid Rd)	1.39	1.5" S9.5C	$610,000
2026	10	013-Cabarrus	Resurfacing	SR 1621 Barr Rd	Pvmt Jt near Hardwood Ln	SR 1622 Trinity Ch Rd	1.15	1.5" S9.5C	$350,000
2026	10	013-Cabarrus	Resurfacing	SR 1643 Rainbow Dr	NC 3	culvert	0.55	Full Depth Patching and 1.5" S9.5B	$86,000
2026	10	013-Cabarrus	Resurfacing	SR 1706 East First St/ MLK Blvd	SR 1008 S Main St	US 29	0.68	Mill 2.0" and 2.0" S9.5C	$650,000
2026	10	013-Cabarrus	Resurfacing	SR 1947 East 1st St	SR 2154 Little Texas Rd	US 29	0.72	1.5" S9.5C	$380,000
2026	10	013-Cabarrus	Rehabilitation	SR 1146 John White Rd	SR 1147 Flowes Store Rd East	SR 1143 Carl Bost Rd	1.44	FDR and 1.5" S9.5C and Widen	$1,500,000
2026	10	013-Cabarrus	Rehabilitation	SR 1147 Flowes Store Rd East	SR 1146 John White Rd	US 601	1.06	FDR and 1.5" S9.5C and Widen	$1,100,000
2026	10	013-Cabarrus	Preservation	SR 1105 Joyner Rd	SR 1006 Mt Pleasant Rd S	US 601	1.67	Seal - Double and Fog Seal	$143,500
2026	10	013-Cabarrus	Preservation	SR 1106 Carriker Rd	SR 1006 Mt Pleasant Rd S	US 601	0.33	Seal - Double and Fog Seal	$30,000
2026	10	013-Cabarrus	Preservation	SR 1302 Hudspeth	SR 1300 Morehead RD	US 29	1.23	Seal - Double and Fog Seal	$77,790
2026	10	013-Cabarrus	Preservation	SR 1604 Bradford Rd	SR 1442 Odell School Rd	EOM	0.89	Seal - Double and Fog Seal	$50,000
2026	10	013-Cabarrus	Preservation	SR 1605 Overcash Rd	SR 1442 Odell School Rd	EOM	0.70	Seal - Double and Fog Seal	$50,000
2026	10	013-Cabarrus	Preservation	SR 1606 Barnett Rd	SR 1601 Odell School Rd	SR 1442 Windy Rd	0.93	Seal - Double and Fog Seal	$50,200
2026	10	013-Cabarrus	Preservation	SR 1916 Albrook Dr	SR 1608 Davidson Rd	Cul-de-sac	0.16	Seal - Double and Fog Seal	$20,000
2026	10	013-Cabarrus	Preservation	SR 1917 Driftwood Dr	SR 1916 Albrook Dr	Cul-de-sac	0.10	Seal - Double and Fog Seal	$15,000
2026	10	013-Cabarrus	Preservation	SR 2415	St. Johns	Cline School Rd.	1.93	Seal - Double and Fog Seal	$123,177
2026	10	013-Cabarrus	Preservation	SR 2427 Cline School Rd	Mt. Olive	Rimmer	3.48	Seal - Double and Fog Seal	$225,000
2026	10	013-Cabarrus	Preservation	SR 2442 Little Buffalo Rd	NC 49	SR 2416	3.37	Seal - Double and Fog Seal	$213,939
2026	10	013-Cabarrus	Preservation	SR 2510 Songwood Rd	SR 2408	SR 2509	0.39	Seal - Double and Fog Seal	$26,000
2026	10	013-Cabarrus	Preservation	SR 2672 Buffalo Hills Dr	NC 49	SR 2633 Heglar Rd	0.89	Seal - Double and Fog Seal	$63,000
2026	10	013-Cabarrus	Preservation	SR 2676 Wilder Rd	SR 2672 Buffalo Hills Dr	Dead end	0.20	Seal - Double and Fog Seal	$20,000
2026	10	013-Cabarrus	Preservation	SR 2704 Blandwood Dr	SR 2672 Buffalo Hills Dr	Dead end	0.17	Seal - Double and Fog Seal	$20,000
2026	10	060-Mecklenburg	Resurfacing	NC 115	Cornelius St	Iredell County Line	1.74	Mill 1.5" and 1.5" S9.5D	$760,000
2026	10	060-Mecklenburg	Resurfacing	NC 115 NB	SR 6029 Independence Hill Rd	SR 2117 Hambright Rd	1.49	Full Depth Patching and 1.5" S9.5D	$920,000
2026	10	060-Mecklenburg	Resurfacing	NC 115 S Old Statesville Rd	Solstice Way	SR 2459 Eastfield Rd	1.41	Full Depth Patching and 1.5" S9.5D	$625,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	10	060-Mecklenburg	Resurfacing	NC 115 S Old Statesville Rd NB	SR 2117 Hambright Rd	pavement jnt @ Damson Dr	0.56	Full Depth Patching and 1.5" S9.5D	$400,000
2026	10	060-Mecklenburg	Resurfacing	NC 160 Steele Creek Rd	327' before NC 49	Steelecroft Pkwy	0.30	Mill 1.5" and 1.5" S9.5C	$134,000
2026	10	060-Mecklenburg	Resurfacing	NC 160 Steele Creek Rd	Steelecroft Pkwy	327' before NC 49	0.32	Mill 1.5" and 1.5" S9.5C	$134,000
2026	10	060-Mecklenburg	Resurfacing	NC 160 West Blvd	Walton Rd	NC 49 (S Tryon St	1.74	Mill 1.5" and 1.5" S9.5D	$1,230,200
2026	10	060-Mecklenburg	Resurfacing	NC 49 S Tryon St	W Tyvola Rd	Yorkshire Dr	2.15	Mill 1.5" and 1.5" S9.5D	$920,000
2026	10	060-Mecklenburg	Resurfacing	NC 49 S Tryon St	Forest Ave	NC 27 E Morehead St	2.01	Mill 1.5" and 1.5" S9.5D	$1,445,000
2026	10	060-Mecklenburg	Resurfacing	NC 49 S Tryon St	Parkaire Ln	Queene Anne Rd	0.54	Mill 1.5" and 1.5" S9.5D	$192,000
2026	10	060-Mecklenburg	Resurfacing	NC 49 University City Blvd NB	US 29 N Tryon St	NC 24 E WT Harris Blvd	0.96	1.5" S9.5D	$546,000
2026	10	060-Mecklenburg	Resurfacing	NC 49 University City Blvd SB	NC 24 E WT Harris Blvd	US 29 N Tryon St	0.94	Full Depth Patching and 1.5" S9.5D	$640,000
2026	10	060-Mecklenburg	Resurfacing	NC 49 W. Morehead St	US 29 Mint St	NC 49	0.25	Mill 1.5" and 1.5" S9.5D	$238,000
2026	10	060-Mecklenburg	Resurfacing	NC 73	Lincoln County line	Brown Mill Rd	1.96	Full Depth Patching and 1.5" S9.5D	$693,000
2026	10	060-Mecklenburg	Resurfacing	SR 1116 Shopton Rd. West	Catawba River Bridge	SR 1335 Wildlife Rd	0.93	Mill 1.5" and 1.5" S9.5B	$475,000
2026	10	060-Mecklenburg	Resurfacing	SR 1576 West Tyvola Rd	I-77	eom	0.19	1.5" S9.5C	$390,000
2026	10	060-Mecklenburg	Resurfacing	SR 1604 Hawfield Rd	SR 1601 Moores Chapel Rd	end of maintenance	0.43	Full Depth Patching and 1.5" S9.5B	$150,000
2026	10	060-Mecklenburg	Resurfacing	SR 1884 Riverside Dr	SR 1667 Harwood Ln	end of maintenance	0.61	Full Depth Patching and 1.5" S9.5C	$310,000
2026	10	060-Mecklenburg	Resurfacing	SR 2043 Primm Rd	SR 2025 Miranda Rd	end of maintenance	0.68	Full Depth Patching and 1.25" S9.5B	$290,000
2026	10	060-Mecklenburg	Resurfacing	SR 2117 Hambright Rd	end of island at Blyrthe School	NC 21 Statesville Rd	0.45	Mill 1.5" and 1.5" S9.5B	$380,000
2026	10	060-Mecklenburg	Resurfacing	SR 2129 Jim Kidd Rd	SR 2128 Beatties Ford Rd	end of maint	1.18	Mill 1.5" and 1.5" S9.5B	$429,200
2026	10	060-Mecklenburg	Resurfacing	३ 2131 Bud Henderson / Old Bud Hendersc	Beatties Ford Rd	Gilead Rd	1.48	Full Depth Patching and 1.5" S9.5C	$725,000
2026	10	060-Mecklenburg	Resurfacing	SR 2420 East Rocky River Rd	SR 5321 Kistler Farm Rd	SR 2693 Davidson-Concord Rd	1.37	1.5" S9.5C	$456,000
2026	10	060-Mecklenburg	Resurfacing	SR 2433 Mayes Rd	SR 2430 Westmoreland	NC 73 Sam Furr Rd	1.12	Mill 1.5" and 1.5" S9.5B	$450,000
2026	10	060-Mecklenburg	Resurfacing	SR 2442 Ashbury Chapel Rd	SR 2448 Huntersville Concord Rd	SR 2444 Huss McGinnis Rd	1.30	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$470,000
2026	10	060-Mecklenburg	Resurfacing	SR 2442 Ashbury Chapel Rd	SR 2444 Huss McGinnis Rd	SR 2459 Eastfield Rd	1.91	1.5" S9.5C	$860,000
2026	10	060-Mecklenburg	Resurfacing	SR 2444 Hus McGinnis Rd	Asbury Chapel Rd	eom	0.90	Full Depth Patching and 1.25" S9.5B	$290,000
2026	10	060-Mecklenburg	Resurfacing	SR 2600 Washam Potts Rd	NC 115 S Main St	end of maintenance	1.42	1.5" S9.5C	$680,000
2026	10	060-Mecklenburg	Resurfacing	SR 2693 Concord Rd	NC 115	SR 2693 Davidson-Concord Rd	1.95	Mill 1.5" and 1.5" S9.5D	$1,161,000
2026	10	060-Mecklenburg	Rehabilitation	SR 1628 Centergrove Ln	SR 1625 Sam Wilson Rd	EOM	0.39	FDR and 1.5" S9.5B	$200,000
2026	10	060-Mecklenburg	Rehabilitation	SR 2000 Tema Cr	SR 2373 Rozzelles Ferry Rd	SR 2373 Rozzelles Ferry Rd	0.46	FDR and 1.5" S9.5B	$200,000
2026	10	060-Mecklenburg	Rehabilitation	SR 2374 Mountain Island Dr W	NC 16 Brookshire Blvd	EOM	0.22	FDR and 1.5" S9.5B	$130,000
2026	10	060-Mecklenburg	Preservation	SR 1106 Hamilton Rd	Youngblood	Steele Creek	0.73	Rejuvenator	$18,000
2026	10	060-Mecklenburg	Preservation	SR 1980 Ashley Rd	SR 1979 Triangle Dr	SR 1816 Scott Futrell Dr	0.43	Rejuvenator	$11,000
2026	10	060-Mecklenburg	Preservation	SR 3026 Holiday Dr	Plaza Road Ext	cul-de-sac	0.29	Full Depth Patching and 1.25" S9.5B	$70,000
2026	10	060-Mecklenburg	Preservation	SR 4791 Danby Rd	SR 4982 Lancaster Hwy	EOM	0.70	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$191,000
2026	10	060-Mecklenburg	Preservation	SR 4791 Danby Rd	Begin divide	SR 4982 Lancaster Hwy	0.09	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$26,000
2026	10	060-Mecklenburg	Preservation	SR 4792 Dansington Ct	SR 4791 Danby Ln	Cul de sac	0.04	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$26,000
2026	10	060-Mecklenburg	Preservation	SR 4793 Linthorpe Ct	SR 4791 Danby Ln	Cul de sac	0.05	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$26,000
2026	10	060-Mecklenburg	Preservation	SR 4794 Faversham Ct	SR 4791 Danby Ln	Cul de sac	0.04	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$25,000
2026	10	060-Mecklenburg	Preservation	SR 4805 Dannemara Dr	SR 4791 Danby Ln	Cul de sac	0.19	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$51,000
2026	10	060-Mecklenburg	Preservation	SR 4806 Eden Ct	SR 4791 Danby Ln	Cul de sac	0.28	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$92,000
2026	10	060-Mecklenburg	Preservation	SR 4807 Delcorte Ln	SR 4791 Danby Ln	Cul de sac	0.06	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$22,000
2026	10	060-Mecklenburg	Preservation	SR 4843 Darington Ct	SR 4791 Danby Ln	Cul de sac	0.11	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$40,000
2026	10	060-Mecklenburg	Preservation	SR 4844 Delman Ln	SR 4791 Danby Ln	Cul de sac	0.11	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$42,000
2026	10	060-Mecklenburg	Preservation	SR 4845 Longcroft Ct	SR 4791 Danby Ln	Cul de sac	0.02	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$16,000
2026	10	060-Mecklenburg	Preservation	SR 4857 Dawlish Ln	EOM	Cul de sac	0.02	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$14,000
2026	10	060-Mecklenburg	Preservation	SR 4858 Dealtry Ln	EOM	Cul de sac	0.01	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$17,000
2026	10	060-Mecklenburg	Preservation	SR 5076 Windrift Rd	Plaza Rd Ext	cul-de-sac	0.44	Full Depth Patching and 1.25" S9.5B	$209,000
2026	10	060-Mecklenburg	Preservation	SR 5418 Majestic Oak Dr	NC 49 York Rd	Cul-de-sac	0.45	Rejuvenator	$12,000
2026	10	060-Mecklenburg	Preservation	SR 5419 Crooked Branch Ln	SR 5418 Majestic Oak Dr	Cul-de-sac	0.30	Rejuvenator	$8,000
2026	10	060-Mecklenburg	Preservation	SR 5420 Hickory View Ln	SR 5418 Majestic Oak Dr	Dead End	0.20	Rejuvenator	$6,000
2026	10	060-Mecklenburg	Preservation	SR 5421 Lonesome Oak Cir	SR 5419 Crooked Branch Ln	Cul-de-sac	0.05	Rejuvenator	$2,000
2026	10	060-Mecklenburg	Preservation	SR 5951 Old Maple Cir	SR 5418 Majestic Oak Dr	EOM	0.02	Rejuvenator	$2,000
2026	10	084-Stanly	Resurfacing	NC 205	E 2nd St (City St)	E 10th Street (City St)	1.77	Mill 1.5" and 1.5" S9.5C	$815,000
2026	10	084-Stanly	Resurfacing	NC 742	E 1st St (City St)	E 2nd St (City St)	0.21	Mill 1.5" and 1.5" S9.5C	$30,000
2026	10	084-Stanly	Resurfacing	SR 1258 Newt Rd	NC 24/27	SR 1249 Canton Rd	0.39	1.5" S9.5C	$150,000
2026	10	084-Stanly	Resurfacing	SR 1719 Falls Rd	NC 740	Staley St	0.59	Mill 1.5" and 1.5" S9.5C	$305,000
2026	10	084-Stanly	Resurfacing	US 52 North	Lavasque St (Beg c&g)	Jt past NC 49	0.90	Mill 1.5" and 1.5" S9.5C	$830,000
2026	10	084-Stanly	Resurfacing	US 52 North	Jt near SR 1214 Austin Rd	NC 740	1.35	Mill 1.5" and 1.5" S9.5C	$1,380,000
2026	10	084-Stanly	Resurfacing	US 52 North	SR 1524 Prospect Church Rd	SR 1496 Walnut Dr	0.88	Mill 1.5" and 1.5" S9.5C	$680,000
2026	10	084-Stanly	Resurfacing	US 52 North	Morton St	0.1 mi before Knollwood Cir	1.13	Mill 1.5" and 1.5" S9.5C	$950,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	10	084-Stanly	Preservation	SR 1100 Old Sandbar	NC 742	NC 205	2.17	Seal - Double and Widen	$75,950
2026	10	084-Stanly	Preservation	SR 1116 Harris	SR 1117 Griffin Greene	SR 1107 Silver Rd	0.71	Seal - Double and Widen	$39,000
2026	10	084-Stanly	Preservation	SR 1917 Bethlehem Ch Rd	SR 1954 Prince Rd	SR 2001 Old Aquadale Rd	0.18	Seal - Double	$5,000
2026	10	084-Stanly	Preservation	SR 1917 Bethlehem Ch Rd	SR 1954 Prince Rd	SR 2001 Old Aquadale Rd	1.35	Seal - Double	$38,000
2026	10	084-Stanly	Preservation	SR 1917 Old School Rd	SR 1953 Barbees Grove Rd	SR 1970 Hazard Rd	1.66	Seal - Double	$49,000
2026	10	084-Stanly	Preservation	SR 1943 Old Davis Rd	Anson Co Line	SR 1935 Plank Rd	3.73	Seal - Triple	$131,000
2026	10	084-Stanly	Preservation	SR 1951 Deborah St	SR 1951 Wilhoit Ave	SR 1952 Church St	0.05	Seal - Double	$3,000
2026	10	084-Stanly	Preservation	SR 1951 Wilhoit Ave	SR 2001 Old Aquadale Rd	SR 1951 Deborah St	0.07	Seal - Double	$3,500
2026	10	084-Stanly	Preservation	SR 1952 Church St	SR 2001 Old Aquadale Rd	SR 1952 Green Memorial	0.15	Seal - Double	$3,600
2026	10	084-Stanly	Preservation	SR 1952 Green Memorial	SR 1952 Church St	NC 138	0.06	Seal - Double	$3,000
2026	10	084-Stanly	Preservation	SR 1953 Barbees Grove Rd	NC 138	NC 138	3.59	Seal - Double	$80,000
2026	10	084-Stanly	Preservation	SR 1954 Prince Rd	SR 2001 Old Aquadale Rd	SR 1917 Bethlehem Rd	1.73	Seal - Double	$60,000
2026	10	084-Stanly	Preservation	SR 1956 Reap Rd	SR 1956 Old Aquadale Rd	SR 1956 Old Aquadale Rd	2.13	Seal - Double	$50,000
2026	10	084-Stanly	Preservation	SR 1960 Mabry Rd	SR 1984 Union Grove Rd	eom	1.83	Seal - Double	$65,000
2026	10	084-Stanly	Preservation	SR 1961 Dry Rd	SR 1956 Old Aquadale Rd	eom	0.40	Seal - Double	$13,000
2026	10	084-Stanly	Preservation	SR 1962 Medlin Rd	SR 1963 St. Martin Rd	SR 1996 Lona Rd	0.50	Seal - Double	$20,000
2026	10	084-Stanly	Preservation	SR 1964 Wyatt	NC 24/27	SR 1963 St Martin Rd	1.06	Seal - Double	$48,000
2026	10	084-Stanly	Preservation	SR 1967 Sides Rd	SR 1963 St Martin Rd	SR 1956 Old Aquadale Rd	1.37	Seal - Double	$44,000
2026	10	084-Stanly	Preservation	SR 1969 Booger Hollar	SR 1968 St Martin Rd	SR 1953 Barbees Grove Rd	2.20	Seal - Double	$125,001
2026	10	084-Stanly	Preservation	SR 1974 Alonzo Rd	SR 1970 Hazard Rd	NC 138	1.79	Seal - Double and Widen	$65,000
2026	10	084-Stanly	Preservation	SR 1979 Bridgeport	EOP dirt road	SR 1221 Frog Pond Rd	0.58	Seal - Double	$24,000
2026	10	084-Stanly	Preservation	SR 1982 Loop	SR 1934 Mt Zion	SR 1934 Mt Zion	2.75	Seal - Double	$96,250
2026	10	084-Stanly	Preservation	SR 1985 Little Creek	SR 1969 Booger Hollar	eom	0.76	Seal - Double	$23,000
2026	10	084-Stanly	Preservation	SR 1996 Lona Rd	SR 1962 Hobert Rd	eom	0.24	Seal - Double	$5,000
2026	10	084-Stanly	Preservation	SR 2008 Oakhurst	NC 138	eom	0.25	Seal - Double	$5,000
2026	10	084-Stanly	Preservation	SR 2009 Mulberry	SR 2008 Oakhurst Ln	eom	0.13	Seal - Double	$4,000
2026	10	084-Stanly	Preservation	SR 2010 Elm Tree	SR 2042 Justus Rd	SR 2009 Mulberry	0.09	Seal - Double	$4,000
2026	10	084-Stanly	Preservation	SR 2012 Bull Hill Rd	SR 1975 Mclester Rd	SR 1977 Hatley	0.63	Seal - Double	$23,050
2026	10	084-Stanly	Preservation	SR 2024 Converse	NC 24/27	SR 2025 Norton	0.08	Seal - Double	$4,000
2026	10	084-Stanly	Preservation	SR 2025 Norton	SR 2024 Converse	SR 2026 Curtis	0.03	Seal - Double	$3,000
2026	10	084-Stanly	Preservation	SR 2026 Curtis	SR 2025 Norton	SR 1969 Efird Rd	0.17	Seal - Double	$5,300
2026	10	084-Stanly	Preservation	SR 2037 West Ridge Ct	SR 1965 Carriker Rd	eom	0.24	Seal - Double	$5,979
2026	10	084-Stanly	Preservation	SR 2046 Carriker Rd Ext	SR 2046 Clark Rd Ext	eom	0.05	Seal - Double	$4,000
2026	10	090-Union	Resurfacing	NC 742	Anson County line	Stanly County line	2.65	Full Depth Patching and 1.5" S9.5B	$943,000
2026	10	090-Union	Resurfacing	NC 75	SR 1157 Fletcher Broome	SR 1315 Newtown Rd	1.78	#67 Mat Seal and 2.0" S9.5C	$485,000
2026	10	090-Union	Resurfacing	SR 1003 White Store	Anson County Line	SR 1005 Landsford Rd	1.02	1.5" S9.5B	$392,000
2026	10	090-Union	Resurfacing	SR 1003 White Store	SR 1005 Landsford Rd	SR 1911 - Leonard Morgan	2.46	Full Depth Patching and 1.5" S9.5B	$882,000
2026	10	090-Union	Resurfacing	SR 1113 Davis Rd	SR 1117 Providence Rd	SR 1263 Shady Oak Ln	1.42	#67 Mat Seal and 2.0" S9.5B	$650,000
2026	10	090-Union	Resurfacing	SR 1121 Harkey Rd	SR 1117 Providence Rd	SR 1137 Potters Rd	2.32	Full Depth Patching and 1.5" S9.5B	$771,500
2026	10	090-Union	Resurfacing	SR 1134 Lathan Rd	SR 1134 Old Hwy Rd	NC 522	0.72	Full Depth Patching and 1.5" S9.5B	$388,000
2026	10	090-Union	Resurfacing	SR 1315 Newtown Rd	NC 75	SR 1007 Rocky River Rd	2.34	1.5" S9.5B	$866,000
2026	10	090-Union	Resurfacing	SR 1525 Millgrove Rd	SR 1004 Lawyers Rd	NC 218	2.97	1.5" S9.5B	$1,200,000
2026	10	090-Union	Resurfacing	SR 1533 Howey Bottom	SR 1004 W Layers Rd	SR 1534 W Duncan Rd	0.87	1.5" S9.5C	$345,000
2026	10	090-Union	Resurfacing	SR 1534 West Duncan	SR 1533 Howey Botttoms	NC 218	2.49	1.5" S9.5C	$1,002,000
2026	10	090-Union	Resurfacing	SR 1547 Brief Rd	US 601	Mecklenburg County Line	2.03	1.5" S9.5B	$750,000
2026	10	090-Union	Resurfacing	SR 1751 Monroe Ansonville	Treway Ln (city street)	Bob White Cir	0.92	Full Depth Patching and 1.5" S9.5B	$382,000
2026	10	090-Union	Resurfacing	SR 1758 N. Main St	Wilson St	Municipal Limits	0.64	1.5" S9.5B	$285,000
2026	10	090-Union	Resurfacing	SR 1760 Old Williams Rd	SR 1758 N. Main St	Pvmt Jt at cul-de-sac	1.10	1.5" S9.5B	$355,000
2026	10	090-Union	Resurfacing	SR 1901 Hasty Rd	SR 1740 W Main St	SR 1005 S White St	1.25	1.5" S9.5B	$423,000
2026	10	090-Union	Resurfacing	SR 1902 S Elm St	Green St	SR 1901 Hasty Rd	0.60	1.5" S9.5B	$283,000
2026	10	090-Union	Resurfacing	SR 2115 Stack Rd	SR 2128 Mullis Rd	Jt past SR 2133 Sandy Ridge Rd	2.67	#78 Mat Seal and 2.0" S9.5C	$1,257,000
2026	10	090-Union	Resurfacing	SR 2136 Macedonia Church Rd	SR 2115 Stack Rd	NC 207	1.11	Full Depth Patching and 1.5" S9.5B	$335,000
2026	10	090-Union	Resurfacing	SR 2649 Corporate Blvd	US 74	SR 1367 Unionville Indian Trail Rd	0.38	Mill 1.5" and 1.5" S9.5B	$260,000
2026	10	090-Union	Resurfacing	SR 2650 Business Park Dr	SR 2649 Corporate Blvd	EOM	0.14	Mill 1.5" and 1.5" S9.5B	$118,000
2026	10	090-Union	Resurfacing	SR 2651 Associates Ln	SR 2649 Corporate Blvd	EOM	0.11	Mill 1.5" and 1.5" S9.5B	$96,000
2026	10	090-Union	Resurfacing	SR 3177 Groves Edge Ln	SR 2948 Marvin School Rd	SR 3816 (Running Horse Ln	0.56	1.5" S9.5B	$235,000
2026	10	090-Union	Resurfacing	SR 3328 Avanti Dr	NC 16	EOM	0.66	1.5" S9.5B	$263,000
2026	10	090-Union	Resurfacing	SR 3329 Prima Cornice Ct	SR 3328 Avanti Dr	EOM	0.14	1.5" S9.5B	$45,000
2026	10	090-Union	Resurfacing	SR 3330 Resolution Ct	BOM	EOM	0.09	1.5" S9.5B	$26,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	10	090-Union	Resurfacing	SR 3331 Silk Pond Dr	SR 3328 Avanti Dr	SR 3333 Montane Run	0.13	1.5" S9.5B	$45,000
2026	10	090-Union	Resurfacing	SR 3332 Ptarmigan Ct	SR 3328 Avanti Dr	EOM	0.04	1.5" S9.5B	$16,000
2026	10	090-Union	Resurfacing	SR 3333 Montane Run Ct	BOM	EOM	0.26	1.5" S9.5B	$86,000
2026	10	090-Union	Resurfacing	SR 3486 Wheatfield Dr	SR 1313 Joe Kerr	SR 3487 Briar Patch Ter	0.38	1.5" S9.5B	$160,000
2026	10	090-Union	Resurfacing	SR 3487 Briar Patch Ter	SR 3488 Kindling Wood Dr	EOM	0.39	1.5" S9.5B	$150,000
2026	10	090-Union	Resurfacing	SR 3488 Kindling Wood Ln	SR 3487 Briar Patch Ter	EOM	0.43	1.5" S9.5B	$160,000
2026	10	090-Union	Resurfacing	SR 3489 Smokey Hollow Dr	SR 3486 Wheatfield Dr	SR 3176 Wandering Way	0.30	1.5" S9.5B	$105,000
2026	10	090-Union	Resurfacing	SR 3515 Lancaster Ave	West Ave	SR 3515 S Charlotte Ave	0.49	Mill 1.5" and 1.5" S9.5B	$295,200
2026	10	090-Union	Resurfacing	SR 3640 Wyndham Ln	SR 2948 Marvin School Rd	EOM	0.44	1.0" S4.75A	$148,000
2026	10	090-Union	Resurfacing	SR 3641 Appomatox Dr	SR 1313 Joe Kerr	EOM	0.62	1.0" S4.75A	$217,000
2026	10	090-Union	Resurfacing	SR 3642 Armistead C	SR 3640 Wyndham Ln	EOM	0.07	1.0" S4.75A	$22,000
2026	10	090-Union	Resurfacing	SR 3643 Stonehurst Ln	SR 3641 Appomatox Dr	EOM	0.18	1.0" S4.75A	$56,000
2026	10	090-Union	Resurfacing	SR 3838 Pelham Ln	SR 3641 Appomatox Dr	EOM	0.04	1.0" S4.75A	$17,200
2026	10	090-Union	Resurfacing	SR 3839 Bristol Ct	SR 3641 Appomatox Dr	EOM	0.04	1.0" S4.75A	$19,000
2026	10	090-Union	Resurfacing	SR 3840 Corbin Ct	SR 3641 Appomatox Dr	EOM	0.03	1.0" S4.75A	$13,000
2026	10	090-Union	Resurfacing	SR 3841 Marvin Branch Ct	SR 3643 Stonehurst Ln	EOM	0.05	1.0" S4.75A	$18,000
2026	10	090-Union	Rehabilitation	SR 1920 Zion Ch	SR 1921 State Line Rd	SR 1919 Canal Rd	0.89	FDR and 1.0" S9.5A	$225,000
2026	10	090-Union	Preservation	SR 1396 Carter Rd	SR 1476 Wesley Woods	NC 84	0.29	Seal - Double and Fog Seal	$20,500
2026	10	090-Union	Preservation	SR 1448 Leisure Dr	SR 1325 McNeely Rd	eom	0.19	Seal - Double and Fog Seal	$13,500
2026	10	090-Union	Preservation	SR 1449 Pleasure Dr	SR 1448 Leisure Dr	eom	0.19	Seal - Double and Fog Seal	$13,500
2026	10	090-Union	Preservation	SR 1450 Rain Tree Ln	SR 1357 Potters Rd	eom	0.70	Seal - Double and Fog Seal	$50,000
2026	10	090-Union	Preservation	SR 1458 Gatewood	SR 1346 Beauth Church Rd	eom	0.47	Seal - Double and Fog Seal	$33,500
2026	10	090-Union	Preservation	SR 1463 Oxford Terrace	SR 1442 Wellington Dr	eom	0.13	Seal - Double and Fog Seal	$10,000
2026	10	090-Union	Preservation	SR 1476 Wesley Woods	NC 84	SR 1396	0.36	Seal - Double and Fog Seal	$25,500
2026	10	090-Union	Preservation	SR 1731 Curtil Ln	US 74	Anson County line	0.93	Seal - Double and Fog Seal	$72,000
2026	10	090-Union	Preservation	SR 1906 Rushing Rd	SR 1905 High Ridge Ch	Anson County line	0.36	Seal - Double	$22,500
2026	10	090-Union	Preservation	SR 1911 Leonard Morgan Rd	SR 1005 Landsford Rd	SR 1003 White Store Rd	2.15	Seal - Double	$95,000
2026	10	090-Union	Preservation	SR 1919 Canal Rd	SR 1937 Old Pageland-Monroe	SR 1005 Landsford Rd	0.99	Seal - Double	$43,000
2026	10	090-Union	Preservation	SR 1929 Philadelphia Ch Rd	SR 1003 White Store Rd	SR 1915 Smith Town Rd	2.22	Seal - Double	$98,000
2026	10	090-Union	Preservation	SR 1929 Philadelphia Ch Rd	SR 1915 Smith Town Rd	SR 1005 Landsford Rd	0.88	Seal - Double	$38,000
2026	10	090-Union	Preservation	SR 1933 Ajars Rd	SR 1934 Camden Rd	eom	0.98	Seal - Double	$23,000
2026	10	090-Union	Preservation	SR 1940 Belk Mill Rd	SR 1941 Old Pageland/Monroe	SR 1937 Old Pageland Marshville R(	2.04	Seal - Double	$90,000
2026	10	090-Union	Preservation	SR 1953 McRorie Rd	SR 1951 Mt Springs Ch Rd	SR1941 Old Pageland/Monroe	0.24	Seal - Double	$11,000
2026	10	090-Union	Preservation	SR 1960 Lee Pierce Rd	SR 1934 Camden Rd	SR 1740 Old Hwy 74	0.52	Seal - Double	$23,000
2026	10	090-Union	Preservation	SR 1965 Jenkins Rd	SR 1005 Landsford Rd	eom	0.49	Seal - Double	$22,000
2026	10	090-Union	Preservation	SR 1970 D.A. Simpson Rd	SR1941 Old Pageland/Monroe	eom	0.39	Seal - Double	$17,000
2026	10	090-Union	Preservation	SR 1990 Sojourn Rd	SR 1903 Flint Ridge Ch	SR 1991 Sojourn Rd	0.99	Seal - Double	$46,250
2026	10	090-Union	Preservation	SR 1991 Sojourn Rd	SR 1990 Sojuorn Rd	SR 1903 Flint Ridge Ch	0.51	Seal - Double	$25,300
2026	10	090-Union	Preservation	SR 2204 Eudy Rd	US 601 S	eom	0.16	Crack Seal and Double Seal	$7,500
2026	10	090-Union	Preservation	SR 2246 Burgess Helms RD	SR 2126 Pig Mattox Rd	eom	0.25	Seal - Double	$11,000
2026	10	090-Union	Preservation	SR 2253 Hargette Rd	SR 1940 Belk Mill Rd	US 601	0.50	Seal - Double	$22,000
2026	10	090-Union	Preservation	SR 2553 Homestead Pl	SR 1346 Beauth Church Rd	eom	0.72	Seal - Double and Fog Seal	$52,000
2026	10	090-Union	Preservation	SR 2576 Carmona Ct	SR 1357 Potter Rd	EOM	0.16	Seal - Double and Fog Seal	$11,000
2026	10	090-Union	Preservation	SR 2955 Cornerstone Dr	SR 2954 Rising Sun Ln	eom	0.06	Seal - Double and Fog Seal	$7,000
2026	11	003-Alleghany	Resurfacing	NC 18	SR 1145	NC 113	2.71	Full Depth Patching and 1.5" S9.5C	$869,440
2026	11	003-Alleghany	Resurfacing	SR 1441	NC 18	VA LINE	0.40	Leveling and 1.5" S9.5B	$126,720
2026	11	003-Alleghany	Resurfacing	SR 1448	SR 1453	SR 1442	0.83	Leveling and 1.5" S9.5B	$292,160
2026	11	003-Alleghany	Resurfacing	SR 1453	NC 18	SR 1448	1.44	Leveling and 1.5" S9.5B	$506,880
2026	11	003-Alleghany	Preservation	SR 1118	SR 1120	SR 1114	0.99	Seal - Triple and Fog Seal	$83,890
2026	11	003-Alleghany	Preservation	SR 1300	NC 113	SR 1301/END PVMT	1.41	Seal - Triple and Fog Seal	$119,100
2026	11	003-Alleghany	Preservation	SR 1301	SR 1300	US 221	0.96	Seal - Triple and Fog Seal	$81,100
2026	11	003-Alleghany	Preservation	SR 1303	SR 1300	SR 1308	2.67	Seal - Triple and Fog Seal	$225,300
2026	11	003-Alleghany	Preservation	SR 1317	NC 93	SR 1318	2.04	Seal - Triple and Fog Seal	$153,190
2026	11	003-Alleghany	Preservation	SR 1482	SR 1422	SR 1459	1.79	Seal - Triple and Fog Seal	$94,515
2026	11	005-Ashe	Resurfacing	SR 1114	SR 1112	NC 194	0.70	1.5" S9.5B	$221,760
2026	11	005-Ashe	Resurfacing	SR 1128	NC 88	NC 88	1.00	1.5" S9.5B	$316,800
2026	11	005-Ashe	Resurfacing	SR 1130	SR 1185	END PVMT	0.49	1.5" S9.5B	$137,984
2026	11	005-Ashe	Resurfacing	SR 1169	Bridge # 334	SR 1176	1.32	1.5" S9.5B	$411,840
2026	11	005-Ashe	Resurfacing	SR 1185	SR 1130	END PVMT	0.20	1.5" S9.5B	$63,360

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	11	005-Ashe	Resurfacing	SR 1198	SR 1185	END PVMT	0.26	1.5" S9.5B	$73,216
2026	11	005-Ashe	Resurfacing	SR 1208	NC 194	EOM	0.75	1.5" S9.5B	$237,600
2026	11	005-Ashe	Resurfacing	SR 1209	SR 1208	END Maintenance	0.22	1.5" S9.5B	$60,544
2026	11	005-Ashe	Resurfacing	SR 1291	NC 88	SR 1130	0.06	1.5" S9.5B	$16,896
2026	11	005-Ashe	Resurfacing	SR 1292	SR 1130	EOM	0.09	1.5" S9.5B	$25,344
2026	11	005-Ashe	Resurfacing	SR 1340	NC 88	MP 2.15	2.15	1.5" S9.5B	$681,120
2026	11	005-Ashe	Resurfacing	SR 1342	SR 1394	NC 88	0.85	1.5" S9.5B	$269,280
2026	11	005-Ashe	Resurfacing	SR 1511	SR 1573	SR 1573	1.15	1.5" S9.5B	$364,320
2026	11	005-Ashe	Preservation	SR 1133	SR 1138	SR 1125	0.55	Seal - Triple and Fog Seal	$46,464
2026	11	005-Ashe	Preservation	SR 1180	SR 1181	MP 1.05	1.05	Seal - Triple and Fog Seal	$98,560
2026	11	005-Ashe	Preservation	SR 1205	SR 1126	EOM	0.46	Seal - Triple and Fog Seal	$34,543
2026	11	005-Ashe	Preservation	SR 1239	NC 163	SR 1155	0.29	Seal - Triple and Fog Seal	$20,416
2026	11	005-Ashe	Preservation	SR 1240	NC 194	END Maintenance	0.50	Seal - Triple and Fog Seal	$37,472
2026	11	005-Ashe	Preservation	SR 1259	SR 1239	END Maintenance	0.12	Seal - Triple and Fog Seal	$9,011
2026	11	005-Ashe	Preservation	SR 1335	SR 1334	EOM	0.40	Seal - Triple and Fog Seal	$33,792
2026	11	005-Ashe	Preservation	SR 1346	SR 1342	END Maintenance	0.28	Seal - Triple and Fog Seal	$21,026
2026	11	005-Ashe	Preservation	SR 1356	SR 1354	SR 1324	3.42	Seal - Triple and Fog Seal	$275,572
2026	11	005-Ashe	Preservation	SR 1518	NC 194	EOM	0.67	Seal - Triple and Fog Seal	$50,313
2026	11	005-Ashe	Preservation	SR 1521	END PVMT	SR 1523	1.28	Seal - Triple and Fog Seal	$108,134
2026	11	005-Ashe	Preservation	SR 1577	SR 1573	EOM	0.63	Seal - Triple and Fog Seal	$47,309
2026	11	005-Ashe	Preservation	SR 1624	BR PkWay	Wilkes Co Line/SR 1566	0.07	Seal - Triple and Fog Seal	$5,914
2026	11	005-Ashe	Preservation	SR 1638	SR 1653	CUL-DE-SAC	0.66	Seal - Triple and Fog Seal	$55,757
2026	11	006-Avery	Resurfacing	SR 1113	US 221	EOM	0.60	1.5" S9.5B	$168,960
2026	11	006-Avery	Resurfacing	SR 1134	SR 1132	EOM	0.82	1.5" S9.5B	$230,630
2026	11	006-Avery	Resurfacing	SR 1148	US 221	SR 1143	0.33	1.5" S9.5B	$92,930
2026	11	006-Avery	Resurfacing	SR 1197	SR 1174	EOM	0.32	1.5" S9.5B	$90,110
2026	11	006-Avery	Resurfacing	SR 1206	SR 1143	EOM	0.39	1.5" S9.5B	$123,550
2026	11	006-Avery	Resurfacing	SR 1310	NC 194	END PAVEMENT	1.06	1.5" S9.5B	$334,540
2026	11	006-Avery	Resurfacing	SR 1317	SR 1316	TN LINE	0.49	1.5" S9.5B	$154,280
2026	11	006-Avery	Resurfacing	SR 1335	NC 194	EOP	0.74	1.5" S9.5B	$234,430
2026	11	006-Avery	Resurfacing	SR 1337	SR 1355	EOM	0.39	1.5" S9.5B	$109,820
2026	11	006-Avery	Resurfacing	SR 1337	NC 184	SR 1355	1.72	1.5" S9.5B	$544,900
2026	11	006-Avery	Resurfacing	SR 1340	NC 184	EOM	0.25	1.5" S9.5B	$77,610
2026	11	006-Avery	Resurfacing	SR 1362	NC 184	EOM	0.20	1.5" S9.5B	$56,320
2026	11	006-Avery	Resurfacing	SR 1363	NC 184	EOM	0.20	1.5" S9.5B	$56,320
2026	11	006-Avery	Resurfacing	SR 1507	US 221	MP 0.10	0.10	1.5" S9.5B	$38,720
2026	11	006-Avery	Resurfacing	SR 1547	NC 181	EOM	0.44	1.5" S9.5B	$123,910
2026	11	006-Avery	Resurfacing	SR 1549	SR 1548	END MAINTENANCE	0.39	1.5" S9.5B	$121,970
2026	11	006-Avery	Preservation	SR 1126	US 19E	Mitchell Co Line	2.95	Seal - Triple and Fog Seal	$203,428
2026	11	014-Caldwell	Resurfacing	Rmp 6484	SR 1001	US 321 SB	0.22	Mill 1.5" and 1.5" S9.5C	$113,340
2026	11	014-Caldwell	Resurfacing	Rmp 6485	US 321 SB	SR 1001	0.15	Mill 1.5" and 1.5" S9.5C	$73,920
2026	11	014-Caldwell	Resurfacing	SR 1379	US 321	EOM	0.35	1.5" S9.5B	$110,880
2026	11	014-Caldwell	Resurfacing	SR 1511	SR 1551	SR 1605	4.11	1.5" S9.5B	$1,302,048
2026	11	014-Caldwell	Resurfacing	SR 1517	SR 1560	EOM	0.25	1.5" S9.5B	$79,200
2026	11	014-Caldwell	Resurfacing	SR 1560	NC 268	US 321	1.29	1.5" S9.5B	$454,080
2026	11	014-Caldwell	Resurfacing	SR 1592	NC 268	SR 1592	0.93	1.5" S9.5B	$278,256
2026	11	014-Caldwell	Resurfacing	SR 1601	SR 1517	EOM	0.17	1.5" S9.5B	$50,864
2026	11	014-Caldwell	Resurfacing	SR 1767	SR 1160	EOM	0.81	1.5" S9.5B	$256,608
2026	11	014-Caldwell	Resurfacing	US 321 SB	Gore at SR 1001 SB On Ramp	SR 1160	2.98	Mill 1.5" and 1.5" S9.5C	$1,330,825
2026	11	014-Caldwell	Resurfacing	US 321 SB Off Ramp	US 321 SB	SR 1933 SB	0.22	Mill 1.5" and 1.5" S9.5C	$73,570
2026	11	014-Caldwell	Resurfacing	US 321 SB On Ramp	Gore	US 321 SB	0.14	Mill 1.5" and 1.5" S9.5C	$49,280
2026	11	014-Caldwell	Resurfacing	US 64	US 321	NC 90	1.33	Mill 1.5" and 1.5" S9.5C	$1,174,005
2026	11	014-Caldwell	Preservation	SR 1322	SR 1326	SR 1324	1.16	Seal - Triple and Fog Seal	$108,885
2026	11	014-Caldwell	Preservation	SR 1349	SR 1350	SR 1347	1.98	Seal - Triple and Fog Seal	$185,856
2026	11	014-Caldwell	Preservation	SR 1351	SR 1353	EOM	0.29	Seal - Triple and Fog Seal	$24,499
2026	11	014-Caldwell	Preservation	SR 1362	BEGIN PVMT	SR 1367	1.34	Seal - Triple and Fog Seal	$125,781
2026	11	014-Caldwell	Preservation	SR 1369	SR 1368	EOM	2.71	Seal - Triple and Fog Seal	$208,927
2026	11	014-Caldwell	Preservation	SR 1401	SR 1316	EOM	0.39	Seal - Triple and Fog Seal	$32,947
2026	11	014-Caldwell	Preservation	SR 1415	US 321	EOM	0.43	Seal - Triple and Fog Seal	$32,290

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	11	014-Caldwell	Preservation	SR 1502	SR 1503	EOM	0.56	Seal - Triple and Fog Seal	$47,309
2026	11	014-Caldwell	Preservation	SR 1940	SR 1142	CUL-DE-SAC	0.44	Seal - Triple and Fog Seal	$41,301
2026	11	014-Caldwell	Preservation	SR 1941	SR 1940	CUL-DE-SAC	0.10	Seal - Triple and Fog Seal	$8,448
2026	11	014-Caldwell	Preservation	SR 1942	SR 1940	CUL-DE-SAC	0.12	Seal - Triple and Fog Seal	$10,138
2026	11	014-Caldwell	Preservation	SR 1943	SR 1940	CUL-DE-SAC	0.12	Seal - Triple and Fog Seal	$10,138
2026	11	014-Caldwell	Preservation	SR 1944	SR 1940	CUL-DE-SAC	0.12	Seal - Triple and Fog Seal	$10,138
2026	11	014-Caldwell	Preservation	SR 1946	US 321 ALT	EOM	0.28	Seal - Triple and Fog Seal	$21,026
2026	11	014-Caldwell	Preservation	SR 1953	US 64	EOM	0.25	Seal - Triple and Fog Seal	$21,120
2026	11	014-Caldwell	Preservation	SR 1954	SR 1134	CUL-DE-SAC	0.10	Seal - Triple and Fog Seal	$8,448
2026	11	014-Caldwell	Preservation	SR 1955	SR 1136	EOM	0.29	Seal - Triple and Fog Seal	$24,499
2026	11	014-Caldwell	Preservation	SR 1965	BEG MAINT	SR 1108	0.09	Seal - Triple and Fog Seal	$8,448
2026	11	086-Surry	Resurfacing	SR 1341	BRIDGE # 52 over Fisher River	SR 1345	0.58	1.5" S9.5B	$182,160
2026	11	086-Surry	Resurfacing	SR 1359	SR 2258	US 601	0.75	1.5" S9.5B	$264,000
2026	11	086-Surry	Resurfacing	SR 1372	SR 1371	SR 1375	0.26	1.5" S9.5B	$82,368
2026	11	086-Surry	Resurfacing	SR 1373	SR 1372	SR 1324	0.13	1.5" S9.5B	$36,608
2026	11	086-Surry	Resurfacing	SR 1374	SR 1371	SR 1375	0.31	1.5" S9.5B	$98,208
2026	11	086-Surry	Resurfacing	SR 1375	SR 1376	SR 1372	0.40	1.5" S9.5B	$112,640
2026	11	086-Surry	Resurfacing	SR 1375	SR 1372	SR 1376	0.45	1.5" S9.5B	$142,560
2026	11	086-Surry	Resurfacing	SR 1376	SR 1761	US 52	0.28	1.5" S9.5B	$78,848
2026	11	086-Surry	Resurfacing	SR 1396	SR 1602	Br # 210 over I-77	1.79	1.5" S9.5B	$693,088
2026	11	086-Surry	Resurfacing	SR 1397	NC 89	SR 1605	1.05	1.5" S9.5B	$332,640
2026	11	086-Surry	Resurfacing	SR 1602	SR 1618	SR 1397	1.45	1.5" S9.5B	$510,400
2026	11	086-Surry	Resurfacing	SR 1605	SR 1606	SR 1397	1.18	1.5" S9.5B	$373,824
2026	11	086-Surry	Resurfacing	SR 1618	SR 1622	SR 1602	2.05	1.5" S9.5B	$721,600
2026	11	086-Surry	Resurfacing	SR 1642	US 52	SR 1640	0.11	1.5" S9.5B	$34,848
2026	11	086-Surry	Resurfacing	SR 1702	SR 1701	VA State Line	1.31	1.5" S9.5B	$461,120
2026	11	086-Surry	Resurfacing	SR 1798	SR 1789	SR 1803	1.86	1.5" S9.5B	$654,720
2026	11	086-Surry	Resurfacing	SR 2019	SR 2022	SR 2012	1.83	1.5" S9.5B	$644,160
2026	11	086-Surry	Rehabilitation	I 77	MM 95.0	MM 99.0	4.00	Mill 1.5" and 1.5" S9.5C	$1,150,000
2026	11	086-Surry	Preservation	SR 1326	WILKES CO LINE/SR 1906	SR 1315	1.86	Seal - Triple and Fog Seal	$174,592
2026	11	086-Surry	Preservation	SR 1330	SR 1331	BRIDGE	0.78	Seal - Triple and Fog Seal	$58,573
2026	11	086-Surry	Preservation	SR 1334	SR 1335	SR 1338	2.42	Seal - Triple and Fog Seal	$181,705
2026	11	086-Surry	Preservation	SR 1335	SR 1331	SR 1336	1.02	Seal - Triple and Fog Seal	$95,744
2026	11	086-Surry	Preservation	SR 1342	SR 1001	SR 1341	2.56	Seal - Triple and Fog Seal	$216,269
2026	11	086-Surry	Preservation	SR 1343	SR 1001	SR 1342	1.26	Seal - Triple and Fog Seal	$106,445
2026	11	086-Surry	Preservation	SR 1353	SR 1350	SR 1356	2.41	Seal - Triple and Fog Seal	$203,597
2026	11	086-Surry	Preservation	SR 1500	SR 1344	EOM	0.32	Seal - Triple and Fog Seal	$30,131
2026	11	086-Surry	Preservation	SR 1504	SR 1395	EOM	0.37	Seal - Triple and Fog Seal	$34,731
2026	11	086-Surry	Preservation	SR 1507	SR 1344	DEAD END	0.37	Seal - Triple and Fog Seal	$34,731
2026	11	086-Surry	Preservation	SR 1520	SR 1404	END MAINT	0.46	Seal - Triple and Fog Seal	$43,180
2026	11	086-Surry	Preservation	SR 1529	SR 1181	SR 1133	0.14	Seal - Triple and Fog Seal	$11,830
2026	11	086-Surry	Preservation	SR 1633	SR 1389	NC 89	0.04	Seal - Triple and Fog Seal	$3,379
2026	11	086-Surry	Preservation	SR 1682	SR 1637	GORDON ST	0.34	Seal - Triple and Fog Seal	$28,720
2026	11	086-Surry	Preservation	SR 1792	SR 1791	NC 103	1.12	Seal - Triple and Fog Seal	$105,131
2026	11	086-Surry	Preservation	SR 1893	SR 1700	END MAINT	0.20	Seal - Triple and Fog Seal	$15,019
2026	11	086-Surry	Preservation	SR 2070	SR 2069	SR 2072	1.92	Seal - Triple and Fog Seal	$180,224
2026	11	086-Surry	Preservation	SR 2154	SR 1483	EOM	0.18	Seal - Triple and Fog Seal	$16,890
2026	11	086-Surry	Preservation	SR 2202	SR 1003	EOM	0.25	Seal - Triple and Fog Seal	$18,770
2026	11	095-Watauga	Resurfacing	SR 1603	SR 1602	EOM	0.70	1.5" S9.5B	$209,440
2026	11	095-Watauga	Resurfacing	US 221	US 321	US 421	0.81	Mill 1.5" and 1.5" S9.5B	$855,360
2026	11	095-Watauga	Resurfacing	US 221	SR 1417	SR 1674	2.01	1.5" S9.5C	$990,528
2026	11	095-Watauga	Resurfacing	US 221	SR 1416	SR 1417	2.38	1.5" S9.5C	$1,424,192
2026	11	095-Watauga	Preservation	SR 1138	SR 1136	EOP	0.57	Seal - Triple and Fog Seal	$42,803
2026	11	095-Watauga	Preservation	SR 1158	SR 1134	EOM	0.45	Seal - Triple and Fog Seal	$33,792
2026	11	095-Watauga	Preservation	SR 1351	SR 1350	SR 1334	1.34	Seal - Triple and Fog Seal	$113,203
2026	11	095-Watauga	Preservation	SR 1355	SR 1671	SR 1392	1.44	Seal - Triple and Fog Seal	$121,651
2026	11	095-Watauga	Preservation	SR 1361	US421	PVMT CHG	0.14	Seal - Triple and Fog Seal	$13,141
2026	11	095-Watauga	Preservation	SR 1403	SR 1349	SR 1377	0.59	Seal - Triple and Fog Seal	$49,674
2026	11	095-Watauga	Preservation	SR 1408	US 321	US321	0.24	Seal - Triple and Fog Seal	$20,275

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	11	095-Watauga	Preservation	SR 1515	SR 169	End of Pavement	0.58	Seal - Triple and Fog Seal	$54,443
2026	11	095-Watauga	Preservation	SR 1515	Begin Pavement	US 221	0.27	Seal - Triple and Fog Seal	$25,344
2026	11	095-Watauga	Preservation	SR 1550	SR 1552	SR 1551	1.64	Seal - Triple and Fog Seal	$138,547
2026	11	095-Watauga	Preservation	SR 1551	SR 1550	SR 1552	0.46	Seal - Triple and Fog Seal	$43,179
2026	11	095-Watauga	Preservation	SR 1564	US221	US221	0.25	Seal - Triple and Fog Seal	$18,773
2026	11	097-Wilkes	Resurfacing	NC 268	SR 1989	SR 2144	2.62	1.5" S9.5B	$1,014,460
2026	11	097-Wilkes	Resurfacing	RMP 2546	NC 16/NC 18	US 421 SB	0.33	Mill 1.5" and 1.5" S9.5C	$127,770
2026	11	097-Wilkes	Resurfacing	RMP 2548	NC 16/NC 18	US 421 NB	0.26	Mill 1.5" and 1.5" S9.5C	$100,670
2026	11	097-Wilkes	Resurfacing	RMP 2551	US 421 NB	NC 16/NC 18	0.16	Mill 1.5" and 1.5" S9.5C	$61,952
2026	11	097-Wilkes	Resurfacing	RMP 2552	US 421 SB	NC 16/NC 18	0.27	Mill 1.5" and 1.5" S9.5C	$104,540
2026	11	097-Wilkes	Resurfacing	RMP 2554	SR 1001	US 421 SB	0.23	Mill 1.5" and 1.5" S9.5C	$89,050
2026	11	097-Wilkes	Resurfacing	RMP 2556	From US 421 NB	SR 1001 Roundabout	0.19	Mill 1.5" and 1.5" S9.5C	$73,565
2026	11	097-Wilkes	Resurfacing	RMP 2558	SR 1001 Roundabout	US 421 NB	0.20	Mill 1.5" and 1.5" S9.5C	$77,440
2026	11	097-Wilkes	Resurfacing	RMP 2561	US 421 SB	SR 1001	0.26	Mill 1.5" and 1.5" S9.5C	$100,670
2026	11	097-Wilkes	Resurfacing	SR 1325	SR 1320	SR 1322	1.03	1.5" S9.5B	$326,304
2026	11	097-Wilkes	Resurfacing	SR 1934	SR 1999	SR 2014	3.38	Leveling and 1.5" S9.5B	$1,070,780
2026	11	097-Wilkes	Resurfacing	SR 1999	SR 2004	SR 1934	3.43	Leveling and 1.5" S9.5B	$1,086,620
2026	11	097-Wilkes	Resurfacing	US 421 NB	Begin Widening at SR 1001 NB Off Ramp	ırfacing joint, west of NC 16/NC 18	1.56	Mill 1.5" and 1.5" S9.5C	$823,680
2026	11	097-Wilkes	Resurfacing	US 421 SB	·vious resurfacing joint, end of NC 268 SB On Ra	End SR 1001, SB On Ramp	1.60	Mill 1.5" and 1.5" S9.5C	$844,800
2026	11	097-Wilkes	Preservation	SR 1158	SR 1155	SR 1135	1.18	Seal - Triple and Fog Seal	$88,610
2026	11	097-Wilkes	Preservation	SR 1174	SR 1194	END SECT	0.24	Seal - Triple and Fog Seal	$20,275
2026	11	097-Wilkes	Preservation	SR 1182	US 421	END Maintenance	0.69	Seal - Triple and Fog Seal	$64,768
2026	11	097-Wilkes	Preservation	SR 1183	SR 1182	End Maintenance	0.12	Seal - Triple and Fog Seal	$11,264
2026	11	097-Wilkes	Preservation	SR 1188	BOM	SR 2483	0.10	Seal - Triple and Fog Seal	$8,448
2026	11	097-Wilkes	Preservation	SR 1203	SR 1182	CuldeSac	0.30	Seal - Triple and Fog Seal	$25,344
2026	11	097-Wilkes	Preservation	SR 1204	SR 1203	Cul-De-Sac	0.23	Seal - Triple and Fog Seal	$21,589
2026	11	097-Wilkes	Preservation	SR 1205	SR 1203	End Maintenance	0.10	Seal - Triple and Fog Seal	$9,387
2026	11	097-Wilkes	Preservation	SR 1206	SR 1183	Cul-De-Sac	0.29	Seal - Triple and Fog Seal	$27,221
2026	11	097-Wilkes	Preservation	SR 1209	NC 268	EOM	0.34	Seal - Triple and Fog Seal	$31,915
2026	11	097-Wilkes	Preservation	SR 1221	SR 1145	EOM	0.24	Seal - Triple and Fog Seal	$20,275
2026	11	097-Wilkes	Preservation	SR 1232	SR 1209	EOM	0.09	Seal - Triple and Fog Seal	$8,448
2026	11	097-Wilkes	Preservation	SR 1236	SR 1145	SR 1145	0.25	Seal - Triple and Fog Seal	$18,773
2026	11	097-Wilkes	Preservation	SR 1240	SR 1221	EOM	0.50	Seal - Triple and Fog Seal	$42,240
2026	11	097-Wilkes	Preservation	SR 1255	SR 1209	EOM	0.20	Seal - Triple and Fog Seal	$16,896
2026	11	097-Wilkes	Preservation	SR 1260	SR 1103	SR 1174	0.15	Seal - Triple and Fog Seal	$12,672
2026	11	097-Wilkes	Preservation	SR 1265	SR 1235	Cul-De-Sac	0.21	Seal - Triple and Fog Seal	$17,741
2026	11	097-Wilkes	Preservation	SR 1266	SR 1197	Cul-De-Sac	0.16	Seal - Triple and Fog Seal	$13,094
2026	11	097-Wilkes	Preservation	SR 1317	SR 1315	SR 1346	1.74	Seal - Triple and Fog Seal	$146,995
2026	11	097-Wilkes	Preservation	SR 1318	SR 1319	EOM	0.39	Seal - Triple and Fog Seal	$29,286
2026	11	097-Wilkes	Preservation	SR 1324	SR 1322	DE	0.20	Seal - Triple and Fog Seal	$16,896
2026	11	097-Wilkes	Preservation	SR 1340	SR 1317	SR 1342	0.91	Seal - Triple and Fog Seal	$76,877
2026	11	097-Wilkes	Preservation	SR 1345	SR 1344	EOM	1.08	Seal - Triple and Fog Seal	$91,238
2026	11	097-Wilkes	Preservation	SR 1367	SR 1317	DE	0.30	Seal - Triple and Fog Seal	$22,528
2026	11	097-Wilkes	Preservation	SR 1377	US 421	US 421	0.40	Seal - Triple and Fog Seal	$37,547
2026	11	097-Wilkes	Preservation	SR 1379	NC 16	SR 1380	0.36	Seal - Triple and Fog Seal	$33,792
2026	11	097-Wilkes	Preservation	SR 1380	SR 1379	Cul-De-Sac	0.45	Seal - Triple and Fog Seal	$42,240
2026	11	097-Wilkes	Preservation	SR 1381	SR 1379	SR 1313	0.33	Seal - Triple and Fog Seal	$30,976
2026	11	097-Wilkes	Preservation	SR 1382	SR 1381	SR 1383	0.12	Seal - Triple and Fog Seal	$11,264
2026	11	097-Wilkes	Preservation	SR 1383	SR 1382	SR 1313	0.32	Seal - Triple and Fog Seal	$30,037
2026	11	097-Wilkes	Preservation	SR 1384	SR 1381	SR 1383	0.14	Seal - Triple and Fog Seal	$13,141
2026	11	097-Wilkes	Preservation	SR 1390	SR 1379	Cul-De-Sac	0.19	Seal - Triple and Fog Seal	$17,835
2026	11	097-Wilkes	Preservation	SR 1395	SR 1381	SR 1383	0.11	Seal - Triple and Fog Seal	$10,325
2026	11	097-Wilkes	Preservation	SR 1397	SR 1396	Cul-De-Sac	0.07	Seal - Triple and Fog Seal	$6,571
2026	11	097-Wilkes	Preservation	SR 1398	SR 1390	Cul-De-Sac	0.10	Seal - Triple and Fog Seal	$9,387
2026	11	097-Wilkes	Preservation	SR 1414	SR 1380	Cul-De-Sac	0.12	Seal - Triple and Fog Seal	$11,264
2026	11	097-Wilkes	Preservation	SR 1415	SR 1379	Cul-De-Sac	0.07	Seal - Triple and Fog Seal	$6,571
2026	11	097-Wilkes	Preservation	SR 1427	SR 1372	EOP	0.11	Seal - Triple and Fog Seal	$9,293
2026	11	097-Wilkes	Preservation	SR 1429	SR 1380	Cul-De-Sac	0.08	Seal - Triple and Fog Seal	$6,758
2026	11	097-Wilkes	Preservation	SR 1433	US 421	EOM	0.27	Seal - Triple and Fog Seal	$22,810

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	11	097-Wilkes	Preservation	SR 1434	SR 1221	EOM	0.11	Seal - Triple and Fog Seal	$9,293
2026	11	097-Wilkes	Preservation	SR 1435	US 421	SR 1441	0.19	Seal - Triple and Fog Seal	$17,835
2026	11	097-Wilkes	Preservation	SR 1442	SR 1435	EOM	0.16	Seal - Triple and Fog Seal	$13,517
2026	11	097-Wilkes	Preservation	SR 1515	SR 1517	DE	0.40	Seal - Triple and Fog Seal	$33,792
2026	11	097-Wilkes	Preservation	SR 1520	SR 1517	DE	0.41	Seal - Triple and Fog Seal	$34,637
2026	11	097-Wilkes	Preservation	SR 1534	NC 18	EOP	1.00	Seal - Triple and Fog Seal	$84,227
2026	11	097-Wilkes	Preservation	SR 1566	ASHE CO LINE	SR 1597	0.16	Seal - Triple and Fog Seal	$13,517
2026	11	097-Wilkes	Preservation	SR 1622	NC 18	DE	0.14	Seal - Triple and Fog Seal	$10,513
2026	11	097-Wilkes	Preservation	SR 1706	SR 1002	SR 1707	2.20	Seal - Triple and Fog Seal	$185,856
2026	11	097-Wilkes	Preservation	SR 1719	NC 18	DE	0.21	Seal - Triple and Fog Seal	$17,741
2026	11	097-Wilkes	Preservation	SR 1756	NC 18	DE	0.11	Seal - Triple and Fog Seal	$8,260
2026	11	097-Wilkes	Preservation	SR 1794	SR 1712	SR 1794	0.09	Seal - Triple and Fog Seal	$7,857
2026	11	097-Wilkes	Preservation	SR 1906	SR 1902	SURRY	0.08	Seal - Triple and Fog Seal	$7,509
2026	11	097-Wilkes	Preservation	SR 1970	SR 1966	DE	0.40	Seal - Triple and Fog Seal	$30,037
2026	11	099-Yadkin	Resurfacing	Rmp 2593	US 21	US 421 SB	0.22	Mill 1.5" and 1.5" S9.5C	$92,900
2026	11	099-Yadkin	Resurfacing	Rmp 2594	US 421 NB	US 21	0.29	Mill 1.5" and 1.5" S9.5C	$122,500
2026	11	099-Yadkin	Resurfacing	Rmp 2599	SR 1141	US 421 NB	0.40	Mill 1.5" and 1.5" S9.5C	$154,880
2026	11	099-Yadkin	Resurfacing	Rmp 2600	US 421 SB	SR 1141	0.29	Mill 1.5" and 1.5" S9.5C	$122,500
2026	11	099-Yadkin	Resurfacing	US 421 NB	MP 11.41/Begin On Ramp Gore	US 21	3.71	Mill 1.5" and 1.5" S9.5C	$1,480,775
2026	11	099-Yadkin	Resurfacing	US 421 SB	US 21	MP 9.92/End Off Ramp Gore	3.70	Mill 1.5" and 1.5" S9.5C	$1,475,845
2026	11	099-Yadkin	Preservation	SR 1159	DAVIE CO LINE	SR 1002	1.43	Seal - Triple and Fog Seal	$120,806
2026	11	099-Yadkin	Preservation	SR 1186	SR 1159	END MAINT	0.38	Seal - Triple and Fog Seal	$30,319
2026	11	099-Yadkin	Preservation	SR 1203	SR 1444	Culdesac	0.06	Seal - Triple and Fog Seal	$5,632
2026	11	099-Yadkin	Preservation	SR 1204	SR 1444	EOM	0.09	Seal - Triple and Fog Seal	$8,448
2026	11	099-Yadkin	Preservation	SR 1205	SR 1150	SR 1126	0.13	Seal - Triple and Fog Seal	$12,203
2026	11	099-Yadkin	Preservation	SR 1205	SR 1150	SR 1150	0.31	Seal - Triple and Fog Seal	$29,099
2026	11	099-Yadkin	Preservation	SR 1319	SR 1320	SR 1300	1.17	Seal - Triple and Fog Seal	$109,824
2026	11	099-Yadkin	Preservation	SR 1440	SR 1150	EOM	0.22	Seal - Triple and Fog Seal	$18,586
2026	11	099-Yadkin	Preservation	SR 1441	SR 1150	SR 1314	0.47	Seal - Triple and Fog Seal	$39,706
2026	11	099-Yadkin	Preservation	SR 1444	Cul-De-Sac	SR 1150	0.73	Seal - Triple and Fog Seal	$61,670
2026	11	099-Yadkin	Preservation	SR 1532	SR 1529	SR 1533	1.23	Seal - Triple and Fog Seal	$115,456
2026	11	099-Yadkin	Preservation	SR 1612	SR 1549	END Maintenance	1.10	Seal - Triple and Fog Seal	$102,315
2026	11	099-Yadkin	Preservation	SR 1632	SR 1549	EOM	0.20	Seal - Triple and Fog Seal	$18,773
2026	11	099-Yadkin	Preservation	SR 1658	SR 1612	CUL-DE-SAC	0.40	Seal - Triple and Fog Seal	$37,547
2026	11	099-Yadkin	Preservation	SR 1659	SR 1658	EOM	0.08	Seal - Triple and Fog Seal	$7,415
2026	11	099-Yadkin	Preservation	SR 1665	SR 1658	EOM	0.08	Seal - Triple and Fog Seal	$7,509
2026	12	002-Alexander	Resurfacing	NC 127	SR 1163	US 64	4.38	1.5" S9.5C	$704,000
2026	12	002-Alexander	Resurfacing	NC 16	NC 90	SR 1400	5.85	Mill 1.5" and 1.5" S9.5C	$1,597,000
2026	12	002-Alexander	Resurfacing	SR 1104	NC 90	SR 1819	0.77	1.0" S9.5B	$115,800
2026	12	002-Alexander	Resurfacing	SR 1108	US 64	SR 1111	0.71	1.0" S9.5B	$106,200
2026	12	002-Alexander	Resurfacing	SR 1111	SR 1110	NC 16	1.37	1.5" S9.5B	$172,155
2026	12	002-Alexander	Resurfacing	SR 1137	SR 1124	SR 1135	1.79	1.5" S9.5B	$358,000
2026	12	002-Alexander	Resurfacing	Sr 1157	SR 1156	Caldwell CL	1.36	1.5" S9.5B	$189,890
2026	12	002-Alexander	Resurfacing	SR 1183	NC 16	DEAD END	0.59	1.0" S9.5B	$59,400
2026	12	002-Alexander	Resurfacing	SR 1325	NC 16	End Maint.	0.26	1.0" S9.5A	$25,600
2026	12	002-Alexander	Resurfacing	SR 1336	NC 16	Wilkes County Line	1.18	1.5" S9.5B	$165,073
2026	12	002-Alexander	Resurfacing	SR 1409	SR 1407	NC 90	2.74	1.5" S9.5B	$547,200
2026	12	002-Alexander	Resurfacing	SR 1426	SR 1425	SR 1425	1.42	1.5" S9.5B	$219,480
2026	12	002-Alexander	Resurfacing	SR 1484	Iredell County Line	Iredell County Line	0.03	1.0" S9.5B	$5,100
2026	12	002-Alexander	Resurfacing	SR 1515	SR 1454	SR 1456	1.12	1.5" S9.5B	$156,150
2026	12	002-Alexander	Resurfacing	SR 1565	SR 1479	SR 1566	0.16	1.0" S9.5A	$15,500
2026	12	002-Alexander	Resurfacing	SR 1566	SR 1479	Dead End	0.09	1.0" S9.5A	$8,700
2026	12	002-Alexander	Resurfacing	SR 1570	SR 1480	DEAD END	0.18	1.0" S9.5B	$17,500
2026	12	002-Alexander	Resurfacing	SR 1626	SR 1605	SR 1005	3.13	1.0" S9.5B	$313,000
2026	12	002-Alexander	Resurfacing	SR 1644	SR 1005	DEAD END	0.26	1.0" S9.5B	$25,900
2026	12	002-Alexander	Resurfacing	SR 1664	SR 1605	SR 1627	0.81	1.0" S9.5B	$81,400
2026	12	002-Alexander	Resurfacing	SR 1685	SR 1005	DEAD END	0.33	1.0" S9.5B	$33,400
2026	12	002-Alexander	Resurfacing	SR 1833	NC 16	DEAD END	0.56	1.0" S9.5B	$55,600
2026	12	002-Alexander	Resurfacing	SR 1909	SR 1610	Cul-de-sac	0.28	1.0" S9.5A	$28,300

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	12	002-Alexander	Preservation	SR 1301	SR 1348	SR 1302	1.34	Seal - Double and Fog Seal	$46,725
2026	12	002-Alexander	Preservation	SR 1311	Mama Dessie Lane (Private)	SR 1333	0.58	Seal - Double and Fog Seal	$20,300
2026	12	002-Alexander	Preservation	SR 1315	SR 1307	Graydon Dyson Road (Private)	1.01	Seal - Double and Fog Seal	$35,350
2026	12	002-Alexander	Preservation	SR 1320	SR 1318	US 64	0.92	Seal - Double and Fog Seal	$32,340
2026	12	002-Alexander	Preservation	SR 1328	SR 1313	SR 1332	1.40	.75" S4.75A	$126,453
2026	12	002-Alexander	Preservation	SR 1328	SR 1332	SR 1331	1.03	.75" S4.75A	$92,582
2026	12	002-Alexander	Preservation	SR 1329	SR 1331	SR 1328	1.02	.75" S4.75A	$102,367
2026	12	002-Alexander	Preservation	SR 1439	SR 1403	SR 1403	0.99	Seal - Double and Fog Seal	$34,545
2026	12	002-Alexander	Preservation	Sr 1441	SR 1403	SR 1442	0.95	.75" S4.75A	$95,342
2026	12	002-Alexander	Preservation	SR 1442	SR 1001	Sam Campbell Road (Private)	1.03	.75" S4.75A	$103,370
2026	12	002-Alexander	Preservation	SR 1498	Dead End	SR 1502	0.56	.75" S4.75A	$56,201
2026	12	002-Alexander	Preservation	SR 1515	SR 1001	SR 1454	1.14	Seal - Double and Fog Seal	$39,900
2026	12	002-Alexander	Preservation	SR 1614	SR 1605	SR 1610	1.47	Seal - Double and Fog Seal	$51,310
2026	12	002-Alexander	Preservation	SR 1618	SR 1630	SR 1617	1.50	Seal - Double and Fog Seal	$52,465
2026	12	002-Alexander	Preservation	SR 1663	SR 1005	SR 1630	1.75	Seal - Double and Fog Seal	$61,250
2026	12	018-Catawba	Resurfacing	SR 1005	SR 2932	SR 1692	2.09	Mill 1.5" and 1.5" S9.5C	$447,500
2026	12	018-Catawba	Resurfacing	SR 1005	SR 1692	SR 1005	1.85	Mill 1.5" and 1.5" S9.5C	$462,500
2026	12	018-Catawba	Resurfacing	SR 1007	SR 1692	NC 16 BUS	2.28	Mill 1.5" and 1.5" S9.5C	$170,625
2026	12	018-Catawba	Resurfacing	SR 1358	US 70	Main Avenue	0.39	Full Depth Patching and 1.5" S9.5C	$97,500
2026	12	018-Catawba	Resurfacing	SR 1530	SR 1400	END MAINT	0.41	Full Depth Patching and 1.5" S9.5B	$102,000
2026	12	018-Catawba	Resurfacing	SR 1535	SR 1491	DE	0.35	1.0" S9.5B	$87,500
2026	12	018-Catawba	Resurfacing	SR 1608	SR 1400	SR 1530	0.40	Full Depth Patching and 1.25" S9.5A	$99,750
2026	12	018-Catawba	Resurfacing	SR 1621	SR 1441	END MAINT	0.36	Full Depth Patching and 1.25" S9.5A	$88,750
2026	12	018-Catawba	Resurfacing	SR 1640	SR 1529	END MAINT	0.36	Full Depth Patching and 1.25" S9.5A	$90,500
2026	12	018-Catawba	Resurfacing	SR 1641	SR 1544	DEAD END	0.21	Patching and 1.0" S9.5A	$52,250
2026	12	018-Catawba	Resurfacing	SR 1643	SR 1529	SR 1647	0.28	.75" S4.75A	$70,000
2026	12	018-Catawba	Resurfacing	SR 1647	SR 1643	END MAINT	0.21	.75" S4.75A	$52,000
2026	12	018-Catawba	Resurfacing	SR 1655	SR 1530	SR 1400	0.22	Full Depth Patching and 1.25" S9.5A	$54,500
2026	12	018-Catawba	Resurfacing	SR 1658	SR 1529	END MAINT	0.17	Full Depth Patching and 1.25" S9.5A	$42,250
2026	12	018-Catawba	Resurfacing	SR 1687	SR 1657	SR 1684	0.12	Full Depth Patching and 1.25" S9.5A	$12,650
2026	12	018-Catawba	Resurfacing	SR 1692	SR 1007	SR 1476	3.57	Mill 1.5" and 1.5" S9.5C	$892,500
2026	12	018-Catawba	Resurfacing	SR 1692	SR 1476	SR 1007	0.77	Mill 1.5" and 1.5" S9.5C	$57,750
2026	12	018-Catawba	Resurfacing	SR 1692	SR 1692	SR 1468	1.42	Mill 1.5" and 1.5" S9.5C	$355,000
2026	12	018-Catawba	Resurfacing	SR 2214	SR 1647	CUL DE SAC	0.04	.75" S4.75A	$10,500
2026	12	018-Catawba	Resurfacing	SR 2231	SR 1692	NC 127	1.97	Mill 1.5" and 1.5" S9.5C	$492,500
2026	12	018-Catawba	Resurfacing	SR 2244	SR 1490	SR 2246	0.31	Patching and 1.0" S9.5A	$76,750
2026	12	018-Catawba	Resurfacing	SR 2245	SR 2244	SR 2246	0.39	Patching and 1.0" S9.5A	$97,000
2026	12	018-Catawba	Resurfacing	SR 2246	SR 2244	DEAD END	0.25	Patching and 1.0" S9.5A	$62,500
2026	12	018-Catawba	Resurfacing	SR 2247	SR 2246	CUL DE SAC	0.09	Full Depth Patching and 1.25" S9.5A	$23,500
2026	12	018-Catawba	Resurfacing	SR 2248	SR 2245	SR 2246	0.21	Patching and 1.0" S9.5A	$52,000
2026	12	018-Catawba	Resurfacing	SR 2250	SR 1544	SR 2251	0.14	Patching and 1.0" S9.5A	$33,750
2026	12	018-Catawba	Resurfacing	SR 2251	SR 1554	DE	0.26	Patching and 1.0" S9.5A	$65,000
2026	12	018-Catawba	Resurfacing	SR 2252	SR 2250	DE	0.09	Patching and 1.0" S9.5A	$23,000
2026	12	018-Catawba	Resurfacing	SR 2272	SR 1530	CUL DE SAC	0.34	Full Depth Patching and 1.25" S9.5A	$85,250
2026	12	018-Catawba	Resurfacing	SR 2273	SR 2274	SR 2272	0.19	.75" S4.75A	$47,500
2026	12	018-Catawba	Resurfacing	SR 2274	SR 2274	END MAINT	0.56	Full Depth Patching and 1.25" S9.5A	$138,750
2026	12	018-Catawba	Resurfacing	SR 2326	SR 1608	END MAINT	0.17	Full Depth Patching and 1.25" S9.5A	$42,250
2026	12	018-Catawba	Resurfacing	SR 2349	SR 1643	END MAINT	0.21	.75" S4.75A	$53,250
2026	12	018-Catawba	Resurfacing	SR 2359	SR 1640	SR 1507	0.20	.75" S4.75A	$50,500
2026	12	018-Catawba	Resurfacing	SR 2384	SR 1400	SR 1608	0.31	Full Depth Patching and 1.25" S9.5A	$77,250
2026	12	018-Catawba	Resurfacing	SR 2393	SR 1655	END MAINT	0.30	.75" S4.75A	$74,000
2026	12	018-Catawba	Resurfacing	SR 3004	SR 1453	END MAINT	0.61	Patching and 1.0" S9.5A	$152,500
2026	12	018-Catawba	Resurfacing	SR 3018	SR 1453	SR 3018	0.48	Patching and 1.0" S9.5A	$120,000
2026	12	018-Catawba	Resurfacing	US 321 Bus	Lincoln County	NC 10	10.97	Full Depth Patching and 1.5" S9.5B	$2,742,500
2026	12	018-Catawba	Preservation	SR 1227	NC 10	CUL-DE-SAC	0.37	.75" S4.75A	$31,000
2026	12	018-Catawba	Preservation	SR 1813	SR 1003	SR 1848	2.33	Microsurface	$93,000
2026	12	018-Catawba	Preservation	SR 1818	SR 1813	SR 1815	3.25	Microsurface	$130,000
2026	12	018-Catawba	Preservation	SR 1831	SR 1004	SR 1833	2.44	Microsurface	$98,000
2026	12	018-Catawba	Preservation	SR 2028	SR 2036	SR 2026	1.73	Microsurface	$25,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	12	018-Catawba	Preservation	SR 2086	SR 1002	CUL-DE-SAC	0.30	.75" S4.75A	$25,000
2026	12	018-Catawba	Preservation	SR 2088	NC 10	SR 2089	0.08	.75" S4.75A	$7,000
2026	12	018-Catawba	Preservation	SR 2089	SR 2088	CUL-DE-SAC	0.34	.75" S4.75A	$29,000
2026	12	018-Catawba	Preservation	SR 2107	NC 10	CUL-DE-SAC	0.77	.75" S4.75A	$65,000
2026	12	018-Catawba	Preservation	SR 2528	NC 10	DEAD END	0.58	.75" S4.75A	$49,000
2026	12	018-Catawba	Preservation	SR 2589	NC 10	CUL-DE-SAC	0.32	.75" S4.75A	$27,000
2026	12	018-Catawba	Preservation	SR 2613	SR 1838	Cul-de-sac	0.65	.75" S4.75A	$72,800
2026	12	018-Catawba	Preservation	SR 2695	SR 1869	SR 2696	0.21	.75" S4.75A	$18,000
2026	12	018-Catawba	Preservation	SR 2696	SR 2695	SR 2697	0.16	.75" S4.75A	$17,000
2026	12	018-Catawba	Preservation	SR 2697	SR 2696	CUL-DE-SAC	0.16	.75" S4.75A	$17,000
2026	12	018-Catawba	Preservation	SR 2705	SR 2613	SR 2613	0.19	.75" S4.75A	$21,280
2026	12	018-Catawba	Preservation	SR 2708	SR 1867	END MAINT	0.07	.75" S4.75A	$6,000
2026	12	018-Catawba	Preservation	SR 2709	SR 2708	END MAINT	0.13	.75" S4.75A	$11,000
2026	12	018-Catawba	Preservation	SR 2776	SR 1003	SR 1810	1.42	Microsurface	$56,000
2026	12	018-Catawba	Preservation	SR 2786	SR 1869	CUL-DE-SAC	0.10	.75" S4.75A	$9,000
2026	12	018-Catawba	Preservation	SR 2921	SR 1143	DEAD END	0.20	.75" S4.75A	$17,000
2026	12	018-Catawba	Preservation	SR 2943	SR 1144	CUL-DE-SAC	0.17	.75" S4.75A	$14,000
2026	12	018-Catawba	Preservation	SR 2944	CUL-DE-SAC	CUL-DE-SAC	0.34	.75" S4.75A	$29,000
2026	12	018-Catawba	Preservation	SR 2961	SR 2944	CUL-DE-SAC	0.08	.75" S4.75A	$7,000
2026	12	018-Catawba	Preservation	SR 2978	NC 127	CUL-DE-SAC	0.13	.75" S4.75A	$11,000
2026	12	023-Cleveland	Resurfacing	NC 10	SR 1004 +.143	Lincoln Co. line	8.39	1.5" S9.5B	$1,990,725
2026	12	023-Cleveland	Resurfacing	NC 150	US 74 business	Gaston Co. line	7.75	1.5" S9.5C	$2,114,939
2026	12	023-Cleveland	Resurfacing	SR 1002	RUTHERFORD CO	NC 150	5.60	1.5" S9.5B	$640,640
2026	12	023-Cleveland	Resurfacing	SR 1190	SR 1003	SR 1189	0.39	1.5" S9.5B	$41,235
2026	12	023-Cleveland	Resurfacing	SR 1327	SR 1388	SR 1351	4.61	1.5" S9.5B and Widen	$761,574
2026	12	023-Cleveland	Resurfacing	SR 1341	SR 1313	SR 1350	4.03	1.5" S9.5B	$841,492
2026	12	023-Cleveland	Resurfacing	SR 1342	SR 1343	SR 1341	1.54	1.5" S9.5B	$226,200
2026	12	023-Cleveland	Resurfacing	SR 1346	SR 1343	SR 1341	1.34	1.5" S9.5B	$207,453
2026	12	023-Cleveland	Resurfacing	SR 1354	SR 1327	SR 1327	1.19	1.5" S9.5B	$165,591
2026	12	023-Cleveland	Resurfacing	SR 1355	SR 1354	RUTHFRD. CO	0.21	1.5" S9.5C	$31,186
2026	12	023-Cleveland	Resurfacing	SR 1370	SR 1369	Dead End	0.29	1.5" S9.5B	$39,841
2026	12	023-Cleveland	Resurfacing	SR 1650	NC 18	NC 18	1.68	1.0" S9.5B	$143,608
2026	12	023-Cleveland	Resurfacing	SR 1677	NC 18	SR 1650	0.06	1.0" S9.5B	$6,214
2026	12	023-Cleveland	Resurfacing	SR 1800	NC 18	NC 182	1.35	1.5" S9.5B	$112,913
2026	12	023-Cleveland	Resurfacing	SR 1803	S.R. 1809	NC 18	2.01	1.5" S9.5B	$256,000
2026	12	023-Cleveland	Resurfacing	SR 1806	SR 1802	SR 1005	1.12	1.5" S9.5B	$174,371
2026	12	023-Cleveland	Resurfacing	SR 2044	SR 2033	SR 1001	1.39	1.5" S9.5B	$332,648
2026	12	023-Cleveland	Resurfacing	SR 2069	NC 150	NC 150	1.20	1.5" S9.5B	$169,180
2026	12	023-Cleveland	Resurfacing	SR 2224	NC 18	SR 2218	1.07	1.5" S9.5B	$174,972
2026	12	023-Cleveland	Resurfacing	SR 2404	SR 1100	DEAD END	0.07	1.5" S9.5B	$5,967
2026	12	023-Cleveland	Resurfacing	SR 2498	SR 2036	DEAD END	0.43	1.5" S9.5B	$63,252
2026	12	023-Cleveland	Preservation	40001532	SR 1529	D.E.	0.70	Seal - Double	$36,781
2026	12	023-Cleveland	Preservation	40001542	SR 1632	SR 1573	1.00	Seal - Double	$46,831
2026	12	023-Cleveland	Preservation	Abes Mountain Rd	SR 1202	SR 1202	2.46	Seal - Double and Fog Seal	$155,065
2026	12	023-Cleveland	Preservation	Bailey Rd	SR 1002	SR 1207	0.66	Seal - Double and Fog Seal	$24,126
2026	12	023-Cleveland	Preservation	Beachwood Rd	SR 1203	DE	0.70	Seal - Double and Fog Seal	$38,910
2026	12	023-Cleveland	Preservation	Camp Creek Ch. Rd	NC 150	SR 1206	3.72	Seal - Double and Fog Seal	$147,342
2026	12	023-Cleveland	Preservation	Ellis Ferry Rd	SR 1140	DE	1.36	Seal - Double and Fog Seal	$62,325
2026	12	023-Cleveland	Preservation	Greenlee Rd	SR 1002	SR 1202	0.96	Seal - Double and Fog Seal	$47,926
2026	12	023-Cleveland	Preservation	Mosteller Rd	Rutherford Co	SR 1209	0.37	Seal - Double and Fog Seal	$13,328
2026	12	023-Cleveland	Preservation	Prospect Church Rd	SC line	SR 1002	4.52	Seal - Double and Fog Seal	$162,828
2026	12	023-Cleveland	Preservation	Red Rd	SR 1140	SR 1219	2.28	Seal - Double and Fog Seal	$82,134
2026	12	023-Cleveland	Preservation	SR 2075	SR 1001	NC 150	1.87	Seal - Double	$65,100
2026	12	023-Cleveland	Preservation	Timber Dr	SR 1200	SR 1198	0.49	Seal - Double and Fog Seal	$18,012
2026	12	023-Cleveland	Preservation	Wood Rd	S.C. Line	SR 1002	2.63	Seal - Double and Fog Seal	$95,103
2026	12	036-Gaston	Resurfacing	BUS NC 16	NC 273	LINC. CO.	1.09	1.5" S9.5C	$410,000
2026	12	036-Gaston	Resurfacing	NC 273	SR 2525	SR 2528	1.60	1.5" S9.5C	$600,000
2026	12	036-Gaston	Resurfacing	NC 273	SR 2646	SR 2532	1.30	1.5" S9.5C	$320,000
2026	12	036-Gaston	Resurfacing	NC 273	US 29/74	SR 2594	2.50	1.5" S9.5C	$650,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	12	036-Gaston	Resurfacing	NC 273	NC 279	SR 2525	2.00	1.5" S9.5B	$350,000
2026	12	036-Gaston	Resurfacing	NC 275	NC 279	Bridge	2.36	1.5" S9.5B	$245,500
2026	12	036-Gaston	Resurfacing	NC 275	LANIER ST	Stanley City Limits	2.51	1.5" S9.5C	$642,000
2026	12	036-Gaston	Resurfacing	NC 279	SR 2274+.07	NC 7	1.77	1.5" S9.5B	$426,600
2026	12	036-Gaston	Resurfacing	NC 7	SR 2329	I-85	0.94	1.5" S9.5C	$360,000
2026	12	036-Gaston	Resurfacing	NC275	Stanley City Limit	W. Carpenter St.	0.69	1.5" S9.5B	$96,400
2026	12	036-Gaston	Resurfacing	SR 1188	SR 1118	CLEV. CO.	0.75	1.5" S9.5B	$111,900
2026	12	036-Gaston	Resurfacing	SR 1472	SR 1474	SR 1440	0.75	1.5" S9.5B	$113,800
2026	12	036-Gaston	Resurfacing	SR 1828	NC 27	SR1844	1.67	1.5" S9.5B	$295,550
2026	12	036-Gaston	Resurfacing	SR 1840	SR 1828	SR 1830	0.47	1.5" S9.5B	$83,000
2026	12	036-Gaston	Resurfacing	SR 1900	LINC CO	SR 1820	0.36	1.5" S9.5B	$63,250
2026	12	036-Gaston	Resurfacing	SR 1903	NC27	SR1902	0.62	1.5" S9.5B	$91,000
2026	12	036-Gaston	Resurfacing	SR 1905	BRIDGE	NC 273	2.19	1.5" S9.5B	$385,725
2026	12	036-Gaston	Resurfacing	SR 1914	SR 1905	SR 1915	0.40	1.5" S9.5B	$70,000
2026	12	036-Gaston	Resurfacing	SR 1915	SR1914	NC 273	0.17	1.5" S9.5B	$29,750
2026	12	036-Gaston	Resurfacing	SR 1918	NC 27	SR 1935	2.50	1.5" S9.5B	$350,000
2026	12	036-Gaston	Resurfacing	SR 2198	NC 27	NC 273	0.39	1.5" S9.5B	$70,000
2026	12	036-Gaston	Resurfacing	SR 2200	NC 7	C.L. Ranlo	1.32	Full Depth Patching and 1.5" S9.5C	$246,100
2026	12	036-Gaston	Resurfacing	SR 2209	US 29	SR 2491	0.23	1.5" S9.5B	$102,500
2026	12	036-Gaston	Resurfacing	SR 2560	BRIDGE	SR 2519	0.30	1.5" S9.5C	$200,000
2026	12	036-Gaston	Resurfacing	SR 2560	SR 2519	END C AN G	0.47	1.5" S9.5C	$82,000
2026	12	036-Gaston	Resurfacing	SR 2648	SR 2421	D.END	0.58	1.5" S9.5A	$101,200
2026	12	036-Gaston	Resurfacing	SR 3103	SR 1188	END MAINT	0.20	1.5" S9.5B	$35,000
2026	12	036-Gaston	Resurfacing	SR 3107	SR 1118	D END	0.22	1.5" S9.5B	$35,000
2026	12	036-Gaston	Resurfacing	SR1001	NC 275	SR 1803	1.60	1.5" S9.5B	$210,000
2026	12	036-Gaston	Resurfacing	SR1103	SR3118	SR1112	3.13	1.5" S9.5B	$390,000
2026	12	036-Gaston	Resurfacing	SR1135	NC274	US 29/74	1.61	1.5" S9.5B	$224,700
2026	12	036-Gaston	Resurfacing	SR1924	SR 2085	NC 27	0.77	1.5" S9.5B	$128,824
2026	12	036-Gaston	Resurfacing	SR2380	NC 7	ESM	0.38	1.5" S9.5B	$96,228
2026	12	036-Gaston	Resurfacing	SR2392	SR2207	ESM	0.38	1.5" S9.5B	$108,061
2026	12	036-Gaston	Resurfacing	SR2413	US 321	SR2412	0.60	1.5" S9.5B	$79,600
2026	12	036-Gaston	Resurfacing	SR2421	SR2420	SR2412	0.62	1.5" S9.5B	$84,600
2026	12	036-Gaston	Resurfacing	SR2424	S.C.	SR2423	0.60	1.5" S9.5B	$114,380
2026	12	036-Gaston	Resurfacing	US 29/74S	SR 1303	SR1122	2.15	1.5" S9.5B	$595,000
2026	12	036-Gaston	Preservation	SR 1102	SR 1104	SR 1112	1.26	Microsurface	$68,300
2026	12	036-Gaston	Preservation	SR 1119	SR 1125	SR 1125	0.40	1.0" S9.5A	$21,900
2026	12	036-Gaston	Preservation	SR 1175	SR 1103	D END	0.31	1.0" S9.5B	$15,500
2026	12	036-Gaston	Preservation	SR 1201	US 321	D END	0.45	1.0" S9.5B	$22,500
2026	12	036-Gaston	Preservation	SR 1212	SR 1116	D END	0.29	1.0" S9.5B	$11,500
2026	12	036-Gaston	Preservation	SR 1391	SR 1310	SR 1310	0.05	1.0" S9.5B	$3,200
2026	12	036-Gaston	Preservation	SR 1470	SR 1426	D END	0.33	1.0" S9.5B	$33,000
2026	12	036-Gaston	Preservation	SR 1477	SR 1402	D END	0.22	1.0" S9.5B	$22,000
2026	12	036-Gaston	Preservation	SR 1482	SR 1409	D END	0.40	1.0" S9.5B	$24,500
2026	12	036-Gaston	Preservation	SR 1487	SR 1412	CUL DE SAC	0.19	1.0" S9.5B	$18,000
2026	12	036-Gaston	Preservation	SR 1498	SR1452	SR 1456	0.58	Microsurface	$32,000
2026	12	036-Gaston	Preservation	SR 1529	SR1528	CDS	0.25	1.0" S9.5B	$11,200
2026	12	036-Gaston	Preservation	SR 1638	CITY LIMITS	SR 1637	0.50	Microsurface	$35,000
2026	12	036-Gaston	Preservation	SR 1641	NC 274	SR 1638	0.94	Microsurface	$60,000
2026	12	036-Gaston	Preservation	SR 1642	SR 1637	SR 1644	0.47	Microsurface	$30,000
2026	12	036-Gaston	Preservation	SR 1672	SR 1609	D END	0.19	1.0" S9.5B	$14,900
2026	12	036-Gaston	Preservation	SR 1737	SR 1622	CDS	0.24	1.0" S9.5B	$18,200
2026	12	036-Gaston	Preservation	SR 1752	SR 1602	CDS	0.18	1.0" S9.5B	$14,850
2026	12	036-Gaston	Preservation	SR 1759	SR 1617	D END	0.35	1.0" S9.5B	$26,450
2026	12	036-Gaston	Preservation	SR 1760	SR 1759	D END	0.16	1.0" S9.5B	$12,000
2026	12	036-Gaston	Preservation	SR 1761	SR 1761	D END	0.20	1.0" S9.5B	$15,000
2026	12	036-Gaston	Preservation	SR 1762	SR 1761	D END	0.07	1.0" S9.5B	$5,250
2026	12	036-Gaston	Preservation	SR 1802	SR 1805	SR 1806	0.85	Microsurface	$34,000
2026	12	036-Gaston	Preservation	SR 1852	NC 275	D END	0.19	1.0" S9.5B	$14,900
2026	12	036-Gaston	Preservation	SR 1854	NC 275	D END	0.21	1.0" S9.5B	$16,100

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	12	036-Gaston	Preservation	SR 1868	SR 1836	D END	0.16	1.0" S9.5B	$12,250
2026	12	036-Gaston	Preservation	SR 1870	NC 275	D END	0.20	1.0" S9.5B	$15,300
2026	12	036-Gaston	Preservation	SR 1882	SR 1802	D END	0.22	1.0" S9.5B	$16,600
2026	12	036-Gaston	Preservation	SR 1885	SR 1827	CDS	0.38	1.0" S9.5B	$28,000
2026	12	036-Gaston	Preservation	SR 1886	SR 1820	D END	0.21	1.0" S9.5B	$16,100
2026	12	036-Gaston	Preservation	SR 1890	SR 1827	CDS	0.36	1.0" S9.5B	$34,500
2026	12	036-Gaston	Preservation	SR 1891	SR 1890	CDS	0.11	1.0" S9.5B	$9,000
2026	12	036-Gaston	Preservation	SR 1906	SR1902	SR1905	1.84	1.5" S9.5B	$328,700
2026	12	036-Gaston	Preservation	SR 2435	NC 274	NC 279	3.33	Microsurface	$134,000
2026	12	036-Gaston	Preservation	SR1401	NC161	CLEV. CO	4.53	Microsurface	$160,000
2026	12	036-Gaston	Preservation	SR1419	NC274	SR1418	0.96	Microsurface	$41,100
2026	12	036-Gaston	Preservation	SR1426	NC150	CLEV CO	0.92	Microsurface	$50,600
2026	12	036-Gaston	Preservation	SR1437	SR1416	DE	0.71	Microsurface	$31,000
2026	12	036-Gaston	Preservation	SR1447	SR1446	SR1443	1.01	Microsurface	$47,000
2026	12	036-Gaston	Preservation	SR1530	SR1528	SR1533	0.14	1.0" S9.5B	$9,500
2026	12	036-Gaston	Preservation	SR1531	SR1528	D END	0.15	1.0" S9.5B	$8,300
2026	12	036-Gaston	Preservation	SR1606	SR1607	SR1605	1.04	Microsurface	$44,300
2026	12	036-Gaston	Preservation	SR1610	SR1607	SR1609	1.05	Microsurface	$43,200
2026	12	049-Iredell	Resurfacing	SR 1006	SR 1500	SR 1006	5.77	1.5" S9.5C	$1,290,250
2026	12	049-Iredell	Resurfacing	SR 1106	NC 115	Dead End	0.51	1.0" S9.5B	$63,500
2026	12	049-Iredell	Resurfacing	SR 1107	SR 1102	SR 1102	0.34	1.0" S9.5B	$42,500
2026	12	049-Iredell	Resurfacing	SR 1115	SR 1100	Cul-De-Sac	2.91	1.0" S9.5B	$364,000
2026	12	049-Iredell	Resurfacing	SR 1128	NC 115	End Maint.	1.09	1.0" S9.5B	$136,500
2026	12	049-Iredell	Resurfacing	SR 1135	NC 115	US 21	0.66	1.5" S9.5C	$108,900
2026	12	049-Iredell	Resurfacing	SR 1158	SR 1150	SR 1159	0.09	1.0" S9.5B	$10,750
2026	12	049-Iredell	Resurfacing	SR 1159	SR 1150	Dead End	0.39	1.0" S9.5B	$48,625
2026	12	049-Iredell	Resurfacing	SR 1179	SR 1179 +0.9 miles	SR 1100	1.93	1.5" S9.5C	$318,450
2026	12	049-Iredell	Resurfacing	SR 1215	SR 1115	SR 1215	1.67	1.0" S9.5B	$208,750
2026	12	049-Iredell	Resurfacing	SR 1246	US 21	NC 115	1.02	1.5" S9.5C	$168,960
2026	12	049-Iredell	Resurfacing	SR 1337	SR 1005	SR 1338	1.28	1.0" S9.5B	$160,250
2026	12	049-Iredell	Resurfacing	SR 1359	SR 1355	US 70	1.14	1.5" S9.5B	$188,100
2026	12	049-Iredell	Resurfacing	SR 1370	US 70	SR 1369	0.67	1.5" S9.5C	$150,750
2026	12	049-Iredell	Resurfacing	SR 1435	SR 1398	DE	0.07	1.0" S9.5B	$8,750
2026	12	049-Iredell	Resurfacing	SR 1449	SR 1300	DE	0.64	1.5" S9.5C	$105,600
2026	12	049-Iredell	Resurfacing	SR 1457	SR 1115	SR 1457	0.83	1.0" S9.5B	$104,000
2026	12	049-Iredell	Resurfacing	SR 1507	US 70	SR 1505	1.27	1.5" S9.5C	$285,750
2026	12	049-Iredell	Resurfacing	SR 1508	US 70	SR 1505	1.07	1.5" S9.5C	$240,750
2026	12	049-Iredell	Resurfacing	SR 1521	SR 1520	NC 90	2.82	1.5" S9.5C	$634,500
2026	12	049-Iredell	Resurfacing	SR 1652	SR 1520	SR 1520	0.46	1.0" S9.5B	$103,500
2026	12	049-Iredell	Resurfacing	SR 1666	SR 1652	SR 1652	0.14	1.0" S9.5B	$23,000
2026	12	049-Iredell	Resurfacing	SR 1765	SR 1520	Cul-de-Sac	0.15	1.0" S9.5B	$25,000
2026	12	049-Iredell	Resurfacing	SR 1783	SR 1505	Cul-De-Sac	0.63	1.0" S9.5B	$78,875
2026	12	049-Iredell	Resurfacing	SR 1784	SR 1783	Cul-De-Sac	0.07	1.0" S9.5B	$9,250
2026	12	049-Iredell	Resurfacing	SR 1785	SR 1783	Cul-De-Sac	0.15	1.0" S9.5B	$19,250
2026	12	049-Iredell	Resurfacing	SR 1792	SR 1502	Cul-De-Sac	0.33	1.0" S9.5B	$74,250
2026	12	049-Iredell	Resurfacing	SR 1834	SR 1833	NC 901	1.22	1.0" S9.5B	$152,000
2026	12	049-Iredell	Resurfacing	SR 1897	SR 1874	Dead End	0.99	1.0" S9.5B	$123,750
2026	12	049-Iredell	Resurfacing	SR 1902	NC 115	End Pvmt.	0.40	1.0" S9.5B	$50,250
2026	12	049-Iredell	Resurfacing	SR 1910	NC 115	SR 1907	1.05	1.0" S9.5B	$130,875
2026	12	049-Iredell	Resurfacing	SR 1920	SR 1892	Dead End	0.81	1.0" S9.5B	$101,250
2026	12	049-Iredell	Resurfacing	SR 1991	SR 1821	Dead End	0.61	1.0" S9.5B	$76,125
2026	12	049-Iredell	Resurfacing	SR 2013	SR 1920	Dead End	0.40	1.0" S9.5B	$50,000
2026	12	049-Iredell	Resurfacing	SR 2026	SR 1845	Dead End	0.50	1.0" S9.5B	$62,500
2026	12	049-Iredell	Resurfacing	SR 2027	SR 2026	Dead End	0.09	1.0" S9.5B	$10,625
2026	12	049-Iredell	Resurfacing	SR 2028	SR 1920	Dead End	0.19	1.0" S9.5B	$23,750
2026	12	049-Iredell	Resurfacing	SR 2043	SR 1845	Cul-De-Sac	0.29	1.0" S9.5B	$36,500
2026	12	049-Iredell	Resurfacing	SR 2044	SR 1845	Cul-De-Sac	0.39	1.0" S9.5B	$48,125
2026	12	049-Iredell	Resurfacing	SR 2144	NC 901	SR 2145	1.03	1.0" S9.5B	$128,750
2026	12	049-Iredell	Resurfacing	SR 2149	SR 2145	Dead End	1.38	1.5" S9.5C	$227,700

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	12	049-Iredell	Resurfacing	SR 2151	SR 2158	Dead End	1.44	1.0" S9.5B	$179,375
2026	12	049-Iredell	Resurfacing	SR 2351	SR 2434	Cul-de-sac	0.89	1.0" S9.5B	$111,750
2026	12	049-Iredell	Resurfacing	SR 2399	NC 152	NC 801	3.29	1.5" S9.5C	$542,850
2026	12	049-Iredell	Resurfacing	SR 2434	SR 2351	I-77 On-Ramp	0.28	1.0" S9.5B	$34,750
2026	12	049-Iredell	Resurfacing	SR 2459	SR 2320	SR 2493	0.38	1.0" S9.5B	$47,500
2026	12	049-Iredell	Resurfacing	SR 2462	SR 2320	Dead End	0.33	1.0" S9.5B	$40,750
2026	12	049-Iredell	Resurfacing	SR 2582	SR 2342	Cul-De-Sac	1.80	1.0" S9.5B	$225,500
2026	12	049-Iredell	Resurfacing	SR 2611	SR 2582	SR 2633	0.20	1.0" S9.5B	$24,500
2026	12	049-Iredell	Resurfacing	SR 2630	SR 2462	Dead End	0.25	1.0" S9.5B	$31,500
2026	12	049-Iredell	Resurfacing	SR 2632	SR 2632	End Maint.	0.11	1.0" S9.5B	$13,500
2026	12	049-Iredell	Resurfacing	SR 2633	SR 2634	SR 2633	0.12	1.0" S9.5B	$15,250
2026	12	049-Iredell	Resurfacing	SR 2634	SR 2611	Cul-De-Sac	0.11	1.0" S9.5B	$14,125
2026	12	049-Iredell	Resurfacing	SR 2818	SR 3160	DE	0.26	1.0" S9.5B	$32,250
2026	12	049-Iredell	Resurfacing	SR 2819	SR 2818	DE	0.09	1.0" S9.5B	$10,875
2026	12	049-Iredell	Resurfacing	SR 2820	SR 3161	DE	0.07	1.0" S9.5B	$9,000
2026	12	049-Iredell	Resurfacing	SR 2821	SR 3163	Cul-de-sac	0.05	1.0" S9.5B	$5,750
2026	12	049-Iredell	Resurfacing	SR 3039	SR 3006	SR 3040	0.11	1.0" S9.5B	$13,750
2026	12	049-Iredell	Resurfacing	SR 3040	SR 3039	SR 3041	0.19	1.0" S9.5B	$23,750
2026	12	049-Iredell	Resurfacing	SR 3041	SR 3040	Dead End	0.12	1.0" S9.5B	$15,000
2026	12	049-Iredell	Resurfacing	SR 3130	SR 1461	DE	0.16	1.0" S9.5B	$20,000
2026	12	049-Iredell	Resurfacing	SR 3160	SR 3160	SR 2818	0.17	1.0" S9.5B	$21,375
2026	12	049-Iredell	Resurfacing	SR 3161	SR 3160	DE	0.31	1.0" S9.5B	$38,625
2026	12	049-Iredell	Resurfacing	SR 3163	SR 3160	Cul-de-sac	0.36	1.0" S9.5B	$45,375
2026	12	049-Iredell	Resurfacing	SR 3233	SR 1106	Dead End	0.27	1.0" S9.5B	$33,750
2026	12	049-Iredell	Resurfacing	SR 3283	SR 3282	Cul-De-Sac	0.48	1.0" S9.5B	$60,125
2026	12	049-Iredell	Resurfacing	SR 3284	SR 3283	Cul-De-Sac	0.12	1.0" S9.5B	$15,000
2026	12	049-Iredell	Resurfacing	SR 3295	SR 3304	Dead End	0.07	1.0" S9.5B	$8,625
2026	12	049-Iredell	Resurfacing	SR 3304	SR 1215	Dead End	0.19	1.0" S9.5B	$23,750
2026	12	049-Iredell	Resurfacing	US 21	Pvmt. Change @ I-77	US 21/NC 115 Split	0.12	1.5" S9.5C	$26,550
2026	12	049-Iredell	Resurfacing	US 21	Pvmt. Change @ I-77	US 21/NC 115 Split	2.49	1.5" S9.5C	$561,150
2026	12	049-Iredell	Resurfacing	US 21	Pvmt. Change @ I-77	US 21/NC 115 Split	2.14	1.5" S9.5C	$481,500
2026	12	049-Iredell	Resurfacing	US 70	Pvmt. Change	Rowan CL	3.94	1.5" S9.5C	$1,083,500
2026	12	049-Iredell	Preservation	SR 1501	SR 1500	SR 1502	1.31	Seal - Double	$45,850
2026	12	049-Iredell	Preservation	SR 1599	SR 1598	SR 1598	0.78	Seal - Double	$35,280
2026	12	049-Iredell	Preservation	SR 1602	SR 1598	SR 1604	0.94	Seal - Double	$42,075
2026	12	049-Iredell	Preservation	SR 1604	Begin Maint.	SR 1602	1.18	Seal - Double	$53,235
2026	12	049-Iredell	Preservation	SR 1604	SR 1602	SR 1598	0.62	Seal - Double	$27,945
2026	12	049-Iredell	Preservation	SR 1804	SR 1803	NC 901	0.45	Seal - Double	$20,250
2026	12	049-Iredell	Preservation	SR 1805	SR 1803	SR 1807	1.98	Seal - Double	$89,055
2026	12	049-Iredell	Preservation	SR 1807	Wilkes Co.	NC 901	1.80	Seal - Double	$80,820
2026	12	049-Iredell	Preservation	SR 1819	SR 1821	SR 1983	0.90	Seal - Double	$40,275
2026	12	049-Iredell	Preservation	SR 1821	SR 1832	SR 1831	4.08	Seal - Double	$183,600
2026	12	049-Iredell	Preservation	SR 1867	SR 1863	SR 1861	0.91	Seal - Double	$41,085
2026	12	049-Iredell	Preservation	SR 1871	SR 1870	NC 115	1.98	Seal - Double	$89,235
2026	12	049-Iredell	Preservation	SR 1905	Begin Pvmt.	NC 115	1.76	Seal - Double	$79,290
2026	12	049-Iredell	Preservation	SR 1968	SR 1922	SR 1971	0.17	.75" S4.75A	$12,750
2026	12	049-Iredell	Preservation	SR 1969	SR 1922	SR 1988	0.24	.75" S4.75A	$18,000
2026	12	049-Iredell	Preservation	SR 1971	SR 1922	Dead End	0.34	.75" S4.75A	$25,500
2026	12	049-Iredell	Preservation	SR 1972	SR 1924	SR 1971	0.39	.75" S4.75A	$29,250
2026	12	049-Iredell	Preservation	SR 1973	SR 1924	SR 1974	0.32	.75" S4.75A	$24,000
2026	12	049-Iredell	Preservation	SR 1988	SR 1955	US 21	0.23	.75" S4.75A	$17,250
2026	12	049-Iredell	Preservation	SR 1996	SR 1924	SR 2002	0.46	.75" S4.75A	$34,500
2026	12	049-Iredell	Preservation	SR 2002	SR 1922	SR 2030	0.54	.75" S4.75A	$40,500
2026	12	049-Iredell	Preservation	SR 2030	SR 1996	SR 2002	0.15	.75" S4.75A	$11,250
2026	12	049-Iredell	Preservation	SR 2053	SR 1924	Dead End	0.23	.75" S4.75A	$17,250
2026	12	049-Iredell	Preservation	SR 2377	SR 2378	Dead End	0.40	.75" S4.75A	$30,000
2026	12	049-Iredell	Preservation	SR 2380	SR 2379	Dead End	0.37	.75" S4.75A	$28,500
2026	12	049-Iredell	Preservation	SR 2381	SR 2379	Dead End	0.20	.75" S4.75A	$15,000
2026	12	049-Iredell	Preservation	SR 2420	SR 1001	Dead End	0.47	.75" S4.75A	$35,250

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	12	049-Iredell	Preservation	SR 2425	SR 1001	Dead End	0.28	.75" S4.75A	$21,000
2026	12	049-Iredell	Preservation	SR 2592	SR 2377	Dead End	0.15	.75" S4.75A	$11,250
2026	12	049-Iredell	Preservation	SR 2644	SR 2646	SR 2645	0.17	.75" S4.75A	$12,750
2026	12	049-Iredell	Preservation	SR 2645	Dead End	Dead End	0.18	.75" S4.75A	$13,500
2026	12	049-Iredell	Preservation	SR 2646	SR 1001	Cul-De-Sac	0.34	.75" S4.75A	$25,500
2026	12	055-Lincoln	Resurfacing	NC 16 Bus	SR 1389	Catawba Co	5.37	Full Depth Patching and 1.5" S9.5C	$1,046,760
2026	12	055-Lincoln	Resurfacing	NC 16 NB	Gaston Co	R. R. Bridge	4.96	Full Depth Patching and 1.5" S9.5C	$967,200
2026	12	055-Lincoln	Resurfacing	NC 16 SB	R. R. Bridge	Gaston Co	4.95	Full Depth Patching and 1.5" S9.5C	$965,250
2026	12	055-Lincoln	Resurfacing	SR 1104	SR 1113	SR 1111	1.19	Full Depth Patching and 1.5" S9.5C	$232,050
2026	12	055-Lincoln	Resurfacing	SR 1111	NC 27	SR 1104	1.63	Full Depth Patching and 1.5" S9.5C	$317,850
2026	12	055-Lincoln	Resurfacing	SR 1381	SR 1763	SR 1386	2.84	Full Depth Patching and 1.5" S9.5B	$554,580
2026	12	055-Lincoln	Resurfacing	SR 1386	NC 16	NC 73	4.64	Full Depth Patching and 1.5" S9.5B	$904,410
2026	12	055-Lincoln	Resurfacing	SR 1574	SR 1376	CUL-DE-SAC	0.58	Patching and 1.0" S9.5A	$49,000
2026	12	055-Lincoln	Preservation	SR 1136	SR 1139	DE	0.51	Microsurface	$27,412
2026	12	055-Lincoln	Preservation	sr 1139	sr 1135	nc 27	1.35	Microsurface	$72,777
2026	12	055-Lincoln	Preservation	SR 1159	NC 182	SR 1140	1.72	Seal - Double	$92,342
2026	12	055-Lincoln	Preservation	SR 1169	SR 1002	SR 1168	1.12	Seal - Double	$60,146
2026	12	055-Lincoln	Preservation	SR 1198	SR 1002	SR 1113	2.07	Seal - Double	$111,208
2026	12	055-Lincoln	Preservation	SR 1242	US 321 BUS	GASTON CO	1.53	Seal - Double	$8,237
2026	12	055-Lincoln	Preservation	SR 1252	SR 1239	SR 1222	1.88	Seal - Double	$100,835
2026	12	055-Lincoln	Preservation	SR 1273	SR 1274	CATAWBA CO	0.47	Seal - Double	$25,262
2026	12	055-Lincoln	Preservation	SR 1279	US 321 BUS	CATAWBA CO	2.18	Seal - Double	$117,175
2026	12	055-Lincoln	Preservation	SR 1309	SR 1001	SR 1313	0.95	Seal - Double	$51,062
2026	12	055-Lincoln	Preservation	SR 1309	SR 1001	NC 27	2.90	Seal - Double and Fog Seal	$155,928
2026	12	055-Lincoln	Preservation	SR 1310	NC 27	GASTON CO	0.63	Seal - Double	$6,280
2026	12	055-Lincoln	Preservation	SR 1322	SR 1001	DEAD END	0.72	Seal - Double	$38,700
2026	12	055-Lincoln	Preservation	SR 2058	SR 1169	Gaston Co	0.32	Seal - Double	$16,985
2026	13	011-Buncombe	Resurfacing	SR 1001 (MEADOWSTOWN ROAD)	MADISON COUNTY LINE	NC 63	1.41	Mill 1.5" and 1.5" S9.5C	$275,675
2026	13	011-Buncombe	Resurfacing	SR 3071 (AVONDALE ROAD)	US 74 ALTERNATE	END OF MAINTENANCE	1.17	Full Depth Patching and 1.5" S9.5C	$185,050
2026	13	011-Buncombe	Resurfacing	SR 3073 (LOVERS LOOP ROAD)	SR 3071 (AVONDALE ROAD)	END OF MAINTENANCE	0.60	Full Depth Patching and 1.5" S9.5C	$89,933
2026	13	011-Buncombe	Resurfacing	SR 3075 (ONTEORA BOULEVARD)	I 40	R 3069 (PORTER ROAD) + .07 MILE	0.20	Full Depth Patching and 1.5" S9.5C	$39,950
2026	13	011-Buncombe	Resurfacing	SR 3075 (ONTEORA BOULEVARD)	PAVEMENT CHANGE	SR 3052 (SCHOOL ROAD EAST)	0.90	Full Depth Patching and 1.5" S9.5C	$175,675
2026	13	011-Buncombe	Resurfacing	SR 3075 (WEST CHAPEL ROAD)	SR 3052 (SCHOOL ROAD)	US 25	0.92	Full Depth Patching and 1.5" S9.5C	$168,000
2026	13	011-Buncombe	Resurfacing	SR 3079 (OAKVIEW PARK ROAD)	SR 3052 (SCHOOL ROAD EAST)	RAIL ROAD	0.39	Full Depth Patching and 1.5" S9.5C	$69,899
2026	13	011-Buncombe	Resurfacing	SR 3116 (MILLS GAP ROAD)	25 ALTERNATE	COUNTY LINE	4.92	Full Depth Patching and 1.5" S9.5C	$885,600
2026	13	011-Buncombe	Resurfacing	SR 3117 (REYNOLDS SCHOOL ROAD)	SR 3121 (ROSE HILL ROAD)	RIDGEVIEW WAY (PRIVATE)	0.82	Full Depth Patching and 1.5" S9.5C	$158,950
2026	13	011-Buncombe	Resurfacing	SR 3121 (PINNERS COVE ROAD)	SR 3119 (MERRILS COVE ROAD)	SR 3116 (MILLS GAP ROAD)	3.74	Full Depth Patching	$89,994
2026	13	011-Buncombe	Resurfacing	SR 3121 (ROSE HILL ROAD)	US 74 ALTERNATE	SR 3074 (BEE RIDGE ROAD)	1.18	Full Depth Patching and 1.5" S9.5C	$215,989
2026	13	011-Buncombe	Resurfacing	SR 3121 (ROSE HILL ROAD)	SR 3074 (BEE RIDGE ROAD)	SR 3119 (MERRILLS COVE ROAD)	1.06	Full Depth Patching and 1.5" S9.5C	$143,599
2026	13	011-Buncombe	Resurfacing	8 (UPPER BRUSH CREEK / LOWER BRUSH (	US 74 ALTERNATE	SR 3136 (CANE CREEK ROAD)	5.17	Full Depth Patching and 1.5" S9.5C	$904,750
2026	13	011-Buncombe	Resurfacing	SR 3147 (UPPER BRUSH CREEK ROAD)	SR 3136 (CANE CREEK ROAD)	3138 (LOWER BRUSH CREEK ROAI	0.37	Full Depth Patching and 1.5" S9.5C	$64,545
2026	13	011-Buncombe	Resurfacing	SR 3153 (WILLIAMS ROAD)	SR 3150 (CONCORD ROAD)	SR 3116 (MILLS GAP ROAD)	1.31	Full Depth Patching and 1.5" S9.5C	$251,459
2026	13	011-Buncombe	Resurfacing	SR 3159 (CEDAR LANE)	SR 3158 (OAK TERRACE)	US 25 ALTERNATE	0.42	Full Depth Patching and 1.5" S9.5C	$73,500
2026	13	011-Buncombe	Resurfacing	SR 3161 (LOCUST COURT)	SR 3158 (OAK TERRACE)	SR 3162 (ROYAL PINES DRIVE)	0.34	Full Depth Patching and 1.5" S9.5C	$76,565
2026	13	011-Buncombe	Resurfacing	SR 3162 (ROYAL PINES DRIVE)	SR 3158 (OAK TERRACE)	US 25 ALTERNATE	0.86	Full Depth Patching and 1.5" S9.5C	$127,955
2026	13	011-Buncombe	Resurfacing	SR 3163 (WALNUT STREET)	SR 3159 (CEDAR LANE)	SR 3162 (ROYAL PINES DRIVE)	0.27	Full Depth Patching and 1.5" S9.5C	$32,400
2026	13	011-Buncombe	Resurfacing	SR 3164 (SYCAMORE DRIVE)	SR 3163 (WALNUT STREET)	SR 3165 (MAPLE COURT)	0.28	Full Depth Patching and 1.5" S9.5C	$58,999
2026	13	011-Buncombe	Resurfacing	SR 3166 (MYRTLE STREET)	SR 3165 (SYCAMORE DRIVE)	US 25 ALTERNATE	0.12	Full Depth Patching and 1.5" S9.5C	$14,280
2026	13	011-Buncombe	Resurfacing	LLER ROAD SOUTH /LEE STREET/ ROSCRA(	US 25	SR 3185 (RATHFARNHAM ROAD)	0.33	Full Depth Patching and 1.5" S9.5C	$72,000
2026	13	011-Buncombe	Resurfacing	SR 3184 (ROSCRAGGON ROAD)	US 25 ALTERNATE	DEAD END	0.27	Full Depth Patching and 1.5" S9.5C	$55,699
2026	13	011-Buncombe	Resurfacing	SR 3185 (RATHFARNHAM ROAD)	SR 3181 (ROSSCRAGGON ROAD)	US 25 ALTERNATE	0.21	Full Depth Patching and 1.5" S9.5C	$25,560
2026	13	011-Buncombe	Resurfacing	SR 3185 (RATHFARNHAM ROAD)	US 25 ALTERNATE	END OF PAVEMENT	0.30	Full Depth Patching and 1.5" S9.5C	$51,625
2026	13	011-Buncombe	Resurfacing	SR 3190 (ROYAL OAKS ROAD)	US 25	SR 3192 (FAIR OAKS ROAD)	0.31	Full Depth Patching and 1.5" S9.5C	$59,999
2026	13	011-Buncombe	Resurfacing	SR 3202 (OAKLEY DOGWOOD DRIVE)	SR 3052 (SCHOOL ROAD EAST)	END OF MAINTENANCE	0.20	Full Depth Patching and 1.5" S9.5C	$41,000
2026	13	011-Buncombe	Resurfacing	SR 3217 (WESTON ROAD)	US 25 ALTERNATE	SR 3158 (OAK TERRACE)	0.74	Full Depth Patching and 1.5" S9.5C	$128,025
2026	13	011-Buncombe	Resurfacing	SR 3233 (SOMERSET ROAD)	SR 3192 (FAIR OAKS ROAD)	END OF MAINTENANCE	0.17	Full Depth Patching and 1.5" S9.5C	$29,750
2026	13	011-Buncombe	Resurfacing	SR 3238 (FAIRVIEW ROAD)	BRIDGE	END OF MAINTENANCE	0.33	Full Depth Patching and 1.5" S9.5C	$39,600
2026	13	011-Buncombe	Resurfacing	SR 3256 (TUCKAWAY DRIVE)	SR 3185 (RATHFARNHAM ROAD)	SR 3256 (TUCKAWAY DRIVE)	0.21	Full Depth Patching and 1.5" S9.5C	$45,450
2026	13	011-Buncombe	Resurfacing	SR 3277 (FOREST RUN DRIVE)	SR 3121 (PINNERS COVE ROAD)	CUL DE SAC	0.24	Full Depth Patching and 1.5" S9.5C	$42,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	13	011-Buncombe	Resurfacing	SR 3282 (BREEZEWAY DRIVE)	SR 3256 (TUCKAWAY DRIVE)	END OF MAINTENANCE	0.14	Full Depth Patching and 1.5" S9.5C	$24,500
2026	13	011-Buncombe	Resurfacing	SR 3290 (FOX RIDGE DRIVE)	SR 3128 (EMMAS GROVE ROAD)	CUL DE SAC	0.32	Full Depth Patching and 1.0" S4.75A	$38,400
2026	13	011-Buncombe	Resurfacing	SR 3300 (WHITE PINE CIRCLE)	SR 3221 (WHITE PINE DRIVE)	SR 3221 (WHITE PINE DRIVE)	0.87	Full Depth Patching and 1.25" S9.5B	$140,250
2026	13	011-Buncombe	Resurfacing	SR 3301 (WHITE PINE WAY)	SR 3300 (WHITE PINE CIRCLE)	SR 3300 (WHITE PINE CIRCLE)	0.13	Full Depth Patching and 1.25" S9.5B	$16,250
2026	13	011-Buncombe	Resurfacing	SR 3302 (BALDWIN COURT)	SR 3189 (BALDWIN ROAD)	SR 3315 (MEADOWS CIRCLE)	0.18	Full Depth Patching and 1.5" S9.5C	$31,500
2026	13	011-Buncombe	Resurfacing	SR 3305 (WOODHAVEN DRIVE)	SR 3187 (PENSACOLA AVENUE)	END OF MAINTENANCE	0.11	Full Depth Patching and 1.5" S9.5C	$13,200
2026	13	011-Buncombe	Resurfacing	SR 3318 (SPRING COVE COURT)	BEGIN MAINT	CUL DE SAC	0.06	Full Depth Patching and 1.5" S9.5C	$11,025
2026	13	011-Buncombe	Resurfacing	SR 3326 (WESTON HEIGHTS DRIVE)	SR 3150 (CONCORD ROAD)	CUL DE SAC	0.48	Full Depth Patching and 1.5" S9.5C	$129,995
2026	13	011-Buncombe	Resurfacing	SR 3342 (SPRINGFIELD WAY)	SR 3189 (BALDWIN ROAD)	CUL DE SAC	0.10	Full Depth Patching and 1.5" S9.5C	$17,500
2026	13	011-Buncombe	Resurfacing	SR 3347 (EMERALD COURT)	SR 3189 (BALDWIN ROAD)	CUL DE SAC	0.08	Full Depth Patching and 1.0" S4.75A	$10,000
2026	13	011-Buncombe	Resurfacing	SR 3348 (KIT COVE)	SR 3290 (FOX RIDGE DRIVE)	CUL DE SAC	0.17	Full Depth Patching and 1.0" S4.75A	$17,000
2026	13	011-Buncombe	Resurfacing	SR 3356 (KNOLL DRIVE)	SR 3138 (UPPER BRUSH CREEK ROAD)	CUL DE SAC	0.15	Full Depth Patching and 1.0" S4.75A	$26,250
2026	13	011-Buncombe	Resurfacing	SR 3365 (BROMPTON ROAD)	SR 3116 (MILLS GAP ROAD)	SR 3366 (PORTOBELLO ROAD)	0.11	Full Depth Patching and 1.5" S9.5C	$13,200
2026	13	011-Buncombe	Resurfacing	SR 3366 (PORTOBELLO ROAD)	CUL DE SAC	DEAD END	0.48	Full Depth Patching and 1.5" S9.5C	$57,480
2026	13	011-Buncombe	Resurfacing	SR 3375 (KNOLLWOOD DRIVE)	SR 3374 (SPRING LAKE DRIVE)	CUL DE SAC	0.05	Full Depth Patching and 1.25" S9.5B	$7,720
2026	13	011-Buncombe	Resurfacing	SR 3376 (GUN FLINT TRAIL)	SR 3374 (GUN FLINT TRAIL)	CUL DE SAC	0.16	Full Depth Patching and 1.25" S9.5B	$24,000
2026	13	011-Buncombe	Resurfacing	SR 3532 (EDGEWOOD DRIVE)	US 25	END OF MAINTENANCE	0.21	Full Depth Patching and 1.0" S4.75A	$25,550
2026	13	011-Buncombe	Resurfacing	SR 3548 (HEYWOOD ROAD)	BRIDGE ABUTMENT AT CRAVEN STREET	BEVERLYROAD (CITY STREET)	0.56	Full Depth Patching and 1.5" S9.5C	$114,000
2026	13	011-Buncombe	Resurfacing	US 25	SR 3116 (MILLS GAP ROAD) + 1.32 MILE	3112 (EDGEWOOD ROAD)+ .345 M	1.25	Full Depth Patching and 1.5" S9.5C	$221,489
2026	13	011-Buncombe	Resurfacing	US 25	SR 3185 (RATHFARNHAM ROAD)+ .22 MILE	3116 (MILLS GAP ROAD)+ 1.32 MI	2.00	Full Depth Patching and 1.5" S9.5C	$410,995
2026	13	011-Buncombe	Preservation	SR 1341 (BRICKYARD ROAD)	SR 1338 (EMMA ROAD)	SR 1338 (EMMA ROAD)	1.24	Full Depth Patching and Double Seal and Fog Seal	$95,000
2026	13	011-Buncombe	Preservation	SR 1349 (ADAMS HILL ROAD)	SR 1353 (RIVERVIEW CHURCH ROAD)	1332 (NORTH LOUISIANA AVENU	0.89	Full Depth Patching and Double Seal and Fog Seal	$32,450
2026	13	011-Buncombe	Preservation	SR 1363 (OLD LEICESTER ROAD)	SR 1367 (OLIVETTE ROAD)	SR 1002 (OLD LEICESTER HIGHWAY	0.63	Full Depth Patching and Double Seal and Fog Seal	$47,250
2026	13	011-Buncombe	Preservation	SR 1367 (OLIVETTE ROAD)	SR 1002 (OLD LEICESTER HIGHWAY)	SR 1645 (MACEDONIA ROAD)	0.69	Full Depth Patching and 1.25" S9.5B	$155,650
2026	13	011-Buncombe	Preservation	SR 1372 (FOSTER ESTATE DRIVE)	SR 1002 (OLD LEICESTER HIGHWAY)	SR 1002 (OLD LEICESTER HIGHWAY	0.76	Full Depth Patching and 1.0" S4.75A	$129,999
2026	13	011-Buncombe	Preservation	.456 (KEYSTONE,CARDINAL,HOLLY HILL DR	SR 1369 MOUNT CARMEL ROAD)	SR 1374 (ODONALD ROAD)	1.09	Full Depth Patching and 1.0" S4.75A	$222,377
2026	13	011-Buncombe	Preservation	SR 1457 (HOLLY HILL COURT)	SR 1456 (HOLLY HILL DRIVE)	CUL DE SAC	0.10	Full Depth Patching and 1.0" S4.75A	$17,999
2026	13	011-Buncombe	Preservation	SR 1505 (LAKEVIEW ACRES DRIVE)	SR 1002 (OLD LEICESTER HIGHWAY)	END OF MAINTENANCE	0.17	Full Depth Patching and 1.0" S4.75A	$21,250
2026	13	011-Buncombe	Preservation	SR 1506 (SPRINGSIDE DRIVE)	SR 1505 (LAKEVIEW ACRES DRIVE)	CUL DE SAC	0.14	Full Depth Patching and 1.0" S4.75A	$17,500
2026	13	011-Buncombe	Preservation	SR 1516 (REMINGTON DRIVE)	SR 1372 (FOSTER ESTATE DRIVE)	END OF MAINTENANCE	0.12	Full Depth Patching and 1.0" S4.75A	$15,125
2026	13	011-Buncombe	Preservation	SR 1610 (MARTIN BRANCH ROAD)	SR 1607 (BEAR CREEK ROAD)	SR 1612 (GIBBS ROAD)	1.54	Full Depth Patching and Double Seal and Fog Seal	$145,799
2026	13	011-Buncombe	Preservation	SR 1615 (GILBERT ROAD)	NC 63	SR 1608 (TURKEY CREEK ROAD)	0.85	Full Depth Patching and Double Seal and Fog Seal	$69,855
2026	13	011-Buncombe	Preservation	SR 1621 (RIDGEVIEW ROAD)	SR 1620 (ALEXANDER ROAD)	SR 1622 (OLD NC 20 HIGHWAY)	1.36	Full Depth Patching and Double Seal and Fog Seal	$88,617
2026	13	011-Buncombe	Preservation	SR 1623 RHYMER ROAD	SR 1622 (OLD NC 20)	SR 1641 (JENKINS VALLEY ROAD)	1.02	Full Depth Patching and Double Seal and Fog Seal	$81,600
2026	13	011-Buncombe	Preservation	SR 1627 TIPTON HILL ROAD	SR 1620 (ALEXANDER ROAD)	SR 1629 (OLD HIGHWAY 20)	1.99	Full Depth Patching and Double Seal and Fog Seal	$159,200
2026	13	011-Buncombe	Preservation	SR 1632 (CEDAR HILL ROAD)	SR 1629 (OLD NC 20 HIGHWAY)	END OF PAVEMENT	1.40	Full Depth Patching and Double Seal and Fog Seal	$70,000
2026	13	011-Buncombe	Preservation	SR 1634 (FLETCHER MARTIN ROAD)	SR 1620 (ALEXANDER ROAD)	SR 1629 (OLD HIGHWAY 20)	1.42	Full Depth Patching and 1.25" S9.5B	$187,795
2026	13	011-Buncombe	Preservation	SR 1648 (JOHNSON ROAD)	SR 1647 (OLIVETTE ROAD)	END OF MAINTENANCE	0.37	Full Depth Patching and Double Seal and Fog Seal	$18,500
2026	13	011-Buncombe	Preservation	SR 1656 (FOX ROAD)	SR 1659 (OWENBY ROAD)	END OF MAINTENANCE	0.15	Full Depth Patching and Double Seal and Fog Seal	$7,500
2026	13	011-Buncombe	Preservation	SR 1659 (OWENBY ROAD/ CHURCH ROAD)	SR 1002 (OLD LEICESTER HIGHWAY)	END OF MAINTENANCE	0.45	Full Depth Patching and Double Seal and Fog Seal	$22,500
2026	13	011-Buncombe	Preservation	SR 1803 (TIPPERARY DRIVE)	SR 1368 (LEES CREEK ROAD)	CUL DE SAC	0.53	Full Depth Patching and 1.0" S4.75A	$66,250
2026	13	011-Buncombe	Preservation	SR 1806 (WATERFORD COURT)	SR 1805 (KILKENNY DRIVE)	CUL DE SAC	0.16	Full Depth Patching and 1.0" S4.75A	$20,000
2026	13	011-Buncombe	Preservation	SR 1808 (FIELDCRESTPLACE/ CIRCLE)	SR 1456 (HOLLY HILL DRIVE)	SR 1808 (FIELDCREST PLACE/CIRCLE	0.49	Full Depth Patching and 1.0" S4.75A	$65,000
2026	13	011-Buncombe	Preservation	SR 1814 (WONDU VIEW COURT)	SR 1813 (KEYSTONE DRIVE EXTENSION)	END OF MAINTENANCE	0.09	Full Depth Patching and 1.0" S4.75A	$10,625
2026	13	011-Buncombe	Preservation	SR 1825 (CARDINAL DRIVE)	SR 1456 (KEYSTONE DRIVE)	SR 1456 (HOLLY HILL DRIVE)	0.35	Full Depth Patching and 1.0" S4.75A	$55,556
2026	13	011-Buncombe	Preservation	SR 1851 (SHELBY ROAD)	SR 1357 (GORMAN BRIDGE ROAD)	CUL DE SAC	0.33	Full Depth Patching and Double Seal and Fog Seal	$22,655
2026	13	011-Buncombe	Preservation	SR 1853 (DAVLYN DRIVE)	SR 1369 (MOUNT CARMEL ROAD)	SR 1803 (TIPPERARY ROAD)	0.07	Full Depth Patching and 1.0" S4.75A	$8,750
2026	13	011-Buncombe	Preservation	SR 1854 (SCOTTLYNN DRIVE)	SR 1113 (BYRD ROAD)	SR 1803 (TIPPERARY DRIVE)	0.18	Full Depth Patching and 1.0" S4.75A	$22,500
2026	13	011-Buncombe	Preservation	SR 1862 (SCOTTLYNN COURT)	SR 1854 (SCOTTLYNN DRIVE)	CUL DE SAC	0.04	Full Depth Patching and 1.0" S4.75A	$5,000
2026	13	011-Buncombe	Preservation	1877 (TIPPERARY/MOUNT CARMEL DRIV	SR 1854 (SCOTTLYNN DRIVE)	END OF STATE MAINTENANCE	0.24	Full Depth Patching and 1.0" S4.75A	$30,000
2026	13	011-Buncombe	Preservation	SR 1880 (FRIENDLY WAY)	SR 1865 (LYNWOOD CIRCLE)	CUL DE SAC	0.18	Full Depth Patching and 1.0" S4.75A	$22,500
2026	13	011-Buncombe	Preservation	SR 1884 (WESTMONT DRIVE)	SR 1877 (MOUNT CARMEL DRIVE)	CUL DE SAC	0.13	Full Depth Patching and 1.0" S4.75A	$16,250
2026	13	011-Buncombe	Preservation	SR 1887 QUIET WOODS DRIVE	SR 1620 (ALEXANDER ROAD)	CUL DE SAC	0.68	Full Depth Patching and 1.0" S4.75A	$86,250
2026	13	011-Buncombe	Preservation	SR 1889 (SOUTHERN PINES PLACE)	SR 1887 (QUIET WOODS DRIVE)	CUL DE SAC	0.29	Full Depth Patching and 1.0" S4.75A	$36,250
2026	13	011-Buncombe	Preservation	SR 1890 (HOLLOW LOG LANE)	SR1889 (SOUTHERN PINES PLACE)	CUL DE SAC	0.10	Full Depth Patching and 1.0" S4.75A	$16,779
2026	13	011-Buncombe	Preservation	SR 1891 (FRIENDLY PLACE)	SR 1880 (FRIENDLY WAY)	CUL DE SAC	0.18	Full Depth Patching and 1.0" S4.75A	$22,500
2026	13	011-Buncombe	Preservation	SR 1892 (FRIENDLY CIRCLE)	CUL DE SAC	SR 1891 (FRIENDLY LANE)	0.05	Full Depth Patching and 1.0" S4.75A	$6,250
2026	13	012-Burke	Resurfacing	SR 1102 (HOPEWELL ROAD)	SR 1107 (HOPEWELL ROAD)	US 64	3.75	Full Depth Patching and 1.25" S9.5B	$699,899
2026	13	012-Burke	Resurfacing	SR 1107 (HOPEWELL ROAD)	US 64 (BURKMONT AVENUE)	SR 1102 (GOLF COURSE ROAD)	1.45	Full Depth Patching and 1.25" S9.5B	$289,999

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	13	012-Burke	Resurfacing	SR 1120 (RICH ROAD)	SR 1149 (CONLEY ROAD)	US 64	0.73	Full Depth Patching and 1.0" S4.75A	$148,000
2026	13	012-Burke	Resurfacing	SR 1147 (LONDON STREET)	SR 1168 (CONLEY ROAD)	US 70	0.47	Full Depth Patching and 1.5" S9.5C	$97,000
2026	13	012-Burke	Resurfacing	SR 1149 (CONLEY ROAD)	SR 1142 (JAMESTOWN ROAD)	US 64	6.02	Full Depth Patching and 1.5" S9.5C	$656,000
2026	13	012-Burke	Resurfacing	SR 1163 (CHAIN DRIVE)	SR 1147 (CAUSBY ROAD/I 40 ON RAMP WEST)	END OF MAINTENANCE	0.56	Full Depth Patching and 1.5" S9.5C	$99,000
2026	13	012-Burke	Resurfacing	SR 1168 (LONDON STREET/CONLEY ROAD)	SR 1147 (CAUSBY ROAD)	SR 1142 (JAMESTOWN ROAD)	0.98	Full Depth Patching and 1.5" S9.5C	$199,000
2026	13	012-Burke	Resurfacing	SR 1206 (SNOWHILL CHURCH ROAD)	SR 1334 (HOMESTEAD DRIVE)	US 70	1.13	Full Depth Patching and 1.5" S9.5C	$229,000
2026	13	012-Burke	Resurfacing	SR 1206 (SNOWHILL CHURCH ROAD)	US 70	R 1279 (ROY MCGALLIARD AVENUE	1.88	Full Depth Patching and 1.5" S9.5C	$380,000
2026	13	012-Burke	Resurfacing	SR 1230 (CONLEY BUMGARNER ROAD)	SR 1230 (CONLEY BUMGARNER ROAD)	SR 1223 (POWERHOUSE ROAD)	1.93	Full Depth Patching and 1.5" S9.5C	$390,000
2026	13	012-Burke	Resurfacing	SR 1955 (RURITAN DRIVE)	SR 1956 (BURKEMONT ROAD)	SR 1949 (SALEM ROAD)	0.61	Full Depth Patching and 1.0" S4.75A	$123,000
2026	13	012-Burke	Resurfacing	SR 1956 (BURKEMONT ROAD)	SR 1949 (SALEM ROAD)	SR 2002 (WESTERN AVENUE)	1.04	Full Depth Patching and 1.5" S9.5C	$211,000
2026	13	012-Burke	Resurfacing	R 1956 (BURKEMONT ROAD/JENKINS ROAI	SR 2002 (WESTERN AVENUE)	SR 1960 (CHARLIE CRAWLEY ROAD)	1.77	Full Depth Patching and 1.5" S9.5C	$358,000
2026	13	012-Burke	Resurfacing	SR 1960 (CHARLIE CRAWLEY ROAD)	SR 1961 (DUCKWORTH CIRCLE)	SR 1956 (JENKINS ROAD)	0.44	Full Depth Patching and 1.25" S9.5B	$78,300
2026	13	012-Burke	Resurfacing	SR 1961 (DUCKWORTH CIRCLE)	US 64	US 64	0.86	Full Depth Patching and 1.25" S9.5B	$68,950
2026	13	012-Burke	Resurfacing	SR 2002 (WESTERN AVENUE)	SR 1956 (BURKMONT AVENUE)	END OF MAINTENANCE	1.11	Full Depth Patching and 1.25" S9.5B	$199,800
2026	13	012-Burke	Resurfacing	SR 2013 (COMMUNITY COLLEGE DRIVE)	US 64	END OF STATE MAINTENANCE	0.41	Full Depth Patching and 1.25" S9.5C	$75,000
2026	13	012-Burke	Resurfacing	SR 2015 (MOUNTAIN GLEN CIRCLE)	SR 1957 (BURKEMONT ROAD)	SR 1957 (BURKEMONT ROAD)	0.46	Full Depth Patching and 1.0" S4.75A	$93,000
2026	13	012-Burke	Resurfacing	SR 2122 (WESLEY ROAD)	US 64	END OF MAINTENANCE	0.29	Full Depth Patching and 1.0" S4.75A	$50,000
2026	13	012-Burke	Resurfacing	SR 2123 (CERAMIC TILE DRIVE)	SR 1163 (CHAIN DRIVE)	END OF MAINTENANCE	0.63	Full Depth Patching and 1.5" S9.5C	$112,500
2026	13	012-Burke	Resurfacing	SR 2126 (SIMPSON FIELD LOOP)	BEGIN MAINTENANCE	END OF MAINTENANCE	0.39	Full Depth Patching and 1.0" S4.75A	$79,000
2026	13	012-Burke	Resurfacing	SR 2338 (LAKE ACRES DRIVE)	SR 1635 (AIRPORT RHODHISS ROAD)	CUL DE SAC	0.58	Full Depth Patching and 1.0" S4.75A	$68,000
2026	13	012-Burke	Resurfacing	US 64	MP 9.11	MP 10.13	0.20	Full Depth Patching and 1.5" S9.5C	$41,000
2026	13	012-Burke	Resurfacing	US 64	SR 1170 (SUTTLE STREET) + .167 MILES	SR 2122 (WESLEY ROAD)	1.93	Full Depth Patching and 1.5" S9.5C	$390,000
2026	13	012-Burke	Preservation	10TH STREET NORTH EAST	SR 1630 (WILSON ROAD)	US 70	0.56	Full Depth Patching and Double Seal and Fog Seal	$23,099
2026	13	012-Burke	Preservation	NC 221	MCDOWELL COUNTY LINE	AVERY COUNTY LINE	0.14	Crack Seal	$1,035
2026	13	012-Burke	Preservation	SR 1435 (OLD JOHNS RIVER ROAD)	END OF MAINT	SR 1426 (PAX HILL ROAD)	0.80	Full Depth Patching and Double Seal and Fog Seal	$60,030
2026	13	012-Burke	Preservation	SR 1518 (DEVINNEY AVENUE)	SR 1512 (AMHERST ROAD)	END OF MAINTENANCE	0.62	Full Depth Patching and Double Seal and Fog Seal	$45,000
2026	13	012-Burke	Preservation	SR 1519 (DEVINNEY STREET)	SR 1518 (DEVINNEY AVENUE)	END OF MAINTENANCE	0.39	Full Depth Patching and Double Seal and Fog Seal	$31,450
2026	13	012-Burke	Preservation	SR 1534 (WILLIAMS ROAD)	SR 1531 (NORTH MAIN STREET)	END OF MAINTENANCE	0.38	Full Depth Patching and 1.0" S4.75A	$57,000
2026	13	012-Burke	Preservation	SR 1547 (REFOUR ROAD NORTH EAST)	SR 1554 (BREVARD STREET)	US 70	0.49	Full Depth Patching and Double Seal and Fog Seal	$34,555
2026	13	012-Burke	Preservation	SR 1566 (TOM THOMAS DRIVE)	SR 1519 (DEVINNEY STREET)	END OF MAINTENANCE	0.13	Full Depth Patching and Double Seal and Fog Seal	$8,999
2026	13	012-Burke	Preservation	SR 1567 (RACE TRACK STREET)	SR 1501 (ANTIOCH ROAD)	SR 2219 (RACE TRACK STREET)	0.40	Full Depth Patching and Double Seal and Fog Seal	$34,555
2026	13	012-Burke	Preservation	SR 1569 (PUTNAM STREET)	NC 18	END OF MAINTENANCE	0.50	Full Depth Patching and Double Seal and Fog Seal	$38,888
2026	13	012-Burke	Preservation	SR 1591 (EASTBROOK CIRCLE)	PAVEMENT JOINT	SR 1520 (WALL STREET)	0.28	Full Depth Patching and 1.0" S4.75A	$28,500
2026	13	012-Burke	Preservation	SR 1619 (BAILEY ROAD)	SR 1611 (RHODHISS ROAD)	SR 1621 (ICARD RHODHISS ROAD)	2.02	Full Depth Patching and Double Seal and Fog Seal	$150,000
2026	13	012-Burke	Preservation	SR 1626 (GUS ICARD STREET)	SR 1621 (ICARD RHODHISS ROAD)	END OF MAINTENANCE	0.29	Full Depth Patching and Double Seal and Fog Seal	$18,525
2026	13	012-Burke	Preservation	SR 1631 (41ST STREET NORTH WEST)	SR 1630 (WILSON ROAD)	END OF MAINTENANCE	0.19	Full Depth Patching and Double Seal and Fog Seal	$14,250
2026	13	012-Burke	Preservation	SR 1648 (SETTLEMYRE, LAIL STREET)	SR 1647 (CAPE HICKORY ROAD)	SR 2345 (MCCRAY FARMS DRIVE)	0.20	Full Depth Patching and Double Seal and Fog Seal	$17,000
2026	13	012-Burke	Preservation	SR 1667 (BROWN CIRCLE ROAD)	SR 1611 (RHODHISS ROAD)	SR 1611 (RHODHISS ROAD)	0.19	Full Depth Patching and Double Seal and Fog Seal	$14,250
2026	13	012-Burke	Preservation	SR 1711 (BLANTON ROAD)	SR 1704 (BETHEL ROAD)	SR 1708 (EAST PARKER ROAD)	0.52	Full Depth Patching and Double Seal and Fog Seal	$40,195
2026	13	012-Burke	Preservation	SR 1720 (RECTOR STREET)	NC 114	END OF MAINTENANCE	0.23	Full Depth Patching and Double Seal and Fog Seal	$9,120
2026	13	012-Burke	Preservation	SR 1816 (STEAKHOUSE ROAD)	BEGIN MAINTENANCE	SR 1712 (DREXEL ROAD)	0.45	Full Depth Patching and Double Seal and Fog Seal	$33,545
2026	13	012-Burke	Preservation	SR 1830 (TOM DEAL AVENUE)	I 40	END OF MAINTENANCE	0.51	Full Depth Patching and Double Seal and Fog Seal	$45,450
2026	13	012-Burke	Preservation	SR 1968 (BOLLINGER LOOP)	US 64	US 64	1.33	Patching and Double Seal and Fog Seal	$87,996
2026	13	012-Burke	Preservation	SR 2208 (CUBE DRIVE)	SR 1538 (ENON ROAD)	DEAD END	0.50	Full Depth Patching and 1.0" S4.75A	$68,775
2026	13	012-Burke	Preservation	SR 2219 (SWINK/RACETRACK STREET)	SR 1567 (RACE TRACK STREET)	COUNTY LINE	0.14	Full Depth Patching and Double Seal and Fog Seal	$10,995
2026	13	057-Madison	Resurfacing	NC 209	MP 13.91	US 25/70	6.93	Full Depth Patching and 1.5" S9.5C	$1,173,845
2026	13	057-Madison	Resurfacing	SR 1334 (REVERE ROAD)	SR 1318 (BIG LAUREL ROAD)	SR 1323 (BURTON COVE ROAD)	4.08	Full Depth Patching and 1.5" S9.5C	$714,000
2026	13	057-Madison	Resurfacing	SR 1457 (LOWER PONDER BRANCH ROAD)	US 23 ALTERNATE	SR 1503 (LAUREL VALLEY ROAD)	0.40	Full Depth Patching and 1.5" S9.5C	$81,000
2026	13	057-Madison	Resurfacing	SR 1503 (LAUREL VALLEY ROAD)	US 23 ALTERNATE	1457 (LOWER PONDER BRANCH RO	1.34	Full Depth Patching and 1.5" S9.5C	$158,000
2026	13	057-Madison	Resurfacing	SR 1569 (BULL CREEK ROAD)	SR 1574 (HAZEL BROOK ROAD)	SR 1573 (GREEN HILL ROAD)	1.51	Full Depth Patching and 1.5" S9.5C	$306,000
2026	13	057-Madison	Resurfacing	SR 1570 (KELLY HUNTER)	SR 1569 (BULL CREEK ROAD)	SR 1561 (UPPER WHITE OAK ROAD)	1.69	Full Depth Patching and 1.5" S9.5C	$342,000
2026	13	057-Madison	Resurfacing	SR 1576 (BEND OF IVY ROAD)	SR 1574 (HAZELBROOK ROAD)	SR 1611 (SILVER MILL ROAD)	0.78	Full Depth Patching and 1.5" S9.5C	$140,400
2026	13	057-Madison	Resurfacing	US 19	YANCEY COUNTY LINE	SR 1511 (BETHEL CIRCLE)	1.85	Full Depth Patching and 1.5" S9.5C	$374,000
2026	13	057-Madison	Resurfacing	US 19	SR 1511 (BETHEL CIRCLE)	YANCEY COUNTY LINE	1.85	Full Depth Patching and 1.5" S9.5C	$374,000
2026	13	057-Madison	Preservation	SR 1183 (UPPER SHUT IN)	BEGIN PAVEMENT	US 25	5.13	Full Depth Patching and Double Seal and Fog Seal	$410,255
2026	13	057-Madison	Preservation	SR 1323 (BURTON COVE ROAD)	SR 1344 (REVERE ROAD)	OST 1.19 +.02 MILE IS END OF PAV	1.19	Full Depth Patching and Double Seal and Fog Seal	$89,250
2026	13	057-Madison	Preservation	SR 1324 (CHANDLER COVE ROAD)	SR 1344 (REVERE ROAD)	END OF PAVEMENT	1.12	Full Depth Patching and Double Seal and Fog Seal	$84,000
2026	13	057-Madison	Preservation	SR 1326 (DOUG COVE ROAD)	SR 1323 (BURTON COVE ROAD)	END OF PAVEMENT	0.57	Full Depth Patching and Double Seal and Fog Seal	$42,750
2026	13	057-Madison	Preservation	SR 1500 (SMITH CREEK ROAD)	US 23 ALTERNATE	SR 1502 (PUNCHEON FORK ROAD)	3.09	Full Depth Patching and Double Seal and Fog Seal	$299,775

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	13	059-McDowell	Resurfacing	NC 221	SR 1571 (ENGLISH ROAD)	SR 1571 (ENGLISH ROAD)+ 2 MILES	2.00	Full Depth Patching and 1.5" S9.5C	$455,650
2026	13	059-McDowell	Resurfacing	NC 221	SR 1560 (OLD LINVILLE ROAD)	SR 1571 (ENGLISH ROAD)	1.71	Full Depth Patching and 1.5" S9.5C	$385,650
2026	13	059-McDowell	Resurfacing	NC 221	SR 1572 (CARPENTER ROAD)	SR 1560 (OLD LINVILLE ROAD)	1.83	Full Depth Patching and 1.5" S9.5C	$410,850
2026	13	059-McDowell	Resurfacing	NC 221	SR 1781 (POLLY SPOUT ROAD)+ 1.946 Miles	SR 1786 (OLD US 221 SOUTH)	0.35	Full Depth Patching and 1.5" S9.5C	$99,550
2026	13	059-McDowell	Resurfacing	NC 221	SR 1571 (ENGLISH ROAD) + 2 Miles	BURKE COUNTY LINE	2.11	Full Depth Patching and 1.5" S9.5C	$525,345
2026	13	059-McDowell	Resurfacing	NC 221	SR 1781 (POLLY SPOUT ROAD)+ 1.946 MILES	SR 1786 (OLD US 221 SOUTH)	1.45	Full Depth Patching and 1.5" S9.5C	$425,250
2026	13	059-McDowell	Resurfacing	NC 221	RUTHERFORD COUNTY LINE	781 (POLLY SPOUT ROAD) + 1.946 M	2.00	Full Depth Patching and 1.5" S9.5C	$602,250
2026	13	059-McDowell	Resurfacing	SR 1131 (DAVIS TOWN CHURCH ROAD)	SR 1103 (BAT CAVE ROAD)	SR 1123 (BETHLEHEM ROAD)	1.80	Full Depth Patching and 1.5" S9.5C	$323,450
2026	13	059-McDowell	Resurfacing	SR 1152 (NEW HOPE WAY)	US 221 SOUTH	SR 1147 (OLD NEAL ROAD)	0.64	Full Depth Patching and 1.5" S9.5C	$125,650
2026	13	059-McDowell	Resurfacing	SR 1167 (RANDOLPH DRIVE)	SR 1276 (ASHEWORTH LOOP)	END OF MAINTENANCE	0.40	Full Depth Patching and 1.5" S9.5C	$82,000
2026	13	059-McDowell	Resurfacing	SR 1169 (BURMA ROAD WEST)	SR 1170 (CALIFORINA AVENUE)	END OF MAINTENANCE	1.52	Full Depth Patching and 1.5" S9.5C	$308,000
2026	13	059-McDowell	Resurfacing	SR 1197 (GREENLEE ROAD WEST)	BEGIN MAINTENANCE	SR 1214 (OLD NC 10 WEST)	0.11	Full Depth Patching and 1.5" S9.5C	$14,779
2026	13	059-McDowell	Resurfacing	SR 1274 (CATAWBA RIVER ROAD)	BEGIN MAINTENANCE	SR 1254 (MORRIS HOLLOW ROAD)	1.45	Full Depth Patching and 1.5" S9.5C	$292,000
2026	13	059-McDowell	Resurfacing	SR 1274 (CATAWBA RIVER ROAD)	SR 1254 (MORRIS HOLLOW ROAD)	DEAD END	1.60	Full Depth Patching and 1.5" S9.5C	$325,000
2026	13	059-McDowell	Resurfacing	SR 1407 (MILL CREEK ROAD)	BEGIN PAVEMENT	BUNCOMBE COUNTY LINE	0.83	Full Depth Patching and 1.5" S9.5C	$168,000
2026	13	059-McDowell	Resurfacing	SR 1407 (MILL CREEK ROAD)	US 70	PAVEMENT CHANGE	2.14	Full Depth Patching and 1.5" S9.5C	$433,000
2026	13	059-McDowell	Resurfacing	SR 1407 (MILL CREEK ROAD)	PAVEMENT CHANGE	BRIDGE	1.61	Full Depth Patching and 1.5" S9.5C	$325,000
2026	13	059-McDowell	Resurfacing	SR 1407 (MILL CREEK ROAD)	BRIDGE	SR 1408 (GRAPHITE ROAD)	1.25	Full Depth Patching and 1.5" S9.5C	$252,000
2026	13	059-McDowell	Resurfacing	SR 1536 (MEMORIAL PARK ROAD)	SR 1548 (WILDLIFE ROAD)	US 70	1.40	Full Depth Patching and 1.5" S9.5C	$284,000
2026	13	059-McDowell	Resurfacing	SR 1536 (MEMORIAL PARK ROAD)	SR 1593 (COBBLESTONE DRIVE)	SR 1548 (WILDLIFE ROAD)	1.61	Full Depth Patching and 1.5" S9.5C	$326,000
2026	13	059-McDowell	Resurfacing	SR 1834 (BOYD ROAD)	SR 1760 (HARMONY GROVE ROAD)	END OF MAINTENANCE	0.42	Full Depth Patching and 1.5" S9.5C	$86,000
2026	13	059-McDowell	Preservation	SR 1144 (HENSLEY ROAD)	SR 1001 (MONTFORD COVE ROAD)	END OF MAINTENANCE	0.57	Full Depth Patching and Double Seal and Fog Seal	$34,260
2026	13	059-McDowell	Preservation	SR 1147 (OLD NEAL ROAD)	SR 1153 (GOOSE CREEK ROAD)	SR 1351 (MUD CUT ROAD)	1.89	Full Depth Patching and Double Seal and Fog Seal	$113,220
2026	13	059-McDowell	Preservation	SR 1149 (WHITE PINE DRIVE)	SR 1337 (EPLEE LANE)	DEAD END	0.39	Full Depth Patching and 1.5" S9.5C	$75,450
2026	13	059-McDowell	Preservation	SR 1169 (STEPPE STREET/ POPLAR DRIVE)	SR 1164 (SHADY LANE)	D OF MAINTENANCE (POPLAR DRI'	0.17	Full Depth Patching and 1.0" S4.75A	$34,355
2026	13	059-McDowell	Preservation	SR 1765 (DEER PARK ROAD)	SR 1760 (HARMONY GROVE ROAD)	SR 1764 (PINNACLE CHURCH ROAD	2.35	Full Depth Patching and Double Seal and Fog Seal	$182,000
2026	13	059-McDowell	Preservation	SR 1796 (MARLOWE ROAD)	NC 226	SR 1794 (OLD GLENWOOD ROAD)	2.14	Full Depth Patching and Double Seal and Fog Seal	$128,400
2026	13	061-Mitchell	Resurfacing	NC 197	SR 1305 (WHITSON BRANCH ROAD)	SR 1313 (MILLER ROAD)	3.96	Full Depth Patching and 1.5" S9.5C	$1,245,600
2026	13	061-Mitchell	Resurfacing	NC 197	SR 1313 (MILLER ROAD)	SR 1349 (PIGEON ROOST ROAD)	1.39	Full Depth Patching and 1.5" S9.5C	$282,000
2026	13	061-Mitchell	Resurfacing	NC 197	SR 1349 (PIGEON ROOST ROAD)	.304 (HUNTDALE ROAD) (+1.038 M	2.00	Full Depth Patching and 1.5" S9.5C	$404,000
2026	13	061-Mitchell	Resurfacing	NC 197	SR 1304 (HUNTDALE ROAD)+1.038 MILES	SR 1350 (FLAT BRANCH ROAD)	1.35	Full Depth Patching and 1.5" S9.5C	$274,000
2026	13	061-Mitchell	Resurfacing	NC 197	SR 1350 (FLAT BRANCH ROAD)	50 (FLAT BRANCH ROAD) + 1.988 M	1.99	Full Depth Patching and 1.5" S9.5C	$402,000
2026	13	061-Mitchell	Resurfacing	NC 197	SR 1350 (FLAT BRANCH ROAD) + 2 MILES	21 (POPLAR CREEK ROAD) + 0.44 M	1.22	Full Depth Patching and 1.5" S9.5C	$195,200
2026	13	061-Mitchell	Resurfacing	SR 1002 (CRABTREE ROAD)	MILE POST 2.0	PAVEMENT CHANGE	1.30	Full Depth Patching and 1.5" S9.5C	$262,000
2026	13	061-Mitchell	Resurfacing	SR 1002 (CRABTREE ROAD)	PAVEMENT CHANGE	1225 (CHESTNUT MOUNTAIN ROA	1.67	Full Depth Patching and 1.5" S9.5C	$338,000
2026	13	061-Mitchell	Resurfacing	SR 1002 (CRABTREE ROAD)	US 19 E	MP 2.0	1.90	Full Depth Patching and 1.5" S9.5C	$404,000
2026	13	061-Mitchell	Preservation	SR 1125 (ALTAPASS CHURCH ROAD)	SR 1121 (ALTAPASS HIGHWAY)	DEAD END	0.83	Full Depth Patching and Double Seal and Fog Seal	$49,800
2026	13	061-Mitchell	Preservation	SR 1219 (NORA LANE)	SR 1211 (CANE CREEK ROAD)	END OF MAINTENANCE	0.71	Full Depth Patching and Double Seal and Fog Seal	$42,660
2026	13	061-Mitchell	Preservation	SR 1238 (WALT CARPENTER ROAD)	SR 1128 (HUMPBACK MOUNTAIN ROAD)	END OF MAINTENANCE	0.39	Full Depth Patching and Double Seal and Fog Seal	$23,400
2026	13	061-Mitchell	Preservation	SR 1262 (WALNUT STRAIGHT ROAD)	SR 1121 (ALTAPASS HIGHWAY)	END OF MAINTENANCE	0.10	Full Depth Patching and Double Seal and Fog Seal	$6,000
2026	13	061-Mitchell	Preservation	SR 1283 (BERRY HILL ROAD)	US 19 E	END OF MAINTENANCE	0.21	Full Depth Patching and Double Seal and Fog Seal	$12,600
2026	13	061-Mitchell	Preservation	SR 1284 (BARNEY MKINNEY ROAD)	SR 1114 (HALLTOWN ROAD)	END OF PAVEMENT	0.09	Full Depth Patching and Double Seal and Fog Seal	$5,400
2026	13	061-Mitchell	Preservation	SR 1303 (JOHN SPARKS ROAD)	NC 226	END OF MAINTENANCE	0.68	Full Depth Patching and Double Seal and Fog Seal	$43,200
2026	13	061-Mitchell	Preservation	SR 1315 (RELIEF ROAD EXT)	SR 1314 (NO NAME ON MAP)	END OF MAINTENANCE	0.14	Full Depth Patching and Double Seal and Fog Seal	$8,520
2026	13	081-Rutherford	Resurfacing	SR 1001 (COVE ROAD)	SR 1332 (PADGETT ROAD)	SR 1331 (PINEY KNOB ROAD)	1.20	Full Depth Patching and 1.5" S9.5C	$234,344
2026	13	081-Rutherford	Resurfacing	SR 1001 (COVE ROAD)	SR 1351 (DARLINGTON ROAD)	US 64	0.96	Full Depth Patching and 1.5" S9.5C	$199,899
2026	13	081-Rutherford	Resurfacing	SR 1001 (COVE ROAD)	SR 1331 (PINEY KNOB ROAD)	SR 1345 (PLEASANT GROVE ROAD)	1.67	Full Depth Patching and 1.5" S9.5C	$334,599
2026	13	081-Rutherford	Resurfacing	SR 1163 (PIEDMONT ROAD)	SR 1164 (NEW HOPE ROAD)	SR 1168 (SILVERPLATE GRILL ROAD	1.60	Full Depth Patching and 1.5" S9.5C	$357,899
2026	13	081-Rutherford	Resurfacing	SR 1163 (PIEDMONT ROAD)	NC 108	SR 1164 (NEW HOPE ROAD)	0.52	Full Depth Patching and 1.5" S9.5C	$102,430
2026	13	081-Rutherford	Resurfacing	SR 1187 (CAMP HILL ROAD)	SR 1186 (GIRL SCOUT CAMP ROAD)	END OF MAINTENANCE	0.73	Full Depth Patching and 1.25" S9.5B	$149,850
2026	13	081-Rutherford	Resurfacing	SR 1188 (NELONS ROAD)	SR 1186 (GIRL SCOUT CAMP ROAD)	END OF MAINTENANCE	0.67	Full Depth Patching and 1.25" S9.5B	$136,000
2026	13	081-Rutherford	Resurfacing	SR 1322 (BOBBY MCKINNEY ROAD)	SR 1321 (THERMAL CITY ROAD)	END OF MAINTENANCE	0.50	Full Depth Patching and 1.25" S9.5B	$102,000
2026	13	081-Rutherford	Resurfacing	SR 1328 (PAINTERS GAP ROAD)	US 221	SR 1362 (GILKEY SCHOOL ROAD)	0.26	Full Depth Patching and 1.5" S9.5C	$53,000
2026	13	081-Rutherford	Resurfacing	SR 1328 (PAINTERS GAP ROAD)	SR 1362 (GILKEY SCHOOL ROAD)	SR 1329 (BROOKS LAKE ROAD)	1.60	Full Depth Patching and 1.5" S9.5C	$357,972
2026	13	081-Rutherford	Resurfacing	SR 1328 (PAINTERS GAP ROAD)	SR 1319 (HEMPHILL ROAD)	SR 1001 (COVE ROAD)	0.57	Full Depth Patching and 1.5" S9.5C	$109,099
2026	13	081-Rutherford	Resurfacing	SR 1328 (PAINTERS GAP ROAD)	MP 7.437	SR 1319 (HEMPHILL ROAD)	2.37	Full Depth Patching and 1.5" S9.5C	$445,999
2026	13	081-Rutherford	Resurfacing	SR 1328 (PAINTERS GAP ROAD)	SR 1329 (BROOKS LAKE ROAD)	SR 1327 (HORN MILL ROAD)	0.81	Full Depth Patching and 1.5" S9.5C	$175,779
2026	13	081-Rutherford	Resurfacing	SR 1328 (PAINTERS GAP ROAD)	SR 1325 (NANNEYTOWN ROAD)	PAVEMENT CHANGE	0.76	Full Depth Patching and 1.5" S9.5C	$157,785
2026	13	081-Rutherford	Resurfacing	SR 1328 (PAINTERS GAP ROAD)	PAVEMENT CHANGE	MP 7.437	1.30	Full Depth Patching and 1.5" S9.5C	$243,399

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	13	081-Rutherford	Resurfacing	SR 1328 (PAINTERS GAP ROAD)	SR 1327 (HORN MILL ROAD)	SR1332 (PADGETT ROAD)	1.43	Full Depth Patching and 1.5" S9.5C	$298,789
2026	13	081-Rutherford	Resurfacing	SR 1328 (PAINTERS GAP ROAD)	SR 1332 (PADGETT ROAD)	SR 1325 (NANNYTOWN ROAD)	1.28	Full Depth Patching and 1.5" S9.5C	$233,455
2026	13	081-Rutherford	Resurfacing	SR 1351 (DARLINGTON ROAD)	PAVEMENT CHANGE	SR 1329 (BROOKS LAKE ROAD)	0.65	Full Depth Patching and 1.5" S9.5C	$134,450
2026	13	081-Rutherford	Resurfacing	SR 1351 (DARLINGTON ROAD)	SR 1329 (BROOKS LAKE ROAD)	SR 1355 (MOUNTAIN CREEK ROAD)	1.55	Full Depth Patching and 1.5" S9.5C	$299,876
2026	13	081-Rutherford	Resurfacing	SR 1351 (DARLINGTON ROAD)	SR 1001 (COVE ROAD)	BRIDGE	1.07	Full Depth Patching and 1.5" S9.5C	$201,250
2026	13	081-Rutherford	Resurfacing	SR 1351 (DARLINGTON ROAD)	BRIDGE	PAVEMENT CHANGE	1.53	Full Depth Patching and 1.5" S9.5C	$302,225
2026	13	081-Rutherford	Resurfacing	SR 1367 (THOMPSON ROAD)	US 64	US 221	1.39	Full Depth Patching and 1.5" S9.5C	$299,899
2026	13	081-Rutherford	Resurfacing	SR 1371 (ANTIOCH ROAD)	SR 1008 (BILLS CREEK ROAD)	SR 1008 (BILLS CREEK ROAD)	1.47	Full Depth Patching and 1.5" S9.5C	$245,670
2026	13	081-Rutherford	Resurfacing	SR 1373 (MOGENE ROAD)	SR 1355 (MOUNTAIN CREEK ROAD)	SR 1355 (MOUNTAIN CREEK ROAD)	0.25	Full Depth Patching and 1.5" S9.5C	$51,000
2026	13	081-Rutherford	Resurfacing	SR 1375 (EDGERTON ROAD)	SR 1008 (BILLS CREEK ROAD)	DEAD END	0.14	Full Depth Patching and 1.25" S9.5B	$15,650
2026	13	081-Rutherford	Resurfacing	SR 1379 (HALL ROAD)	SR 1331 (PINEY KNOB ROAD)	DEAD END	0.31	Full Depth Patching and 1.25" S9.5B	$63,000
2026	13	081-Rutherford	Resurfacing	SR 1385 (ATCHLEY ROAD)	SR 1332 (PADGETT ROAD)	END MAINTENANCE	0.62	Full Depth Patching and 1.25" S9.5B	$67,899
2026	13	081-Rutherford	Resurfacing	SR 1392 (WT WILKINS ROAD)	US 64	CUL DE SAC	0.47	Full Depth Patching and 1.25" S9.5B	$55,645
2026	13	081-Rutherford	Resurfacing	US221 (EAST MAIN STREET)	SR 1591 (LEDBETTER ROAD)	US221 (SOUTH MAIN STREET)	2.40	Full Depth Patching and 1.25" S9.5B	$485,000
2026	13	081-Rutherford	Preservation	SR 1505 (OWENS CHAPEL ROAD)	SR 1501 (CONEY ISLAND ROAD)	SR 1508 (OLD UNION MILLS ROAD)	1.70	Full Depth Patching and Double Seal and Fog Seal	$129,999
2026	13	081-Rutherford	Preservation	SR 1506 (FERGUSON RIDGE ROAD)	SR 1505 (OWENS CHAPEL ROAD)	PAVEMENT CHANGE	0.08	Full Depth Patching and Double Seal and Fog Seal	$4,640
2026	13	081-Rutherford	Preservation	508 (OWENS CHAPEL/OLD UNION MILLS R	US 221	US 221	0.41	Full Depth Patching and Double Seal and Fog Seal	$23,780
2026	13	081-Rutherford	Preservation	SR 1526 (GILMER EDWARDS ROAD)	SR 1527 (OAK SPRINGS ROAD)	SR 1533 (CHILLY BOWL ROAD)	1.18	Full Depth Patching and Double Seal and Fog Seal	$87,824
2026	13	081-Rutherford	Preservation	SR 1526 (GILMER EDWARDS ROAD)	SR 1533 (CHILLY BOWL ROAD)	SR 1532 (GILBOA CHURCH ROAD)	1.65	Full Depth Patching and Double Seal and Fog Seal	$102,355
2026	13	081-Rutherford	Preservation	SR 1532 (GILBOA CHURCH ROAD)	SR 1366 (ROPER LOOP ROAD)	US 221	0.57	Full Depth Patching and Double Seal and Fog Seal	$33,060
2026	13	081-Rutherford	Preservation	SR 1532 (GILBOA CHURCH ROAD)	US 221	SR 1366 (ROPER LOOP ROAD)	1.52	Full Depth Patching and Double Seal and Fog Seal	$102,455
2026	13	081-Rutherford	Preservation	SR 1533 (CHILLY BOWL ROAD)	SR 1532 (GILBOA CHURCH ROAD)	SR 1526 (GILMER EDWARDS ROAD)	1.25	Full Depth Patching and Double Seal and Fog Seal	$72,500
2026	13	081-Rutherford	Preservation	SR 1550 (LEE ROAD)	SR 1510 (HUDLOW ROAD)	SR 1549 (ROCK CORNER ROAD)	1.35	Full Depth Patching and Double Seal and Fog Seal	$78,300
2026	13	081-Rutherford	Preservation	SR 1558 (MACKEY FREEMAN ROAD)	SR 1559 (FREEMAN ROAD)	US 64	1.53	Full Depth Patching and Double Seal and Fog Seal	$88,392
2026	13	081-Rutherford	Preservation	SR 1558 MACKEY FREEMAN ROAD)	SR 1007 (PEARIDGE ROAD)	SR 1559 (FREEMAN ROAD)	0.58	Full Depth Patching and Double Seal and Fog Seal	$33,698
2026	13	081-Rutherford	Preservation	SR 1559 (FREEMAN ROAD)	SR 1558 (MACKEY FREEMAN ROAD)	SR 1538 (WHITESIDES ROAD)	2.37	Full Depth Patching and Double Seal and Fog Seal	$137,460
2026	13	081-Rutherford	Preservation	SR 1565 (GUN CLUB ROAD)	SR 1006 (BOSTIC SUNSHINE HIGHWAY)	SR 1563 (ROBINSONS CREEK ROAD)	0.96	Full Depth Patching and Double Seal and Fog Seal	$55,680
2026	13	081-Rutherford	Preservation	SR 1565 (GUN CLUB ROAD)	SR 1563 (ROBINSON CREEK ROAD)	1006 (BOSTIC SUNSHINE HIGHWA	0.82	Full Depth Patching and Double Seal and Fog Seal	$47,560
2026	13	081-Rutherford	Preservation	SR 1709 (WALKER DAIRY ROAD)	SR 1796 (ENGINEER ROAD)	SR 1712 (JOE BOSTIC ROAD)	1.51	Seal - Double and Fog Seal	$56,799
2026	13	081-Rutherford	Preservation	SR 1721 (WATERS ROAD)	SR 1720 (TONEY ROAD)	SR 1713 (DEPRIEST ROAD)	1.80	Seal - Double and Fog Seal	$48,995
2026	13	100-Yancey	Resurfacing	NC 80	SR 1152 (BLUE ROCK ROAD)	US 19	4.10	Full Depth Patching and 1.5" S9.5C	$528,000
2026	13	100-Yancey	Resurfacing	SR 1154 (UPPER BROWNS CREEK ROAD)	NC 80S	END OF PAVEMENT	1.41	Full Depth Patching and 1.5" S9.5C	$267,850
2026	13	100-Yancey	Resurfacing	SR 1167 (SEVEN MILE RIDGE ROAD)	SR 1166 (HICKORY HILL ROAD)	MITCHELL COUNTY LINE	2.72	Full Depth Patching and 1.5" S9.5C	$408,000
2026	13	100-Yancey	Resurfacing	SR 1169 (HALLS CHAPEL ROAD)	SR 1167 (SEVEN MILE RIDGE ROAD)	SR 1152 (BLUE ROCK ROAD)	4.05	Full Depth Patching and 1.5" S9.5C	$678,995
2026	13	100-Yancey	Resurfacing	US 19E	BRIDGE ABUTMENT (BRIDGE 009)	SR 1196 (CRESTVIEW ROAD)	0.80	Full Depth Patching and 1.5" S9.5C	$444,699
2026	13	100-Yancey	Resurfacing	US 19E	SR 1196 (CRESTVIEW ROAD)	BRIDGE 009 ABUTMENT	0.80	Full Depth Patching and 1.5" S9.5C	$322,250
2026	13	100-Yancey	Preservation	SR 1155 (WHITE OAK ROAD) (UPPER)	NC 80 S	SR 1156 (SHUFORD CREEK ROAD)	1.71	Full Depth Patching and Double Seal and Fog Seal	$128,000
2026	13	100-Yancey	Preservation	56 (WHITE OAK ROAD / SHUFORD CREEK R	SR 1157 (WHITE OAK ROAD)	END OF PAVEMENT	1.34	Full Depth Patching and Double Seal and Fog Seal	$100,500
2026	13	100-Yancey	Preservation	57 (WHITE OAK ROAD/ WHITE OAK CREEK I	NC 80 S	OF PAVEMENT IS .13MI MORE THAI	1.92	Full Depth Patching and Double Seal and Fog Seal	$144,000
2026	13	100-Yancey	Preservation	SR 1164 (DOVERS BRANCH ROAD)	NC 80S	END OF PAVEMENT	0.60	Full Depth Patching and Double Seal and Fog Seal	$50,000
2026	13	100-Yancey	Preservation	SR 1170 (LOWER BROWNS CREEK ROAD)	SR 1154 (GRINDSTAFF ROAD)	END OF PAVEMENT	0.86	Full Depth Patching and Double Seal and Fog Seal	$73,000
2026	13	100-Yancey	Preservation	SR 1199 (CLEAR CREEK ROAD)	NC 80 S	END OF PAVEMENT	0.72	Full Depth Patching and Double Seal and Fog Seal	$54,000
2026	13	100-Yancey	Preservation	SR 1206 (RHODODENDRON PARK)	SR 1157 (WHITE OAK ROAD)	END OF MAINTENANCE	0.40	Full Depth Patching and Double Seal and Fog Seal	$34,000
2026	13	100-Yancey	Preservation	SR 1209 (STILL FORK ROAD)	NC 80 S	END OF MAINTENANCE	0.55	Full Depth Patching and Double Seal and Fog Seal	$41,250
2026	14	020-Cherokee	Resurfacing	SR 1326	SR 1331	SR 1358	5.75	1.25" SF9.5A	$1,581,250
2026	14	020-Cherokee	Resurfacing	SR 1554	SR 1555	SR 1651	1.33	1.25" SF9.5A	$365,750
2026	14	020-Cherokee	Resurfacing	SR 1555	Hendrix Rd SR 1531	SR 1554	2.08	1.25" SF9.5A	$572,000
2026	14	020-Cherokee	Resurfacing	SR 1651	SR 1554	US 19 East	0.17	1.25" SF9.5A	$46,750
2026	14	020-Cherokee	Preservation	SR 1352	SR 1351	EOP	1.10	Seal - Double and Fog Seal	$77,000
2026	14	020-Cherokee	Preservation	SR 1374	US 19	SR 1428	1.77	Seal - Double and Split Seal	$123,900
2026	14	020-Cherokee	Preservation	SR 1447	SR 1326	EOM	1.89	Seal - Double and Fog Seal	$132,230
2026	14	020-Cherokee	Preservation	SR 1507	SR 1516	SR 1388	1.78	Seal - Double and Fog Seal	$124,600
2026	14	020-Cherokee	Preservation	SR 1514	SR 1513	EOM	0.69	Seal - Double and Fog Seal	$48,300
2026	14	020-Cherokee	Preservation	SR 1542	NC 141	EOM	0.53	Seal - Double and Fog Seal	$37,100
2026	14	020-Cherokee	Preservation	SR 1547	US 64	EOM	0.56	Seal - Double and Fog Seal	$39,200
2026	14	020-Cherokee	Preservation	SR 1573	SR 1556	SR 1564	1.49	Seal - Double and Fog Seal	$104,300
2026	14	020-Cherokee	Preservation	SR 1608	SR 1501	EOM	0.43	Seal - Double and Fog Seal	$30,100
2026	14	022-Clay	Resurfacing	SR 1112	SR 1100	Georgia State Line	0.59	1.5" S9.5B	$161,975
2026	14	022-Clay	Resurfacing	SR 1300	SR 1319	SR 1307	1.19	Leveling and 1.5" S9.5B	$327,250

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	14	022-Clay	Preservation	Barnard Rd.	SR 1141	US 64	1.04	Seal - Double and Fog Seal	$72,800
2026	14	022-Clay	Preservation	Lawerence Smith Rd.	SR 1325	SR 1325	1.61	Seal - Double and Fog Seal	$112,700
2026	14	022-Clay	Preservation	Swaims Rd	SR 1140	US 64	1.61	Seal - Double and Fog Seal	$112,700
2026	14	038-Graham	Resurfacing	SR 1265	1277	EOM	0.21	1.25" S9.5B	$57,750
2026	14	038-Graham	Resurfacing	SR 1277	NC 143	NC 143	1.99	1.25" S9.5B	$547,250
2026	14	038-Graham	Preservation	SR 1138	US 129	US 129	1.77	Seal - Double and Fog Seal	$124,180
2026	14	038-Graham	Preservation	SR 1249	Sr 1242	SR 1247	4.33	Seal - Double and Fog Seal	$302,890
2026	14	038-Graham	Preservation	SR 1254	SR 1144	EOM	1.41	Seal - Double and Fog Seal	$98,700
2026	14	044-Haywood	Resurfacing	SR 1355	SR 1338	NC 209	7.95	Full Depth Patching and 1.5" S9.5B and Widening	$2,500,000
2026	14	044-Haywood	Resurfacing	SR 1364	SR 1363	NC 209	1.19	Full Depth Patching and 1.5" S9.5B	$326,425
2026	14	044-Haywood	Resurfacing	US 19	SR 1307 (Moody Farm Rd)	End of divided hwy	4.02	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$7,000,000
2026	14	044-Haywood	Preservation	SR 1238	SR 1239	Dead End	0.23	Seal - Double and Fog Seal	$16,310
2026	14	044-Haywood	Preservation	SR 1262	SR 1264	SR 1263	0.13	Seal - Double and Fog Seal	$9,100
2026	14	044-Haywood	Preservation	SR 1310	US 276	EOP	0.72	Seal - Double and Fog Seal	$50,120
2026	14	044-Haywood	Preservation	SR 1312	US 276	EOP	0.19	Seal - Double and Fog Seal	$13,160
2026	14	044-Haywood	Preservation	SR 1316	SR 1318	EOP	0.99	Seal - Double and Fog Seal	$69,090
2026	14	044-Haywood	Preservation	SR 1318	SR 1321	SR 1313	0.85	Seal - Double and Fog Seal	$59,710
2026	14	044-Haywood	Preservation	SR 1319	SR 1318	EOP	0.91	Seal - Double and Fog Seal	$63,420
2026	14	044-Haywood	Preservation	SR 1321	US 276	SR 1318	0.30	Seal - Double and Fog Seal	$21,000
2026	14	044-Haywood	Preservation	SR 1323	SR 1322	EOP	0.27	Seal - Double and Fog Seal	$19,040
2026	14	044-Haywood	Preservation	SR 1324	US 276	EOP	0.40	Seal - Double and Fog Seal	$28,000
2026	14	044-Haywood	Preservation	SR 1326	US 276	SR 1395	1.00	Seal - Double and Fog Seal	$70,280
2026	14	044-Haywood	Preservation	SR 1387	US 276	EOP	0.31	Seal - Double and Fog Seal	$21,700
2026	14	044-Haywood	Preservation	SR 1389	SR 1309	END MAINT	0.70	Seal - Double and Fog Seal	$48,860
2026	14	044-Haywood	Preservation	SR 1391	US 19	SR 1392	0.13	Seal - Double and Fog Seal	$9,100
2026	14	044-Haywood	Preservation	SR 1549	SR 1513	DEAD END	0.72	Seal - Double and Fog Seal	$50,190
2026	14	044-Haywood	Preservation	SR 1820	SR 1523	SR 1819	0.72	Seal - Double and Fog Seal	$50,400
2026	14	044-Haywood	Preservation	SR 1848	SR 1847	EOM	0.11	Seal - Double and Fog Seal	$7,700
2026	14	044-Haywood	Preservation	SR 1863	SR 1871	EOM	0.61	Seal - Double and Fog Seal	$42,490
2026	14	044-Haywood	Preservation	SR 1913	SR 1818	DEAD END	0.19	Seal - Double and Fog Seal	$13,370
2026	14	044-Haywood	Preservation	SR 1947	SR 1922	DEAD END	0.04	Seal - Double and Fog Seal	$2,800
2026	14	045-Henderson	Resurfacing	SR 1338	NC 280	EOM	5.24	Full Depth Patching and 1.5" S9.5B	$1,440,450
2026	14	045-Henderson	Resurfacing	SR 1348	SR 1345	SR 3492	2.89	1.5" S9.5B	$794,750
2026	14	045-Henderson	Resurfacing	SR 1349	SR 1348	NC 191	1.01	2.0" S9.5B	$277,475
2026	14	045-Henderson	Resurfacing	SR 1372	US 25 Bus	EOM	1.01	Mill 1.5" and 1.5" S9.5B	$277,750
2026	14	045-Henderson	Resurfacing	SR 1419	NC 191	SR 3526	1.85	1.5" S9.5B	$508,750
2026	14	045-Henderson	Resurfacing	SR 1582	SR 1574	SR 1622	1.77	1.25" S9.5B	$486,750
2026	14	045-Henderson	Resurfacing	SR 1591	SR 1572	SR 1602	4.19	1.25" S9.5B	$1,152,800
2026	14	045-Henderson	Resurfacing	SR 1622	SR 1006	SR 1583	1.03	1.25" S9.5B	$283,250
2026	14	045-Henderson	Resurfacing	SR 1749	0.03 SR 1749	SR 1847	0.71	Leveling and 1.5" S9.5B	$195,250
2026	14	045-Henderson	Resurfacing	SR 1779	0.11 SR 1779	US 176	0.63	1.25" S9.5B	$173,250
2026	14	045-Henderson	Resurfacing	SR 2237	SR 1351	EOM	0.19	Full Depth Patching and 1.5" S9.5C	$51,425
2026	14	045-Henderson	Resurfacing	US 176	NC 225/US25	SR 1783 N.HighlandLk	2.18	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,000,000
2026	14	045-Henderson	Resurfacing	US 25	Bridge #169	SR 1534 Naples Rd	0.58	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$500,000
2026	14	045-Henderson	Resurfacing	US 25	Maxwell Dr + 0.03	Bridge #216	1.60	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,000,000
2026	14	045-Henderson	Resurfacing	US 64	Bridge # 57	SR 1186	5.71	Full Depth Patching and 1.5" S9.5C	$2,000,000
2026	14	045-Henderson	Preservation	SR 1565	SR 1553	SR 1569	4.49	Seal - Double and Fog Seal	$143,648
2026	14	045-Henderson	Preservation	SR 1569	SR 1565	SR 1595	7.19	Seal - Double and Fog Seal	$230,080
2026	14	045-Henderson	Preservation	SR 1572	SR 1575	SR 1591	4.70	Seal - Double and Fog Seal	$150,400
2026	14	045-Henderson	Preservation	SR 1573	SR 1565	EOP	0.42	Seal - Double and Fog Seal	$13,440
2026	14	045-Henderson	Preservation	SR 1575	SR 1586	SR 1572	0.90	Seal - Double and Fog Seal	$28,800
2026	14	045-Henderson	Preservation	SR 1587	SR 1586	SR 1591	2.69	Seal - Double and Fog Seal	$85,984
2026	14	045-Henderson	Preservation	SR 1595	SR 1569	EOM	1.00	Seal - Double and Fog Seal	$32,000
2026	14	045-Henderson	Preservation	SR 1598	US 74A	EOM	0.30	Seal - Double and Fog Seal	$9,600
2026	14	045-Henderson	Preservation	SR 1612	SR 1613	EOM	0.56	Seal - Double and Fog Seal	$17,920
2026	14	045-Henderson	Preservation	SR 1613	US 64	SR 1602	1.78	Seal - Double and Fog Seal	$57,024
2026	14	045-Henderson	Preservation	SR 1616	SR 1602	SR 1614	0.76	Seal - Double and Fog Seal	$24,320
2026	14	045-Henderson	Preservation	SR 1649	SR 1551	EOM	0.45	Seal - Mat and Triple Seal	$14,368
2026	14	045-Henderson	Preservation	SR 1702	US 64	EOP	0.80	Seal - Double and Fog Seal	$25,600

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	14	045-Henderson	Preservation	SR 1861	SR 1783	SR 1724	1.22	Seal - Double and Fog Seal	$39,040
2026	14	050-Jackson	Resurfacing	SR 1002	NC 107	SR 1732	3.12	1.5" S9.5B	$858,000
2026	14	050-Jackson	Resurfacing	SR 1377	EOP	US 441 South	2.22	Full Depth Patching and 1.25" S9.5B	$610,500
2026	14	050-Jackson	Resurfacing	SR 1397	SR 1534	SR 1395	0.90	Full Depth Patching and 1.0" S4.75A	$247,500
2026	14	050-Jackson	Resurfacing	SR 1397	Swain County Line	SR 1566	0.53	1.25" S9.5B	$145,750
2026	14	050-Jackson	Preservation	SR 1303	SR 1300	EOM	0.65	Seal - Double and Fog Seal	$45,500
2026	14	050-Jackson	Preservation	SR 1339	SR 1340	SR 1340	0.73	Seal - Double and Fog Seal	$51,100
2026	14	050-Jackson	Preservation	SR 1386	US 23	EOM	1.06	Seal - Double and Fog Seal	$74,200
2026	14	050-Jackson	Preservation	SR 1473	SR 1377	EOM	0.70	Seal - Double and Fog Seal	$49,000
2026	14	050-Jackson	Preservation	SR 1495	NC 116	EOP	0.21	Seal - Double and Fog Seal	$14,700
2026	14	050-Jackson	Preservation	SR 1551	SR 1367	EOP	1.03	Seal - Double and Fog Seal	$71,960
2026	14	050-Jackson	Preservation	SR 1574	SR 1339	SR 1577	0.52	Seal - Double and Fog Seal	$36,400
2026	14	050-Jackson	Preservation	SR 1577	SR 1574	EOM	0.86	Seal - Double and Fog Seal	$60,200
2026	14	050-Jackson	Preservation	SR 1578	US 441	EOM	0.25	Seal - Double and Fog Seal	$17,500
2026	14	050-Jackson	Preservation	SR 1734	SR 1002	EOM	0.22	Seal - Double and Fog Seal	$15,400
2026	14	050-Jackson	Preservation	SR 1774	SR 1586	EOM	0.15	Seal - Double and Fog Seal	$10,500
2026	14	050-Jackson	Preservation	SR 1778	SR 1002	EOM	0.22	Seal - Double and Fog Seal	$15,400
2026	14	050-Jackson	Preservation	SR 1787	SR 1728	EOM	0.40	Seal - Double and Fog Seal	$28,000
2026	14	050-Jackson	Preservation	SR 1790	NC 107	EOM	0.26	Seal - Double and Fog Seal	$17,850
2026	14	050-Jackson	Preservation	SR 1796	SR 1778	EOM	0.15	Seal - Double and Fog Seal	$10,500
2026	14	056-Macon	Resurfacing	SR 1538	SR 1537	SR 1558	2.26	Full Depth Patching and 1.25" S9.5B	$621,500
2026	14	056-Macon	Resurfacing	SR 1644	US 441	SR 1653	0.49	Full Depth Patching and 1.25" S9.5B	$134,750
2026	14	056-Macon	Resurfacing	SR 1674	SR 1697	SR 1674	1.52	Full Depth Patching and 1.25" S9.5B	$418,000
2026	14	056-Macon	Resurfacing	US 64	US 64	US 64/JCL	2.80	Full Depth Patching and 1.25" S9.5B	$2,000,000
2026	14	056-Macon	Preservation	SR 1402	SR 1402	To end of pavement on SR 1402	1.34	Seal - Double and Fog Seal	$93,800
2026	14	056-Macon	Preservation	SR 1404	SR 1397	SR 1310	2.88	Seal - Double and Fog Seal	$201,600
2026	14	056-Macon	Preservation	SR 1412	SR 1310	SR 1412	0.34	Seal - Double and Fog Seal	$23,800
2026	14	056-Macon	Preservation	SR 1414	SR 1412	SR 1414	2.14	Seal - Double and Fog Seal	$149,800
2026	14	056-Macon	Preservation	SR 1457	County Line SR 1457	End of pavement 1457	1.98	Seal - Double and Fog Seal	$138,600
2026	14	075-Polk	Resurfacing	SR 1142	SR 1181	SR 1151	0.54	Full Depth Patching and 1.25" S9.5B	$162,000
2026	14	075-Polk	Resurfacing	SR 1181	US 176	SR 1142	0.74	Full Depth Patching and 1.25" S9.5B	$222,000
2026	14	075-Polk	Resurfacing	SR 1531	NC 108	US 74 Overpass	2.01	Patching and 1.5" S9.5A	$603,000
2026	14	075-Polk	Preservation	SR 1100	Henderson Co. Line	SR 1102	4.13	Seal - Double and Fog Seal	$132,160
2026	14	075-Polk	Preservation	SR 1101	SR 1100	Henderson Co. Line	1.63	Seal - Double and Fog Seal	$52,192
2026	14	075-Polk	Preservation	SR 1169	SR 1100	EOM	0.43	Seal - Double and Fog Seal	$13,760
2026	14	075-Polk	Preservation	SR 1314	SR 1311	SR 1313	1.81	Seal - Double and Fog Seal	$57,920
2026	14	075-Polk	Preservation	SR 1504	SR 1502	EOM	0.45	Seal - Double and Fog Seal	$14,400
2026	14	075-Polk	Preservation	SR 1519	SR 1520	SC Line	1.90	Seal - Double and Fog Seal	$60,800
2026	14	075-Polk	Preservation	SR 1536	NC 9	SR 1521	1.37	Seal - Double and Fog Seal	$43,840
2026	14	075-Polk	Preservation	SR 1539	SR 1521	SR 1521	1.97	Seal - Double and Fog Seal	$63,040
2026	14	087-Swain	Resurfacing	SR 1114	SR 1113	EOP	1.05	Patching and 1.5" S9.5A	$288,750
2026	14	087-Swain	Resurfacing	SR 1312	SR 1314	SR 1311	1.15	1.5" S9.5B	$317,350
2026	14	087-Swain	Resurfacing	SR 1323	SR 1328	SR 1322	0.90	1.5" S9.5B	$248,050
2026	14	087-Swain	Resurfacing	US 19	SR 1364 (Everett St)	SR 1336 (Old River Rd)	2.12	Full Depth Patching and 1.5" S9.5C	$1,000,000
2026	14	087-Swain	Preservation	SR 1103	US 19	EOP	2.50	Seal - Double and Fog Seal	$175,000
2026	14	087-Swain	Preservation	SR 1172	SR 1173	Dead End	0.70	Seal - Double and Fog Seal	$49,000
2026	14	087-Swain	Preservation	SR 1312	SR 1314	SR 1311	1.15	Seal - Double and Fog Seal	$80,780
2026	14	088-Transylvania	Resurfacing	SR 1130	sr1107	EOM	0.35	1.5" S9.5B	$96,250
2026	14	088-Transylvania	Resurfacing	SR 1309	sr1313	us 64	0.64	1.5" S9.5B	$176,000
2026	14	088-Transylvania	Resurfacing	SR 1541	sr1540	pavement change	0.76	1.5" S9.5B	$209,000
2026	14	088-Transylvania	Resurfacing	SR1528	US 64	Hend. Co. Line	4.09	Full Depth Patching and 1.5" S9.5C	$1,250,000
2026	14	088-Transylvania	Resurfacing	US 64	SR 1135	Pvmt Change @ SR 1329	2.39	Full Depth Patching and 1.5" S9.5C	$2,000,000
2026	14	088-Transylvania	Preservation	SR 1135	NC 178	US 64	0.98	Seal - Double and Fog Seal	$31,360
2026	14	088-Transylvania	Preservation	SR 1178	SR 1124	Dead End	0.09	Seal - Double and Fog Seal	$2,880
2026	14	088-Transylvania	Preservation	SR 1181	SR 1164	SR 1115	0.44	Seal - Double and Fog Seal	$13,920
2026	14	088-Transylvania	Preservation	SR 1187	SR 1181	SR 1186	0.17	Seal - Double and Fog Seal	$5,408
2026	14	088-Transylvania	Preservation	SR 1190	US 64	Dead End	0.22	Seal - Double and Fog Seal	$7,040
2026	14	088-Transylvania	Preservation	SR 1201	SR 1110	SR 1110	0.56	Seal - Double and Fog Seal	$17,888
2026	14	088-Transylvania	Preservation	SR 1208	US 64	SR 1123	0.48	Seal - Double and Fog Seal	$15,360

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2026	14	088-Transylvania	Preservation	SR 1324	SR 1325	JACKSON CL	4.50	Seal - Double and Fog Seal	$144,128
2026	14	088-Transylvania	Preservation	SR 1344	US 64	WCL Brevard	1.92	Seal - Double and Fog Seal	$61,344
2026	14	088-Transylvania	Preservation	SR 1347	US 64	SCL BREVARD	0.20	Seal - Double and Fog Seal	$6,368
2026	14	088-Transylvania	Preservation	SR 1541	PVMT CHNG	SR 1609	0.33	Seal - Double and Fog Seal	$10,560
2026	14	088-Transylvania	Preservation	SR 1609	SR 1541	SR 1541	1.83	Seal - Double and Fog Seal	$58,560
2027	1	008-Bertie	Resurfacing	NC 308	US 17	NC 11	14.99	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$4,370,000
2027	1	008-Bertie	Resurfacing	SR 1120 (Thompson Dr.)	SR 1119	NC 308	0.81	Full Depth Patching and 1.5" S9.5B	$165,000
2027	1	008-Bertie	Resurfacing	SR 1200 (Hexlena Rd.)	SR 1228	US 13	4.38	Full Depth Patching and 1.5" S9.5B	$870,000
2027	1	008-Bertie	Resurfacing	SR 1257 (School Rd.)	SR 1260	Begin 24' Pavement	1.57	Full Depth Patching and 1.5" S9.5B	$380,000
2027	1	008-Bertie	Resurfacing	SR 1257 (School Rd.)	Begin 24' Pavement	US 13	0.20	Full Depth Patching and 1.5" S9.5B	$75,000
2027	1	008-Bertie	Resurfacing	SR 1257 (School Rd.)	NC 308	SR 1260	1.07	Full Depth Patching and 1.5" S9.5B	$260,000
2027	1	008-Bertie	Resurfacing	SR 1308 (Polly Rd.)	End Pavement	SR 1304	0.84	Full Depth Patching and 1.5" S9.5B	$170,000
2027	1	008-Bertie	Resurfacing	SR 1314 (Nowell Farm Rd.)	NC 42	SR 1342	3.05	Full Depth Patching and 1.5" S9.5B	$605,000
2027	1	008-Bertie	Resurfacing	SR 1343 (Pocosin Rd.)	SR 1349	SR 1304	2.25	Full Depth Patching and 1.5" S9.5B	$450,000
2027	1	008-Bertie	Resurfacing	SR 1500 (Sans Souci Rd.)	SR 1549	NC 45	2.81	Full Depth Patching and 1.5" S9.5B	$560,000
2027	1	008-Bertie	Resurfacing	US 13	avement Joint South of SR 1321 (S. Commerce S	Hertford County Line	1.50	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$457,000
2027	1	008-Bertie	Resurfacing	US 13	SR 1221 (Charles Taylor Rd.)	SR 1228 (Earley Station Rd.)	0.84	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$276,000
2027	1	008-Bertie	Resurfacing	US 13	NC 305	SR 1221 (Charles Taylor Rd.)	2.07	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$681,000
2027	1	008-Bertie	Resurfacing	US 13	SR 1257 (School Rd.)	NC 305	2.11	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$694,000
2027	1	008-Bertie	Resurfacing	US 17 Bus.	US 13	NC 308	2.21	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$778,000
2027	1	008-Bertie	Preservation	SR 1115 (Pritchard Farm Rd.)	Dead End	NC 308	1.01	Seal - Double	$46,000
2027	1	008-Bertie	Preservation	SR 1205 (AC Smith Rd.)	NC 308	SR 1208 (Church Street Ext.)	1.02	1.25" S9.5B	$124,000
2027	1	008-Bertie	Preservation	SR 1251 (Railroad Street)	Roxobel NCL	Dead End	0.19	1.25" S9.5B	$24,000
2027	1	008-Bertie	Preservation	SR 1254 (Saunders Rd.)	NC 11	Dead End	0.11	1.25" S9.5B	$14,000
2027	1	008-Bertie	Preservation	SR 1389	US 17	End of Pavement	0.15	Seal - Double	$11,000
2027	1	008-Bertie	Preservation	SR 1511 (Sutton Rd.)	SR 1502 (Avoca Farm Rd.)	NC 45	5.16	Seal - Double	$258,000
2027	1	008-Bertie	Preservation	SR 1544 (Wading Creek Rd.)	NC 308	End of Pavement	0.08	Seal - Double	$4,000
2027	1	015-Camden	Resurfacing	SR 1133 (Mckimmey Rd.)	SR 1134 (Mercer Dr.)	SR 1121 (Trotman Rd.)	1.44	Full Depth Patching and 1.5" S9.5B	$288,000
2027	1	015-Camden	Resurfacing	SR 1134 (Mercer Dr.)	SR 1133 (McKimmey Rd.)	Dead End	0.29	Full Depth Patching and 1.5" S9.5B	$58,000
2027	1	015-Camden	Resurfacing	SR 1207 (Bourbon St.)	SR 1145 (Lambs Rd.)	SR 1145 (Lambs Rd.)	2.99	Full Depth Patching and 1.5" S9.5B	$597,000
2027	1	015-Camden	Resurfacing	SR 1211 (Bingham Rd.)	SR 1212 (River Bridge Rd.)	Dead End	1.70	Full Depth Patching and 1.5" S9.5B	$339,000
2027	1	015-Camden	Preservation	SR 1138 (Chantilly Rd.)	SR 1132 (Country Club Rd.)	Dead End	0.70	1.25" S9.5B	$86,000
2027	1	015-Camden	Preservation	SR 1161 (Walston Ln.)	NC 343	Dead End	0.38	1.25" S9.5B	$42,000
2027	1	015-Camden	Preservation	SR 1210 (Lake Rd.)	NC 343	Dead End	1.50	1.25" S9.5B	$164,000
2027	1	015-Camden	Preservation	SR 1257 (Havenwood Dr.)	US 158	Dead End	0.21	1.25" S9.5B	$23,000
2027	1	021-Chowan	Resurfacing	SR 1309 (Icaria/Skinner Rd.)	NC 32	SR 1303 (Happy Home Rd.)	2.28	Full Depth Patching and 1.5" S9.5B	$455,000
2027	1	021-Chowan	Resurfacing	SR 1321 (Whitemon Lane)	End Maint	NC 32	1.00	Full Depth Patching and 1.5" S9.5B	$200,000
2027	1	021-Chowan	Preservation	SR 1110 (Sycamore Rd.)	End Maint	SR 1108 (Indian Trail Rd.)	1.28	1.25" S9.5B	$156,000
2027	1	021-Chowan	Preservation	SR 1117 (Holley Grove Rd.)	NC 37	End of Maintenance	0.30	1.25" S9.5B	$33,000
2027	1	027-Currituck	Resurfacing	SR 1124 (Fishers Landing Rd.)	US 158	Dead End	1.40	1.5" S9.5B	$280,000
2027	1	027-Currituck	Resurfacing	SR 1143 (Worth Guard Rd)	Dead End	SR 1143 (Hampton Rd)	0.62	Mill 1.5" and 1.5" S9.5B	$291,000
2027	1	027-Currituck	Resurfacing	SR 1148 (N. Gregory Rd)	US 158	NC 34	1.89	Full Depth Patching and 1.5" S9.5B	$377,000
2027	1	027-Currituck	Resurfacing	SR 1149 (Alan Sawyer Rd.)	SR 1147 (Indiantown Rd.)	Dead End	0.52	1.5" S9.5B	$104,000
2027	1	027-Currituck	Resurfacing	SR 1159 (Soundview Dr)	SR 1137 (Narrow Shore Rd)	SR 1418 (Sandy Ln)	0.26	Full Depth Patching and 1.5" S9.5B	$47,000
2027	1	027-Currituck	Resurfacing	SR 1201 (Buckhorn Rd.)	NC 34	End Pavement	1.47	1.5" S9.5B	$295,000
2027	1	027-Currituck	Resurfacing	SR 1404 (Worth Guard Rd)	US 158	SR 1143 (Worth Guard Rd)	0.04	Mill 1.5" and 1.5" S9.5B	$17,000
2027	1	027-Currituck	Preservation	SR 1294 (E. Canvas Back Rd.)	Dead End	SR 1245-Bells Island Rd.	0.50	1.25" S9.5B	$61,000
2027	1	027-Currituck	Preservation	SR 1294 (W. Canvas Back Rd.)	SR 1245-Bells Island Rd.	Dead End	0.12	1.25" S9.5B	$15,000
2027	1	027-Currituck	Preservation	SR 1311 (Redhead Dr.)	SR 1245-Bells Island Rd.	SR 1331-Gadwell Dr.	0.21	1.25" S9.5B	$26,000
2027	1	027-Currituck	Preservation	SR 1312 (White Heroin Dr.)	SR 1311 (Redhead Dr.)	Cul-de-sac	0.19	1.25" S9.5B	$24,000
2027	1	027-Currituck	Preservation	SR 1331 (Gadwell Dr.)	SR 1311-Redhead Dr.	Cul-de-sac	0.17	1.25" S9.5B	$21,000
2027	1	027-Currituck	Preservation	SR 1341 (Baggy Davis Lane)	SR 1245-Bells Island Rd.	Dead End	0.18	1.25" S9.5B	$20,000
2027	1	027-Currituck	Preservation	SR 1354 (Canadian Goose Dr.)	SR 1245-Bells Island Rd.	Dead End	0.15	1.25" S9.5B	$19,000
2027	1	027-Currituck	Preservation	SR 1356 (Swan Dr.)	SR 1245-Bells Island Rd.	Dead End	0.16	1.25" S9.5B	$18,000
2027	1	027-Currituck	Preservation	SR 1357 (Widgeon Dr.)	SR 1245-Bells Island Rd.	Dead End	0.10	1.25" S9.5B	$11,000
2027	1	027-Currituck	Preservation	SR 1392 (Teal Dr.)	SR 1245-Bells Island Rd.	Dead End	0.11	1.25" S9.5B	$11,000
2027	1	027-Currituck	Preservation	SR 1395 (Mallard Dr.)	SR 1245-Bells Island Rd.	Dead End	0.14	1.25" S9.5B	$16,000
2027	1	027-Currituck	Preservation	SR 1501 (Wood Duck Dr.)	SR 1245-Bells Island Rd.	Dead End	0.11	1.25" S9.5B	$13,000
2027	1	028-Dare	Resurfacing	NC 12	SR 1482 (Buccaneer Dr.)	Northern Buxton Town Limits	3.91	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,235,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	1	028-Dare	Resurfacing	NC 12	Bias Lane	SR 1479 (Widgeon Dr.)	3.01	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$899,000
2027	1	028-Dare	Resurfacing	SR 1230-Rocky Rollison Rd.	End Pavement	NC 12	0.45	Full Depth Patching and 1.5" S9.5B	$81,000
2027	1	028-Dare	Resurfacing	SR 1231-Old Lighthouse Rd.	NC 12	Gate	0.65	Full Depth Patching and 1.5" S9.5B	$129,000
2027	1	028-Dare	Resurfacing	SR 1232-Buxton Back Rd.	NC 12	NC 12	1.25	Full Depth Patching and 1.5" S9.5B	$249,000
2027	1	028-Dare	Resurfacing	SR 1233-Light Plant Rd.	Dead End	NC 12	0.22	Full Depth Patching and 1.5" S9.5B	$44,000
2027	1	028-Dare	Resurfacing	SR 1234-Cross Rd.	SR 1232-Back Rd.	NC 12	0.27	Full Depth Patching and 1.5" S9.5B	$54,000
2027	1	028-Dare	Resurfacing	SR 1291-Diamond Point Rd.	Dead End	SR 1231-Old Lighthouse Rd.	0.26	Full Depth Patching and 1.5" S9.5B	$47,000
2027	1	028-Dare	Resurfacing	SR 1527-Diamond Shoals Drive	SR 1291-Diamond Point Rd.	SR 1231-Old Lighthouse Rd.	0.42	Full Depth Patching and 1.5" S9.5B	$76,000
2027	1	028-Dare	Resurfacing	SR 1529-Lost Tree Trail	Dead End	SR 1232-Old Lighthouse Rd.	1.01	Full Depth Patching and 1.5" S9.5B	$202,000
2027	1	028-Dare	Resurfacing	SR 1530-Crooked Ridge Trail	Dead End	SR 1529-Lost Tree Trail	0.22	Full Depth Patching and 1.5" S9.5B	$44,000
2027	1	028-Dare	Resurfacing	SR 1531-Middle Ridge Trail	Dead End	SR 1529-Lost Tree Trail	0.48	Full Depth Patching and 1.5" S9.5B	$95,000
2027	1	028-Dare	Preservation	SR 1293-Seabreeze Dr.	NC 12	SR 1557-Seabreeze Dr.	0.32	1.0" S9.5B	$39,000
2027	1	028-Dare	Preservation	SR 1409-Christopher Rd.	SR 1409-Christopher Rd.	NC 12	0.67	1.0" S9.5B	$82,000
2027	1	028-Dare	Preservation	SR 1410-Teresa Ct.	Dead End	SR 1409-Christopher Rd.	0.05	1.0" S9.5B	$7,000
2027	1	028-Dare	Preservation	SR 1417-Plover Dr.	CDS	NC 12	0.49	1.0" S9.5B	$60,000
2027	1	028-Dare	Preservation	SR 1425-Wampum Dr.	CDS	NC 12	0.52	1.0" S9.5B	$64,000
2027	1	028-Dare	Preservation	SR 1469-Seahawk Dr. W.	CDS	NC 12	0.28	1.0" S9.5B	$34,000
2027	1	028-Dare	Preservation	SR 1482-Buccener Dr.	NC 12	End Maint	0.09	1.0" S9.5B	$10,000
2027	1	028-Dare	Preservation	SR 1483-Treacher Lane	CDS	CDS	0.13	1.0" S9.5B	$14,000
2027	1	028-Dare	Preservation	SR 1484-E. Seahawk Dr.	CDS	NC 12	0.28	1.0" S9.5B	$35,000
2027	1	028-Dare	Preservation	SR 1518-Dune Rd.	SR 1519-Speckle Trout Dr.	NC 12	0.50	1.0" S9.5B	$61,000
2027	1	028-Dare	Preservation	SR 1519-Speckle Trout Dr.	SR 1518-Dune Rd.	End of Maintenance	0.07	1.0" S9.5B	$9,000
2027	1	028-Dare	Preservation	SR 1555-Osprey Ridge Rd.	CDS	NC 12	0.20	1.0" S9.5B	$25,000
2027	1	028-Dare	Preservation	SR 1557-Seabreeze Dr.	CDS	CDS	0.05	1.0" S9.5B	$7,000
2027	1	037-Gates	Resurfacing	NC 137	SR 1114 (Turner Rd.)	Begin C&G	2.17	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$612,000
2027	1	037-Gates	Resurfacing	NC 137	SR 1118 (Taylor Mill Rd.)	SR 1114 (Turner Rd.)	1.77	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$499,000
2027	1	037-Gates	Resurfacing	NC 137	SR 1126 (Corner High Rd.)	SR 1118 (Taylor Mill Rd.)	1.74	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$490,000
2027	1	037-Gates	Resurfacing	NC 137	Begin C&G	NC 37	0.47	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$208,000
2027	1	037-Gates	Resurfacing	NC 37	Bridge #13	US 158 Bus.	0.67	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$268,000
2027	1	037-Gates	Resurfacing	SR 1123 (Mullen Rd.)	SR 1122 (Hill Lane)	End of Maintenance	0.31	Full Depth Patching and 1.5" S9.5B	$62,000
2027	1	037-Gates	Resurfacing	SR 1134 (Lewis Mill Rd.)	NC 137	End of Maintenance	0.50	Full Depth Patching and 1.5" S9.5B	$100,000
2027	1	037-Gates	Resurfacing	SR 1202 (Gatlington Rd.)	US 13	SR 1208 (Saunders Rd.)	2.09	Full Depth Patching and 1.5" S9.5B	$376,000
2027	1	037-Gates	Resurfacing	SR 1311 (Hazelton Rd.)	SR 1308 (Drum Hill Rd.)	SR 1304 (Willeyton Rd.)	1.95	Full Depth Patching and 1.5" S9.5B	$389,000
2027	1	037-Gates	Resurfacing	SR 1318 (Middle Swamp Rd)	US 158	SR 1319 (Clay Hill Rd)	1.53	Full Depth Patching and 1.5" S9.5B	$321,000
2027	1	037-Gates	Resurfacing	SR 1414 (Hobbsville Rd.)	NC 32	SR 1413 (Sandy Cross Rd.)	4.11	Full Depth Patching and 1.5" S9.5B	$587,000
2027	1	037-Gates	Resurfacing	US 158 Bus.	US 158	SR 1437 (Savage St.)	2.11	Full Depth Patching and 1.5" S9.5C	$463,000
2027	1	037-Gates	Resurfacing	US 158 Bus.	SR 1437 (Savage St.)	NC 37	0.48	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$169,000
2027	1	037-Gates	Preservation	SR 1129 (Horton Ln.)	SR 1128 (Barfield Rd.)	End of Maintenance	0.40	1.25" S9.5B	$44,000
2027	1	037-Gates	Preservation	SR 1223 (Dildy Lane)	End Maint	NC 37	0.19	1.25" S9.5B	$21,000
2027	1	037-Gates	Preservation	SR 1232 (Emily St.)	SR 1345 (Whitehurst Rd.)	End Of Maintenance	0.35	1.25" S9.5B	$43,000
2027	1	037-Gates	Preservation	SR 1233 (Kelly St.)	End Maint	SR 1345 (Whitehurst Rd.)	0.39	1.25" S9.5B	$48,000
2027	1	037-Gates	Preservation	SR 1314 (Hardy Askew Rd.)	Dead End	SR 1300 (Medical Center Rd.)	0.59	1.25" S9.5B	$72,000
2027	1	037-Gates	Preservation	SR 1345 (Whitehurst Rd.)	CDS	SR 1304 (Willeyton Rd.)	0.44	1.25" S9.5B	$54,000
2027	1	046-Hertford	Resurfacing	NC 561	NC 461	US 13 (Academy St.)	5.98	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,650,000
2027	1	046-Hertford	Resurfacing	SR 1112 (St. Johns Millinium Rd.)	NC 561	SR 1123 (Jackie Brinkley Rd.)	1.55	Full Depth Patching and 1.5" S9.5B	$279,000
2027	1	046-Hertford	Resurfacing	SR 1315 (New Hope Church Rd.)	SR 1347 (Winborne Mill Rd.)	SR 1310 (Statesville Rd.)	2.21	Full Depth Patching and 1.5" S9.5B	$397,000
2027	1	046-Hertford	Resurfacing	SR 1322 (Battles Beach Rd.)	SR 1319 (Mill Neck Rd.)	US 158	1.92	Full Depth Patching and 1.5" S9.5B	$383,000
2027	1	046-Hertford	Resurfacing	SR 1407 (Bluefoot Rd.)	NC 461	SR 1403 (Ahoskie Cofield Rd.)	2.79	Full Depth Patching and 1.5" S9.5B	$557,000
2027	1	046-Hertford	Resurfacing	SR 1411 (Brindleyville Rd.)	SR 1409 (Hall Siding Rd.)	US 13	1.38	Full Depth Patching and 1.5" S9.5B	$276,000
2027	1	046-Hertford	Resurfacing	US 258	SR 1306 (Parkers Ferry Rd.)	SR 1319 (Mill Neck Rd.)	2.39	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$617,000
2027	1	046-Hertford	Preservation	SR 1131 (West Saluda Hall Rd.)	NC 461	NC 11	0.45	1.0" S9.5B	$55,000
2027	1	046-Hertford	Preservation	SR 1133 (Log Cabin Rd.)	SR 1108 (Boone Farm Rd.)	Dead End	0.25	1.0" S9.5B	$31,000
2027	1	046-Hertford	Preservation	SR 1225 (Commercial Rd.)	NC 42	Dead End	0.24	1.0" S9.5B	$30,000
2027	1	046-Hertford	Preservation	SR 1241 (Ridge Rd.)	SR 1105 (Johnny Mitchell Rd.)	CDS	0.21	1.0" S9.5B	$26,000
2027	1	046-Hertford	Preservation	SR 1242 (Planters Walk Rd.)	SR 1105 (Johnny Mitchell Rd.)	SR 1243 (Stable Lane)	0.08	1.0" S9.5B	$11,000
2027	1	046-Hertford	Preservation	SR 1243 (Stable Lane)	SR 1242 (Planters Walk Rd.)	CDS	0.30	1.0" S9.5B	$37,000
2027	1	046-Hertford	Preservation	SR 1463 (Poole Rd.)	SR 1409 (Ahoskie Cofield Rd.)	Dead End	0.16	1.0" S9.5B	$20,000
2027	1	046-Hertford	Preservation	SR 1465 (Cedar Rd.)	SR 1466 (Brantley Rd.)	Dead End	0.36	1.0" S9.5B	$44,000
2027	1	046-Hertford	Preservation	SR 1466 (Brantley Rd.)	SR 1409 (Ahoskie Cofield Rd.)	SR 1409 (Ahoskie Cofield Rd.)	0.44	1.0" S9.5B	$54,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	1	046-Hertford	Preservation	SR 1467 (Magnolia Rd.)	SR 1463 (Poole Rd.)	Dead End	0.17	1.0" S9.5B	$21,000
2027	1	046-Hertford	Preservation	SR 4670 Starwood Ave	SR 1171 The Plaza Ext	EOM	0.13	Rejuvenator	$2,573
2027	1	046-Hertford	Preservation	SR 4696 Welland Trail	SR 4670 Starwood Ave	EOM	0.16	Rejuvenator	$3,166
2027	1	048-Hyde	Resurfacing	NC 94	SR 1307 (Seth Rd.)	Tyrrell Co	2.37	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$668,000
2027	1	048-Hyde	Resurfacing	NC 94	SR 1311(N. Lake Rd.)	SR 1307 (Seth Rd.)	2.56	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$721,000
2027	1	048-Hyde	Resurfacing	US 264	SR 1304 (Turnpike Rd.)	700' East of NC 94	4.85	Full Depth Patching and 1.5" S9.5C	$1,161,000
2027	1	048-Hyde	Preservation	SR 1311 (North Lake Rd.)	US 264	NC 94	13.87	Seal - Double	$692,000
2027	1	058-Martin	Resurfacing	NC 142	NC 42	NC 125	5.81	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,810,000
2027	1	058-Martin	Resurfacing	NC 142	Edgecombe County Line	NC 42	0.97	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$251,000
2027	1	058-Martin	Resurfacing	NC 42	NC 142	NC 11	1.13	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$292,000
2027	1	058-Martin	Resurfacing	NC 42	Edgecombe Co	NC 142	1.34	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$409,000
2027	1	058-Martin	Resurfacing	SR 1113 (Wynn Rd)	SR 1142 (Prison Camp Rd)	SR 1143 (Robert Taylor Rd)	0.97	Full Depth Patching and 1.5" S9.5B	$213,000
2027	1	058-Martin	Resurfacing	SR 1148 (Crisp Rd.)	SR 1145 (Sam Everett Rd.)	NC 903	2.09	Full Depth Patching and 1.5" S9.5B	$417,000
2027	1	058-Martin	Resurfacing	SR 1315 (Spring Green Rd)	NC 125	NC 903	0.25	Full Depth Patching and 1.5" S9.5B	$55,000
2027	1	058-Martin	Resurfacing	SR 1330 (David Mayer Rd.)	NC 125	SR 1329 (Mayo Farm Rd.)	0.80	Full Depth Patching and 1.5" S9.5B	$160,000
2027	1	058-Martin	Resurfacing	SR 1429 (Penco Dr)	NC 125	PVMT CHNG	0.29	#67 Mat Seal and 1.5" S9.5B	$69,000
2027	1	058-Martin	Resurfacing	SR 1430 (Penco Dr)	NC 125	PVMT CHNG	0.19	#67 Mat Seal and 1.5" S9.5B	$45,000
2027	1	058-Martin	Resurfacing	SR 1500 (Holly Springs Church Rd.)	SR 1595 (Jones Rd.)	NC 171	3.83	Full Depth Patching and 1.5" S9.5B	$765,000
2027	1	058-Martin	Resurfacing	SR 1532 (Tice Cemetery Rd.)	SR 1530 (Piney Grove Church Rd.)	SR 1531 (Tice Rd.)	0.25	Full Depth Patching and 1.5" S9.5B	$50,000
2027	1	058-Martin	Resurfacing	SR 1534 (Cecil Whitehurst Rd.)	Beaufort Co	SR 1533 (Godard Rd.)	0.56	Full Depth Patching and 1.5" S9.5B	$115,000
2027	1	058-Martin	Resurfacing	SR 1535 (Hollow Pond Rd.)	SR 1516 (Thouroughfare Rd.)	NC 171	2.61	Full Depth Patching and 1.5" S9.5B	$525,000
2027	1	058-Martin	Resurfacing	SR 1538 (Manning Rd)	SR 1548 (Brown Rd)	SR 1545 (Arthur Modlin Rd)	1.17	Full Depth Patching and 1.5" S9.5B	$248,000
2027	1	058-Martin	Preservation	SR 1113 (Wynn Rd.)	SR 1143 (Roberts Taylor Rd.)	SR 1138 (Everetts Rd.)	1.14	Seal - Double	$57,000
2027	1	058-Martin	Preservation	SR 1134 (Jack Robertson Rd.)	SR 1138 (Everetts Rd.)	SR 1136 (Archer Mobley Rd.)	1.70	Seal - Double	$85,000
2027	1	058-Martin	Preservation	SR 1138 (Everetts Rd.)	SR 1142 (Prison Camp Rd.)	SR 1134 (Jack Robertson Rd.)	1.46	Seal - Double	$85,000
2027	1	058-Martin	Preservation	1557 (Piney Woods, Uniontown, Swinson F	SR 1563 (Grey Farm Rd.)	US 64	5.25	Seal - Double	$236,000
2027	1	058-Martin	Preservation	SR 1560 (Davis Rd.)	SR 1559 (Corinth Ch. Rd.)	SR 1592 (Old US 64)	0.50	Seal - Double	$25,000
2027	1	066-Northampton	Resurfacing	SR 1128 (Occoneechee Neck Rd.)	Dead End	SR 1126 (Barrows Mill Rd.)	2.77	Full Depth Patching and 1.5" S9.5B	$553,000
2027	1	066-Northampton	Resurfacing	SR 1130 (Burgwyn Rd.)	Dead End	SR 1128 (Occoneechee Neck Rd.)	0.98	Full Depth Patching and 1.5" S9.5B	$176,000
2027	1	066-Northampton	Resurfacing	SR 1132 (Urquhart Farm Rd.)	Dead End	SR 1128 (Occoneechee Neck Rd.)	0.46	Full Depth Patching and 1.5" S9.5B	$83,000
2027	1	066-Northampton	Resurfacing	SR 1300 (Big Johns Store Rd.)	SR 1324 (Peanut Market Rd.)	NC 186	5.52	Full Depth Patching and 1.5" S9.5B	$1,212,000
2027	1	066-Northampton	Resurfacing	SR 1313 (Hargraves Rd.)	SR 1311 (Jackson Bypass Rd.)	End of Pavement	1.20	Full Depth Patching and 1.0" S4.75A	$132,000
2027	1	066-Northampton	Resurfacing	SR 1328 (High Bridge Rd.)	NC 186	SR 1333 (Devil's Racetrack Rd.)	2.31	Full Depth Patching and 1.5" S9.5B	$415,000
2027	1	066-Northampton	Resurfacing	SR 1604 (Lowes Blvd.)	NC 461	Plant Entrance	1.09	Full Depth Patching and 1.5" S9.5B	$261,000
2027	1	066-Northampton	Resurfacing	SR 1617 (Technology Dr.)	SR 1604 (Lowes Blvd.)	Dead End	0.40	Full Depth Patching and 1.5" S9.5B	$96,000
2027	1	066-Northampton	Preservation	SR 1121 (Braswell Rd.)	NC 305	SR 1121 (W.J. Duke Service Rd)	2.48	Crack Seal	$16,000
2027	1	066-Northampton	Preservation	SR 1121 (W.J. Duke Service Rd)	SR 1108 (Bryantown Rd.)	NC 305	5.21	Crack Seal	$32,000
2027	1	066-Northampton	Preservation	SR 1127 (Bull Hill Rd.)	SR 1129 (Barrows Mill Rd.)	Dead End	0.90	Seal - Double	$45,000
2027	1	066-Northampton	Preservation	SR 1129 (Bill Johnston Rd.)	SR 1128 (Occonneechee Neck Rd.)	Dead End	1.85	Seal - Double	$93,000
2027	1	066-Northampton	Preservation	SR 1324 (Peanut Market Rd.)	SR 1300 (Big John Store Rd.)	NC 186	2.99	Crack Seal	$19,000
2027	1	066-Northampton	Preservation	SR 1500 (Fire Tower Rd.)	US 158	SR 1504 (Creeksville Rd.)	6.64	Seal - Double	$348,000
2027	1	066-Northampton	Preservation	SR 1511 (Bridgers Rd.)	SR 1501 (Dusty Hill Rd.)	Dead End	0.48	Seal - Double	$22,000
2027	1	070-Pasquotank	Resurfacing	NC 344 (Halstead Blvd. / Weeksville Hwy.)	RMP-4644	End of Pavement	0.33	Mill 1.5" and 1.5" S9.5C	$202,000
2027	1	070-Pasquotank	Resurfacing	NC 344 (Halstead Blvd. / Weeksville Hwy.)	US 17 (Hughes Blvd.)	RMP-4644	3.22	Mill 1.5" and 1.5" S9.5C	$983,000
2027	1	070-Pasquotank	Resurfacing	NC 344 (Halstead Blvd. / Weeksville Hwy.)	RMP-4643	US 17 (Hughes Blvd.)	3.21	Mill 1.5" and 1.5" S9.5C	$980,000
2027	1	070-Pasquotank	Resurfacing	SR 1144 (Foreman Bundy Rd.)	Perquimans Co	US 17	4.70	Full Depth Patching and 1.5" S9.5B	$938,000
2027	1	070-Pasquotank	Resurfacing	SR 1301 (Banks Rd.)	SR 1140 (Okisko Rd.)	End of Pavement	0.18	Full Depth Patching and 1.5" S9.5B	$36,000
2027	1	070-Pasquotank	Resurfacing	SR 1303 (Cherry Glade Rd.)	SR 1144 (Foreman Bundy Rd.)	Perquimans Co	3.27	Full Depth Patching and 1.5" S9.5B	$652,000
2027	1	070-Pasquotank	Resurfacing	SR 1419 (Nancy Dr)	SR 1140 (Okisko Rd.)	SR 1418 (Nancy Dr)	0.29	Full Depth Patching and 1.5" S9.5B	$58,000
2027	1	070-Pasquotank	Preservation	SR 1309 (Main St. Ext.)	US 17 Bus. (Hughes Blvd.)	Pavement Joint	0.54	1.25" S9.5B	$76,000
2027	1	070-Pasquotank	Preservation	SR 1321 (Parsonage St.)	US 17 Bus. (Hughes Blvd.)	Dead End	0.90	1.25" S9.5B	$94,000
2027	1	070-Pasquotank	Preservation	SR 1325 (W. Broad St.)	US 17 Bus. (Hughes Blvd.)	Dead End	0.13	1.25" S9.5B	$16,000
2027	1	070-Pasquotank	Preservation	SR 1327 (Griggs St.)	US 17 Bus. (Hughes Blvd.)	Dead End	0.08	1.25" S9.5B	$11,000
2027	1	070-Pasquotank	Preservation	SR 1385 (Pot-O-Gold Trl.)	SR 1332 (Creek Rd.)	Dead End	0.42	1.25" S9.5B	$52,000
2027	1	072-Perquimans	Resurfacing	SR 1223 (Five Bridge Rd.)	SR 1224 (Chapanoke Rd.)	Pasquotank CountyLine	0.43	Full Depth Patching and 1.5" S9.5B	$86,000
2027	1	072-Perquimans	Resurfacing	SR 1301 (Old Neck Rd.)	US 17	SR 1302 (Old Neck Rd.)	2.64	Full Depth Patching and 1.5" S9.5B	$475,000
2027	1	072-Perquimans	Resurfacing	SR 1302 (Old Neck Rd.)	SR 1301 (Bundy Rd.)	SR 1300 (New Hope Rd.)	0.75	Full Depth Patching and 1.5" S9.5B	$145,000
2027	1	072-Perquimans	Resurfacing	SR 1303 (Woodland Church Rd.)	US 17	SR 1300 (New Hope Rd.)	2.63	Full Depth Patching and 1.5" S9.5B	$525,000
2027	1	072-Perquimans	Resurfacing	SR 1323 (Winslow Rd.)	SR 1300 (New Hope Rd.)	Dead End	2.22	Full Depth Patching and 1.5" S9.5B	$443,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	1	072-Perquimans	Resurfacing	SR 1346 (Poor Hill Rd.)	SR 1339 (Pender Rd.)	SR 1486 (Washington Dr.)	2.81	Full Depth Patching and 1.5" S9.5B	$561,000
2027	1	072-Perquimans	Resurfacing	SR 1486 (Washington Dr.)	SR 1346 (Poor Hill Rd.)	EOM (Johnson Dr.)	0.91	Full Depth Patching and 1.5" S9.5B	$182,000
2027	1	072-Perquimans	Preservation	SR 1129 (Riverwood Drive)	Dead End	SR 1109 (Don Juan Rd.)	0.68	1.25" S9.5B	$75,000
2027	1	072-Perquimans	Preservation	SR 1301 (Bundy Rd.)	End Pavement	SR 1302 (Old Neck Rd.)	0.34	1.25" S9.5B	$38,000
2027	1	072-Perquimans	Preservation	SR 1353 (Hertford Beach Rd.)	SR 1336 (Harvey Point Rd.)	End Of Maintenance	0.34	1.25" S9.5B	$42,000
2027	1	072-Perquimans	Preservation	SR 1363 (Billy's Beach Rd)	SR 1382 (Russell Drive)	SR 1301 (Old Neck Rd.)	0.51	1.25" S9.5B	$62,000
2027	1	072-Perquimans	Preservation	SR 1381 (Cedar / Ash / Pine / Poplar Rd.)	SR 1380 (Dogwood Dr.)	SR 1340 (Snug Harbor Rd.)	0.71	1.25" S9.5B	$87,000
2027	1	072-Perquimans	Preservation	SR 1402 (Newbold White Rd.)	SR 1336 (Harvey Point Rd.)	End Of Maintenance	0.22	1.25" S9.5B	$25,000
2027	1	072-Perquimans	Preservation	SR 1476 (Granby Street)	End Maint	SR 1475 (North Commerce)	0.36	1.25" S9.5B	$44,000
2027	1	072-Perquimans	Preservation	SR 1478 (Harvey Street)	End Maint	SR 1336 (Harvey Point Rd.)	0.07	1.25" S9.5B	$9,000
2027	1	072-Perquimans	Preservation	SR 1479 (Newbold Street)	End Maint	SR 1336 (Harvey Point Rd.)	0.08	1.25" S9.5B	$10,000
2027	1	089-Tyrrell	Resurfacing	NC 94	Hyde Co	SR 1321 (S.GumneckRd.)	10.29	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,840,000
2027	1	089-Tyrrell	Resurfacing	NC 94	SR 1101 Hunter Rd.)	SR 1102 (Jones Rd.)	1.99	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$645,000
2027	1	089-Tyrrell	Resurfacing	SR 1200 (Albemarle Church Rd.)	Washington Co	SR 1117 (Bay Post Office Rd.)	1.39	Full Depth Patching and 1.5" S9.5B	$250,000
2027	1	094-Washington	Resurfacing	SR 1112 (Garrett Island Rd.)	SR 1113 (Old Roper Loop)	End Of Pavement	1.59	Full Depth Patching and 1.5" S9.5B	$318,000
2027	1	094-Washington	Resurfacing	SR 1125 (E Millpond Rd.)	SR 1175 (S Railroad St.)	1300' South of US 64	0.83	Full Depth Patching and 1.5" S9.5B	$232,000
2027	1	094-Washington	Resurfacing	SR 1126 (Newland Rd.)	NC 32	5200' South of US 64	2.20	1.5" S9.5B	$483,000
2027	1	094-Washington	Resurfacing	SR 1175 (S Railroad St.)	SR 1122 (E Buncombe St)	SR 1125 (E Millpond Rd.)	0.50	1.5" S9.5B	$100,000
2027	1	094-Washington	Resurfacing	SR 1352 (Griffin Rd.)	NC 32	Cul-de-sac	0.22	1.5" S9.5B	$40,000
2027	1	094-Washington	Preservation	SR 1133 (Mariner Rd.)	NC 32	SR 1132 (Backwoods Rd.)	1.20	Crack Seal	$8,000
2027	1	094-Washington	Preservation	SR 1150 (Gus Town Rd.)	SR 1149 (Ambrose Rd.)	SR 1149 (Ambrose Rd.)	1.67	Crack Seal	$11,000
2027	1	094-Washington	Preservation	SR 1181 (White Oak Loop Rd.)	NC 45	NC 45	0.29	Crack Seal	$2,000
2027	2	007-Beaufort	Resurfacing	NC 33	BRIDGE	SR 1110	12.59	1.5" S9.5B	$2,700,000
2027	2	007-Beaufort	Resurfacing	NC 33	US 17	PITT COUNTY	3.48	1.5" S9.5B	$702,426
2027	2	007-Beaufort	Resurfacing	SR 1307	SR 1302	END MAINTENANCE	0.36	1.25" S9.5B	$54,150
2027	2	007-Beaufort	Resurfacing	SR 1326	SR 1311	SR 1328	1.63	1.5" S9.5B	$340,000
2027	2	007-Beaufort	Resurfacing	SR 1462	US 264	SR 1463	0.11	1.5" S9.5B	$22,200
2027	2	007-Beaufort	Resurfacing	SR 1463	CUL-DE-SAC	SR 1467	0.41	1.5" S9.5B	$82,000
2027	2	007-Beaufort	Resurfacing	SR 1467	CUL-DE-SAC	CUL-DE-SAC	0.35	1.5" S9.5B	$70,600
2027	2	007-Beaufort	Resurfacing	SR 1468	SR 1454	END MAINTENANCE	0.13	1.5" S9.5B	$25,800
2027	2	007-Beaufort	Resurfacing	SR 1507	SR 1600	NC 32	2.10	1.5" S9.5B	$420,000
2027	2	007-Beaufort	Resurfacing	SR 1528	NC 32	US 264	5.44	1.5" S9.5B	$1,088,000
2027	2	007-Beaufort	Resurfacing	SR 1528	SR 1526	NC 32	3.34	1.5" S9.5B	$665,000
2027	2	007-Beaufort	Resurfacing	SR 1602	NC 32	SR 1343	3.09	1.5" S9.5B	$616,000
2027	2	007-Beaufort	Preservation	SR 1515	SR 1424	SR 1422	3.96	Seal - Double	$198,000
2027	2	007-Beaufort	Preservation	SR 1527	SR 1526	SR 1528	1.91	Seal - Double	$72,542
2027	2	007-Beaufort	Preservation	SR 1532	SR 1530	NC 32	2.37	Seal - Double	$90,098
2027	2	007-Beaufort	Preservation	SR 1607	SR 1343	SR 1343	1.88	Seal - Double	$71,440
2027	2	007-Beaufort	Preservation	SR 1608	SR 1607	US 264	2.06	Seal - Double	$78,166
2027	2	016-Carteret	Resurfacing	SR 1340	SR 1335	SR 1436	0.24	1.5" S9.5B	$47,600
2027	2	016-Carteret	Resurfacing	SR 1341	SR 1335	DEAD END	0.60	1.5" S9.5B	$119,800
2027	2	016-Carteret	Resurfacing	SR 1342	SR 1343	END MAINTENANCE	0.36	1.5" S9.5B	$71,400
2027	2	016-Carteret	Resurfacing	SR 1344	SR 1343	DEAD END	0.42	1.5" S9.5B	$84,000
2027	2	016-Carteret	Resurfacing	SR 1354	US 70	END MAINTENANCE	0.56	1.5" S9.5B	$112,200
2027	2	016-Carteret	Resurfacing	SR 1362	SR 1363	END PAVEMENT	0.76	1.5" S9.5B	$152,600
2027	2	016-Carteret	Resurfacing	SR 1363	US 70	END PAVEMENT	0.68	1.5" S9.5B	$136,000
2027	2	016-Carteret	Resurfacing	SR 1364	SR 1363	END MAINTENANCE	0.31	1.5" S9.5B	$61,400
2027	2	016-Carteret	Resurfacing	SR 1365	SR 1362	END MAINTENANCE	0.06	1.5" S9.5B	$12,000
2027	2	016-Carteret	Resurfacing	SR 1366	SR 1363	END MAINTENANCE	0.13	1.5" S9.5B	$25,000
2027	2	016-Carteret	Resurfacing	SR 1368	US 70	US 70	0.47	1.5" S9.5B	$93,000
2027	2	016-Carteret	Resurfacing	SR 1369	US 70	DEAD END	0.28	1.5" S9.5B	$56,000
2027	2	016-Carteret	Resurfacing	SR 1410	SR 1342	END MAINTENANCE	0.13	1.5" S9.5B	$26,000
2027	2	016-Carteret	Resurfacing	SR 1411	US 70	END MAINTENANCE	0.08	1.5" S9.5B	$16,000
2027	2	016-Carteret	Resurfacing	SR 1436	SR 1340	SR 1437	0.05	1.5" S9.5B	$10,600
2027	2	016-Carteret	Resurfacing	SR 1437	SR 1436	SR 1438	0.18	1.5" S9.5B	$36,400
2027	2	016-Carteret	Resurfacing	SR 1438	SR 1437	DEAD END	0.06	1.5" S9.5B	$12,000
2027	2	016-Carteret	Resurfacing	SR 1454	SR 1340	SR 1481	0.26	1.5" S9.5B	$51,200
2027	2	016-Carteret	Resurfacing	SR 1455	DEAD END	DEAD END	0.29	1.5" S9.5B	$57,800
2027	2	016-Carteret	Resurfacing	SR 1471	SR 1335	END MAINTENANCE	0.15	1.5" S9.5B	$30,600

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	2	016-Carteret	Resurfacing	SR 1481	SR 1454	CUL-DE-SAC	0.17	1.5" S9.5B	$33,000
2027	2	016-Carteret	Rehabilitation	SR 1345	SR 1343	DEAD END	0.71	2.5" I19.0C and 1.5" S9.5B	$215,000
2027	2	025-Craven	Resurfacing	SR 1108	SR 1101	US 70	0.39	1.5" S9.5B	$78,000
2027	2	025-Craven	Resurfacing	SR 1119	SR 1113	SR 1118	0.55	1.5" S9.5B	$110,000
2027	2	025-Craven	Resurfacing	SR 1123	SR 1113	DEAD END	0.10	1.5" S9.5B	$20,000
2027	2	025-Craven	Resurfacing	SR 1128	SR 1113	DEAD END	0.11	1.5" S9.5B	$22,000
2027	2	025-Craven	Resurfacing	SR 1129	SR 1113	SR 1113	1.29	1.5" S9.5B	$258,000
2027	2	025-Craven	Resurfacing	SR 1130	SR 1129	DEAD END	0.35	1.5" S9.5B	$69,600
2027	2	025-Craven	Resurfacing	SR 1134	SR 1113	SR 1133	0.17	1.5" S9.5B	$34,000
2027	2	025-Craven	Resurfacing	SR 1191	SR 1119	DEAD END	0.22	1.5" S9.5B	$44,000
2027	2	025-Craven	Resurfacing	SR 1192	SR 1113	SR 1191	0.39	1.5" S9.5B	$78,000
2027	2	025-Craven	Resurfacing	SR 1250	SR 1256	SR 1249	0.88	1.5" S9.5B	$176,000
2027	2	025-Craven	Resurfacing	SR 1266	BEGIN PAVEMENT	END PAVEMENT	0.62	1.5" S9.5B	$123,400
2027	2	025-Craven	Resurfacing	SR 1270	SR 1005	SR 1005	1.20	1.5" S9.5B	$240,400
2027	2	025-Craven	Resurfacing	SR 1508	SR 1444	CUL-DE-SAC	0.28	Mill 1.5" and 1.5" S9.5B	$91,000
2027	2	025-Craven	Resurfacing	SR 1911	SR 1114	DEAD END	0.24	1.5" S9.5B	$48,000
2027	2	025-Craven	Resurfacing	SR 1921	SR 1102	END MAINTENANCE	0.27	1.5" S9.5B	$53,600
2027	2	025-Craven	Resurfacing	SR 1926	SR 1102	DEAD END	0.23	1.5" S9.5B	$46,000
2027	2	025-Craven	Resurfacing	SR 1932	SR 1112	DEAD END	0.35	1.5" S9.5B	$70,000
2027	2	025-Craven	Resurfacing	SR 1951	SR 1004	SR 1952	0.08	Mill 1.5" and 1.5" S9.5B	$26,000
2027	2	025-Craven	Resurfacing	SR 1952	SR 1953	CUL-DE-SAC	0.59	Mill 1.5" and 1.5" S9.5B	$191,750
2027	2	025-Craven	Resurfacing	SR 1953	SR 1952	DEAD END	0.16	Mill 1.5" and 1.5" S9.5B	$52,000
2027	2	025-Craven	Resurfacing	SR 1954	SR 1952	DEAD END	0.08	Mill 1.5" and 1.5" S9.5B	$26,000
2027	2	025-Craven	Resurfacing	SR 1961	SR 1114	DEAD END	0.08	1.5" S9.5B	$16,000
2027	2	025-Craven	Resurfacing	SR 2079	SR 1952	Cul-de-sac	0.03	Mill 1.5" and 1.5" S9.5B	$11,050
2027	2	025-Craven	Resurfacing	SR 9001	US 70 RAMP	US 17 NB	0.42	Mill 1.5" and 1.5" S9.5C	$105,000
2027	2	025-Craven	Resurfacing	US 17 NB	MAYSVILLE BYP LIM	US 70 RAMP	4.42	Mill 1.5" and 1.5" S9.5C	$2,800,000
2027	2	025-Craven	Resurfacing	US 17 SB	SR 9001	MAYSVILLE BYP LIM	4.14	Mill 1.5" and 1.5" S9.5C	$2,800,000
2027	2	025-Craven	Rehabilitation	SR 1102	Begin PVMNT	SR 1101	1.00	2.5" I19.0C and 1.5" S9.5B	$425,000
2027	2	040-Greene	Resurfacing	SR 1342	NC 903	SR 1335	2.43	1.5" S9.5B	$486,000
2027	2	040-Greene	Resurfacing	SR 1355	NC 123	SR 1335	0.84	1.5" S9.5B	$168,000
2027	2	040-Greene	Resurfacing	SR 1413	SR 1400	NC 903	3.01	1.5" S9.5B	$602,000
2027	2	040-Greene	Resurfacing	SR 1430	SR 1091	NC 123	1.18	Full Depth Patching and 1.5" S9.5B and Widening	$522,750
2027	2	040-Greene	Resurfacing	SR 1430	END C&G	NC 123	0.39	Mill 1.75" and 1.75" S9.5B	$125,775
2027	2	040-Greene	Resurfacing	SR 1436	SR 1091	NC 58	0.43	1.5" S9.5B	$86,000
2027	2	052-Jones	Resurfacing	SR 1300	SR 1315	NC 58	4.68	1.5" S9.5B	$900,000
2027	2	052-Jones	Resurfacing	SR 1300	NC 58	SR 1315	4.82	1.5" S9.5B	$1,000,000
2027	2	054-Lenoir	Resurfacing	NC 11 NB	NC 11 (5 LANE SECTION)	PITT COUNTY	5.83	Mill 1.5" and 1.5" S9.5C	$1,700,000
2027	2	054-Lenoir	Resurfacing	NC 11 NB	NC 11 (5 LANE SECTION)	PITT COUNTY	4.27	Mill 1.5" and 1.5" S9.5C	$1,200,000
2027	2	054-Lenoir	Resurfacing	NC 11 NB	BEGIN 4 LANE	END 4 LANE	3.42	Mill 1.5" and 1.5" S9.5C	$1,150,000
2027	2	054-Lenoir	Resurfacing	NC 11 SB	PITT COUNTY	NC 11 (5 LANE SECTION)	4.24	Mill 1.5" and 1.5" S9.5C	$1,200,000
2027	2	054-Lenoir	Resurfacing	NC 11 SB	SR 1121	END 4 LANE	3.39	Mill 1.5" and 1.5" S9.5C	$1,150,000
2027	2	054-Lenoir	Resurfacing	NC 11 SB	PITT COUNTY	NC 11 (5 LANE SECTION)	5.83	Mill 1.5" and 1.5" S9.5C	$1,650,000
2027	2	054-Lenoir	Resurfacing	SR 1091	SR 1704	SR 1004	0.43	1.5" S9.5B	$82,000
2027	2	054-Lenoir	Resurfacing	SR 1118	SR 1116	JONES COUNTY	3.44	1.5" S9.5B	$688,000
2027	2	054-Lenoir	Resurfacing	SR 1158	NC 11	NC 11	3.00	2.0" S9.5C	$500,000
2027	2	054-Lenoir	Resurfacing	SR 1575	NC 58	SR 1541	2.46	1.5" S9.5B	$491,400
2027	2	054-Lenoir	Resurfacing	SR 1704	SR 1700	SR 1091	2.19	1.5" S9.5B	$438,000
2027	2	054-Lenoir	Resurfacing	SR 1800	SR 1801	DEAD END	1.27	1.5" S9.5B	$215,562
2027	2	054-Lenoir	Resurfacing	SR 1800	SR 1801	DEAD END	0.21	1.5" S9.5B	$36,438
2027	2	054-Lenoir	Resurfacing	SR 1810	SR 1811	NC 11	3.10	1.5" S9.5B	$617,800
2027	2	054-Lenoir	Resurfacing	SR 1812	SR 1811	SR 1810	1.39	1.5" S9.5B	$451,750
2027	2	054-Lenoir	Preservation	SR 1158	NC 11	NC 11	3.00	FDR and Double Seal	$1,042,231
2027	2	069-Pamlico	Resurfacing	SR 1219	SR 1217	DEAD END	0.74	1.5" S9.5B	$147,000
2027	2	069-Pamlico	Resurfacing	SR 1232	SR 1230	DEAD END	1.15	1.5" S9.5B	$229,000
2027	2	069-Pamlico	Resurfacing	SR 1234	SR 1230	SR 1230	2.05	1.5" S9.5B	$410,600
2027	2	069-Pamlico	Resurfacing	SR 1235	SR 1234	DEAD END	0.84	1.5" S9.5B	$168,400
2027	2	069-Pamlico	Resurfacing	SR 1372	SR 1308	CUL-DE-SAC	0.34	1.5" S9.5B	$67,800
2027	2	069-Pamlico	Resurfacing	SR 1377	SR 1366	DEAD END	0.30	1.5" S9.5B	$60,800

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	2	069-Pamlico	Rehabilitation	SR 1365	SR 1308	END MAINTENANCE	0.10	2.5" I19.0C and 1.5" S9.5B	$44,200
2027	2	074-Pitt	Resurfacing	NC 11 NB	LENOIR COUNTY	NC 102	6.81	Mill 1.5" and 1.5" S9.5C	$2,200,000
2027	2	074-Pitt	Resurfacing	NC 11 SB	NC 102	LENOIR COUNTY	5.51	Mill 1.5" and 1.5" S9.5C	$1,600,000
2027	2	074-Pitt	Resurfacing	NC 11 SB	NC 102	LENOIR COUNTY	0.69	Mill 1.5" and 1.5" S9.5C	$300,000
2027	2	074-Pitt	Resurfacing	SR 1246	SR 1245	NC 222	3.19	2.0" S9.5C	$610,000
2027	2	074-Pitt	Resurfacing	SR 1247	NC 43	SR 1246	5.60	2.0" S9.5C	$1,000,000
2027	2	074-Pitt	Resurfacing	SR 1403	SR 1401	SR 1401	2.44	1.5" S9.5B	$488,600
2027	2	074-Pitt	Resurfacing	SR 1444	NC 33	CUL-DE-SAC	0.51	1.5" S9.5B	$102,000
2027	2	074-Pitt	Resurfacing	SR 1454	SR 1401	SR 1401	0.78	1.5" S9.5B	$156,000
2027	2	074-Pitt	Resurfacing	SR 1455	SR 1454	SR 1454	0.22	1.5" S9.5B	$44,000
2027	2	074-Pitt	Resurfacing	SR 1456	SR 1454	SR 1454	0.20	1.5" S9.5B	$40,000
2027	2	074-Pitt	Resurfacing	SR 1458	SR 1454	SR 1454	0.17	1.5" S9.5B	$34,000
2027	2	074-Pitt	Resurfacing	SR 1459	SR 1454	SR 1454	0.13	1.5" S9.5B	$26,000
2027	2	074-Pitt	Resurfacing	SR 1469	NC 33	SR 1401	0.80	1.5" S9.5B	$159,400
2027	2	074-Pitt	Resurfacing	SR 1700	SR 1711	SR 1723	2.71	1.5" S9.5B	$542,000
2027	2	074-Pitt	Resurfacing	SR 2100	US 13	SR 2101	0.21	1.5" S9.5B	$41,600
2027	2	074-Pitt	Resurfacing	SR 2101	SR 2100	SR 1202	0.27	1.5" S9.5B	$54,000
2027	2	074-Pitt	Resurfacing	SR 2102	SR 2100	CUL-DE-SAC	0.38	1.5" S9.5B	$76,000
2027	2	074-Pitt	Resurfacing	SR 2103	SR 2102	SR 2101	0.11	1.5" S9.5B	$22,000
2027	2	074-Pitt	Resurfacing	SR 2114	SR 2116	CUL-DE-SAC	0.04	Mill 1.5" and 1.5" S9.5B	$13,000
2027	2	074-Pitt	Resurfacing	SR 2115	SR 1134	CUL-DE-SAC	0.47	1.5" S9.5B	$94,400
2027	2	074-Pitt	Resurfacing	SR 2116	SR 2115	CUL-DE-SAC	0.14	Mill 1.5" and 1.5" S9.5B	$44,525
2027	2	074-Pitt	Resurfacing	SR 2117	SR 2115	CUL-DE-SAC	0.10	1.5" S9.5B	$20,600
2027	2	074-Pitt	Rehabilitation	SR 1777	NC 33	SR 1755	5.45	2.5" I19.0C and 1.5" S9.5B	$2,316,250
2027	2	074-Pitt	Preservation	SR 1246	SR 1245	NC 222	3.19	FDR and Double Seal	$1,500,000
2027	2	074-Pitt	Preservation	SR 1247	NC 43	SR 1246	5.60	FDR and Double Seal	$2,000,000
2027	2	074-Pitt	Preservation	SR 1413	SR 1400	SR 1415	3.26	Seal - Double	$123,880
2027	2	074-Pitt	Preservation	SR 1414	SR 1413	NC 33	3.12	Seal - Double	$118,560
2027	2	074-Pitt	Preservation	SR 1511	NC 30	SR 1512	1.54	Seal - Double	$58,520
2027	2	074-Pitt	Preservation	SR 1512	US 13 / NC 11	SR 1518	2.49	Seal - Double	$94,620
2027	2	074-Pitt	Preservation	SR 1547	SR 1517	NC 903	2.90	Seal - Double	$110,200
2027	2	074-Pitt	Preservation	SR 1548	SR 1547	NC 903	1.80	Seal - Double	$68,400
2027	2	074-Pitt	Preservation	SR 1549	SR 1551	SR 1550	2.40	Seal - Double	$91,200
2027	3	010-Brunswick	Resurfacing	SR 1130	US 17	NC 130	4.01	Full Depth Patching and 1.5" S9.5B	$1,127,280
2027	3	010-Brunswick	Resurfacing	SR 1135	SR 1134	DEAD END	0.92	Full Depth Patching and 1.5" S9.5B and Widening	$349,600
2027	3	010-Brunswick	Resurfacing	SR 1165	SR 1164	NC 179	1.13	Full Depth Patching and 1.5" S9.5B	$309,375
2027	3	010-Brunswick	Resurfacing	SR 1233	SR 1145	DEAD END	0.06	Full Depth Patching and 1.25" S9.5B	$17,360
2027	3	010-Brunswick	Resurfacing	SR 1329	SR 1330	SR 1328	0.51	Full Depth Patching and 1.5" S9.5B	$571,140
2027	3	010-Brunswick	Resurfacing	SR 1353	SR 1342	SR 1345	0.72	Full Depth Patching and 1.5" S9.5B	$273,600
2027	3	010-Brunswick	Resurfacing	SR 1357	MM 0.37	US 17	0.57	Full Depth Patching and 1.25" S9.5B	$159,600
2027	3	010-Brunswick	Resurfacing	SR 1362	SR 1357	END OF MAINT	0.31	Full Depth Patching and 1.5" S9.5B and Widening	$118,940
2027	3	010-Brunswick	Resurfacing	SR 1552	US 17	END MAINT	0.09	Full Depth Patching and 1.25" S9.5A	$17,000
2027	3	010-Brunswick	Resurfacing	SR 1568	US 17	DEAD END	0.30	Full Depth Patching and 1.25" S9.5A	$27,000
2027	3	010-Brunswick	Resurfacing	SR 1970	SR 1139	END MAINT	0.11	Full Depth Patching and 1.5" S9.5B and Widening	$43,320
2027	3	010-Brunswick	Resurfacing	SR1134	SR1132	NC130	2.39	Full Depth Patching and 1.5" S9.5B and Widening	$1,288,960
2027	3	010-Brunswick	Resurfacing	US 17 N	SR 1316 - 0.14mi	Lula Trl SW	5.88	1.5" S9.5C	$2,381,400
2027	3	010-Brunswick	Resurfacing	US 17 S	Elder Bright Trl NW	SR 1316 + 0.14mi	5.88	1.5" S9.5C	$2,381,400
2027	3	010-Brunswick	Preservation	SR 1113	END PVMT	SR 1112	0.25	1.25" S9.5B	$27,610
2027	3	010-Brunswick	Preservation	SR 1200	SR 1114	END OF MAINT	0.78	1.25" S9.5B	$84,800
2027	3	010-Brunswick	Preservation	SR 1251	SR 1114	DEAD END	0.88	1.25" S9.5B	$96,800
2027	3	010-Brunswick	Preservation	SR 1490	US 17 BUS	DEAD END	0.25	1.25" S9.5B	$27,610
2027	3	010-Brunswick	Preservation	SR 1507	NC 906	SR 1508	0.82	1.25" S9.5B	$96,640
2027	3	010-Brunswick	Preservation	SR 1508	NC 906	END OF MAINT	1.27	1.25" S9.5B	$139,700
2027	3	010-Brunswick	Preservation	SR 1510	US 17 BUS	DEAD END	0.50	1.25" S9.5B	$54,780
2027	3	010-Brunswick	Preservation	SR 1538	NC 906	DEAD END	0.27	1.25" S9.5B	$30,030
2027	3	010-Brunswick	Preservation	SR 1556	NC 906	DEAD END	0.58	1.25" S9.5B	$63,470
2027	3	010-Brunswick	Preservation	SR 1705	US 17 BUS	DEAD END	0.23	1.25" S9.5B	$25,630
2027	3	010-Brunswick	Preservation	SR 1814	SR 1155	SR 1817	0.36	1.25" S9.5B	$40,040
2027	3	010-Brunswick	Preservation	SR 1815	SR 1814	SR 1816	0.05	1.25" S9.5B	$5,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	3	010-Brunswick	Preservation	SR 1816	SR 1815	SR 1817	0.10	1.25" S9.5B	$11,000
2027	3	010-Brunswick	Preservation	SR 1817	SR 1155	SR 1816	0.10	1.25" S9.5B	$11,110
2027	3	010-Brunswick	Preservation	SR 1818	SR 1817	SR 1819	0.18	1.25" S9.5B	$19,800
2027	3	010-Brunswick	Preservation	SR 1819	SR 1820	SR 1818	0.05	1.25" S9.5B	$5,500
2027	3	010-Brunswick	Preservation	SR 1820	SR 1817	SR 1819	0.18	1.25" S9.5B	$19,800
2027	3	010-Brunswick	Preservation	SR 1826	SR 1132	END MAINT	0.78	1.25" S9.5B	$85,800
2027	3	010-Brunswick	Preservation	SR 1885	SR 1132	END MAINT	0.40	1.25" S9.5B	$44,000
2027	3	010-Brunswick	Preservation	SR 1886	SR 1885	SR 1132	0.23	1.25" S9.5B	$25,300
2027	3	010-Brunswick	Preservation	SR 1923	SR 1132	END MAINT	0.87	1.25" S9.5B	$95,700
2027	3	010-Brunswick	Preservation	SR 1924	SR 1923	SR 1923	0.15	1.25" S9.5B	$16,500
2027	3	010-Brunswick	Preservation	SR1138	SR 1137	DEAD END	0.83	1.25" S9.5B	$91,300
2027	3	031-Duplin	Resurfacing	NC50	SR 1830	NC 41	6.04	1.5" S9.5C and Widen	$1,792,395
2027	3	031-Duplin	Resurfacing	SR 1107	SR 1106	US 117	0.32	1.5" S9.5B	$58,868
2027	3	031-Duplin	Resurfacing	SR 1108	NC 24	Sampson County Line	1.35	1.5" S9.5B	$269,000
2027	3	031-Duplin	Resurfacing	SR 1133	SR1146	SR 1101	2.54	1.5" S9.5B	$102,000
2027	3	031-Duplin	Resurfacing	SR 1141	NC 50	NC 11	4.72	1.5" S9.5B and Widen	$1,180,000
2027	3	031-Duplin	Resurfacing	SR 1141	NC 11	US 117	4.29	1.5" S9.5B and Widen	$1,087,000
2027	3	031-Duplin	Resurfacing	SR 1148	US 117	NC 11	4.26	1.5" S9.5B	$852,000
2027	3	031-Duplin	Resurfacing	SR 1192	Sampson County Line	SR 1110	0.78	1.5" S9.5B	$156,000
2027	3	031-Duplin	Resurfacing	SR 1513	Test A	Test B	2.78	1.5" S9.5B	$415,000
2027	3	031-Duplin	Resurfacing	SR 1732	SR 1705	SR 1700	4.24	1.5" S9.5B	$848,000
2027	3	031-Duplin	Resurfacing	SR 1957	NC 11	SR 1141	3.99	1.5" S9.5B	$750,000
2027	3	031-Duplin	Resurfacing	US 117	Powell St	N. Peterson St	0.97	Mill 1.5" and 1.5" S9.5C	$523,800
2027	3	031-Duplin	Resurfacing	US 117	SR 1116	SR 1396	2.01	Mill 1.5" and 1.5" S9.5C	$624,105
2027	3	031-Duplin	Preservation	SR 1359	SR 1306	Dead End	1.33	Patching and Double Seal and Fog Seal	$296,600
2027	3	031-Duplin	Preservation	SR 1362	SR 1361	SR 1004	0.74	Patching	$150,000
2027	3	031-Duplin	Preservation	SR 1534	SR 1306	SR 1533	2.84	Patching	$123,000
2027	3	031-Duplin	Preservation	SR 1724	SR 1961	SR 1800	0.52	Patching	$101,400
2027	3	031-Duplin	Preservation	SR 1908	SR 1927	Dead End	0.40	Patching	$30,000
2027	3	031-Duplin	Preservation	SR 1974	SR 1827	NC 50	1.70	Patching	$331,500
2027	3	065-New Hanover	Resurfacing	SR 1372	SR 2048	SR 1391	0.42	Mill 1.25" and 1.25" S9.5B	$115,775
2027	3	065-New Hanover	Resurfacing	SR 1378	NC 132	SR 2091	0.05	Full Depth Patching and 1.25" S9.5B	$110,000
2027	3	065-New Hanover	Resurfacing	SR 1403	SR 1404	SR 1878	1.75	Full Depth Patching and 1.25" S9.5B	$390,000
2027	3	065-New Hanover	Resurfacing	SR 1403	SR 1878	X-Cross	1.27	Mill 1.5" and 1.5" S9.5B	$390,000
2027	3	065-New Hanover	Resurfacing	SR 1403	SR 1403 South	SR 1404 + .163	2.00	Full Depth Patching and 1.25" S9.5B	$440,000
2027	3	065-New Hanover	Resurfacing	SR 1411	US 117	SR 1411 South + .328 miles	1.84	Rout/Seal Cracks and 1.5" S9.5B	$410,000
2027	3	065-New Hanover	Resurfacing	SR 1934	SR 1929	Cul-De-Sac	0.03	Mill 1.5" and 1.5" S9.5B	$10,000
2027	3	065-New Hanover	Resurfacing	SR 2713	SR 2711	Dead End	0.04	Mill 1.25" and 1.25" S9.5B	$10,000
2027	3	065-New Hanover	Resurfacing	SR 2714	SR 2711	Dead End	0.04	Mill 1.25" and 1.25" S9.5B	$10,000
2027	3	065-New Hanover	Resurfacing	SR 2724	SR 2723	SR 2723 + .214 miles	0.21	Mill 1.25" and 1.25" S9.5B	$50,000
2027	3	065-New Hanover	Resurfacing	SR 2735	C_D_S	C_D_S	0.50	Mill 1.25" and 1.25" S9.5B	$138,050
2027	3	065-New Hanover	Resurfacing	SR 2736	SR 2735	Dead End	0.06	Mill 1.25" and 1.25" S9.5B	$15,675
2027	3	065-New Hanover	Resurfacing	US 17	Pine Grove	US 74	3.86	1.5" S9.5C	$2,761,830
2027	3	065-New Hanover	Resurfacing	US 17	Railroad Track	Hawthorne Road	0.92	1.5" S9.5C	$635,485
2027	3	065-New Hanover	Resurfacing	US 421	Medical Center	Greenfield	1.65	1.5" S9.5C	$1,113,750
2027	3	065-New Hanover	Rehabilitation	SR 1002	US 117	SR 1281	1.86	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5C	$530,000
2027	3	065-New Hanover	Rehabilitation	SR 1573	SR 1539	Seventh ST	2.05	Mill 1.5" and 1.5" S9.5B	$580,000
2027	3	065-New Hanover	Preservation	SR 2164	SR 2148	SR 2242	0.40	1.0" S4.75A	$110,275
2027	3	065-New Hanover	Preservation	SR 2222	NC 133	NC 133 + 0.233 miles	0.23	.75" S4.75A	$64,075
2027	3	065-New Hanover	Preservation	SR 2238	SR 2237	SR 2722	0.68	1.0" S4.75A	$187,550
2027	3	065-New Hanover	Preservation	SR 2355	SR 2348	Cul-De-Sac	0.05	1.0" S4.75A	$14,300
2027	3	065-New Hanover	Preservation	SR 2371	SR 2348	Dead End	0.49	1.0" S4.75A	$135,575
2027	3	065-New Hanover	Preservation	SR 2538	NC 132 S	Cul-De-Sac	0.82	1.0" S4.75A	$224,125
2027	3	065-New Hanover	Preservation	SR 2569	SR 2568	Cul-De-Sac	0.10	1.0" S4.75A	$27,225
2027	3	065-New Hanover	Preservation	SR 2640	SR 2639	SR 2705	0.60	1.0" S4.75A	$164,175
2027	3	065-New Hanover	Preservation	SR 2666	SR 2671	CUL-DE-SAC	0.06	.75" Sand Asphalt	$17,600
2027	3	065-New Hanover	Preservation	SR 2676	SR 2675	SR 2705	0.30	1.0" S4.75A	$81,400
2027	3	067-Onslow	Resurfacing	Belgrade-Swansboro	NC 24	US 17	13.70	1.5" S9.5B	$3,014,000
2027	3	067-Onslow	Resurfacing	Cow Horn Rd	SR 1003	SR 1308	3.02	1.5" S9.5B	$665,280

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	3	067-Onslow	Resurfacing	Curt Holland	SR 1434	EOM	1.15	1.5" S9.5B	$253,000
2027	3	067-Onslow	Resurfacing	Great Neck Landing	SR 1503	Dead End	0.95	1.5" S9.5B and Widen	$209,000
2027	3	067-Onslow	Resurfacing	Lake Cole Rd	SR 1886	SR 1415	0.66	1.5" S9.5B	$145,200
2027	3	067-Onslow	Resurfacing	Lake Cole Rd	SR 1413	SR 1414	0.83	1.5" S9.5B	$182,600
2027	3	067-Onslow	Resurfacing	Morris Landing Rd	SR 1534	End Maint.	1.67	1.5" S9.5B	$367,400
2027	3	067-Onslow	Resurfacing	Old Maplehurst	NC 53	US 17	1.33	1.5" S9.5B	$292,600
2027	3	067-Onslow	Resurfacing	Old Rocky Run Rd	SR 1413	Dead End	0.21	1.5" S9.5B	$46,200
2027	3	067-Onslow	Resurfacing	Queens Creek Rd	NC 24	SR 1503	3.94	1.5" S9.5B	$866,800
2027	3	067-Onslow	Resurfacing	Thomas Holland	SR 1443	EOM	0.45	1.5" S9.5B	$99,220
2027	3	067-Onslow	Resurfacing	US 17 N	Southwest Creek	US 17 BUS	2.67	1.5" S9.5C	$1,331,667
2027	3	067-Onslow	Resurfacing	US 17 S	US 17 BUS	Southwest Creek	2.82	1.5" S9.5C	$1,408,590
2027	3	067-Onslow	Resurfacing	Van Riggs Rd	SR 1501	SR 2220	0.35	1.5" S9.5B	$78,750
2027	3	067-Onslow	Resurfacing	White Oak Ln	SR 1414	Dead End	0.21	Mill .75" and .75" S9.5A	$46,200
2027	3	067-Onslow	Resurfacing	Wood Rd	SR 1415	ESM	0.32	1.5" S9.5A	$70,400
2027	3	067-Onslow	Rehabilitation	Barbara Ave	SR 1406	SR 1417	0.44	Mill 1.5" and 1.5" S9.5B	$96,580
2027	3	067-Onslow	Rehabilitation	Holly Ridge Rd	SR 1531	SR 1535	0.80	Mill 1.25" and 1.25" S9.5B	$176,440
2027	3	067-Onslow	Preservation	Baysden Dr	SR 1308	CDS	0.32	1.25" S9.5B	$59,000
2027	3	067-Onslow	Preservation	Beverly Dr	SR 1994 (Baysden)	EOM	0.13	1.25" S9.5B	$24,000
2027	3	067-Onslow	Preservation	Busch Dr	SR 2092 (Cypress Knee)	SR 2063 (Luke Ln)	0.26	1.25" S9.5B	$48,000
2027	3	067-Onslow	Preservation	Candlewood Dr	SR 1981	End Maint	0.24	1.0" S4.75A	$22,000
2027	3	067-Onslow	Preservation	Carole Dr	US 258	SR 1260	0.20	1.0" S4.75A	$17,730
2027	3	067-Onslow	Preservation	Cinnamon Dr	SR 1501	CDS	0.33	1.0" S4.75A	$30,060
2027	3	067-Onslow	Preservation	Cross Creek Dr	SR 1316	SR 1389	0.20	1.0" S4.75A	$17,170
2027	3	067-Onslow	Preservation	Cypress Knee Dr	SR 1003 (Comfort Rd)	CDS	0.35	1.25" S9.5B	$65,844
2027	3	067-Onslow	Preservation	Dayrell Dr	SR 1501	SR 1657	0.34	1.0" S4.75A	$30,600
2027	3	067-Onslow	Preservation	Diane Ct	SR 1261	CDS	0.06	1.0" S4.75A	$4,930
2027	3	067-Onslow	Preservation	Diane Dr	US 258	CDS	0.39	1.0" S4.75A	$34,920
2027	3	067-Onslow	Preservation	Foxtrace Ln	SR 1501	SR 1657	0.36	1.0" S4.75A	$32,400
2027	3	067-Onslow	Preservation	Glancy Rd	SR 1512	EOM	0.59	1.0" S9.5B	$98,441
2027	3	067-Onslow	Preservation	Huff Ave	SR 1296	SR 1299	0.09	1.0" S9.5B	$13,500
2027	3	067-Onslow	Preservation	King St	SR 1665	End Maint	0.36	1.0" S4.75A	$32,310
2027	3	067-Onslow	Preservation	Lakeview Ave	NC 111	SR 2105	0.52	1.0" S9.5B	$78,000
2027	3	067-Onslow	Preservation	Mahogany Dr	SR 1369 (Shamrock)	SR 1970 (Ponderosa)	0.14	1.25" S9.5B	$26,000
2027	3	067-Onslow	Preservation	N Parker Rd	SR 1407	CDS	0.17	1.0" S4.75A	$14,450
2027	3	067-Onslow	Preservation	Nutfield Dr	SR 1588	SR 1661	0.25	1.0" S4.75A	$22,500
2027	3	067-Onslow	Preservation	S River Dr	SR 2058 (Cross Creek)	SR 2705 (Falls Creek)	0.28	1.25" S9.5B	$52,000
2027	3	067-Onslow	Preservation	Seashore Dr	SR 1512	SR 1559	0.32	1.0" S9.5B	$47,700
2027	3	067-Onslow	Preservation	Shirley Dr	SR 1281	End C&G	0.28	1.0" S4.75A	$24,930
2027	3	067-Onslow	Preservation	Spanish Moss Ct	SR 1296	CDS	0.04	1.0" S9.5B	$6,000
2027	3	067-Onslow	Preservation	Stillwood Cir	SR 1280	SR 1280	0.29	1.0" S4.75A	$24,225
2027	3	067-Onslow	Preservation	Stillwood Ct	SR 1281	CDS	0.06	1.0" S4.75A	$4,845
2027	3	067-Onslow	Preservation	Stillwood Dr	US 258	End Maint.	0.27	1.0" S4.75A	$23,035
2027	3	067-Onslow	Preservation	Sweet Bay Ct	SR 2104	CDS	0.05	1.0" S9.5B	$7,500
2027	3	067-Onslow	Preservation	W Volant St	SR 1657	EOM	0.24	1.0" S4.75A	$22,500
2027	3	067-Onslow	Preservation	Willow Springs Dr E	SR 1296	SR 2106	0.10	1.0" S9.5B	$18,000
2027	3	067-Onslow	Preservation	Willow Springs Dr W	SR 1296	CDS	0.14	1.0" S9.5B	$21,000
2027	3	067-Onslow	Preservation	Winter Rd	SR 1369	SR 1992	0.44	1.25" S9.5B	$81,000
2027	3	067-Onslow	Preservation	Wood Dr	NC 111	SR 2100	0.11	1.0" S9.5B	$18,000
2027	3	071-Pender	Resurfacing	NC 11/53	End C&G East of Whitehouse Ave	US 421	5.43	1.5" S9.5C	$1,687,257
2027	3	071-Pender	Resurfacing	NC 53	US 117 Bus	US 421	8.67	1.5" S9.5C	$2,810,052
2027	3	071-Pender	Resurfacing	SR 1119	NC 210	NC 210	1.53	1.5" S9.5B	$336,600
2027	3	071-Pender	Resurfacing	SR 1120	US 421	NC 53	8.10	Full Depth Patching and 1.5" S9.5B	$1,760,000
2027	3	071-Pender	Resurfacing	SR 1122	US 421	NC 53	1.15	1.5" S9.5B	$253,000
2027	3	071-Pender	Resurfacing	SR 1209	CL	US 421	6.50	Full Depth Patching and 1.5" S9.5B	$1,264,762
2027	3	071-Pender	Resurfacing	SR 1303	SR 1001	SAMPSON CO	0.90	1.5" S9.5B	$198,000
2027	3	071-Pender	Resurfacing	SR 1564	SR 1563	DEAD END	0.60	1.5" S9.5B	$132,000
2027	3	071-Pender	Resurfacing	SR 1573	SR 1002	DEAD END	1.36	1.5" S9.5B	$299,200
2027	3	071-Pender	Resurfacing	SR 1683	NC 210	DEAD END	0.05	1.5" S9.5B	$11,000
2027	3	071-Pender	Preservation	SR 1335	SR 1209	DEAD END	0.79	.75" S4.75A	$84,347

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	3	071-Pender	Preservation	SR 1336	SR 1319	SR 1120	9.00	Full Depth Patching and 1.0" S4.75A	$948,153
2027	3	082-Sampson	Resurfacing	SR 1157	US 701	US 701	2.60	Full Depth Patching and 1.5" S9.5B	$715,000
2027	3	082-Sampson	Resurfacing	SR 1226	SR 1932	SR 1214	2.54	1.5" S9.5B	$698,500
2027	3	082-Sampson	Resurfacing	SR 1227	SR 1226	SR 1231	1.40	Mill Curb and 1.5" S9.5B	$385,000
2027	3	082-Sampson	Resurfacing	SR 1281	SR 1296	SR 1227	0.86	Mill Curb and 1.5" S9.5B	$236,500
2027	3	082-Sampson	Resurfacing	SR 1293	NC 411	Dead End	0.20	1.0" S9.5B	$55,000
2027	3	082-Sampson	Resurfacing	SR 1420	SR 1233	NC 24	1.80	1.5" S9.5B	$0
2027	3	082-Sampson	Resurfacing	SR 1652	SR 1615	Dead End	0.70	1.5" S9.5B	$0
2027	3	082-Sampson	Resurfacing	SR 1713	SR 1711	Dead End	0.70	1.5" S9.5B	$0
2027	3	082-Sampson	Resurfacing	SR 1817	SR 1636	US 701	5.60	1.5" S9.5B	$1,540,000
2027	3	082-Sampson	Resurfacing	SR 1819	US 701	SR 1746	2.78	1.5" S9.5B	$764,500
2027	3	082-Sampson	Resurfacing	SR 1820	SR 1819	SR 1817	1.45	1.5" S9.5B	$398,750
2027	3	082-Sampson	Resurfacing	SR 1851	SR 1296	SR 1852	0.08	Mill Curb and 1.5" S9.5B	$22,000
2027	3	082-Sampson	Resurfacing	SR 1852	SR 1851	SR 1838	0.54	Mill Curb and 1.5" S9.5B	$148,500
2027	3	082-Sampson	Resurfacing	SR 1946	Duplin County	SR 1945	4.33	1.5" S9.5B	$0
2027	3	082-Sampson	Resurfacing	US 421 N	Begin Divided Section	SR 1834	5.38	1.5" S9.5C	$1,887,327
2027	3	082-Sampson	Resurfacing	US 421 S	SR 1839	End Divided Section	4.72	1.5" S9.5C	$1,655,667
2027	3	082-Sampson	Resurfacing	US 701 N	US 421	US 701 BUS	2.60	1.5" S9.5C	$1,053,405
2027	3	082-Sampson	Resurfacing	US 701 S	US 701 BUS	US 421	2.73	1.5" S9.5C	$1,104,030
2027	3	082-Sampson	Preservation	SR 1309	SR 1365	SR 1311	2.88	Seal - Double and Fog Seal	$110,913
2027	3	082-Sampson	Preservation	SR 1311	SR 1006	US 421	7.68	Seal - Double and Fog Seal	$295,770
2027	3	082-Sampson	Preservation	SR 1620	US 13	NC 55	11.24	Seal - Double and Fog Seal	$432,872
2027	3	082-Sampson	Preservation	SR 1845	US 701	US 13	5.00	Seal - Double and Fog Seal	$192,945
2027	4	033-Edgecombe	Resurfacing	NC 33	SR 1605	US 64A	4.66	Mill 1.5" and 1.5" S9.5B	$932,000
2027	4	033-Edgecombe	Resurfacing	SR 1212	End C&G	SR 1207	1.84	1.5" S9.5B	$303,600
2027	4	033-Edgecombe	Resurfacing	SR 1212	SR 1211	End C&G	0.93	Mill 1.5" and 1.5" S9.5B	$367,350
2027	4	033-Edgecombe	Resurfacing	SR 1252	US 64A	NC 97	1.99	1.5" S9.5B	$268,650
2027	4	033-Edgecombe	Resurfacing	SR 1308E	SR 1211	033	1.08	Mill 1.5" and 1.5" S9.5B	$199,800
2027	4	033-Edgecombe	Resurfacing	SR 1308W	NC 33	SR 1211	1.07	Mill 1.5" and 1.5" S9.5B	$197,950
2027	4	033-Edgecombe	Resurfacing	SR 1346	SR 1207	US 64A	1.99	1.5" S9.5B	$328,350
2027	4	033-Edgecombe	Resurfacing	SR 1600	NC-33	US-64A	0.89	1.5" S9.5B	$120,150
2027	4	033-Edgecombe	Resurfacing	SR 1606	NC-42	SR 1608	4.91	1.5" S9.5B	$664,200
2027	4	033-Edgecombe	Resurfacing	SR 1607	US 64A	Dead End	0.80	1.5" S9.5B	$108,000
2027	4	033-Edgecombe	Resurfacing	SR 1608	NC-33	NC-42	4.55	Mill 1.5" and 1.5" S9.5B	$767,050
2027	4	033-Edgecombe	Resurfacing	SR 1610	NC-42	Pitt County Line	1.21	1.5" S9.5B	$163,350
2027	4	033-Edgecombe	Resurfacing	SR 1621	SR 1608	Pitt County Line	0.10	1.5" S9.5B	$13,500
2027	4	033-Edgecombe	Resurfacing	SR 1631	SR 1608	Dead End	0.35	1.5" S9.5B	$47,250
2027	4	033-Edgecombe	Resurfacing	US 64A	US 258	Pitt CL	7.48	Mill 1.5" and 1.5" S9.5B	$1,466,000
2027	4	033-Edgecombe	Preservation	NC 43	SR 1126 South End	US 64A	12.71	Crack Seal	$89,438
2027	4	033-Edgecombe	Preservation	SR 1113	SR 1108	SR 1004	0.77	Microsurface	$50,050
2027	4	033-Edgecombe	Preservation	SR 1347	US 64A	SR 13474	0.80	1.25" S9.5B	$90,000
2027	4	033-Edgecombe	Preservation	SR 1359	SR 1347	Dead End	0.10	1.25" S9.5B	$11,250
2027	4	033-Edgecombe	Preservation	SR 1410	SR 1409	SR 1404	1.23	Microsurface	$79,950
2027	4	033-Edgecombe	Preservation	SR 1503	NC 97	US 258	1.25	Microsurface	$81,250
2027	4	033-Edgecombe	Preservation	SR 1523	US 64A	US 258	1.54	Microsurface	$100,100
2027	4	033-Edgecombe	Preservation	SR 1539	US-64A	SR 1561	0.51	Microsurface	$33,150
2027	4	033-Edgecombe	Preservation	SR 1559	US 64 Alt	Dead End	0.17	1.25" S9.5B	$19,125
2027	4	033-Edgecombe	Preservation	SR 1561	SR 1539	End Maintenance	0.15	Microsurface	$9,750
2027	4	033-Edgecombe	Preservation	SR 1565	US 64 Alt	Dead End	0.30	1.25" S9.5B	$33,750
2027	4	033-Edgecombe	Preservation	SR 1567	NC 122	Dead End	0.33	1.25" S9.5B	$37,125
2027	4	033-Edgecombe	Preservation	SR 1571	SR 1539	End Maintenance	0.10	Microsurface	$6,500
2027	4	033-Edgecombe	Preservation	SR 1585	SR 1523	Dead End	0.13	Microsurface	$8,450
2027	4	033-Edgecombe	Preservation	SR 1586	SR 1523	Dead End	0.15	Microsurface	$9,750
2027	4	033-Edgecombe	Preservation	SR 1632	SR 1606	Dead End	0.31	1.25" S9.5B	$37,975
2027	4	033-Edgecombe	Preservation	SR 1633	SR 1632	Dead End	0.14	1.25" S9.5B	$15,750
2027	4	042-Halifax	Resurfacing	NC 481	I-95	NC 481 Bus	4.20	Mill 1.5" and 1.5" S9.5C	$892,500
2027	4	042-Halifax	Resurfacing	SR 1100	SR 1003	SR 1003	3.95	1.5" S9.5B	$523,375
2027	4	042-Halifax	Resurfacing	SR 1103	SR 1003	SR 1114	2.85	1.5" S9.5B	$377,625
2027	4	042-Halifax	Resurfacing	SR 1210	I-95	SR 1002	2.18	1.5" S9.5B	$288,850

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	4	042-Halifax	Resurfacing	SR 1216	NC 561	SR 1002	4.20	1.5" S9.5B	$556,500
2027	4	042-Halifax	Resurfacing	SR 1220	SR 1220	SR 1243	0.51	1.5" S9.5B	$68,850
2027	4	042-Halifax	Resurfacing	SR 1227	SR 1338	Edge of Pavement	0.86	1.5" S9.5B	$124,700
2027	4	042-Halifax	Resurfacing	SR 1240	NC 481	Dead End	0.14	1.5" S9.5B	$18,900
2027	4	042-Halifax	Resurfacing	SR 1243	NC 481	SR 1220	0.05	1.5" S9.5B	$7,250
2027	4	042-Halifax	Resurfacing	SR 1317	NC 561	Nash County Line	2.23	1.5" S9.5B	$323,350
2027	4	042-Halifax	Resurfacing	SR 1327	SR 1214	Nash Co	3.66	1.5" S9.5B	$530,700
2027	4	042-Halifax	Resurfacing	SR 1342	SR 1338	Nash County Line	1.85	1.5" S9.5B	$247,050
2027	4	042-Halifax	Resurfacing	SR 1418	NC 48	SR 1415	1.77	1.5" S9.5B	$256,650
2027	4	042-Halifax	Resurfacing	SR 1611	NC 48	SR 1600	2.21	1.25" S9.5B	$408,850
2027	4	042-Halifax	Resurfacing	SR 1625	SR 1627	Dead End	1.61	1.5" S9.5B	$234,900
2027	4	042-Halifax	Resurfacing	SR 1820	NC 903	NC 125	4.33	1.5" S9.5B	$588,300
2027	4	042-Halifax	Resurfacing	US 301	SR 1125	NC 561	5.54	Mill 1.5" and 1.5" S9.5C	$886,950
2027	4	042-Halifax	Preservation	NC 125	US 301	SR 1733	5.32	Crack Seal	$33,250
2027	4	042-Halifax	Preservation	SR 1103	US 158	Dead End	0.63	Microsurface	$40,950
2027	4	042-Halifax	Preservation	SR 1112	SR 1112	SR 1103	4.85	Seal - Double and Fog Seal	$182,350
2027	4	042-Halifax	Preservation	SR 1132	SR 1131	Dead End	1.35	Seal - Double	$50,875
2027	4	042-Halifax	Preservation	SR 1210	NC 903	SR 1001	4.06	Crack Seal	$25,375
2027	4	042-Halifax	Preservation	SR 1416	SR 1001	SR 1415	1.68	Crack Seal	$10,500
2027	4	042-Halifax	Preservation	SR 1460	SR 1112	SR 1103	1.49	Microsurface	$86,850
2027	4	042-Halifax	Preservation	SR 1683	NC 48	NC 125	1.49	Crack Seal	$9,313
2027	4	042-Halifax	Preservation	SR 1683	NC 561	NC 561	1.55	Seal - Double and Fog Seal	$73,625
2027	4	042-Halifax	Preservation	SR 1809	SR 1820	NC 903	4.36	Seal - Double and Fog Seal	$207,100
2027	4	042-Halifax	Preservation	SR 1811	SR 1810	SR 1812	2.47	Seal - Double and Fog Seal	$117,325
2027	4	042-Halifax	Preservation	SR 1813	US 258	EOP	1.31	Seal - Double and Fog Seal	$62,225
2027	4	042-Halifax	Preservation	US 158	SR 1432	NC 48	4.63	Crack Seal	$28,938
2027	4	051-Johnston	Resurfacing	SR 1001	Begin C&G	US 301	0.75	1.5" S9.5B	$221,250
2027	4	051-Johnston	Resurfacing	SR 1001	SR 2335	Begin C&G	3.87	1.5" S9.5B	$522,450
2027	4	051-Johnston	Resurfacing	SR 1004	Wake County Line	W Stallings Street	2.37	1.5" S9.5B	$319,950
2027	4	051-Johnston	Resurfacing	SR 1008	NC 50	US 701	2.39	1.5" S9.5B	$322,650
2027	4	051-Johnston	Resurfacing	SR 1113	NC 96	NC 50	5.83	1.5" S9.5B	$787,050
2027	4	051-Johnston	Resurfacing	SR 1165	SR 1163	US 301	0.67	1.5" S9.5B	$90,045
2027	4	051-Johnston	Resurfacing	SR 1304	SR 1168	NC 50	1.69	1.5" S9.5B	$227,475
2027	4	051-Johnston	Resurfacing	SR 1307	SR 1303	Harnett County Line	1.86	1.5" S9.5B	$251,100
2027	4	051-Johnston	Resurfacing	SR 1313	Harnett County Line	SR 1309	3.14	1.5" S9.5B	$423,360
2027	4	051-Johnston	Resurfacing	SR 1324	NC 50	Dead End	1.44	1.5" S9.5B	$194,400
2027	4	051-Johnston	Resurfacing	SR 1325	SR 1324	Dead End	0.76	1.5" S9.5B	$102,600
2027	4	051-Johnston	Resurfacing	SR 1332	SR 1335	SR 1334	1.79	1.5" S9.5B	$241,515
2027	4	051-Johnston	Resurfacing	SR 1333	SR 1335	SR 1334	1.26	1.5" S9.5B	$169,560
2027	4	051-Johnston	Resurfacing	SR 1335	SR 1162	NC 210	4.54	1.5" S9.5B	$612,900
2027	4	051-Johnston	Resurfacing	SR 1336	SR 1335	SR 1334	3.04	1.5" S9.5B	$410,400
2027	4	051-Johnston	Resurfacing	SR 1342	SR 1343	SR 1341	1.21	1.5" S9.5B	$163,350
2027	4	051-Johnston	Resurfacing	SR 1382	SR 1330	Dead End	1.14	1.5" S9.5B	$153,900
2027	4	051-Johnston	Resurfacing	SR 1399	SR 1330	NC 50	1.77	1.5" S9.5B and Widen	$431,750
2027	4	051-Johnston	Resurfacing	SR 1516	SR 1010	Dead End	1.45	1.5" S9.5B	$196,290
2027	4	051-Johnston	Resurfacing	SR 1528	NC 50	Dead End	1.29	1.5" S9.5B	$173,610
2027	4	051-Johnston	Resurfacing	SR 1544	SR 1309	NC 50	1.34	1.5" S9.5B	$180,900
2027	4	051-Johnston	Resurfacing	SR 1552	W Stallings Street	US 70 Bus W	0.65	Mill 1.5" and 1.5" S9.5B	$191,750
2027	4	051-Johnston	Resurfacing	SR 1579	SR 1010	SR 1010	1.38	1.5" S9.5B	$186,840
2027	4	051-Johnston	Resurfacing	SR 1583	SR 1555	SR 2073	0.68	1.5" S9.5B	$91,800
2027	4	051-Johnston	Resurfacing	SR 1709	SR 1700	W Stallings Street	1.37	1.5" S9.5B	$184,950
2027	4	051-Johnston	Resurfacing	SR 1921	US 301	SR 1003	0.65	Mill 1.5" and 1.5" S9.5B	$130,000
2027	4	051-Johnston	Resurfacing	SR 1927	SR 2309	SR 1928	3.25	1.5" S9.5B	$958,750
2027	4	051-Johnston	Resurfacing	SR 1929	SR 1003	SR 1928	0.85	1.5" S9.5B	$114,750
2027	4	051-Johnston	Resurfacing	SR 2118	NC 42	SR 2117	1.30	1.5" S9.5B	$175,500
2027	4	051-Johnston	Resurfacing	SR 2148	NC 222	Wilson CL	1.97	1.5" S9.5B	$265,950
2027	4	051-Johnston	Resurfacing	SR 2364	SR 2320	SR 2363	0.92	1.5" S9.5B	$124,200
2027	4	051-Johnston	Resurfacing	SR 2383	S Railroad Street	SR 2593	0.74	1.5" S9.5B	$127,650
2027	4	051-Johnston	Resurfacing	SR 2393	SR 2302	SR 1927	1.28	1.5" S9.5B	$185,600

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	4	051-Johnston	Resurfacing	SR 2410	SR 2393	End of State Maintenance	0.12	1.5" S9.5B	$16,200
2027	4	051-Johnston	Resurfacing	SR 2508	SR 1007	SR 1007	1.83	1.5" S9.5B	$247,050
2027	4	051-Johnston	Resurfacing	SR 2519	US 70	SR 2523	2.92	1.5" S9.5B	$394,200
2027	4	051-Johnston	Resurfacing	SR 2542	SR 1007	SR 2543	1.60	1.5" S9.5B	$216,000
2027	4	051-Johnston	Resurfacing	SR 2560	US 70 BUS	Martin Luther King Dr	0.83	1.5" S9.5B	$136,950
2027	4	051-Johnston	Resurfacing	SR 2687	Kilgo Street	Dead End	0.68	1.5" S9.5B	$91,800
2027	4	051-Johnston	Resurfacing	SR 2707	SR 1307	Dead End	0.67	1.5" S9.5B	$90,315
2027	4	051-Johnston	Resurfacing	SR 2708	SR 2707	Dead End	0.52	1.5" S9.5B	$69,660
2027	4	051-Johnston	Resurfacing	US 301	SR 2159 +.3 Miles	Wilson County Line	1.48	Mill 1.5" and 1.5" S9.5C	$743,700
2027	4	051-Johnston	Resurfacing	US 301	Poole Drive + .10 Miles	SR 2332	1.20	Mill 1.5" and 1.5" S9.5C	$255,000
2027	4	051-Johnston	Resurfacing	US 301	SR 1927	Poole Drive + .10 Mile	0.68	Mill 1.5" and 1.5" S9.5B	$200,600
2027	4	051-Johnston	Resurfacing	US 301	US 70	SR 1927	1.18	Mill 1.5" and 1.5" S9.5C	$592,950
2027	4	051-Johnston	Preservation	SR 1393	SR 1356	SR 2718	0.25	1.25" S9.5B	$28,125
2027	4	051-Johnston	Preservation	SR 1394	SR 1393	Cul-De-Sac	0.07	1.25" S9.5B	$7,875
2027	4	051-Johnston	Preservation	SR 1395	SR 1393	Cul-De-Sac	0.07	1.25" S9.5B	$7,875
2027	4	051-Johnston	Preservation	SR 1662	Cul-De-Sac	Cul-De-Sac	0.08	1.25" S9.5B	$9,000
2027	4	051-Johnston	Preservation	SR 1663	SR 1704	Cul-De-Sac	0.38	1.25" S9.5B	$42,750
2027	4	051-Johnston	Preservation	SR 1663	NC 42	Cul-De-Sac	0.68	1.25" S9.5B	$76,500
2027	4	051-Johnston	Preservation	SR 1817	SR 1010	Cul-De-Sac	0.33	1.25" S9.5B	$37,125
2027	4	051-Johnston	Preservation	SR 1818	SR 1817	Cul-De-Sac	0.05	1.25" S9.5B	$5,625
2027	4	051-Johnston	Preservation	SR 1892	SR 1663	SR 1532	0.66	1.25" S9.5B	$74,250
2027	4	051-Johnston	Preservation	SR 1892	SR 1892	Cul-De-Sac	0.44	1.25" S9.5B	$49,500
2027	4	051-Johnston	Preservation	SR 1894	SR 1893	Cul-De-Sac	0.10	1.25" S9.5B	$11,250
2027	4	051-Johnston	Preservation	SR 1896	Cul-De-Sac	Cul-De-Sac	0.32	1.25" S9.5B	$36,000
2027	4	051-Johnston	Preservation	SR 1985	SR 1893	Cul-De-Sac	0.09	1.25" S9.5B	$10,125
2027	4	051-Johnston	Preservation	SR 2027	SR 2073	Cul-De-Sac	0.10	1.25" S9.5B	$11,250
2027	4	051-Johnston	Preservation	SR 2034	SR 1903	Cul-De-Sac	0.65	1.25" S9.5B	$73,125
2027	4	051-Johnston	Preservation	SR 2035	SR 2034	Cul-De-Sac	0.13	1.25" S9.5B	$14,625
2027	4	051-Johnston	Preservation	SR 2036	SR 2034	Cul-De-Sac	0.08	1.25" S9.5B	$9,000
2027	4	051-Johnston	Preservation	SR 2073	SR 1583	SR 2073	0.89	1.25" S9.5B	$100,125
2027	4	051-Johnston	Preservation	SR 2075	SR 2073	Cul-De-Sac	0.06	1.25" S9.5B	$6,750
2027	4	051-Johnston	Preservation	SR 2079	SR 1572	Cul-De-Sac	0.11	1.25" S9.5B	$12,375
2027	4	051-Johnston	Preservation	SR 2185	SR 2110	Cul-De-Sac	0.46	1.25" S9.5B	$51,750
2027	4	051-Johnston	Preservation	SR 2187	NC 222	Cul-De-Sac	0.29	1.25" S9.5B	$32,625
2027	4	051-Johnston	Preservation	SR 2188	SR 2187	Cul-De-Sac	0.07	1.25" S9.5B	$7,875
2027	4	051-Johnston	Preservation	SR 2258	SR 1524	Cul-De-Sac	0.35	1.25" S9.5B	$39,375
2027	4	051-Johnston	Preservation	SR 2259	SR 2258	Cul-De-Sac	0.15	1.25" S9.5B	$16,875
2027	4	051-Johnston	Preservation	SR 2260	SR 2259	Cul-De-Sac	0.09	1.25" S9.5B	$10,125
2027	4	051-Johnston	Preservation	SR 2307	US 70A	SR 2306	1.43	1.25" S9.5B	$160,875
2027	4	051-Johnston	Preservation	SR 2507	SR 1007	I-95	2.52	1.25" S9.5B	$283,500
2027	4	051-Johnston	Preservation	SR 2546	SR 1007	SR 2553	0.52	1.25" S9.5B	$59,800
2027	4	051-Johnston	Preservation	SR 2690	SR 1707	Cul-De-Sac	0.43	1.25" S9.5B	$48,375
2027	4	051-Johnston	Preservation	SR 2691	SR 2690	Cul-De-Sac	0.09	1.25" S9.5B	$10,125
2027	4	051-Johnston	Preservation	Sr 2692	SR 2690	Cul-De-Sac	0.05	1.25" S9.5B	$5,625
2027	4	051-Johnston	Preservation	SR 2696	SR 2695	Cul-De-Sac	0.73	1.25" S9.5B	$96,725
2027	4	051-Johnston	Preservation	SR 2698	SR 1703	CUL-DE-SAC	0.39	1.25" S9.5B	$51,675
2027	4	051-Johnston	Preservation	SR 2699	SR 2698	CUL-DE-SAC	0.04	1.25" S9.5B	$4,500
2027	4	051-Johnston	Preservation	SR 2718	SR 1393	Cul-De-Sac	0.19	1.25" S9.5B	$21,375
2027	4	051-Johnston	Preservation	SR 2719	SR 1393	Cul-De-Sac	0.05	1.25" S9.5B	$5,625
2027	4	051-Johnston	Preservation	SR 2813	SR 1903	Cul-De-Sac	0.59	1.25" S9.5B	$66,375
2027	4	051-Johnston	Preservation	SR 2814	SR 2813	SR 2831	0.25	1.25" S9.5B	$28,125
2027	4	051-Johnston	Preservation	SR 2827	SR 2813	Summit Overlook Dr	0.19	1.25" S9.5B	$21,375
2027	4	051-Johnston	Preservation	SR 2828	SR 2827	Cul-De-Sac	0.05	1.25" S9.5B	$5,625
2027	4	051-Johnston	Preservation	SR 2829	SR 2827	Neuse Landing Dr	0.34	1.25" S9.5B	$38,250
2027	4	051-Johnston	Preservation	SR 2830	SR 2814	SR 2829	0.11	1.25" S9.5B	$12,375
2027	4	051-Johnston	Preservation	SR 2831	SR 2814	Cul-De-Sac	0.13	1.25" S9.5B	$14,625
2027	4	051-Johnston	Preservation	SR 2991	SR 2990	Cul-De-Sac	0.06	1.25" S9.5B	$6,750
2027	4	051-Johnston	Preservation	SR 2992	SR 2990	Cul-De-Sac	0.28	1.25" S9.5B	$31,500
2027	4	051-Johnston	Preservation	SR 2993	SR 2992	Cul-De-Sac	0.16	1.25" S9.5B	$18,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	4	051-Johnston	Preservation	SR 2994	SR 2992	Cul-De-Sac	0.04	1.25" S9.5B	$4,500
2027	4	051-Johnston	Preservation	SR 2995	NC 210	Cul-De-Sac	0.44	1.25" S9.5B	$49,500
2027	4	051-Johnston	Preservation	SR 2996	SR 2995	Cul-De-Sac	0.10	1.25" S9.5B	$11,250
2027	4	051-Johnston	Preservation	SR 3200	SR 2696	Cul-De-sac	0.05	1.25" S9.5B	$6,125
2027	4	051-Johnston	Preservation	SR 3201	SR 2696	Cul-De-Sac	0.08	1.25" S9.5B	$9,800
2027	4	051-Johnston	Preservation	SR 3202	SR 3203	Cul-De-Sac	0.05	1.25" S9.5B	$6,125
2027	4	051-Johnston	Preservation	SR 3203	SR 2698	SR 2696	0.22	1.25" S9.5B	$28,885
2027	4	051-Johnston	Preservation	SR 3243	SR 2696	Cul-De-Sac	0.03	1.25" S9.5B	$3,375
2027	4	051-Johnston	Preservation	SR 3244	SR 3203	Cul-De-Sac	0.02	1.25" S9.5B	$2,250
2027	4	051-Johnston	Preservation	SR 3245	SR 2698	CUL-DE-SAC	0.31	1.25" S9.5B	$41,075
2027	4	051-Johnston	Preservation	SR 3246	SR 2696	CUL-DE-SAC	0.03	1.25" S9.5B	$3,375
2027	4	051-Johnston	Preservation	SR 3247	SR 2696	CUL-DE-SAC	0.03	1.25" S9.5B	$3,375
2027	4	051-Johnston	Preservation	SR 3248	SR 3245	CUL-DE-SAC	0.11	1.25" S9.5B	$12,375
2027	4	051-Johnston	Preservation	SR 3249	SR 3245	SR 3248	0.09	1.25" S9.5B	$10,125
2027	4	051-Johnston	Preservation	SR 3250	SR 3245	CUL-DE-SAC	0.04	1.25" S9.5B	$4,500
2027	4	051-Johnston	Preservation	SR 3730	SR 1330	SR 3731	0.13	1.25" S9.5B	$14,625
2027	4	051-Johnston	Preservation	SR 3731	N Farm House Trail	Cul-De-Sac	0.23	1.25" S9.5B	$25,875
2027	4	051-Johnston	Preservation	SR 3732	SR 3731	Cul-De-Sac	0.06	1.25" S9.5B	$6,750
2027	4	064-Nash	Resurfacing	NC 97 East	Nashville Road	Edgecombe County Line	1.20	Mill 1.5" and 1.5" S9.5B	$216,000
2027	4	064-Nash	Resurfacing	NC-43	Swift Creek School Rd	Halifax County Line	5.45	Mill 1.5" and 1.5" S9.5B	$2,616,000
2027	4	064-Nash	Resurfacing	SR 1001	Mile Post 5.54	Mile Post 6.30	0.76	1.5" S9.5B	$209,000
2027	4	064-Nash	Resurfacing	SR 1002	Franklin County Line	NC 581	3.56	1.5" S9.5B	$587,400
2027	4	064-Nash	Resurfacing	SR 1123	SR 1124	US 264 Alt	0.84	1.5" S9.5B	$121,800
2027	4	064-Nash	Resurfacing	SR 1154	SR 1155	Franklin County Line	0.37	1.5" S9.5B	$53,650
2027	4	064-Nash	Resurfacing	SR 1324	SR 1310	Franklin County Line	3.03	1.5" S9.5B	$439,350
2027	4	064-Nash	Resurfacing	SR 1324	SR 1603	SR 1717	1.95	1.5" S9.5B	$282,750
2027	4	064-Nash	Resurfacing	SR 1324	NC 43	Dead End	0.26	1.25" S9.5B	$31,850
2027	4	064-Nash	Resurfacing	SR 1325	NC 58	SR 1310	1.38	1.25" S9.5B	$155,250
2027	4	064-Nash	Resurfacing	SR 1440	Sykes Road	Dead End	0.87	1.25" S9.5B	$97,875
2027	4	064-Nash	Resurfacing	SR 1540	US-301	Mile Post 0.21	0.21	1.5" S9.5B	$27,825
2027	4	064-Nash	Resurfacing	SR 1541	Church Street	NC-43	1.70	1.5" S9.5B	$467,500
2027	4	064-Nash	Resurfacing	SR 1541	NC-43	Sutters Creek Blvd	0.49	Mill 1.5" and 1.5" S9.5B	$95,550
2027	4	064-Nash	Resurfacing	SR 1541	Sutters Creek Blvd	County Club Rd	0.47	Mill 1.5" and 1.5" S9.5B	$84,600
2027	4	064-Nash	Resurfacing	SR 1607	SR 1604	NC 43	1.60	1.5" S9.5B	$264,000
2027	4	064-Nash	Resurfacing	SR 1707	SR 1544	SR 1603	2.13	1.5" S9.5B	$351,450
2027	4	064-Nash	Resurfacing	SR 1816	SR 1753	Dead End	1.19	1.5" S9.5B	$172,550
2027	4	064-Nash	Resurfacing	SR 1917	SR 1921	SR 1145	1.91	1.25" S9.5B	$276,950
2027	4	064-Nash	Resurfacing	SR 1921	NC 581	SR 1917	1.09	1.25" S9.5B	$179,850
2027	4	064-Nash	Resurfacing	SR 1928	SR 1001	SR 1145	1.26	1.5" S9.5B	$182,700
2027	4	064-Nash	Resurfacing	SR 1942	E Hornes Church Road	Bloomery Road	1.04	1.5" S9.5B	$150,800
2027	4	064-Nash	Resurfacing	US 301	Nash County Line	NC 97	5.49	Mill 1.5" and 1.5" S9.5C	$1,500,000
2027	4	064-Nash	Resurfacing	US 301	NC 97	Nash County Line	5.45	Mill 1.5" and 1.5" S9.5C	$1,500,000
2027	4	064-Nash	Resurfacing	US-264 ALT	Mile Post 5.80	Mile Post 7.60	1.80	1.5" S9.5B	$495,000
2027	4	064-Nash	Resurfacing	US-301 Bus S	Church St	Church St	1.17	Mill 1.5" and 1.5" S9.5B	$210,600
2027	4	064-Nash	Resurfacing	US-64 Alt	Mile Post 10.7	US-64	2.32	1.5" S9.5B	$345,000
2027	4	064-Nash	Preservation	SR 1139	NC-581	Dead End	0.84	1.25" S9.5B	$94,500
2027	4	064-Nash	Preservation	SR 1178	SR 1147	Dead End	0.20	1.0" S4.75A	$22,500
2027	4	064-Nash	Preservation	SR 1181	NC-581	Mile Post 0.25	0.25	1.0" S4.75A	$28,125
2027	4	064-Nash	Preservation	SR 1183	NC 581	Roseheath Ct	0.20	1.25" S9.5B	$22,500
2027	4	064-Nash	Preservation	SR 1185	SR 1175	Dead End	0.21	1.25" S9.5B	$23,625
2027	4	064-Nash	Preservation	SR 1302	SR 1301	NC-58	1.80	Seal - Double	$45,000
2027	4	064-Nash	Preservation	SR 1687	SR 1604	Dead End	0.47	1.25" S9.5B	$52,875
2027	4	064-Nash	Preservation	SR 1688	SR 1687	Dead End	0.10	1.25" S9.5B	$11,250
2027	4	064-Nash	Preservation	SR 1696	SR 1604	Dead End	0.65	1.25" S9.5B	$73,125
2027	4	064-Nash	Preservation	SR 1753	NC-58	SR 1745	1.65	1.0" S4.75A	$166,250
2027	4	064-Nash	Preservation	SR 1755	NC-58	Dead End	0.36	1.25" S9.5B	$40,500
2027	4	064-Nash	Preservation	SR 1790	SR 1745	SR 1741	0.15	1.0" S4.75A	$16,875
2027	4	064-Nash	Preservation	SR 1791	NC-97	SR 1790	0.09	1.0" S4.75A	$11,925
2027	4	064-Nash	Preservation	SR 1816	SR 1753	Dead End	1.19	1.0" S4.75A	$133,875

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	4	064-Nash	Preservation	SR 1855	SR 1854	SR 1868	0.20	1.0" S4.75A	$22,500
2027	4	064-Nash	Preservation	SR 1856	Dead End	Dead End	0.07	1.0" S4.75A	$7,875
2027	4	064-Nash	Preservation	SR 1867	SR 1854	Dead End	0.10	1.0" S4.75A	$11,250
2027	4	064-Nash	Preservation	SR 1868	SR 1854	Dead End	0.57	1.0" S4.75A	$64,125
2027	4	064-Nash	Preservation	SR 1869	SR 1507	Dead End	0.06	1.0" S4.75A	$7,350
2027	4	064-Nash	Preservation	SR 1939	NC-97	SR 1984	1.22	1.0" S4.75A	$129,250
2027	4	064-Nash	Preservation	SR 1984	Wilson County Line	Dead End	1.06	1.0" S4.75A	$122,500
2027	4	064-Nash	Preservation	SR 1998	SR 1145	Dead End	0.20	1.25" S9.5B	$22,500
2027	4	064-Nash	Preservation	SR 2104	SR 1145	SR 1741	0.25	1.25" S9.5B	$28,125
2027	4	064-Nash	Preservation	SR 2206	SR 1604	Dead End	0.07	.75" S4.75A	$6,125
2027	4	064-Nash	Preservation	SR 2310	SR 1604	Dead End	0.14	1.25" S9.5B	$15,750
2027	4	064-Nash	Preservation	SR 2320	SR 1687	Dead End	0.11	1.25" S9.5B	$12,375
2027	4	064-Nash	Preservation	SR1182	SR-1181	Dead End	0.08	1.0" S4.75A	$9,000
2027	4	096-Wayne	Resurfacing	SR 1006	NC 55	US 13	6.67	1.5" S9.5B	$900,450
2027	4	096-Wayne	Resurfacing	SR 110	SR 1006	SR 1132	7.21	1.5" S9.5B	$973,350
2027	4	096-Wayne	Resurfacing	SR 1113	SR 1120	NC 55	3.07	1.25" S9.5B	$414,450
2027	4	096-Wayne	Resurfacing	SR 1325	SR 1324	SR 1002	1.40	1.25" S9.5B	$157,500
2027	4	096-Wayne	Resurfacing	SR 1341	NC 222	SR 1342	1.19	1.25" S9.5B	$145,775
2027	4	096-Wayne	Resurfacing	SR 1412	SR 1325	Dead End	0.27	1.25" S9.5B	$30,375
2027	4	096-Wayne	Resurfacing	SR 1426	SR 1002	SR 1336	1.29	1.25" S9.5B	$145,125
2027	4	096-Wayne	Resurfacing	SR 1458	NC 222	Dead End	0.63	1.25" S9.5B	$70,875
2027	4	096-Wayne	Resurfacing	SR 1571	NC 111	SR 1556	1.95	1.5" S9.5B	$263,250
2027	4	096-Wayne	Resurfacing	SR 1576	US 13	SR 1556	1.40	1.25" S9.5B	$157,163
2027	4	096-Wayne	Resurfacing	SR 1577	SR 1556	SR 1576	0.39	1.25" S9.5B	$43,875
2027	4	096-Wayne	Resurfacing	SR 1709	SR 1003	US 13	1.20	Mill 1.5" and 1.5" S9.5B	$207,000
2027	4	096-Wayne	Resurfacing	SR 1711	SR 1709	Dead End	2.31	1.5" S9.5B	$311,850
2027	4	096-Wayne	Resurfacing	SR 1726	NC 111	NC 111	3.23	1.5" S9.5B	$436,050
2027	4	096-Wayne	Resurfacing	SR 1731	US 70	SR 1719	1.59	1.25" S9.5B	$178,875
2027	4	096-Wayne	Resurfacing	SR 1733	SR 1731	Lenoir County Line	1.32	1.25" S9.5B	$148,500
2027	4	096-Wayne	Resurfacing	SR 1744	SR 1932	NC 111	5.41	1.5" S9.5B	$730,350
2027	4	096-Wayne	Resurfacing	SR 1756	SR 1733	Lenoir County Line	0.33	1.25" S9.5B	$37,125
2027	4	096-Wayne	Resurfacing	SR 1758	SR 1711	Dead End	1.22	1.5" S9.5B	$164,700
2027	4	096-Wayne	Resurfacing	SR 1759	SR 1709	SR 1711	0.75	1.5" S9.5B	$101,250
2027	4	096-Wayne	Resurfacing	SR 1895	SR 1711	Dead End	0.81	1.5" S9.5B	$161,400
2027	4	096-Wayne	Resurfacing	SR 1896	SR 1895	Cul-De-Sac	0.14	1.5" S9.5B	$28,600
2027	4	096-Wayne	Resurfacing	SR 1930	SR 1932	US 117 ALT	2.32	1.5" S9.5B	$382,800
2027	4	096-Wayne	Resurfacing	SR 2240	SR 1895	Cul-de-Sac	0.16	Mill 1.5" and 1.5" S9.5B	$31,600
2027	4	096-Wayne	Resurfacing	US 117	SR 2314	SR 2313	0.65	Mill 1.5" and 1.5" S9.5C	$329,640
2027	4	096-Wayne	Resurfacing	US 13	SR 1572	Greene County Line	3.31	Mill 2.0" and 2.0" S9.5C	$965,700
2027	4	096-Wayne	Resurfacing	US 13	SR 1003	SR 1705	1.64	Mill 2.0" and 2.0" S9.5C	$475,600
2027	4	096-Wayne	Preservation	SR 1001	Johnston County Line	NC 222	2.10	Seal - Double and Fog Seal	$94,500
2027	4	096-Wayne	Preservation	SR 1151	US 13	Dead End	0.64	Crack Seal	$4,019
2027	4	096-Wayne	Preservation	SR 1281	SR 1131	Cul-De-Sac	0.32	Crack Seal	$1,994
2027	4	096-Wayne	Preservation	SR 1282	SR 1131	SR 1281	0.19	Crack Seal	$1,156
2027	4	096-Wayne	Preservation	SR 1296	SR 1131	SR 1281	0.25	Crack Seal	$1,531
2027	4	096-Wayne	Preservation	SR 1297	SR 1151	Dead End	0.09	Crack Seal	$538
2027	4	096-Wayne	Preservation	SR 1339	NC 581	SR 1333	1.56	1.25" S9.5B	$175,500
2027	4	096-Wayne	Preservation	SR 1343	SR 1342	NC 581	2.97	Seal - Double and Fog Seal	$133,560
2027	4	096-Wayne	Preservation	SR 1346	NC 581	Johnston CL	1.19	Seal - Double and Fog Seal	$53,550
2027	4	096-Wayne	Preservation	SR 1347	NC 581	Wilson CL	0.33	Seal - Double and Fog Seal	$14,760
2027	4	096-Wayne	Preservation	SR 1353	Wilson Co	NC 222	1.88	Crack Seal	$11,750
2027	4	096-Wayne	Preservation	SR 1354	US 117	Dead End	0.95	1.25" S9.5B	$106,425
2027	4	096-Wayne	Preservation	SR 1355	US-117	SR 1354	0.43	1.25" S9.5B	$48,375
2027	4	096-Wayne	Preservation	SR 1378	NC 222	Dead End	0.65	Seal - Double and Fog Seal	$29,250
2027	4	096-Wayne	Preservation	SR 1500	US 117	SR 1502	1.09	1.25" S9.5B	$122,625
2027	4	096-Wayne	Preservation	SR 1501	US 117	SR 1501	0.88	1.25" S9.5B	$98,550
2027	4	096-Wayne	Preservation	SR 1703	US-13	SR-1702	1.26	1.25" S9.5B	$141,750
2027	4	096-Wayne	Preservation	SR 1706	SR 1702	SR 1705	1.06	Seal - Double and Fog Seal	$47,700
2027	4	096-Wayne	Preservation	SR 1716	SR 1715	Greene County Line	1.42	1.25" S9.5B	$159,750

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	4	096-Wayne	Preservation	SR 1960	NC 111	NC 111	2.75	Crack Seal	$17,188
2027	4	096-Wayne	Preservation	US 117 Alt	Duplin Co	Station St	2.00	Crack Seal	$12,500
2027	4	096-Wayne	Preservation	US 117 Alt	Station St	SR 1145	1.00	Crack Seal	$6,250
2027	4	096-Wayne	Preservation	US 117 Alt	SR 1170	SR 2000	0.70	Crack Seal	$4,375
2027	4	096-Wayne	Preservation	US 117 Bus	US 13	SR 2052	0.50	Crack Seal	$3,125
2027	4	098-Wilson	Resurfacing	NC 58	Joint near Country Club Road	Nash CL	4.02	1.5" S9.5B	$532,650
2027	4	098-Wilson	Resurfacing	SR 1003	Bridge Joint @ US 301	W Elm City City Limit	1.00	Mill 1.5" and 1.5" S9.5C	$180,000
2027	4	098-Wilson	Resurfacing	SR 1155	SR 1215	SR 1001	1.01	1.5" S9.5B	$136,350
2027	4	098-Wilson	Resurfacing	SR 1158	NC 42	US 264Alt Raleigh Rd Pkwy	2.08	Mill 1.5" and 1.5" S9.5B	$821,600
2027	4	098-Wilson	Resurfacing	SR 1306	Nash County Line	Dead End	2.21	1.5" S9.5B	$319,725
2027	4	098-Wilson	Resurfacing	SR 1310	SR 1382	Dead End	1.13	1.25" S9.5B	$127,125
2027	4	098-Wilson	Resurfacing	SR 1328	NC 42	US 301	3.39	Mill 1.5" and 1.5" S9.5B	$678,000
2027	4	098-Wilson	Resurfacing	SR 1338	SR 1337	SR 1339	1.73	1.25" S9.5B	$194,625
2027	4	098-Wilson	Resurfacing	SR 1378	SR 1382	Dead End	0.74	1.25" S9.5B	$107,300
2027	4	098-Wilson	Resurfacing	SR 1400	SR 1003	Nash County Line	3.64	1.5" S9.5B and Widen	$1,017,400
2027	4	098-Wilson	Resurfacing	SR 1416	US 301	SR 1418	2.86	1.5" S9.5B and Widen	$815,670
2027	4	098-Wilson	Resurfacing	SR 1437	N Branch Street	Asphalt Change	0.31	Mill 1.5" and 1.5" S9.5B	$52,700
2027	4	098-Wilson	Resurfacing	US 264-A	SR 1192	US 301	2.39	Mill 1.5" and 1.5" S9.5B	$944,050
2027	4	098-Wilson	Resurfacing	US 301	Wilson County Line	SR 1368	4.40	Mill 1.5" and 1.5" S9.5C	$1,000,000
2027	4	098-Wilson	Resurfacing	US 301	Wilson County Line	SR 1368	4.33	Mill 1.5" and 1.5" S9.5C	$1,000,000
2027	4	098-Wilson	Preservation	SR 1003	Edgecombe County Line	SR 1419	5.16	Microsurface	$335,400
2027	4	098-Wilson	Preservation	SR 1100	NC 581	County Line	2.17	Crack Seal	$13,562
2027	4	098-Wilson	Preservation	SR 1126	SR 1131	SR 1142	2.87	Microsurface	$186,550
2027	4	098-Wilson	Preservation	SR 1144	NC 42	SR 1142	2.12	Crack Seal	$13,250
2027	4	098-Wilson	Preservation	SR 1149	US 264 ALT	SR 1142	4.12	Crack Seal	$57,500
2027	4	098-Wilson	Preservation	SR 1314	NC 58	NASH CL	1.35	Microsurface	$87,750
2027	4	098-Wilson	Preservation	SR 1330	SR 1327	SR 1368	2.68	Crack Seal	$16,750
2027	4	098-Wilson	Preservation	SR 1334	NC 58	SR 1327	1.48	Crack Seal	$9,250
2027	4	098-Wilson	Preservation	SR 1366	SR 1327	DEAD END	0.41	Crack Seal	$2,562
2027	4	098-Wilson	Preservation	SR 1367	SR 1327	DEAD END	0.69	Crack Seal	$4,312
2027	4	098-Wilson	Preservation	SR 1433	SR 1432	Dead End	0.68	Microsurface	$44,200
2027	4	098-Wilson	Preservation	SR 1642	US 117	US 117	0.69	1.0" S4.75A	$77,625
2027	5	032-Durham	Resurfacing	Beasley Ave	NC 98	END MAINT	0.11	Full Depth Patching and 1.5" S9.5B	$19,000
2027	5	032-Durham	Resurfacing	Boyce Mill Rd.	NC 98	WAKE CO	0.67	Full Depth Patching and 1.5" S9.5B	$145,000
2027	5	032-Durham	Resurfacing	Comfort Ln	SR 1324	Dead End	0.28	Full Depth Patching and 1.5" S9.5B	$64,000
2027	5	032-Durham	Resurfacing	Granada Dr	SR 1815	SR 2027	0.13	Full Depth Patching and 1.5" S9.5B	$26,000
2027	5	032-Durham	Resurfacing	Hamlin Rd	SR 1632	END MAINT	1.36	Full Depth Patching and 1.5" S9.5B	$297,000
2027	5	032-Durham	Resurfacing	Hillandale Rd	SR 1320	I-85	1.40	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$571,000
2027	5	032-Durham	Resurfacing	Husketh Dr	SR 1814	Dead End	0.13	Full Depth Patching and 1.5" S9.5B	$25,000
2027	5	032-Durham	Resurfacing	Massey Chapel/Barbee Rd.	NC 54	SR 1118	1.54	Full Depth Patching and 1.5" S9.5B	$337,000
2027	5	032-Durham	Resurfacing	Miami Blvd	SR 2028	I-40	2.38	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,596,000
2027	5	032-Durham	Resurfacing	Miami Blvd	I-40	End Divided	0.22	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$0
2027	5	032-Durham	Resurfacing	NC 55	TW Alexander Dr	Carpenter Fletcher Rd	2.50	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,895,000
2027	5	032-Durham	Resurfacing	NC 55	Carpenter Fletcher Rd	NC 147 Bridge	4.72	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$3,163,000
2027	5	032-Durham	Resurfacing	NC 55	Longitude Dr	Carpenter Fletcher Rd	2.50	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$837,000
2027	5	032-Durham	Resurfacing	Neal Rd	US 70 Bus	SR 1317	0.24	Mill 1.5" and 3.0" S9.5B	$54,000
2027	5	032-Durham	Resurfacing	Sedwick Rd.	NC 55	SR 1100	1.23	Full Depth Patching and 1.5" S9.5B	$402,000
2027	5	032-Durham	Resurfacing	Shiloh Dr	SR 2026	Dead End	0.12	Full Depth Patching and 1.5" S9.5B	$24,000
2027	5	032-Durham	Resurfacing	US 15/501	Mt. Moriah Rd	ORANGE CO	0.43	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$265,000
2027	5	032-Durham	Resurfacing	US 15/501	ORANGE CO	Mt. Moriah Rd	0.43	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$264,000
2027	5	032-Durham	Preservation	Blalock Rd	SR1628	Cul-de-sac	0.14	1.0" S9.5B	$16,000
2027	5	032-Durham	Preservation	Bundy Ave	SR 1636	I-85 Ramp	0.57	1.0" S9.5B	$71,000
2027	5	032-Durham	Preservation	Constance Ave	SR 1671	Dead End	0.17	1.0" S9.5B	$21,000
2027	5	032-Durham	Preservation	Creekside Cv	SR 2320	Cul-de-sac	0.09	1.0" S9.5B	$11,000
2027	5	032-Durham	Preservation	Dawn Tr	SR 2326	Cul-de-sac	0.30	1.0" S9.5B	$37,000
2027	5	032-Durham	Preservation	Eno Woods Tr	SR 1449	ORANGE CO	0.06	1.0" S9.5B	$7,000
2027	5	032-Durham	Preservation	Morton Dr	SR 1634	Dead End	0.23	1.0" S9.5B	$29,000
2027	5	032-Durham	Preservation	November Dr	SR 1449	SR 2326	0.72	1.0" S9.5B	$89,000
2027	5	032-Durham	Preservation	Red Coach Rd	SR 1453	End Pavement	0.18	1.0" S9.5B	$22,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	5	032-Durham	Preservation	Riley Dr	SR 1634	Dead End	0.17	1.0" S9.5B	$21,000
2027	5	032-Durham	Preservation	Roberts Rd	SR 1616	Cul-de-sac	0.67	1.0" S9.5B	$83,000
2027	5	032-Durham	Preservation	Strawberry Ln	SR 2320	Cul-de-sac	0.06	1.0" S9.5B	$7,000
2027	5	032-Durham	Preservation	Thunder Rd	SR 2320	SR 2320	0.31	1.0" S9.5B	$38,000
2027	5	032-Durham	Preservation	Ventoria Rd	SR 1640	END MAINT	0.28	1.0" S9.5B	$35,000
2027	5	032-Durham	Preservation	Woodhaven Dr	SR 1451	Cul-de-sac	0.54	1.0" S9.5B	$68,000
2027	5	035-Franklin	Resurfacing	Beasley Rd	SR 1235	US 401	3.44	Full Depth Patching and 1.25" S9.5B	$636,000
2027	5	035-Franklin	Resurfacing	Duke Memorial Rd	NASH CO	NC 581	3.84	Full Depth Patching and 1.25" S9.5B	$710,000
2027	5	035-Franklin	Resurfacing	Fletcher Fuller	SR 1003	SR 1253	0.27	Full Depth Patching and 1.5" S9.5B	$59,000
2027	5	035-Franklin	Resurfacing	Mitchell Rd	NC 581	Dead End	0.79	Full Depth Patching and 1.5" S9.5B	$172,000
2027	5	035-Franklin	Resurfacing	NC 39	US 64	Pavement Joint	6.74	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$1,785,000
2027	5	035-Franklin	Resurfacing	NC 98	NC 39	Nash County	3.69	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$813,000
2027	5	035-Franklin	Resurfacing	Ramp 6288	NC 39	NC 39	0.12	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$31,000
2027	5	035-Franklin	Resurfacing	Ramp 6348	NC 39	NC 98	0.08	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$20,000
2027	5	035-Franklin	Resurfacing	Ricks Rd	NC 561	NC 561	0.59	Full Depth Patching and 1.25" S9.5B	$103,000
2027	5	035-Franklin	Resurfacing	Sid Eaves	SR 1100	US 401	2.02	Full Depth Patching and 1.5" S9.5B	$440,000
2027	5	035-Franklin	Resurfacing	Sollie Ayscue	SR 1003	SR 1253	0.82	Full Depth Patching and 1.5" S9.5B	$179,000
2027	5	035-Franklin	Resurfacing	US 401	NC 39	Warren County	6.67	Full Depth Patching and 1.5" S9.5C	$1,621,000
2027	5	035-Franklin	Preservation	Gooch	SR 1003	VANCE CO	1.61	Full Depth Patching and 1.25" S9.5B	$313,000
2027	5	035-Franklin	Preservation	May Rd	NC 561	SR 1223	1.24	Full Depth Patching and 1.25" S9.5B	$241,000
2027	5	035-Franklin	Preservation	Thomas Arnold Rd	SR 1757	SR 1244	0.96	Full Depth Patching and Double Seal and Fog Seal	$95,000
2027	5	035-Franklin	Preservation	Thomas Jones	SR 1446	Dead End	1.40	Full Depth Patching and 1.25" S9.5B	$272,000
2027	5	035-Franklin	Preservation	Thomas Rd	SR 1770	SR 1759	0.45	Full Depth Patching and Double Seal and Fog Seal	$392,000
2027	5	039-Granville	Resurfacing	Culbreth Rd	SR 1139	SR 1004	3.50	Full Depth Patching and 1.5" S9.5B	$763,000
2027	5	039-Granville	Resurfacing	Julian Daniel Rd	SR 1004	SR 1124	0.96	Full Depth Patching and 1.5" S9.5B	$210,000
2027	5	039-Granville	Resurfacing	Moss-Hayes Rd	NC 56	SR 1638	1.52	Full Depth Patching and 1.5" S9.5B	$331,000
2027	5	039-Granville	Resurfacing	Otha Mangum Rd	SR 1215	SR 1004	1.89	Full Depth Patching and 1.5" S9.5B	$411,000
2027	5	039-Granville	Resurfacing	Russell Rd	SR 1138	Dead End	0.64	Full Depth Patching and 1.5" S9.5B	$139,000
2027	5	039-Granville	Resurfacing	W Lyon Station Rd	NC 56	SR 1127	2.40	Full Depth Patching and 1.5" S9.5B	$576,000
2027	5	039-Granville	Rehabilitation	Blackstone Dr	SR 1102	SR 1249	0.29	Undercut then fabric, 8" ABC, 1.5" S9.5B	$226,000
2027	5	039-Granville	Rehabilitation	Cobblestone Dr	Cul-de-sac	Cul-de-sac	0.81	Undercut then fabric, 8" ABC, 1.5" S9.5B	$638,000
2027	5	039-Granville	Rehabilitation	Flint Ct	SR 1249	Cul-de-sac	0.03	Undercut then fabric, 8" ABC, 1.5" S9.5B	$24,000
2027	5	039-Granville	Preservation	Bob Daniel Rd	SR 1150	SR 1304	2.70	Full Depth Patching and 1.25" S9.5B	$525,000
2027	5	039-Granville	Preservation	Hebron Rd	US 158	SR 1304	3.31	Full Depth Patching and 1.25" S9.5B	$644,000
2027	5	073-Person	Resurfacing	Bethany Church Rd	SR 1721	GRANVILLE CO	1.72	Full Depth Patching and 1.5" S9.5B	$374,000
2027	5	073-Person	Resurfacing	Northpark Drive	SR 1605	Dead End	0.78	Full Depth Patching and 1.5" S9.5B	$187,000
2027	5	073-Person	Resurfacing	Reams Ave	SR 1363	US 501	0.46	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$141,000
2027	5	073-Person	Resurfacing	Surl Mt Tirzah Rd	SR 1723	US 158	4.71	Full Depth Patching and 1.5" S9.5B	$1,130,000
2027	5	073-Person	Resurfacing	Westover Dr	SR 1333	SR 1365	0.62	Full Depth Patching and 1.5" S9.5B	$135,000
2027	5	073-Person	Resurfacing	Westover Dr	SR 1365	EOM	0.04	Full Depth Patching and 1.5" S9.5B	$8,000
2027	5	073-Person	Preservation	Barker Rd	SR 1318	Caswell County	1.86	Full Depth Patching and Double Seal	$168,000
2027	5	073-Person	Preservation	Carver Holt Rd	SR 1348	Dead End	0.38	Full Depth Patching and Double Seal	$34,000
2027	5	073-Person	Preservation	Charlie Reade Rd	SR 1717	SR 1715	1.13	Full Depth Patching and Double Seal	$102,000
2027	5	073-Person	Preservation	Franklin Rd	SR 1318	Dead End	1.02	Full Depth Patching and Double Seal	$92,000
2027	5	073-Person	Preservation	Glennie Irvin Rd	SR 1318	Dead End	0.65	Full Depth Patching and Double Seal	$58,000
2027	5	073-Person	Preservation	Henry Brandon Rd	SR 1318	End Pvmt	0.66	Full Depth Patching and Double Seal	$60,000
2027	5	073-Person	Preservation	Munday Rd	SR 1337	Cul-de-sac	0.59	Full Depth Patching and Double Seal	$53,000
2027	5	073-Person	Preservation	Nora Poole Rd	SR 1342	Dead End	0.94	Full Depth Patching and Double Seal	$85,000
2027	5	073-Person	Preservation	Scott Rd	SR 1318	Cul-de-sac	1.12	Full Depth Patching and Double Seal	$101,000
2027	5	073-Person	Preservation	Terrell School Rd	Virginia State Line	Dead End	0.50	Full Depth Patching and Double Seal	$45,000
2027	5	073-Person	Preservation	Virginia Line Rd	SR 1319	Virginia State Line	0.65	Full Depth Patching and Double Seal	$59,000
2027	5	091-Vance	Resurfacing	Egypt-Mountain Road	US 1	SR 1101	4.49	Full Depth Patching and 1.25" S9.5B	$873,000
2027	5	091-Vance	Resurfacing	S. Lake Lodge/Briggs/Comm. House	US 1 Bus	SR 1110	5.11	Full Depth Patching and 1.25" S9.5B	$993,000
2027	5	091-Vance	Resurfacing	South Cokesbury	SR 1513	SR 1533	2.17	Full Depth Patching and 1.25" S9.5B	$380,000
2027	5	091-Vance	Resurfacing	South Cokesbury	SR 1515	SR 1510	0.63	Full Depth Patching and 1.25" S9.5B	$110,000
2027	5	091-Vance	Resurfacing	US 1 BUS	US 1	Pavement Joint	4.44	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,389,000
2027	5	091-Vance	Resurfacing	US 1 Bus	US 1	Pavement Joint	4.44	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,189,000
2027	5	091-Vance	Preservation	County Line	SR 1362	SR 1360	1.19	Full Depth Patching and Double Seal and Fog Seal	$118,000
2027	5	091-Vance	Preservation	Frank Bullock Rd	SR 1366	END MAINT	0.67	Full Depth Patching and Double Seal and Fog Seal	$66,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	5	091-Vance	Preservation	James Matthews	NC 39	VIRGINIA	0.50	Full Depth Patching and Double Seal and Fog Seal	$49,000
2027	5	091-Vance	Preservation	North Piney Grove	END MAINT	END MAINT	1.49	Full Depth Patching and Double Seal and Fog Seal	$148,000
2027	5	091-Vance	Preservation	Wilson Brothers	WARREN CO	SR 1363	1.66	Full Depth Patching and Double Seal and Fog Seal	$148,000
2027	5	092-Wake	Resurfacing	Amsterdam Pl	SR 1537	Dead End	0.55	Full Depth Patching and 1.25" S9.5B	$107,000
2027	5	092-Wake	Resurfacing	Arden Forest Rd	SR 5822	SR 5093	0.25	Full Depth Patching and 1.25" S9.5B	$49,000
2027	5	092-Wake	Resurfacing	Arden Forest Rd	SR 1393	SR 5051	0.14	Full Depth Patching and 1.25" S9.5B	$26,000
2027	5	092-Wake	Resurfacing	Ballyclare Ct	Cul-de-sac	Cul-de-sac	0.37	Full Depth Patching and 1.25" S9.5B	$65,000
2027	5	092-Wake	Resurfacing	Barnwood Ct	SR 3874	Cul-de-sac	0.24	Full Depth Patching and 1.25" S9.5B	$47,000
2027	5	092-Wake	Resurfacing	Belgium Dr	END MAINT	Dead End	0.60	Full Depth Patching and 1.25" S9.5B	$117,000
2027	5	092-Wake	Resurfacing	Bent Oak Ct	SR 2731	Cul-de-sac	0.17	Full Depth Patching and 1.25" S9.5B	$29,000
2027	5	092-Wake	Resurfacing	Birnamwood Ct	SR 1393	Cul-de-sac	0.42	1.0" S9.5B	$52,000
2027	5	092-Wake	Resurfacing	Boyce Mill Rd	SR 1381	Durham County	0.11	Full Depth Patching and 1.5" S9.5B	$24,000
2027	5	092-Wake	Resurfacing	Breda Ct	SR 1594	Cul-de-sac	0.04	Full Depth Patching and 1.25" S9.5B	$8,000
2027	5	092-Wake	Resurfacing	Brently Dr	SR 1388	SR 1010	0.20	Full Depth Patching and 1.25" S9.5B	$39,000
2027	5	092-Wake	Resurfacing	Briarglen Ln	SR 1393	Cul-de-sac	0.43	Full Depth Patching and 1.25" S9.5B	$84,000
2027	5	092-Wake	Resurfacing	Briarwood Dr	SR 1375	Dead End	0.41	Full Depth Patching and 1.25" S9.5B	$80,000
2027	5	092-Wake	Resurfacing	Brushy Meadows Dr	SR 1393	Cul-de-sac	0.41	Full Depth Patching and 1.5" S9.5B	$89,000
2027	5	092-Wake	Resurfacing	Buck Wallow Rd	SR 1831	SR 4551	0.24	Full Depth Patching and 1.5" S9.5B	$52,000
2027	5	092-Wake	Resurfacing	Cablewood Dr	SR 4881	SR 4881	0.28	Full Depth Patching and 1.25" S9.5B	$54,000
2027	5	092-Wake	Resurfacing	Capital Blvd NB	Jacqueline Ln	vt Joint Approx 600' N of Thorton R	1.44	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$772,000
2027	5	092-Wake	Resurfacing	Capital Blvd SB	Pvt Joint Approx 600' N of Thorton Rd	Jacqueline Ln	1.43	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$766,000
2027	5	092-Wake	Resurfacing	Chestnut Hill Rd	Cul-de-sac	Cul-de-sac	0.27	Full Depth Patching and 1.25" S9.5B	$52,000
2027	5	092-Wake	Resurfacing	Country Brooke Dr	SR 3833	Cul-de-sac	0.12	Full Depth Patching and 1.25" S9.5B	$21,000
2027	5	092-Wake	Resurfacing	Cypress Ford Dr	SR 1301	SR 4702	0.57	Full Depth Patching and 1.5" S9.5B	$125,000
2027	5	092-Wake	Resurfacing	Denberg Ln	SR 1536	Cul-de-sac	0.19	Full Depth Patching and 1.25" S9.5B	$34,000
2027	5	092-Wake	Resurfacing	Dublin Woods Dr	SR 1650	END MAINT	0.40	Full Depth Patching and 1.5" S9.5B	$122,000
2027	5	092-Wake	Resurfacing	Dutch Creek Dr	SR 1539	SR 1010	0.46	Full Depth Patching and 1.25" S9.5B	$89,000
2027	5	092-Wake	Resurfacing	Dutch Harbor Ct	SR 1594	SR 3966	0.11	Full Depth Patching and 1.25" S9.5B	$19,000
2027	5	092-Wake	Resurfacing	Dutch Harbor Ct	Cul-de-sac	Cul-de-sac	0.07	Full Depth Patching and 1.25" S9.5B	$12,000
2027	5	092-Wake	Resurfacing	Dutchman Dr	SR 1379	SR 1539	0.89	Full Depth Patching and 1.25" S9.5B	$173,000
2027	5	092-Wake	Resurfacing	Farmpond Rd	SR 1613	Dead End	0.35	Full Depth Patching and 1.5" S9.5B	$76,000
2027	5	092-Wake	Resurfacing	Ferrell Woods Ln	SR 3887	Cul-de-sac	0.17	Full Depth Patching and 1.25" S9.5B	$33,000
2027	5	092-Wake	Resurfacing	Fonville Rd	SR 2000	Cul-de-sac	0.48	Full Depth Patching and 1.25" S9.5B	$94,000
2027	5	092-Wake	Resurfacing	Frosty Hollow Rd	SR 4537	Grace Cove Ln	0.15	Full Depth Patching and 1.25" S9.5B	$26,000
2027	5	092-Wake	Resurfacing	Glenfair Way	SR 4851	Cul-de-sac	0.16	Full Depth Patching and 1.25" S9.5B	$31,000
2027	5	092-Wake	Resurfacing	Great Woods Rd	SR 4537	Cul De Sac	0.16	Full Depth Patching and 1.25" S9.5B	$27,000
2027	5	092-Wake	Resurfacing	Green Level Church Rd	Cul-de-sac	SR 1608	1.52	Full Depth Patching and 1.5" S9.5B	$364,000
2027	5	092-Wake	Resurfacing	Greenbreeze Ln	Cul-de-sac	Cul-de-sac	0.42	1.0" S9.5B	$52,000
2027	5	092-Wake	Resurfacing	Greensflag Ln	SR 4771	Cul-de-sac	0.22	Full Depth Patching and 1.25" S9.5B	$43,000
2027	5	092-Wake	Resurfacing	Hammond Rd	Hoke St	Rush St	1.52	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$680,000
2027	5	092-Wake	Resurfacing	Hammond Rd	Rush St	Hoke St	1.53	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$682,000
2027	5	092-Wake	Resurfacing	Hanna Ln	SR 1301	Cul-de-sac	0.24	Full Depth Patching and 1.25" S9.5B	$47,000
2027	5	092-Wake	Resurfacing	Heartland Dr	Cul-de-sac	Cul-de-sac	0.33	Full Depth Patching and 1.25" S9.5B	$64,000
2027	5	092-Wake	Resurfacing	Hill St	SR 2271	END MAINT	0.22	Full Depth Patching and 1.5" S9.5B	$48,000
2027	5	092-Wake	Resurfacing	Holland Farms Way	SR 2726	Dead End	0.43	Full Depth Patching and 1.5" S9.5B	$84,000
2027	5	092-Wake	Resurfacing	Holland Hilld Dr	SR 1301	Dead End	0.68	Full Depth Patching and 1.25" S9.5B	$132,000
2027	5	092-Wake	Resurfacing	Hollander Pl	Cul-de-sac	Cul-de-sac	0.25	Full Depth Patching and 1.25" S9.5B	$49,000
2027	5	092-Wake	Resurfacing	Holly Oak Ct	SR 2765	Cul-de-sac	0.24	Full Depth Patching and 1.25" S9.5B	$47,000
2027	5	092-Wake	Resurfacing	Holly Springs Rd	Pavement Joint	SR 1379	1.13	Full Depth Patching and 1.5" S9.5B	$295,000
2027	5	092-Wake	Resurfacing	Holt Rd	Begin C&G	SR 3011	0.64	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$184,000
2027	5	092-Wake	Resurfacing	Holt Rd	SR 1611	Begin C&G	0.46	Full Depth Patching and 1.5" S9.5B	$99,000
2027	5	092-Wake	Resurfacing	Incline Dr	SR 1921	Cul-de-sac	0.15	Full Depth Patching and 1.25" S9.5B	$26,000
2027	5	092-Wake	Resurfacing	Keith Rd	SR 1917	Dead End	0.95	Full Depth Patching and 1.5" S9.5B	$206,000
2027	5	092-Wake	Resurfacing	Kelly Rd	Pavement Joint	SR 1600	0.24	Full Depth Patching and 1.5" S9.5B	$52,000
2027	5	092-Wake	Resurfacing	Kenridge Ln	Dead End	Cul-de-sac	0.23	Full Depth Patching and 1.25" S9.5B	$45,000
2027	5	092-Wake	Resurfacing	Kenwood Meadows Dr	SR 2736	Cul-de-sac	0.25	Full Depth Patching and 1.25" S9.5B	$49,000
2027	5	092-Wake	Resurfacing	Kildaire Farm Rd	SR 1009	SR 1415	2.21	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,483,000
2027	5	092-Wake	Resurfacing	Kingpost Dr	SR 4701	SR 5093	0.74	Full Depth Patching and 1.25" S9.5B	$144,000
2027	5	092-Wake	Resurfacing	Knightdale Eagle Rock Rd	SR 2500	Pavement Joint	0.61	Full Depth Patching and 1.5" S9.5B	$146,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	5	092-Wake	Resurfacing	Lakefall Dr	NC 98	SR 4550	0.29	Full Depth Patching and 1.5" S9.5B	$63,000
2027	5	092-Wake	Resurfacing	Landingham Dr	NC 42	SR 4869	0.86	Full Depth Patching and 1.25" S9.5B	$168,000
2027	5	092-Wake	Resurfacing	Lautenberg Ln	Cul-de-sac	Dead End	0.59	1.0" S9.5B	$73,000
2027	5	092-Wake	Resurfacing	Lawdraker Rd	SR 1010	Dead End	0.98	Full Depth Patching and 1.25" S9.5B	$190,000
2027	5	092-Wake	Resurfacing	Lead Mine Rd	SR 1851	Begin C&G	2.45	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$875,000
2027	5	092-Wake	Resurfacing	Lead Mine Rd	Begin C&G	SR 5147	0.35	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$234,000
2027	5	092-Wake	Resurfacing	Lead Mine Rd	US 70	SR 1851	0.76	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$553,000
2027	5	092-Wake	Resurfacing	Linaria Ln	SR 4772	Cul-de-sac	0.18	Full Depth Patching and 1.25" S9.5B	$34,000
2027	5	092-Wake	Resurfacing	Linwick Dr	SR 4777	Cul-de-sac	0.31	Full Depth Patching and 1.25" S9.5B	$61,000
2027	5	092-Wake	Resurfacing	Loch Highlands Dr	SR 1379	Cul-de-sac	0.19	Full Depth Patching and 1.25" S9.5B	$34,000
2027	5	092-Wake	Resurfacing	Max Ln	SR 3887	Dead End	0.07	Full Depth Patching and 1.25" S9.5B	$14,000
2027	5	092-Wake	Resurfacing	Mendi Ct	SR 4711	Cul-de-sac	0.03	Full Depth Patching and 1.25" S9.5B	$5,000
2027	5	092-Wake	Resurfacing	Mistyridge Rd	SR 4046	SR 4049	0.27	Full Depth Patching and 1.25" S9.5B	$53,000
2027	5	092-Wake	Resurfacing	NC 42	SR 1006	Johnston Co	4.51	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,208,000
2027	5	092-Wake	Resurfacing	NC 50	JOHNSTON CO	US 70	7.46	Full Depth Patching and 1.5" S9.5C	$2,471,000
2027	5	092-Wake	Resurfacing	NC 50	Pavement Joint	Norwood Rd	1.80	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$482,000
2027	5	092-Wake	Resurfacing	NC 96	Skeet Dr	US 401	5.27	Full Depth Patching and 1.5" S9.5C	$1,455,000
2027	5	092-Wake	Resurfacing	NC 96	US 401	NC 98	1.20	Full Depth Patching and 1.5" S9.5C	$332,000
2027	5	092-Wake	Resurfacing	Netherlands Dr	SR 1152	Cul-de-sac	0.96	Full Depth Patching and 1.25" S9.5B	$187,000
2027	5	092-Wake	Resurfacing	NW Maynard Rd	Beg Div Hwy	Pavement Joint	0.28	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$82,000
2027	5	092-Wake	Resurfacing	NW Maynard Rd	Pavement Joint	End Divided	0.28	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$82,000
2027	5	092-Wake	Resurfacing	Oakwealth Dr	SR 5093	Cul-de-sac	0.29	1.0" S9.5B	$36,000
2027	5	092-Wake	Resurfacing	Old Gold Pl	SR 3874	Cul-de-sac	0.29	Full Depth Patching and 1.25" S9.5B	$56,000
2027	5	092-Wake	Resurfacing	Oviedo Dr	NC 42	Cul-de-sac	0.63	Full Depth Patching and 1.25" S9.5B	$123,000
2027	5	092-Wake	Resurfacing	Oxford Green Dr	SR 5301	Cul De Sac	0.43	1.0" S9.5B	$53,000
2027	5	092-Wake	Resurfacing	Praed Pl	SR 1393	END MAINT	0.37	Full Depth Patching and 1.25" S9.5B	$72,000
2027	5	092-Wake	Resurfacing	Proctor St/Old Bunn Rd	NC 96	NC 97	2.84	Full Depth Patching and 1.5" S9.5B	$620,000
2027	5	092-Wake	Resurfacing	Red Brick Rd	SR 4820	SR 4824	0.19	Full Depth Patching and 1.25" S9.5B	$37,000
2027	5	092-Wake	Resurfacing	Robertson St	SR 2501	N First Ave	1.37	Full Depth Patching and 1.5" S9.5B	$298,000
2027	5	092-Wake	Resurfacing	Sassafras Ln	SR 1847	Cul-de-sac	0.23	Full Depth Patching and 1.25" S9.5B	$40,000
2027	5	092-Wake	Resurfacing	Shady Greens Dr	SR 1393	Cul-de-sac	0.41	Full Depth Patching and 1.5" S9.5B	$89,000
2027	5	092-Wake	Resurfacing	South Pointe Dr	SR 1388	SR 5037	0.32	Full Depth Patching and 1.25" S9.5B	$56,000
2027	5	092-Wake	Resurfacing	Southern Trace Trl	NC 50	END MAINT	0.50	Full Depth Patching and 1.5" S9.5B	$115,000
2027	5	092-Wake	Resurfacing	Spanish Moss Ln	NC 50	SR 4820	0.21	Full Depth Patching and 1.25" S9.5B	$41,000
2027	5	092-Wake	Resurfacing	Stansted Dr	SR 1301	SR 4702	0.49	Full Depth Patching and 1.25" S9.5B	$95,000
2027	5	092-Wake	Resurfacing	Starchase Ln	SR 1122	Cul-de-sac	0.61	1.0" S9.5B	$76,000
2027	5	092-Wake	Resurfacing	Strickland Rd	NC 50	SR 1005	1.64	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$1,087,000
2027	5	092-Wake	Resurfacing	Summer Oaks Dr	SR 1387	Cul-de-sac	0.36	1.0" S9.5B	$41,000
2027	5	092-Wake	Resurfacing	Tannenhill Trl	Cul-de-sac	Cul-de-sac	0.15	Full Depth Patching and 1.25" S9.5B	$29,000
2027	5	092-Wake	Resurfacing	The Dyke	SR1536	SR 1541	0.26	Full Depth Patching and 1.25" S9.5B	$51,000
2027	5	092-Wake	Resurfacing	The Hague	SR 1537	SR 1541	0.16	Full Depth Patching and 1.25" S9.5B	$31,000
2027	5	092-Wake	Resurfacing	Tobacco Barn Rd	SR 1100	Dead End	0.43	Full Depth Patching and 1.5" S9.5B	$84,000
2027	5	092-Wake	Resurfacing	Trailwood Dr	SR 1321	Beg C&G	0.93	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$205,000
2027	5	092-Wake	Resurfacing	Trinity Rd	I-40	SR 1664	1.93	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,290,000
2027	5	092-Wake	Resurfacing	Trinity Rd	SR 1655	I-40	0.35	Full Depth Patching and 1.5" S9.5B	$160,000
2027	5	092-Wake	Resurfacing	Trinity Rd	SR 1656	SR 1655	0.04	Full Depth Patching and 1.5" S9.5B	$10,000
2027	5	092-Wake	Resurfacing	Trinity Rd/Trenton Rd	NC 54	I-40	1.89	Full Depth Patching and 1.5" S9.5B	$452,000
2027	5	092-Wake	Resurfacing	Tyler Farms Dr	SR 2736	Dead End	0.31	Full Depth Patching and 1.25" S9.5B	$60,000
2027	5	092-Wake	Resurfacing	US 70 EB	Womens Club Dr	SR 1728	2.76	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,478,000
2027	5	092-Wake	Resurfacing	US 70 EB	Womens Club Dr	Sr 1728	2.76	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,678,000
2027	5	092-Wake	Resurfacing	US 70 WB	Oberlin Road	Womens Club Dr	1.06	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$283,000
2027	5	092-Wake	Resurfacing	US 70 WB	White Oak Rd	The Circle	0.35	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$95,000
2027	5	092-Wake	Resurfacing	US 70 WB	SR 1728	End Divided	0.33	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$88,000
2027	5	092-Wake	Resurfacing	Vintage Ridge Ln	SR 1301	Cul-de-sac	0.33	Full Depth Patching and 1.25" S9.5B	$65,000
2027	5	092-Wake	Resurfacing	Wade to Glenwood Ramp	Wade Ave	Glenwood Ave	0.14	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$38,000
2027	5	092-Wake	Resurfacing	Waterwood Ct	SR 2001	END MAINT	0.32	Full Depth Patching and 1.25" S9.5B	$61,000
2027	5	092-Wake	Resurfacing	Wayfair Ct	Cul-de-sac	Cul-de-sac	0.12	Full Depth Patching and 1.25" S9.5B	$23,000
2027	5	092-Wake	Resurfacing	Willow Bridge Ln	SR 4773	Cul-de-sac	0.17	Full Depth Patching and 1.25" S9.5B	$32,000
2027	5	092-Wake	Resurfacing	Willowdale Ct	SR 1390	Cul-de-sac	0.15	Full Depth Patching and 1.25" S9.5B	$25,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	5	092-Wake	Resurfacing	Wiltree Dr	SR 4779	Cul-de-sac	0.33	1.0" S9.5B	$41,000
2027	5	092-Wake	Resurfacing	Wimberly Rd	SR 1006	Harnett County	1.98	Full Depth Patching and 1.5" S9.5B	$215,000
2027	5	092-Wake	Resurfacing	Wyndfair Dr	SR 2770	Cul-de-sac	0.48	Full Depth Patching and 1.5" S9.5B	$105,000
2027	5	092-Wake	Preservation	Appius Ct	SR 5303	Cul-de-sac	0.07	1.0" S9.5B	$9,000
2027	5	092-Wake	Preservation	Athena Ct	SR 5301	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2027	5	092-Wake	Preservation	Bainford Dr	SR 4779	END MAINT	0.07	1.0" S9.5B	$9,000
2027	5	092-Wake	Preservation	Barkton Way	SR 5810	Cul-de-sac	0.10	1.0" S9.5B	$12,000
2027	5	092-Wake	Preservation	Basal Creek Ln	SR 4702	Cul-de-sac	0.24	1.0" S9.5B	$30,000
2027	5	092-Wake	Preservation	Bridgefair Ct	SR 4851	Cul-de-sac	0.09	1.0" S9.5B	$11,000
2027	5	092-Wake	Preservation	Candlewick Dr	Rolesville Rd	Rose Pl	0.27	1.0" S9.5B	$33,000
2027	5	092-Wake	Preservation	Capua Ct	SR 5300	Cul-de-sac	0.15	1.0" S9.5B	$19,000
2027	5	092-Wake	Preservation	Carriagehouse Ct	SR 1405	Cul-de-sac	0.20	1.0" S9.5B	$25,000
2027	5	092-Wake	Preservation	Castlereagh Ln	SR 1845	SR 4947	0.09	1.0" S9.5B	$10,000
2027	5	092-Wake	Preservation	Charlbert Ct	SR 3960	Cul-de-sac	0.13	1.0" S9.5B	$16,000
2027	5	092-Wake	Preservation	Clairway Ct	SR 4852	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2027	5	092-Wake	Preservation	Clubview Ct	SR 4703	Cul-de-sac	0.12	1.0" S9.5B	$15,000
2027	5	092-Wake	Preservation	Coolwater Ct	SR 4454	Cul-de-sac	0.02	1.0" S9.5B	$3,000
2027	5	092-Wake	Preservation	Cotton Boll Rd	SR 4821	Cul-de-sac	0.07	1.0" S9.5B	$9,000
2027	5	092-Wake	Preservation	Crispwood Ct	Cul-de-sac	Cul-de-sac	0.08	1.0" S9.5B	$10,000
2027	5	092-Wake	Preservation	Crofters Glen Ct	SR 3874	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2027	5	092-Wake	Preservation	Crossgar Ct	SR 4948	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2027	5	092-Wake	Preservation	Dogwood Dr	SR 2249	End Pavement	0.20	1.0" S9.5B	$22,000
2027	5	092-Wake	Preservation	Drumquin Dr	SR 4947	Cul-de-sac	0.22	1.0" S9.5B	$26,000
2027	5	092-Wake	Preservation	Early Morning Trl	SR 4894	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2027	5	092-Wake	Preservation	Fieldcrest Ln	SR 4851	END MAINT	0.16	1.0" S9.5B	$19,000
2027	5	092-Wake	Preservation	Fountainside Ct	SR 4454	SR 4493	0.05	1.0" S9.5B	$6,000
2027	5	092-Wake	Preservation	Freshwater Ct	Dead End	Cul-de-sac	0.09	1.0" S9.5B	$10,000
2027	5	092-Wake	Preservation	Gail Ridge Ln	Candlewick Dr	Rose Place	0.32	1.0" S9.5B	$39,000
2027	5	092-Wake	Preservation	Hammerman Dr	Cul-de-sac	Cul-de-sac	0.15	1.0" S9.5B	$19,000
2027	5	092-Wake	Preservation	Highlander Dr	SR 4356	Cul-de-sac	0.08	1.0" S9.5B	$10,000
2027	5	092-Wake	Preservation	Hill Creek Dr	SR 4821	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2027	5	092-Wake	Preservation	Indore Rd	SR 1375	Cul-de-sac	0.13	1.0" S9.5B	$15,000
2027	5	092-Wake	Preservation	Jordan Woods Dr	SR 4897	Cul-de-sac	0.25	1.0" S9.5B	$27,000
2027	5	092-Wake	Preservation	Kelly Oak Ct	SR 5810	Cul-de-sac	0.11	1.0" S9.5B	$13,000
2027	5	092-Wake	Preservation	Lakefield Dr	SR 2727	Cul-de-sac	0.18	1.0" S9.5B	$20,000
2027	5	092-Wake	Preservation	Landview Ave	SR 3831	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2027	5	092-Wake	Preservation	Layton Ridge Dr	SR 5037	SR 1387	0.31	1.0" S9.5B	$38,000
2027	5	092-Wake	Preservation	Lizard Lick Rd	NC 97	Riley Hill Rd	1.74	1.0" S9.5B	$216,000
2027	5	092-Wake	Preservation	Lockey Rd	SR 1301	END MAINT	0.15	1.0" S9.5B	$19,000
2027	5	092-Wake	Preservation	Lord Britton Pl	SR 2738	Cul-de-sac	0.16	1.0" S9.5B	$20,000
2027	5	092-Wake	Preservation	Luminary Ln	SR 4869	Dead End	0.30	1.0" S9.5B	$37,000
2027	5	092-Wake	Preservation	Middleberry Ln	SR 3751	SR 3821	0.24	1.0" S9.5B	$30,000
2027	5	092-Wake	Preservation	Millstone Cr	SR 5820	Cul-de-sac	0.18	1.0" S9.5B	$22,000
2027	5	092-Wake	Preservation	Mycenae Pl	SR 5300	Cul-de-sac	0.26	1.0" S9.5B	$32,000
2027	5	092-Wake	Preservation	Northfield Ct	SR 3753	Cul-de-sac	0.14	1.0" S9.5B	$17,000
2027	5	092-Wake	Preservation	Oakson Ct	SR 4701	Cul-de-sac	0.09	1.0" S9.5B	$11,000
2027	5	092-Wake	Preservation	Panther Dr	SR 2723	Cul-de-sac	0.24	1.0" S9.5B	$30,000
2027	5	092-Wake	Preservation	Plantbed Ct	Cul-de-sac	Cul-de-sac	0.06	1.0" S9.5B	$7,000
2027	5	092-Wake	Preservation	Pleasanr Rd	SR 1375	Cul-de-sac	0.19	1.0" S9.5B	$21,000
2027	5	092-Wake	Preservation	Princeview Dr	SR 3889	Dead End	0.07	1.0" S9.5B	$9,000
2027	5	092-Wake	Preservation	Rathkeale Ct	SR 5093	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2027	5	092-Wake	Preservation	Red Brick Rd	SR 4820	Cul-de-sac	0.03	1.0" S9.5B	$4,000
2027	5	092-Wake	Preservation	Rose Pl	Gail Ridge Ln	Candlewick Dr	0.07	1.0" S9.5B	$9,000
2027	5	092-Wake	Preservation	Rustic Mill Dr	SR 1388	Dead End	0.20	1.0" S9.5B	$24,000
2027	5	092-Wake	Preservation	Sedona Pl	SR 1388	Cul-de-sac	0.17	1.0" S9.5B	$21,000
2027	5	092-Wake	Preservation	Stalling Glen Ln	SR 4356	Dead End	0.15	1.0" S9.5B	$19,000
2027	5	092-Wake	Preservation	Stonewater Dr	SR 4356	Cul-de-sac	0.16	1.0" S9.5B	$20,000
2027	5	092-Wake	Preservation	Stonewater Dr	SR 4356	Dead End	0.18	1.0" S9.5B	$22,000
2027	5	092-Wake	Preservation	Sunlit Ln	SR 2204	SR 2271	0.07	1.0" S9.5B	$8,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	5	092-Wake	Preservation	Thistleby Rd	SR 4781	Cul-de-sac	0.06	1.0" S9.5B	$7,000
2027	5	092-Wake	Preservation	Two Brothers Run	SR 2727	Cul-de-sac	0.17	1.0" S9.5B	$21,000
2027	5	092-Wake	Preservation	Valley Hill Ct.	SR 1386	Cul-de-sac	0.07	Full Depth Patching and 1.25" S9.5B	$12,000
2027	5	092-Wake	Preservation	Vandam Dr	SR 1388	Cul-de-sac	0.16	1.0" S9.5B	$20,000
2027	5	092-Wake	Preservation	Vernie Dr	SR 4357	Cul-de-sac	0.31	1.0" S9.5B	$38,000
2027	5	092-Wake	Preservation	Wakeford Dr	SR 4777	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2027	5	092-Wake	Preservation	Waterwinds Ct	SR 4454	Cul-de-sac	0.03	1.0" S9.5B	$3,000
2027	5	092-Wake	Preservation	Whistleberry Ct	SR 1992	Cul-de-sac	0.11	1.0" S9.5B	$14,000
2027	5	092-Wake	Preservation	Whitefield Dr	SR 2750	Cul-de-sac	0.21	1.0" S9.5B	$26,000
2027	5	092-Wake	Preservation	Willowdale Ct	SR 1390	Cul-de-sac	0.14	1.0" S9.5B	$17,000
2027	5	092-Wake	Preservation	Wilshire Ct	SR 4781	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2027	5	092-Wake	Preservation	Windrow Ln	SR 2727	Cul-de-sac	0.35	1.0" S9.5B	$43,000
2027	5	092-Wake	Preservation	Windstar Way	SR 4869	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2027	5	092-Wake	Preservation	Winsome Ct	SR 4898	Cul-de-sac	0.06	1.0" S9.5B	$6,000
2027	5	092-Wake	Preservation	Witherbee Ln	SR 3752	Cul-de-sac	0.29	1.0" S9.5B	$36,000
2027	5	093-Warren	Resurfacing	Read Road	US-158/401	SR 1107	0.98	1.0" S9.5B	$111,000
2027	5	093-Warren	Resurfacing	US 401	Begin C&G	Cousin Lucy Ln	0.40	Full Depth Patching and 1.5" S9.5C	$142,000
2027	5	093-Warren	Resurfacing	US 401	FRANKLIN CO	Begin C&G	11.03	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,710,000
2027	5	093-Warren	Resurfacing	Waverly Thompson	SR 1309	US 158	4.10	1.0" S9.5B	$509,000
2027	5	093-Warren	Resurfacing	Wise Five Forks	SR 1335	SR 1305	7.95	Full Depth Patching and 1.25" S9.5B	$1,546,000
2027	5	093-Warren	Preservation	Cooks Chapel Rd	SR 1305	US 58 Byp	0.88	1.0" S9.5B	$98,000
2027	5	093-Warren	Preservation	Embro-Odell	SR 1507	SR 1521	6.74	Full Depth Patching and Double Seal and Fog Seal	$600,000
2027	5	093-Warren	Preservation	O'Neal Rd	SR 1604	END MAINT	0.66	Full Depth Patching and Double Seal and Fog Seal	$58,000
2027	6	009-Bladen	Resurfacing	NC 211	SR 1134	Robeson Co	6.64	Mill 1.5" and 1.5" S9.5C	$2,556,000
2027	6	009-Bladen	Resurfacing	NC 87 Bypass	NC 41	SR 1145	3.88	Mill 1.5" and 1.5" S9.5C	$1,552,000
2027	6	009-Bladen	Resurfacing	NC 87 Bypass	SR 1145	NC 41	3.88	Mill 1.5" and 1.5" S9.5C	$1,552,000
2027	6	009-Bladen	Preservation	SR 1105	NC 131	NC 410	1.56	Seal - Double	$56,000
2027	6	009-Bladen	Preservation	SR 1106	NC 410	SR 1341	2.63	Seal - Double	$100,000
2027	6	009-Bladen	Preservation	SR 1108	NC 41	NC 87	0.52	Seal - Double	$16,200
2027	6	009-Bladen	Preservation	SR 1154	SR 1155	Dead End	0.59	Seal - Double	$18,800
2027	6	009-Bladen	Preservation	SR 1155	NC 87	NC 41/87	2.33	Seal - Double	$87,500
2027	6	009-Bladen	Preservation	SR 1155	NC 87 BUS	NC 87	1.63	Seal - Double	$60,000
2027	6	009-Bladen	Preservation	SR 1191	NC 131	NC 87	1.93	Seal - Double	$78,800
2027	6	009-Bladen	Preservation	SR 1196	NC 131	End Pvmt	0.60	Seal - Double	$21,200
2027	6	009-Bladen	Preservation	SR 1206	NC 242	SR 1150	0.75	Seal - Cape	$28,700
2027	6	009-Bladen	Preservation	SR 1226	SR 1206	SR 1228	0.15	Seal - Cape	$6,700
2027	6	009-Bladen	Preservation	SR 1227	SR 1226	CDS	0.24	Seal - Cape	$10,000
2027	6	009-Bladen	Preservation	SR 1228	SR 1226	CDS	0.08	Seal - Cape	$3,100
2027	6	009-Bladen	Preservation	SR 1244	SR 1003	CDS	0.49	Seal - Cape	$18,700
2027	6	009-Bladen	Preservation	SR 1336	NC 87	NC 87	6.23	Seal - Double	$250,000
2027	6	009-Bladen	Preservation	SR 1337	NC 87	MP 0.792	0.79	Seal - Double	$31,000
2027	6	009-Bladen	Preservation	SR 1340	NC 87	SR 1336	0.90	Seal - Double	$32,500
2027	6	009-Bladen	Preservation	SR 1341	NC 87	NC 131	2.86	Seal - Double	$106,300
2027	6	009-Bladen	Preservation	SR 1348	NC 87	SR 1108	0.12	Seal - Double	$3,700
2027	6	009-Bladen	Preservation	SR 1357	SR 1336	SR 1361	0.53	Seal - Cape	$31,280
2027	6	009-Bladen	Preservation	SR 1360	SR 1336	Dead End	0.34	Seal - Cape	$12,500
2027	6	009-Bladen	Preservation	SR 1361	SR 1357	SR 1362	0.32	Seal - Cape	$16,200
2027	6	009-Bladen	Preservation	SR 1362	SR 1361	SR 1363	0.10	Seal - Cape	$3,750
2027	6	009-Bladen	Preservation	SR 1363	SR 1362	CDS	0.21	Seal - Cape	$8,100
2027	6	009-Bladen	Preservation	SR 1366	SR 1336	Dead End	0.36	Seal - Cape	$13,700
2027	6	009-Bladen	Preservation	SR 1367	SR 1337	Dead End	0.12	Seal - Double	$4,300
2027	6	024-Columbus	Resurfacing	SR 1001	BRG 021	SR 1907	3.56	1.5" S9.5B	$712,000
2027	6	024-Columbus	Resurfacing	SR 1001	SR 1907	NC 214	1.30	Full Depth Patching and 1.5" S9.5B	$260,000
2027	6	024-Columbus	Resurfacing	SR 1001	BRG 007	BRG 021	0.96	Leveling and 1.5" S9.5B	$192,000
2027	6	024-Columbus	Resurfacing	SR 1209	SR 1170	Dead End	0.10	1.5" S9.5B	$20,000
2027	6	024-Columbus	Resurfacing	SR 1317	SR 1429	NC 410	1.49	1.5" S9.5B	$298,000
2027	6	024-Columbus	Resurfacing	SR 1428	SR 1429	SR 1430	1.25	1.5" S9.5B	$250,000
2027	6	024-Columbus	Resurfacing	SR 1429	SR 1317	US 701	5.16	1.5" S9.5B	$1,032,000
2027	6	024-Columbus	Resurfacing	SR 1437	SR 1429	SR 1436	1.59	1.5" S9.5B	$318,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	6	024-Columbus	Resurfacing	SR 1440	US 74 Bus	SR 1437	0.81	1.5" S9.5B	$162,000
2027	6	024-Columbus	Resurfacing	SR 1757	NCL Lake Waccamaw	NC 214	1.13	1.5" S9.5B	$226,000
2027	6	024-Columbus	Resurfacing	US 701 Bus	SR 1973	SR 1916	1.04	Mill 1.5" and 1.5" S9.5C	$416,000
2027	6	024-Columbus	Resurfacing	US 74 Bus	SR 1567	End C&G	1.88	Mill 1.5" and 1.5" S9.5C	$752,000
2027	6	024-Columbus	Resurfacing	US 74 Bus	SR 1585	SR 1567	6.26	1.5" S9.5C	$2,504,000
2027	6	024-Columbus	Preservation	SR 1003	BLADEN CO	SR 1574	10.68	Seal - Double	$394,000
2027	6	024-Columbus	Preservation	SR 1506	NC 242	SR 1574	3.15	Seal - Double	$112,000
2027	6	024-Columbus	Preservation	SR 1509	SR 1506	NC 242	1.73	Seal - Double	$62,500
2027	6	024-Columbus	Preservation	SR 1510	SR 1574	SR 1509	1.85	Seal - Double	$68,800
2027	6	024-Columbus	Preservation	SR 1513	SR 1574	DEAD END	1.00	Seal - Double	$37,500
2027	6	024-Columbus	Preservation	SR 1516	SR 1506	BLADEN CO	3.60	Seal - Double	$125,000
2027	6	024-Columbus	Preservation	SR 1517	SR 1003	SR 1530	1.09	Seal - Double	$40,000
2027	6	024-Columbus	Preservation	SR 1518	BLADEN CO	NC 242	1.62	Seal - Double	$79,300
2027	6	024-Columbus	Preservation	SR 1519	NC 131	NC 242	5.08	Seal - Double	$187,000
2027	6	024-Columbus	Preservation	SR 1521	SR 1519	SR 1002	1.37	Seal - Double	$50,000
2027	6	024-Columbus	Preservation	SR 1523	SR 1574	SR 1003	0.56	Seal - Double	$20,000
2027	6	024-Columbus	Preservation	SR 1526	SR 1574	END MAINT	0.80	Seal - Double	$25,000
2027	6	024-Columbus	Preservation	SR 1529	SR 1002	SR 1003	0.91	Seal - Double	$33,700
2027	6	024-Columbus	Preservation	SR 1530	SR 1532	NC 131	1.93	Seal - Double	$94,500
2027	6	024-Columbus	Preservation	SR 1532	SR 1519	SR 1003	2.54	Seal - Double	$125,000
2027	6	024-Columbus	Preservation	SR 1539	BLADEN CO	NC 131	0.61	Seal - Double	$22,500
2027	6	024-Columbus	Preservation	SR 1541	BLADEN CO	BLADEN CO	2.24	Seal - Double	$82,500
2027	6	024-Columbus	Preservation	SR 1545	SR 1003	US 701	0.74	Seal - Double	$27,500
2027	6	024-Columbus	Preservation	SR 1577	SR 1574	Dead End	0.81	Seal - Double	$30,000
2027	6	024-Columbus	Preservation	SR 1588	SR 1574	DEAD END	0.07	Seal - Double	$2,500
2027	6	024-Columbus	Preservation	SR 1589	SR 1574	DEAD END	0.08	Seal - Double	$2,500
2027	6	024-Columbus	Preservation	SR 1590	NC 242	DEAD END	0.09	Seal - Double	$3,100
2027	6	024-Columbus	Preservation	SR 1599	SR 1519	SR 1532	1.79	Seal - Double	$62,500
2027	6	024-Columbus	Preservation	SR 1604	NC 242	END PVMT	0.23	Seal - Double	$5,000
2027	6	026-Cumberland	Resurfacing	NC 82	US 13	US 301	5.73	1.5" S9.5B	$1,260,600
2027	6	026-Cumberland	Resurfacing	SR 1104	US 401	SR 1140	3.27	1.5" S9.5B and Widen	$867,610
2027	6	026-Cumberland	Resurfacing	SR 1139	SR 1112	HOKE CO	0.70	1.5" S9.5B	$115,500
2027	6	026-Cumberland	Resurfacing	SR 1140	SR 1104	SR 1112	1.25	1.5" S9.5B and Widen	$343,750
2027	6	026-Cumberland	Resurfacing	SR 1403	Kimridge Drive	SR 1404	0.65	Mill 1.5" and 1.5" S9.5B	$355,850
2027	6	026-Cumberland	Resurfacing	SR 1404	SR 1007	SR 1403	2.22	Mill 1.5" and 1.5" S9.5B	$1,332,000
2027	6	026-Cumberland	Resurfacing	SR 1705	NC 217	SR 1609	3.62	1.5" S9.5B	$597,300
2027	6	026-Cumberland	Resurfacing	SR 1707	Pit Driveway	SR 1700	1.16	1.5" S9.5B	$190,740
2027	6	026-Cumberland	Resurfacing	SR 2035	NC 210	Sampson Co	2.45	Mill 1.5" and 1.5" S9.5B	$539,000
2027	6	026-Cumberland	Resurfacing	SR 3644	SR 1288	DEAD END	0.54	1.5" S9.5B	$89,100
2027	6	026-Cumberland	Resurfacing	SR 3728	SR 1115	CUL-DE-SAC	0.33	1.0" S9.5B	$54,450
2027	6	026-Cumberland	Resurfacing	SR 3729	SR 1116	SR 3728	0.14	1.0" S9.5B	$23,100
2027	6	026-Cumberland	Resurfacing	SR 3730	SR 3729	CUL-DE-SAC	0.08	1.0" S9.5B	$13,200
2027	6	026-Cumberland	Resurfacing	SR 3731	SR 3728	CUL-DE-SAC	0.05	1.0" S9.5B	$8,250
2027	6	026-Cumberland	Resurfacing	SR 3732	SR 3728	CUL-DE-SAC	0.15	1.0" S9.5B	$24,750
2027	6	026-Cumberland	Resurfacing	SR 3733	SR 1115	DEAD END	0.18	1.0" S9.5B	$29,700
2027	6	026-Cumberland	Resurfacing	SR 3734	SR 3733	CUL-DE-SAC	0.08	1.0" S9.5B	$13,200
2027	6	026-Cumberland	Resurfacing	SR 4086	SR 1288	DEAD END	0.42	1.5" S9.5B	$69,300
2027	6	026-Cumberland	Resurfacing	SR 4902	SR 4086	DEAD END	0.44	1.5" S9.5B	$72,105
2027	6	026-Cumberland	Resurfacing	US 301 / 95 BUS	SR 2337	SR 1006	0.75	1.5" S9.5B	$239,800
2027	6	026-Cumberland	Resurfacing	US 301 / 95 BUS	SR 1006	SR 2337	0.74	1.5" S9.5B	$237,600
2027	6	026-Cumberland	Resurfacing	US 401	NC 210	US 401 BUS	2.23	Mill 2.0" and 2.0" S9.5C	$1,360,300
2027	6	043-Harnett	Resurfacing	NC 27	NC 55	Johnston Co	5.90	Mill 1.5" and 1.5" S9.5B	$1,298,000
2027	6	043-Harnett	Resurfacing	SR 1120	NC 210	SR 2045	3.02	1.5" S9.5B	$453,000
2027	6	043-Harnett	Resurfacing	SR 1705	SR 1581	SR 1714	3.75	1.5" S9.5B	$562,500
2027	6	043-Harnett	Resurfacing	SR 1715	SR 1705	SR 1722	1.69	1.5" S9.5B	$253,350
2027	6	043-Harnett	Resurfacing	SR 1723	SR 1703	NC 55	1.94	1.5" S9.5B	$290,850
2027	6	043-Harnett	Resurfacing	SR 1769	ERWIN CITY LIMITS	SR 2014+.371 MI	3.22	1.5" S9.5B	$483,000
2027	6	043-Harnett	Resurfacing	SR 1793	US 301	SR 1837	0.94	Mill 1.5" and 1.5" S9.5B	$376,000
2027	6	043-Harnett	Resurfacing	SR 1799	SR 1808	SAMPSON CO	1.24	1.5" S9.5B and Widen	$310,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	6	043-Harnett	Resurfacing	SR 1902	US 301	CUL-DE-SAC	0.11	1.5" S9.5B	$16,500
2027	6	043-Harnett	Resurfacing	SR 1914	SR 1802	CUL-DE-SAC	0.38	1.5" S9.5B	$57,000
2027	6	043-Harnett	Resurfacing	SR 2005	NC 27	NC 55	3.38	5.0" B25.0B	$338,000
2027	6	043-Harnett	Resurfacing	SR 2021	US 401	NC 217	6.68	1.5" S9.5B	$1,002,000
2027	6	043-Harnett	Resurfacing	SR 2045	SR 2030	Cumberland Co	5.59	1.5" S9.5B	$838,500
2027	6	043-Harnett	Resurfacing	SR 2048	SR 2045	NC 210	3.45	5.0" B25.0B	$345,000
2027	6	043-Harnett	Resurfacing	SR 2239	SR 1116	DEAD END	0.80	1.5" S9.5B	$200,000
2027	6	043-Harnett	Resurfacing	SR 2614	SR 2239	SR 2615	0.08	1.5" S9.5B	$15,600
2027	6	043-Harnett	Resurfacing	SR 2615	SR 2614	DEAD END	0.04	1.5" S9.5B	$7,800
2027	6	043-Harnett	Resurfacing	SR 2616	SR 2615	CUL-DE-SAC	0.04	1.5" S9.5B	$7,800
2027	6	043-Harnett	Resurfacing	SR 2617	SR 2239	CUL-DE-SAC	0.12	1.5" S9.5B	$23,400
2027	6	043-Harnett	Resurfacing	US 301	SR 1808	ELLIS AVE	0.49	Mill 1.5" and 1.5" S9.5B	$110,250
2027	6	043-Harnett	Resurfacing	US 421	US 401	SR 1291	0.58	1.5" S9.5C	$323,400
2027	6	043-Harnett	Preservation	SR 1705	SR 1714	US 301	2.11	Seal - Split	$95,000
2027	6	043-Harnett	Preservation	SR 1707	SR 1709	SR 1711	2.48	Seal - Split	$111,900
2027	6	043-Harnett	Preservation	SR 1708	SR 1707	SR 1709	1.06	Seal - Split	$37,500
2027	6	043-Harnett	Preservation	SR 1709	NC 27	SR 1808	4.59	Seal - Split	$206,800
2027	6	043-Harnett	Preservation	SR 1712	SR 1802	SR 1705	3.19	Seal - Split	$143,500
2027	6	043-Harnett	Preservation	SR 1714	SR 1712	SR 1705	0.99	Seal - Split	$44,500
2027	6	043-Harnett	Preservation	SR 1721	SR 1725	SR 1725	0.52	Seal - Split	$18,700
2027	6	043-Harnett	Preservation	SR 1722	SR 1705	SR 1703	1.66	Seal - Split	$75,000
2027	6	043-Harnett	Preservation	SR 1789	SR 1808	SR 1799	1.25	Seal - Split	$56,000
2027	6	043-Harnett	Preservation	SR 1800	US 301	END MAINT.	0.26	Seal - Split	$12,000
2027	6	043-Harnett	Preservation	SR 1801	SR 1712	US 301	0.53	Seal - Split	$17,500
2027	6	043-Harnett	Preservation	SR 1802	SR 1808	SR 1810	1.82	Seal - Split	$62,500
2027	6	043-Harnett	Preservation	SR 1803	SR 1802	SR 1835	0.54	Seal - Split	$17,500
2027	6	043-Harnett	Preservation	SR 1805	SR 1803	SR 1810	1.74	Seal - Split	$62,500
2027	6	043-Harnett	Preservation	SR 1806	SR 1803	SR 1810	1.50	Seal - Split	$55,000
2027	6	043-Harnett	Preservation	SR 1807	SR 1806	END PVMT	0.43	Seal - Split	$15,000
2027	6	043-Harnett	Preservation	SR 1810	US 301	SR 1834	1.54	Seal - Split	$62,500
2027	6	043-Harnett	Preservation	SR 1834	BGN MAINT	SR 1810	0.10	Seal - Split	$3,700
2027	6	043-Harnett	Preservation	SR 1835	SR 1709	SR 1808	2.11	Seal - Split	$95,000
2027	6	043-Harnett	Preservation	SR 1840	BGN MAINT	SR 1709	0.81	Seal - Split	$38,700
2027	6	043-Harnett	Preservation	SR 1841	SR 1808	SR 1709	1.91	Seal - Split	$90,000
2027	6	043-Harnett	Preservation	SR 1884	E Broad ST	END MAINT	0.49	Seal - Split	$17,500
2027	6	043-Harnett	Preservation	SR 1889	SR 1720	US421	0.48	Seal - Split	$17,500
2027	6	078-Robeson	Resurfacing	NC 130	NC 130 BUS	NC 130 BYP	0.51	1.5" S9.5B	$102,000
2027	6	078-Robeson	Resurfacing	NC 130	US 501	NC 83	4.11	1.5" S9.5B	$822,000
2027	6	078-Robeson	Resurfacing	NC 130 BYP	NC 130	NC130	3.44	1.5" S9.5B	$688,000
2027	6	078-Robeson	Resurfacing	SR 1339	SR 1303	SR 1338	2.43	1.5" S9.5B	$432,000
2027	6	078-Robeson	Resurfacing	SR 1515	NC 72	NC 211	3.58	1.5" S9.5B	$648,000
2027	6	078-Robeson	Resurfacing	SR 1528	NC 211	SR 1527	2.16	1.5" S9.5B	$396,000
2027	6	078-Robeson	Resurfacing	SR 1529	SR 1528	NC 211	0.44	1.5" S9.5B	$80,000
2027	6	078-Robeson	Resurfacing	SR 1632	SR 1339	SR 1604	0.35	1.0" S9.5B	$42,000
2027	6	078-Robeson	Resurfacing	SR 2209	NC 41	SR 2208	1.60	1.5" S9.5B	$288,000
2027	6	078-Robeson	Resurfacing	SR 2230	SR 2235	SR 2225	5.32	1.5" S9.5B	$1,060,000
2027	6	078-Robeson	Resurfacing	SR 2233	SR 2230	SR 2208	2.05	1.5" S9.5B	$360,000
2027	6	078-Robeson	Resurfacing	SR 2241	SR 2208	SR 2235	2.50	1.5" S9.5B	$450,000
2027	6	078-Robeson	Resurfacing	SR 2242	SR 2208	SR 2235	2.27	1.5" S9.5B	$408,000
2027	6	078-Robeson	Resurfacing	SR 2278	SR 2277	NC 41	1.88	1.5" S9.5B	$342,000
2027	6	078-Robeson	Resurfacing	SR 2298	NC 41	NC 130	1.12	1.5" S9.5A	$220,000
2027	6	078-Robeson	Resurfacing	SR 2424	SR 2426	SR 2422 + .2 MI	1.87	1.5" S9.5B	$342,000
2027	6	078-Robeson	Resurfacing	SR 2453	NC 41	SR 2454	3.00	1.5" S9.5B	$540,000
2027	6	078-Robeson	Resurfacing	SR 2455	NC 904	US 301	10.59	1.5" S9.5B	$1,890,000
2027	6	078-Robeson	Resurfacing	SR 2465	NC 904	NC 130	1.85	1.5" S9.5B	$342,000
2027	6	078-Robeson	Resurfacing	SR 2472	SR 2476	NC 41	3.15	1.5" S9.5B	$567,000
2027	6	078-Robeson	Resurfacing	SR 2473	NC 904	SR 2472	1.30	1.5" S9.5B	$234,000
2027	6	078-Robeson	Resurfacing	SR 2479	SR 2478	SR 2482	2.65	1.5" S9.5B	$530,000
2027	6	078-Robeson	Resurfacing	SR1169	SR 1168	SR 1170	1.12	1.5" S9.5B	$201,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	6	078-Robeson	Preservation	SR 2258	SR 2282	NC 904	1.69	Seal - Split	$56,300
2027	6	078-Robeson	Preservation	SR 2277	SR 2472	SR 2282	3.61	Seal - Split	$125,000
2027	6	078-Robeson	Preservation	SR 2278	SR 2277	SR 2258	3.15	Seal - Split	$112,600
2027	6	078-Robeson	Preservation	SR 2279	SR 2277	SR 2258	0.08	Seal - Split	$3,900
2027	6	078-Robeson	Preservation	SR 2281	SR 2285	SR 2277	0.82	Seal - Double	$40,000
2027	6	078-Robeson	Preservation	SR 2284	SR 2282	SR 2283	0.67	Seal - Split	$32,800
2027	6	078-Robeson	Preservation	SR 2286	SR 2282	NC 904	0.45	Seal - Double	$22,000
2027	6	078-Robeson	Preservation	SR 2287	SR 2283	DEAD END	0.81	Seal - Split	$39,600
2027	6	078-Robeson	Preservation	SR 2324	NC 41	DEAD END	0.21	Seal - Split	$10,000
2027	6	078-Robeson	Preservation	SR 2336	SR 2278	SR 2280	0.44	Seal - Split	$21,500
2027	6	078-Robeson	Preservation	SR 2462	SR 2485	SR 2489	2.77	Seal - Split	$93,800
2027	6	078-Robeson	Preservation	SR 2465	NC 904	NC 130	1.87	Seal - Split	$68,800
2027	6	078-Robeson	Preservation	SR 2471	NC 904	SR 2472	0.90	Seal - Split	$31,280
2027	6	078-Robeson	Preservation	SR 2472	SR 2481	NC 41	4.46	Seal - Split	$162,500
2027	6	078-Robeson	Preservation	SR 2473	NC 904	SR 2472	1.30	Seal - Split	$47,500
2027	6	078-Robeson	Preservation	SR 2474	SR 2278	SR 2278	1.47	Seal - Split	$53,800
2027	6	078-Robeson	Preservation	SR 2475	SC SL	SR 2477	0.66	Seal - Split	$23,700
2027	6	078-Robeson	Preservation	SR 2476	SC SL	SR 2472	1.70	Seal - Split	$62,500
2027	6	078-Robeson	Preservation	SR 2477	SR 2278	SR 2476	1.47	Seal - Split	$53,800
2027	6	078-Robeson	Preservation	SR 2478	SR 2477	NC 904	2.50	Seal - Split	$92,500
2027	6	078-Robeson	Preservation	SR 2479	SR 2478	SR 2482	2.65	Seal - Split	$97,500
2027	6	078-Robeson	Preservation	SR 2481	SR 2482	SR 2489	3.55	Seal - Split	$131,500
2027	6	078-Robeson	Preservation	SR 2482	SC SL	NC 904	2.83	Seal - Split	$100,000
2027	6	078-Robeson	Preservation	SR 2484	SR 2481	DEAD END	0.58	Seal - Split	$21,250
2027	6	078-Robeson	Preservation	SR 2485	SC SL	NC 904	3.11	Seal - Split	$112,000
2027	6	078-Robeson	Preservation	SR 2486	SR 2462	SR 2481	1.34	Seal - Split	$50,000
2027	6	078-Robeson	Preservation	SR 2488	SR 2462	SC LINE	0.33	Seal - Split	$11,260
2027	6	078-Robeson	Preservation	SR 2489	SC SL	NC 130	2.38	Seal - Double	$89,000
2027	6	078-Robeson	Preservation	SR 2535	SR 2485	SR 2482	1.78	Seal - Split	$56,300
2027	7	001-Alamance	Resurfacing	Boywood Rd.	SR 2116	NC 87	1.61	#78 Mat Seal and 1.5" S9.5B	$689,050
2027	7	001-Alamance	Resurfacing	Lowder Rd.	SR 1002	SR 1761	1.86	#78 Mat Seal and 1.5" S9.5B	$484,980
2027	7	001-Alamance	Resurfacing	NC 49 (S)	RCL	Lewis Dr.	15.53	#78 Mat Seal and 1.5" S9.5B	$2,755,434
2027	7	001-Alamance	Resurfacing	Pleasant Hill Church Rd.	SR 1005	CCL	4.78	#78 Mat Seal and 1.5" S9.5B	$1,250,000
2027	7	001-Alamance	Resurfacing	Preacher Homes Rd.	NC 87	SR 2116	3.77	#78 Mat Seal and 1.5" S9.5B	$993,850
2027	7	001-Alamance	Resurfacing	Willie Pace Rd.	NC 119	SR 1761	3.48	#78 Mat Seal and 1.5" S9.5B	$922,250
2027	7	001-Alamance	Preservation	Albert Jeffries Rd.	SR 1754	END MAINT	0.20	Seal - Double and Fog Seal	$7,900
2027	7	001-Alamance	Preservation	Boone Lane Rd.	SR 1002	NC 62	1.07	Seal - Double and Fog Seal	$36,500
2027	7	001-Alamance	Preservation	Earl Kimber Rd.	SR 1001	END MAINT	0.33	Seal - Double and Fog Seal	$11,500
2027	7	001-Alamance	Preservation	Ellis Jeffries Rd.	SR 1754	END MAINT	0.34	Seal - Double and Fog Seal	$11,600
2027	7	001-Alamance	Preservation	Faucete Lane	SR 1729	NC 62	1.38	Seal - Double and Fog Seal	$47,000
2027	7	001-Alamance	Preservation	Fonville Rd.	SR 1752	SR 1729	0.68	Seal - Double and Fog Seal	$23,200
2027	7	001-Alamance	Preservation	George Miles Rd.	SR 1761	END MAINT	0.45	Seal - Double and Fog Seal	$16,700
2027	7	001-Alamance	Preservation	Harvey Chandler Rd.	SR 1754	NC 62	0.08	Seal - Double and Fog Seal	$2,800
2027	7	001-Alamance	Preservation	Hassell Corbett Rd.	SR 1002	END MAINT	0.50	Seal - Double and Fog Seal	$17,800
2027	7	001-Alamance	Preservation	Hughes Mill Rd.	NC 62	CCL	0.09	Seal - Double and Fog Seal	$3,100
2027	7	001-Alamance	Preservation	Hughes Mill Rd.	NC 62	SR 1761	2.30	Seal - Double and Fog Seal	$78,300
2027	7	001-Alamance	Preservation	Jim Barnwell Rd.	SR 1750	END MAINT	0.14	Seal - Double and Fog Seal	$4,800
2027	7	001-Alamance	Preservation	Kimber Rd.	SR 1761	END MAINT	0.10	Seal - Double and Fog Seal	$4,100
2027	7	001-Alamance	Preservation	Little Egypt Rd.	SR 1190	SR 1128	0.49	Seal - Double and Fog Seal	$18,000
2027	7	001-Alamance	Preservation	Louis Graham Rd.	SR 1754	NC 62	1.17	Seal - Double and Fog Seal	$39,900
2027	7	001-Alamance	Preservation	Martins Chapel Rd.	NC 119	END MAINT	0.45	Seal - Double and Fog Seal	$15,500
2027	7	001-Alamance	Preservation	McCauley Rd.	SR 1764	NC 62	0.98	Seal - Double and Fog Seal	$33,500
2027	7	001-Alamance	Preservation	Ms. Blanchard Rd.	SR 1729	END MAINT	0.41	Seal - Double and Fog Seal	$16,500
2027	7	001-Alamance	Preservation	Odell King Rd.	SR 1761	END MAINT	0.46	Seal - Double and Fog Seal	$15,700
2027	7	001-Alamance	Preservation	Old Stoney Mtn. Rd.	SR 1614	CCL	0.31	Seal - Double and Fog Seal	$10,600
2027	7	001-Alamance	Preservation	Oliver Ln.	SR 1001	END MAINT	0.22	Seal - Double and Fog Seal	$6,600
2027	7	001-Alamance	Preservation	Oscar Bailey Rd.	NC 62	END MAINT	0.24	Seal - Double and Fog Seal	$8,600
2027	7	001-Alamance	Preservation	Patillo Church Rd.	SR 1762	NC 62	2.54	Seal - Double and Fog Seal	$86,500
2027	7	001-Alamance	Preservation	Rascoe Rd.	SR 1001	CCL	1.30	Seal - Double and Fog Seal	$44,300

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	7	001-Alamance	Preservation	Roney-Line Berry Rd.	SR 1729	END MAINT	0.30	Seal - Double and Fog Seal	$11,400
2027	7	001-Alamance	Preservation	Shady Lane	NC 119	END MAINT	0.20	Seal - Double and Fog Seal	$20,500
2027	7	001-Alamance	Preservation	SR 3300 E 7th St	Charlottetowne Ave	N Laurel Ave	0.90	Rejuvenator	$23,748
2027	7	001-Alamance	Preservation	Stoney Mtn. Rd.	SR 1001	CCL	1.98	Seal - Double and Fog Seal	$74,900
2027	7	001-Alamance	Preservation	Willi Pace Rd.	SR 1761	SR 1001	1.46	Seal - Double and Fog Seal	$49,700
2027	7	001-Alamance	Preservation	William Allen Rd.	SR 1754	END MAINT	0.24	Patching and Double Seal and Fog Seal	$8,200
2027	7	001-Alamance	Preservation	Wyatt Lane	SR 1754	END MAINT	0.54	Seal - Double and Fog Seal	$18,500
2027	7	017-Caswell	Resurfacing	(N) Ninth Avenue	SR 1163	US 158	0.15	#78 Mat Seal and 1.5" S9.5B	$39,800
2027	7	017-Caswell	Resurfacing	(N) Tenth Avenue	SR 1163	US 158	0.22	#78 Mat Seal and 1.5" S9.5B	$58,400
2027	7	017-Caswell	Resurfacing	(S) Second Street	SR 1156	SR 1171	0.02	#78 Mat Seal and 1.5" S9.5B	$53,100
2027	7	017-Caswell	Resurfacing	(S) Seventh St.	SR 1158	END MAINT	0.20	#78 Mat Seal and 1.5" S9.5B	$53,200
2027	7	017-Caswell	Resurfacing	Annie Compton Rd.	SR 1503	VSL	0.09	#78 Mat Seal and 1.5" S9.5B	$23,900
2027	7	017-Caswell	Resurfacing	Atwater St.	SR 1163	US 158	0.28	#78 Mat Seal and 1.5" S9.5B	$74,250
2027	7	017-Caswell	Resurfacing	Barco St.	SR 1156	END MAINT	0.01	#78 Mat Seal and 1.5" S9.5B	$50,500
2027	7	017-Caswell	Resurfacing	Business Park Dr.	SR 1572	END MAINT	0.10	#78 Mat Seal and 1.5" S9.5B	$47,800
2027	7	017-Caswell	Resurfacing	Cemetary Street	SR 1142	SR 1143	0.05	#78 Mat Seal and 1.5" S9.5B	$13,300
2027	7	017-Caswell	Resurfacing	Chandler's Mill Rd.	SR 1372	RCL	2.00	#78 Mat Seal and 1.5" S9.5B	$530,100
2027	7	017-Caswell	Resurfacing	Church St.	SR 1585	SR 1156	0.60	#78 Mat Seal and 1.5" S9.5B	$159,100
2027	7	017-Caswell	Resurfacing	Club House Rd.	SR 1572	END PVMT	0.10	#78 Mat Seal and 1.5" S9.5A	$26,520
2027	7	017-Caswell	Resurfacing	Clubhouse Rd.	SR 1572	DEAD END	0.50	#78 Mat Seal and 1.5" S9.5B	$26,600
2027	7	017-Caswell	Resurfacing	Cooper-Rodgers Rd.	SR 1156	END MAINT	0.02	#78 Mat Seal and 1.5" S9.5B	$53,100
2027	7	017-Caswell	Resurfacing	County Park Rd.	US 158	SR 1586	0.15	#78 Mat Seal and 1.5" S9.5B	$39,800
2027	7	017-Caswell	Resurfacing	Court Square	SR 1156	END MAINT	0.02	#78 Mat Seal and 1.5" S9.5B	$6,000
2027	7	017-Caswell	Resurfacing	Dillard School Dr.	US 158	END MAINT	0.08	#78 Mat Seal and 1.5" S9.5B	$111,400
2027	7	017-Caswell	Resurfacing	Eighth Avenue	SR 1163	END MAINT	0.03	#78 Mat Seal and 1.5" S9.5B	$84,900
2027	7	017-Caswell	Resurfacing	Fire Department Dr.	SR 1156	END MAINT	0.05	#78 Mat Seal and 1.5" S9.5B	$13,300
2027	7	017-Caswell	Resurfacing	Fire Tower Rd.	SR 1572	NC 86	1.00	#78 Mat Seal and 1.5" S9.5B	$265,200
2027	7	017-Caswell	Resurfacing	First Avenue	SR 1585	SR 1586	0.02	#78 Mat Seal and 1.5" S9.5B	$71,600
2027	7	017-Caswell	Resurfacing	Fourth Avenue	SR 1583	SR 1163	0.23	#78 Mat Seal and 1.5" S9.5B	$61,000
2027	7	017-Caswell	Resurfacing	Gwynn Street	SR 1743	SR 1742	0.05	#78 Mat Seal and 1.5" S9.5B	$13,300
2027	7	017-Caswell	Resurfacing	Hooper St.	SR 1163	SR 1156	0.15	#78 Mat Seal and 1.5" S9.5B	$39,900
2027	7	017-Caswell	Resurfacing	Julia St.	SR 1739	END MAINT	0.10	#78 Mat Seal and 1.5" S9.5B	$26,500
2027	7	017-Caswell	Resurfacing	Kimbro St.	US 158	NC 62	0.67	#78 Mat Seal and 1.5" S9.5B	$177,600
2027	7	017-Caswell	Resurfacing	Lee St.	SR 1739	END MAINT	0.06	#78 Mat Seal and 1.5" S9.5B	$16,000
2027	7	017-Caswell	Resurfacing	Murphy St.	NC 62	END MAINT	0.10	#78 Mat Seal and 1.5" S9.5B	$26,500
2027	7	017-Caswell	Resurfacing	Murray Rd.	SR 1572	END MAINT	0.81	#78 Mat Seal and 1.5" S9.5B	$214,800
2027	7	017-Caswell	Resurfacing	Nicks Hooper Rd.	NC 86	END MAINT	0.10	#78 Mat Seal and 1.5" S9.5B	$26,200
2027	7	017-Caswell	Resurfacing	North Avenue	NC 86	SR 1163	0.29	#78 Mat Seal and 1.5" S9.5B	$76,900
2027	7	017-Caswell	Resurfacing	Oaktree Street	SR 1156	END MAINT	0.05	#78 Mat Seal and 1.5" S9.5B	$132,600
2027	7	017-Caswell	Resurfacing	Pemberton St.	US 158	SR 1156	0.28	#78 Mat Seal and 1.5" S9.5B	$74,300
2027	7	017-Caswell	Resurfacing	Piedmont Dr.-PCC	NC 62	END MAINT	0.09	#78 Mat Seal and 1.5" S9.5B	$23,900
2027	7	017-Caswell	Resurfacing	School Dr.	SR 1739	NC 62	0.02	#78 Mat Seal and 1.5" S9.5B	$69,000
2027	7	017-Caswell	Resurfacing	Sixth Avenue	SR 1163	SR 1163	0.17	#78 Mat Seal and 1.5" S9.5B	$45,100
2027	7	017-Caswell	Resurfacing	Sunline Dr.	SR 1589	END MAINT	0.17	#78 Mat Seal and 1.5" S9.5B	$45,100
2027	7	017-Caswell	Resurfacing	Third Avenue	SR 1585	SR 1156	0.20	#78 Mat Seal and 1.5" S9.5B	$159,100
2027	7	017-Caswell	Resurfacing	Wall Street	SR 1163	SR 1589	1.04	#78 Mat Seal and 1.5" S9.5B	$275,620
2027	7	017-Caswell	Resurfacing	West Main St.	SR 1744	SR 1741	0.40	#78 Mat Seal and 1.5" S9.5B	$106,100
2027	7	017-Caswell	Preservation	Bill Powell Rd.	SR 1523	END MAINT	0.37	Seal - Double and Fog Seal	$12,700
2027	7	017-Caswell	Preservation	Blanch Rd.	SR 1500	NC 62	7.99	Seal - Double and Fog Seal	$245,000
2027	7	017-Caswell	Preservation	Blanch Road Extension	SR 1500	SR 1523	0.24	Seal - Double and Fog Seal	$9,500
2027	7	017-Caswell	Preservation	County Home Rd.	SR 1521	END MAINT	1.00	Seal - Double and Fog Seal	$30,500
2027	7	017-Caswell	Preservation	Crooked Rd.	SR 1523	END MAINT	0.60	Seal - Double and Fog Seal	$18,700
2027	7	017-Caswell	Preservation	Crumpton Rd.	NC 62	END MAINT	0.50	Seal - Double and Fog Seal	$15,500
2027	7	017-Caswell	Preservation	Dailey Rd.	SR 1523	END MAINT	1.00	Seal - Double and Fog Seal	$31,000
2027	7	017-Caswell	Preservation	Files Rd.	SR 1572	END MAINT	2.29	Seal - Double and Fog Seal	$69,500
2027	7	017-Caswell	Preservation	Fire Tower Rd.	SR 1572	NC 86	1.00	Seal - Double and Fog Seal	$30,500
2027	7	017-Caswell	Preservation	Guthrie Rd.	SR 1521	END MAINT	0.54	Seal - Double and Fog Seal	$18,500
2027	7	017-Caswell	Preservation	Hines Hatchett Rd.	SR 1500	END MAINT	0.79	Seal - Double and Fog Seal	$24,500
2027	7	017-Caswell	Preservation	Melvin Wrenn Rd.	NC 86	SR 1500	1.56	Seal - Double and Fog Seal	$48,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	7	017-Caswell	Preservation	Purley Church Rd.	NC 86	SR 1500	1.14	Seal - Double and Fog Seal	$36,700
2027	7	017-Caswell	Preservation	Slade Rd.	SR 1523	NC 62	4.20	Seal - Double and Fog Seal	$131,000
2027	7	017-Caswell	Preservation	Sunline Dr.	SR 1589	END MAINT	0.17	Seal - Double and Fog Seal	$6,000
2027	7	017-Caswell	Preservation	Twin Chimney Rd.	SR 1521	END MAINT	1.50	Seal - Double and Fog Seal	$45,500
2027	7	017-Caswell	Preservation	Vernon Rd.	NC 62	END MAINT	0.74	Seal - Double and Fog Seal	$24,500
2027	7	017-Caswell	Preservation	Weadon Rd.	SR 1523	END MAINT	1.10	Seal - Double and Fog Seal	$33,500
2027	7	041-Guilford	Resurfacing	29 Service Rd.	US 29	DEAD END	0.25	#78 Mat Seal and 1.5" S9.5B	$66,253
2027	7	041-Guilford	Resurfacing	Agatha Dr.	SR 2107	END MAINT	0.16	#78 Mat Seal and 1.5" S9.5A	$28,500
2027	7	041-Guilford	Resurfacing	Allenwood Rd.	SR 2746	DEADEND	0.23	#78 Mat Seal and 1.5" S9.5B	$61,000
2027	7	041-Guilford	Resurfacing	Allred Farm Way	SR 3285	DEAD END	0.21	#78 Mat Seal and 1.5" S9.5B	$55,700
2027	7	041-Guilford	Resurfacing	Anita Ln.	US 29	CUL-DE-SAC	0.28	#78 Mat Seal and 1.5" S9.5B	$74,300
2027	7	041-Guilford	Resurfacing	April Ln.	US 29	SR 2917	0.15	#78 Mat Seal and 1.5" S9.5B	$39,800
2027	7	041-Guilford	Resurfacing	Assembly Rd.	BEG MAINT	CUL-DE-SAC	0.42	#78 Mat Seal and 1.5" S9.5B	$111,300
2027	7	041-Guilford	Resurfacing	Autumn Lake Dr.	NC 150	END MAINT	0.24	#78 Mat Seal and 1.5" S9.5A	$42,500
2027	7	041-Guilford	Resurfacing	Beachland Rd.	DEAD END	DEAD END	0.10	#78 Mat Seal and 1.5" S9.5B	$26,600
2027	7	041-Guilford	Resurfacing	Beaverbrook Dr.	SR 3207	DEADEND	0.36	#78 Mat Seal and 1.5" S9.5B	$95,500
2027	7	041-Guilford	Resurfacing	Bentwood Dr.	SR 4744	SR 4746	0.21	#78 Mat Seal and 1.5" S9.5B	$55,700
2027	7	041-Guilford	Resurfacing	Blue Lantern Rd.	SR 2808	SR 2887	0.85	#78 Mat Seal and 1.5" S9.5B	$225,300
2027	7	041-Guilford	Resurfacing	Bostonian Dr.	NC 150	SR 5425	0.45	#78 Mat Seal and 1.5" S9.5B	$119,256
2027	7	041-Guilford	Resurfacing	Breezy Hill Rd.	SR 2700	DEAD END	0.27	#78 Mat Seal and 1.5" S9.5B	$71,600
2027	7	041-Guilford	Resurfacing	Brent Rd.	SR 2523	DEAD END	0.26	#78 Mat Seal and 1.5" S9.5B	$68,903
2027	7	041-Guilford	Resurfacing	Brooke Dylan Ct.	SR 4746	CUL-DE-SAC	0.12	#78 Mat Seal and 1.5" S9.5B	$31,900
2027	7	041-Guilford	Resurfacing	Brooke Ellen Ct.	SR 5245	CUL-DE-SAC	0.09	#78 Mat Seal and 1.5" S9.5B	$23,851
2027	7	041-Guilford	Resurfacing	Bryant's Way Dr.	SR 2565	CUL-DE-SAC	0.24	#78 Mat Seal and 1.5" S9.5B	$63,700
2027	7	041-Guilford	Resurfacing	Buck Land Dr.	SR 4754	DEAD END	0.17	#78 Mat Seal and 1.5" S9.5B	$45,100
2027	7	041-Guilford	Resurfacing	Cannan Forest Dr.	SR 2835	SR 5343	0.17	#78 Mat Seal and 1.5" S9.5B	$45,100
2027	7	041-Guilford	Resurfacing	Carla Ln.	SR 2788	DEADEND	0.22	#78 Mat Seal and 1.5" S9.5B	$58,400
2027	7	041-Guilford	Resurfacing	Carson Ridge Dt.	SR 2007	CUL-DE-SAC	0.09	#78 Mat Seal and 1.5" S9.5B	$61,900
2027	7	041-Guilford	Resurfacing	Carson Valley Rd.	SR 2190	CUL-DE-SAC	0.18	#78 Mat Seal and 1.5" S9.5B	$47,500
2027	7	041-Guilford	Resurfacing	Cedar Creek Rd.	SR 2926	DEAD END	0.29	#78 Mat Seal and 1.5" S9.5B	$76,900
2027	7	041-Guilford	Resurfacing	Cedar Springs Dr.	SR 1818	SR 1968	0.37	#78 Mat Seal and 1.5" S9.5A	$65,500
2027	7	041-Guilford	Resurfacing	Cedarline Dr.	SR 2269	END MAINT	0.32	#78 Mat Seal and 1.5" S9.5A	$56,600
2027	7	041-Guilford	Resurfacing	Claire-Mont Dr.	SR 2514	SR 4778	0.23	#78 Mat Seal and 1.5" S9.5B	$61,000
2027	7	041-Guilford	Resurfacing	Cobbletone Walk Dr.	SR 1001	CUL-DE-SAC	0.33	#78 Mat Seal and 1.5" S9.5B	$87,454
2027	7	041-Guilford	Resurfacing	Country Hill Dr.	SR 2565	DEAD END	0.22	#78 Mat Seal and 1.5" S9.5B	$58,400
2027	7	041-Guilford	Resurfacing	Creek Ln.	SR 2808	DEAD END	0.27	#78 Mat Seal and 1.5" S9.5B	$71,600
2027	7	041-Guilford	Resurfacing	Crestway Dr.	SR 2011	SR 2275	0.18	#78 Mat Seal and 1.5" S9.5A	$31,900
2027	7	041-Guilford	Resurfacing	Cude Rd.	SR 2010	SR 2133	0.49	#78 Mat Seal and 1.5" S9.5B	$368,370
2027	7	041-Guilford	Resurfacing	Danbrook Rd.	SR 2746	DEAD END	0.36	#78 Mat Seal and 1.5" S9.5B	$95,500
2027	7	041-Guilford	Resurfacing	Dapple Grey Rd.	SR 1858	END MAINT	0.34	#78 Mat Seal and 1.5" S9.5A	$60,500
2027	7	041-Guilford	Resurfacing	Donvic Dr.	SR 2273	END MAINT	0.19	#78 Mat Seal and 1.5" S9.5A	$35,700
2027	7	041-Guilford	Resurfacing	East Belgave Terrace	SR 4817	END MAINT	0.06	#78 Mat Seal and 1.5" S9.5A	$10,700
2027	7	041-Guilford	Resurfacing	Elmont Rd.	NC 61	DEAD END	0.29	#78 Mat Seal and 1.5" S9.5B	$76,900
2027	7	041-Guilford	Resurfacing	Fairway Run Dr.	SR 2714	DEAD END	0.45	#78 Mat Seal and 1.5" S9.5B	$119,270
2027	7	041-Guilford	Resurfacing	Faye Dr.	SR 3803	END MAINT	0.42	#78 Mat Seal and 1.5" S9.5A	$89,000
2027	7	041-Guilford	Resurfacing	Franz Warner Parkway	SR 3056	CUL-DE-SAC	0.43	Mill 1.5" and 1.5" S9.5B	$23,588
2027	7	041-Guilford	Resurfacing	Friendhip Glen Dr.	SR 2728	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$233,300
2027	7	041-Guilford	Resurfacing	Friendship Glen Ct.	SR 4754	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$18,600
2027	7	041-Guilford	Resurfacing	Gwynodd Rd.	SR 2128	END MAINT	0.06	#78 Mat Seal and 1.5" S9.5B	$14,500
2027	7	041-Guilford	Resurfacing	Hackamore Rd.	SR 2124	CUL-DE-SAC	0.39	#78 Mat Seal and 1.5" S9.5B	$104,200
2027	7	041-Guilford	Resurfacing	Hartstone Dr.	SR 1855	END MAINT	0.13	#78 Mat Seal and 1.5" S9.5A	$23,000
2027	7	041-Guilford	Resurfacing	Hearthridge Ct.	SR 2028	END MAINT	0.15	#78 Mat Seal and 1.5" S9.5A	$26,700
2027	7	041-Guilford	Resurfacing	High Rock Rd.	SR 2770	SR2746	2.28	#78 Mat Seal and 1.5" S9.5B	$606,900
2027	7	041-Guilford	Resurfacing	Holden Rd./Harris Dr.	SR 1104	SR 4059	1.55	#78 Mat Seal and 1.5" S9.5B	$409,500
2027	7	041-Guilford	Resurfacing	Holly Glen Dr.	SR 4847	END MAINT	0.28	#78 Mat Seal and 1.5" S9.5A	$49,700
2027	7	041-Guilford	Resurfacing	I-73	PVMT CHANGE	PVMT CHANGE	1.00	#78 Mat Seal and 1.5" S9.5B	$804,300
2027	7	041-Guilford	Resurfacing	I-73	PVMT CHANGE	PVMT CHANGE	1.00	#78 Mat Seal and 1.5" S9.5B	$804,300
2027	7	041-Guilford	Resurfacing	Jones-Little Rd.	SR 2560	SR 5211	0.17	#78 Mat Seal and 1.5" S9.5B	$45,100
2027	7	041-Guilford	Resurfacing	Kelford Dr.	SR 3729	DEAD END	0.16	#78 Mat Seal and 1.5" S9.5B	$42,400

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	7	041-Guilford	Resurfacing	Kivett Dairy Rd.	SR 3051	DEAD END	0.29	#78 Mat Seal and 1.5" S9.5B	$76,900
2027	7	041-Guilford	Resurfacing	Leabourne Rd.	NC 68	SR 2010	0.94	#78 Mat Seal and 1.5" S9.5B	$249,120
2027	7	041-Guilford	Resurfacing	Lonnie Ct.	SR 1905	END MAINT	0.11	#78 Mat Seal and 1.5" S9.5A	$23,000
2027	7	041-Guilford	Resurfacing	Lucille Way	SR 3314	DEAD END	0.08	#78 Mat Seal and 1.5" S9.5B	$21,200
2027	7	041-Guilford	Resurfacing	Madison farm Rd.	SR 1005	CUL-DE-SAC	0.34	#78 Mat Seal and 1.5" S9.5B	$90,104
2027	7	041-Guilford	Resurfacing	Mattingly Ct.	SR 2523	CUL-DE-SAC	0.08	#78 Mat Seal and 1.5" S9.5B	$21,500
2027	7	041-Guilford	Resurfacing	Maverick Rd.	SR 1860	END MAINT	0.29	#78 Mat Seal and 1.5" S9.5A	$51,500
2027	7	041-Guilford	Resurfacing	McLeansville Rd.	SR 2770	US 70	1.60	#67 Mat Seal and 1.5" S9.5B	$429,763
2027	7	041-Guilford	Resurfacing	McLeansville Rd.	SR 2565	SR 2770	1.95	#78 Mat Seal and 1.25" S9.5A and Widen	$953,900
2027	7	041-Guilford	Resurfacing	McLeansville Rd.	SR 2770	US 70	1.66	#67 Mat Seal and 1.5" S9.5B	$444,777
2027	7	041-Guilford	Resurfacing	Middleland Dr.	NC 150	END MAINT	0.18	#78 Mat Seal and 1.5" S9.5B	$47,702
2027	7	041-Guilford	Resurfacing	Moores Mill Ct.	SR 5066	END MAINT	0.11	#78 Mat Seal and 1.5" S9.5A	$19,500
2027	7	041-Guilford	Resurfacing	Moores Mill Rd.	SR 4848	END MAINT	0.27	#78 Mat Seal and 1.5" S9.5A	$48,000
2027	7	041-Guilford	Resurfacing	Mountiline Ct.	SR 2275	END MAINT	0.06	#78 Mat Seal and 1.5" S9.5A	$10,700
2027	7	041-Guilford	Resurfacing	Mountline Dr.	SR 2269	SR 3810	0.37	#78 Mat Seal and 1.5" S9.5A	$65,500
2027	7	041-Guilford	Resurfacing	N. Broad St.	SR 4757	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$18,600
2027	7	041-Guilford	Resurfacing	N. O'Henry Blvd (Sands)	SR 2835	DEAD END	0.34	#78 Mat Seal and 1.5" S9.5B	$90,100
2027	7	041-Guilford	Resurfacing	N. O'Henry Blvd(Gatew.)	US 29	Gatewood Ave.	0.21	#78 Mat Seal and 1.5" S9.5B	$55,650
2027	7	041-Guilford	Resurfacing	N. O'Henry Blvd.	BEG MAINT	DEAD END	0.28	#78 Mat Seal and 1.5" S9.5B	$74,100
2027	7	041-Guilford	Resurfacing	N. O'Henry Blvd.	McKnight Mill Rd.	US 29	0.35	#78 Mat Seal and 1.5" S9.5B	$92,800
2027	7	041-Guilford	Resurfacing	N. O'Henry Blvd. (2608)	BEG MAINT	DEAD END	0.12	#78 Mat Seal and 1.5" S9.5B	$31,800
2027	7	041-Guilford	Resurfacing	NC 68	Pvmt. near Americahs	Pvmt. Change S.Market St.	1.72	#78 Mat Seal and 1.5" S9.5B	$250,000
2027	7	041-Guilford	Resurfacing	NC 68	SR 1008	SR 4464	1.06	#78 Mat Seal and 1.5" S9.5B	$530,100
2027	7	041-Guilford	Resurfacing	Newman Davis Rd.	SR 1137	SR 1104	1.42	#78 Mat Seal and 1.5" S9.5B	$375,530
2027	7	041-Guilford	Resurfacing	Oak Creek Ct.	SR 4847	END MAINT	0.05	#78 Mat Seal and 1.5" S9.5A	$10,700
2027	7	041-Guilford	Resurfacing	Oak Creek Dr.	SR 2107	SR 4848	0.47	#78 Mat Seal and 1.5" S9.5A	$83,500
2027	7	041-Guilford	Resurfacing	Oak Ripple Ct.	SR 4757	CUL-DE-SAC	0.06	#78 Mat Seal and 1.5" S9.5B	$15,900
2027	7	041-Guilford	Resurfacing	Oak Wind Rd.	SR 2798	DEAD END	0.33	#78 Mat Seal and 1.5" S9.5B	$87,500
2027	7	041-Guilford	Resurfacing	Old Mine Rd.	SR 2531	END MAINT	0.17	#78 Mat Seal and 1.5" S9.5B	$45,100
2027	7	041-Guilford	Resurfacing	Parnell Dr.	SR 2867	SR 2865	0.23	#78 Mat Seal and 1.5" S9.5B	$61,000
2027	7	041-Guilford	Resurfacing	Rettop Rd.	SR 2770	CUL-DE-SAC	0.38	#78 Mat Seal and 1.5" S9.5B	$100,800
2027	7	041-Guilford	Resurfacing	Saddle Brook Rd.	SR 2078	END MAINT	0.34	#78 Mat Seal and 1.5" S9.5A	$63,700
2027	7	041-Guilford	Resurfacing	Saddlewood Dr.	SR 2133	END MAINT	0.27	#78 Mat Seal and 1.5" S9.5B	$48,500
2027	7	041-Guilford	Resurfacing	Sands Dr.	Begin C&G	Cone Blvd.	0.16	Mill 1.5" and 2.0" S9.5B	$9,000
2027	7	041-Guilford	Resurfacing	Sands Dr.	SR 2835	Begin C&G	0.25	#78 Mat Seal and 1.5" S9.5B	$66,300
2027	7	041-Guilford	Resurfacing	Seacrest Dr.	SR 2001	CUL-DE-SAC	0.15	#78 Mat Seal and 1.5" S9.5B	$38,500
2027	7	041-Guilford	Resurfacing	Service Rd. @ US 29	US 29	DEADEND	0.10	#78 Mat Seal and 1.5" S9.5B	$26,600
2027	7	041-Guilford	Resurfacing	Sheraton Park Rd.	SR 1007	SR 3402	2.80	#78 Mat Seal and 1.5" S9.5B	$741,300
2027	7	041-Guilford	Resurfacing	Southwest School Rd.	BEG MAINT	SR 1836	0.83	#78 Mat Seal and 1.5" S9.5B	$219,700
2027	7	041-Guilford	Resurfacing	Stonewood Dr.	SR2520	CUL-DE-SAC	0.29	#78 Mat Seal and 1.5" S9.5B	$76,850
2027	7	041-Guilford	Resurfacing	Strader Rd.	NC 150	SR 1002	1.60	#78 Mat Seal and 1.5" S9.5A	$286,500
2027	7	041-Guilford	Resurfacing	Summerson Dr.	AR 4773	DEAD END	0.10	#78 Mat Seal and 1.5" S9.5B	$26,600
2027	7	041-Guilford	Resurfacing	Sun Harbor Dr.	SR 4754	DEAD END	0.23	#78 Mat Seal and 1.5" S9.5B	$61,000
2027	7	041-Guilford	Resurfacing	Sunberry Dr.	SR 4754	DEAD END	0.16	#78 Mat Seal and 1.5" S9.5B	$42,500
2027	7	041-Guilford	Resurfacing	Sweetgum Rd.	SR 2746	DEAD END	0.35	#78 Mat Seal and 1.5" S9.5B	$92,800
2027	7	041-Guilford	Resurfacing	Taylorcrest Rd.	SR 2835	SR 2866	0.29	#78 Mat Seal and 1.5" S9.5B	$78,900
2027	7	041-Guilford	Resurfacing	Timberline Dr.	SR 2275	END MAINT	0.18	#78 Mat Seal and 1.5" S9.5A	$31,900
2027	7	041-Guilford	Resurfacing	Triangle Dr.	SR 2868	SR 2867	0.17	#78 Mat Seal and 1.5" S9.5B	$45,053
2027	7	041-Guilford	Resurfacing	Turner Smith Rd.	SR 2728	SR 2705	3.66	#78 Mat Seal and 1.5" S9.5B	$1,000,000
2027	7	041-Guilford	Resurfacing	US 70	SR 2848	SR 2851	1.19	Mill 1.5" and 1.5" S9.5B	$235,000
2027	7	041-Guilford	Resurfacing	Vickory Chapel Rd.	SR 1293	SR 1113	1.26	#78 Mat Seal and 1.5" S9.5B	$334,200
2027	7	041-Guilford	Resurfacing	Wagmont Dr.	CUL-DE-SAC	DEAD END	0.13	#78 Mat Seal and 1.5" S9.5B	$34,500
2027	7	041-Guilford	Resurfacing	Wagoner Rd.	NC 61	SR 2755	1.31	#78 Mat Seal and 1.5" S9.5B	$347,200
2027	7	041-Guilford	Resurfacing	Westcott Dr.	SR 2128	END MAINT	0.44	#78 Mat Seal and 1.5" S9.5A	$86,700
2027	7	041-Guilford	Resurfacing	White Blossom Dr.	SR 2133	END MAINT	0.42	#78 Mat Seal and 1.5" S9.5B	$75,000
2027	7	041-Guilford	Resurfacing	Willard Dairy Rd.	NC 68	Barrow Rd.	0.80	#78 Mat Seal and 1.5" S9.5B	$212,100
2027	7	041-Guilford	Resurfacing	Wolf Ridge Ct.	SR 2018	END MAINT	0.31	#78 Mat Seal and 1.5" S9.5A	$54,900
2027	7	041-Guilford	Resurfacing	Zack Rd.	NC 150	END MAINT	0.28	#78 Mat Seal and 1.5" S9.5A	$49,700
2027	7	041-Guilford	Preservation	Belford Rd.	NC 150	END MAINT.	0.60	Seal - Double and Fog Seal	$63,180

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	7	041-Guilford	Preservation	Bloomfield Rd.	US 70	END MAINT	0.76	Seal - Double and Fog Seal	$23,500
2027	7	041-Guilford	Preservation	Bridgepoint Rd.	SR 3000	SR 3140	0.30	Seal - Double and Fog Seal	$12,000
2027	7	041-Guilford	Preservation	Brittney Lane	SR 2748	DEAD END	0.31	Seal - Double and Fog Seal	$9,500
2027	7	041-Guilford	Preservation	Buchanan Church Rd.	US 70	DEAD END	0.64	Seal - Double and Fog Seal	$20,000
2027	7	041-Guilford	Preservation	Buchanan Heights Rd.	DEAD END	DEAD END	0.23	Seal - Double and Fog Seal	$7,000
2027	7	041-Guilford	Preservation	Clarkland Rd.	SR 2133	END MAINT	0.63	Seal - Double and Fog Seal	$25,000
2027	7	041-Guilford	Preservation	Crescent Rd.	US 70	NC 61	0.63	Seal - Double and Fog Seal	$19,000
2027	7	041-Guilford	Preservation	Dow Rd.	SR 3060	DEAD END	0.51	Seal - Double and Fog Seal	$15,500
2027	7	041-Guilford	Preservation	Greeson Rd.	NC 61	SR 3064	0.82	Seal - Double and Fog Seal	$25,000
2027	7	041-Guilford	Preservation	Gusenbury Rd.	NC 61	END MAINT	0.30	Seal - Double and Fog Seal	$11,000
2027	7	041-Guilford	Preservation	Holts Chapel Rd.	SR 3027	SR 3008	0.65	Seal - Double and Fog Seal	$20,000
2027	7	041-Guilford	Preservation	Janet Lane	SR 3028	DEAD END	0.20	Seal - Double and Fog Seal	$7,000
2027	7	041-Guilford	Preservation	Marley Dr.	SR 3051	DEAD END	0.38	Seal - Double and Fog Seal	$11,500
2027	7	041-Guilford	Preservation	Martin Lake Rd.	NC 150	END MAINT.	0.20	Seal - Double and Fog Seal	$21,060
2027	7	041-Guilford	Preservation	Maverick Rd.	SR 1860	END MAINT	0.30	Seal - Double and Fog Seal	$9,000
2027	7	041-Guilford	Preservation	Maxfield Rd.	SR 3026	DEAD END	0.38	Seal - Double and Fog Seal	$7,000
2027	7	041-Guilford	Preservation	Medearis St.	SR 2117	END MAINT	0.12	Seal - Double and Fog Seal	$4,000
2027	7	041-Guilford	Preservation	Old McConnell Rd.	SR 3000	SR 3000	0.40	Seal - Double and Fog Seal	$14,000
2027	7	041-Guilford	Preservation	Parsonage Rd.	US 220	SR 2117	0.16	Seal - Double and Fog Seal	$17,901
2027	7	041-Guilford	Preservation	Penn-Lo Drive	US 70	END PVMT	0.30	Seal - Double and Fog Seal	$11,000
2027	7	041-Guilford	Preservation	Pinetree Dr.	US 70	DEAD END	0.20	Seal - Double and Fog Seal	$6,500
2027	7	041-Guilford	Preservation	Pinewood Acres Dr.	SR 4762	DEAD END	0.10	Seal - Double and Fog Seal	$6,000
2027	7	041-Guilford	Preservation	Pontiac Dr.	SR 3026	SR 3161	0.26	Seal - Double and Fog Seal	$8,000
2027	7	041-Guilford	Preservation	Roy Clift Rd.	SR 2007	DEAD END	0.20	Seal - Double and Fog Seal	$6,000
2027	7	041-Guilford	Preservation	Shadyside Dr.	SR 2117	END MAINT.	0.39	Seal - Double and Fog Seal	$42,120
2027	7	041-Guilford	Preservation	Shoeline Rd.	SR 2107	END MAINT	0.53	Seal - Double and Fog Seal	$20,000
2027	7	041-Guilford	Preservation	Sprucetree Dr.	US 70	DEAD END	0.25	Seal - Double and Fog Seal	$8,000
2027	7	041-Guilford	Preservation	Steeple Rd.	SR 3026	SR 3161	0.10	Seal - Double and Fog Seal	$3,000
2027	7	041-Guilford	Preservation	Stella Dr.	SR 3060	SR 2923	0.32	Seal - Double and Fog Seal	$10,000
2027	7	041-Guilford	Preservation	Wagoner Bend Rd.	SR 4762	DEAD END	0.57	Seal - Double and Fog Seal	$17,500
2027	7	041-Guilford	Preservation	West Acres Dr.	SR 3026	SR 3161	0.10	Seal - Double and Fog Seal	$3,000
2027	7	041-Guilford	Preservation	Zane Dr.	SR 4368	END MAINT.	0.15	Seal - Double and Fog Seal	$15,795
2027	7	068-Orange	Resurfacing	Ben Wilson	SR 1142	DIRT SECTION	0.25	#78 Mat Seal and 1.5" S9.5B	$66,300
2027	7	068-Orange	Resurfacing	Ben Wilson	SR 1142	END PVMT	0.45	#78 Mat Seal and 1.5" S9.5B	$119,300
2027	7	068-Orange	Resurfacing	Bowman Rd.	SR 1146	ACL	1.86	#78 Mat Seal and 1.5" S9.5B	$492,950
2027	7	068-Orange	Resurfacing	Carr Store Rd.	NC 49	SR 1357	4.60	#78 Mat Seal and 1.5" S9.5B	$1,219,100
2027	7	068-Orange	Resurfacing	Casey Lane	SR 1306	CUL-DE-SAC	0.23	#78 Mat Seal and 1.5" S9.5B	$60,900
2027	7	068-Orange	Resurfacing	Corbett Ridge Rd.	NC 49	CCL	2.58	#78 Mat Seal and 1.5" S9.5B	$686,400
2027	7	068-Orange	Resurfacing	E. Brown St.	ACL	SR 1376	0.11	#78 Mat Seal and 1.5" S9.5B	$29,200
2027	7	068-Orange	Resurfacing	E. Graham St.	ACL	SR 1304	0.20	#78 Mat Seal and 1.5" S9.5B	$53,100
2027	7	068-Orange	Resurfacing	E. Stagecoach Rd.	ACL	SR 1306	0.30	#78 Mat Seal and 1.5" S9.5B	$79,600
2027	7	068-Orange	Resurfacing	Lebanon Rd.	SR 1304	SR 1376	0.70	#78 Mat Seal and 1.5" S9.5B	$185,600
2027	7	068-Orange	Resurfacing	Millhouse Rd.	NC 86	SR 2200	1.20	#78 Mat Seal and 1.5" S9.5B	$318,020
2027	7	068-Orange	Resurfacing	Millhouse Rd.	SR 1725	SR 1727	0.70	#78 Mat Seal and 1.5" S9.5B	$185,600
2027	7	068-Orange	Resurfacing	NC 54	US15-501	Anderson Prk/Pvmt. Joint	3.60	Mill 1.5" and 1.5" S9.5B	$2,855,164
2027	7	068-Orange	Resurfacing	NC 57	NC 157	PCL	5.00	#67 Mat Seal and 1.5" S9.5B	$1,325,100
2027	7	068-Orange	Resurfacing	New Hope Church Rd.	NC 86	SR 1710	1.83	#78 Mat Seal and 1.5" S9.5B	$485,000
2027	7	068-Orange	Resurfacing	Turkey Farm Rd.	SR 1731	SR 1718	2.02	#78 Mat Seal and 1.5" S9.5B	$535,400
2027	7	068-Orange	Preservation	Brookfield Rd.	NC 54	SR 1944	0.27	Seal - Double and Fog Seal	$9,500
2027	7	068-Orange	Preservation	Carl Durham Rd.	NC 54	SR 1005	2.19	Seal - Double and Fog Seal	$77,000
2027	7	068-Orange	Preservation	Collins Mountain Rd.	SR 1005	END MAINT	1.43	Seal - Double and Fog Seal	$51,000
2027	7	068-Orange	Preservation	Crawford Dairy Rd.	SR 1005	CCL	1.44	Seal - Double and Fog Seal	$51,000
2027	7	068-Orange	Preservation	Dawson Rd.	SR 1005	END MAINT	0.86	Seal - Double and Fog Seal	$31,000
2027	7	068-Orange	Preservation	Ferguson Rd.	SR 1005	SR 1942	1.83	Seal - Double and Fog Seal	$64,500
2027	7	068-Orange	Preservation	Ford Rd.	SR 1005	END MAINT	0.71	Seal - Double and Fog Seal	$25,000
2027	7	068-Orange	Preservation	Gold Mine Loop	SR 1957	SR 1958	0.76	Seal - Double and Fog Seal	$27,000
2027	7	068-Orange	Preservation	Gold Mine Loop	SR 1958	SR 1958	0.48	Seal - Double and Fog Seal	$17,000
2027	7	068-Orange	Preservation	Hatch Rd.	NC 54	SR 1005	1.65	Seal - Double and Fog Seal	$58,000
2027	7	068-Orange	Preservation	Ivey Rd.	Sr 1005	END MAINT	0.60	Seal - Double and Fog Seal	$22,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	7	068-Orange	Preservation	Lloydtown Rd.	SR 1961	ACL	1.80	Seal - Double and Fog Seal	$63,000
2027	7	068-Orange	Preservation	Millaken Rd.	SR 1958	SR 1956	1.81	Seal - Double and Fog Seal	$63,000
2027	7	068-Orange	Preservation	Morrow Mill Rd.	SR 1961	ACL	0.64	Seal - Double and Fog Seal	$23,000
2027	7	068-Orange	Preservation	Morrow Mill Rd.	SR 1956	ACL	1.86	Seal - Double and Fog Seal	$65,200
2027	7	068-Orange	Preservation	Neville Rd.	NC 54	SR 1005	1.66	Seal - Double and Fog Seal	$59,000
2027	7	068-Orange	Preservation	Pineview Dr.	SR 1943	END MAINT	0.16	Seal - Double and Fog Seal	$5,700
2027	7	068-Orange	Preservation	Pineview Rd.	SR 2042	END MAINT	0.13	Seal - Double and Fog Seal	$5,000
2027	7	068-Orange	Preservation	Sesame Rd.	SR 1005	END MAINT	0.44	Seal - Double and Fog Seal	$15,500
2027	7	068-Orange	Preservation	Stansbury Rd.	SR 1946	END MAINT	0.21	Seal - Double and Fog Seal	$8,000
2027	7	068-Orange	Preservation	Willis Rd.	SR 1948	END MAINT	0.28	Seal - Double and Fog Seal	$10,000
2027	7	079-Rockingham	Resurfacing	Angieline Ct.	SR 1110	END MAINT	0.40	#78 Mat Seal and 1.5" S9.5B	$55,700
2027	7	079-Rockingham	Resurfacing	Arrowhead Rd.	SR 1914	CUL-DE-SAC	0.35	#78 Mat Seal and 1.5" S9.5B	$48,900
2027	7	079-Rockingham	Resurfacing	Boone Rd.	SR 2006	SR 3003	0.95	Mill 1.5" and 1.5" S9.5B	$348,970
2027	7	079-Rockingham	Resurfacing	Campsite Rd.	SR 1176	END MAINT	0.29	#78 Mat Seal and 1.5" S9.5B	$40,400
2027	7	079-Rockingham	Resurfacing	Case School Rd.	SR 1321	NC 704	1.56	#78 Mat Seal and 1.5" S9.5B	$256,100
2027	7	079-Rockingham	Resurfacing	County Creek Rd.	NC 135	CUL-DE-SAC	0.13	#78 Mat Seal and 1.5" S9.5B	$18,100
2027	7	079-Rockingham	Resurfacing	Cure Drive	SR 1198	END MAINT	0.20	#78 Mat Seal and 1.5" S9.5B	$37,084
2027	7	079-Rockingham	Resurfacing	Cure Drive	SR 1198	END MAINT	0.08	#78 Mat Seal and 1.5" S9.5B	$14,571
2027	7	079-Rockingham	Resurfacing	Cure Drive	SR 1198	END MAINT	0.20	#78 Mat Seal and 1.5" S9.5B	$37,157
2027	7	079-Rockingham	Resurfacing	Cure Drive	SR 1198	END MAINT	0.08	#78 Mat Seal and 1.5" S9.5B	$14,543
2027	7	079-Rockingham	Resurfacing	First Court Rd.	SR 2682	END MAINT	0.17	#78 Mat Seal and 1.5" S9.5B	$23,700
2027	7	079-Rockingham	Resurfacing	Flack St.	SR 2817	SR 2817	0.15	#78 Mat Seal and 1.5" S9.5B	$20,900
2027	7	079-Rockingham	Resurfacing	Gibson Rd.	US 311	SR 1138	0.74	#78 Mat Seal and 1.5" S9.5B	$250,000
2027	7	079-Rockingham	Resurfacing	Hamilton St. (N)	SR 1605	SR 1708	0.61	Mill 1.25" and 1.25" S9.5B	$122,000
2027	7	079-Rockingham	Resurfacing	Hamilton St. (N)	SR 1605	SR 1708	0.61	#78 Mat Seal and 1.5" S9.5B	$121,700
2027	7	079-Rockingham	Resurfacing	Knowles Rd.	SR 2571	SR 2579	1.66	#78 Mat Seal and 1.5" S9.5B	$272,500
2027	7	079-Rockingham	Resurfacing	Lane Rd.	SR 1605	DEAD END	0.19	#78 Mat Seal and 1.5" S9.5B	$26,500
2027	7	079-Rockingham	Resurfacing	Malibu St.	CUL-DE-SAC	CUL-DE-SAC	0.12	#78 Mat Seal and 1.5" S9.5B	$16,800
2027	7	079-Rockingham	Resurfacing	Marion Ridge Dr.	SR 2203	CUL-DE-SAC	0.20	#78 Mat Seal and 1.5" S9.5B	$27,900
2027	7	079-Rockingham	Resurfacing	Monroeton Rd.	Us 158	SR 2406	1.59	#78 Mat Seal and 1.5" S9.5B	$270,200
2027	7	079-Rockingham	Resurfacing	Monroeton Rd.	US 158	SR 2406	1.59	#78 Mat Seal and 1.5" S9.5B	$270,220
2027	7	079-Rockingham	Resurfacing	Mullins Rd.	Us 158	DEAD END	0.57	#78 Mat Seal and 1.5" S9.5B	$80,000
2027	7	079-Rockingham	Resurfacing	NC 704	US 220	NC 65	2.00	#67 Mat Seal and 1.5" S9.5C and Widen	$2,948,804
2027	7	079-Rockingham	Resurfacing	Oak Leaf Drive	US 158	SR 2992	0.20	#78 Mat Seal and 1.5" S9.5B	$27,900
2027	7	079-Rockingham	Resurfacing	Price-Galloway St.	US 311	END PAVEMENT	0.23	#78 Mat Seal and 1.5" S9.5B	$32,100
2027	7	079-Rockingham	Resurfacing	Rosemary St.	SR 2536	SR 2539	0.06	#78 Mat Seal and 1.5" S9.5B	$15,400
2027	7	079-Rockingham	Resurfacing	Second Ct.	SR 2682	DEAD END	0.12	#78 Mat Seal and 1.5" S9.5B	$16,800
2027	7	079-Rockingham	Resurfacing	Steamside Ct.	CUL-DE-SAC	CUL-DE-SAC	0.11	#78 Mat Seal and 1.5" S9.5B	$15,400
2027	7	079-Rockingham	Resurfacing	Tony Rd.	SR 1170	DEAD END	0.27	#78 Mat Seal and 1.5" S9.5B	$37,600
2027	7	079-Rockingham	Resurfacing	Triangle Station Park Rd.	NC 700	SR 1914	0.06	#78 Mat Seal and 1.5" S9.5B	$9,500
2027	7	079-Rockingham	Resurfacing	Triangle Station Park Rd.	NC 700	SR 1914	0.06	#78 Mat Seal and 1.5" S9.5B	$9,500
2027	7	079-Rockingham	Resurfacing	US 220 (N)	SR 110	On Ramp at US220 (Bus.)	5.79	#67 Mat Seal and 2.0" S9.5C	$1,651,308
2027	7	079-Rockingham	Resurfacing	US 220 S	Off Ramp at Us 220 Bus.	SR 1110	5.79	#67 Mat Seal and 2.0" S9.5C	$1,651,400
2027	7	079-Rockingham	Resurfacing	Ware St.	SR 1005	SR 1793	0.08	#78 Mat Seal and 1.5" S9.5B	$11,200
2027	7	079-Rockingham	Resurfacing	Westerly Park Rd.	SR 1501	SR 1553	1.85	#78 Mat Seal and 1.5" S9.5B	$292,880
2027	7	079-Rockingham	Preservation	Almond Rd.	SR 2937	SR 2381	1.73	Seal - Double and Fog Seal	$52,500
2027	7	079-Rockingham	Preservation	Ballard Rd.	SR 2203	END MAINT	0.20	Seal - Double and Fog Seal	$5,000
2027	7	079-Rockingham	Preservation	Butter Rd.	SR 2124	END MAINT	1.00	Seal - Double and Fog Seal	$30,500
2027	7	079-Rockingham	Preservation	Carter Rd.	SR 2371	END PVMT	0.99	Seal - Double and Fog Seal	$29,800
2027	7	079-Rockingham	Preservation	Communications Ln	SR 2082	END PVMT	0.15	Seal - Double and Fog Seal	$3,750
2027	7	079-Rockingham	Preservation	Crowder Rd.	NC 704	NC 65	0.48	Seal - Double and Fog Seal	$14,500
2027	7	079-Rockingham	Preservation	Crumpton Rd.	NC 87	DEAD END	0.57	Seal - Double and Fog Seal	$17,500
2027	7	079-Rockingham	Preservation	Dairy Rd.	SR 1001	END MAINT	1.43	Seal - Double and Fog Seal	$43,000
2027	7	079-Rockingham	Preservation	Dallas Rd.	SR 2203	END MAINT	1.08	Seal - Double and Fog Seal	$27,000
2027	7	079-Rockingham	Preservation	Dan River Rd.	END MAINT/SR 2145	END MAINT	0.30	Seal - Double and Fog Seal	$9,500
2027	7	079-Rockingham	Preservation	Delancey Rd.	SR 1998	END MAINT	0.19	Seal - Double and Fog Seal	$5,900
2027	7	079-Rockingham	Preservation	Dilard Rd.	NC 87	DEAD END	0.20	Seal - Double and Fog Seal	$6,500
2027	7	079-Rockingham	Preservation	Dove Rd.	BEG PVMT	DEAD END	0.25	Seal - Double and Fog Seal	$7,800
2027	7	079-Rockingham	Preservation	Eagle Falls Rd.	SR 2127	SR 2145	2.06	Seal - Double and Fog Seal	$62,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	7	079-Rockingham	Preservation	Ellington Rd.	SR 2203	END MAINT	0.72	Seal - Double and Fog Seal	$18,000
2027	7	079-Rockingham	Preservation	Foch Farm Rd	NC 65	DEAD END	0.71	Seal - Double and Fog Seal	$22,500
2027	7	079-Rockingham	Preservation	Fox Rd.	SR 2127	END MAINT	0.10	Seal - Double and Fog Seal	$3,500
2027	7	079-Rockingham	Preservation	Giles Rd.	SR 1001	END MAINT	0.58	Seal - Double and Fog Seal	$18,500
2027	7	079-Rockingham	Preservation	Hall Farm Rd.	NC 87	END MAINT	0.09	Seal - Double and Fog Seal	$2,800
2027	7	079-Rockingham	Preservation	Henry Rd.	SR 2259	DEAD END	0.60	Seal - Double and Fog Seal	$18,500
2027	7	079-Rockingham	Preservation	Heritage Rd.	SR 2021	END MAINT	0.55	Seal - Double and Fog Seal	$16,700
2027	7	079-Rockingham	Preservation	Hines Rd.	SR 2203	END MAINT	0.30	Seal - Double and Fog Seal	$7,500
2027	7	079-Rockingham	Preservation	Hudspeth Park Rd.	SR 1991	DEAD END	0.30	Seal - Double and Fog Seal	$7,500
2027	7	079-Rockingham	Preservation	Huffines Mill Rd.	SR 2316	NC 65	2.41	Seal - Double and Fog Seal	$72,500
2027	7	079-Rockingham	Preservation	Jarrel Farm Rd.	SR 2039	DEAD END	0.20	Seal - Double and Fog Seal	$6,375
2027	7	079-Rockingham	Preservation	Jarrell Rd.	SR 2203	END MAINT	0.82	Seal - Double and Fog Seal	$24,500
2027	7	079-Rockingham	Preservation	Jones Chapel Rd.	SR 1001	END MAINT	0.41	Seal - Double and Fog Seal	$12,500
2027	7	079-Rockingham	Preservation	Loftis Rd.	SR 2363	DEAD END	0.16	Seal - Double and Fog Seal	$5,000
2027	7	079-Rockingham	Preservation	Maggy Valley Rd.	NC 87	DEAD END	0.79	Seal - Double and Fog Seal	$19,750
2027	7	079-Rockingham	Preservation	Massey Creek Rd.	BEG PVMT	NC 704	0.12	Seal - Double and Fog Seal	$3,800
2027	7	079-Rockingham	Preservation	Massey Creek Rd.	SR 2259	END PVMT	0.65	Seal - Double and Fog Seal	$20,100
2027	7	079-Rockingham	Preservation	New Lebanon Church Rd.	SR 2359	NC 65	2.54	Seal - Double and Fog Seal	$76,500
2027	7	079-Rockingham	Preservation	Pannell Rd.	NC 87	NC 65	4.18	Seal - Double and Fog Seal	$125,500
2027	7	079-Rockingham	Preservation	Payless Rd.	SR 2127	END MAINT	0.79	Seal - Double and Fog Seal	$23,800
2027	7	079-Rockingham	Preservation	Peach Tree Rd.	NC 87	END MAINT	1.00	Seal - Double and Fog Seal	$31,000
2027	7	079-Rockingham	Preservation	Percy Rd.	SR 2123	DEAD END	0.17	Seal - Double and Fog Seal	$5,500
2027	7	079-Rockingham	Preservation	Pinrod Rd.	SR 2009	END MAINT	0.10	Seal - Double and Fog Seal	$3,500
2027	7	079-Rockingham	Preservation	Pleasantville Church Rd.	NC 704	END MAINT	0.25	Seal - Double and Fog Seal	$7,500
2027	7	079-Rockingham	Preservation	Purcell Rd.	NC 65	END PVMT	0.86	Seal - Double and Fog Seal	$26,000
2027	7	079-Rockingham	Preservation	Quail Rd.	NC 14	NC 14	0.29	Seal - Double and Fog Seal	$8,800
2027	7	079-Rockingham	Preservation	Ralph E. Wood Rd.	NC 65	END MAINT	0.85	Seal - Double and Fog Seal	$26,000
2027	7	079-Rockingham	Preservation	Richardson Rd.	SR 2203	END MAINT	0.40	Seal - Double and Fog Seal	$9,925
2027	7	079-Rockingham	Preservation	Roberts Farm Rd.	SR 2361	END PVMT	0.83	Seal - Double and Fog Seal	$25,000
2027	7	079-Rockingham	Preservation	Rob-Tom Rd.	SR 2203	END MAINT	0.90	Seal - Double and Fog Seal	$22,500
2027	7	079-Rockingham	Preservation	Russell L. Rd.	NC 65	END MAINT	0.63	Seal - Double and Fog Seal	$19,000
2027	7	079-Rockingham	Preservation	Seedling Rd.	NC 65	DEAD END	0.36	Seal - Double and Fog Seal	$11,000
2027	7	079-Rockingham	Preservation	Sims Rd.	SR 2371	END MAINT	0.41	Seal - Double and Fog Seal	$12,500
2027	7	079-Rockingham	Preservation	Spring Rd.	SR 2368	END MAINT	0.40	Seal - Double and Fog Seal	$12,500
2027	7	079-Rockingham	Preservation	Sutton Rd.	SR 2145	SR 2260	1.20	Seal - Double and Fog Seal	$36,500
2027	7	079-Rockingham	Preservation	Talley Rd.	SR 2009	DEAD END	0.83	Seal - Double and Fog Seal	$25,000
2027	7	079-Rockingham	Preservation	Tyre Dodson Rd.	NC 65	DEAD END	0.16	Seal - Double and Fog Seal	$4,900
2027	7	079-Rockingham	Preservation	Valley Level Rd.	NC 65	END MAINT	0.47	Seal - Double and Fog Seal	$14,500
2027	7	079-Rockingham	Preservation	Vernon Rd.	SR 1001	SR 2380	2.58	Seal - Double and Fog Seal	$77,500
2027	7	079-Rockingham	Preservation	Walsh Rd.	SR 2038	DEAD END	0.22	Seal - Double and Fog Seal	$5,500
2027	7	079-Rockingham	Preservation	Webb Loop Rd.	SR 2302	SR 2302	2.24	Seal - Double and Fog Seal	$67,500
2027	7	079-Rockingham	Preservation	Wheatley Rd.	SR 2203	END MAINT	0.10	Seal - Double and Fog Seal	$3,500
2027	8	019-Chatham	Resurfacing	NC 42 E	LEE CO	BUCKHORN BRIDGE	2.86	1.5" S9.5B	$490,000
2027	8	019-Chatham	Resurfacing	SR 1006	RANDOLPH CO	SR 1108	4.30	1.5" S9.5B	$645,000
2027	8	019-Chatham	Resurfacing	SR 1105	SR 1006	SR 1105	0.95	1.25" S9.5B	$143,000
2027	8	019-Chatham	Resurfacing	SR 1108	SR 2113	SR 1006	3.32	1.25" S9.5B	$550,000
2027	8	019-Chatham	Resurfacing	SR 1141	SR 2312	NC 902	1.51	1.25" S9.5B	$272,000
2027	8	019-Chatham	Resurfacing	SR 1172	SR 1006	SR 1174	0.11	#78 Mat Seal and 1.5" S9.5B	$24,000
2027	8	019-Chatham	Resurfacing	SR 1173	SR 1172	SR 1190	0.23	#78 Mat Seal and 1.5" S9.5B	$50,000
2027	8	019-Chatham	Resurfacing	SR 1174	CULDESAC	SR 1188	0.54	#78 Mat Seal and 1.5" S9.5B	$116,000
2027	8	019-Chatham	Resurfacing	SR 1188	SR 1174	SR 1189	0.12	#78 Mat Seal and 1.5" S9.5B	$26,000
2027	8	019-Chatham	Resurfacing	SR 1190	SR 1196	SR 1173	0.15	#78 Mat Seal and 1.5" S9.5B	$32,000
2027	8	019-Chatham	Resurfacing	SR 1196	CULDESAC	DEAD END	0.45	1.25" S9.5B	$97,000
2027	8	019-Chatham	Resurfacing	SR 1197	SR 1196	DEAD END	0.06	1.25" S9.5B	$13,000
2027	8	019-Chatham	Resurfacing	SR 1335	SR 1343	SR 1346	2.31	1.25" S9.5B	$346,500
2027	8	019-Chatham	Resurfacing	SR 1363	PVMT JT	US 64	0.83	1.5" S9.5B	$120,000
2027	8	019-Chatham	Resurfacing	SR 1509	SR 1511	SR 1508	1.87	1.25" S9.5B	$280,500
2027	8	019-Chatham	Resurfacing	SR 1516	SR 1520	NC 87	3.02	1.25" S9.5B	$453,000
2027	8	019-Chatham	Resurfacing	SR 1529	US 15-501	END MAINT	0.63	1.25" S9.5B	$100,800

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	8	019-Chatham	Resurfacing	SR 1530	US 15-501	END MAINT	0.86	1.25" S9.5B	$137,600
2027	8	019-Chatham	Resurfacing	SR 1553	SR 1552	NC 87	1.18	1.25" S9.5B	$177,000
2027	8	019-Chatham	Resurfacing	SR 1553	SR 1549	SR 1552	1.77	1.25" S9.5B	$265,500
2027	8	019-Chatham	Resurfacing	SR 1561	SR 1346	US 64	2.67	1.25" S9.5B	$400,500
2027	8	019-Chatham	Resurfacing	SR 1643	SR 1528	CUL DE SAC	0.13	1.25" SF9.5A	$17,000
2027	8	019-Chatham	Resurfacing	SR 1682	SR 1532	CUL DE SAC	0.55	1.25" S9.5B	$88,000
2027	8	019-Chatham	Resurfacing	SR 1702	PVMT CHG	DEAD END	0.90	1.25" SF9.5A	$112,000
2027	8	019-Chatham	Resurfacing	SR 1718	US 501	SR 1785	1.29	#78 Mat Seal and 1.5" S9.5B	$278,000
2027	8	019-Chatham	Resurfacing	SR 1731	NC 751	WAKE CO	2.81	1.5" S9.5B	$950,000
2027	8	019-Chatham	Resurfacing	SR 1732	END C&G	END C&G	0.74	1.25" S9.5B	$118,400
2027	8	019-Chatham	Resurfacing	SR 1732	SR 1731	END C&G	0.65	1.5" S9.5A	$81,000
2027	8	019-Chatham	Resurfacing	SR 1796	SR 1718	CULDESAC	0.09	1.5" S9.5B	$16,000
2027	8	019-Chatham	Resurfacing	SR 1803	SR 1802	CUL DE SAC	0.13	1.25" SF9.5A	$16,000
2027	8	019-Chatham	Resurfacing	SR 1804	SR 1802	CUL DE SAC	0.12	1.25" S9.5B	$19,200
2027	8	019-Chatham	Resurfacing	SR 1807	CUL DE SAC	SR 1806	0.42	1.25" S9.5B	$67,200
2027	8	019-Chatham	Resurfacing	SR 1808	SR 1807	END MAINT	0.10	1.25" SF9.5A	$13,000
2027	8	019-Chatham	Resurfacing	SR 1812	SR 1806	SR 1813	0.35	1.25" S9.5B	$56,000
2027	8	019-Chatham	Resurfacing	SR 1817	SR 1802	SR 1836	0.57	1.25" SF9.5A	$71,000
2027	8	019-Chatham	Resurfacing	SR 1829	SR 1846	SR 1811	0.26	1.25" SF9.5A	$33,000
2027	8	019-Chatham	Resurfacing	SR 1830	SR 1832	SR 1832	0.82	1.25" SF9.5A	$103,000
2027	8	019-Chatham	Resurfacing	SR 1831	SR 1008	SR 1830	0.05	1.25" SF9.5A	$7,000
2027	8	019-Chatham	Resurfacing	SR 1833	SR 1830	CUL DE SAC	0.09	1.25" SF9.5A	$11,000
2027	8	019-Chatham	Resurfacing	SR 1836	SR 1817	CUL DE SAC	0.47	1.25" SF9.5A	$59,000
2027	8	019-Chatham	Resurfacing	SR 1839	SR 1700	CUL DE SAC	0.31	1.25" SF9.5A	$38,000
2027	8	019-Chatham	Resurfacing	SR 1843	SR 1830	CUL DE SAC	0.08	1.25" SF9.5A	$10,000
2027	8	019-Chatham	Resurfacing	SR 1856	SR 1858	END LOOP	0.11	1.25" SF9.5A	$14,000
2027	8	019-Chatham	Resurfacing	SR 1860	CUL DE SAC	CUL DE SAC	0.25	1.25" SF9.5A	$31,000
2027	8	019-Chatham	Resurfacing	SR 1865	SR 1726	SR 1868	0.13	1.25" SF9.5A	$17,000
2027	8	019-Chatham	Resurfacing	SR 1866	SR 1865	CUL DE SAC	0.21	1.25" SF9.5A	$27,000
2027	8	019-Chatham	Resurfacing	SR 1867	SR 1865	CUL DE SAC	0.20	1.25" SF9.5A	$25,000
2027	8	019-Chatham	Resurfacing	SR 1868	SR 1865	SR 1866	0.52	1.25" SF9.5A	$38,000
2027	8	019-Chatham	Resurfacing	SR 1883	SR 1868	CUL DE SAC	0.12	1.25" SF9.5A	$16,000
2027	8	019-Chatham	Resurfacing	SR 1884	US 15-501	PVMT JT	0.86	1.25" S9.5B	$137,600
2027	8	019-Chatham	Resurfacing	SR 2120	US 421	SR 2170	2.49	1.25" S9.5B	$448,000
2027	8	019-Chatham	Resurfacing	SR 2142	SR 2139	SR 2188	2.38	1.25" S9.5B	$428,000
2027	8	019-Chatham	Resurfacing	SR 2318	SR 2320	NC 902	1.01	1.5" S9.5B	$182,000
2027	8	019-Chatham	Resurfacing	US 421 NB	NC 902	SR 2113	5.51	1.5" S9.5C	$1,040,000
2027	8	019-Chatham	Resurfacing	US 421 SB	SR 2113	NC 902	5.53	1.5" S9.5C	$1,040,000
2027	8	019-Chatham	Resurfacing	US 64 EB	SR 1700	SR 1008	3.24	1.5" S9.5C	$725,000
2027	8	019-Chatham	Resurfacing	US 64 WB	SR 1008	SR 1700	4.73	1.5" S9.5C	$850,000
2027	8	019-Chatham	Resurfacing	US 64 WB	WAKE CO	SR 1008	3.04	1.5" S9.5B	$450,000
2027	8	019-Chatham	Preservation	NC 22	MOORE CO	RANDOLPH CO	4.00	Crack Seal	$18,000
2027	8	019-Chatham	Preservation	NC 42	LEE CO	BUCKHORN BRIDGE	5.24	Crack Seal	$24,000
2027	8	019-Chatham	Preservation	SR 1136	SR 1134	SR 1005	1.21	Seal - Double	$63,000
2027	8	019-Chatham	Preservation	SR 1189	SR 1174	END MAINT	0.40	#78 Mat Seal and 1.5" S9.5B	$86,000
2027	8	019-Chatham	Preservation	SR 1523	US 15	END MAINT	0.32	Seal - Double	$20,000
2027	8	019-Chatham	Preservation	SR 1529	US 15	END MAINT	0.50	Seal - Double	$15,000
2027	8	019-Chatham	Preservation	SR 1531	ORANGE CO	SR 1666	0.37	Seal - Double	$20,000
2027	8	019-Chatham	Preservation	SR 1539	SR 1540	ORANGE CO	4.35	Seal - Double	$135,000
2027	8	019-Chatham	Preservation	SR 1539	SR 1525	SR 1540	2.15	Seal - Double	$75,000
2027	8	019-Chatham	Preservation	SR 1541	ORANGE CO	SR 1539	1.50	Seal - Double	$50,000
2027	8	019-Chatham	Preservation	SR 1544	SR 1539	SR 1539	1.08	Seal - Double	$45,000
2027	8	019-Chatham	Preservation	SR 1574	SR 1532	SR 1575	0.20	Seal - Double and Fog Seal	$8,000
2027	8	019-Chatham	Preservation	SR 1575	SR 1574	CUL DE SAC	0.07	Seal - Double and Fog Seal	$3,000
2027	8	019-Chatham	Preservation	SR 1577	SR 1346	DEAD END	0.31	Seal - Double	$9,000
2027	8	019-Chatham	Preservation	SR 1591	SR 1530	END MAINT	0.27	Seal - Double and Fog Seal	$20,000
2027	8	019-Chatham	Preservation	SR 1593	SR 1595	CUL DE SAC	0.81	Seal - Double and Fog Seal	$30,000
2027	8	019-Chatham	Preservation	SR 1600	SR 1525	SR 1532	0.73	Seal - Double	$25,000
2027	8	019-Chatham	Preservation	SR 1649	SR 1515	DEAD END	0.70	Seal - Double	$21,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	8	019-Chatham	Preservation	SR 1676	SR 1539	CUL DE SAC	0.48	Seal - Double and Fog Seal	$20,000
2027	8	019-Chatham	Preservation	SR 1677	SR 1676	CUL DE SAC	0.27	Seal - Double and Fog Seal	$15,000
2027	8	019-Chatham	Preservation	SR 1678	SR 1676	CUL DE SAC	0.04	Seal - Double and Fog Seal	$5,000
2027	8	019-Chatham	Preservation	SR 1681	SR 1531	END MAINT	0.08	Seal - Double	$5,000
2027	8	019-Chatham	Preservation	SR 1709	SR 1713	DEAD END	0.09	Seal - Double and Fog Seal	$4,000
2027	8	019-Chatham	Preservation	SR 1725	SR 1008	DEAD END	0.12	Seal - Double and Fog Seal	$3,000
2027	8	019-Chatham	Preservation	SR 1746	SR 1008	END PVMT	0.30	Seal - Double	$9,000
2027	8	019-Chatham	Preservation	SR 1750	NC 751	SR 1758	2.07	Seal - Double	$62,000
2027	8	019-Chatham	Preservation	SR 1755	NC 751	CUL DE SAC	0.69	Seal - Double	$21,000
2027	8	019-Chatham	Preservation	SR 1764	SR 1752	END MAINT	0.50	Seal - Double and Fog Seal	$15,000
2027	8	019-Chatham	Preservation	SR 1804	SR 1802	CULDESAC	0.04	1.5" S9.5B	$7,200
2027	8	019-Chatham	Preservation	SR 1821	SR 1823	DEAD END	0.07	Seal - Double	$2,000
2027	8	019-Chatham	Preservation	SR 1822	SR 1823	DEAD END	0.10	Seal - Double	$3,000
2027	8	019-Chatham	Preservation	SR 1823	WIDTH CHG	SR 1822	0.34	Seal - Double	$10,000
2027	8	019-Chatham	Preservation	SR 1884	US 15	END MAINT	0.86	Seal - Double and Fog Seal	$35,000
2027	8	019-Chatham	Preservation	SR 1885	SR 1884	CUL DE SAC	0.11	Seal - Double and Fog Seal	$4,000
2027	8	019-Chatham	Preservation	SR 1886	SR 1884	CUL DE SAC	0.21	Seal - Double and Fog Seal	$10,000
2027	8	019-Chatham	Preservation	SR 1887	SR 1884	END MAINT	0.26	Seal - Double and Fog Seal	$15,000
2027	8	019-Chatham	Preservation	SR 1888	SR 1887	CUL DE SAC	0.11	Seal - Double and Fog Seal	$5,000
2027	8	019-Chatham	Preservation	SR 2172	SR 2170	END MAINT	0.99	Seal - Double	$30,000
2027	8	019-Chatham	Preservation	SR 2182	SR 2181	END MAINT	0.72	Seal - Double	$22,000
2027	8	019-Chatham	Preservation	SR 2191	NC 902	END MAINT	0.76	Seal - Double	$23,000
2027	8	019-Chatham	Preservation	SR 2238	SR 2239	CULDESAC	0.06	Seal - Double	$3,000
2027	8	019-Chatham	Preservation	SR 2239	SR 2165	SR 2167	0.41	Seal - Double	$21,000
2027	8	019-Chatham	Preservation	US 15	LEE CO	SR 1989	5.62	Crack Seal	$25,000
2027	8	047-Hoke	Resurfacing	SR1003	CUMBERLAND CO	SR 1406	0.98	Mill 1.5" and 1.5" S9.5B	$308,000
2027	8	047-Hoke	Resurfacing	SR1251	SR1311	US 401	1.09	1.5" S9.5B	$183,727
2027	8	047-Hoke	Resurfacing	SR1303	US401	SR1304	2.17	1.5" S9.5B	$400,360
2027	8	047-Hoke	Resurfacing	SR1304	US401	FT BRAGG	1.68	1.5" S9.5B	$268,240
2027	8	047-Hoke	Resurfacing	SR1422	SR1406	SR1432	3.14	1.5" S9.5B	$536,000
2027	8	047-Hoke	Resurfacing	US401	CUMBERLAND CO	SR1413	2.13	Mill 1.5" and 1.5" S9.5C	$510,000
2027	8	047-Hoke	Preservation	SR1123	US 401	SR 1124	0.98	Seal - Double	$41,160
2027	8	047-Hoke	Preservation	SR1151	SR 1125	DEAD END	0.25	Seal - Double and Fog Seal	$12,500
2027	8	047-Hoke	Preservation	SR1334	SR1333	DEAD END	1.01	Seal - Double and Fog Seal	$57,800
2027	8	047-Hoke	Preservation	SR1335	SR1335	SR1334	0.21	Seal - Double and Fog Seal	$17,800
2027	8	047-Hoke	Preservation	SR1336	SR1334	SR1333	0.26	Seal - Double and Fog Seal	$20,300
2027	8	047-Hoke	Preservation	SR1338	SR1334	DEAD END	0.12	Seal - Double and Fog Seal	$6,000
2027	8	047-Hoke	Preservation	SR1340	SR1333	SR1341	0.29	Seal - Double and Fog Seal	$14,500
2027	8	047-Hoke	Preservation	SR1341	SR1340	SR1361	0.55	Seal - Double and Fog Seal	$27,500
2027	8	047-Hoke	Preservation	SR1347	SR1341	DEAD END	0.09	Seal - Double and Fog Seal	$4,500
2027	8	047-Hoke	Preservation	SR1348	SR1333	SR1341	0.24	Seal - Double and Fog Seal	$12,000
2027	8	047-Hoke	Preservation	SR1349	SR1334	SR1334	0.46	Seal - Double and Fog Seal	$23,000
2027	8	047-Hoke	Preservation	SR1350	SR1349	DEAD END	0.06	Seal - Double and Fog Seal	$3,000
2027	8	047-Hoke	Preservation	SR1351	SR1349	CDS	0.03	Seal - Double and Fog Seal	$1,500
2027	8	047-Hoke	Preservation	SR1352	SR1349	DEAD END	0.02	Seal - Double and Fog Seal	$12,000
2027	8	047-Hoke	Preservation	SR1353	SR1334	SR1349	0.21	Seal - Double and Fog Seal	$10,500
2027	8	047-Hoke	Preservation	SR1355	SR1341	DEAD END	0.17	Seal - Double and Fog Seal	$8,500
2027	8	047-Hoke	Preservation	SR1356	SR1355	SR1348	0.13	Seal - Double and Fog Seal	$20,000
2027	8	047-Hoke	Preservation	SR1357	SR1356	DEAD END	0.07	Seal - Double and Fog Seal	$10,800
2027	8	047-Hoke	Preservation	SR1358	SR1333	SR1395	0.87	Seal - Double and Fog Seal	$50,800
2027	8	047-Hoke	Preservation	SR1359	SR1358	SR1360	0.15	Seal - Double and Fog Seal	$14,800
2027	8	047-Hoke	Preservation	SR1360	SR1333	SR1358	0.44	Seal - Double and Fog Seal	$29,300
2027	8	047-Hoke	Preservation	SR1361	SR1305	SR1333	0.68	Seal - Double and Fog Seal	$41,300
2027	8	047-Hoke	Preservation	SR1362	SR1361	SR1363	0.06	Seal - Double and Fog Seal	$10,300
2027	8	047-Hoke	Preservation	SR1363	SR1362	DEAD END	0.10	Seal - Double and Fog Seal	$5,000
2027	8	047-Hoke	Preservation	SR1388	SR1358	SR1360	0.15	Seal - Double and Fog Seal	$7,500
2027	8	047-Hoke	Preservation	SR1389	SR1358	SR1393	0.22	Seal - Double and Fog Seal	$11,000
2027	8	047-Hoke	Preservation	SR1390	SR1358	SR1389	0.19	Seal - Double and Fog Seal	$9,500
2027	8	047-Hoke	Preservation	SR1391	SR1334	DEAD END	0.10	Seal - Double and Fog Seal	$5,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	8	047-Hoke	Preservation	SR1393	SR1333	SR1358	0.39	Seal - Double and Fog Seal	$19,500
2027	8	047-Hoke	Preservation	SR1394	SR1333	DEAD END	0.12	Seal - Double and Fog Seal	$6,000
2027	8	047-Hoke	Preservation	SR1395	SR1358	SR1393	0.24	Seal - Double and Fog Seal	$12,000
2027	8	047-Hoke	Preservation	SR1652	DEAD END	DEAD END	0.16	Seal - Double and Fog Seal	$7,800
2027	8	053-Lee	Resurfacing	SR 1142	HARNETT CO	NC 87	1.15	1.5" S9.5B	$150,000
2027	8	053-Lee	Resurfacing	SR 1146	NC 78	SR 1001	0.86	1.5" S9.5B	$130,000
2027	8	053-Lee	Resurfacing	SR 1167	SR 1001	CUL DE SAC	1.81	Full Depth Patching and 1.5" S9.5B	$270,480
2027	8	053-Lee	Resurfacing	SR 1181	SR 1181	US 1	1.17	1.5" S9.5B	$170,980
2027	8	053-Lee	Resurfacing	SR 1188	SR 1001	SR 1167	1.43	1.5" S9.5B	$201,680
2027	8	053-Lee	Resurfacing	SR 1203	SR 1144	END MAINT	0.27	Full Depth Patching and 1.25" S9.5A	$40,000
2027	8	053-Lee	Resurfacing	SR 1236	SR 1214	SR 1237	0.46	Full Depth Patching and 1.25" S9.5A	$94,000
2027	8	053-Lee	Resurfacing	SR 1242	SR 1244	SR 1243	0.17	Full Depth Patching and 1.25" S9.5A	$33,250
2027	8	053-Lee	Resurfacing	SR 1276	SR 1274	DEAD END	0.09	Full Depth Patching and 1.25" S9.5A	$16,890
2027	8	053-Lee	Resurfacing	SR 1285	SR 1275	DEAD END	0.04	Full Depth Patching and 1.25" S9.5A	$8,505
2027	8	053-Lee	Resurfacing	SR 1325	SR 1326	SR 1009	3.30	Full Depth Patching and 1.5" S9.5B	$572,560
2027	8	053-Lee	Resurfacing	SR 1326	US 421	SR 1325	1.02	1.5" S9.5B	$151,320
2027	8	053-Lee	Resurfacing	SR 1415	SR 1416	SR 1421	1.64	1.5" S9.5B	$279,080
2027	8	053-Lee	Resurfacing	SR 1426	SR 1426	SR 1483	1.90	1.5" S9.5B	$350,000
2027	8	053-Lee	Resurfacing	SR 1469	SR 1466	DEAD END	0.47	Full Depth Patching and 1.25" S9.5A	$68,000
2027	8	053-Lee	Resurfacing	SR 1472	SR 1466	SR 1466	0.43	Full Depth Patching and 1.25" S9.5A	$62,000
2027	8	053-Lee	Resurfacing	SR 1524	PVMNT CHG	US 421	0.33	1.5" S9.5B	$62,082
2027	8	053-Lee	Resurfacing	SR 1525	SR 1523	SR 1537	1.08	1.5" S9.5B	$175,000
2027	8	053-Lee	Resurfacing	SR 1525	SR 1523	SR 1537	1.08	Full Depth Patching and 1.25" S9.5A	$167,000
2027	8	053-Lee	Resurfacing	SR 1538	FIRE HYDRT	SR 1543	0.88	1.5" S9.5B	$151,032
2027	8	053-Lee	Resurfacing	SR 1558	SR 1559	SR 1561	1.07	1.5" S9.5B	$152,360
2027	8	053-Lee	Resurfacing	SR 1752	SR 1181	US 1 BUS	1.78	1.5" S9.5B	$300,000
2027	8	053-Lee	Resurfacing	US 1 BYPASS	MOORE CO LINE	SR 1179	4.87	Mill 1.5" and 1.5" S9.5B	$1,076,070
2027	8	053-Lee	Resurfacing	US 1 BYPASS	US 15	MOORE CO LINE	4.87	Mill 1.5" and 1.5" S9.5C	$1,010,000
2027	8	053-Lee	Preservation	SR 1143	NC 87	HARNETT CO	0.69	Seal - Double	$22,000
2027	8	053-Lee	Preservation	SR 1294	SR 1157	END MAINT	0.03	Seal - Double	$1,090
2027	8	053-Lee	Preservation	SR 1302	SR 1300	SR 1300	0.89	Seal - Double	$27,000
2027	8	053-Lee	Preservation	SR 1321	NC 42	NC 42	0.66	Seal - Double	$24,240
2027	8	053-Lee	Preservation	SR 1325	SR 1326	SR 1719	0.90	Seal - Double	$28,960
2027	8	053-Lee	Preservation	SR 1325	SR 1719	SR 1384	1.41	Seal - Double	$39,000
2027	8	053-Lee	Preservation	SR 1325	SR 1332	SR 1009	0.63	Seal - Double	$24,306
2027	8	053-Lee	Preservation	SR 1418	SR 1419	SR 1002	1.98	Seal - Double	$60,000
2027	8	053-Lee	Preservation	SR 1425	SR 1002	END MAINT	0.31	Seal - Double	$9,500
2027	8	053-Lee	Preservation	SR 1433	SR 1423	SR 1466	0.67	Seal - Double	$28,560
2027	8	053-Lee	Preservation	SR 1579	LANE CHG	END C&G	3.50	Seal - Double	$196,540
2027	8	053-Lee	Preservation	SR 1582	SR 1529	END PVMT	0.70	Seal - Double	$24,000
2027	8	062-Montgomery	Resurfacing	NC 109	SR 1127	SR 1633	1.65	1.5" S9.5B	$350,000
2027	8	062-Montgomery	Resurfacing	NC 109	SR 1116	SR 1100	2.03	1.5" S9.5B	$366,300
2027	8	062-Montgomery	Resurfacing	NC 24	R/R Track	Bridge over I73/74	0.81	Mill 1.5" and 1.5" S9.5C	$455,000
2027	8	062-Montgomery	Resurfacing	NC 731	SR 1543	SR 1541	2.90	1.5" S9.5B	$500,000
2027	8	062-Montgomery	Resurfacing	NC 731	1.2 miles west of SR 1536	SR 1524	3.04	1.5" S9.5B	$500,000
2027	8	062-Montgomery	Resurfacing	SR 1161	SR 1162	Davidson Co	0.97	1.5" S9.5B	$194,000
2027	8	062-Montgomery	Resurfacing	SR 1162	SR 1161	End Maint	2.28	1.5" S9.5B	$450,000
2027	8	062-Montgomery	Resurfacing	SR 1191	SR 1160	SR 1160	0.33	1.5" S9.5B	$56,000
2027	8	062-Montgomery	Resurfacing	SR 1524	Pvmt Change	US 220 Alt	0.54	1.5" S9.5B	$130,088
2027	8	062-Montgomery	Preservation	NC 24	R/R	End of Island	0.34	Crack Seal	$6,100
2027	8	062-Montgomery	Preservation	SR 1100	SR 1102	SR 1103	1.62	Seal - Double	$65,000
2027	8	062-Montgomery	Preservation	SR 1103	SR 1110	ROW Marker	0.77	Seal - Double	$26,500
2027	8	062-Montgomery	Preservation	SR 1112	NC 73	SR 1130	1.52	Seal - Double	$65,000
2027	8	062-Montgomery	Preservation	SR 1118	NC 731	NC 731 + 1 miles	1.00	Seal - Double	$39,100
2027	8	062-Montgomery	Preservation	SR 1150	SR 1146	SR 1151	0.95	Seal - Double	$42,000
2027	8	062-Montgomery	Preservation	SR 1301	SR 1302	Randolph Co	1.37	Seal - Double	$59,000
2027	8	062-Montgomery	Preservation	SR 1310	SR 1307	Randolph Co	0.81	Seal - Double	$28,400
2027	8	062-Montgomery	Preservation	SR 1331	SR 1310	End Loop	0.52	Seal - Double and Fog Seal	$22,000
2027	8	062-Montgomery	Preservation	SR 1343	SR 1340	SR 1346	3.25	Crack Seal	$57,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	8	062-Montgomery	Preservation	SR 1527	SR 1003	Richmond Co	1.04	Seal - Double	$46,145
2027	8	062-Montgomery	Preservation	SR 1542	Pvmt Change	NC 731	1.22	Seal - Double	$48,000
2027	8	063-Moore	Resurfacing	NC 24	NC 22	SR 1006	0.98	1.5" S9.5C	$155,000
2027	8	063-Moore	Resurfacing	NC 705	SR 1422	SR 1428 +.349	2.00	1.5" S9.5B	$180,000
2027	8	063-Moore	Resurfacing	NC 705	SR 1440	SR 1451	1.72	1.5" S9.5B	$281,500
2027	8	063-Moore	Resurfacing	NC 705	SR 1451	SR 1453	1.64	1.5" S9.5B	$257,000
2027	8	063-Moore	Resurfacing	NC 705	SR 1410	MOORE CO	0.87	1.5" S9.5B	$135,000
2027	8	063-Moore	Resurfacing	NC 73	MONT. CO.	SR 1122	1.58	1.5" S9.5B	$229,000
2027	8	063-Moore	Resurfacing	SR 1002	SR 1501	SR 1275	4.79	1.5" S9.5B	$734,451
2027	8	063-Moore	Resurfacing	SR 1103	RIDGECREST	US 1	3.20	1.5" S9.5B	$512,264
2027	8	063-Moore	Resurfacing	SR 1116	NC 5	SR 1118	0.55	1.0" S9.5A	$51,750
2027	8	063-Moore	Resurfacing	SR 1122	SR 1125	NC 73	0.39	1.25" SF9.5A	$48,950
2027	8	063-Moore	Resurfacing	SR 1122	MP 7.249	SR 1125	1.18	1.25" SF9.5A	$173,642
2027	8	063-Moore	Resurfacing	SR 1122	BRIDGE	SR 1004	1.63	1.25" SF9.5A	$362,273
2027	8	063-Moore	Resurfacing	SR 1122	SR 1115	SR 1169	1.78	1.25" SF9.5A	$284,000
2027	8	063-Moore	Resurfacing	SR 1132	PVMT CHG	SR 1180	0.21	1.25" SF9.5A	$15,250
2027	8	063-Moore	Resurfacing	SR 1133	SR 1133	NC 73	0.19	1.0" S9.5A	$10,000
2027	8	063-Moore	Resurfacing	SR 1181	NC 211	SR 1138	0.09	1.5" S9.5A	$13,000
2027	8	063-Moore	Resurfacing	SR 1210	SR 1265	NC 24	2.22	1.5" S9.5B	$369,500
2027	8	063-Moore	Resurfacing	SR 1229	SR 1210	SR 1227	0.92	1.5" S9.5B	$162,300
2027	8	063-Moore	Resurfacing	SR 1270	PVMT CHG	SR 1210	1.92	1.25" SF9.5A	$260,000
2027	8	063-Moore	Resurfacing	SR 1274	SR 1304	NC 211	0.12	1.25" SF9.5A	$16,000
2027	8	063-Moore	Resurfacing	SR 1275	NC 211	SR 1138	0.15	1.25" SF9.5A	$21,000
2027	8	063-Moore	Resurfacing	SR 1275	SR 1278	NC 211	1.80	1.25" SF9.5A	$300,000
2027	8	063-Moore	Resurfacing	SR 1296	NC 705	END MAINT	0.12	1.0" S9.5A	$5,200
2027	8	063-Moore	Resurfacing	SR 1509	SR 1405	DEAD END	0.41	1.0" S9.5A	$19,000
2027	8	063-Moore	Resurfacing	SR 1803	SR 1833	SR 1837	0.74	1.5" S9.5A	$103,000
2027	8	063-Moore	Resurfacing	SR 1834	NC 22	SR 1833	1.51	1.5" S9.5B	$252,000
2027	8	063-Moore	Resurfacing	SR 1853	NC 22	MP 0.34	0.34	1.5" S9.5B	$40,000
2027	8	063-Moore	Resurfacing	SR 1853	BRIDGE	SR 1843	1.43	1.5" S9.5B	$245,000
2027	8	063-Moore	Resurfacing	SR 1861	PVMT CHG	SR 1860	0.99	1.25" SF9.5A	$130,000
2027	8	063-Moore	Resurfacing	US 1	SR 1871 + .119	SR 1857	3.20	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5C	$1,995,000
2027	8	063-Moore	Preservation	NC 24	SR 2001 + 1.714	HARNETT CO	0.75	Crack Seal	$10,000
2027	8	063-Moore	Preservation	SR 1105	SR 1104	SR 1103	0.70	Full Depth Patching and Double Seal	$39,750
2027	8	063-Moore	Preservation	SR 1114	SR 1113	END MAINT	1.05	Seal - Double	$31,500
2027	8	063-Moore	Preservation	SR 1137	NC 211	SR 1129	1.39	Full Depth Patching and Double Seal	$81,545
2027	8	063-Moore	Preservation	SR 1181	NC 211	SR 1138	0.09	Seal - Double	$2,516
2027	8	063-Moore	Preservation	SR 1182	SR 1172	DEAD END	0.21	Seal - Slurry	$9,343
2027	8	063-Moore	Preservation	SR 1229	SR 1230	SR 1228	2.54	Crack Seal	$25,411
2027	8	063-Moore	Preservation	SR 1248	SR 1252	SR 1249	0.99	Full Depth Patching and Double Seal	$64,704
2027	8	063-Moore	Preservation	SR 1403	SR 1405	SR 1514	1.28	Full Depth Patching and Double Seal	$75,064
2027	8	063-Moore	Preservation	SR 1412	SR 1414	RAND. CO	1.70	Full Depth Patching and Double Seal	$116,174
2027	8	063-Moore	Preservation	SR 1434	NC 24	SR 1276	1.09	Full Depth Patching and Double Seal	$78,127
2027	8	063-Moore	Preservation	SR 1436	SR 1435	SR 1435	1.30	Full Depth Patching and Double Seal	$84,838
2027	8	063-Moore	Preservation	SR 1439	SR 1440	DEAD END	1.07	Full Depth Patching and Double Seal	$69,982
2027	8	063-Moore	Preservation	SR 1446	NC 705	END MAINT	0.23	Full Depth Patching and Double Seal	$17,000
2027	8	063-Moore	Preservation	SR 1447	SR 1511	SR 1446	0.11	Full Depth Patching and Double Seal	$7,015
2027	8	063-Moore	Preservation	SR 1459	SR 1419	CTRY RIVER	1.40	Full Depth Patching and Double Seal	$88,250
2027	8	063-Moore	Preservation	SR 1478	SR 1477	SR 1479	1.61	Full Depth Patching and Double Seal	$93,250
2027	8	063-Moore	Preservation	SR 1489	PVMT CHG	SR 1487	0.33	Full Depth Patching and Double Seal	$22,500
2027	8	063-Moore	Preservation	SR 1621	SR 1622	CHATHAM CO	1.66	Full Depth Patching and Double Seal	$67,000
2027	8	063-Moore	Preservation	SR 1621	SR 1624	SR 1620	1.15	Full Depth Patching and Double Seal	$71,850
2027	8	063-Moore	Preservation	SR 1802	SR 1843	SR 1853	1.29	Full Depth Patching and Double Seal	$69,000
2027	8	063-Moore	Preservation	SR 2004	SR 2005	SR 2002	0.85	Full Depth Patching and Double Seal	$62,280
2027	8	063-Moore	Preservation	SR 2017	NC 690	SR 2018	0.86	Full Depth Patching and Double Seal	$36,000
2027	8	063-Moore	Preservation	SR 2026	SR 2027	MP 3.6	1.54	Full Depth Patching and Double Seal	$56,000
2027	8	063-Moore	Preservation	SR 2026	MP 3.6	SR 2023	1.63	Full Depth Patching and Double Seal	$81,280
2027	8	063-Moore	Preservation	US 1	SR 2118	SR 1102 + 1.705	2.82	Crack Seal	$36,722
2027	8	076-Randolph	Resurfacing	I -73 SBL	DAWSON MILLER RD. (SR 1138)	MONTGOMERY COUNTY LINE	8.26	1.5" S9.5C	$1,825,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	8	076-Randolph	Resurfacing	I-73 NBL	MONTGOMERY COUNTY LINE	DAWSON MILLER RD. RAMP	8.30	1.5" S9.5C	$1,828,000
2027	8	076-Randolph	Resurfacing	SR 1306	SR 1303 Brantley Gordon Rd.	SR 1001 Farmer Denton Rd.	1.88	Full Depth Patching and 1.5" S9.5B	$340,000
2027	8	076-Randolph	Resurfacing	SR 1311	SR 1001 Farmer Denton Rd.	US 64	5.72	Full Depth Patching and 1.5" S9.5B	$955,000
2027	8	076-Randolph	Resurfacing	SR 1339	Davidson Co. Line	SR 1311 Bescher Chapel Rd.	4.24	Full Depth Patching and 1.5" S9.5B	$750,000
2027	8	076-Randolph	Resurfacing	SR 1344	Davidson Co. Line	US 64	3.11	Full Depth Patching and 1.5" S9.5B	$575,000
2027	8	076-Randolph	Resurfacing	SR 1525	SR 1004 Flint Hill Rd.	SR 1009 US Hwy. 311	3.84	Full Depth Patching and 1.5" S9.5B	$700,000
2027	8	076-Randolph	Resurfacing	SR 1532	SR 1571 Old Glenola Rd.	SR 1526 Edgar Rd.	1.77	Patching and #67 Mat Seal and 2.0" S9.5B	$375,000
2027	8	076-Randolph	Resurfacing	SR 1534	SR 1004 Archdale Rd.	SR 1858 Old Marlboro Rd.	1.86	Patching and #67 Mat Seal and 2.0" S9.5B	$355,000
2027	8	076-Randolph	Resurfacing	SR 1557	SR3252 Hopewell Ch. Rd.	SR 3106 Kennedy Rd.	0.79	Full Depth Patching and 1.5" S9.5B	$150,000
2027	8	076-Randolph	Resurfacing	SR 1558	Guilford Co. Line	SR 1595 Surrett Dr.	2.66	Full Depth Patching and 1.5" S9.5B	$450,000
2027	8	076-Randolph	Resurfacing	SR 1566	SR 1004 Trinity Rd.	SR 1004 Archdale Rd.	3.82	Full Depth Patching and 1.5" S9.5B	$725,000
2027	8	076-Randolph	Resurfacing	SR 1595	NC 62	Guilford Co. Line	2.76	Full Depth Patching and 1.5" S9.5B	$500,000
2027	8	076-Randolph	Resurfacing	SR 1619	Guilford County Line	SR 1558 Turnpike Rd.	2.43	Full Depth Patching and 1.5" S9.5B	$500,000
2027	8	076-Randolph	Resurfacing	SR 1621	SR 1627 Old Thomasville Rd.	SR 1619 Prospect St.	0.50	Full Depth Patching and 1.5" S9.5B	$125,000
2027	8	076-Randolph	Resurfacing	SR 1622	Guilford Co. Line	SR 1619 Prospect St.	0.19	Full Depth Patching and 1.5" S9.5B	$50,000
2027	8	076-Randolph	Resurfacing	SR 1624	SR 1627 Old Thomasville Rd.	Dead End	0.23	Full Depth Patching and 1.5" S9.5B	$50,000
2027	8	076-Randolph	Resurfacing	SR 1627	SR 1627 Old Thomasville Rd.	Guilford Co. Line	1.35	Full Depth Patching and 1.5" S9.5B	$250,000
2027	8	076-Randolph	Resurfacing	SR 1628	SR 1621 Bethel Dr.	Dead End	0.11	Full Depth Patching and 1.5" S9.5B	$25,000
2027	8	076-Randolph	Resurfacing	SR 1629	SR 1627 Old Thomasville Rd.	Dead End	0.16	Full Depth Patching and 1.5" S9.5B	$45,000
2027	8	076-Randolph	Resurfacing	SR 1668	SR 1627 Old Thomasville Rd.	End of Maint.	0.16	Full Depth Patching and 1.5" S9.5B	$45,000
2027	8	076-Randolph	Resurfacing	SR 1747	SR 1009 Old US 311	SR 1571 Old Glenola Rd.	0.15	Full Depth Patching and 1.5" S9.5B	$26,200
2027	8	076-Randolph	Resurfacing	SR 1915	SR 1912 Aldridge Rd.	SR 1916 Weant Rd.	1.08	Full Depth Patching and 1.5" S9.5B	$200,000
2027	8	076-Randolph	Resurfacing	SR 1917	Guilford Co. Line	SR 1009 US Hwy. 311	2.53	Full Depth Patching and 1.5" S9.5B	$475,000
2027	8	076-Randolph	Resurfacing	SR 1918	SR 1009 US Hwy 311	SR 1917 Suits Rd.	0.58	Full Depth Patching and 1.5" S9.5B	$130,000
2027	8	076-Randolph	Resurfacing	SR 1919	SR 1009 US Hwy 311	Dead End	0.55	Full Depth Patching and 1.5" S9.5B	$115,000
2027	8	076-Randolph	Resurfacing	SR 1921	SR 1926 Harlow Rd.	SR 1928 Cedar Square Rd.	1.19	Full Depth Patching and 1.5" S9.5B	$226,000
2027	8	076-Randolph	Resurfacing	SR 1924	Guilford Co. Line	SR 1921 Coltrane Mill Rd.	0.80	Full Depth Patching and 1.5" S9.5B	$148,000
2027	8	076-Randolph	Resurfacing	SR 1926	Guilford Co. Line	DEAD END	6.27	Full Depth Patching and 1.5" S9.5B	$1,190,000
2027	8	076-Randolph	Resurfacing	SR 1931	SR 1009 Old US 311	SR 1944 Branson Davis Rd.	1.83	Full Depth Patching and 1.5" S9.5B	$340,000
2027	8	076-Randolph	Resurfacing	SR 1943	SR 1943 Earl Johnson Rd.	SR 2073 Walker Mill Rd.	0.69	Full Depth Patching and 1.5" S9.5B	$131,000
2027	8	076-Randolph	Resurfacing	SR 1995	SR 1915 Huff Rd.	SR Change	0.25	Full Depth Patching and 1.5" S9.5B	$55,000
2027	8	076-Randolph	Resurfacing	SR 1996	SR Change	SR 1995 Ashbrook Circle	0.31	Full Depth Patching and 1.5" S9.5B	$65,000
2027	8	076-Randolph	Resurfacing	SR 2014	SR 1915 Huff Rd.	Cul de Sac	0.44	Full Depth Patching and 1.5" S9.5B	$85,000
2027	8	076-Randolph	Resurfacing	SR 2053	SR 1928 Cedar Square Rd.	SR 1918 Trotter Country Rd.	1.89	Full Depth Patching and 1.5" S9.5B	$350,000
2027	8	076-Randolph	Resurfacing	SR 2056	SR 1627 Old Thomasville Rd.	End of Maint.	0.18	Full Depth Patching and 1.5" S9.5B	$50,000
2027	8	076-Randolph	Resurfacing	SR 2476	SR 2472 Shady Grove Ch. Rd.	US 64	1.57	Full Depth Patching and 1.5" S9.5B	$290,000
2027	8	076-Randolph	Resurfacing	SR 3106	SR 1408 Hoover Hill Rd.	Roundabout	4.52	Full Depth Patching and 1.5" S9.5B	$775,000
2027	8	076-Randolph	Resurfacing	SR 3261	SR 1627 Old Thomasville Rd.	Dead End	0.25	Full Depth Patching and 1.5" S9.5B	$55,000
2027	8	076-Randolph	Preservation	SR 1112	Montgomery County Line	SR 1143 High Pine Ch. Rd.	5.08	Full Depth Patching and Double Seal and Fog Seal	$360,000
2027	8	076-Randolph	Preservation	SR 1114	SR 1143 High Pine Ch. Rd.	SR 1109 Pisgah Rd.	5.51	Full Depth Patching and Double Seal	$375,000
2027	8	076-Randolph	Preservation	SR 1118	SR 1121 New Hope Ch. Rd.	SR 1109 Pisgah Rd.	3.19	Full Depth Patching and Double Seal	$225,000
2027	8	076-Randolph	Preservation	SR 1129	US 220 ALT	Dead End	0.39	Full Depth Patching and Double Seal and Fog Seal	$30,000
2027	8	076-Randolph	Preservation	SR 1131	US 220 ALT	End of Maint.	0.33	Full Depth Patching and Double Seal and Fog Seal	$25,000
2027	8	076-Randolph	Preservation	SR 1135	NC 134	End of Maint.	0.48	Full Depth Patching and Double Seal and Fog Seal	$40,000
2027	8	076-Randolph	Preservation	SR 1180	SR 1181 New Hope Rd.	SR 1179 Lou Cranford Rd.	0.99	Full Depth Patching and Double Seal and Fog Seal	$75,000
2027	8	076-Randolph	Preservation	SR 1195	Begin Pavement	Waymon St.	0.38	Full Depth Patching and Double Seal and Fog Seal	$30,000
2027	8	076-Randolph	Preservation	SR 1196	SR 1102 Charles Mt. Rd.	Dead End	0.53	Full Depth Patching and Double Seal and Fog Seal	$45,000
2027	8	076-Randolph	Preservation	SR 1209	US 220 ALT	Fox Dr.	0.28	Full Depth Patching and Double Seal and Fog Seal	$22,500
2027	8	076-Randolph	Preservation	SR 1215	US 220 ALT	Dead End	0.11	Full Depth Patching and Double Seal and Fog Seal	$11,500
2027	8	076-Randolph	Preservation	SR 1216	SR 1256 Monterey Rd.	SR 1256 Monterey Rd.	0.26	Full Depth Patching and Double Seal and Fog Seal	$20,000
2027	8	076-Randolph	Preservation	SR 1217	US 220 ALT	Dead End	0.17	Full Depth Patching and Double Seal and Fog Seal	$15,500
2027	8	076-Randolph	Preservation	SR 1239	NC 134	Dead End	0.17	Full Depth Patching and Double Seal and Fog Seal	$15,500
2027	8	076-Randolph	Preservation	SR 1240	SR 1138 Dawson Miller Rd.	MM .22	0.22	Full Depth Patching and Double Seal and Fog Seal	$18,500
2027	8	076-Randolph	Preservation	SR 1247	US 220 ALT	Dead End	0.14	Full Depth Patching and Double Seal and Fog Seal	$14,500
2027	8	076-Randolph	Preservation	SR 1257	SR 1256 Monterey Rd.	Dead End	0.26	Full Depth Patching and Double Seal and Fog Seal	$20,000
2027	8	076-Randolph	Preservation	SR 1751	SR 1566 Fairview Ch. Rd.	SR 1752 Fairview Dr. Ext.	0.21	Full Depth Patching and Double Seal and Fog Seal	$17,000
2027	8	076-Randolph	Preservation	SR 1752	SR 1753 Fairview Ln.	SR 1751 Fairview Dr.	0.21	Full Depth Patching and Double Seal and Fog Seal	$17,000
2027	8	076-Randolph	Preservation	SR 1753	Dead End	Dead End	0.14	Full Depth Patching and Double Seal and Fog Seal	$13,000
2027	8	076-Randolph	Preservation	SR 1754	SR 1751 Fairview Dr.	SR 1753 Fairview Ln.	0.22	Full Depth Patching and Double Seal and Fog Seal	$18,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	8	076-Randolph	Preservation	SR 1823	SR 1565 Ronniedale Rd.	Dead End	0.26	Full Depth Patching and Double Seal and Fog Seal	$21,000
2027	8	076-Randolph	Preservation	SR 1824	SR 1565 Ronniedale Rd.	SR 1825 Nola St.	0.21	Full Depth Patching and Double Seal and Fog Seal	$18,000
2027	8	076-Randolph	Preservation	SR 1825	SR 1824 Oakwood Dr.	SR 1826 Nola St. Ext.	0.07	Full Depth Patching and Double Seal and Fog Seal	$8,000
2027	8	076-Randolph	Preservation	SR 1826	SR 1825 Nola St.	Dead End	0.11	Full Depth Patching and Double Seal and Fog Seal	$10,000
2027	8	076-Randolph	Preservation	SR 1846	SR 1566 Fairview Ch. Rd.	SR 1847 Calvert St.	0.17	Full Depth Patching and Double Seal and Fog Seal	$15,000
2027	8	076-Randolph	Preservation	SR 1847	SR 1846 Lanvale Ave.	SR 1848 Summerville Dr.	0.11	Full Depth Patching and Double Seal and Fog Seal	$11,500
2027	8	076-Randolph	Preservation	SR 1848	SR 1847 Calvert St.	End of Maintenance	0.36	Full Depth Patching and Double Seal and Fog Seal	$26,500
2027	8	076-Randolph	Preservation	SR 2844	US 220 ALT	SR 2843 Happy Hollow Rd.	0.20	Full Depth Patching and Double Seal and Fog Seal	$16,500
2027	8	076-Randolph	Preservation	SR 2847	US 220 ALT	Dead End	0.20	Full Depth Patching and Double Seal and Fog Seal	$20,000
2027	8	076-Randolph	Preservation	SR 2854	SR 2853 Ridge Rd.	Dead End	0.49	Full Depth Patching and Double Seal and Fog Seal	$32,000
2027	8	076-Randolph	Preservation	SR 2855	NC 705	Dead End	0.38	Full Depth Patching and Double Seal and Fog Seal	$30,000
2027	8	076-Randolph	Preservation	SR 2856	NC 705	US 220 ALT	0.77	Full Depth Patching and Double Seal and Fog Seal	$60,000
2027	8	076-Randolph	Preservation	SR 2858	US 220 ALT	Dead End	0.27	Full Depth Patching and Double Seal and Fog Seal	$20,000
2027	8	076-Randolph	Preservation	SR 2910	US 220 ALT	SR 2846 Seagrove Plank Rd.	0.91	Full Depth Patching and Double Seal and Fog Seal	$67,500
2027	8	076-Randolph	Preservation	SR 3003	US 220 ALT	Dead End	0.27	Full Depth Patching and Double Seal and Fog Seal	$21,000
2027	8	076-Randolph	Preservation	SR 3111	SR 1566 Fairview Ch. Rd.	SR 3112 Pine Cone Ct.	0.10	Full Depth Patching and Double Seal and Fog Seal	$9,500
2027	8	076-Randolph	Preservation	SR 3112	SR 3111 Hillcrest Ln.	SR 3113 Sunset Knoll Dr.	0.08	Full Depth Patching and Double Seal and Fog Seal	$8,500
2027	8	076-Randolph	Preservation	SR 3113	SR 1566 Fairview Ch. Rd.	SR 3112 Pine Cone Ct.	0.13	Full Depth Patching and Double Seal and Fog Seal	$11,000
2027	8	077-Richmond	Resurfacing	74 BYP E	I-73	SR1103 Overpass	3.00	Mill 1.5" and 1.5" S9.5C	$975,000
2027	8	077-Richmond	Resurfacing	74 BYP W	SR1103 overpass	I-73	2.90	Mill 1.5" and 1.5" S9.5C	$920,000
2027	8	077-Richmond	Resurfacing	EB off ramp	74 byp	SR 1104	0.30	Mill 1.5" and 1.5" S9.5D	$52,000
2027	8	077-Richmond	Resurfacing	EB on ramp	SR 1109	74 byp	0.25	Mill 1.5" and 1.5" S9.5B	$45,000
2027	8	077-Richmond	Resurfacing	NC 381	Scot Co	US 74 bus	4.50	1.5" S9.5B	$760,000
2027	8	077-Richmond	Resurfacing	SR 1230	SR 1139	Dead end	0.50	1.5" S9.5B	$72,500
2027	8	077-Richmond	Resurfacing	SR 1643	SR 1646	SR 1640	2.84	1.5" S9.5B	$405,000
2027	8	077-Richmond	Resurfacing	SR 1648	US 1	US 74 Bus	1.74	Mill 1.5" and 1.5" S9.5B	$450,000
2027	8	077-Richmond	Resurfacing	SR1486	SR 1442	US 1	5.07	1.5" S9.5B	$730,000
2027	8	077-Richmond	Resurfacing	SR1999	US 1	US1 + 0.79miles	0.79	1.5" S9.5B	$113,000
2027	8	077-Richmond	Resurfacing	WB off ramp	74 byp	SR 1109	0.30	Mill 1.5" and 1.5" S9.5B	$52,000
2027	8	077-Richmond	Resurfacing	WB on ramp	Sr 1109	74 byp	0.25	Mill 1.5" and 1.5" S9.5B	$45,000
2027	8	077-Richmond	Preservation	SR 1105	SR 1994	US 1	2.51	Seal - Double	$105,000
2027	8	077-Richmond	Preservation	SR 1109	SR 1115	SR 1108	0.60	Seal - Double and Fog Seal	$18,000
2027	8	077-Richmond	Preservation	SR 1110	SR 1103	SR 1172	0.70	Seal - Double and Fog Seal	$21,000
2027	8	077-Richmond	Preservation	SR 1112	SR 1110	SR1109	0.68	Seal - Double and Fog Seal	$20,000
2027	8	077-Richmond	Preservation	SR 1115	SR 1110	SR1112	0.15	Seal - Double and Fog Seal	$4,600
2027	8	077-Richmond	Preservation	SR 1137	SR 1103	US 1	0.46	Seal - Double	$15,000
2027	8	077-Richmond	Preservation	SR 1166	NC 109	SR 1148	1.03	Seal - Double	$43,200
2027	8	077-Richmond	Preservation	SR 1168	NC 109	NC 109	3.40	Seal - Double	$82,000
2027	8	077-Richmond	Preservation	SR 1208	SR 1109	SR 1209	0.07	Seal - Double and Fog Seal	$2,200
2027	8	077-Richmond	Preservation	SR 1209	Dead End	SR 1208 + .242 miles	0.30	Seal - Double and Fog Seal	$9,100
2027	8	077-Richmond	Preservation	SR 1464	SR 1003	SR 1465	1.27	Seal - Double	$53,400
2027	8	077-Richmond	Preservation	SR 1515	SR 1431	SR 1431	0.49	Seal - Double and Fog Seal	$15,000
2027	8	077-Richmond	Preservation	SR 1518	SR 1418	SR 1519	0.21	Seal - Double and Fog Seal	$6,500
2027	8	077-Richmond	Preservation	SR 1519	SR 1518	SR1520	0.09	Seal - Double and Fog Seal	$2,600
2027	8	077-Richmond	Preservation	SR 1520	SR 1519	SR 1518	0.12	Seal - Double and Fog Seal	$3,600
2027	8	077-Richmond	Preservation	SR 1532	SR 1432	Dead End	0.33	Seal - Double and Fog Seal	$10,000
2027	8	077-Richmond	Preservation	SR 1537	SR 1418	SR 1418	0.25	Seal - Double and Fog Seal	$7,500
2027	8	077-Richmond	Preservation	SR 1548	SR 1513	SR 1431	0.14	Seal - Double and Fog Seal	$4,300
2027	8	077-Richmond	Preservation	SR 1579	SR 1518	SR1518 + .114miles	0.11	Seal - Double and Fog Seal	$3,500
2027	8	077-Richmond	Preservation	SR 1670	US 74 BUS	SR 1720	0.38	Seal - Double and Fog Seal	$11,400
2027	8	077-Richmond	Preservation	SR 1719	Dead end	Dead end	0.21	Seal - Double and Fog Seal	$6,500
2027	8	077-Richmond	Preservation	SR 1720	End Maint	Dead End	0.47	Seal - Double and Fog Seal	$14,000
2027	8	077-Richmond	Preservation	SR 1721	SR 1719	Dead End	0.03	Seal - Double and Fog Seal	$1,000
2027	8	077-Richmond	Preservation	SR 1726	SR 1720	Dead End	0.12	Seal - Double and Fog Seal	$3,600
2027	8	077-Richmond	Preservation	SR 1993	SR 1108	SR 1108+.221 Miles	0.22	Seal - Double and Fog Seal	$6,700
2027	8	077-Richmond	Preservation	SR 2010	SR 1108	SR 2067	0.30	Seal - Double and Fog Seal	$9,000
2027	8	077-Richmond	Preservation	SR 2015	SR 1108	Dead End	0.26	Seal - Double and Fog Seal	$7,800
2027	8	077-Richmond	Preservation	SR 2047	SR 2068	SR 2056	0.08	Seal - Double and Fog Seal	$2,300
2027	8	077-Richmond	Preservation	SR 2056	SR 1241	SR 2047	0.08	Seal - Double and Fog Seal	$2,300

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	8	077-Richmond	Preservation	SR 2060	SR 1108	SR 1108+ .089 miles	0.09	Seal - Double and Fog Seal	$2,700
2027	8	077-Richmond	Preservation	SR 2065	SR1105	Dead End	0.27	Seal - Double and Fog Seal	$8,100
2027	8	077-Richmond	Preservation	SR 2067	SR 2010	SR 2010 +.104 miles	0.17	Seal - Double and Fog Seal	$5,000
2027	8	077-Richmond	Preservation	SR 2069	SR 2068	SR 2067	0.07	Seal - Double and Fog Seal	$2,100
2027	8	077-Richmond	Preservation	SR 2075	SR 2065	SR 2065 + 0.103	0.10	Seal - Double and Fog Seal	$3,100
2027	8	077-Richmond	Preservation	SR1607	NC 177	SER 1614	7.33	Seal - Double	$240,000
2027	8	077-Richmond	Preservation	SR2071	SR 1966	Dead End	0.37	Seal - Double and Fog Seal	$11,100
2027	8	077-Richmond	Preservation	SR2072	SR 2071	Dead End	0.10	Seal - Double and Fog Seal	$3,000
2027	8	083-Scotland	Resurfacing	NC144	SR1105	US15	2.62	1.5" S9.5B	$410,000
2027	8	083-Scotland	Resurfacing	SR1001	RICHMOND CO	SR1351	2.28	1.5" S9.5B	$408,600
2027	8	083-Scotland	Resurfacing	SR1323	SR 1324	NC 144	1.96	1.5" S9.5B	$352,800
2027	8	083-Scotland	Preservation	SR1254	SR 1100	DEAD END	0.10	Crack Seal	$1,000
2027	8	083-Scotland	Preservation	SR1255	SR 1254	DEAD END	0.08	Crack Seal	$800
2027	8	083-Scotland	Preservation	SR1256	SR 1100	DEAD END	0.28	Crack Seal	$2,800
2027	8	083-Scotland	Preservation	SR1257	SR 1256	SR 1261	0.09	Crack Seal	$900
2027	8	083-Scotland	Preservation	SR1258	SR 1256	SR 1104	0.17	Crack Seal	$1,700
2027	8	083-Scotland	Preservation	SR1259	SR 1100	DEAD END	0.20	Crack Seal	$2,000
2027	8	083-Scotland	Preservation	SR1261	SR 1100	SR 1257	0.14	Crack Seal	$1,400
2027	8	083-Scotland	Preservation	SR1263	SR 1104	SR 1282	0.51	Crack Seal	$5,100
2027	8	083-Scotland	Preservation	SR1269	SR 1108	SR 1263	0.50	Crack Seal	$5,000
2027	8	083-Scotland	Preservation	SR1270	SR 1269	SR 1263	0.29	Crack Seal	$2,900
2027	8	083-Scotland	Preservation	SR1278	SR 1269	DEAD END	0.20	Crack Seal	$2,000
2027	8	083-Scotland	Preservation	SR1282	SR 1104	SR 1269	0.09	Crack Seal	$900
2027	8	083-Scotland	Preservation	SR1325	SR1324	SR1336	0.57	Seal - Double	$38,982
2027	8	083-Scotland	Preservation	SR1325	BEG PAVT	SR1324	1.49	Seal - Double	$62,538
2027	8	083-Scotland	Preservation	SR1337	NC144	SR1345	4.73	Seal - Double	$210,055
2027	8	083-Scotland	Preservation	SR1370	SR1001	DEAD END	0.40	Seal - Double and Fog Seal	$41,600
2027	8	083-Scotland	Preservation	SR1408	SR 1412	US 15	1.10	Crack Seal	$11,000
2027	8	083-Scotland	Preservation	SR1412	SR 1415	HOKE CO	7.36	Crack Seal	$73,600
2027	8	083-Scotland	Preservation	SR1433	SR1407	SR1439	5.26	Seal - Double	$232,600
2027	9	029-Davidson	Resurfacing	NC 150	SR 1231	SR 1533	10.75	Mill 1.5" and 1.5" S9.5C	$3,784,000
2027	9	029-Davidson	Resurfacing	SR 1002	SR 2507	ROWAN CO	6.78	1.5" S9.5B	$1,511,265
2027	9	029-Davidson	Resurfacing	SR 1505	SR 1511	SR 1506	1.01	1.5" S9.5B	$202,646
2027	9	029-Davidson	Resurfacing	SR 1510	SR 1508	SR 1511	0.78	1.5" S9.5B	$191,277
2027	9	029-Davidson	Resurfacing	SR 1511	SR 1508	SR 1512	1.61	1.5" S9.5B	$394,815
2027	9	029-Davidson	Resurfacing	SR 1512	SR 1511	NC 150	1.27	1.5" S9.5B	$283,125
2027	9	029-Davidson	Resurfacing	SR 2031	SR 2010	SR 2031	2.29	Mill 1.5" and 1.5" S9.5B	$873,253
2027	9	029-Davidson	Resurfacing	SR 2032	SR 2031	SR 2085	1.28	Mill 1.5" and 1.5" S9.5B	$451,616
2027	9	029-Davidson	Resurfacing	SR 2060	SR 2031	SR 2087	2.34	Mill 1.5" and 1.5" S9.5C	$652,080
2027	9	029-Davidson	Resurfacing	SR 2084	SR 2772	SR 2060	0.62	1.5" S9.5B	$138,219
2027	9	029-Davidson	Resurfacing	SR 2501	SR 1002	NC 47	9.17	1.5" S9.5C	$2,690,747
2027	9	029-Davidson	Resurfacing	SR 3286	SR 1512	EOM	0.56	1.5" S9.5B	$226,723
2027	9	029-Davidson	Preservation	NC 109	R/R Track	SR 2067	8.44	Crack Seal	$59,418
2027	9	029-Davidson	Preservation	SR 1886	SR 1845	SR 1844	0.63	Seal - Double and Fog Seal	$59,136
2027	9	029-Davidson	Preservation	SR 1980	SR 1886	SR 1884	0.41	Seal - Double and Fog Seal	$34,637
2027	9	029-Davidson	Preservation	SR 2001	US 29	SR 20022	0.33	Seal - Double and Fog Seal	$27,878
2027	9	029-Davidson	Preservation	SR 2002	US 29	SR 2001	0.34	Seal - Double and Fog Seal	$31,915
2027	9	029-Davidson	Preservation	SR 2003	SR 2001	EOP	0.43	Seal - Double and Fog Seal	$36,326
2027	9	029-Davidson	Preservation	SR 2009	SR 2010	END	1.01	Seal - Double and Fog Seal	$69,052
2027	9	029-Davidson	Preservation	SR 2011	SR 2010	US 64	0.19	Seal - Double and Fog Seal	$16,051
2027	9	029-Davidson	Preservation	SR 2017	SR 2014	SR 2020	2.03	Seal - Double and Fog Seal	$154,440
2027	9	029-Davidson	Preservation	SR 2033	SR 2031	SR 2034	0.69	Seal - Double and Fog Seal	$52,243
2027	9	029-Davidson	Preservation	SR 2077	SR 2183	EOM	0.26	Seal - Double and Fog Seal	$21,965
2027	9	029-Davidson	Preservation	SR 2223	SR 2783	EOM	0.48	Seal - Double and Fog Seal	$45,244
2027	9	029-Davidson	Preservation	SR 2387	SR 2783	SR 2378	0.57	Seal - Double and Fog Seal	$53,504
2027	9	029-Davidson	Preservation	SR 2707	SR 2020	END	0.19	Seal - Double and Fog Seal	$14,491
2027	9	029-Davidson	Preservation	SR 2710	SR 2027	END	0.31	Seal - Double and Fog Seal	$23,643
2027	9	029-Davidson	Preservation	SR 2711	SR 2710	SR 2712	0.29	Seal - Double and Fog Seal	$21,889
2027	9	029-Davidson	Preservation	SR 2712	SR 2711	SR 2713	0.08	Seal - Double and Fog Seal	$6,330

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	9	029-Davidson	Preservation	SR 2713	SR 2710	SR 2712	0.29	Seal - Double and Fog Seal	$21,965
2027	9	029-Davidson	Preservation	SR 2719	SR 2010	EOM	0.26	Seal - Double and Fog Seal	$17,984
2027	9	029-Davidson	Preservation	SR 2729	SR 2010	EOM	0.17	Seal - Double and Fog Seal	$12,737
2027	9	029-Davidson	Preservation	SR 2732	SR 2775	SR 2733	0.26	Seal - Double and Fog Seal	$20,134
2027	9	029-Davidson	Preservation	SR 2733	EOM	EOM	0.47	Seal - Double and Fog Seal	$35,464
2027	9	029-Davidson	Preservation	SR 2734	SR 2060	SR 2733	0.09	Seal - Double and Fog Seal	$6,635
2027	9	029-Davidson	Preservation	SR 2735	SR 2024	EOM	0.34	Seal - Double and Fog Seal	$25,854
2027	9	029-Davidson	Preservation	SR 2744	SR 2103	EOM	0.32	Seal - Double and Fog Seal	$30,037
2027	9	029-Davidson	Preservation	SR 2745	SR 2744	NC 109	0.13	Seal - Double and Fog Seal	$12,203
2027	9	029-Davidson	Preservation	SR 2751	SR 2024	EOM	0.22	Seal - Double and Fog Seal	$16,931
2027	9	029-Davidson	Preservation	SR 2752	SR 2751	EOM	0.30	Seal - Double and Fog Seal	$22,727
2027	9	029-Davidson	Preservation	SR 2753	SR 2020	END	0.33	Seal - Double and Fog Seal	$24,787
2027	9	029-Davidson	Preservation	SR 2756	SR 2010	SR 2757	0.26	Seal - Double and Fog Seal	$19,753
2027	9	029-Davidson	Preservation	SR 2757	SR 2756	SR 2758	0.11	Seal - Double and Fog Seal	$8,084
2027	9	029-Davidson	Preservation	SR 2758	SR 2759	SR 2757	0.12	Seal - Double and Fog Seal	$9,228
2027	9	029-Davidson	Preservation	SR 2759	SR 2758	END	0.03	Seal - Double and Fog Seal	$2,593
2027	9	029-Davidson	Preservation	SR 2763	SR 2020	END	0.17	Seal - Double and Fog Seal	$11,532
2027	9	029-Davidson	Preservation	SR 2775	SR 2060	EOM	0.64	Seal - Double and Fog Seal	$48,658
2027	9	029-Davidson	Preservation	SR 2782	US 64	EOM	0.34	Seal - Double and Fog Seal	$27,878
2027	9	029-Davidson	Preservation	SR 2788	SR 2024	SR 2852	0.16	Seal - Double and Fog Seal	$12,279
2027	9	029-Davidson	Preservation	SR 2789	SR 2124	EOM	0.14	Seal - Double and Fog Seal	$10,982
2027	9	029-Davidson	Preservation	SR 2808	SR 2183	CUL DE SAC	0.12	Seal - Double and Fog Seal	$10,138
2027	9	029-Davidson	Preservation	SR 2839	SR 2010	EOM	0.18	Seal - Double and Fog Seal	$13,499
2027	9	029-Davidson	Preservation	SR 2852	SR 2752	EOM	0.15	Seal - Double and Fog Seal	$11,440
2027	9	029-Davidson	Preservation	SR 2943	SR 1841	CUL DE SAC	0.26	Seal - Double and Fog Seal	$24,405
2027	9	030-Davie	Resurfacing	SR 1002	SR 1343	US 601	3.08	1.5" S9.5B	$755,543
2027	9	030-Davie	Resurfacing	SR 1442	US 158	NC 801	1.93	1.5" S9.5B	$473,287
2027	9	030-Davie	Resurfacing	SR 1452	NC 801	NC 801	4.65	1.5" S9.5B	$1,140,059
2027	9	030-Davie	Resurfacing	SR 1600	US 158	SR 1601	0.80	1.5" S9.5B	$214,819
2027	9	030-Davie	Resurfacing	SR 1605	US 64	SR 1802	1.08	1.5" S9.5B	$269,749
2027	9	030-Davie	Resurfacing	US 601	US 64	SR 1404	1.23	Mill 1.5" and 1.5" S9.5C	$650,496
2027	9	030-Davie	Resurfacing	US 601	SR 1404	I-40	0.42	Mill 1.5" and 1.5" S9.5C	$310,933
2027	9	030-Davie	Resurfacing	US 64	US 158	SR 1602	1.28	Mill 1.5" and 1.5" S9.5C	$450,560
2027	9	030-Davie	Preservation	SR 1002	YADKIN CO	US 601	6.72	Crack Seal	$43,366
2027	9	030-Davie	Preservation	SR 1325	SR 1324	IREDELL CO LINE	1.11	Seal - Double and Fog Seal	$104,567
2027	9	030-Davie	Preservation	SR 1326	SR 1002	YADKIN CO LIINE	0.56	Seal - Double and Fog Seal	$52,565
2027	9	030-Davie	Preservation	SR 1409	US 158	SR 1466	0.31	Seal - Double and Fog Seal	$28,911
2027	9	030-Davie	Preservation	SR 1435	SR1410	SR 1411	2.63	Seal - Double and Fog Seal	$246,775
2027	9	030-Davie	Preservation	SR 1721	NC 801	EOM	0.43	Seal - Double and Fog Seal	$44,709
2027	9	030-Davie	Preservation	SR 1723	SR 1721	EOM	0.34	Seal - Double and Fog Seal	$34,693
2027	9	030-Davie	Preservation	SR 1727	EOM	EOM	0.23	Seal - Double and Fog Seal	$23,335
2027	9	030-Davie	Preservation	SR 1820	SR 1819	EOM	0.63	Seal - Double and Fog Seal	$59,230
2027	9	030-Davie	Preservation	SR 1821	SR 1819	EOM	1.35	Seal - Double and Fog Seal	$126,813
2027	9	030-Davie	Preservation	SR 1825	SR 1826	EOM	0.47	Seal - Double and Fog Seal	$44,399
2027	9	030-Davie	Preservation	SR 1826	US 601	SR 1819	1.50	Seal - Double and Fog Seal	$141,175
2027	9	030-Davie	Preservation	SR 1850	SR 1820	EOM	0.51	Seal - Double and Fog Seal	$47,403
2027	9	034-Forsyth	Resurfacing	NC 66	SR 2211	SR 4000	3.60	Mill 1.5" and 1.5" S9.5C	$1,267,200
2027	9	034-Forsyth	Resurfacing	NC 66	US 311	SR 2211	3.90	Mill 1.5" and 1.5" S9.5C	$1,372,800
2027	9	034-Forsyth	Resurfacing	SR 1120	US 158	SR 3011	3.51	Mill 1.5" and 1.5" S9.5C	$1,235,520
2027	9	034-Forsyth	Resurfacing	SR 1170	SR 1171	PVMT CHANGE	0.60	1.5" S9.5B	$160,512
2027	9	034-Forsyth	Resurfacing	SR 1528	SR 4463	BETHABARA RD (N/S)	0.52	Mill 1.5" and 1.5" S9.5C	$213,547
2027	9	034-Forsyth	Resurfacing	SR 1628	SR 1611	EOM	0.30	Full Depth Patching and 1.5" S9.5A	$52,800
2027	9	034-Forsyth	Resurfacing	SR 2377	SR 2662	NC 66	3.24	1.5" S9.5C	$729,907
2027	9	034-Forsyth	Resurfacing	SR 2456	NC 66	SR 2207	4.01	1.5" S9.5C	$903,823
2027	9	034-Forsyth	Resurfacing	SR 2648	PVMT JT	SR 2649	0.25	Mill 1.5" and 1.5" S9.5B	$88,704
2027	9	034-Forsyth	Resurfacing	SR 2747	OLD LEXINGTON RD	SR 2825	0.52	Mill 1.5" and 1.5" S9.5C	$276,144
2027	9	034-Forsyth	Resurfacing	SR 3011	DAVIDSON CO	W. CLEMMONSVILLE RD	3.10	1.5" S9.5B	$966,282
2027	9	034-Forsyth	Resurfacing	SR 4002	SR 1611	PVMT CHANGE	2.60	Mill 1.5" and 1.5" S9.5C	$915,200
2027	9	034-Forsyth	Resurfacing	SR 4309	NC 66	NC 66	1.43	Mill 1.5" and 1.5" S9.5C	$501,600

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	9	034-Forsyth	Resurfacing	SR 4325	I-40	EOM	2.12	Mill 1.5" and 1.5" S9.5C	$1,396,560
2027	9	034-Forsyth	Preservation	NC 66	KIGER STREET	STOKES CO. LINE	2.42	Crack Seal	$20,444
2027	9	034-Forsyth	Preservation	SR 1001	SR 1173	SR 1103	3.20	Crack Seal	$19,524
2027	9	034-Forsyth	Preservation	SR 1456	SR 1460	SR 1455	1.24	Seal - Double and Fog Seal	$94,342
2027	9	034-Forsyth	Preservation	SR 1457	SR 1456	EOM	0.28	Seal - Double and Fog Seal	$21,431
2027	9	034-Forsyth	Preservation	SR 1458	SR 1456	SR 1459	0.28	Seal - Double and Fog Seal	$28,189
2027	9	034-Forsyth	Preservation	SR 1459	NC 67	EOM	0.38	Seal - Double and Fog Seal	$35,388
2027	9	034-Forsyth	Preservation	SR 1460	NC 67	NC 67	0.60	Seal - Double and Fog Seal	$67,021
2027	9	034-Forsyth	Preservation	SR 1461	SR 1460	EOM	0.14	Seal - Double and Fog Seal	$13,048
2027	9	034-Forsyth	Preservation	SR 1462	SR 1463	EOM	0.20	Seal - Double and Fog Seal	$16,896
2027	9	034-Forsyth	Preservation	SR 1464	NC 67	EOM	0.71	Seal - Double and Fog Seal	$59,896
2027	9	034-Forsyth	Preservation	SR 1492	NC 67	EOM	0.37	Seal - Double and Fog Seal	$34,731
2027	9	034-Forsyth	Preservation	SR 1493	SR 1458	EOM	0.06	Seal - Double and Fog Seal	$5,069
2027	9	034-Forsyth	Preservation	SR 1521	SR 1459	EOM	0.10	Seal - Double and Fog Seal	$9,668
2027	9	034-Forsyth	Preservation	SR 1540	SR 1456	SR 1459	0.25	Seal - Double and Fog Seal	$23,373
2027	9	034-Forsyth	Preservation	SR 1626	SR 1611	SR 1821	0.48	Seal - Double and Fog Seal	$45,244
2027	9	034-Forsyth	Preservation	SR 1769	SR 1611	SR 1820	0.15	Seal - Double and Fog Seal	$11,135
2027	9	034-Forsyth	Preservation	SR 1819	SR 1611	SR 1820	0.12	Seal - Double and Fog Seal	$9,152
2027	9	034-Forsyth	Preservation	SR 1820	SR 1819	SR 3998	0.21	Seal - Double and Fog Seal	$15,787
2027	9	034-Forsyth	Preservation	SR 1821	SR 1626	SR 1821	0.71	Seal - Double and Fog Seal	$66,645
2027	9	034-Forsyth	Preservation	SR 1843	NC 67	EOM	0.46	Seal - Double and Fog Seal	$42,991
2027	9	034-Forsyth	Preservation	SR 1844	SR 1843	ST 1845	0.23	Seal - Double and Fog Seal	$21,589
2027	9	034-Forsyth	Preservation	SR 1845	SR 1844	EOM	0.24	Seal - Double and Fog Seal	$22,528
2027	9	034-Forsyth	Preservation	SR 1861	SR 1456	EOM	0.08	Seal - Double and Fog Seal	$5,628
2027	9	034-Forsyth	Preservation	SR 1885	SR 1455	SR 1886	0.27	Seal - Double and Fog Seal	$20,287
2027	9	034-Forsyth	Preservation	SR 1886	SR 1885	EOM	0.30	Seal - Double and Fog Seal	$23,185
2027	9	034-Forsyth	Preservation	SR 1887	SR 1886	EOM	0.12	Seal - Double and Fog Seal	$9,152
2027	9	034-Forsyth	Preservation	SR 3211	SR 1464	EOM	0.32	Seal - Double and Fog Seal	$27,203
2027	9	034-Forsyth	Preservation	SR 3279	SR 1463	EOM	0.17	Seal - Double and Fog Seal	$15,770
2027	9	034-Forsyth	Preservation	SR 3322	NC 67	EOM	0.18	Seal - Double and Fog Seal	$16,521
2027	9	034-Forsyth	Preservation	SR 3323	SR 3322	EOM	0.18	Seal - Double and Fog Seal	$17,271
2027	9	034-Forsyth	Preservation	SR 3332	SR 3323	EOM	0.17	Seal - Double and Fog Seal	$15,488
2027	9	034-Forsyth	Preservation	SR 3372	SR 1470	SR 3373	0.15	Seal - Double and Fog Seal	$12,419
2027	9	034-Forsyth	Preservation	SR 3373	SR 3372	EOM	0.14	Seal - Double and Fog Seal	$11,405
2027	9	034-Forsyth	Preservation	SR 3923	NC 67	SR 1620	0.08	Seal - Double and Fog Seal	$7,603
2027	9	034-Forsyth	Preservation	SR 3930	NC 67	EOM	0.15	Seal - Double and Fog Seal	$14,194
2027	9	034-Forsyth	Preservation	SR 3953	SR 1843	EOM	0.12	Seal - Double and Fog Seal	$11,264
2027	9	034-Forsyth	Preservation	SR 3954	SR 3953	EOM	0.16	Seal - Double and Fog Seal	$14,643
2027	9	034-Forsyth	Preservation	SR 3966	SR 4002	EOM	0.18	Seal - Double and Fog Seal	$13,728
2027	9	034-Forsyth	Preservation	SR 3989	SR 3954	EOM	0.06	Seal - Double and Fog Seal	$5,257
2027	9	034-Forsyth	Preservation	SR 3996	SR 1626	EOM	0.11	Seal - Double and Fog Seal	$10,138
2027	9	034-Forsyth	Preservation	SR 3998	SR 1820	EOM	0.15	Seal - Double and Fog Seal	$11,165
2027	9	034-Forsyth	Preservation	SR 4006	SR 1821	EOM	0.10	Seal - Double and Fog Seal	$9,762
2027	9	034-Forsyth	Preservation	SR 4012	SR 3930	EOM	0.11	Seal - Double and Fog Seal	$8,870
2027	9	034-Forsyth	Preservation	SR 4112	SR 1455	EOM	0.42	Seal - Double and Fog Seal	$32,032
2027	9	034-Forsyth	Preservation	SR 4113	SR 4112	SR 4112	0.27	Seal - Double and Fog Seal	$20,287
2027	9	080-Rowan	Resurfacing	NC 150	SR 1350	SR 1825	4.06	1.5" S9.5C	$838,417
2027	9	080-Rowan	Resurfacing	SR 1002	SR 2136	SR 2134	1.60	1.5" S9.5B	$463,701
2027	9	080-Rowan	Resurfacing	SR 1004	SR 2411	SR 2141	3.44	1.5" S9.5B	$843,580
2027	9	080-Rowan	Resurfacing	SR 1211	SR 1350	NC 152	3.02	1.5" S9.5B	$740,585
2027	9	080-Rowan	Resurfacing	SR 1945	SR 2048	US 601	3.05	1.5" S9.5B	$747,451
2027	9	080-Rowan	Resurfacing	SR 1947	SR 2048	SR 1948	1.88	1.5" S9.5B	$503,205
2027	9	080-Rowan	Resurfacing	SR 2048	BRG # 25	NC 801	2.67	1.5" S9.5B	$654,755
2027	9	080-Rowan	Resurfacing	SR 2048	SR 1945	BRG # 25	1.85	1.5" S9.5B	$453,669
2027	9	080-Rowan	Resurfacing	SR 2131	SR 1002	SR 1004	1.77	1.5" S9.5B	$473,243
2027	9	080-Rowan	Resurfacing	SR 2134	SR 2168	SR 1002	1.75	1.5" S9.5B	$429,147
2027	9	080-Rowan	Resurfacing	SR 2200	FULTON ST (NS)	SR 2094	1.30	Mill 1.5" and 1.5" S9.5B	$838,933
2027	9	080-Rowan	Resurfacing	SR 2200	SR 2094	END C&G	0.47	Mill 1.5" and 1.5" S9.5B	$275,733
2027	9	080-Rowan	Resurfacing	SR 2200	END C&G	US 601	1.41	1.5" S9.5B	$345,770

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	9	080-Rowan	Resurfacing	SR 2308	US 52	SR 2126	1.13	1.5" S9.5B	$251,469
2027	9	080-Rowan	Resurfacing	SR 2312	SR 1006	SR 2313	1.16	1.5" S9.5B	$205,990
2027	9	080-Rowan	Resurfacing	SR 2314	SR 2300	SR 2315	1.90	Full Depth Patching and 1.5" S9.5B	$367,840
2027	9	080-Rowan	Resurfacing	SR 2489	SR 1221	CABARRUS CO	2.19	1.5" S9.5B	$537,782
2027	9	080-Rowan	Resurfacing	US 29	SR 2120	Davidson Co Line	2.39	1.5" S9.5C	$1,009,536
2027	9	080-Rowan	Preservation	SR 1212	SR 1211	DEAD END	0.39	Seal - Double and Fog Seal	$36,528
2027	9	080-Rowan	Preservation	SR 1543	NC 152	SR 1545	0.20	Seal - Double and Fog Seal	$19,062
2027	9	080-Rowan	Preservation	SR 1543	SR 1545	EOM	0.25	Seal - Double and Fog Seal	$23,100
2027	9	080-Rowan	Preservation	SR 1544	NC 152	EOM	0.15	Seal - Double and Fog Seal	$13,804
2027	9	080-Rowan	Preservation	SR 1545	NC 152	SR 1543	0.25	Seal - Double and Fog Seal	$23,382
2027	9	080-Rowan	Preservation	SR 1604	SR 1611	NC 152	0.25	Seal - Double and Fog Seal	$21,466
2027	9	080-Rowan	Preservation	SR 1611	EOM	EOM	0.08	Seal - Double and Fog Seal	$6,592
2027	9	080-Rowan	Preservation	SR 1626	SR 1509	EOM	0.24	Seal - Double and Fog Seal	$22,161
2027	9	080-Rowan	Preservation	SR 1640	SR 1626	EOM	0.78	Seal - Double and Fog Seal	$72,868
2027	9	080-Rowan	Preservation	SR 1641	SR 1626	SR 1640	0.37	Seal - Double and Fog Seal	$34,744
2027	9	080-Rowan	Preservation	SR 1647	SR 1640	EOM	0.12	Seal - Double and Fog Seal	$10,987
2027	9	080-Rowan	Preservation	SR 1650	SR 1503	SR 1653	0.46	Seal - Double and Fog Seal	$43,195
2027	9	080-Rowan	Preservation	SR 1651	SR 1651	EOM	0.10	Seal - Double and Fog Seal	$9,390
2027	9	080-Rowan	Preservation	SR 1652	SR 1650	EOM	0.31	Seal - Double and Fog Seal	$29,485
2027	9	080-Rowan	Preservation	SR 1653	SR 1652	EOM	0.44	Seal - Double and Fog Seal	$41,505
2027	9	080-Rowan	Preservation	SR 1729	SR 1526	NC 150	2.30	Crack Seal	$4,445
2027	9	080-Rowan	Preservation	SR 1972	BRG 029	IREDELL CO	3.59	Seal - Double and Fog Seal	$69,863
2027	9	080-Rowan	Preservation	SR 1972	SR 1973	BRG 029	0.93	Seal - Triple and Fog Seal	$269,863
2027	9	080-Rowan	Preservation	SR 1979	SR 72	SR 1003	1.42	Seal - Double and Fog Seal	$106,673
2027	9	080-Rowan	Preservation	SR 1979	SR 1003	EOM	2.08	Seal - Double and Fog Seal	$156,253
2027	9	080-Rowan	Preservation	SR 2048	US 601	SR 1945	2.35	Crack Seal	$4,550
2027	9	080-Rowan	Preservation	SR 2120	US 29	SR 2181 -0.11MI	0.82	Crack Seal	$1,588
2027	9	080-Rowan	Preservation	SR 2200	NS RxR	FULTON ST	0.44	Crack Seal	$2,323
2027	9	080-Rowan	Preservation	US 29	THOMAS ST	NSRR	0.99	Crack Seal	$3,136
2027	9	080-Rowan	Preservation	US 70	SR 1953 -0.1MI	BRG#71 NSRR	3.07	Crack Seal	$8,105
2027	9	080-Rowan	Preservation	US 70	BRG#71 NSRR	SR 1953 +0.1MI	3.06	Crack Seal	$9,694
2027	9	085-Stokes	Resurfacing	NC 65	SR 1950	US 311	3.06	1.5" S9.5C	$689,357
2027	9	085-Stokes	Resurfacing	NC 8	NC 8	SR 1674	6.64	1.5" S9.5B	$1,702,319
2027	9	085-Stokes	Resurfacing	NC 89	NC 8	US 311	5.09	1.5" S9.5B	$1,189,126
2027	9	085-Stokes	Resurfacing	SR 2019	NC 66	NC 8	7.49	1.5" S9.5B	$1,835,522
2027	9	085-Stokes	Preservation	SR 1128	SR 1131	SR 1136	2.26	Crack Seal	$15,875
2027	9	085-Stokes	Preservation	SR 1136	SR 1139	NC 66	2.97	Crack Seal	$19,166
2027	9	085-Stokes	Preservation	SR 1179	NC 268	Surry County Line	0.74	Seal - Double and Fog Seal	$62,346
2027	9	085-Stokes	Preservation	SR 1955	SR 2019	SR 1973	9.26	Seal - Double and Fog Seal	$956,126
2027	10	004-Anson	Resurfacing	NC 145	SC line	Morven City Limits	4.21	1.5" S9.5C and Widen	$1,064,118
2027	10	004-Anson	Resurfacing	NC 742 N	US 52	SR 1422 Boggan Cut	2.77	Full Depth Patching and 1.5" S9.5C	$872,550
2027	10	004-Anson	Resurfacing	SR 1138 Capel Dairy Rd	SR 1205 White Store Rd	NC 109 S	0.69	Full Depth Patching and 1.5" S9.5C	$217,350
2027	10	004-Anson	Resurfacing	SR 1205 White Store Rd	SR 1208 Coffee Pot Rd	SR 1259 Anson High School Rd	1.65	Full Depth Patching and 1.5" S9.5C	$519,750
2027	10	004-Anson	Resurfacing	SR 1250 Poplar Hill Church Rd	SR 1244 Lowery Rd	SR 1246 Mills Rd	1.91	Full Depth Patching and 1.5" S9.5C	$601,650
2027	10	004-Anson	Resurfacing	SR 1456 Olive Branch Rd	SR 1455 Edwards Store Rd	NC 742 N	2.22	1.5" S9.5C and Widen	$561,660
2027	10	004-Anson	Resurfacing	SR 1641 Brown Creek Church Rd	US 52	SR 1652 Lockhart Rd	2.87	Full Depth Patching and 1.5" S9.5C	$904,050
2027	10	004-Anson	Resurfacing	US 52 / US 74	SR 1472 Salisbury Street	US 74	0.33	Mill 2.0" and 2.0" S9.5C	$159,000
2027	10	004-Anson	Preservation	SR 1003 Union Church Road	SR 1228 White Store Road	NC 109	6.41	Seal - Double	$243,580
2027	10	004-Anson	Preservation	SR 1235 Horne Store Road	SR 1236 Upper Store Road	Union County Line	0.78	Seal - Double	$29,640
2027	10	004-Anson	Preservation	SR 1236 Upper White Store Road	SR 1252 Lower White Store Road	SR 1239 Lanes Creek Road	4.62	Seal - Double	$175,560
2027	10	004-Anson	Preservation	SR 1238 Hasty Road	SR Upper White Store Rd	Union County Line	1.20	Seal - Double	$45,600
2027	10	004-Anson	Preservation	SR 1240 Mineral Springs Church Road	SR 1228 White Store Road	SR 1246 Mills Road	2.37	Seal - Double	$90,080
2027	10	004-Anson	Preservation	SR 1244 Lowery Road	SR 1250 Poplar Hill Church Road	R 1240 Mineral Springs Church Roa	2.16	Seal - Double	$82,080
2027	10	004-Anson	Preservation	SR 1250 Poplar Hill Church Road	SR 1228 White Store Road	SR 1244 Lowery Road	0.81	Seal - Double	$30,780
2027	10	004-Anson	Preservation	SR 1410 Phifer Rd	SR 1408 W Deep Springs Rd	SR 1409 Caudle-Kiker Rd	1.00	Seal - Double	$38,000
2027	10	004-Anson	Preservation	SR 1433 McSwain Rd	SR 1435	SR 1434	1.55	Seal - Double	$58,710
2027	10	004-Anson	Preservation	SR 1435 Johnson Rd	SR 1433	SR 1436	1.47	Seal - Double	$55,860
2027	10	004-Anson	Preservation	SR 1440 Carl Taylor	SR 1438	SR 1002	0.84	Seal - Double	$31,920
2027	10	004-Anson	Preservation	SR 1442 Bowers Rd	SR 1445	SR 1002	1.46	Seal - Double	$55,480

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	10	004-Anson	Preservation	SR 1446 Rushing Rd	SR 1002	SR 1443	1.00	Seal - Double	$38,000
2027	10	004-Anson	Preservation	SR 1448 Thanny Helms Rd	NC 218	Union County Line	0.53	Seal - Double	$20,100
2027	10	004-Anson	Preservation	SR 1450 Pork	SR 1449	SR 1444	1.88	Seal - Double	$71,440
2027	10	004-Anson	Preservation	SR 1451 Threadgill Rd	SR 1445 Cappadocia Church Rd	SR 1444 Sub Station Rd	0.31	Seal - Double	$11,780
2027	10	004-Anson	Preservation	SR 1452 Race Track Rd	NC 742	SR 1611 Little Rd	1.29	Seal - Double	$49,020
2027	10	013-Cabarrus	Resurfacing	NC 200	Stanly County Line	SR 1006 Mt Pleasant Rd	3.11	Mill 2.0" and 2.0" S9.5C	$1,079,231
2027	10	013-Cabarrus	Resurfacing	NC 200	SR 1006 Mt Pleasant Rd	US 601	2.62	Mill 2.0" and 2.0" S9.5C	$905,161
2027	10	013-Cabarrus	Resurfacing	NC 73	Begin 2 lane at Mt Pleasant city limits	SR 2609 Blueberry St	1.60	Mill 3.0" and 3.0" S9.5C	$1,242,555
2027	10	013-Cabarrus	Resurfacing	NC 73	SR 2609 Blueberry St	Stanly County Line	3.10	Mill 2.0" and 2.0" S9.5C	$1,079,230
2027	10	013-Cabarrus	Resurfacing	NC 73	SR 2411 Irish Potato Rd	Pmvt jt at Bridge NC 49	3.59	Mill 2.0" and 2.0" S9.5C	$1,253,300
2027	10	013-Cabarrus	Resurfacing	NC 73	NC 3 Branchview Rd	SR 2408 Gold Hill Rd	1.10	Mill 2.0" and 2.0" S9.5C	$382,953
2027	10	013-Cabarrus	Resurfacing	SR 1006 Mt Pleasant Rd	NC 73	Barringer Dr	0.09	Mill 1.5" and 1.5" S9.5C	$65,362
2027	10	013-Cabarrus	Resurfacing	SR 1006 Mt Pleasant Rd	SR 2481 North Dr	NC 49	0.20	Mill 3.0" and 3.0" S9.5B	$167,292
2027	10	013-Cabarrus	Resurfacing	US 29 NB	Kentucky St	Rowan County Line	3.03	Mill 2.0" and 2.0" S9.5C	$1,044,417
2027	10	013-Cabarrus	Resurfacing	US 29 SB	Rowan County Line	I-85	4.00	Mill 2.0" and 2.0" S9.5C	$1,392,556
2027	10	013-Cabarrus	Resurfacing	US 601	SR 2630 (Cold Springs Rd)	SR 1132 (Flowes Store Rd)	2.28	Mill 2.0" and 2.0" S9.5C	$1,194,471
2027	10	013-Cabarrus	Preservation	SR 1142 Running Brook Rd	SR 1143 Cal Bost	SR 1132 Flowe Store Rd	1.36	Seal - Double and Fog Seal	$99,762
2027	10	013-Cabarrus	Preservation	SR 1148	SR 1148 Flowe Store Rd	US 601	2.38	Seal - Double and Fog Seal	$155,592
2027	10	013-Cabarrus	Preservation	SR 1179	SR 1132 Flowes Store Rd.	Dead End	0.31	Seal - Double and Fog Seal	$32,227
2027	10	013-Cabarrus	Preservation	SR 1197 Cimarron Cir	SR 1193 Brandywine Ln	SR 1193 Peppercorn Rd	0.42	Seal - Double and Fog Seal	$25,932
2027	10	013-Cabarrus	Preservation	SR 1891 Winter St	SR 1628 Charlie Walker Rd	dead end	0.15	Seal - Double and Fog Seal	$30,000
2027	10	013-Cabarrus	Preservation	SR 2423 Fisher Rd	NC 49	SR 1006 Mt Pleasant Rd	1.26	Seal - Double and Fog Seal	$84,272
2027	10	013-Cabarrus	Preservation	SR 2431 Parkmont Rd	SR 2429 Rimer Rd	SR 2400 Barrier Rd	0.84	Seal - Double and Fog Seal	$55,457
2027	10	013-Cabarrus	Preservation	SR 2434 Sisk Carter Rd	SR 2429 Rimer Rd	Rowan County line	1.85	Seal - Double and Fog Seal	$119,926
2027	10	013-Cabarrus	Preservation	SR 2447 Cline Rd	SR 2446	SR 2435	0.52	Seal - Double and Fog Seal	$42,415
2027	10	013-Cabarrus	Preservation	SR 2452 Culp	SR 2444 St. Stephens Church	SR 2450 Gold Hill	1.90	Seal - Double and Fog Seal	$129,660
2027	10	013-Cabarrus	Preservation	SR 2470 Amsbury Dr	SR 2411 Coldsprings Rd	EOM	0.30	Seal - Double and Fog Seal	$27,850
2027	10	013-Cabarrus	Preservation	SR 2493 Braughton Ave	SR 2492	SR 2496	0.34	Seal - Double and Fog Seal	$58,500
2027	10	013-Cabarrus	Preservation	SR 2509 Fringewood Dr	SR 2411	SR 2413	0.48	Seal - Double and Fog Seal	$42,227
2027	10	013-Cabarrus	Preservation	SR 2616 Cauble Rd	Bowman Barrier.SR2610	Barrier StoreRd. SR2622	2.40	Seal - Double and Fog Seal	$155,592
2027	10	013-Cabarrus	Preservation	SR 2693 Historic Springs Dr	SR 2630 Cold Springs South	SR 2411 Cold Springs rd	0.56	Seal - Double and Fog Seal	$68,342
2027	10	060-Mecklenburg	Resurfacing	NC 24 Harris Blvd	Old Sugar Creek Rd	SR 2467 +.26 miles	1.75	Mill 1.5" and 1.5" S9.5D	$634,000
2027	10	060-Mecklenburg	Resurfacing	NC 24 WT Harris Blvd WB	SR 2467 Mallard Creek Rd	Old Sugar Creek Rd	1.75	Mill 1.5" and 1.5" S9.5D	$601,000
2027	10	060-Mecklenburg	Resurfacing	NC 49 S Tryon St	NC 160 Steele Creek Rd	I-485	4.34	Mill 1.5" and 1.5" S9.5D	$1,100,000
2027	10	060-Mecklenburg	Resurfacing	NC 49 S Tryon St	I-485	NC 160 Steele Creed Rd	4.34	Mill 1.5" and 1.5" S9.5D	$1,100,000
2027	10	060-Mecklenburg	Resurfacing	NC 49 S Tryon St	Foster Ave	Parkaire Ln	2.04	Mill 1.5" and 1.5" S9.5D	$520,000
2027	10	060-Mecklenburg	Resurfacing	NC 49 York Rd	NC 160 Steele Creek Rd	State Line	3.44	Mill 1.5" and 1.5" S9.5D	$1,060,000
2027	10	060-Mecklenburg	Resurfacing	NC 49 York Rd	State Line	NC 160 Steele Creek Rd	3.46	Mill 1.5" and 1.5" S9.5D	$1,060,000
2027	10	060-Mecklenburg	Resurfacing	NC 51	Carolina Place Pkwy	NC 51 S	0.56	Mill 1.5" and 1.5" S9.5D	$172,000
2027	10	060-Mecklenburg	Resurfacing	NC 51 Matthews Township Parkway NB	NC 16 Providence Rd	SR 1010 West Johns St	3.28	Mill 1.5" and 1.5" S9.5D	$960,000
2027	10	060-Mecklenburg	Resurfacing	NC 51 Mint Hill Rd	SR 3176 Phillips Rd	Blacksmith Rd	0.48	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$132,000
2027	10	060-Mecklenburg	Resurfacing	SR 1004 Lawyers Rd	Begin Div	Union County line	0.40	Full Depth Patching and 1.5" S9.5B	$70,000
2027	10	060-Mecklenburg	Resurfacing	SR 1101 Youngblood Rd W	SR 1102	eom	0.52	Full Depth Patching and 1.5" S9.5B	$80,000
2027	10	060-Mecklenburg	Resurfacing	SR 1116 Shopton Rd W	Kirkwyrd Commons Dr	Dan Caudle Rd	0.86	Full Depth Patching and 1.5" S9.5B	$165,000
2027	10	060-Mecklenburg	Resurfacing	SR 1126 Nations Ford Rd	RR	Westinghouse Blvd.	0.43	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$100,000
2027	10	060-Mecklenburg	Resurfacing	SR 1188 Brick Yard Rd	SR 1191	end of pavement	0.23	Full Depth Patching and 1.25" S9.5B	$44,000
2027	10	060-Mecklenburg	Resurfacing	SR 1191 Old Dowd Rd	SR 1195 Wallace Neel Rd	US 29 Wilkinson Blvd	2.97	Full Depth Patching and 1.5" S9.5C	$750,000
2027	10	060-Mecklenburg	Resurfacing	SR 1338 West Dixie Dr	Dixie River Rd	West Dixie Dr	0.81	Full Depth Patching and 1.25" S9.5B	$152,000
2027	10	060-Mecklenburg	Resurfacing	SR 1347 Nevada Blvd	NC 49 S Tryon St	dead end (Granite St)	1.21	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$229,000
2027	10	060-Mecklenburg	Resurfacing	SR 1397 Voyager Rd	Walkers Ferry Rd	Marlette Dr	0.26	Full Depth Patching and 1.25" S9.5B	$50,000
2027	10	060-Mecklenburg	Resurfacing	SR 1423 Pleasant Way Ln	Shopton Rd	eom	0.20	Full Depth Patching and 1.25" S9.5B	$36,000
2027	10	060-Mecklenburg	Resurfacing	SR 1785 Valleydale Rd	Homestead Glen Blvd	Bellhaven Blvd /Rozzelles Ferry Rd	1.34	Full Depth Patching and 1.5" S9.5C	$330,000
2027	10	060-Mecklenburg	Resurfacing	SR 1815 Queen City Dr	Sloan Dr	SR 1641	1.07	Full Depth Patching and 1.25" S9.5B	$200,000
2027	10	060-Mecklenburg	Resurfacing	SR 1927 Harbor Drive	Moores Chapel Rd	Cold Harbor Dr	0.57	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$132,000
2027	10	060-Mecklenburg	Resurfacing	SR 1928 Pine Cape Dr	Harbor Dr	Cold Harbor Dr	0.14	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$37,000
2027	10	060-Mecklenburg	Resurfacing	SR 1929 Cold Harbor Dr	Begin Maint	eom	0.23	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$57,000
2027	10	060-Mecklenburg	Resurfacing	SR 1983 Margo Dr	Sam Wilson Rd	dead end	0.17	Full Depth Patching and 1.25" S9.5B	$32,000
2027	10	060-Mecklenburg	Resurfacing	SR 2126 Arthur Auten Rd	Neck Rd	end of maint	0.87	Full Depth Patching and 1.25" S9.5B	$164,000
2027	10	060-Mecklenburg	Resurfacing	SR 2130 McIlwaine Rd	SR 2128 Beatties Ford Rd	Sr 2138 McCoy Rd	2.43	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$500,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	10	060-Mecklenburg	Resurfacing	SR 2133 Cashion Rd	Beatties Ford Rd	pvmt change	1.27	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$252,000
2027	10	060-Mecklenburg	Resurfacing	SR 2133 Cashion Rd	pvmt change	Gate	0.43	Full Depth Patching and 1.25" S9.5B	$82,000
2027	10	060-Mecklenburg	Resurfacing	SR 2136 Gilead Rd	Bud Henderson / Old Bud Henderson	Beatties Ford Rd	1.56	Full Depth Patching and 1.5" S9.5B	$350,000
2027	10	060-Mecklenburg	Resurfacing	SR 2138 McCoy Rd	SR 2117 Hambright Rd	SR 2136 Gilead Rd	1.66	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$350,000
2027	10	060-Mecklenburg	Resurfacing	SR 2231 Island View Dr	Norman Island dr	Norman Island Dr	0.26	Full Depth Patching and 1.25" S9.5B	$42,000
2027	10	060-Mecklenburg	Resurfacing	SR 2267 Lamesa Pl	Hambright Rd	eom	0.11	Full Depth Patching and 1.25" S9.5B	$23,000
2027	10	060-Mecklenburg	Resurfacing	SR 2426 Huntersville Concord Rd	McAuley Rd	Cabarrus County line	1.60	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$380,000
2027	10	060-Mecklenburg	Resurfacing	SR 2433 Mayes Rd	NC 115	pvmt change	1.01	Full Depth Patching and 1.5" S9.5B	$180,000
2027	10	060-Mecklenburg	Resurfacing	SR 2443 Sims Rd	Huntersville-Concord Rd	SR 2774	0.10	Full Depth Patching and 1.25" S9.5B	$18,000
2027	10	060-Mecklenburg	Resurfacing	SR 2670 Homewood Dr	Breezewood Dr	eom	0.33	Full Depth Patching and 1.25" S9.5B	$60,000
2027	10	060-Mecklenburg	Resurfacing	SR 2774 Sims Rd	Sims Rd	cul de sac	0.33	Full Depth Patching and 1.25" S9.5B	$60,000
2027	10	060-Mecklenburg	Resurfacing	SR 2775 Dori Dr	Sims Rd	cul de sac	0.10	1.25" S9.5B	$18,000
2027	10	060-Mecklenburg	Resurfacing	SR 2799 Cedar Lane	Dogwood Ln	eom	0.11	Mill 1.5" and 1.5" S9.5B	$18,600
2027	10	060-Mecklenburg	Resurfacing	SR 2805 Harrisburg Rd	Starnes Randall rd	end of paint island	0.47	Full Depth Patching and 1.5" S9.5C	$119,000
2027	10	060-Mecklenburg	Resurfacing	SR 2822 Robinson Ch Rd	Plot Rd	Hood Rd	0.64	Full Depth Patching and 1.5" S9.5B	$137,000
2027	10	060-Mecklenburg	Resurfacing	SR 2961 Plaza Park Dr	Plaza Rd Ext	cul de sac	0.24	Mill 1.5" and 1.5" S9.5B	$40,000
2027	10	060-Mecklenburg	Resurfacing	SR 3105 Mcmanus Rd	Cabarrus County line	SR 3118 Ferguson Rd	1.49	Mill 1.25" and 1.25" S9.5B	$200,000
2027	10	060-Mecklenburg	Resurfacing	SR 3106 Brief Rd	Clear Meadow Ln	Union County line	1.35	Full Depth Patching and 1.5" S9.5C	$250,000
2027	10	060-Mecklenburg	Resurfacing	SR 3108 Ira Flowe Rd	SR 3181 Ferguson Rd	SR 3106 Brief Rd	0.50	Full Depth Patching and 1.5" S9.5B	$121,000
2027	10	060-Mecklenburg	Resurfacing	SR 3174 Idlewild Rd	SR 3125 Thompson Rd	Hoods Village Dr	0.52	Full Depth Patching and 1.5" S9.5C	$240,000
2027	10	060-Mecklenburg	Resurfacing	SR 3278 Clear Creek Dr	Old Camden Rd	dead end	0.61	Mill 1.5" and 1.5" S9.5B	$121,000
2027	10	060-Mecklenburg	Resurfacing	SR 3645 Downs Cir	SR 1129 Downs Rd	EOM	0.24	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5B	$175,000
2027	10	060-Mecklenburg	Resurfacing	SR 4154 Plaincrest Rd	Old Camden Rd	Clear Creek Dr	0.38	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$77,000
2027	10	060-Mecklenburg	Resurfacing	SR 4940 Gatestone Ln	SR 4791 Danby Ln	SR 4943 Dansville Dr	0.31	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$49,000
2027	10	060-Mecklenburg	Resurfacing	SR 4941 Cotton Ln	SR 4940 Galestone Ln	Cul de sac	0.05	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$8,850
2027	10	060-Mecklenburg	Resurfacing	SR 4942 Sawthry Ct	SR 4940 Galestone Ln	Cul de sac	0.03	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$5,100
2027	10	060-Mecklenburg	Resurfacing	SR 4943 Dansville Dr	SR 4791 Danby Ln	EOM	0.27	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$44,000
2027	10	060-Mecklenburg	Resurfacing	SR 4944 Baker Mills Rd	SR 4943 Dansville Dr	Cul de sac	0.24	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$41,200
2027	10	060-Mecklenburg	Resurfacing	SR 4945 Wildris Ct	SR 4944 Baker Mills Rd	Cul de sac	0.05	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$8,850
2027	10	060-Mecklenburg	Resurfacing	SR 4946 Seastone Ln	SR 4944 Baker Mills Rd	Cul de sac	0.04	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$7,000
2027	10	060-Mecklenburg	Resurfacing	SR 4982 North Polk Street	I-485	End Divide	0.25	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$135,000
2027	10	060-Mecklenburg	Resurfacing	SR 5394 East Mallard Creek Church Road	University City Boulevard	US 29 North Tryon Street	1.25	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$425,000
2027	10	060-Mecklenburg	Resurfacing	SR 5394 East Mallard Creek Church Road	US 29 North Tryon Street	University City Boulevard	1.25	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$425,000
2027	10	060-Mecklenburg	Resurfacing	SR 5469 Shopton Rd	NC 160	Pleasant Way Ln	1.15	Full Depth Patching and 1.5" S9.5B	$274,000
2027	10	060-Mecklenburg	Resurfacing	US 21	US 21 South	US 21 South	0.51	Mill 1.5" and 1.5" S9.5D	$90,000
2027	10	060-Mecklenburg	Resurfacing	US 21 Statesville Rd	NC 24 West WT Harris Blvd	SR 2116 Alexandriana Rd	1.61	Full Depth Patching and 1.5" S9.5D	$391,000
2027	10	060-Mecklenburg	Resurfacing	US 21 Statesville Rd	SR 2147 Westmoreland Rd	East Catawba Ave	1.38	Mill 1.5" and 1.5" S9.5D	$402,000
2027	10	060-Mecklenburg	Resurfacing	US 521 Johnston Rd	Providence Road West	Brixham Hill Ave	1.13	Mill 1.5" and 1.5" S9.5D	$330,000
2027	10	060-Mecklenburg	Resurfacing	US 74 WB Indepencence Blvd	NC 27	Briar Creek	2.00	Mill 1.5" and 1.5" S9.5D	$722,000
2027	10	060-Mecklenburg	Rehabilitation	SR 3010 Faires Rd	Plaza Rd Ext	EOM	0.44	FDR and 1.5" S9.5B	$143,822
2027	10	060-Mecklenburg	Preservation	SR 1195 Wallace Neel Rd	Old Dowd Rd	SR 5936	2.56	Rejuvenator	$48,300
2027	10	060-Mecklenburg	Preservation	SR 1425 Markswood Rd	NC 160 Steele Creek Rd	EOM	0.67	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$170,000
2027	10	060-Mecklenburg	Preservation	SR 1477 Regena Ln	SR 1104 Thomas Rd	EOM	0.19	Rejuvenator	$3,760
2027	10	060-Mecklenburg	Preservation	SR 1494 Torrence Branch Rd	SR 1104 Thomas Rd	EOM	0.16	Rejuvenator	$3,166
2027	10	060-Mecklenburg	Preservation	SR 1540 Appling Ln	SR 1104 Thomas Rd	EOM	0.38	Rejuvenator	$7,520
2027	10	060-Mecklenburg	Preservation	SR 1561 Sorrel Ct	SR 1540 Appling Ln	SR 1104 Thomas Rd	0.05	Rejuvenator	$990
2027	10	060-Mecklenburg	Preservation	SR 2025 Oakdale Rd	Woodland Circle	Miranda Rd	0.98	Rejuvenator	$23,705
2027	10	060-Mecklenburg	Preservation	SR 2044 Kidd Ln	SR 2074 Beatties Ford Rd	EOM	0.39	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$76,016
2027	10	060-Mecklenburg	Preservation	SR 2163 Hamilton Dr	SR 2074 Beatties Ford Rd	EOM	0.20	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$55,000
2027	10	060-Mecklenburg	Preservation	SR 2197 Catawba Ave	W of Hamilton St	EOM	0.38	Rejuvenator	$6,685
2027	10	060-Mecklenburg	Preservation	SR 2253 Nance Cove Rd	Brookshire BLVD	C&G @ Tallmeadow Ln	0.57	Rejuvenator	$12,534
2027	10	060-Mecklenburg	Preservation	SR 2433 Mayes Rd	SR 2430 Westmoreland	NC 73 Sam Furr Rd	1.12	Rejuvenator	$18,135
2027	10	060-Mecklenburg	Preservation	SR 2442 Ashbury Chapel Rd	SR 2448 Huntersville Concord Rd	SR 2444 Huss McGinnis Rd	1.30	Rejuvenator	$17,540
2027	10	060-Mecklenburg	Preservation	SR 2540 N Graham St	0.03 Mi Prior to Armour Dr	SR 6026 Dalton Ave	0.23	Rejuvenator	$9,862
2027	10	060-Mecklenburg	Preservation	SR 2831 John Russell Rd	SR 2831 Mclean Rd	SR 2828 Rocky River Rd	0.50	Rejuvenator	$13,194
2027	10	060-Mecklenburg	Preservation	SR 3107 Indian Trail Rd	Brief Rd	Union Co Line	0.49	Rejuvenator	$9,697
2027	10	060-Mecklenburg	Preservation	SR 3288 Beckenham Dr	SR 3110 Arlington Church Rd	EOM	0.30	Rejuvenator	$5,937
2027	10	060-Mecklenburg	Preservation	SR 3289 S Hampton Dr	SR 3288 Beckenham Dr	SR 3102 Cabarrus Rd	0.55	Rejuvenator	$10,885
2027	10	060-Mecklenburg	Preservation	SR 3300 East 7th St	Charlottetown Ave	N Laurel Ave	0.90	Rejuvenator	$23,748

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	10	060-Mecklenburg	Preservation	SR 3553 Friendship Dr	SR 101 E John St	SR 3559 Woodstar Rd	0.20	Rejuvenator	$4,398
2027	10	060-Mecklenburg	Preservation	SR 3554 Forrestmont Dr	SR 1010 E John St	SR 1405 Friendship Dr	0.42	Rejuvenator	$9,895
2027	10	060-Mecklenburg	Preservation	SR 3556 Hardwood Pl	SR 3555 Morningwood Dr	SR 3554 Forrestmont Dr	0.10	Rejuvenator	$1,979
2027	10	060-Mecklenburg	Preservation	SR 3557 Pleasantwood Pl	SR 3555 Morningwood Dr	SR 3554 Forrestmont Dr	0.09	Rejuvenator	$1,781
2027	10	060-Mecklenburg	Preservation	SR 3558 Stillwood Pl	SR 3555 Morningwood Dr	SR 3554 Forrestmont Dr	0.08	Rejuvenator	$1,583
2027	10	060-Mecklenburg	Preservation	SR 3559 Woodstar Rd	SR 3555 Morningwood Dr	EOM	0.14	Rejuvenator	$4,156
2027	10	060-Mecklenburg	Preservation	SR 3560 Woodfern Pl	SR 3554 Forrestmont Dr	Union Co Line	0.06	Rejuvenator	$1,187
2027	10	060-Mecklenburg	Preservation	SR 3561 Woodcalm Pl	SR 3554 Forrestmont Dr	Union Co Line	0.04	Rejuvenator	$792
2027	10	060-Mecklenburg	Preservation	SR 3562 Friendship Dr	SR Morningwood Dr	SR 3560 Woodfern Place	0.02	Rejuvenator	$4,618
2027	10	060-Mecklenburg	Preservation	SR 4155 Cumberland/August Ln	SR 3289 S Hampton Dr	SR 3289 S Hampton Dr	0.05	Rejuvenator	$9,499
2027	10	060-Mecklenburg	Preservation	SR 4220 N Hampton Dr	SR 3288 Beckenham Dr	EOM	0.18	Rejuvenator	$3,958
2027	10	060-Mecklenburg	Preservation	SR 4230 Leyton Place	SR 4155 Cumberland Dr	SR 4155 August Ln	0.20	Rejuvenator	$3,958
2027	10	060-Mecklenburg	Preservation	SR 4696 Welland Trail	SR 4670 Starwood Ave	EOM	0.16	Rejuvenator	$3,166
2027	10	060-Mecklenburg	Preservation	SR 4906 Woodside Falls	SR 4982 Lancaster Hwy	eom	0.78	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$156,000
2027	10	060-Mecklenburg	Preservation	SR 4907 Blue Granite road	SR 4906 Woodside Falls	eom	0.10	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$20,000
2027	10	060-Mecklenburg	Preservation	SR 4908 Slate Rd	SR 4906 Woodside Falls	eom	0.03	Rejuvenator	$6,000
2027	10	060-Mecklenburg	Preservation	SR 4909 Emerald Ct	SR 4910 Sapphire Ln	eom	0.11	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$20,000
2027	10	060-Mecklenburg	Preservation	SR 4910 Sapphire Ln	SR 4906 Woodside Falls	eom	0.27	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$54,000
2027	10	060-Mecklenburg	Preservation	SR 4970 Diamond Dr	SR 4910 Sapphire Ln	eom	0.34	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$61,000
2027	10	060-Mecklenburg	Preservation	SR 4971 Peridot	SR 4970 Diamond Dr	eom	0.05	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$9,000
2027	10	060-Mecklenburg	Preservation	SR 4972 Limestone Ln	SR 4906 Woodside Falls	eom	0.13	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$24,000
2027	10	060-Mecklenburg	Preservation	SR 5510 Haymarket	Nance Cove Rd	EOM	0.51	Rejuvenator	$11,215
2027	10	060-Mecklenburg	Preservation	SR 6026 Dalton Ave	N. Graham St	Statesville Ave	0.04	Rejuvenator	$528
2027	10	060-Mecklenburg	Preservation	SR 6026 Dalton Ave	Statesville Ave	N. Graham St	0.04	Rejuvenator	$1,099
2027	10	060-Mecklenburg	Preservation	SR 6026 Dalton Ave	N Graham St	Statesville Ave	0.04	Rejuvenator	$528
2027	10	060-Mecklenburg	Preservation	SR4670 Starwood Ave	SR 1171 The Plaza Ext	EOM	0.13	Rejuvenator	$2,573
2027	10	060-Mecklenburg	Preservation	US 21 Statesville Rd	Lakeview Rd	I-485 Clockwise	2.80	Rejuvenator	$73,570
2027	10	084-Stanly	Resurfacing	NC 24/27	.10 before SR 1216 Smith Grove Rd	End of Divide	1.72	Mill 1.5" and 1.5" S9.5C	$515,834
2027	10	084-Stanly	Resurfacing	NC 24/27	Begin Divide	.10 past SR 1216 Smith Grove Road	1.69	Mill 1.5" and 1.5" S9.5C	$677,856
2027	10	084-Stanly	Resurfacing	NC 740	SR 1650 NE Connector	Catalina Drive	0.56	Mill 1.5" and 1.5" S9.5C	$140,000
2027	10	084-Stanly	Resurfacing	NC 740	Catalina Drive	End of Divide	0.31	Mill 1.5" and 1.5" S9.5C	$75,000
2027	10	084-Stanly	Resurfacing	SR 1130 Big Lick	Pvt Joint at SR 1137 Elm St	NC 200	0.96	1.5" S9.5B	$216,000
2027	10	084-Stanly	Resurfacing	SR 1137 Elm St	NC 200	SR 1130 Big Lick Rd	1.63	1.5" S9.5B and Widen	$579,000
2027	10	084-Stanly	Resurfacing	SR 1638 Old US 52	US 52	Pvt Joint .12 miles East of US 52	0.12	Mill 1.5" and 1.5" S9.5B	$25,000
2027	10	084-Stanly	Resurfacing	SR 1650 NE Connector	NC 740 By Pass	US 52 North	3.42	Mill 1.5" and 1.5" S9.5C	$699,375
2027	10	084-Stanly	Resurfacing	SR 1720 Stony Gap Rd	bridge joint	NC 24/27	1.81	Mill 1.5" and 1.5" S9.5B	$410,000
2027	10	084-Stanly	Resurfacing	SR 1720 Stony Gap Rd	Old US 52	Bridge joint	1.02	Mill 1.5" and 1.5" S9.5B	$225,000
2027	10	084-Stanly	Resurfacing	SR 1760 Allenton St	SR 1740 Pee Dee Ave	SR 1762 Island Cove Rd	0.85	Mill 1.5" and 1.5" S9.5B	$292,200
2027	10	084-Stanly	Resurfacing	SR 1918 Cottonville Rd	SR 1914 Matt-Neal Rd	R 1918 Cottonville Rd (roundabout	1.59	1.5" S9.5B	$283,000
2027	10	084-Stanly	Resurfacing	US 52	SR 1444 Finch Rd	Lavasque	1.04	Mill 1.5" and 1.5" S9.5C	$765,000
2027	10	084-Stanly	Preservation	SR 1107 Silver Rd	SR 1117 Griffin Green Rd	SR 1110 Swift Rd	1.44	Seal - Double	$44,300
2027	10	084-Stanly	Preservation	SR 1208 Barrier Store	SR 1206 Five Point Rd	Cabarrus County line	0.78	Seal - Double	$21,500
2027	10	084-Stanly	Preservation	SR 1209 Lewis Rd	SR 1208 Barrier Store	Cabarrus County line	0.67	Seal - Double	$18,000
2027	10	084-Stanly	Preservation	SR 1225 Old Mill Rd	SR 1227 Ridgecrest Rd	SR 1134 Millingport Rd	2.72	Seal - Double	$67,840
2027	10	084-Stanly	Preservation	SR 1226 Dusty	SR 1227 Ridgecrest Rd	SR 1225 Old Mill Rd	1.17	Seal - Double	$32,000
2027	10	084-Stanly	Preservation	SR 1228 Rowland	SR 1210 Mission Ch	SR 1239 Old Concord	5.87	Seal - Double	$156,911
2027	10	084-Stanly	Preservation	SR 1229 Pole Running	SR 1206 Five Point Rd	SR 1228 Rowland	1.73	Seal - Double	$46,500
2027	10	084-Stanly	Preservation	SR 1230 Pole Running	SR 1228 Rowland	SR 1231 Bridge	0.93	Seal - Double	$32,550
2027	10	084-Stanly	Preservation	SR 1231 Bridge Rd	SR 1232 Lambert Rd	NC 73	2.54	Seal - Double	$80,000
2027	10	084-Stanly	Preservation	SR 1232 Lambert	SR 1231 Bridge Rd	Cabarrus County line	0.99	Seal - Double	$34,650
2027	10	084-Stanly	Preservation	SR 1233 Herrin Grove	SR 1232 Lambert Rd	SR 1231 Bridge Rd	1.23	Seal - Double	$41,339
2027	10	084-Stanly	Preservation	SR 1237 Watson	SR 1236 Old Concord	NC 73	0.15	Seal - Double	$5,250
2027	10	084-Stanly	Preservation	SR 1238 Flint Ridge	SR 1206 Five Point Rd	SR 1236 Old Concord	3.26	Seal - Double	$95,000
2027	10	084-Stanly	Preservation	SR 1239 Biles	SR 1238 Flint Ridge	SR 1134 Milllingport	2.11	Seal - Double	$68,000
2027	10	084-Stanly	Preservation	SR 1240 Fink Rd	SR 1214 Austin Rd	SR 1242 Hatley Farm	2.55	Seal - Double	$83,390
2027	10	084-Stanly	Preservation	SR 1240 Fink Rd	SR 1134 Millingport Rd	SR 1214 Austin Rd	0.70	Seal - Double	$24,500
2027	10	084-Stanly	Preservation	SR 1261 Rutherford	SR 1249 Canton Rd	SR 1262 Parker	0.60	Seal - Double	$21,000
2027	10	084-Stanly	Preservation	SR 1262 Parker	SR 1249 Canton Rd	SR 1240 Fink Rd	1.32	Seal - Double	$46,200
2027	10	084-Stanly	Preservation	SR 1264 Burleson	SR 1249 Canton Rd	SR 1240 Fink Rd	1.74	Seal - Double	$60,900

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	10	084-Stanly	Preservation	SR 1265 Herman	SR 1249 Canton Rd	dead end	0.32	Seal - Double	$12,000
2027	10	084-Stanly	Preservation	SR 1284 Herrin Grove	SR 1232 Lambert Rd	SR 1209 Lewis Rd	1.39	Seal - Double	$30,000
2027	10	084-Stanly	Preservation	SR 1285 April Lane	SR 1249 Canton Rd	SR 1285 Helms Rd	0.60	Seal - Double	$21,000
2027	10	084-Stanly	Preservation	SR 1285 Helms Rd	SR 1285 April Ln	SR 1256 Endy Rd	0.34	Seal - Double	$11,900
2027	10	084-Stanly	Preservation	SR 1287 Helms	SR 1285 April Ln	SR 1256 Endy Rd	0.68	Seal - Double	$23,800
2027	10	084-Stanly	Preservation	SR 1299 Cille	NC 73	dead end	0.41	Seal - Double	$10,250
2027	10	084-Stanly	Preservation	SR 1300 Karen Dr	SR 1301 Hillcrest	SR 1237 Watson	0.08	Seal - Double	$2,000
2027	10	084-Stanly	Preservation	SR 1301 Hilcrest	SR 1239 Old Concord	SR 1300 Karen Dr	0.15	Seal - Double	$3,750
2027	10	084-Stanly	Preservation	SR 1308 Poplar Lane	SR 1299 Cille	SR 1299 Cille	0.42	Seal - Double	$10,500
2027	10	084-Stanly	Preservation	SR 1315 Cecile Ln	SR 1299 Cille	SR 1316 East Lake	0.12	Seal - Double	$3,000
2027	10	084-Stanly	Preservation	SR 2039 Big Bear	SR 1975 St Martin Rd	eom	0.56	Seal - Double	$19,600
2027	10	090-Union	Resurfacing	NC 205	SR 1002 Ansonville Rd	SR 1006 Olive Branch	1.84	1.5" S9.5B	$635,000
2027	10	090-Union	Resurfacing	NC 207	SR 2152 W Sandy Ridge Rd	SR 2150 Joe Collins Rd	1.40	1.5" S9.5B	$326,100
2027	10	090-Union	Resurfacing	NC 75	SR 1157 Fletcher Broome Rd	Pvmt Jt at MP 11.51	0.79	#78 Mat Seal and 2.0" S9.5C	$422,200
2027	10	090-Union	Resurfacing	NC 84	Roundabout	SR 1334 Willoughby Rd	1.94	1.5" S9.5B	$675,000
2027	10	090-Union	Resurfacing	SR 1002 Ansonville Rd	SR 1719 Marshville/Olive Branch Rd	SR 1720 Lanesboro Rd	1.03	1.5" S9.5C	$360,500
2027	10	090-Union	Resurfacing	SR 1006 Olive Branch	SR 1714 Monroe-Olive Branch Rd	SR 1745 Lucy Shortcut Rd	1.71	1.5" S9.5B	$340,000
2027	10	090-Union	Resurfacing	SR 1006 Olive Branch	NC 205	SR 1745 Lucy Shortcut Rd	3.00	1.5" S9.5B	$600,000
2027	10	090-Union	Resurfacing	SR 1007 Rocky River Rd	US 74	SR 1009 Old Charlotte Ave	0.72	1.5" S9.5B	$435,000
2027	10	090-Union	Resurfacing	SR 1131 Nesbit Rd	NC 200 S	SR 1137 Potters Rd	2.53	1.5" S9.5B	$500,000
2027	10	090-Union	Resurfacing	SR 1149 Doster Rd	NC 200 S	SR 1007 Rocky River Rd	2.23	1.5" S9.5B and Widen	$750,000
2027	10	090-Union	Resurfacing	SR 1162 Wesley Chapel	SR 2515 Mollie Irene	NC 84	0.97	1.5" S9.5C	$320,000
2027	10	090-Union	Resurfacing	SR 1318 Lockhaven Rd	NC 16	Hidden Haven Rd	1.04	1.5" S9.5B and Widen	$275,000
2027	10	090-Union	Resurfacing	SR 1365 Stallings Rd	Mecklenburg County line	SR 1524 Steven Mill Rd	0.76	#67 Mat Seal and 1.5" S9.5C and Widen	$425,000
2027	10	090-Union	Resurfacing	SR 1524 Stevens Mill Rd	SR 1365 Stallings Rd	Mecklenburg County line	0.75	1.5" S9.5B	$145,000
2027	10	090-Union	Resurfacing	SR 1525 Millgrove Rd	NC 218	Mecklenburg County line	1.41	1.5" S9.5B and Widen	$575,000
2027	10	090-Union	Resurfacing	SR 1529 Duncan	Unionville Indian Trail	Ridge Road	1.28	1.5" S9.5B	$415,000
2027	10	090-Union	Resurfacing	SR 1570 Allen Way	US 74	eom	0.45	1.5" S9.5B and Widen	$175,000
2027	10	090-Union	Resurfacing	SR 1627 New Salem Rd	NC 200	SR 1633 Rila Hamilton Rd	1.93	2.5" I19.0B and 1.5" S9.5B	$575,000
2027	10	090-Union	Resurfacing	SR 1635 Sincerity Rd	NC 200	SR 1627 New Salem Rd	1.81	Leveling and 1.5" S9.5B	$350,000
2027	10	090-Union	Resurfacing	SR 1658 New Hope Ch Rd	NC 205	SR 1627 New Salem Rd	1.12	1.5" S9.5C and Widen	$308,000
2027	10	090-Union	Resurfacing	SR 1658 New Hope Ch Rd	SR 1627 New Salem Rd	SR 1657 Haigler Gin	1.62	Leveling and 1.25" S9.5B	$490,000
2027	10	090-Union	Resurfacing	SR 1961 Sycamore Grove Rd	SR 1961 Love St	SR 1957 Monroe-Marshville Rd	1.44	1.5" S9.5B and Widen	$525,000
2027	10	090-Union	Resurfacing	SR 2106 Macedonia Ch	SR 2115 Stack Rd	NC 207	1.10	1.5" S9.5C	$375,000
2027	10	090-Union	Resurfacing	SR 2115 Stack Rd	SR 2316 Macidonia Ch Rd	NC 207	1.83	#67 Mat Seal and 2.0" S9.5C	$540,000
2027	10	090-Union	Resurfacing	SR 2394 Gray Fox	US 74	SR 1551 Helmsville Rd	0.96	Mill 1.25" and 1.25" S9.5A	$380,000
2027	10	090-Union	Resurfacing	SR 2976 Antioch Ct	SR 1338 Antioch Ch	EOM	0.21	1.5" S9.5B	$65,000
2027	10	090-Union	Resurfacing	SR 2977 Miner Ln	SR 1338 Antioch Ch Rd	SR 2978 Weddington Oak	0.09	1.5" S9.5B	$30,000
2027	10	090-Union	Resurfacing	SR 2978 Weddington Oaks Dr	SR 1338 Antioch Ch Rd	eom	0.38	1.5" S9.5B	$115,000
2027	10	090-Union	Resurfacing	US 601 N	Pvmt jnt @ bypass	SR 1367 Unionvill IT rd	3.79	Microsurface	$400,000
2027	10	090-Union	Resurfacing	US 601 N	Wilks dr	Pvmt jnt @ bypass	1.38	Microsurface	$130,000
2027	10	090-Union	Resurfacing	US 74 W	SR 1514 Rocky River Rd	SR 1515 Sardis Ch Rd	2.22	#67 Mat Seal and 2.0" S9.5C	$600,000
2027	10	090-Union	Rehabilitation	SR 1914 Zion Church Rd	SR 1915 Smith Town Rd	eom	0.48	FDR and 1.0" S9.5A	$125,000
2027	10	090-Union	Rehabilitation	SR 2552 Porter	Roscoe Howley	EOM	0.83	FDR and 1.0" S9.5A	$175,000
2027	10	090-Union	Preservation	SR 1904 Marsh Rd	SR 1903 Gilboa D	eom	0.99	Seal - Double	$45,000
2027	10	090-Union	Preservation	SR 1907 Griffins Shortcut	SR 1905 High Ridge Ch	SR 1003 White Store	0.85	Seal - Double Mat and Double Seal	$42,300
2027	10	090-Union	Preservation	SR 1908 Jesse Rushing	SR 1005 Landsford	SR 1905 High Ridge Ch	0.66	Seal - Double	$35,000
2027	10	090-Union	Preservation	SR 1909 Hugins Rd	SR1005 Landsford	Anson County line	1.45	Seal - Double	$72,000
2027	10	090-Union	Preservation	SR 1973 J. J. Autry	SR100 Landsford	Dead End	1.07	Seal - Double	$55,500
2027	10	090-Union	Preservation	SR 1983 Flint Ridge Ch	SR 1005 Landsford	eom	0.96	Seal - Double	$55,500
2027	10	090-Union	Preservation	SR 1984 Little Sleep Hollow	SR 1005 Landsford	Orchard Trail	0.92	Seal - Double	$46,000
2027	10	090-Union	Preservation	SR 1985 Shelf Rd	SR 1005 Landsford	SR 1905 High Ridge Ch	1.78	Seal - Double	$85,000
2027	10	090-Union	Preservation	SR 1986 Bivens Howard	SR 1973 J. J. Autry	eom	0.14	Seal - Double	$15,000
2027	10	090-Union	Preservation	SR 2554 Laurel Grove Ln	SR 2523 Homestead Pl	eom	0.24	Seal - Double and Fog Seal	$27,000
2027	10	090-Union	Preservation	SR 2697 Highview Rd	SR 1328 Antioch Ch Rd	SR 2554 Laurel Grove Ln	0.60	Seal - Double and Fog Seal	$120,000
2027	10	090-Union	Preservation	SR 2698 Ranch View Ct	SR 2697 Highview Rd	eom	0.14	Seal - Double and Fog Seal	$50,000
2027	10	090-Union	Preservation	SR 2699 High Vista	SR 2698 Ranch View Ct	eom	0.07	Seal - Double and Fog Seal	$15,000
2027	10	090-Union	Preservation	SR 2800 Valley View Ct	SR 2697 Highview Rd	eom	0.06	Seal - Double and Fog Seal	$13,500
2027	10	090-Union	Preservation	SR 2801 Long View Ct	SR 2697 Highview Rd	eom	0.10	Seal - Double and Fog Seal	$12,750

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	10	090-Union	Preservation	SR 2807 Weddington Downs	SR 3146 Beauth Ch Rd	eom	0.46	Seal - Double and Fog Seal	$37,200
2027	10	090-Union	Preservation	SR 2808 Eagle Pass Ct	SR 2807 Weddington Downs	eom	0.06	Seal - Double and Fog Seal	$4,000
2027	10	090-Union	Preservation	SR 2809 Tall Oaks	SR 2807 Weddington Downs	eom	0.05	Seal - Double and Fog Seal	$5,500
2027	10	090-Union	Preservation	SR 2954 Rising Sun Ln	SR 2523 Homestead Pl	eom	0.26	Seal - Double and Fog Seal	$21,000
2027	10	090-Union	Preservation	SR 2976 Antioch Ct	SR 1338 Antioch Ch Rd	eom	0.21	Seal - Double and Fog Seal	$20,000
2027	10	090-Union	Preservation	SR 2977 Miner Ln	SR 1338 Antioch Ch Rd	SR 2978 Weddington Oak	0.09	Seal - Double and Fog Seal	$10,000
2027	10	090-Union	Preservation	SR 2978 Weddington Oaks Dr	SR 1338 Antioch Ch Rd	eom	0.38	Seal - Double and Fog Seal	$28,000
2027	11	003-Alleghany	Resurfacing	SR 1135	US 21	SR 1164/End of Pavement	2.15	Leveling and 1.5" S9.5B	$756,800
2027	11	003-Alleghany	Resurfacing	SR 1321	NC 113	SR 1325	1.36	Leveling and 1.5" S9.5B	$478,720
2027	11	003-Alleghany	Resurfacing	SR 1322	SR 1321	NC 113	0.08	Leveling and 1.5" S9.5B	$25,340
2027	11	003-Alleghany	Resurfacing	SR 1467	SR 1444	US 21	0.93	1.5" S9.5B	$294,620
2027	11	003-Alleghany	Preservation	SR 1135	SR 1139	NC 18	2.05	Seal - Mat and Triple Seal	$173,180
2027	11	003-Alleghany	Preservation	SR 1135	BEG PVMT	SR 1139	0.70	Seal - Triple and Fog Seal	$65,700
2027	11	003-Alleghany	Preservation	SR 1163	SR 1168	SR 1164	1.86	Seal - Triple and Fog Seal	$157,470
2027	11	003-Alleghany	Preservation	SR 1164	SR 1163	SR 1135	0.46	Seal - Triple and Fog Seal	$43,180
2027	11	003-Alleghany	Preservation	SR 1167	US 221	SR 1168	1.13	Seal - Triple and Fog Seal	$95,460
2027	11	003-Alleghany	Preservation	SR 1168	SR 1167	SR 1163	0.67	Seal - Triple and Fog Seal	$56,600
2027	11	005-Ashe	Resurfacing	SR 1112	SR 1114	SR 1110	1.56	1.5" S9.5B	$494,208
2027	11	005-Ashe	Resurfacing	SR 1133	SR 1134	END Pavement	1.61	1.5" S9.5B	$566,720
2027	11	005-Ashe	Resurfacing	SR 1135	SR 1133	END Maintenance	0.55	1.5" S9.5B	$193,600
2027	11	005-Ashe	Resurfacing	SR 1137	SR 1248	SR 1133	1.20	1.5" S9.5B	$380,160
2027	11	005-Ashe	Resurfacing	SR 1207	US 221	EOM	0.50	1.5" S9.5B	$140,800
2027	11	005-Ashe	Resurfacing	SR 1244	SR 1248	SR 1244	0.43	1.5" S9.5B	$136,224
2027	11	005-Ashe	Resurfacing	SR 1272	WIDTH CHANGE	EOM	0.23	1.5" S9.5B	$64,768
2027	11	005-Ashe	Resurfacing	SR 1272	US 221	WIDTH CHANGE	0.04	1.5" S9.5B	$18,586
2027	11	005-Ashe	Resurfacing	SR 1276	SR 1272	EOP	0.09	1.5" S9.5B	$25,344
2027	11	005-Ashe	Resurfacing	SR 1280	SR 1244	CUL-DE-SAC	0.26	1.5" S9.5B	$82,368
2027	11	005-Ashe	Resurfacing	SR 1324	SR 1334	SR 1352	2.10	1.5" S9.5B	$591,360
2027	11	005-Ashe	Resurfacing	SR 1324	SR 1352	SR 1353	0.21	1.5" S9.5B	$73,920
2027	11	005-Ashe	Resurfacing	SR 1366	SR 1362	SR 1353	0.31	1.5" S9.5B	$109,120
2027	11	005-Ashe	Preservation	SR 1348	SR 1347	EOM	0.71	Seal - Triple and Fog Seal	$59,981
2027	11	005-Ashe	Preservation	SR 1349	SR 1347	NC 194	1.15	Seal - Triple and Fog Seal	$107,947
2027	11	005-Ashe	Preservation	SR 1373	NC 194	SR 1374	0.51	Seal - Triple and Fog Seal	$47,872
2027	11	005-Ashe	Preservation	SR 1375	NC 194	EOM	1.28	Seal - Triple and Fog Seal	$108,134
2027	11	005-Ashe	Preservation	SR 1380	NC 194	END Maintenance	0.25	Seal - Triple and Fog Seal	$18,773
2027	11	005-Ashe	Preservation	SR 1508	NC 88	END PVMT	1.24	Seal - Triple and Fog Seal	$104,755
2027	11	005-Ashe	Preservation	SR 1598	NC 88	SR 1595	0.88	Seal - Triple and Fog Seal	$74,342
2027	11	005-Ashe	Preservation	SR 1609	SR 1612	BRIDGE	0.72	Seal - Triple and Fog Seal	$60,826
2027	11	005-Ashe	Preservation	SR 1609	BEG PVMT	NC 88	0.25	Seal - Triple and Fog Seal	$21,120
2027	11	005-Ashe	Preservation	SR 1612	SR 1609	NC 88	1.23	Seal - Triple and Fog Seal	$115,456
2027	11	005-Ashe	Preservation	SR 1634	NC 16	END Maintenance	0.40	Seal - Triple and Fog Seal	$33,792
2027	11	005-Ashe	Preservation	SR 1665	SR 1595	END Maintenance	0.20	Seal - Triple and Fog Seal	$15,019
2027	11	005-Ashe	Preservation	SR 1675	NC 16	EOM	0.51	Seal - Triple and Fog Seal	$38,298
2027	11	005-Ashe	Preservation	SR 1676	SR 1580	End Maintenance	0.12	Seal - Triple and Fog Seal	$9,011
2027	11	005-Ashe	Preservation	SR 1677	SR 1511	EOM	0.09	Seal - Triple and Fog Seal	$6,758
2027	11	005-Ashe	Preservation	SR 1678	SR 1501	END Maintenance	0.37	Seal - Triple and Fog Seal	$34,731
2027	11	005-Ashe	Preservation	SR 1679	SR 1580	END PVMT	0.30	Seal - Triple and Fog Seal	$22,528
2027	11	006-Avery	Resurfacing	SR 1106	US 19 E	NC 194	1.17	1.5" S9.5B	$370,650
2027	11	006-Avery	Resurfacing	SR 1163	SR 1157	EOP	1.55	1.5" S9.5B	$491,040
2027	11	006-Avery	Resurfacing	SR 1166	US19E	EOM	2.16	1.5" S9.5B	$608,540
2027	11	006-Avery	Resurfacing	SR 1170	US 19E	EOM	0.75	1.5" S9.5B	$224,400
2027	11	006-Avery	Resurfacing	SR 1310	BEGIN PAVEMENT	SR 1308	0.68	1.5" S9.5B	$216,690
2027	11	006-Avery	Resurfacing	SR 1326	NC 194	EOM	0.50	1.5" S9.5B	$140,800
2027	11	006-Avery	Resurfacing	SR 1370	NC 181	SR 1500	0.53	1.5" S9.5B	$186,560
2027	11	006-Avery	Resurfacing	SR 1500	BOP	NC 194	0.71	1.5" S9.5B	$249,920
2027	11	006-Avery	Resurfacing	SR 1521	NC 181	DE	0.20	1.5" S9.5B	$57,450
2027	11	006-Avery	Preservation	SR 1312	SR 1314	SR 1316	3.46	Seal - Triple and Fog Seal	$276,060
2027	11	014-Caldwell	Resurfacing	NC 90	SR 1354	SR 1353	3.26	Mill 1.5" and 1.5" S9.5C	$1,090,140
2027	11	014-Caldwell	Resurfacing	SR 1115	SR 1205	SR 1001	2.33	1.5" S9.5B	$738,144

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	11	014-Caldwell	Resurfacing	SR 1511	SR 1605	SR 1545	2.03	1.5" S9.5B	$571,650
2027	11	014-Caldwell	Resurfacing	SR 1511	SR 1545	SR 1523	1.83	1.5" S9.5B	$611,950
2027	11	014-Caldwell	Resurfacing	SR 1545	SR 1511	SR 1548	1.81	1.5" S9.5B	$573,408
2027	11	014-Caldwell	Resurfacing	SR 1712	SR 1723	SR 1719	3.70	1.5" S9.5B	$1,302,400
2027	11	014-Caldwell	Resurfacing	SR 1734	SR 1002	US 64	3.19	1.5" S9.5B	$1,122,880
2027	11	014-Caldwell	Preservation	SR 1210	SR 1001	SR 1001	0.46	Seal - Triple and Fog Seal	$43,179
2027	11	014-Caldwell	Preservation	SR 1507	NC 268	SR 1556	1.40	Seal - Triple and Fog Seal	$131,413
2027	11	014-Caldwell	Preservation	SR 1520	SR 1513	EOM	0.22	Seal - Triple and Fog Seal	$16,521
2027	11	014-Caldwell	Preservation	SR 1523	PVT CHANGE	MP 1.83	0.68	Seal - Triple and Fog Seal	$63,829
2027	11	014-Caldwell	Preservation	SR 1604	SR 1513	CUL-DE-SAC	0.67	Seal - Triple and Fog Seal	$56,602
2027	11	014-Caldwell	Preservation	SR 1606	NC 268	CUL-DE-SAC	0.31	Seal - Triple and Fog Seal	$23,279
2027	11	014-Caldwell	Preservation	SR 1727	SR 1726	EOM	0.91	Seal - Triple and Fog Seal	$85,419
2027	11	014-Caldwell	Preservation	SR 1743	SR 1744	SR 1741	1.15	Seal - Triple and Fog Seal	$107,947
2027	11	014-Caldwell	Preservation	SR 1749	SR 1751	SR 1748	1.62	Seal - Triple and Fog Seal	$136,858
2027	11	014-Caldwell	Preservation	SR 1754	Meandering Way (NS)	EOM	0.72	Seal - Triple and Fog Seal	$60,826
2027	11	014-Caldwell	Preservation	SR 1757	Tornado Cir (NS)	Savannah DR (NS)	0.66	Seal - Triple and Fog Seal	$61,952
2027	11	014-Caldwell	Preservation	SR 1792	SR 1716	EOM	0.72	Seal - Triple and Fog Seal	$60,826
2027	11	014-Caldwell	Preservation	SR 1801	US 64	EOM	0.45	Seal - Triple and Fog Seal	$38,016
2027	11	086-Surry	Resurfacing	NC 268 BUS	SR 1144	NC 268	4.35	1.5" S9.5C	$1,607,760
2027	11	086-Surry	Resurfacing	NC 89	urfacing joint at beginning of left turn lane tapeı	SR 1685	2.84	1.5" S9.5B	$999,680
2027	11	086-Surry	Resurfacing	SR 1133	US 21	SR 1001	1.54	1.5" S9.5B	$542,080
2027	11	086-Surry	Resurfacing	SR 1315	SR 1001	WILKES CO	5.58	1.5" S9.5B	$1,816,883
2027	11	086-Surry	Resurfacing	SR 1708	SR 1701	NC 104	1.60	1.5" S9.5B	$506,880
2027	11	086-Surry	Preservation	SR 1106	SR 1105	SR 1110	1.19	Seal - Triple and Fog Seal	$100,531
2027	11	086-Surry	Preservation	SR 1183	SR 1161	EOM	0.30	Seal - Triple and Fog Seal	$22,528
2027	11	086-Surry	Preservation	SR 1360	SR 1359	CUL-DE-SAC	0.49	Seal - Triple and Fog Seal	$41,395
2027	11	086-Surry	Preservation	SR 1380	SR 1394	SR 1379	0.38	Seal - Triple and Fog Seal	$32,102
2027	11	086-Surry	Preservation	SR 1405	SR 1331	CUL-DE-SAC	1.51	Seal - Triple and Fog Seal	$141,739
2027	11	086-Surry	Preservation	SR 1447	SR 1378	END MAINT	0.20	Seal - Triple and Fog Seal	$18,773
2027	11	086-Surry	Preservation	SR 1453	SR 1378	EOM	0.20	Seal - Triple and Fog Seal	$18,773
2027	11	086-Surry	Preservation	SR 1454	SR 1350	Cul-De-Sac	0.23	Seal - Triple and Fog Seal	$19,008
2027	11	086-Surry	Preservation	SR 1464	SR 1378	EOM	0.11	Seal - Triple and Fog Seal	$10,325
2027	11	086-Surry	Preservation	SR 1530	SR 1326	SR 1516	0.39	Seal - Triple and Fog Seal	$29,286
2027	11	086-Surry	Preservation	SR 1531	SR 1504	EOM	0.18	Seal - Triple and Fog Seal	$16,896
2027	11	086-Surry	Preservation	SR 1536	SR 1504	EOM	0.21	Seal - Triple and Fog Seal	$19,712
2027	11	086-Surry	Preservation	SR 1537	SR 1536	DEAD END	0.26	Seal - Triple and Fog Seal	$24,405
2027	11	086-Surry	Preservation	SR 1538	SR 1537	DEAD END	0.08	Seal - Triple and Fog Seal	$7,509
2027	11	086-Surry	Preservation	SR 1551	US 21	CUL-DE-SAC	0.38	Seal - Triple and Fog Seal	$35,669
2027	11	086-Surry	Preservation	SR 1619	SR 1618	EOM	1.00	Seal - Triple and Fog Seal	$84,480
2027	11	086-Surry	Preservation	SR 1672	SR 1618	SR 2431	0.21	Seal - Triple and Fog Seal	$19,712
2027	11	086-Surry	Preservation	SR 1768	NC 89	SR 1766	0.16	Seal - Triple and Fog Seal	$15,019
2027	11	086-Surry	Preservation	SR 1773	US 52	US 52 BUS	0.22	Seal - Triple and Fog Seal	$24,781
2027	11	086-Surry	Preservation	SR 1783	SR 1780	CUL-DE-SAC	0.30	Seal - Triple and Fog Seal	$22,528
2027	11	086-Surry	Preservation	SR 1818	SR 1774	SR 1774	1.32	Seal - Triple and Fog Seal	$123,904
2027	11	086-Surry	Preservation	SR 1819	SR 1876	SR 1815	0.35	Seal - Triple and Fog Seal	$32,853
2027	11	086-Surry	Preservation	SR 1843	SR 1703	EOM	0.02	Seal - Triple and Fog Seal	$1,690
2027	11	086-Surry	Preservation	SR 1846	NC 103	EOM	0.38	Seal - Triple and Fog Seal	$28,536
2027	11	086-Surry	Preservation	SR 1862	SR 1702	DE	0.60	Seal - Triple and Fog Seal	$56,320
2027	11	086-Surry	Preservation	SR 1876	SR 1819	END MAINT	0.39	Seal - Triple and Fog Seal	$36,608
2027	11	086-Surry	Preservation	SR 1884	SR 1842	DE	0.21	Seal - Triple and Fog Seal	$19,524
2027	11	086-Surry	Preservation	SR 1907	SR 1742	SR 1908	0.16	Seal - Triple and Fog Seal	$15,019
2027	11	086-Surry	Preservation	SR 1908	SR 1742	SR 1907	0.16	Seal - Triple and Fog Seal	$15,019
2027	11	086-Surry	Preservation	SR 1928	SR 1939	CUL-DE-SAC	0.40	Seal - Triple and Fog Seal	$37,547
2027	11	086-Surry	Preservation	SR 1929	SR 1928	CUL-DE-SAC	0.11	Seal - Triple and Fog Seal	$10,325
2027	11	086-Surry	Preservation	SR 1938	SR 1928	SR 1742	0.17	Seal - Triple and Fog Seal	$15,957
2027	11	086-Surry	Preservation	SR 1939	SR 1742	SR 1940	0.30	Seal - Triple and Fog Seal	$28,160
2027	11	086-Surry	Preservation	SR 1940	CUL-DE-SAC	CUL-DE-SAC	0.33	Seal - Triple and Fog Seal	$30,976
2027	11	086-Surry	Preservation	SR 1941	SR 1940	SR 1942	0.12	Seal - Triple and Fog Seal	$11,170
2027	11	086-Surry	Preservation	SR 1942	SR 1941	CUL-DE-SAC	0.45	Seal - Triple and Fog Seal	$42,240

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	11	086-Surry	Preservation	SR 1943	SR 1942	DEAD END	0.13	Seal - Triple and Fog Seal	$12,203
2027	11	086-Surry	Preservation	SR 1944	SR 1942	CUL-DE-SAC	0.09	Seal - Triple and Fog Seal	$8,448
2027	11	086-Surry	Preservation	SR 1954	SR 1928	CUL-DE-SAC	0.07	Seal - Triple and Fog Seal	$6,571
2027	11	086-Surry	Preservation	SR 2033	SR 2019	BRIDGE	1.05	Seal - Triple and Fog Seal	$88,704
2027	11	086-Surry	Preservation	SR 2038	SR 1003	SR 2230	1.27	Seal - Triple and Fog Seal	$119,211
2027	11	086-Surry	Preservation	SR 2047	NC 268	SR 2048	2.08	Seal - Triple and Fog Seal	$175,718
2027	11	095-Watauga	Resurfacing	NC 105	SR 1594	Northern intersection of SR 1568	3.97	1.5" S9.5C	$1,865,809
2027	11	095-Watauga	Resurfacing	SR 1233	SR 1306	US 421	4.42	1.5" S9.5B	$1,555,136
2027	11	095-Watauga	Resurfacing	SR 1401	US 221	SR 1328	0.19	1.5" S9.5B	$73,570
2027	11	095-Watauga	Resurfacing	SR 1510	SR 1514	SR 1511	0.19	1.5" S9.5B	$66,880
2027	11	095-Watauga	Preservation	SR 1106	SR 1105	SR 1107	0.06	Seal - Triple and Fog Seal	$5,069
2027	11	095-Watauga	Preservation	SR 1114	SR 1112	SR 1113	1.63	Seal - Triple and Fog Seal	$137,702
2027	11	095-Watauga	Preservation	SR 1140	SR 1113	EOM	0.97	Seal - Triple and Fog Seal	$81,945
2027	11	095-Watauga	Preservation	SR 1230	SR 1233	END Maintenance	0.15	Seal - Triple and Fog Seal	$11,968
2027	11	095-Watauga	Preservation	SR 1242	SR 1213	END Maintenance	0.06	Seal - Triple and Fog Seal	$3,942
2027	11	095-Watauga	Preservation	SR 1305	SR 1233	EOM	1.10	Seal - Triple and Fog Seal	$92,928
2027	11	095-Watauga	Preservation	SR 1365	SR 1305	SR 1306	0.84	Seal - Triple and Fog Seal	$70,963
2027	11	095-Watauga	Preservation	SR 1559	SR 1560	NC 105	0.72	Seal - Triple and Fog Seal	$67,584
2027	11	095-Watauga	Preservation	SR 1560	SR 1559	EOM	0.70	Seal - Triple and Fog Seal	$59,136
2027	11	095-Watauga	Preservation	SR 1598	NC 105	END Maintenance	0.39	Seal - Triple and Fog Seal	$29,512
2027	11	095-Watauga	Preservation	SR 1601	SR 1513	EOM	0.20	Seal - Triple and Fog Seal	$16,896
2027	11	095-Watauga	Preservation	SR 1617	SR 1541	PVMNT Change	0.26	Seal - Triple and Fog Seal	$21,965
2027	11	095-Watauga	Preservation	SR 1646	SR 1645	EOM	0.31	Seal - Triple and Fog Seal	$26,189
2027	11	095-Watauga	Preservation	SR 1656	SR 1524	EOM	0.25	Seal - Triple and Fog Seal	$21,120
2027	11	095-Watauga	Preservation	SR 1661	SR 1657	EOM	0.05	Seal - Triple and Fog Seal	$4,224
2027	11	095-Watauga	Preservation	SR 1669	SR 1663	EOM	0.10	Seal - Triple and Fog Seal	$8,448
2027	11	097-Wilkes	Resurfacing	NC 18	SR 1125	n Widening for Lt Turn Lane at SR 1	5.01	Full Depth Patching and 1.5" S9.5C	$2,557,104
2027	11	097-Wilkes	Resurfacing	RMP 2565	NC 115	US 421 SB	0.18	Mill 1.5" and 1.5" S9.5C	$69,695
2027	11	097-Wilkes	Resurfacing	RMP 2567	US 421 SB	NC 115	0.32	Mill 1.5" and 1.5" S9.5C	$123,904
2027	11	097-Wilkes	Resurfacing	RMP 2570	US 421 NB	SR 2355	0.24	Mill 1.5" and 1.5" S9.5C	$92,930
2027	11	097-Wilkes	Resurfacing	RMP 2571	SR 2355	US 421 NB	0.24	Mill 1.5" and 1.5" S9.5C	$92,930
2027	11	097-Wilkes	Resurfacing	RMP 5908	SR 2325	US 421 NB	0.37	Mill 1.5" and 1.5" S9.5C	$143,264
2027	11	097-Wilkes	Resurfacing	SR 1540	SR 1315	SR 1541	0.93	1.5" S9.5B	$327,360
2027	11	097-Wilkes	Resurfacing	US 421 NB	BR # 759 Over SR 2325	End of US 421 NB On Rmp	1.80	Mill 1.5" and 1.5" S9.5C	$950,400
2027	11	097-Wilkes	Resurfacing	US 421 SB	End SR 1001 SB On Ramp	New Rt Turn Lane for NWS Parking	3.51	Mill 1.5" and 1.5" S9.5C	$1,902,419
2027	11	097-Wilkes	Preservation	SR 1567	Bridge # 0373	SR 1575	0.59	Seal - Triple and Fog Seal	$49,843
2027	11	097-Wilkes	Preservation	SR 1567	Begin Pvmt	SR 1569	1.96	Seal - Triple and Fog Seal	$165,834
2027	11	097-Wilkes	Preservation	SR 1567	SR 1575	SR 1570	1.01	Seal - Triple and Fog Seal	$95,181
2027	11	097-Wilkes	Preservation	SR 1570	Pvmt Change	SR 1567	1.85	Seal - Triple and Fog Seal	$156,288
2027	11	097-Wilkes	Preservation	SR 1570	SR 1571	Pvmt Change	2.41	Seal - Triple and Fog Seal	$203,597
2027	11	097-Wilkes	Preservation	SR 1570	Begin Pvmt	SR 1571	1.91	Seal - Triple and Fog Seal	$161,357
2027	11	097-Wilkes	Preservation	SR 1570	NC 18	End Pvmt	2.12	Seal - Triple and Fog Seal	$198,997
2027	11	097-Wilkes	Preservation	SR 1572	SR 1570	End Pvmt	1.71	Seal - Triple and Fog Seal	$144,461
2027	11	097-Wilkes	Preservation	SR 1577	SR 1315	EOM	0.37	Seal - Triple and Fog Seal	$31,258
2027	11	097-Wilkes	Preservation	SR 1597	SR 1566	EOM	0.89	Seal - Triple and Fog Seal	$75,187
2027	11	097-Wilkes	Preservation	SR 1598	SR 1577	EOM	0.12	Seal - Triple and Fog Seal	$10,138
2027	11	097-Wilkes	Preservation	SR 1599	SR 1577	EOM	0.05	Seal - Triple and Fog Seal	$4,224
2027	11	097-Wilkes	Preservation	SR 1924	SR 1917	SR 1752	0.41	Seal - Triple and Fog Seal	$34,637
2027	11	097-Wilkes	Preservation	SR 1934	SR 1999	SR 2014	3.36	Seal - Triple and Fog Seal	$283,853
2027	11	099-Yadkin	Resurfacing	SR 1538	SR 1541	SR 1537	2.10	Full Depth Patching and 1.5" S9.5C	$739,200
2027	11	099-Yadkin	Resurfacing	SR 1538	SR 1537	SR 1645	2.47	Full Depth Patching and 1.5" S9.5C	$869,440
2027	11	099-Yadkin	Resurfacing	US 21	IREDELL CO	.06 mi South of SR 1314	5.28	Full Depth Patching and 1.5" S9.5C	$2,093,549
2027	11	099-Yadkin	Preservation	SR 1110	SR 1217	SR 1217	0.28	Seal - Triple and Fog Seal	$23,654
2027	11	099-Yadkin	Preservation	SR 1137	SR 1314	CUL-DE-SAC	0.19	Seal - Triple and Fog Seal	$16,051
2027	11	099-Yadkin	Preservation	SR 1166	SR 1153	SR 1002	1.58	Seal - Triple and Fog Seal	$133,478
2027	11	099-Yadkin	Preservation	SR 1184	SR 1171	END MAINT	0.28	Seal - Triple and Fog Seal	$21,026
2027	11	099-Yadkin	Preservation	SR 1214	SR 1133	END MAINT	0.45	Seal - Triple and Fog Seal	$38,016
2027	11	099-Yadkin	Preservation	SR 1385	SR 1331	EOM	0.66	Seal - Triple and Fog Seal	$55,757
2027	11	099-Yadkin	Preservation	SR 1397	SR 1331	CDS	0.30	Seal - Triple and Fog Seal	$25,344

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	11	099-Yadkin	Preservation	SR 1400	SR 1325	EOM	0.60	Seal - Triple and Fog Seal	$50,688
2027	11	099-Yadkin	Preservation	SR 1550	SR 1545	SR 1552	1.77	Seal - Triple and Fog Seal	$166,144
2027	11	099-Yadkin	Preservation	SR 1552	SR 1554	END Maintenance	1.60	Seal - Triple and Fog Seal	$150,187
2027	11	099-Yadkin	Preservation	SR 1552	SR 1550	SR 1554	0.64	Seal - Triple and Fog Seal	$48,060
2027	11	099-Yadkin	Preservation	SR 1557	SR 1556	NC 67	0.71	Seal - Triple and Fog Seal	$66,645
2027	12	002-Alexander	Resurfacing	NC 90	NC 16	SR 1543	1.80	1.5" S9.5B	$591,000
2027	12	002-Alexander	Resurfacing	SR 1001	SR 1458	Wilkes County Line	6.25	1.5" S9.5B	$871,932
2027	12	002-Alexander	Resurfacing	SR 1124	Cul de sac	US 64	8.34	1.5" S9.5C	$1,268,136
2027	12	002-Alexander	Resurfacing	SR 1207	SR 1159	Dead End	0.14	1.0" S9.5B	$19,180
2027	12	002-Alexander	Resurfacing	SR 1255	SR 1144	Dead End	0.07	1.0" S9.5B	$9,100
2027	12	002-Alexander	Resurfacing	SR 1428	SR 1429	DEAD END	0.47	1.5" S9.5B	$65,109
2027	12	002-Alexander	Resurfacing	SR 1446	SR 1001	Iredell County Line	2.29	1.5" S9.5B	$319,690
2027	12	002-Alexander	Resurfacing	SR 1477	SR 1456	Dead End	0.20	1.0" S9.5B	$28,000
2027	12	002-Alexander	Resurfacing	SR 1533	SR 1415	SR 1533	0.48	1.0" S9.5B	$67,760
2027	12	002-Alexander	Resurfacing	SR 1546	SR 1533	Dead End	0.36	1.0" S9.5B	$50,540
2027	12	002-Alexander	Resurfacing	SR 1572	SR 1425	Dead End	0.29	1.0" S9.5B	$40,460
2027	12	002-Alexander	Resurfacing	SR 1575	SR 1546	SR 1546	0.23	1.0" S9.5B	$31,780
2027	12	002-Alexander	Resurfacing	SR 1613	SR 1605	SR 1610	1.64	1.5" S9.5B	$205,156
2027	12	002-Alexander	Resurfacing	SR 1800	SR 1149	Cul De Sac	0.08	1.0" S9.5B	$10,500
2027	12	002-Alexander	Resurfacing	SR 1823	SR 1255	Cul De Sac	0.08	1.0" S9.5B	$10,500
2027	12	002-Alexander	Resurfacing	SR 1826	SR 1148	Cul De Sac	0.12	1.0" S9.5B	$16,520
2027	12	002-Alexander	Resurfacing	SR 1836	SR 1835	Cul De Sac	0.21	1.0" S9.5B	$29,960
2027	12	002-Alexander	Resurfacing	SR 1847	SR 1148	Dead End	0.19	1.0" S9.5B	$27,160
2027	12	002-Alexander	Resurfacing	SR 1869	SR 1124	Cul De Sac	0.20	1.0" S9.5B	$27,860
2027	12	002-Alexander	Resurfacing	SR 1903	SR 1604	Dead End	0.09	1.0" S9.5B	$13,160
2027	12	002-Alexander	Resurfacing	SR 1912	SR 1605	Dead End	0.05	1.0" S9.5B	$7,560
2027	12	002-Alexander	Resurfacing	US 64	SR 1005	Iredell County Line	3.98	Mill 2.0" and 2.0" S9.5C	$1,290,000
2027	12	002-Alexander	Preservation	SR 1221	SR 1124	DEAD END	1.44	Seal - Double and Fog Seal	$50,330
2027	12	002-Alexander	Preservation	SR 1415	SR 1409	SR 1412	1.67	Seal - Double and Fog Seal	$58,450
2027	12	002-Alexander	Preservation	SR 1416	SR 1412	End of Maint.	0.70	Seal - Double and Fog Seal	$24,500
2027	12	002-Alexander	Preservation	SR 1417	SR 1412	SR 1425	0.94	Seal - Double and Fog Seal	$32,900
2027	12	002-Alexander	Preservation	SR 1433	SR 1435	SR 1403	0.96	Seal - Double and Fog Seal	$33,600
2027	12	002-Alexander	Preservation	SR 1435	SR 1433	Wilkes Co. Line	1.32	Seal - Double and Fog Seal	$46,200
2027	12	002-Alexander	Preservation	SR 1443	SR 1001	SR 1001 (Plus 0.30 Miles)	0.30	Seal - Double and Fog Seal	$10,500
2027	12	002-Alexander	Preservation	SR 1447	SR 1449	SR 1454	1.48	Seal - Double and Fog Seal	$51,800
2027	12	002-Alexander	Preservation	SR 1449	SR 1447	SR 1450	0.59	Seal - Double and Fog Seal	$20,650
2027	12	002-Alexander	Preservation	SR 1449	SR 1450	Iredell County Line	0.29	Seal - Double and Fog Seal	$10,150
2027	12	002-Alexander	Preservation	SR 1453	Alexander Co. Line	SR 1462	1.24	Seal - Double and Fog Seal	$43,400
2027	12	002-Alexander	Preservation	SR 1453	SR 1463	SR 1456	1.06	Seal - Double and Fog Seal	$37,450
2027	12	002-Alexander	Preservation	SR 1463	SR 1453	SR 1462	1.46	Seal - Double and Fog Seal	$51,100
2027	12	002-Alexander	Preservation	SR 1466	SR 1462	SR 1461	1.20	Seal - Double and Fog Seal	$42,000
2027	12	002-Alexander	Preservation	SR 1467	SR 1461	Iredell County Line	1.00	Seal - Double	$35,000
2027	12	002-Alexander	Preservation	SR 1469	SR 1456	SR 1467	1.49	Seal - Double and Fog Seal	$52,150
2027	12	002-Alexander	Preservation	SR 1471	SR 1472 (Plus 0.71 Miles)	SR 1469 (Minus 0.10 Miles)	0.10	Seal - Double and Fog Seal	$3,500
2027	12	002-Alexander	Preservation	SR 1473	SR 1474	SR 1456	1.44	Seal - Double and Fog Seal	$50,050
2027	12	002-Alexander	Preservation	SR 1473	SR 1472	SR 1475	1.62	Seal - Double and Fog Seal	$56,700
2027	12	002-Alexander	Preservation	SR 1474	SR 1473	Iredell County Line	0.93	Seal - Double and Fog Seal	$32,550
2027	12	002-Alexander	Preservation	SR 1475	SR 1456	SR 1473	0.81	Seal - Double and Fog Seal	$28,350
2027	12	002-Alexander	Preservation	SR 1555	SR 1447	Dead End	0.92	Seal - Double and Fog Seal	$32,200
2027	12	002-Alexander	Preservation	SR 1630	SR 1626	SR 1610	3.52	Seal - Double	$123,095
2027	12	002-Alexander	Preservation	SR 1639	SR 1604	SR 1613	0.76	Seal - Double	$26,460
2027	12	018-Catawba	Resurfacing	NC 10	NC 16 BUS	SR 1722	11.46	Full Depth Patching and 1.5" S9.5C	$2,292,000
2027	12	018-Catawba	Resurfacing	SR 1709	SR 2429	I 40	4.89	1.5" S9.5B	$953,940
2027	12	018-Catawba	Resurfacing	SR 1709	SR 1006	SR 2429	1.27	1.5" S9.5B	$248,040
2027	12	018-Catawba	Resurfacing	SR 1806	SR 1802	SR 1801	1.81	Full Depth Patching and 1.5" S9.5B	$352,950
2027	12	018-Catawba	Resurfacing	SR 1838	MP 2.00	SR 1838	1.65	1.25" SF9.5A	$322,140
2027	12	018-Catawba	Resurfacing	SR 1838	SR 1848	MP 2.00	2.00	Full Depth Patching and 1.5" S9.5C	$390,000
2027	12	018-Catawba	Resurfacing	SR 1841	NC 150	END MAINT	3.14	Full Depth Patching and 1.5" S9.5B	$612,885
2027	12	018-Catawba	Resurfacing	SR 1847	SR 1848	END MAINT	0.68	Full Depth Patching and 1.5" S9.5B	$131,625

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	12	018-Catawba	Resurfacing	SR 1848	SR 1847	NC 150	9.13	1.5" S9.5B	$1,780,740
2027	12	018-Catawba	Resurfacing	SR 1848	NC 150	SR 1843	0.85	1.25" SF9.5A	$165,360
2027	12	018-Catawba	Resurfacing	SR 1901	SR 1849	DEAD END	1.46	Patching and 1.0" S9.5A	$284,700
2027	12	018-Catawba	Resurfacing	SR 1940	SR 1815	SR 1941	0.15	1.25" SF9.5A	$28,665
2027	12	018-Catawba	Resurfacing	SR 1941	END MAINT	END MAINT	0.22	1.25" SF9.5A	$42,510
2027	12	018-Catawba	Resurfacing	SR 1948	SR 1905	END MAINT	0.41	1.25" SF9.5A	$79,170
2027	12	018-Catawba	Resurfacing	SR 1955	SR 1842	Dead End	0.60	Patching and 1.0" S9.5A	$116,805
2027	12	018-Catawba	Resurfacing	SR 1957	SR 1841	CDS	0.31	Full Depth Patching and 1.25" S9.5B	$60,450
2027	12	018-Catawba	Resurfacing	SR 1975	SR 1842	SR 1976	1.02	Patching and 1.0" S9.5A	$198,900
2027	12	018-Catawba	Resurfacing	SR 1976	SR 1975	END MAINT	0.74	Patching and 1.0" S9.5A	$143,520
2027	12	018-Catawba	Resurfacing	SR 1985	NC 150	DEAD END	0.99	Patching and 1.0" S9.5A	$193,050
2027	12	018-Catawba	Resurfacing	SR 2666	SR 1948	End Maint	0.27	1.25" SF9.5A	$526,550
2027	12	018-Catawba	Resurfacing	SR 2701	SR 1841	DEAD END	0.17	Patching and 1.0" S9.5A	$33,150
2027	12	018-Catawba	Resurfacing	SR 2702	SR 2701	SR 2703	0.14	Patching and 1.0" S9.5A	$27,105
2027	12	018-Catawba	Resurfacing	SR 2703	SR 2702	DEAD END	0.15	Patching and 1.0" S9.5A	$29,250
2027	12	018-Catawba	Resurfacing	SR 2742	SR 1976	DEAD END	0.09	Patching and 1.0" S9.5A	$17,550
2027	12	018-Catawba	Preservation	SR 1520	SR 1453	Dead End	0.60	Microsurface	$32,250
2027	12	018-Catawba	Preservation	SR 1700	NC 16	SR 1704	4.89	Microsurface	$262,837
2027	12	018-Catawba	Preservation	SR 1704	NC 16	SR 1700	2.35	Microsurface	$126,312
2027	12	018-Catawba	Preservation	SR 1707	SR 1006	SR 1716	2.15	Microsurface	$115,562
2027	12	018-Catawba	Preservation	SR 1719	SR 1718	DEAD END	0.94	Microsurface	$50,525
2027	12	018-Catawba	Preservation	SR 1725	NC 10	Dead End	1.35	Microsurface	$72,562
2027	12	018-Catawba	Preservation	SR 1811	SR 1810	Cul-de-sac	1.05	Microsurface	$56,437
2027	12	018-Catawba	Preservation	SR 1814	NC 16	SR 1003	2.11	Microsurface	$113,358
2027	12	018-Catawba	Preservation	SR 1854	SR 1855	SR 1856	0.61	Microsurface	$32,787
2027	12	018-Catawba	Preservation	SR 1876	SR 1858	NC 16	1.60	Microsurface	$86,000
2027	12	018-Catawba	Preservation	SR 1881	SR 1880	SR 1882	1.12	Microsurface	$60,038
2027	12	018-Catawba	Preservation	SR 2033	SR 2030	NC 10	1.45	Microsurface	$77,937
2027	12	023-Cleveland	Resurfacing	40001162	US 74	SR 1161	0.97	1.5" S9.5B	$97,954
2027	12	023-Cleveland	Resurfacing	40001162	US 74	SR 1161	0.00	1.5" S9.5B	$304
2027	12	023-Cleveland	Resurfacing	40001811	SR 1809	NC 226	2.00	1.5" S9.5B	$411,594
2027	12	023-Cleveland	Resurfacing	NC 161	I-85	Gaston Co Line	2.61	1.5" S9.5C	$1,314,844
2027	12	023-Cleveland	Resurfacing	NC 161	S.C. Line	I-85	4.75	1.5" S9.5C	$1,600,000
2027	12	023-Cleveland	Resurfacing	NC 18	SR 1654+.130	Lincoln Co. line	6.48	1.5" S9.5C	$1,213,257
2027	12	023-Cleveland	Resurfacing	NC 18	SR 1950	END C&G	2.96	1.5" S9.5C	$610,000
2027	12	023-Cleveland	Resurfacing	NC 18	SC line	NC 150	5.96	1.5" S9.5B	$1,048,960
2027	12	023-Cleveland	Resurfacing	NC 182	N.C. 18	S.R. 1001	0.53	1.5" S9.5B	$93,352
2027	12	023-Cleveland	Resurfacing	SR 1361	NC 226	SR 1351	4.04	1.5" S9.5B	$462,176
2027	12	023-Cleveland	Resurfacing	SR 1364	NC 226	SR 1363	1.04	1.5" S9.5B	$118,404
2027	12	023-Cleveland	Resurfacing	SR 1403	SR 1370	SR 1369	0.22	1.5" S9.5B	$27,422
2027	12	023-Cleveland	Resurfacing	SR 1513	SR 1509	SR 1004	1.60	1.5" S9.5B	$183,040
2027	12	023-Cleveland	Resurfacing	SR 1602	SR 1601	CUL DE SAC	0.49	1.5" S9.5B	$56,056
2027	12	023-Cleveland	Resurfacing	SR 1866	SR 1005	DEAD END	0.52	1.5" S9.5B	$59,144
2027	12	023-Cleveland	Resurfacing	SR 1894	SR 1866	DEAD END	0.25	1.5" S9.5B	$28,485
2027	12	023-Cleveland	Resurfacing	SR 1920	NC 150	SR 1926	0.65	1.5" S9.5B	$74,300
2027	12	023-Cleveland	Resurfacing	SR 1927	NC 18	SR 1926	0.99	1.5" S9.5B	$113,484
2027	12	023-Cleveland	Resurfacing	SR 1935	SR 1001	DEAD END	0.93	1.5" S9.5B	$106,163
2027	12	023-Cleveland	Resurfacing	SR 2038	SR 2034	SR 2039	1.27	1.5" S9.5B	$137,280
2027	12	023-Cleveland	Resurfacing	SR 2070	NC 150	SR 2071	2.61	1.5" S9.5B	$412,023
2027	12	023-Cleveland	Resurfacing	SR 2092	Service Rd	Service Rd	0.55	1.5" S9.5B	$62,691
2027	12	023-Cleveland	Resurfacing	SR 2273	SR 2245	SR 2235	1.18	1.5" S9.5B	$134,877
2027	12	023-Cleveland	Resurfacing	SR 2309	SR 2235	DEAD END	0.70	1.5" S9.5B	$79,736
2027	12	023-Cleveland	Resurfacing	SR 2670	SR 2159	DEAD END	0.48	1.5" S9.5B	$54,454
2027	12	023-Cleveland	Preservation	40001273	1272	DE	0.75	.75" S4.75A	$90,539
2027	12	023-Cleveland	Preservation	40001274	1273	DE	0.19	.75" S4.75A	$29,789
2027	12	023-Cleveland	Preservation	40001275	1273	DE	0.06	.75" S4.75A	$20,039
2027	12	023-Cleveland	Preservation	40001276	1273	DE	0.05	.75" S4.75A	$19,289
2027	12	023-Cleveland	Preservation	40001277	1273	DE	0.10	.75" S4.75A	$23,039
2027	12	023-Cleveland	Preservation	40001278	DE	DE	0.07	.75" S4.75A	$20,789

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	12	023-Cleveland	Preservation	40001503	NC 182	SR 1501	0.99	Seal - Double	$62,537
2027	12	023-Cleveland	Preservation	40001540	1573	1544	0.27	Seal - Double	$48,539
2027	12	023-Cleveland	Preservation	40001573	NC 10	SR 1543	1.19	Seal - Double	$68,901
2027	12	023-Cleveland	Preservation	40001819	NC 182	SR 1364	2.07	Seal - Double	$98,714
2027	12	023-Cleveland	Preservation	40002519	1127	DE	0.10	.75" S4.75A	$23,039
2027	12	023-Cleveland	Preservation	40002534	1273	DE	0.19	.75" S4.75A	$24,539
2027	12	023-Cleveland	Preservation	40002538	2519	DE	0.18	.75" S4.75A	$29,039
2027	12	023-Cleveland	Preservation	40002543	1127	DE	0.15	.75" S4.75A	$26,789
2027	12	023-Cleveland	Preservation	S.R. 1127	1273	D.E.	1.12	.75" S4.75A	$99,539
2027	12	023-Cleveland	Preservation	S.R. 1272	1273	NC 150	0.37	.75" S4.75A	$43,289
2027	12	023-Cleveland	Preservation	S.R. 2021	Gaston Co Line	Linwood Road	0.90	.75" S4.75A	$98,539
2027	12	023-Cleveland	Preservation	S.R. 2025	NC 216	County Line	0.69	.75" S4.75A	$67,289
2027	12	023-Cleveland	Preservation	S.R. 2032	2026	2033	0.66	.75" S4.75A	$65,039
2027	12	023-Cleveland	Preservation	S.R. 2605	2032	DE	0.28	.75" S4.75A	$36,539
2027	12	036-Gaston	Resurfacing	NC 273	A& E DRIVE	NC 27	0.53	1.5" S9.5B	$233,100
2027	12	036-Gaston	Resurfacing	NC 274	SR2416	RIVERMONT	0.58	1.5" S9.5B	$136,600
2027	12	036-Gaston	Resurfacing	NC 274	RIVERMONT	SR 1255	0.96	1.5" S9.5B	$715,000
2027	12	036-Gaston	Resurfacing	NC 274	SR 1255	NEW PVT	0.46	1.5" S9.5B	$400,000
2027	12	036-Gaston	Resurfacing	NC 7	NC 273	US 29/74	1.88	1.5" S9.5B	$362,000
2027	12	036-Gaston	Resurfacing	NC 7	US321	I-85	1.77	1.5" S9.5B	$1,043,000
2027	12	036-Gaston	Resurfacing	SR 1327	NC 275	SR 1456	0.10	1.5" S9.5B	$20,000
2027	12	036-Gaston	Resurfacing	SR 1401	NC 161	CLEV CO	4.53	1.5" S9.5B	$790,100
2027	12	036-Gaston	Resurfacing	SR 1402	NC 161	CLEV. CO	3.06	1.5" S9.5A and Widen	$583,000
2027	12	036-Gaston	Resurfacing	SR 1405	SR 1403	NC 274	1.57	1.5" S9.5B	$275,300
2027	12	036-Gaston	Resurfacing	SR 1409	SR 1408	CLEV CO	2.62	1.5" S9.5B and Widen	$460,675
2027	12	036-Gaston	Resurfacing	SR 1415	SR 1417	NC 216	1.09	1.5" S9.5B	$178,000
2027	12	036-Gaston	Resurfacing	SR 1416	NC 279	SR 1438	1.61	1.5" S9.5B	$240,000
2027	12	036-Gaston	Resurfacing	SR 1431	NC 274	SR 1416	2.20	1.5" S9.5B	$385,200
2027	12	036-Gaston	Resurfacing	SR 1444	SR 1445	SR 1443	0.63	1.5" S9.5B	$110,250
2027	12	036-Gaston	Resurfacing	SR 1454	SR 1453	SR 1448	0.45	1.5" S9.5B	$62,000
2027	12	036-Gaston	Resurfacing	SR 1474	SR 1443	SR 1441	0.93	1.5" S9.5B	$169,000
2027	12	036-Gaston	Resurfacing	SR 1607	BUS 321	SR 1611	1.84	1.5" S9.5C	$300,000
2027	12	036-Gaston	Resurfacing	SR 1907	LINC CO	SR 1820	1.17	1.5" S9.5C	$206,600
2027	12	036-Gaston	Resurfacing	SR 2015	US 29	SR 2014	0.31	1.5" S9.5B	$55,000
2027	12	036-Gaston	Resurfacing	SR 2035	SR 2036	SR 2021	0.61	1.5" S9.5B	$157,750
2027	12	036-Gaston	Resurfacing	SR 2044	NC 273	BRIDGE	0.90	1.5" S9.5B	$158,000
2027	12	036-Gaston	Resurfacing	SR 2200	ROUND A BOUT	DUKE ST	0.36	1.5" S9.5B	$128,520
2027	12	036-Gaston	Resurfacing	SR 2200	LINCOLN ST	ROUND A BOUT	1.20	1.5" S9.5B	$148,700
2027	12	036-Gaston	Resurfacing	SR 2424	S.C.	SR2423	0.60	1.5" S9.5B	$80,000
2027	12	036-Gaston	Resurfacing	SR2327	NC279	ESM	0.60	1.5" S9.5B	$79,500
2027	12	036-Gaston	Resurfacing	US 29/74N	SR1122	SR 1303	2.14	1.5" S9.5B	$600,000
2027	12	036-Gaston	Resurfacing	US321B	SR1607 HARDIN RD	LINC.CO	2.51	1.5" S9.5B	$539,000
2027	12	036-Gaston	Preservation	SR 1107	SR 1103	END STATE	0.40	1.0" S9.5B	$22,000
2027	12	036-Gaston	Preservation	SR 1110	US 321S	D END	0.26	1.0" S9.5B	$13,200
2027	12	036-Gaston	Preservation	SR 1116	CLEV. CO	CLEV.CO	0.67	Microsurface	$34,000
2027	12	036-Gaston	Preservation	SR 1117	D END	D END	0.28	1.0" S9.5B	$15,700
2027	12	036-Gaston	Preservation	SR 1124	SR 1125	D END	0.50	1.0" S9.5B	$21,000
2027	12	036-Gaston	Preservation	SR 1132	SE 1131	D END	0.25	1.0" S9.5B	$15,800
2027	12	036-Gaston	Preservation	SR 1172	SR 1131	D END	0.29	1.0" S9.5B	$21,600
2027	12	036-Gaston	Preservation	SR 1180	SR 1154	SR 1181 +.061 MILES	0.13	1.0" S9.5B	$10,000
2027	12	036-Gaston	Preservation	SR 1181	SR 1180	SR 1182	0.13	1.0" S9.5B	$6,300
2027	12	036-Gaston	Preservation	SR 1195	SR 1126	SR 1280+.177 MILES	0.55	1.0" S9.5B	$62,000
2027	12	036-Gaston	Preservation	SR 1202	SR 1125	DEAD END	0.23	1.0" S9.5B	$17,000
2027	12	036-Gaston	Preservation	SR 1221	SR 1136	D END	0.28	1.0" S9.5B	$14,500
2027	12	036-Gaston	Preservation	SR 1223	SR 1222	DEAD END	0.06	1.0" S9.5B	$2,500
2027	12	036-Gaston	Preservation	SR 1228	SR 1128	SR 1230	0.45	1.0" S9.5B	$23,450
2027	12	036-Gaston	Preservation	SR 1230	SR 1128	SR 1128	0.25	1.0" S9.5B	$16,100
2027	12	036-Gaston	Preservation	SR 1241	SR 1125	D END	0.64	Microsurface	$31,600
2027	12	036-Gaston	Preservation	SR 1242	SR 1103	SR 1103+0.099 MILES	0.10	1.0" S9.5B	$2,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	12	036-Gaston	Preservation	SR 1243	SR 1103	CDS	0.11	1.0" S9.5B	$8,400
2027	12	036-Gaston	Preservation	SR 1244	SR 1243	CDS	0.08	1.0" S9.5B	$6,000
2027	12	036-Gaston	Preservation	SR 1252	SR 1128	SR 1253	0.41	1.0" S9.5B	$41,000
2027	12	036-Gaston	Preservation	SR 1253	SR 1131	SR 1252	0.26	1.0" S9.5B	$25,600
2027	12	036-Gaston	Preservation	SR 1400	SR 1401	CLEV CO	1.25	Microsurface	$130,000
2027	12	036-Gaston	Preservation	SR 1409	SR 1408	CLEV. CO	2.62	Microsurface	$144,400
2027	12	036-Gaston	Preservation	SR 1423	SR 1422	SR 1421	0.08	Microsurface	$3,000
2027	12	036-Gaston	Preservation	SR 1472	SR 1474	SR 1440	0.75	Microsurface	$41,350
2027	12	036-Gaston	Preservation	SR 1616	SR 1609	LINC CO	0.38	Microsurface	$15,800
2027	12	036-Gaston	Preservation	SR 1638	NC 274	SR 1644	0.42	Microsurface	$15,700
2027	12	036-Gaston	Preservation	SR 1802	SR 1001	SR 1805	1.83	Microsurface	$76,000
2027	12	036-Gaston	Preservation	SR 1893	SR 1836	D END	0.20	1.0" S9.5B	$15,000
2027	12	036-Gaston	Preservation	SR 1917	SR 1916	DE	0.54	Microsurface	$20,600
2027	12	036-Gaston	Preservation	SR 1919	SR 1905	CDS	1.01	Microsurface	$44,000
2027	12	036-Gaston	Preservation	SR 1961	SR 1917	DE	0.32	Microsurface	$12,200
2027	12	036-Gaston	Preservation	SR 1977	SR 1919	D END	0.55	Microsurface	$26,000
2027	12	036-Gaston	Preservation	SR 2017	US 29/74	us 29/74	0.25	1.0" S9.5B	$23,800
2027	12	036-Gaston	Preservation	SR 2117	NC 275	D END	0.10	1.0" S9.5B	$7,700
2027	12	036-Gaston	Preservation	SR1101	S.C.	SR1102	0.25	Microsurface	$13,750
2027	12	036-Gaston	Preservation	SR1422	CLEV CO	SR1423	0.42	Microsurface	$20,000
2027	12	036-Gaston	Preservation	SR1443	SR1440	NC274	4.30	Microsurface	$162,000
2027	12	036-Gaston	Preservation	SR1452	NC 274	NC 279	3.88	Microsurface	$225,000
2027	12	036-Gaston	Preservation	SR1453	SR1452	SR1452	1.58	Microsurface	$87,800
2027	12	036-Gaston	Preservation	SR1652	NC150	SR1651	1.79	Microsurface	$73,800
2027	12	036-Gaston	Preservation	SR1706	SR1160	D END	0.21	1.0" S9.5B	$15,000
2027	12	036-Gaston	Preservation	SR1821	SR1820	LINC.CO	0.51	Microsurface	$26,500
2027	12	049-Iredell	Resurfacing	NC 150	NC 115	Rowan County Line	4.01	1.5" S9.5C	$700,875
2027	12	049-Iredell	Resurfacing	SR 1100	Begin Divided	SR 3290	4.93	1.5" S9.5C	$1,232,250
2027	12	049-Iredell	Resurfacing	SR 1100	Round-about	I-77 Bridge	6.30	1.5" S9.5C	$1,575,000
2027	12	049-Iredell	Resurfacing	SR 1110	SR 1206	SR 1193	0.50	1.0" S9.5B	$105,000
2027	12	049-Iredell	Resurfacing	SR 1193	SR 1110	DE	0.88	1.0" S9.5B	$184,800
2027	12	049-Iredell	Resurfacing	SR 1194	SR 1193	SR 2936	0.33	1.0" S9.5B	$69,300
2027	12	049-Iredell	Resurfacing	SR 1195	SR 1193	DE	0.25	1.0" S9.5B	$52,500
2027	12	049-Iredell	Resurfacing	SR 1207	SR 1179	SR 1179	1.10	1.0" S9.5B	$247,500
2027	12	049-Iredell	Resurfacing	SR 1304	NC 150	End of Maint	0.98	1.0" S9.5B	$215,000
2027	12	049-Iredell	Resurfacing	SR 1344	Begin Maint.	DE	0.82	1.0" S9.5B	$102,875
2027	12	049-Iredell	Resurfacing	SR 1345	SR 1004	SR 1344	0.16	1.0" S9.5B	$20,000
2027	12	049-Iredell	Resurfacing	SR 1382	SR 1004	DE	0.44	1.0" S9.5B	$54,375
2027	12	049-Iredell	Resurfacing	SR 1436	SR 1344	DE	0.12	1.0" S9.5B	$15,125
2027	12	049-Iredell	Resurfacing	SR 1437	SR 1004	DE	1.76	1.5" S9.5C	$289,575
2027	12	049-Iredell	Resurfacing	SR 1470	SR 1304	DE	0.19	1.0" S9.5B	$42,750
2027	12	049-Iredell	Resurfacing	SR 1496	SR 1382	DE	0.26	1.0" S9.5B	$32,625
2027	12	049-Iredell	Resurfacing	SR 1898	NC 115	SR 1873	2.39	1.5" S9.5C	$537,750
2027	12	049-Iredell	Resurfacing	SR 2155	US 64	SR 2167	1.37	1.5" S9.5C	$308,250
2027	12	049-Iredell	Resurfacing	SR 2165	SR 2155	US 64	1.44	1.0" S9.5B	$324,000
2027	12	049-Iredell	Resurfacing	SR 2167	SR 2163	SR 2155	1.28	1.5" S9.5C	$288,000
2027	12	049-Iredell	Resurfacing	SR 2182	SR 2155	DE	0.59	1.0" S9.5B	$135,000
2027	12	049-Iredell	Resurfacing	SR 2209	US 64	DE	0.28	1.0" S9.5B	$63,000
2027	12	049-Iredell	Resurfacing	SR 2278	SR 2155	DE	0.23	1.0" S9.5B	$51,750
2027	12	049-Iredell	Resurfacing	SR 2344	SR 2345	End of Maint.	0.65	1.0" S9.5B	$146,250
2027	12	049-Iredell	Resurfacing	SR 2345	SR 2347	SR 2348	0.77	1.0" S9.5B	$173,250
2027	12	049-Iredell	Resurfacing	SR 2347	US 21	US 21	0.99	1.0" S9.5B	$220,000
2027	12	049-Iredell	Resurfacing	SR 2364	SR 2362	County Line	1.15	1.0" S9.5B	$258,750
2027	12	049-Iredell	Resurfacing	SR 2365	SR 2362	SR 1001	1.56	1.0" S9.5B	$351,000
2027	12	049-Iredell	Resurfacing	SR 2508	SR 2360	SR 2563	0.37	1.0" S9.5B	$83,250
2027	12	049-Iredell	Resurfacing	SR 2563	SR 2360	SR 2508	0.89	1.0" S9.5B	$200,250
2027	12	049-Iredell	Resurfacing	SR 2577	SR 2508	DE	0.59	1.0" S9.5B	$135,000
2027	12	049-Iredell	Resurfacing	SR 2726	SR 1004	DE	0.28	1.0" S9.5B	$34,500
2027	12	049-Iredell	Resurfacing	SR 2732	SR 1437	SR 2747	0.33	1.0" S9.5B	$41,250

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	12	049-Iredell	Resurfacing	SR 2747	SR 2732	DE	0.20	1.0" S9.5B	$24,750
2027	12	049-Iredell	Resurfacing	SR 2901	SR 1295	DE	0.19	1.0" S9.5B	$23,875
2027	12	049-Iredell	Resurfacing	SR 2931	SR 1234	DE	0.17	1.0" S9.5B	$21,750
2027	12	049-Iredell	Resurfacing	SR 2932	SR 2931	DE	0.05	1.0" S9.5B	$6,750
2027	12	049-Iredell	Resurfacing	SR 2936	SR 1194	DE	0.14	1.0" S9.5B	$29,400
2027	12	049-Iredell	Resurfacing	SR 2937	SR 2936	DE	0.14	1.0" S9.5B	$29,400
2027	12	049-Iredell	Resurfacing	SR 2980	SR 1179	DE	0.38	1.0" S9.5B	$85,500
2027	12	049-Iredell	Resurfacing	SR 3097	SR 1108	DE	0.44	1.0" S9.5B	$54,750
2027	12	049-Iredell	Resurfacing	SR 3098	SR 3186	SR 3097	0.24	1.0" S9.5B	$29,375
2027	12	049-Iredell	Resurfacing	SR 3099	SR 3097	DE	0.11	1.0" S9.5B	$14,250
2027	12	049-Iredell	Resurfacing	SR 3117	SR 1004	Cul-De-Sac	0.57	1.0" S9.5B	$128,250
2027	12	049-Iredell	Resurfacing	SR 3118	SR 3117	Cul-De-Sac	0.18	1.0" S9.5B	$40,500
2027	12	049-Iredell	Resurfacing	SR 3119	SR 3117	SR 3117	0.30	1.0" S9.5B	$67,500
2027	12	049-Iredell	Resurfacing	SR 3120	SR 3118	Cul-de-Sac	0.06	1.0" S9.5B	$13,500
2027	12	049-Iredell	Resurfacing	SR 3134	SR 1303	DE	0.10	1.0" S9.5B	$15,000
2027	12	049-Iredell	Resurfacing	SR 3157	SR 1321	DE	0.18	1.0" S9.5B	$21,875
2027	12	049-Iredell	Resurfacing	SR 3176	SR 1382	DE	0.14	1.0" S9.5B	$17,250
2027	12	049-Iredell	Resurfacing	SR 3186	SR 3097	DE	0.27	1.0" S9.5B	$33,500
2027	12	049-Iredell	Resurfacing	US 70	Catawba CL	SR 1005	5.93	1.5" S9.5C	$1,037,225
2027	12	049-Iredell	Preservation	SR 1520	SR 1005	SR 1521	1.45	Seal - Double	$62,350
2027	12	049-Iredell	Preservation	SR 1561	SR 1554	NC 115	5.77	Seal - Double and Fog Seal	$256,500
2027	12	049-Iredell	Preservation	SR 1565	SR 1554	Alex County	1.16	Seal - Double and Fog Seal	$52,200
2027	12	049-Iredell	Preservation	SR 1569	SR 1554	SR 1561	1.82	Seal - Double and Fog Seal	$85,050
2027	12	049-Iredell	Preservation	SR 1570	SR 1554	SR 1767	3.52	Seal - Double and Fog Seal	$158,400
2027	12	049-Iredell	Preservation	SR 1644	NC 115	Dead End	0.31	Seal - Double	$13,201
2027	12	049-Iredell	Preservation	SR 1687	SR 1562	Dead End	0.37	Seal - Double	$15,781
2027	12	049-Iredell	Preservation	SR 1800	NC 115	SR 1801	0.71	Seal - Double	$30,444
2027	12	049-Iredell	Preservation	SR 1812	SR 1852	SR 1832	1.19	Seal - Double	$51,084
2027	12	049-Iredell	Preservation	SR 1813	SR 1831	SR 1833	1.01	Seal - Double	$43,516
2027	12	049-Iredell	Preservation	SR 1813	SR 1832	SR 1829	1.16	Seal - Double	$49,966
2027	12	049-Iredell	Preservation	SR 1887	SR 1891	SR 1845	2.20	Seal - Double	$94,514
2027	12	049-Iredell	Preservation	SR 1900	SR 1902	End of Maint.	0.71	Seal - Double	$30,530
2027	12	049-Iredell	Preservation	SR 1912	SR 1907	End of Pvmt.	0.12	Seal - Double	$5,160
2027	12	049-Iredell	Preservation	SR 1917	SR 1919	Dead End	0.70	Seal - Double	$30,100
2027	12	049-Iredell	Preservation	SR 1918	SR 1919	Dead End	0.91	Seal - Double	$38,915
2027	12	049-Iredell	Preservation	SR 1919	US 21	SR 1890	1.92	Seal - Double	$82,345
2027	12	049-Iredell	Preservation	SR 1954	SR 1907	End of Maint	0.35	Seal - Double	$14,921
2027	12	049-Iredell	Preservation	SR 2154	US 21	Dead End	0.67	Seal - Double	$28,767
2027	12	049-Iredell	Preservation	SR 2233	US 21	End of Maint.	0.16	Seal - Double	$6,794
2027	12	049-Iredell	Preservation	SR1606	SR 1598	SR 1607	0.36	Seal - Double	$15,480
2027	12	049-Iredell	Preservation	SR1886	SR 1890	SR 1891	1.72	Seal - Double	$73,917
2027	12	055-Lincoln	Resurfacing	NC 16 BUS	SR 1439	SR 1389	1.40	Full Depth Patching and 1.5" S9.5C	$272,025
2027	12	055-Lincoln	Resurfacing	SR 1113	SR 1002	SR 1008	8.69	Full Depth Patching and 1.5" S9.5B	$1,695,135
2027	12	055-Lincoln	Resurfacing	SR 1168	NC 182	GASTON CO	2.89	Full Depth Patching and 1.5" S9.5B	$563,550
2027	12	055-Lincoln	Resurfacing	SR 1336	SR 1003	SR 1335	0.66	Full Depth Patching and 1.5" S9.5C	$127,725
2027	12	055-Lincoln	Resurfacing	SR 1373	SR 1360	SR 1362	3.17	Full Depth Patching and 1.5" S9.5B	$618,345
2027	12	055-Lincoln	Resurfacing	SR 1380	SR 1386	NC 16	0.54	Full Depth Patching and 1.5" S9.5C	$105,300
2027	12	055-Lincoln	Resurfacing	SR 1387	NC 16 BUS	SR 1380	0.38	Full Depth Patching and 1.5" S9.5B	$74,100
2027	12	055-Lincoln	Resurfacing	SR 1387	SR 1380	SR 2192	0.72	Full Depth Patching and 1.5" S9.5C	$142,350
2027	12	055-Lincoln	Resurfacing	SR 1388	SR 1380	NC 16 BUS	0.53	Full Depth Patching and 1.5" S9.5B	$103,350
2027	12	055-Lincoln	Resurfacing	SR 1390	SR 1439	Cul-de-sac	0.97	Full Depth Patching and 1.5" S9.5C	$189,150
2027	12	055-Lincoln	Resurfacing	SR 1470	SR 1432	SR 1471	0.30	Full Depth Patching and 1.5" S9.5B	$58,500
2027	12	055-Lincoln	Resurfacing	SR 1859	SR 1180	End Maint	0.58	Patching and 1.0" S9.5A	$113,100
2027	12	055-Lincoln	Resurfacing	SR 1950	SR 1399	CUL-DE-SAC	0.23	Patching and 1.0" S9.5A	$44,655
2027	12	055-Lincoln	Resurfacing	SR 2103	SR 2102	CUL-DE-SAC	0.58	Mill 1.0" and 1.0" S9.5B	$112,125
2027	12	055-Lincoln	Resurfacing	SR 2104	SR 2103	CUL-DE-SAC	0.11	Mill 1.0" and 1.0" S9.5B	$21,450
2027	12	055-Lincoln	Resurfacing	SR 2105	SR 2103	CUL-DE-SAC	0.05	Mill 1.0" and 1.0" S9.5B	$8,775
2027	12	055-Lincoln	Resurfacing	SR 2106	SR 2103	SR 1397	0.55	Mill 1.0" and 1.0" S9.5B	$106,275
2027	12	055-Lincoln	Resurfacing	SR 2107	SR 2106	CUL-DE-SAC	0.12	Mill 1.0" and 1.0" S9.5B	$23,400

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	12	055-Lincoln	Resurfacing	SR 2108	SR 2106	CUL-DE-SAC	0.17	Mill 1.0" and 1.0" S9.5B	$33,150
2027	12	055-Lincoln	Resurfacing	SR 2109	SR 2106	SR 2106	0.55	Mill 1.0" and 1.0" S9.5B	$107,250
2027	12	055-Lincoln	Resurfacing	SR 2110	SR 2109	CUL-DE-SAC	0.09	Mill 1.0" and 1.0" S9.5B	$17,550
2027	12	055-Lincoln	Resurfacing	SR 2112	SR 1373	CUL-DE-SAC	0.35	Patching and 1.0" S9.5A	$67,275
2027	12	055-Lincoln	Resurfacing	SR 2113	SR 2112	CUL-DE-SAC	0.22	Patching and 1.0" S9.5A	$42,900
2027	12	055-Lincoln	Resurfacing	SR 2114	SR 2112	CUL-DE-SAC	0.13	Patching and 1.0" S9.5A	$25,350
2027	12	055-Lincoln	Resurfacing	SR 2164	SR 2109	Cul-de-sac	0.16	Mill 1.5" and 1.5" S9.5C	$21,200
2027	12	055-Lincoln	Resurfacing	SR 2165	SR 2164	Cul-de-sac	0.04	Mill 1.5" and 1.5" S9.5C	$7,410
2027	12	055-Lincoln	Resurfacing	SR 2166	SR 2109	Cul-de-sac	0.06	Mill 1.5" and 1.5" S9.5C	$10,920
2027	12	055-Lincoln	Resurfacing	SR 2194	SR 1792	Cul-de-sac	0.08	Full Depth Patching and 1.5" S9.5C	$14,820
2027	12	055-Lincoln	Resurfacing	SR 3002	SR 1360	CUL-DE-SAC	0.73	Patching and 1.0" S9.5A	$142,155
2027	12	055-Lincoln	Resurfacing	SR 3003	SR 3002	CUL-DE-SAC	0.30	Patching and 1.0" S9.5A	$58,500
2027	12	055-Lincoln	Resurfacing	SR 3004	SR 3002	CUL-DE-SAC	0.21	Patching and 1.0" S9.5A	$40,755
2027	12	055-Lincoln	Preservation	SR 1108	SR 1111	SR 1114	1.38	Microsurface	$74,175
2027	12	055-Lincoln	Preservation	SR 1108	SR 1002	SR 1109	1.16	Microsurface	$62,350
2027	12	055-Lincoln	Preservation	SR 1121	SR 1120	SR 1122	1.01	Microsurface	$54,287
2027	12	055-Lincoln	Preservation	SR 1191	SR 1002	Cul-de-sac	0.44	Microsurface	$23,650
2027	12	055-Lincoln	Preservation	SR 1212	SR 1211	SR 1922	0.90	Seal - Double	$48,321
2027	12	055-Lincoln	Preservation	SR 1213	SR 1197	SR 1211	1.31	Seal - Double	$70,197
2027	12	055-Lincoln	Preservation	SR 1244	SR 1242	EOM	0.40	.75" S4.75A	$44,800
2027	12	055-Lincoln	Preservation	SR 1245	SR 1244	GASTON CO	0.78	Seal - Double	$7,800
2027	12	055-Lincoln	Preservation	SR 1314	NC 27	SR 1001	4.67	Seal - Double	$250,905
2027	12	055-Lincoln	Preservation	SR 1337	SR 1003	END PVMT	0.49	.75" S4.75A	$55,328
2027	12	055-Lincoln	Preservation	SR 1435	SR 1005	Dead End	0.17	.75" S4.75A	$19,040
2027	12	055-Lincoln	Preservation	SR 1557	SR 1338	SR 1337	0.74	.75" S4.75A	$82,320
2027	12	055-Lincoln	Preservation	SR 1711	SR 1347	SR 1367	0.62	.75" S4.75A	$69,440
2027	12	055-Lincoln	Preservation	SR 1777	NC 150	Cul-de-sac	0.23	.75" S4.75A	$25,536
2027	12	055-Lincoln	Preservation	SR 2150`	SR 1003	Cul-de-sac	0.44	.75" S4.75A	$49,280
2027	12	055-Lincoln	Preservation	SR 2168	SR 2150	Cul-de-sac	0.29	.75" S4.75A	$32,480
2027	13	011-Buncombe	Resurfacing	2887 (SMITH KNOLLS ROAD)	US 74 ALTERNATE	DEAD END	1.01	Full Depth Patching and 1.5" S9.5C	$181,800
2027	13	011-Buncombe	Resurfacing	SR 2500 (BLUE RIDGE ROAD)	US 70	BEGIN 24' PAVEMENT	1.03	Full Depth Patching and 1.5" S9.5C	$195,000
2027	13	011-Buncombe	Resurfacing	SR 2500 (BLUE RIDGE ROAD)	BEG. 24' PAVEMENT	NC 9	0.45	Full Depth Patching and 1.5" S9.5C	$99,900
2027	13	011-Buncombe	Resurfacing	(SOUTH BLUE RIDGE ROAD/OLD LAKEY GA	NC 9	SR 2500 (BLUE RIDGE ROAD)	1.05	Full Depth Patching and 1.5" S9.5C	$185,669
2027	13	011-Buncombe	Resurfacing	SR 2771 (OLD CHARLOTTE HIGHWAY)	US 74	SR 2772 (JUNE SAYLES ROAD)	0.30	Full Depth Patching and 1.5" S9.5C	$42,225
2027	13	011-Buncombe	Resurfacing	SR 2773 (OLD CHARLOTTE HIGHWAY)	US 74 ALTERNATE	US 74 ALTERNATE	0.32	Full Depth Patching and 1.5" S9.5C	$55,550
2027	13	011-Buncombe	Resurfacing	SR 2776 (OLD FORT ROAD)	US 74 ALTERNATE	SR 2800 (MILLER ROAD)	1.76	Full Depth Patching and 1.5" S9.5C	$336,225
2027	13	011-Buncombe	Resurfacing	SR 2776 (OLD FORT ROAD)	SR 2800 (MILLER ROAD)	BRIDGE	7.31	Full Depth Patching and 1.5" S9.5C	$1,695,456
2027	13	011-Buncombe	Resurfacing	SR 2791 (OLD FORT ROAD)	SR 2755 (STONE MOUNTAIN FARM ROAD)	SR 2794 (CAMP ELLIOTT ROAD)	0.97	Full Depth Patching and 1.5" S9.5C	$201,000
2027	13	011-Buncombe	Resurfacing	SR 2806 (GARREN CREEK ROAD)	SR 2815 (VILLAGE ROAD)	GREGORY HILL ROAD	3.09	Full Depth Patching and 1.5" S9.5C	$550,800
2027	13	011-Buncombe	Resurfacing	L3 (SUGAR HOLLOW / BUTTERROW COVE I	US 74	END OF MAINTENANCE	0.40	Full Depth Patching and 1.25" S9.5B	$70,000
2027	13	011-Buncombe	Resurfacing	SR 2815 (VILLAGE ROAD)	US 74	US 74	0.35	Full Depth Patching and 1.25" S9.5B	$44,000
2027	13	011-Buncombe	Resurfacing	SR 2816 (CHURCH ROAD)	SR 2815 (VILLAGE ROAD)	782 (BLUE RIDGE DEVELOPMENT R(	1.89	Full Depth Patching and 1.25" S9.5B	$295,550
2027	13	011-Buncombe	Resurfacing	SR 2817 (NOBLE ROAD)	SR 2815 (VILLAGE ROAD)	SR 2816 (CHURCH ROAD)	0.82	Full Depth Patching and 1.25" S9.5B	$152,250
2027	13	011-Buncombe	Resurfacing	SR 2840 (EASTCREST DRIVE)	US 74	SR 2841 (EASTRIDGE COURT)	0.13	Full Depth Patching and 1.0" S4.75A	$16,250
2027	13	011-Buncombe	Resurfacing	SR 2841 (EASTRIDGE COURT)	CUL DE SAC	CUL DE SAC	0.12	Full Depth Patching and 1.0" S4.75A	$15,775
2027	13	011-Buncombe	Resurfacing	SR 2850 (GARRISON ROAD)	SR 2806 (GARREN CREEK ROAD)	DEAD END	0.42	Full Depth Patching and 1.5" S9.5C	$78,000
2027	13	011-Buncombe	Resurfacing	SR 2862 (OLD CHARLOTTE HIGHWAY)	US 74	END OF MAINTENANCE	0.39	Full Depth Patching and 1.5" S9.5C	$72,245
2027	13	011-Buncombe	Resurfacing	SR 2884 (COBBLE HILL ROAD)	SR 2810 (HOLLYWOOD ROAD)	CUL DE SAC	0.15	Full Depth Patching and 1.25" S9.5B	$13,020
2027	13	011-Buncombe	Resurfacing	SR 2891 (OLD EASTWOOD VILLAGE BLVD)	SR 2771 (OLD CHARLOTTE HIGHWAY)	CUL DE SAC	0.18	Mill 1.5" and 1.5" S9.5C	$40,000
2027	13	011-Buncombe	Resurfacing	SR 2895 (NUTHATCH COURT)	SR 2816 (CHURCH ROAD)	CUL DE SAC	0.28	Full Depth Patching and 1.25" S9.5B	$49,000
2027	13	011-Buncombe	Resurfacing	SR 2896 (CHICKADEE LANE)	SR 2816 (CHURCH ROAD)	SR 2895 (NUTHATCH COURT)	0.09	Full Depth Patching and 1.25" S9.5B	$15,750
2027	13	011-Buncombe	Resurfacing	SR 3081 (ROCK HILL ROAD)	US 25A	US 25	0.49	1.25" S9.5B	$95,345
2027	13	011-Buncombe	Resurfacing	SR 3128 (OLD GAP CREEK ROAD)	SR 3133 (SHARON ROAD)	SR 3127 (EMMAS GROVE ROAD)	0.46	Full Depth Patching and 1.5" S9.5C	$82,800
2027	13	011-Buncombe	Resurfacing	SR 3131 (LYTLE ROAD)	SR 3128 (EMMAS GROVE ROAD)	END OF MAINTENANCE	0.37	Full Depth Patching and 1.5" S9.5C	$64,750
2027	13	011-Buncombe	Resurfacing	SR 3231 (REYNOLDS SCHOOL ROAD)	SR 3121 (ROSE HILL ROAD)	END OF STATE MAINTENANCE	0.78	Full Depth Patching and 1.25" S9.5B	$157,455
2027	13	011-Buncombe	Resurfacing	SR 3268 (REYNOLDS DRIVE)	SR 3231 (REYNOLDS SCHOOL ROAD)	CUL DE SAC	0.21	Full Depth Patching and 1.0" S4.75A	$27,300
2027	13	011-Buncombe	Resurfacing	SR 3279 (CHARLES A LYTLE LANE)	US 74	END OF MAINTENANCE	0.13	Full Depth Patching and 1.5" S9.5C	$18,545
2027	13	011-Buncombe	Resurfacing	SR 3327 (MEADOW WOOD TRAIL)	SR 3131 (LYTLE ROAD)	CUL DE SAC	0.34	Full Depth Patching and 1.5" S9.5C	$49,364
2027	13	011-Buncombe	Resurfacing	SR 3335 (MEADOW BROOK DRIVE)	SR 3327 (MEADOW WOOD TRAIL)	SR 3327 (MEADOW WOOD TRAIL)	0.46	Full Depth Patching and 1.5" S9.5C	$80,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	13	011-Buncombe	Resurfacing	SR 3354 (CANE CREEK CIRCLE)	SR 3136 (CANE CREEK ROAD)	SR 3355 (CANE CREEK CIRCLE)	0.25	Full Depth Patching and 1.25" S9.5B	$38,000
2027	13	011-Buncombe	Resurfacing	SR 3355 (CANE CREEK CIRCLE)	SR 3354 (CANE CREEK CIRCLE)	SR 3354 (CANE CREEK CIRCLE)	0.28	Full Depth Patching and 1.25" S9.5B	$42,000
2027	13	011-Buncombe	Resurfacing	SR 3358 (MOUNTAIN VIEW LANE)	SR 3335 (MEADOW BROOK DRIVE)	CUL DE SAC	0.13	Full Depth Patching and 1.0" S4.75A	$15,600
2027	13	011-Buncombe	Resurfacing	SR 3374 (SPRING LAKE DRIVE)	SR 3136 (CANE CREEK ROAD)	CUL DE SAC	0.37	Full Depth Patching and 1.25" S9.5B	$55,500
2027	13	011-Buncombe	Resurfacing	US 74	SR 2881 + .455 MILE	NC 81	1.32	Full Depth Patching and 1.5" S9.5C	$302,277
2027	13	011-Buncombe	Resurfacing	US 74	NC 81	I-240	0.59	Full Depth Patching and 1.5" S9.5C	$365,000
2027	13	011-Buncombe	Resurfacing	US 74	I-240 West + .098 MILE	US 74 ALTERNATE	0.12	Full Depth Patching and 1.5" S9.5C	$46,000
2027	13	011-Buncombe	Resurfacing	US 74 ALTERNATE RAMP	SR 2834 (GASHES CREEK ROAD -- .01 MILE	US 74 (FAIRVIEW ROAD --.13 MILE)	0.49	Full Depth Patching and 1.5" S9.5C	$179,450
2027	13	011-Buncombe	Preservation	SR 1252 (CONNER ROAD)	SR 1248 (OAK HILL ROAD)	END OF PAVEMENT	0.26	Full Depth Patching and 1.0" S4.75A	$22,000
2027	13	011-Buncombe	Preservation	SR 1260 (KAREN PLACE)	SR 1257 (MKINNEY ROAD)	ł 1257 (MKINNEY ROAD) + 0.11 MII	0.11	Full Depth Patching and 1.0" S4.75A	$10,000
2027	13	011-Buncombe	Preservation	SR 1294 (LAUREL COVE ROAD)	SR 1220 (HOOKERS GAP ROAD)	END OF MAINTENANCE	0.20	Full Depth Patching and 1.0" S4.75A	$34,450
2027	13	011-Buncombe	Preservation	SR 1297 (BROWNTOWN ROAD)	BRIDGE	SR 1004 (NEWFOUND ROAD)	1.55	Full Depth Patching and Double Seal and Fog Seal	$131,000
2027	13	011-Buncombe	Preservation	SR 1299 (MOORES VALLEY ROAD)	SR 1004 (NEWFOUND ROAD)	END OF MAINTENANCE	0.70	Full Depth Patching and Double Seal and Fog Seal	$59,000
2027	13	011-Buncombe	Preservation	SR 1304 (COLE ROAD)	BEGIN PAVEMENT	SR 1303 (FRISBEE ROAD)	0.37	Full Depth Patching and 1.0" S4.75A	$71,775
2027	13	011-Buncombe	Preservation	SR 1310 (PINEY MOUNTAIN ROAD)	SR 1306 (DIX CREEK NO 2 ROAD)	:REEK NO 2) +0.45 MILES (END OF S	0.45	Full Depth Patching and Double Seal and Fog Seal	$38,000
2027	13	011-Buncombe	Preservation	SR 1311 (SHORT DIX CREEK ROAD)	SR 1309 (DIX CREEK NO 1 ROAD)	SR 1306 (DIX CREEK NO 2 ROAD)	0.26	Full Depth Patching and 1.0" S4.75A	$49,995
2027	13	011-Buncombe	Preservation	SR 1320 (McKINNISH COVE ROAD)	SR 1319 (JOHNSTON SCHOOL ROAD)	END OF MAINTENANCE	1.01	Full Depth Patching and Double Seal and Fog Seal	$75,750
2027	13	011-Buncombe	Preservation	SR 1321 (McKINNISH COVE DRIVE)	SR 1320 (McKINNISH COVE DRIVE)	END OF MAINTENANCE	0.22	Full Depth Patching and Double Seal and Fog Seal	$14,450
2027	13	011-Buncombe	Preservation	SR 1323 (SPIVEY MOUNTAIN ROAD	SR 1319 (COWAN COVE ROAD)	PAVEMENT CHANGE	0.59	Full Depth Patching and Double Seal and Fog Seal	$44,250
2027	13	011-Buncombe	Preservation	SR 1373 (OLD COUNTY HOME ROAD)	NC 63	SR 1369 (MOUNT CARMEL ROAD)	0.80	Full Depth Patching and 1.0" S4.75A	$68,000
2027	13	011-Buncombe	Preservation	SR 1375 (DIX CREEL CHAPEL ROAD)	NC 63	END OF MAINTENANCE	1.06	Full Depth Patching and Double Seal and Fog Seal	$80,250
2027	13	011-Buncombe	Preservation	SR 1383 (GREEN VALLEY ROAD)	SR 1381 (RABBIT HAM ROAD)	NC 63	1.56	Full Depth Patching and Double Seal and Fog Seal	$116,900
2027	13	011-Buncombe	Preservation	SR 1384 (SOUTH TURKEY CREEK ROAD)	SR 1220 (POTATO BRANCH ROAD)	BRIDGE	0.32	Full Depth Patching and 1.0" S4.75A	$27,000
2027	13	011-Buncombe	Preservation	SR 1386 (SANDY RIVER ROAD)	SR 1220 (SOUTH TURKEY CREEK ROAD)	END OF MAINTENANCE	0.70	Full Depth Patching and 1.0" S4.75A	$87,500
2027	13	011-Buncombe	Preservation	SR 1389 (NORTH TURKEY CREEK ROAD)	SR 1401 (EARLYS MOUNTAIN ROAD)	MP 3.90	2.50	Full Depth Patching and Double Seal and Fog Seal	$146,455
2027	13	011-Buncombe	Preservation	SR 1392 (BALD CREEK ROAD)	SR 1394 (WILLOW CREEK ROAD)	SR 1397 (SURETT COVE ROAD	1.51	Full Depth Patching and Double Seal and Fog Seal	$129,250
2027	13	011-Buncombe	Preservation	SR 1394 (BIG SANDY MUSH)	SR 1393 (HOGEYE ROAD)	SR 1394 (WILLOW CREEK ROAD)	1.13	Full Depth Patching and 1.25" S9.5B	$255,565
2027	13	011-Buncombe	Preservation	SR 1394 BIG SANDY MUSH ROAD)	SR 1394 (SANDY MUSH CREEK ROAD)	SR 1393 (HOGEYE ROAD)	1.24	Seal - Fog	$10,000
2027	13	011-Buncombe	Preservation	SR 1398 (BOYD COVE ROAD)	SR 1392 (BALD CREEK ROAD)	DEAD END	1.04	Full Depth Patching and Double Seal and Fog Seal	$88,900
2027	13	011-Buncombe	Preservation	SR 1399 (ROBINSON COVE ROAD)	SR 1392 (BALD CREEK ROAD)	DEAD END	1.20	Full Depth Patching and Double Seal and Fog Seal	$102,000
2027	13	011-Buncombe	Preservation	SR 1401 (EARLYS MOUNTAIN ROAD)	SR 1389 (NORTH TURKEY CREEK ROAD)	R 1334 (SANDY MUSH CREEK ROAD	2.22	Full Depth Patching and Double Seal and Fog Seal	$166,500
2027	13	011-Buncombe	Preservation	SR 1442 (WINDY HILL ROAD)	SR 1442 (WINDY HILL ROAD)	1443 (WINDY HILL ROAD) + .21 MII	0.21	Full Depth Patching and 1.0" S4.75A	$18,000
2027	13	011-Buncombe	Preservation	SR 1443 (WINDY HILL ROAD)	SR 1255 (STARNES COVE ROAD)	SR 1442 (WINDY HILL ROAD)	0.07	Full Depth Patching and 1.0" S4.75A	$6,000
2027	13	011-Buncombe	Preservation	SR 1475 (SPAULDING DRIVE)	SR 1224 (MONTE VISTA DRIVE)	DEAD END	0.20	Full Depth Patching and 1.0" S4.75A	$19,000
2027	13	011-Buncombe	Preservation	SR 1481 (AURORA VISTA DRIVE)	SR 1263 (MKINNEY ROAD)	END OF MAINTENANCE	0.30	Full Depth Patching and 1.0" S4.75A	$52,255
2027	13	011-Buncombe	Preservation	SR 1484 (FOREST RIDGE DRIVE)	SR 1315 (OLD COUNTY HOME ROAD)	END OF PAVEMENT	0.20	Full Depth Patching and 1.0" S4.75A	$17,000
2027	13	011-Buncombe	Preservation	SR 1515 (WEBB HILL ROAD)	NC 63	NC 63 + 0.061 MILES	0.06	Full Depth Patching and Double Seal and Fog Seal	$4,100
2027	13	011-Buncombe	Preservation	SR 1612 (GIBBS ROAD)	SR 1608 (TURKEY CREEK ROAD)	SR 1610 (MARTIN BRANCH ROAD)	1.16	Full Depth Patching and Double Seal and Fog Seal	$99,000
2027	13	011-Buncombe	Preservation	SR 1800 (OLD NC 63 HIGHWAY)	NC 63	NC 63	0.23	Full Depth Patching and Double Seal and Fog Seal	$15,550
2027	13	012-Burke	Resurfacing	SR 1129 (DYSARTSVILLE ROAD)	US 70	MCDOWELL COUNTY LINE	4.98	Full Depth Patching and 1.5" S9.5C	$1,179,560
2027	13	012-Burke	Resurfacing	SR 1147 (CAUSBY ROAD)	SR 1142 (JAMESTOWN ROAD)	SR 1168 (LONDON STREET)	1.80	Full Depth Patching and 1.5" S9.5C	$324,000
2027	13	012-Burke	Resurfacing	ł 1147 (LONDON STREET/CATAWBA STREE	US 70	SR 1319 (TURKEY TAIL LANE)	0.77	Full Depth Patching and 1.5" S9.5C	$153,000
2027	13	012-Burke	Resurfacing	SR 1147 (WATERMILL GLEN ALPINE ROAD)	SR 1319 (TURKEY TAIL LANE)	NC 126	1.27	Full Depth Patching and 1.5" S9.5C	$272,250
2027	13	012-Burke	Resurfacing	SR 1192 (JUNIOR HENRY STREET)	SR 1142 (JAMESTOWN ROAD)	END OF MAINTENANCE	0.10	Full Depth Patching and 1.0" S4.75A	$14,445
2027	13	012-Burke	Resurfacing	SR 1207 (SOL MULL STREET)	US 70 WEST	CUL DE SAC	0.73	Full Depth Patching and 1.5" S9.5C	$105,000
2027	13	012-Burke	Resurfacing	SR 1222 (MCCONNAUGHEY LANE)	SR 1222 (SWAN POND DRIVE)	END OF MAINTENANCE	0.04	Full Depth Patching and 1.5" S9.5C	$5,675
2027	13	012-Burke	Resurfacing	SR 1240 (FISH HATCHERY ROAD)	SR 1261 (TABLE ROCK MOUNTAIN ROAD)	SR 1254 (PEA RIDGE ROAD)	3.68	Full Depth Patching and 1.5" S9.5C	$666,000
2027	13	012-Burke	Resurfacing	R 1254 (FISH HATCHERY/ PEA RIDGE ROAD	NC 181	NC 126	5.20	Full Depth Patching and 1.5" S9.5C	$485,000
2027	13	012-Burke	Resurfacing	SR 1323 (LAUREL POINT DRIVE)	SR 1234 (BENFIELDS LANDING ROAD)	CUL DE SAC	0.25	Full Depth Patching and 1.0" S4.75A	$32,250
2027	13	012-Burke	Resurfacing	SR 1324 (HEMLOCK COURT)	SR 1323 (LAUREL POINT DRIVE)	CUL DE SAC	0.10	Full Depth Patching and 1.0" S4.75A	$15,000
2027	13	012-Burke	Resurfacing	SR 1348 (LAKE FOREST COVE)	SR 1234 (BENFIELDS LANDING)	BULB OUT ON DRIVE	0.29	Full Depth Patching and 1.0" S4.75A	$54,450
2027	13	012-Burke	Resurfacing	SR 1355 (GRAYSON GREENE LANE)	SR 1355 (GRAYSON GREENE LANE)	CUL DE SAC	0.06	Full Depth Patching and 1.0" S4.75A	$10,224
2027	13	012-Burke	Resurfacing	SR 1362 (NORTHVIEW DRIVE)	SR 1361 (FAIR OAK DRIVE)	CUL DE SAC	0.20	Full Depth Patching and 1.0" S4.75A	$20,000
2027	13	012-Burke	Resurfacing	SR 1364 (OLD DRY CREEK ROAD)	SR 1350 (SOUTHPORT DRIVE)	CUL DE SAC	1.12	Full Depth Patching and 1.25" S9.5B	$188,275
2027	13	012-Burke	Resurfacing	SR 1365 (KALMIA DRIVE)	SR 1364 (OLD DRY CREEK ROAD)	CUL DE SAC	0.09	Full Depth Patching and 1.25" S9.5B	$14,224
2027	13	012-Burke	Resurfacing	R 1405 (BROWN MOUNTAIN BEACH ROAD	COUNTY LINE	NC 181	4.13	Full Depth Patching and 1.5" S9.5C	$565,550
2027	13	012-Burke	Resurfacing	SR 1408 (GLEN POWELL AVENUE)	NC 181	END OF MAINTENANCE	0.28	Full Depth Patching and 1.5" S9.5C	$35,550
2027	13	012-Burke	Resurfacing	∋ (HARMON STREET)SR 1409 (HARMON ST	NC 181	END OF MAINTENANCE	0.43	Full Depth Patching and 1.5" S9.5C	$92,000
2027	13	012-Burke	Resurfacing	SR 1470 (WARRIOR FORK TRAIL)	SR 1440 (SPAINHOUR ROAD)	END OF MAINTENANCE	1.06	Full Depth Patching and 1.5" S9.5C	$152,225

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	13	012-Burke	Resurfacing	SR 1480 (NORTH DEERFIELD DRIVE)	SR 1480 (LAKE DRIVE)	END OF MAINTENANCE	0.25	Full Depth Patching and 1.25" S9.5B	$23,000
2027	13	012-Burke	Resurfacing	SR 1487 (HUNTER RIDGE COURT)	SR 1486 (TIMBER TRACE)	END OF MAINTENANCE	0.11	Full Depth Patching and 1.25" S9.5B	$15,450
2027	13	012-Burke	Resurfacing	SR 1491 (SOUTH DEERFIELD DRIVE)	SR 1486 (LAKE DRIVE)	END OF MAINTENANCE	0.12	Full Depth Patching and 1.25" S9.5B	$15,550
2027	13	012-Burke	Resurfacing	US 64	SR 1168 (CONLEY ROAD)+ 0.33 MILES	SR 1961 (DUCKWORTH CIRCLE)	4.00	Full Depth Patching and 1.5" S9.5C	$944,943
2027	13	012-Burke	Resurfacing	US 70	MCDOWELL COUNTY LINE	SR 1138 (KATHY ROAD)	4.00	Full Depth Patching and 1.5" S9.5C	$1,064,000
2027	13	012-Burke	Preservation	SR 1737 (FLAT GAP ROAD)	SR 1488 (MILLSTONE AVENUE)	I4 (MINERAL SPRINGS MOUNTAIN	4.66	Full Depth Patching and Double Seal and Fog Seal	$375,550
2027	13	012-Burke	Preservation	SR 1742 (MOURGLEA AVENUE)	SR 1001 (RUTHERFORD COLLEGE ROAD)	END OF MAINTENANCE	0.55	Full Depth Patching and Double Seal and Fog Seal	$45,550
2027	13	012-Burke	Preservation	SR 1745 (OLD LOWMAN STREET)	SR 1001 (MINERAL SPRINGS MOUNTAIN ROAD)	END OF MAINTENANCE	0.31	Full Depth Patching and Double Seal and Fog Seal	$22,250
2027	13	012-Burke	Preservation	SR 1758 (BEREA CHURCH ROAD)	SR 1620 (0LD 70 LOOP ROAD)	SR 1762 (EAST BURKE BLVD)	1.26	Full Depth Patching and Double Seal and Fog Seal	$110,995
2027	13	012-Burke	Preservation	SR 1760 (ICARD DARY ROAD)	SR 1786 (MILLER BRIDGE ROAD)	SR 1837 (CAVALIER WAY)	0.56	Full Depth Patching and Double Seal and Fog Seal	$44,995
2027	13	012-Burke	Preservation	SR 1765 (BERRY ROAD)	US 70	SR 1761 (OLD NC 10)	0.81	Full Depth Patching and Double Seal and Fog Seal	$56,550
2027	13	012-Burke	Preservation	SR 1766 (SUNSET GRILL STREET)	US 70	END OF MAINTENANCE	0.31	Full Depth Patching and Double Seal and Fog Seal	$12,400
2027	13	012-Burke	Preservation	SR 1783 (BURKE COUNTY LINE ROAD)	COUNTY LINE	END OF PAVEMENT	0.41	Full Depth Patching and Double Seal and Fog Seal	$35,550
2027	13	012-Burke	Preservation	SR 1784 (OLD BRITTAIN ROAD)	SR 1803 (JOHNSON BRIDGE ROAD)	SR 1761 (OLD NC 10)	1.02	Full Depth Patching and Double Seal and Fog Seal	$77,000
2027	13	012-Burke	Preservation	SR 1792 (MOUNT HEBRON AVENUE)	SR 1786 (MILLER BRIDGE ROAD)	END OF MAINTENANCE	0.74	Full Depth Patching and Double Seal and Fog Seal	$29,600
2027	13	012-Burke	Preservation	SR 1793 (NOBBY LAIL ROAD)	SR 1001 (MINERAL SPRINGS MOUNTAIN ROAD)	SR 1786 (MILLER BRIDGE ROAD)	1.87	Full Depth Patching and Double Seal and Fog Seal	$144,715
2027	13	012-Burke	Preservation	SR 1807 (ROGERS ROAD)	SR 1800 (GEORGE HILDEBRAN SCHOOL ROAD)	SR 1803 (JOHNSON BRIDGE ROAD)	0.86	Full Depth Patching and Double Seal and Fog Seal	$73,000
2027	13	012-Burke	Preservation	SR 1811 (ZERO MULL ROAD)	NC 18	NC 18	1.08	Full Depth Patching and Double Seal and Fog Seal	$64,800
2027	13	012-Burke	Preservation	SR 1812 (BARUS STREET)	SR 1734 (MILLSTONE AVENUE)	END OF MAINTENANCE	0.51	Full Depth Patching and Double Seal and Fog Seal	$20,320
2027	13	012-Burke	Preservation	SR 1821 (BARUS POND LOOP 1)	SR 1737 (FLAT GAP ROAD)	END MILE POST	0.53	Full Depth Patching and Double Seal and Fog Seal	$21,160
2027	13	012-Burke	Preservation	SR 1828 (TEAGUE AVENUE)	SR 1765 (BERRY ROAD)	END OF MAINTENANCE	0.21	Full Depth Patching and Double Seal and Fog Seal	$18,000
2027	13	012-Burke	Preservation	SR 1841 (CHERRYVALE AVENUE)	BEGIN MAINTENANCE	END OF MAINTENANCE	0.21	Full Depth Patching and Double Seal and Fog Seal	$12,600
2027	13	012-Burke	Preservation	SR 1847 (MANUAEL AVENUE)	SR 1786 (MILLER BRIDGE ROAD)	END OF MAINTENANCE	0.20	Full Depth Patching and Double Seal and Fog Seal	$15,555
2027	13	012-Burke	Preservation	SR 1855 (BARUS POND LOOP 2)	SR 1737 (FLAT GAP ROAD)	END MILE POST	0.61	Full Depth Patching and Double Seal and Fog Seal	$21,000
2027	13	012-Burke	Preservation	SR 1899 (G.W. ABEE STREET)	SR 1744 (MINERAL SPRINGS MOUNTAIN ROAD)	DEAD END	0.34	Full Depth Patching and 1.0" S4.75A	$69,000
2027	13	012-Burke	Preservation	SR 2527 (EASY STREET)	SR 1807 (ROGERS ROAD)	END OF MAINTENANCE	0.11	Full Depth Patching and Double Seal and Fog Seal	$8,999
2027	13	012-Burke	Preservation	SR 2544 (OAK KNOLL)	CUL DE SAC	CUL DE SAC	0.11	Full Depth Patching and 1.0" S4.75A	$22,500
2027	13	012-Burke	Preservation	SR 2545 (CREEKSIDE LANE)	SR 1890 (I 40 ASCCESS ROAD)	SR 2544 (OAK KNOLL)	0.21	Full Depth Patching and 1.0" S4.75A	$26,000
2027	13	012-Burke	Preservation	SR 2546 (LAUREL COURT)	SR 2545 (CREEKSIDE LANE)	CUL DE SAC	0.07	Full Depth Patching and 1.0" S4.75A	$15,455
2027	13	057-Madison	Resurfacing	NC 212	SR 1314 (CUTSHALL TOWN ROAD)	TENN STATE LINE	5.31	Full Depth Patching and 1.5" S9.5B	$1,149,000
2027	13	057-Madison	Resurfacing	SR (1318 BIG LAUREL ROAD)	SR 1316 (CHAPEL HILL ROAD)	R 1395 (WALNUT MOUNTAIN ROAI	5.76	Full Depth Patching and 1.5" S9.5C	$1,135,795
2027	13	057-Madison	Resurfacing	SR 1370 (GRAPEVINE ROAD)	NC 213	SR 1364 (EAST FORK ROAD)	1.27	Full Depth Patching and 1.5" S9.5C	$177,250
2027	13	057-Madison	Resurfacing	US 23 ALTERNATE	US 19 EAST	SR 1636 US 23	7.64	Full Depth Patching and 1.5" S9.5C	$3,594,499
2027	13	057-Madison	Resurfacing	US 25/70	MILEPOST 4.2	SR 1137 (ROBERTS HILL ROAD)	2.76	Full Depth Patching and 1.5" S9.5C	$702,555
2027	13	057-Madison	Preservation	SR 1576 (ELLER FORD/BEND OF IVY ROAD)	BUNCOMBE COUNTY LINE	RIDGE ABUTMENT:NUMBER 56004	2.85	Full Depth Patching and Double Seal and Fog Seal	$205,599
2027	13	057-Madison	Preservation	SR 1578 (BOONE FARM ROAD)	SR 1611 (SILVER MILL ROAD)	END OF MAINTENANCE	0.32	Full Depth Patching and Double Seal and Fog Seal	$19,550
2027	13	057-Madison	Preservation	SR 1611 (SILVER MILL ROAD)	NC 213	NC 213	2.48	Full Depth Patching and Double Seal and Fog Seal	$199,995
2027	13	059-McDowell	Resurfacing	NC 126	US 221	SR 1575 +1.259 MILES	2.00	2.5" I19.0B and 1.5" S9.5C	$867,000
2027	13	059-McDowell	Resurfacing	NC 126	SR 1575 +1.259 MILES	BURKE COUNTY LINE	1.84	2.5" I19.0B and 1.5" S9.5B	$854,344
2027	13	059-McDowell	Resurfacing	NC 183	US 221	BURKE COUNTY LINE	0.15	Full Depth Patching and 1.5" S9.5C	$27,750
2027	13	059-McDowell	Resurfacing	R 1147 (BETHEL CHURCH / LAWING ROAD	SR 1148 (BEAVER CREEK ROAD)+ 1.181	DEAD END	1.20	Full Depth Patching and 1.5" S9.5C	$201,222
2027	13	059-McDowell	Resurfacing	SR 1147 (BETHEL CHURCH ROAD)	SR 1351 (MUD CUT ROAD) + 0.113	1148 (BEAVER CREEK ROAD)+ 1.18	2.00	Full Depth Patching and 1.5" S9.5C	$345,450
2027	13	059-McDowell	Resurfacing	SR 1147 (OLD NEAL ROAD)	SR 1153 (GOOSE CREEK ROAD)	SR 1351 (MUD CUT ROAD) + 0.113	2.00	Full Depth Patching and 1.5" S9.5C	$355,656
2027	13	059-McDowell	Resurfacing	SR 1148 (BEAVER CREEK ROAD)	SR 1147 (BETHEL CHURCH ROAD)	SR 1150 (SPOOKY HOLLOW ROAD)	1.22	Full Depth Patching and 1.5" S9.5C	$243,345
2027	13	059-McDowell	Resurfacing	SR 1150 (SPOOKY HOLLOW ROAD)	US 221	END OF MAINTENANCE	1.19	Full Depth Patching and 1.5" S9.5C	$275,221
2027	13	059-McDowell	Resurfacing	SR 1351 (MUD CUT ROAD)	SR 1001 (SUGAR HILL ROAD)	R 1145 (ROCK HOUSE ROAD)+0.33	2.00	Full Depth Patching and 1.5" S9.5C	$288,750
2027	13	059-McDowell	Resurfacing	SR 1351 (MUD CUT ROAD)	SR 1145 (ROCK HOUSR ROAD)+0.334	US 221	1.84	Full Depth Patching and 1.5" S9.5C	$285,450
2027	13	059-McDowell	Resurfacing	SR 1539 (ROLANDS CHAPEL ROAD)	SR 1536 (OLD NC 10 EAST)	US 70	1.01	Full Depth Patching and 1.5" S9.5C	$135,550
2027	13	059-McDowell	Resurfacing	SR 1540 (TWIN OAKES DRIVE)	SR 1536 (OLD NC 10 EAST)	SR 1583 (JOHN SWOFFORD ROAD)	0.16	Full Depth Patching and 1.5" S9.5C	$22,250
2027	13	059-McDowell	Resurfacing	SR 1583 (JOHN SWOFFORD ROAD)	SR 1540 (OLD NC10)	SR 1539 (ROLANDS CHAPEL ROAD)	0.91	Full Depth Patching and 1.5" S9.5C	$135,000
2027	13	059-McDowell	Resurfacing	US 64	RUTHERFORD COUNTY LINE + 2 MILES	BURKE COUNTY LINE	1.93	Full Depth Patching and 1.5" S9.5C	$506,000
2027	13	059-McDowell	Resurfacing	US 64	RUTHERFORD COUNTY LINE	RUTHERFORD CO + 2 MILES	2.00	Full Depth Patching and 1.5" S9.5C	$479,499
2027	13	059-McDowell	Resurfacing	US 70	SR 1575 + 1.259	BURKE COUNTY LINE	0.83	Full Depth Patching and 1.5" S9.5C	$192,977
2027	13	059-McDowell	Preservation	SR 1227 (CURTIS CREEK ROAD)	US 70	END OF PAVEMENT	2.70	Full Depth Patching and Double Seal and Fog Seal	$228,000
2027	13	059-McDowell	Preservation	SR 1232 (EBENEZER CHURCH ROAD)	SR 1246 (GREENLEE ROAD)	SR 1231 (EBENEZER ROAD)	1.15	Full Depth Patching and Double Seal and Fog Seal	$97,000
2027	13	059-McDowell	Preservation	SR 1235 (LAKEYTOWN ROAD)	RAILROAD STREET	SR 1237 (WILDLIFE LAKE ROAD)	2.28	Full Depth Patching and Double Seal and Fog Seal	$192,000
2027	13	059-McDowell	Preservation	SR 1410 (CANE CREEK ROAD)	US 70	US 70	1.54	Full Depth Patching and Double Seal and Fog Seal	$130,000
2027	13	059-McDowell	Preservation	SR 1413 (BURNETTE ROAD)	US 70	END OF MAINTENANCE	0.75	Full Depth Patching and Double Seal and Fog Seal	$63,000
2027	13	059-McDowell	Preservation	SR 1414 (MAPLE HILL DRIVE)	SR 1413 (BURNETTE ROAD)	END OF MAINTENANCE	0.61	Full Depth Patching and Double Seal and Fog Seal	$52,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	13	061-Mitchell	Resurfacing	NC 197	SR 1321 (POPLAR CREEK ROAD)+ 0.457 MILES	TENN STATE LINE	2.41	Full Depth Patching and 1.5" S9.5C	$557,000
2027	13	061-Mitchell	Resurfacing	NC 226	NC 197	SR 1325 (BEANS CREEK ROAD)	3.58	Full Depth Patching and 1.5" S9.5C	$779,955
2027	13	061-Mitchell	Resurfacing	SR 1104 (CHESTNUT GROVE ROAD)	SR 1100 (MKINNEY MINE ROAD)	END OF PAVEMENT	1.05	Full Depth Patching and 1.5" S9.5C	$190,000
2027	13	061-Mitchell	Resurfacing	SR 1143 (BEAVER CREEEK ROAD)	US 19	I0 (UPPER HANGING ROCK ROAD)+	1.47	Full Depth Patching and 1.5" S9.5C	$305,000
2027	13	061-Mitchell	Resurfacing	SR 1144 (STAFFORD ROAD)	BEGIN MAINTENANCE	END OF MAINTENANCE	0.35	Full Depth Patching and 1.5" S9.5C	$75,545
2027	13	061-Mitchell	Resurfacing	SR 1154 (CLIFF BUCHANAN ROAD)	SR 1236 (OLD US 19E)	END OF MAINTENANCE	0.12	Full Depth Patching and 1.5" S9.5C	$24,776
2027	13	061-Mitchell	Resurfacing	SR 1155 (NED HUGHES ROAD)	US19E	END OF MAINTENANCE	0.19	Full Depth Patching and 1.5" S9.5C	$14,000
2027	13	061-Mitchell	Resurfacing	SR 1163 (DEER PARK LAKE ROAD)	SR 1162 (PENLAND ROAD)	END OF MAINTENANCE	0.78	Full Depth Patching and 1.5" S9.5C	$125,000
2027	13	061-Mitchell	Resurfacing	SR 1212 (SANDY BRANCH ROAD)	BEGIN PAVEMENT	SR 1211 (CANE CREEK ROAD)	0.59	Full Depth Patching and 1.5" S9.5C	$85,000
2027	13	061-Mitchell	Resurfacing	SR 1213 (SANDY BRANCH ROAD)	SR 1211 (CANE CREEK ROAD)	END OF PAVEMENT	0.53	Full Depth Patching and 1.5" S9.5C	$75,000
2027	13	061-Mitchell	Resurfacing	1403 (ATTY JOHN PETERSON /ROAN ROA	NC 226	SR 1275 (OAK AVENUE)	1.94	Full Depth Patching and 1.5" S9.5C	$560,999
2027	13	061-Mitchell	Preservation	SR 1123 (DAVENPORT ROAD)	SR 1121 (ALTAPASS HIGHWAY)	END OF MAINTENANCE	0.92	Full Depth Patching and Double Seal and Fog Seal	$78,000
2027	13	061-Mitchell	Preservation	SR 1126 (JACKSON TOWN ROAD)	BLUE RIDGE PARKWAY	END OF PAVEMENT	2.87	Full Depth Patching and Double Seal and Fog Seal	$242,000
2027	13	061-Mitchell	Preservation	SR 1127 (BLUE RIDGE CHURCH ROAD)	SR 11127 (BLUE RIDGE CHURCH ROAD)	END OF PAVEMENT	0.14	Full Depth Patching and Double Seal and Fog Seal	$12,000
2027	13	081-Rutherford	Resurfacing	RAILROAD AVENUE	US 64	US 221 ALTERNATE	1.54	Mill 1.5" and 1.5" S9.5C	$456,562
2027	13	081-Rutherford	Resurfacing	SR 1502 (PINE TREE ROAD)	SR 1501 (CONEY ISLAND ROAD)	END OF MAINTENANCE	0.30	Full Depth Patching and 1.25" S9.5B	$42,250
2027	13	081-Rutherford	Resurfacing	SR 1503 (BARNES ROAD)	SR 1510 (HUDLOW ROAD)	DEAD END	0.20	Full Depth Patching and 1.5" S9.5C	$25,550
2027	13	081-Rutherford	Resurfacing	SR 1512 (CAMP CREEK ROAD)	SR 1504 (CENTENNIAL ROAD)	US 64	6.87	Full Depth Patching and 1.5" S9.5C	$1,082,500
2027	13	081-Rutherford	Resurfacing	SR 1516 (ROBERTSON ROAD)	US 64	US 64	0.32	Full Depth Patching and 1.5" S9.5C	$40,000
2027	13	081-Rutherford	Resurfacing	SR 1528 (JUSTICE ROAD)	SR 1527 (OAK SPRINGS ROAD)	END OF MAINTENANCE	0.41	Full Depth Patching and 1.5" S9.5C	$55,450
2027	13	081-Rutherford	Resurfacing	SR 1536 (OLD US 221 NORTH HIGHWAY)	US 221	US 64	1.80	Full Depth Patching and 1.5" S9.5C	$255,500
2027	13	081-Rutherford	Resurfacing	'6 (CHERRY MOUNTAIN / WEST CHURCH S	CROWE PARK ROAD (CITY)	SR 1583 (BRICK ROAD)	1.21	Full Depth Patching and 1.25" S9.5B	$175,325
2027	13	081-Rutherford	Resurfacing	SR 1576 (CHERRY MOUNTAIN STREET)	TRADE STREET	END CURB AND GUTTER	0.27	Full Depth Patching and 1.25" S9.5B	$50,125
2027	13	081-Rutherford	Resurfacing	SR 1576 (CHERRY MOUNTAIN STREET)	END CURB AND GUTTER	CROWE PARK ROAD (CITY)	0.77	Full Depth Patching and 1.25" S9.5B	$105,500
2027	13	081-Rutherford	Resurfacing	SR 1576 (WEST CHURCH STREET)	SR 1583 (BRICK ROAD)	1006 (BOSTIC SUNSHINE HIGHWA	0.63	Full Depth Patching and 1.25" S9.5B	$89,250
2027	13	081-Rutherford	Resurfacing	SR 1583 (BRICK ROAD)	SR 1576 (CHERRY MOUNTAIN STREET)	SR 1561 (PEARIDGE ROAD)	0.44	Full Depth Patching and 1.5" S9.5C	$55,255
2027	13	081-Rutherford	Resurfacing	SR 1585 (HORN BOTTOM ROAD)	WATER PLANT DRIVEWAY	END CURB AND GUTTER	0.70	Full Depth Patching and 1.5" S9.5C	$101,500
2027	13	081-Rutherford	Resurfacing	SR 1585 (HORN BOTTOM ROAD)	SR 1549 (LINCOLN ROAD)	WATER PLANT DRIVEWAY	2.29	Full Depth Patching and 1.5" S9.5C	$419,000
2027	13	081-Rutherford	Resurfacing	SR 1585 (HORN BOTTOM ROAD)	END CURB AND GUTTER	US 74 BUSINESS	0.25	Full Depth Patching and 1.5" S9.5C	$55,450
2027	13	081-Rutherford	Resurfacing	SR 1594 (HUTCHINS HOLLOW ROAD)	SR 1538 (WHITESIDES ROAD)	END MAINTENANCE	0.15	Full Depth Patching and 1.5" S9.5C	$20,050
2027	13	081-Rutherford	Resurfacing	SR 1602 (BOY SCOUT ROAD)	BRIDGE	SR 1504 (CENTENNIAL ROAD)	1.27	Full Depth Patching and 1.25" S9.5B	$222,000
2027	13	081-Rutherford	Resurfacing	SR 1602 (BOY SCOUT ROAD)	SR 1510 (HUDLOW ROAD)	BRIDGE	1.50	Full Depth Patching and 1.5" S9.5C	$277,000
2027	13	081-Rutherford	Resurfacing	SR 1810 (MOUNT VERNON CEMETERY)	SR 1510 (HUDLOW ROAD)	END MAINTENANCE	0.31	1.5" S9.5C	$33,255
2027	13	081-Rutherford	Preservation	SR 1568 (BURNS ROAD)	US 74 BUSINESS	SR 1569 (HUSKEY ROAD)	0.73	Full Depth Patching and Double Seal and Fog Seal	$62,000
2027	13	081-Rutherford	Preservation	SR 1569 (HUSKEY ROAD)	SR 1007 (PINEY MOUNTAIN CHURCH ROAD)	SR 1568 (BURNS ROAD) + .94 MILES	0.96	Full Depth Patching and Double Seal and Fog Seal	$65,550
2027	13	081-Rutherford	Preservation	SR 1574 (TINEY ROAD)	SR 1571 (PINEHURST ROAD) + .439 MILES	SR 1595 (OLD US 74 HIGHWAY)	1.57	Full Depth Patching and Double Seal and Fog Seal	$122,355
2027	13	081-Rutherford	Preservation	SR 1574 (TINEY ROAD)	SR 1007 (PINEY MOUNTAIN CHURCH ROAD)	1571 (PINEHURST ROAD) + .439 MI	2.00	Full Depth Patching and Double Seal and Fog Seal	$155,650
2027	13	081-Rutherford	Preservation	SR 1577 (CROSS ROAD)	SR 1595 (OLD US 74 HIGHWAY)	SR 1576 (EAST HIGH ROAD)	0.35	Full Depth Patching and Double Seal and Fog Seal	$22,250
2027	13	081-Rutherford	Preservation	SR 1734 (CROW WOODS ROAD)	SR 1733 (JONESTOWN ROAD)	NC 226	1.22	Seal - Double and Fog Seal	$34,445
2027	13	081-Rutherford	Preservation	SR 1757 (JACK MOORE MOUNTAIN ROAD)	SR 1749 (HOLLIS ROAD)	SR 1753 (HINTON CREEK)	1.68	Seal - Double and Fog Seal	$56,565
2027	13	081-Rutherford	Preservation	1758 (JACK MOORE MOUNTAIN ROAD EX	CLEVELAND COUNTY	SR 1753 (HINTON CREEK)	0.36	Seal - Double and Fog Seal	$10,999
2027	13	081-Rutherford	Preservation	SR 1760 (HOPEWELL ROAD)	CLEVELAND COUNTY	SR 1749 (HOLLIS ROAD)	2.30	Seal - Double and Fog Seal	$89,995
2027	13	081-Rutherford	Preservation	SR 1765 (EVANS EDWARDS ROAD)	SR 1762 (NEW HOUSE ROAD)	SR 1749 (HOLLIS ROAD)	1.56	Seal - Double and Fog Seal	$65,050
2027	13	081-Rutherford	Preservation	SR 1768 (PIINEY MOUNTAIN ROAD)	SR 1770 (WALLS CHURCH ROAD)	007 (PINEY MOUNTAIN CHURCH R(	0.93	Seal - Double and Fog Seal	$34,445
2027	13	081-Rutherford	Preservation	SR 1777 (SHORT ROAD)	SR 1749 (HOLLIS ROAD)	END OF MAINTENANCE	1.56	Seal - Double and Fog Seal	$45,550
2027	13	081-Rutherford	Preservation	SR 1781 (EAST BUTLER ROAD)	SR 1762 (NEWHOUSE ROAD)	SR 1782 (EDLEY TONEY ROAD)	1.31	Seal - Double and Fog Seal	$45,550
2027	13	081-Rutherford	Preservation	SR 1786 (GLOVER ROAD)	SR 1749 (HOLLIS ROAD)	SR 1769 (SALEM CHURCH ROAD)	1.21	Seal - Double and Fog Seal	$45,550
2027	13	081-Rutherford	Preservation	SR 1788 (BLACK ROAD)	SR 1762 (NEW HOUSE ROAD)	DEAD END	0.61	Seal - Double and Fog Seal	$19,995
2027	13	100-Yancey	Resurfacing	NC 80	SR 1158 (COBERTS CREEK ROAD)	SR 1152 (BLUE ROCK ROAD)	4.26	Full Depth Patching and 1.5" S9.5C	$1,125,254
2027	13	100-Yancey	Resurfacing	SR 1116 (BALL ROAD)	PAVEMENT CHANGE	DEAD END	0.24	Full Depth Patching and 1.5" S9.5B	$44,450
2027	13	100-Yancey	Resurfacing	SR 1308 (DOUBLE ISLAND ROAD)	SR 1315 (COW BRANCH ROAD)	SR 1313 (RIDGE ROAD)	1.27	Full Depth Patching and 1.5" S9.5C	$204,777
2027	13	100-Yancey	Resurfacing	SR 1369 (NORTH MAIN STREET)	SR 1369 (GREEN MOUNTAIN DRIVE)	TOWN SQUARE	0.27	Full Depth Patching and 1.5" S9.5C	$57,775
2027	13	100-Yancey	Resurfacing	SR 1373 (MITCHELL BRANCH ROAD)	SR 1428 (EAST MAIN STREET)	END OF MAINTENANCE	0.88	Full Depth Patching and 1.5" S9.5C	$134,450
2027	13	100-Yancey	Resurfacing	SR 1393 (LICKSKILLET ROAD)	PAVEMENT JOINT AT US 19	1.51 +.11 MILE IS END OF PAVEMI	1.51	Full Depth Patching and 1.5" S9.5C	$185,550
2027	13	100-Yancey	Resurfacing	SR 1428 (EAST MAIN STREET)	TOWN SQUARE	END 24' PAVEMENT	1.14	Full Depth Patching and 1.5" S9.5C	$239,000
2027	13	100-Yancey	Resurfacing	SR 1429 (PENSACOLA ROAD)	US 19E	SR 1428 (EAST MAIN STREET)	0.10	Full Depth Patching and 1.5" S9.5C	$15,550
2027	13	100-Yancey	Resurfacing	US 19E	NC 197N	1143 (LOWER GEORGES FORK ROA	1.18	Full Depth Patching and 1.5" S9.5C	$580,200
2027	13	100-Yancey	Resurfacing	US 19E	NC 197N	1143 (LOWER GEORGES FORK ROA	0.14	Full Depth Patching and 1.5" S9.5C	$72,467
2027	13	100-Yancey	Preservation	SR 1312 (UPPER DOE BAG ROAD)	SR 1308 (DOUBLE ISLAND ROAD)	END OF PAVEMENT	1.44	Full Depth Patching and Double Seal and Fog Seal	$108,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	13	100-Yancey	Preservation	SR 1313 (RIDGE ROAD)	SR 1308 (DOUBLE ISLAND ROAD)	SR 1308 (DOUBLE ISLAND ROAD)	2.97	Full Depth Patching and Double Seal and Fog Seal	$215,445
2027	13	100-Yancey	Preservation	SR 1317 (BIG BRUSH CREEK ROAD)	SR 1308 (DOUBLE ISLAND ROAD)	SR 1308 (DOUBLE ISLAND ROAD)	3.73	Full Depth Patching and Double Seal and Fog Seal	$279,750
2027	14	020-Cherokee	Resurfacing	SR 1326	Tenn St.	SR 1365	1.77	Leveling and 1.5" S9.5B	$485,650
2027	14	020-Cherokee	Resurfacing	SR 1556	SR 1558	SR 1564	4.50	1.25" SF9.5A	$1,237,500
2027	14	020-Cherokee	Resurfacing	SR 1576	SR 1305	SR 1580	1.28	1.25" SF9.5A	$352,000
2027	14	020-Cherokee	Preservation	SR 1142	SR 1141	END MAINT	0.60	Seal - Double and Fog Seal	$41,720
2027	14	020-Cherokee	Preservation	SR 1300	US 64	SR 1303	2.37	Seal - Double and Fog Seal	$165,900
2027	14	020-Cherokee	Preservation	SR 1301	US 64	US 64	0.68	Seal - Double and Fog Seal	$47,810
2027	14	020-Cherokee	Preservation	SR 1385	SR 1386	EOM	0.30	Seal - Double and Fog Seal	$21,000
2027	14	020-Cherokee	Preservation	SR 1388	US 19	EOP	2.15	Seal - Double and Fog Seal	$150,500
2027	14	020-Cherokee	Preservation	SR 1399	SR 1391	EOM	0.29	Seal - Double and Fog Seal	$20,300
2027	14	020-Cherokee	Preservation	SR 1410	SR 1389	EOM	0.12	Seal - Double and Fog Seal	$8,400
2027	14	020-Cherokee	Preservation	SR 1595	NC 60	SR 1593	0.87	Seal - Double and Fog Seal	$61,110
2027	14	020-Cherokee	Preservation	SR 1670	NC 141	SR 1533	0.94	Seal - Double and Fog Seal	$65,800
2027	14	022-Clay	Resurfacing	SR 1115	US 69	GA line	1.46	Patching and Leveling and 1.5" S9.5B	$401,500
2027	14	022-Clay	Resurfacing	SR 1150	HWY 175	End of Maint.	0.78	Full Depth Patching and 1.5" S9.5B	$214,500
2027	14	022-Clay	Resurfacing	SR 1200	SR 1159	End of Maint.	0.87	1.5" S9.5B	$239,250
2027	14	022-Clay	Preservation	SR 1151	US 64	END MAINT	0.98	Seal - Double and Fog Seal	$68,390
2027	14	022-Clay	Preservation	SR 1193	SR 1157	SR 1157 + .13 Miles	0.13	Seal - Double and Fog Seal	$9,100
2027	14	022-Clay	Preservation	SR 1339	US 64	EOP	1.19	Seal - Double and Fog Seal	$83,300
2027	14	022-Clay	Preservation	SR 1361	US 64	SR 1361	2.07	Seal - Double and Fog Seal	$144,550
2027	14	038-Graham	Resurfacing	SR 1223	NC 143	EOM	2.95	1.25" S9.5B	$811,250
2027	14	038-Graham	Preservation	SR 1118	NC 143	SR 1112	1.90	Seal - Double and Fog Seal	$133,000
2027	14	038-Graham	Preservation	SR 1206	SR 1275	US 129	3.40	Seal - Double and Fog Seal	$237,650
2027	14	038-Graham	Preservation	SR 1209	SR 1275	EOM	0.11	Seal - Double and Fog Seal	$7,700
2027	14	044-Haywood	Resurfacing	SR 1505	SR 1503	EOM	4.39	Full Depth Patching and 1.5" S9.5B	$1,206,425
2027	14	044-Haywood	Resurfacing	SR 1523	End of C&G	NC 215	3.29	Full Depth Patching and 1.25" S9.5A	$904,750
2027	14	044-Haywood	Resurfacing	SR 1523	NC 215	SR 1948	0.06	Full Depth Patching and 1.25" S9.5A	$16,500
2027	14	044-Haywood	Resurfacing	SR 1808	SR 1809	Dead End	0.12	Full Depth Patching and 1.5" S9.5B	$32,725
2027	14	044-Haywood	Resurfacing	US 19	End Dvd Hwy Smathers St.	Begin Dvd HWY	0.89	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$800,000
2027	14	044-Haywood	Preservation	SR 1148	SR 1147	DEAD END	0.09	Seal - Double and Fog Seal	$6,160
2027	14	044-Haywood	Preservation	SR 1199	SR 1197	DEAD END	0.16	Seal - Double and Fog Seal	$11,200
2027	14	044-Haywood	Preservation	SR 1209	US 19	SR 1210	0.75	Seal - Double and Fog Seal	$52,500
2027	14	044-Haywood	Preservation	SR 1210	US 19	SR 1210	0.78	Seal - Double and Fog Seal	$54,600
2027	14	044-Haywood	Preservation	SR 1221	SR 1140	SR 1222	0.15	Seal - Double and Fog Seal	$10,570
2027	14	044-Haywood	Preservation	SR 1222	SR 1221	SR 1233	0.06	Seal - Double and Fog Seal	$3,920
2027	14	044-Haywood	Preservation	SR 1223	SR 1140	SR 1222	0.15	Seal - Double and Fog Seal	$10,430
2027	14	044-Haywood	Preservation	SR 1224	SR 1140	Dead End	0.22	Seal - Double and Fog Seal	$15,190
2027	14	044-Haywood	Preservation	SR 1233	SR 1223	SR 1234	0.05	Seal - Double and Fog Seal	$3,640
2027	14	044-Haywood	Preservation	SR 1235	SR 1140	SR 1234	0.07	Seal - Double and Fog Seal	$4,830
2027	14	044-Haywood	Preservation	SR 1249	SR 1243	EOP	0.12	Seal - Double and Fog Seal	$8,400
2027	14	044-Haywood	Preservation	SR 1261	SR 1210	SR 1260	0.08	Seal - Double and Fog Seal	$5,600
2027	14	044-Haywood	Preservation	SR 1263	SR 1260	SR 1265	0.41	Seal - Double and Fog Seal	$28,700
2027	14	044-Haywood	Preservation	SR 1265	US 19	SR 1263	0.31	Seal - Double and Fog Seal	$21,560
2027	14	044-Haywood	Preservation	SR 1266	SR 1209	SR 1209	0.39	Seal - Double and Fog Seal	$27,300
2027	14	044-Haywood	Preservation	SR 1400	BOM	DEAD END	0.09	Seal - Double and Fog Seal	$6,300
2027	14	044-Haywood	Preservation	SR 1406	SR 1392	DEAD EAD	0.16	Seal - Double and Fog Seal	$11,480
2027	14	044-Haywood	Preservation	SR 1516	SR 1513	DEAD END	0.16	Seal - Double and Fog Seal	$11,200
2027	14	044-Haywood	Preservation	SR 1517	SR 1654	DEAD END	0.31	Seal - Double and Fog Seal	$21,980
2027	14	044-Haywood	Preservation	SR 1533	SR 1513	SR 1519	0.06	Seal - Double and Fog Seal	$3,990
2027	14	044-Haywood	Preservation	SR 1542	SR 1513	EOP	0.22	Seal - Double and Fog Seal	$15,330
2027	14	044-Haywood	Preservation	SR 1547	SR 1546	DEAD END	0.33	Seal - Double and Fog Seal	$23,100
2027	14	044-Haywood	Preservation	SR 1851	SR 1858	SR 1854	0.90	Seal - Double and Fog Seal	$63,210
2027	14	044-Haywood	Preservation	SR 1861	SR 1847	EOP	0.59	Seal - Double and Fog Seal	$41,300
2027	14	044-Haywood	Preservation	SR 1862	NC 110	EOM	0.53	Seal - Double and Fog Seal	$37,240
2027	14	044-Haywood	Preservation	SR 1868	SR 1867	NC 110	0.58	Seal - Double and Fog Seal	$40,740
2027	14	044-Haywood	Preservation	SR 1870	SR 1871	EOP	0.73	Seal - Double and Fog Seal	$51,030
2027	14	044-Haywood	Preservation	SR 1871	SR 1870	EOP	0.51	Seal - Double and Fog Seal	$35,840
2027	14	044-Haywood	Preservation	SR 1872	NC 110	SR 1871	0.72	Seal - Double and Fog Seal	$50,050

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	14	044-Haywood	Preservation	SR 1873	SR 1871	DEAD END	0.08	Seal - Double and Fog Seal	$5,670
2027	14	044-Haywood	Preservation	SR 1910	NC 110	EOM	0.33	Seal - Double and Fog Seal	$23,380
2027	14	045-Henderson	Resurfacing	SR 1314	SR 1331	US 64	1.55	Leveling and 1.5" S9.5B	$426,250
2027	14	045-Henderson	Resurfacing	SR 1332	SR 1426	NC 280	0.40	1.25" S9.5B	$110,275
2027	14	045-Henderson	Resurfacing	SR 1340	SR 1338	EOM	1.00	Leveling and 1.5" S9.5B	$274,725
2027	14	045-Henderson	Resurfacing	SR 1347	SR 1345	EOM	1.00	1.5" S9.5B	$275,000
2027	14	045-Henderson	Resurfacing	SR 1426	NC 191	NC 280	1.91	1.5" S9.5B and Widen	$523,875
2027	14	045-Henderson	Resurfacing	SR 1478	SR 1323	SR 1323	0.30	1.25" S9.5B	$82,500
2027	14	045-Henderson	Resurfacing	SR 1488	US 64	SR 1323	0.53	1.25" S9.5B	$146,850
2027	14	045-Henderson	Resurfacing	SR 2006	SR 1323	EOM	0.26	1.25" S9.5B	$70,125
2027	14	045-Henderson	Resurfacing	SR 2029	SR 1322	SR 1323	0.80	1.5" S9.5B	$219,175
2027	14	045-Henderson	Resurfacing	SR 2135	US 64	SR 2135	0.20	1.25" S9.5B	$55,000
2027	14	045-Henderson	Resurfacing	SR 2229	SR 1323	EOM	0.47	1.25" S9.5B	$129,250
2027	14	045-Henderson	Resurfacing	SR 2251	SR 1488	SR 1488	0.20	1.25" S9.5B	$55,000
2027	14	045-Henderson	Resurfacing	SR 2252	SR 1488	SR 1488	0.46	1.25" S9.5B	$126,225
2027	14	045-Henderson	Resurfacing	SR 2262	SR 1488	EOM	0.09	1.25" S9.5B	$25,850
2027	14	045-Henderson	Resurfacing	US 176	SR 1783 N Highland Lk	Begin Dvd Hwy	2.38	Mill 1.5" and 1.5" S9.5C	$2,000,000
2027	14	045-Henderson	Resurfacing	US 176 E	Begin Divided Hwy	End Divided Hwy	0.48	Full Depth Patching and 1.5" S9.5C	$250,000
2027	14	045-Henderson	Resurfacing	US 176 W	Begin Divided Hwy	End Divided Hwy	0.48	Full Depth Patching and 1.5" S9.5C	$250,000
2027	14	045-Henderson	Preservation	SR 1196	SR 1127	SR 1191	3.96	Seal - Double and Fog Seal	$277,480
2027	14	045-Henderson	Preservation	SR 1309	SR 2415	US 64	2.79	Seal - Double and Fog Seal	$195,300
2027	14	045-Henderson	Preservation	SR 1312	SR 1309	US 64	1.09	Seal - Double and Fog Seal	$76,300
2027	14	045-Henderson	Preservation	SR 1335	SR 1338	SR 1328	0.92	Seal - Double and Fog Seal	$64,470
2027	14	045-Henderson	Preservation	SR 1365	NC 191	SR 1345	2.97	Seal - Double and Fog Seal	$207,900
2027	14	045-Henderson	Preservation	SR 1395	SR 1383	NC 191	0.67	Seal - Double and Fog Seal	$46,900
2027	14	045-Henderson	Preservation	SR 1698	US 64	SR 1699	1.03	Seal - Double and Fog Seal	$72,100
2027	14	045-Henderson	Preservation	SR 1699	SR 2271	SR 1698	0.41	Seal - Double and Fog Seal	$28,700
2027	14	045-Henderson	Preservation	SR 2202	US 64	SR 2206	0.58	Seal - Double and Fog Seal	$40,600
2027	14	045-Henderson	Preservation	SR 2204	SR 1309	SR 2205	0.39	Seal - Double and Fog Seal	$27,300
2027	14	045-Henderson	Preservation	SR 2205	SR 2204	EOP	0.23	Seal - Double and Fog Seal	$16,100
2027	14	045-Henderson	Preservation	SR 2271	US 64	EOP	0.68	Seal - Double and Fog Seal	$47,600
2027	14	045-Henderson	Preservation	SR 2285	SR 2271	EOP	0.10	Seal - Double and Fog Seal	$6,930
2027	14	045-Henderson	Preservation	SR 2295	SR 2271	EOP	0.12	Seal - Double and Fog Seal	$8,400
2027	14	045-Henderson	Preservation	SR 2415	NC 191	SR 1309	0.09	Seal - Double and Fog Seal	$6,230
2027	14	045-Henderson	Preservation	SR 2419	SR 2271	EOP	0.09	Seal - Double and Fog Seal	$6,300
2027	14	050-Jackson	Resurfacing	NC 107	US 64	Pvmt Change	11.57	Full Depth Patching and 1.5" S9.5C	$7,750,000
2027	14	050-Jackson	Resurfacing	SR 1307	US 441	EOM	1.01	Full Depth Patching and 1.25" S9.5A	$277,750
2027	14	050-Jackson	Resurfacing	SR 1446	SR 1432	EOP	2.14	Full Depth Patching and 1.25" S9.5A	$588,500
2027	14	050-Jackson	Resurfacing	SR-1144	SR-1145	EOP	1.00	Full Depth Patching and 1.5" S9.5B	$275,000
2027	14	050-Jackson	Resurfacing	US 64	NC 107 + 0.06 Miles	Pvmt Change 2 to 3 Lane	1.23	Full Depth Patching and 1.5" S9.5C	$775,000
2027	14	050-Jackson	Resurfacing	US 64	Pvmt Change 2 to 3 Lane	Pvmt Change 3 to 2 Lane	0.42	Full Depth Patching and 1.5" S9.5C	$350,000
2027	14	050-Jackson	Preservation	SR 1107	Macon Co. Line	NC 107	6.83	Seal - Double and Fog Seal	$478,030
2027	14	056-Macon	Resurfacing	SR 1319	SR 1442	EOM	1.10	1.25" S9.5B	$302,500
2027	14	056-Macon	Resurfacing	SR 1636	US 23	SR 1638	5.16	Full Depth Patching and 1.25" S9.5B	$1,419,000
2027	14	056-Macon	Resurfacing	US 441 Bus.	W. Main St.	SR 1442 (W. Palmer St)	0.06	Mill 1.5" and 1.5" S9.5C	$16,500
2027	14	056-Macon	Resurfacing	US 441 Bus.	SR 1724 (Big Bear Ln)	Porter St.	0.76	Mill 1.5" and 2.5" I19.0C and 1.5" S9.5C	$209,000
2027	14	056-Macon	Preservation	SR 1119	US 441	EOP	0.09	Seal - Double and Fog Seal	$6,300
2027	14	056-Macon	Preservation	SR 1633	US 23	SR 1632	1.21	Seal - Double and Fog Seal	$84,700
2027	14	056-Macon	Preservation	SR 1635	SR 1636	SR 1727 + 2.1 Miles	2.99	Seal - Double and Fog Seal	$209,300
2027	14	056-Macon	Preservation	SR 1639	SR 1639	Dead End	0.62	Seal - Double and Fog Seal	$43,400
2027	14	056-Macon	Preservation	SR 1643	SR 1653	SR 1645 + 0.081 miles	0.78	Seal - Double and Fog Seal	$54,880
2027	14	056-Macon	Preservation	SR 1669	US 64	Dead End	0.53	Seal - Double and Fog Seal	$37,100
2027	14	056-Macon	Preservation	SR 1698	SR 1668	Dead End	0.40	Seal - Double and Fog Seal	$28,000
2027	14	056-Macon	Preservation	SR 1700	SR 1702	EOM	0.28	Seal - Double and Fog Seal	$19,600
2027	14	056-Macon	Preservation	SR 1714	SR 1696	X-Cross	0.35	Seal - Double and Fog Seal	$24,500
2027	14	056-Macon	Preservation	SR 1726	SR 1629	SR 1683	1.58	Seal - Double and Fog Seal	$110,670
2027	14	075-Polk	Resurfacing	SR 1147	MP 0.81	SR 1006	1.25	1.25" S9.5B	$375,000
2027	14	075-Polk	Resurfacing	SR 1359	SR 1004	SR 1004	1.47	1.25" S9.5B	$441,000
2027	14	075-Polk	Resurfacing	SR 1538	NC9	SR 1326	1.34	1.25" S9.5B	$402,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2027	14	075-Polk	Resurfacing	US 74 E	Bridge 0221 @ Exit 163	NC 9 Overpass	4.32	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$4,000,000
2027	14	075-Polk	Resurfacing	US 74 W	NC 9 Overpass	Bridge 222 @ Exit 163	4.32	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$4,000,000
2027	14	075-Polk	Preservation	SR 1006	SR 1142	SR 1147	0.50	Seal - Double and Fog Seal	$35,000
2027	14	075-Polk	Preservation	SR 1140	SR 1139	NC 9	1.27	Seal - Double and Fog Seal	$88,760
2027	14	075-Polk	Preservation	SR 1150	SR 1151	SR 1193	0.47	Seal - Double and Fog Seal	$32,900
2027	14	075-Polk	Preservation	SR 1151	SR 1142	Fish Top Parking Area	2.50	Seal - Double and Fog Seal	$175,000
2027	14	075-Polk	Preservation	SR 1193	SR 1150	EOM	0.21	Seal - Double and Fog Seal	$14,700
2027	14	075-Polk	Preservation	SR 1305	SC Line	SR 1343	1.00	Seal - Double and Fog Seal	$70,000
2027	14	087-Swain	Resurfacing	SR 1195	US 19	JACKSON CL	1.42	1.5" S9.5B	$390,225
2027	14	087-Swain	Resurfacing	SR1333	SR 1364	SR 1337	1.66	Patching and 1.25" S9.5A	$456,500
2027	14	087-Swain	Preservation	SR 1162	SR 1166	EOP	1.66	Seal - Double and Fog Seal	$116,200
2027	14	087-Swain	Preservation	SR 1322	SR 1321	SR 1323	0.48	Seal - Double and Fog Seal	$33,390
2027	14	087-Swain	Preservation	SR 1326	SR 1328	SR 1364	1.05	Seal - Double and Fog Seal	$73,360
2027	14	087-Swain	Preservation	SR 1329	SR 1364	END MAINT	1.21	Seal - Double and Fog Seal	$84,980
2027	14	087-Swain	Preservation	SR 1350	EOP	EOM	0.40	Seal - Double	$27,790
2027	14	088-Transylvania	Resurfacing	SR 1141	US 178	EOM	1.24	1.25" S9.5B	$339,625
2027	14	088-Transylvania	Resurfacing	SR 1161	US 64	SR 1110	0.44	1.25" S9.5B	$121,825
2027	14	088-Transylvania	Resurfacing	SR 1534	SR 1536	SR 1533	2.40	1.25" S9.5B	$660,000
2027	14	088-Transylvania	Resurfacing	SR 1536	SR 1528	SR 1534	1.30	1.5" S9.5B	$357,500
2027	14	088-Transylvania	Resurfacing	SR1521	US64	SR1504	0.73	1.5" S9.5B	$200,750
2027	14	088-Transylvania	Preservation	SR 1305	NC 281	EOP	0.59	Seal - Double and Fog Seal	$41,020
2027	14	088-Transylvania	Preservation	SR 1307	NC 281	EOP	0.89	Seal - Double and Fog Seal	$62,300
2027	14	088-Transylvania	Preservation	SR 1310	SR 1326	SR1311	1.17	Seal - Double and Fog Seal	$81,900
2027	14	088-Transylvania	Preservation	SR 1314	SR 1313	EOP	0.40	Seal - Double and Fog Seal	$28,000
2027	14	088-Transylvania	Preservation	SR 1382	NC 281	EOP	0.26	Seal - Double and Fog Seal	$18,130
2027	14	088-Transylvania	Preservation	SR 1402	SR 1326	EOP	0.15	Seal - Double and Fog Seal	$10,500
2027	14	088-Transylvania	Preservation	SR 1407	NC 280	DEAD END	0.13	Seal - Double and Fog Seal	$9,310
2027	14	088-Transylvania	Preservation	SR 1559	US 276	EOP	2.66	Seal - Double and Fog Seal	$186,410
2028	1	008-Bertie	Resurfacing	NC 11	NC 308	NC 305	7.58	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,670,000
2028	1	008-Bertie	Resurfacing	NC 11	SR 1108 (Indian Woods Rd.)	NC 308	3.14	Full Depth Patching and 1.5" S9.5C	$1,003,000
2028	1	008-Bertie	Resurfacing	NC 42	NC 45	US 13	10.36	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$3,201,000
2028	1	008-Bertie	Resurfacing	SR 1002 (Quebec Rd.)	SR 1325	Hertford Co	1.96	Full Depth Patching and 1.5" S9.5B	$391,000
2028	1	008-Bertie	Resurfacing	SR 1102 (Pleasant Oak Rd.)	SR 1100 (Grabtown Rd.)	End of Pavement	0.91	Full Depth Patching and 1.5" S9.5B	$182,000
2028	1	008-Bertie	Resurfacing	SR 1102 (Pleasant Oak Rd.)	Beginning of Pavement	US 13	0.20	Full Depth Patching and 1.5" S9.5B	$41,000
2028	1	008-Bertie	Resurfacing	SR 1106 (St Francis Rd.)	SR 1100	US 13	3.62	Full Depth Patching and 1.5" S9.5B	$723,000
2028	1	008-Bertie	Resurfacing	SR 1228 (Earley Station Rd.)	US 13	SR 1246 (Sheriff Garrett Rd.)	2.79	Full Depth Patching and 1.5" S9.5B	$585,000
2028	1	008-Bertie	Resurfacing	SR 1328 (Buncombe Rd.)	SR 1329	NC 42	2.33	Full Depth Patching and 1.5" S9.5B	$465,000
2028	1	008-Bertie	Resurfacing	SR 1335 (River St.)	Begin Pavement	Begin C&G	0.58	Full Depth Patching and 1.5" S9.5B	$174,000
2028	1	008-Bertie	Resurfacing	SR 1335 (River St.)	NC 45	Begin C&G	0.56	Mill 1.5" and 1.5" S9.5B	$198,000
2028	1	008-Bertie	Resurfacing	SR 1501 (Bal Gra Rd.)	End Maint	US 17	2.59	Full Depth Patching and 1.5" S9.5B	$517,000
2028	1	008-Bertie	Resurfacing	SR 1507 (Peterson Church Rd.)	SR 1502	SR 1540	1.56	Full Depth Patching and 1.5" S9.5B	$311,000
2028	1	008-Bertie	Resurfacing	US 13	Bridge #51	SR 1257 (School Rd.)	2.09	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$686,000
2028	1	008-Bertie	Resurfacing	US 13	US 17 Bypass	Bridge #51	0.95	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$424,000
2028	1	008-Bertie	Resurfacing	US 13 Bus.	Village Ave.	Bridge #51 Overpass	0.19	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$122,000
2028	1	008-Bertie	Preservation	SR 1203 (Moore Rd.)	SR 1200 (Connaritsa Rd.)	NC 11	0.20	Seal - Double	$10,000
2028	1	008-Bertie	Preservation	SR 1203 (Moore Rd.)	SR 1204 (72 Siding Rd.)	NC 11	4.28	Seal - Double	$214,000
2028	1	008-Bertie	Preservation	SR 1247 (Mt. Olive Rd.)	NC 308	SR 1260 (Republican Rd.)	3.31	Seal - Double	$166,000
2028	1	008-Bertie	Preservation	SR 1249 (Tyler School Rd.)	Hertford Co	SR 1207 (Wilber Howard Rd.)	1.71	Seal - Double	$77,000
2028	1	008-Bertie	Preservation	SR 1342 (Morris Ford Rd.)	SR 1312 (Meadow Rd.)	SR 1001 (Wakelon Rd.)	4.04	Seal - Double	$202,000
2028	1	008-Bertie	Preservation	SR 1353 (Academy St.)	NC 42	NC 45	0.30	Crack Seal	$2,000
2028	1	008-Bertie	Preservation	SR 1505 (Rupert Earl Rd.)	US 17	Dead End	0.52	Crack Seal	$4,000
2028	1	015-Camden	Resurfacing	SR 1145 (Trafton/Lamb's Rd.)	NC 343	SR 1203 (Scotland Rd.)	3.67	Full Depth Patching and 1.5" S9.5B	$696,000
2028	1	015-Camden	Resurfacing	SR 1204 (Whitehurst Ln.)	NC 34	US 158	2.43	Full Depth Patching and 1.5" S9.5B	$485,000
2028	1	015-Camden	Preservation	SR 1113 (Milltown Rd. / Beach Tree Dr.))	NC 343	SR 1143 (Park Dr.)	1.55	1.25" S9.5B	$170,000
2028	1	015-Camden	Preservation	SR 1143 (Park Dr.)	SR 1113 (Milltown Rd.)	SR 1113 (Milltown Rd.)	0.33	1.25" S9.5B	$37,000
2028	1	015-Camden	Preservation	SR 1144 (Shore Dr.)	SR 1113 (Shore Dr)	Dead End	0.29	1.25" S9.5B	$36,000
2028	1	021-Chowan	Resurfacing	SR 1200 (Mexico Rd. / Macedonia Rd.)	NC 32	NC 32	7.01	Full Depth Patching and 1.5" S9.5B	$1,399,000
2028	1	021-Chowan	Preservation	SR 1313 (Bear Swamp Rd.)	Perquimans County Line	Perquimans County Line	1.88	Seal - Double	$94,000
2028	1	027-Currituck	Resurfacing	SR 1214 (Guinea Rd)	SR 1222 (Tulls Creek Rd.)	NC 168	1.01	Full Depth Patching and 1.5" S9.5B	$202,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	1	027-Currituck	Resurfacing	SR 1218 (NW. Backwoods Rd.)	SR 1227 (South Mills Rd.)	Virginia State Line	3.38	Full Depth Patching and 1.5" S9.5B	$674,000
2028	1	027-Currituck	Resurfacing	SR 1266 (Richard Shaw Rd)	SR 1516 (Newton Rd)	Dead End	0.33	Full Depth Patching and 1.5" S9.5B	$66,000
2028	1	027-Currituck	Resurfacing	SR 1516 (Newton Rd)	SR 1227 (South Mills Rd.)	NC 168	0.79	Full Depth Patching and 1.5" S9.5B	$154,000
2028	1	027-Currituck	Resurfacing	SR 1516 (Shingle Landing Rd.)	SR 1222 (Tulls Creek Rd.)	NC 168	1.69	Full Depth Patching and 1.5" S9.5B	$337,000
2028	1	027-Currituck	Preservation	SR 1144	SR 1143	Dead End	0.38	Crack Seal	$5,000
2028	1	027-Currituck	Preservation	SR 1161	SR 1164	Dead End	0.08	Crack Seal	$5,000
2028	1	027-Currituck	Preservation	SR 1164	SR 1143	Dead End	0.14	Crack Seal	$5,000
2028	1	027-Currituck	Preservation	SR 1165	SR 1144	Dead End	0.30	Crack Seal	$5,000
2028	1	027-Currituck	Preservation	SR 1245 (Bells Island Rd.)	Old Oaks Dr.	Dead End	1.11	1.25" S9.5B	$135,000
2028	1	027-Currituck	Preservation	SR 1380 (Nautical Ln.)	SR 1245-Bells Island Rd.	Dead End	0.57	1.25" S9.5B	$63,000
2028	1	027-Currituck	Preservation	SR 1383 (Skippers Ln.)	SR 1380-Nautical Ln.	SR 1380-Nautical Ln.	0.20	1.25" S9.5B	$22,000
2028	1	028-Dare	Resurfacing	NC 12	Northern Buxton Town Limits	Southern Avon Town Limits	3.81	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,231,000
2028	1	028-Dare	Resurfacing	NC 345	SR 1141 (Thicket Lump Rd.)	SR 1135 (Baumtown Rd.)	1.91	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$583,000
2028	1	028-Dare	Resurfacing	SR 1137-Old Wharf Rd.	Dead End	SR 1168-Old Wharf Rd.	0.16	Full Depth Patching and 1.5" S9.5B	$29,000
2028	1	028-Dare	Resurfacing	SR 1139-Lovers Lane	NC 345	End Maint	0.40	Full Depth Patching and 1.5" S9.5B	$80,000
2028	1	028-Dare	Resurfacing	SR 1140-Harbor Rd.	NC 345	End Maint	0.98	Full Depth Patching and 1.5" S9.5B	$255,000
2028	1	028-Dare	Resurfacing	SR 1143-Tink Tllett Rd.	NC 345	NC 345	0.46	Full Depth Patching and 1.5" S9.5B	$92,000
2028	1	028-Dare	Resurfacing	SR 1144-Burrus Rd.	SR 1146-ER Daniels Rd.	NC 345	0.35	Full Depth Patching and 1.5" S9.5B	$56,000
2028	1	028-Dare	Resurfacing	SR 1145-Old Schoolhouse Rd.	SR 1168-Old Wharf Rd.	NC 345	0.45	Full Depth Patching and 1.5" S9.5B	$81,000
2028	1	028-Dare	Resurfacing	SR 1146-ER Daniels Rd.	SR 1320-Pine Rd.	SR 1145-Old Schoolhouse Rd.	0.77	Full Depth Patching and 1.5" S9.5B	$139,000
2028	1	028-Dare	Resurfacing	SR 1146-ER Daniels Rd.	Dead End	SR 1320-Pine Rd.	0.63	Full Depth Patching and 1.5" S9.5B	$114,000
2028	1	028-Dare	Resurfacing	SR 1148-Pugh Rd.	SR 1168-Old Wharf Rd.	SR 1146-ER Daniels Rd.	0.29	Full Depth Patching and 1.5" S9.5B	$53,000
2028	1	028-Dare	Resurfacing	SR 1168-Old Wharf Rd.	SR 1137-Hooker Rd.	NC 345	1.19	Full Depth Patching and 1.5" S9.5B	$238,000
2028	1	028-Dare	Resurfacing	SR 1187-Pond Rd.	SR 1137-Hooker Rd.	Dead End	0.17	Full Depth Patching and 1.5" S9.5B	$31,000
2028	1	028-Dare	Preservation	NC 12	Hatteras Ferry Dock	SR 1246-Austin Rd.	2.57	Crack Seal	$25,000
2028	1	028-Dare	Preservation	NC 12	SR 1246-Austin Rd.	Osprey Way (Pvt)	1.93	Crack Seal	$17,000
2028	1	028-Dare	Preservation	SR 1107-Old Mann's Harbor Rd.	US 64	US 64	0.71	Crack Seal	$5,000
2028	1	028-Dare	Preservation	SR 1108-Ina Waterfield Rd.	US 64	Dead End	0.17	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1110-Old Ferry Dock Rd.	US 64	Dead End	0.45	Crack Seal	$3,000
2028	1	028-Dare	Preservation	SR 1136-Old Church Rd.	SR 1168-Old Wharf Rd.	Dead End	0.29	1.0" S9.5B	$32,000
2028	1	028-Dare	Preservation	SR 1137-Owen Shipyard Rd.	SR 1168 Old Wharf Rd.	SR 1168-Old Wharf Rd.	0.39	1.0" S9.5B	$43,000
2028	1	028-Dare	Preservation	SR 1138-Tillett Rd.	Dead End	NC 345	0.34	1.0" S9.5B	$38,000
2028	1	028-Dare	Preservation	SR 1141-Thicket Lump Dr.	Dead End	SR 1142-Tucker Daniels Rd.	0.21	1.0" S9.5B	$23,000
2028	1	028-Dare	Preservation	SR 1142-The Lane	SR 1143-Tillet Rd	NC 345	0.26	1.0" S9.5B	$29,000
2028	1	028-Dare	Preservation	SR 1147-E.R. Daniels Rd.	SR 1168-Old Wharf Rd	SR 1146-E.R. Daniels Rd.	0.09	1.0" S9.5B	$10,000
2028	1	028-Dare	Preservation	SR 1160-Dare Ave.	SR 1167-Old NC 345	Dead End	0.16	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1179-Highland Dr.	US 64	Dead End	0.16	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1180-Harbor Dr.	CDS	US 64	0.23	Crack Seal	$2,000
2028	1	028-Dare	Preservation	SR 1236-C Deering Ridge Rd.	Dead End	NC 12	0.38	Crack Seal	$3,000
2028	1	028-Dare	Preservation	SR 1237-Kohler Dr.	End Maint	NC 12	0.90	Crack Seal	$5,000
2028	1	028-Dare	Preservation	SR 1238-Altona Lane	Dead End	SR 1237-Kohler Dr.	0.21	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1239-Kohler Dr.	SR 1237-Kohler Dr.	NC 12	0.02	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1248-Islington Court	Dead End	NC 12	0.15	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1253-Pricilla Curve Rd.	Dead End	SR 1237-Kohler Rd.	0.18	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1254-Stowe Landing Rd.	SR 1237-Kohler Rd.	SR 1255-MV Australia Lane	0.08	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1255-MV Australia Lane	Dead End	SR 1238-Altona Lane	0.15	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1258-Fulcher Rd.	Dead End	NC 12	0.23	Crack Seal	$2,000
2028	1	028-Dare	Preservation	SR 1266-Waltham Rd.	Dead End	NC 12	0.11	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1310-Flambeau Rd.	SR 1241-Bilt Stowe Rd.	SR 1311-Light House Rd.	0.29	Crack Seal	$2,000
2028	1	028-Dare	Preservation	SR 1311-Light House Rd.	SR 1310-Flambeau Rd.	SR 1312-Sea Scape Lane	0.06	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1312-Sea Scape Rd.	Dead End	SR 1311-light House Rd.	0.12	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1339-Hassel Rd.	SR 1105-Shipyard Rd.	Dead End	0.09	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1340-Saxton Cut Dr.	Dead End	SR 1237-Kohler Rd.	0.15	Crack Seal	$1,000
2028	1	028-Dare	Preservation	SR 1346-Croatan Way	SR 1107-Old Manns Harbor Rd.	CDS	0.31	Crack Seal	$3,000
2028	1	037-Gates	Resurfacing	NC 37	NC 32	Bridge #13	7.89	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,007,000
2028	1	037-Gates	Resurfacing	SR 1114 (Turner Rd.)	SR 1113 (White Oak Rd.)	SR 1117 (Askew Rd.)	0.94	Full Depth Patching and 1.5" S9.5B	$169,000
2028	1	037-Gates	Resurfacing	SR 1200 (Sand Banks Rd.)	SR 1226 (Jernigan Lane)	SR 1204 (Byrum Rd.)	0.63	Full Depth Patching and 1.5" S9.5B	$127,000
2028	1	037-Gates	Resurfacing	SR 1200 (Sand Banks Rd.)	SR 1226 (Jernigan Lane)	VA Line	1.30	Full Depth Patching and 1.5" S9.5B	$259,000
2028	1	037-Gates	Resurfacing	SR 1204 (Byrum Rd.)	SR 1200 (Sand Banks Rd.)	SR 1202 (Gatlington Rd.)	1.88	Full Depth Patching and 1.5" S9.5B	$375,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	1	037-Gates	Resurfacing	SR 1307 (Brinkley Rd.)	SR 1306 (Goodman Rd.)	SR 1305 (Union Branch Rd.)	1.22	Full Depth Patching and 1.5" S9.5B	$244,000
2028	1	037-Gates	Resurfacing	SR 1410 (Zion Rd.)	SR 1409 (Gray Rd.)	SR 1411 (Water Swamp Rd)	0.93	Full Depth Patching and 1.5" S9.5B	$186,000
2028	1	037-Gates	Resurfacing	SR 1411 (Water Swamp Rd)	SR 1404 (Silver Springs Rd)	SR 1410 (Zion Rd.)	2.39	Full Depth Patching and 1.5" S9.5B	$406,000
2028	1	037-Gates	Preservation	SR 1304 (Willeyton Rd.)	VA Line	SR 1303 (Parker Rd.)	7.39	Seal - Double	$369,000
2028	1	046-Hertford	Resurfacing	NC 45	Bertie Co.	NC 561	5.27	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,590,000
2028	1	046-Hertford	Resurfacing	SR 1159 (Hebrone Church Rd.)	SR 1160 (Benthall Bridge Rd.)	Northampton County	0.56	Full Depth Patching and 1.5" S9.5B	$112,000
2028	1	046-Hertford	Resurfacing	SR 1160 (Benthall Bridge Rd.)	SR 1142 (Flea Hill Rd.)	SR 1169 (W. Woodrow School Rd.)	4.07	Full Depth Patching and 1.5" S9.5B	$853,000
2028	1	046-Hertford	Resurfacing	SR 1167 (Cool Spring Rd.)	SR 1176 (Mt. Tabor Church Rd.)	US 158	1.32	Full Depth Patching and 1.5" S9.5B	$264,000
2028	1	046-Hertford	Resurfacing	SR 1420 (Ward Rd.)	Bertie Co	US 13	2.28	Full Depth Patching and 1.5" S9.5B	$455,000
2028	1	046-Hertford	Resurfacing	SR 1426 (Perry Rd.)	SR 1427 (Thomas Bridge Rd.)	End of Pavement	0.55	Full Depth Patching and 1.5" S9.5B	$110,000
2028	1	046-Hertford	Resurfacing	US 258	SR 1310 (Statesville Rd.)	SR 1306 (Parkers Ferry Rd.)	2.41	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$623,000
2028	1	046-Hertford	Resurfacing	US 258	Bridge #09	SR 1310 (Statesville Rd.)	2.28	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$588,000
2028	1	046-Hertford	Preservation	SR 1178 (Underwood Rd.)	SR 1167 (Cool Spring Rd.)	US 158	1.79	Seal - Double	$90,000
2028	1	046-Hertford	Preservation	SR 1424 (Godwin Town Rd.)	SR 1409 (Ahoskie Cofield Rd.)	NC 561	2.99	Seal - Double	$150,000
2028	1	046-Hertford	Preservation	SR 1427 (Thomas Bridge Rd.)	NC 45	NC 561	5.62	Seal - Double	$281,000
2028	1	048-Hyde	Resurfacing	NC 94	US 264	SR 1311(N. Lake Rd.)	6.20	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,750,000
2028	1	048-Hyde	Resurfacing	SR 1141 (Beullah Rd)	49 (MontgomSR 1143 (Sladesville Creedle Rd)er	SR 1145 (Loop Rd)	1.07	Full Depth Patching and 1.5" S9.5B	$193,000
2028	1	048-Hyde	Resurfacing	SR 1145 (Loop Rd)	SR 1141 (Beullah Rd)	SR 1146 (Makelyvile Rd)	2.99	Full Depth Patching and 1.5" S9.5B	$537,000
2028	1	048-Hyde	Resurfacing	SR 1352 (Shallop Creek Rd.)	Dead End	NC 45	0.23	Full Depth Patching and 1.5" S9.5B	$46,000
2028	1	048-Hyde	Resurfacing	SR 1353 (School House Rd.)	Dead End	NC 45	0.07	Full Depth Patching and 1.5" S9.5B	$14,000
2028	1	048-Hyde	Resurfacing	SR 1354 (Morphonos Rd.)	Dead End	NC 45	0.13	Full Depth Patching and 1.5" S9.5B	$26,000
2028	1	048-Hyde	Resurfacing	SR 1363 (Refuge Rd.)	End Maint	NC 45	0.67	Full Depth Patching and 1.5" S9.5B	$120,000
2028	1	048-Hyde	Resurfacing	SR 1364 (Prison Road	End Maint	SR 1305 (Piney Woods Rd.)	0.83	Full Depth Patching and 1.5" S9.5B	$166,000
2028	1	048-Hyde	Preservation	SR 1152 (Puddin Hill Rd.)	SR 1139 (Hodges Rd.)	SR 1148 (Sladesville Rd.)	2.57	Crack Seal	$20,000
2028	1	048-Hyde	Preservation	SR 1153 (New Rd.)	SR 1152 (Puddin Hill Rd.)	SR 1154 (Old US 264)	0.89	Crack Seal	$10,000
2028	1	058-Martin	Resurfacing	NC 903	End C&G	NC 11	3.43	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$926,000
2028	1	058-Martin	Resurfacing	NC 903	NC 125	End C&G	0.42	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$237,000
2028	1	058-Martin	Resurfacing	SR 1001 (Bear Grass Rd.)	SR 1214 (Brivershar Dr)	SR 1121 (Eli Bowen)	1.64	Full Depth Patching and 1.5" S9.5B	$328,000
2028	1	058-Martin	Resurfacing	SR 1001 (Bear Grass Rd.)	US 17 Bus.	SR 1214 (Brivershar Dr)	1.18	Full Depth Patching and 1.5" S9.5B	$236,000
2028	1	058-Martin	Resurfacing	SR 1001 (Bear Grass Rd.)	Begin C&G	SR 1121 (Eli Bowen)	2.39	Full Depth Patching and 1.5" S9.5B	$477,000
2028	1	058-Martin	Resurfacing	SR 1001 (Bear Grass Rd.)	End C&G	Beaufort County Line	2.48	Full Depth Patching and 1.5" S9.5B	$495,000
2028	1	058-Martin	Resurfacing	SR 1001 (Bear Grass Rd.)	Begin C&G	End C&G	0.60	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$212,000
2028	1	058-Martin	Resurfacing	SR 1104 (Cratt Rd.)	SR 1100 (Sweet Home Rd.	SR 1106 (Joe Mobley Rd.)	1.87	Full Depth Patching and 1.5" S9.5B	$374,000
2028	1	058-Martin	Resurfacing	SR 1106 (Ed's Grocery Rd.)	SR 1001 (Bear Grass Rd.)	SR 1310 (Chapman Rd)	1.35	Full Depth Patching and 1.5" S9.5B	$270,000
2028	1	058-Martin	Resurfacing	SR 1129 (Harry Ayers Rd.)	SR 1128 (Price Rd.)	SR 1133 (Five Cent Rd.)	1.26	Full Depth Patching and 1.5" S9.5B	$252,000
2028	1	058-Martin	Preservation	SR 1127 (Henry Mizelle Rd.)	SR 1142 (Prison Camp Rd.)	SR 1001 (Bear Grass Rd.)	1.53	Seal - Double	$77,000
2028	1	058-Martin	Preservation	SR 1150 (Lee House Rd.)	NC 903	SR 1159 (Third Street Ext.)	1.71	Seal - Double	$86,000
2028	1	058-Martin	Preservation	SR 1151 (Everetts Rd.)	SR 1150 (Lee House Rd.)	SR 1145 (Sam Everett Rd.)	1.63	Seal - Double	$82,000
2028	1	058-Martin	Preservation	SR 1337 (Ray Turner Rd)	SR 1348 (Peele Rd)	NC 11	0.39	Seal - Double	$18,000
2028	1	058-Martin	Preservation	1337 (Ray Turner Rd)SR 1337 (Ray Turner R	NC 125	SR 1348 (Peele Rd)	1.96	Seal - Double	$88,000
2028	1	058-Martin	Preservation	SR 1401 (CL Keel Rd.)	NC 903	SR 1159 (Robersonville Products)	2.43	Seal - Double	$122,000
2028	1	066-Northampton	Resurfacing	SR 1118 (Bolton Road)	End of Pavement	NC 305	3.71	Full Depth Patching and 1.5" S9.5B	$667,000
2028	1	066-Northampton	Resurfacing	SR 1311 (Jackson Bypass Rd.)	US 158	NC 305	3.92	Full Depth Patching and 1.5" S9.5B	$822,000
2028	1	066-Northampton	Resurfacing	SR 1328 (High Bridge Rd.)	SR 1329 (Devil's Racetrack Rd.)	SR 1333 (Mt. Carmel Rd.)	1.97	Full Depth Patching and 1.5" S9.5B	$393,000
2028	1	066-Northampton	Resurfacing	SR 1372 (Post Office Rd.)	NC 186	End of Pavement	0.11	Full Depth Patching and 1.5" S9.5B	$18,000
2028	1	066-Northampton	Resurfacing	SR 1501 (Dusty Hill Rd.)	NC 305	SR 1503 (Lasker Rd)	3.81	Full Depth Patching and 1.5" S9.5B	$760,000
2028	1	066-Northampton	Resurfacing	SR 1538 (Parker Rd.)	SR 1537 (Perdue Hatchery Rd.)	US 258	1.12	Full Depth Patching and 1.5" S9.5B	$202,000
2028	1	066-Northampton	Resurfacing	US 301	US 158	VA Line	6.77	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,370,000
2028	1	066-Northampton	Preservation	SR 1274 (Timberline Dr.)	End Maint	SR 1263 (Honeysuckle Dr.)	0.87	1.25" S9.5B	$96,000
2028	1	066-Northampton	Preservation	SR 1275 (Flatrock Rd.)	CDS	SR 1274 (Timberline Dr.)	0.65	1.25" S9.5B	$72,000
2028	1	066-Northampton	Preservation	SR 1276 (Dogwood Dr.)	CDS	SR 1275 (Flatrock Rd.)	0.24	1.25" S9.5B	$27,000
2028	1	066-Northampton	Preservation	SR 1279 (Cedar Dr.)	SR 1252 (Vincent Lane)	SR 1280 (Water Front Dr.)	0.11	1.25" S9.5B	$13,000
2028	1	066-Northampton	Preservation	SR 1280 (Waterfront Dr.)	CDS	CDS	0.23	1.25" S9.5B	$25,000
2028	1	066-Northampton	Preservation	SR 1282 (Pine Cone Rd.)	CDS	SR 1263 (Honeysuckle Dr.)	0.14	1.25" S9.5B	$16,000
2028	1	066-Northampton	Preservation	SR 1283 (Sandy Shores Dr.)	CDS	CDS	0.43	1.25" S9.5B	$48,000
2028	1	066-Northampton	Preservation	SR 1294 (Southport Court)	CDS	SR 1274 (Timberline Dr.)	0.14	1.25" S9.5B	$16,000
2028	1	066-Northampton	Preservation	SR 1297 (Greenwood Dr.)	SR 1298 (Dogwood Acres)	SR 1263 (Honeysuckle Dr.)	0.22	1.25" S9.5B	$25,000
2028	1	066-Northampton	Preservation	SR 1298 (Dogwood Acres)	Dead End	CDS	0.13	1.25" S9.5B	$15,000
2028	1	066-Northampton	Preservation	SR 1609 (Westbriar Circle)	SR 1252 (Vincent Lane)	SR 1610 (Southern Circle)	0.13	1.25" S9.5B	$17,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	1	066-Northampton	Preservation	SR 1610 (North/Southbriar Circle)	CDS	CDS	0.11	1.25" S9.5B	$14,000
2028	1	066-Northampton	Preservation	SR 1611 (Heritage Lane)	SR 1609 (Westbriar Circle)	SR 1612 (Sunset Circle)	0.28	1.25" S9.5B	$35,000
2028	1	066-Northampton	Preservation	SR 1612 (Sunset Circle)	SR 1611 (Heritage Lane)	CDS	0.04	1.25" S9.5B	$6,000
2028	1	066-Northampton	Preservation	SR1263 (Honeysuckle Dr.)	VA Line	SR 1282 (Pine Cone Dr.)	0.97	1.25" S9.5B	$108,000
2028	1	070-Pasquotank	Resurfacing	NC 344 (Halstead Blvd. / Weeksville Hwy.)	Pavement Joint	US 17 Bus.	3.97	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,300,000
2028	1	070-Pasquotank	Resurfacing	SR 1132 (Florida Rd.)	SR 1101 (Peartree Rd.)	NC 344	2.35	Full Depth Patching and 1.5" S9.5B	$469,000
2028	1	070-Pasquotank	Resurfacing	SR 1220 (Dances Bay Rd.)	SR 1100 (Nixonton Rd.)	Dead End	1.79	Full Depth Patching and 1.5" S9.5B	$357,000
2028	1	070-Pasquotank	Resurfacing	SR 1270 (Small Dr.)	SR 1129 (Chances Ln.)	SR 1622 (Blimpview Dr.)	1.64	Full Depth Patching and 1.5" S9.5B	$328,000
2028	1	070-Pasquotank	Resurfacing	SR 1298 (Becca Rd.)	SR 1132 (Florida Rd.)	Dead End	0.42	Full Depth Patching and 1.5" S9.5B	$83,000
2028	1	070-Pasquotank	Resurfacing	SR 1299 (Wiley Dr.)	SR 1298 (Becca Rd.)	Dead End	0.41	Full Depth Patching and 1.5" S9.5B	$82,000
2028	1	070-Pasquotank	Resurfacing	SR 1415 (Morgan Rd)	SR 1416 (Northside Rd)	Dead End	0.16	Full Depth Patching and 1.5" S9.5B	$29,000
2028	1	070-Pasquotank	Resurfacing	SR 1462 Corporate Dr	SR 1333 Main St Ext	SR 1464 Commerce Dr	0.62	Full Depth Patching and 1.5" S9.5B	$137,000
2028	1	070-Pasquotank	Resurfacing	SR 1470 (Tiff Lane)	SR 1416 (Northside Rd)	Dead End	0.39	Full Depth Patching and 1.5" S9.5B	$78,000
2028	1	070-Pasquotank	Resurfacing	SR 1471 (Clay Ct)	SR 1470 (Tiff Lane)	Dead End	0.05	Full Depth Patching and 1.5" S9.5B	$10,000
2028	1	070-Pasquotank	Resurfacing	SR 1472 (Hope Ct)	SR 1470 (Tiff Lane)	Dead End	0.07	Full Depth Patching and 1.5" S9.5B	$14,000
2028	1	070-Pasquotank	Resurfacing	SR 1495 (Katies Trail)	SR 1416 (Northside Rd)	Dead End	0.72	Full Depth Patching and 1.5" S9.5B	$144,000
2028	1	070-Pasquotank	Resurfacing	SR 1496 (Madeline Ln)	SR 1495 (Katies Trail)	SR 1495 (Katies Trail)	0.40	Full Depth Patching and 1.5" S9.5B	$80,000
2028	1	070-Pasquotank	Resurfacing	SR 1497 (Nicholas Ct)	SR 1495 (Katies Trail)	Dead End	0.06	Full Depth Patching and 1.5" S9.5B	$12,000
2028	1	070-Pasquotank	Resurfacing	SR 1626 (Sylvan Ct)	SR 1299 (Wiley Dr)	Dead End	0.07	Full Depth Patching and 1.5" S9.5B	$14,000
2028	1	070-Pasquotank	Resurfacing	US 17 Bus. (Ehringhaus St.).)	US 17 (Hughes Blvd.)	SR 1269 (S. Road St.)	1.69	Mill 1.5" and 1.5" S9.5B	$1,160,000
2028	1	070-Pasquotank	Preservation	SR 1464 Commerce	US 17	End	1.23	1.25" S9.5B	$228,000
2028	1	070-Pasquotank	Preservation	SR 1490 Executive Dr	SR 1464 Commerce	SR 1464 Commerce	0.41	1.25" S9.5B	$55,000
2028	1	070-Pasquotank	Preservation	SR 1492 (Richochet Ct.)	SR 1341 (Scott Rd.)	CDS	0.06	1.25" S9.5B	$8,000
2028	1	070-Pasquotank	Preservation	SR 1493 (Elbert Dr.)	SR 1341 (Scott Rd.)	CDS	0.23	1.25" S9.5B	$29,000
2028	1	070-Pasquotank	Preservation	SR 1494 (Kayla Ct.)	SR 1341 (Scott Rd.)	CDS	0.12	1.25" S9.5B	$15,000
2028	1	072-Perquimans	Resurfacing	SR 1107 (Cedar Stretch Rd.)	SR 1108 (Ballahack Rd)	SR 1110 (Center Hill Hwy)	1.07	Full Depth Patching and 1.5" S9.5B	$214,000
2028	1	072-Perquimans	Resurfacing	SR 1108 (Cedar Stretch Rd.)	SR 1110 (W Grubb St.)	SR 1107 (Cedar Stretch Rd.)	0.70	Full Depth Patching and 1.5" S9.5B	$126,000
2028	1	072-Perquimans	Resurfacing	SR 1110 (W. Grubb St.)	Begin C&G	US 17 Bus.	1.04	Mill 1.5" and 1.5" S9.5B	$367,000
2028	1	072-Perquimans	Resurfacing	SR 1131 (Dobb St.)	US 17 Bus.	End of Maintenance	0.29	Mill 1.5" and 1.5" S9.5B	$96,000
2028	1	072-Perquimans	Resurfacing	SR 1132 (Woods Ln.)	SR 1131 (Dobb St.)	Dead End	0.12	Full Depth Patching and 1.5" S9.5B	$22,000
2028	1	072-Perquimans	Resurfacing	SR 1219 (Bembury Rd.)	SR 1214 (Lake Rd.)	SR 1219 (Main St.)	0.81	Full Depth Patching and 1.5" S9.5B	$162,000
2028	1	072-Perquimans	Resurfacing	SR 1234 (Cottonwood Dr.)	SR 1214 (Lake Rd.)	Cul-de-sac	0.38	Full Depth Patching and 1.5" S9.5B	$76,000
2028	1	072-Perquimans	Resurfacing	SR 1302 (Union Hall Rd.)	US 17	SR 1300 (New Hope Rd.)	1.04	Full Depth Patching and 1.5" S9.5B	$208,000
2028	1	072-Perquimans	Resurfacing	SR 1312 (Cove Rd.)	SR 1300 (New Hope Rd.)	Dead End	2.19	Full Depth Patching and 1.5" S9.5B	$437,000
2028	1	072-Perquimans	Resurfacing	SR 1313 (Spivey Ln.)	SR 1312 (Cove Rd.)	End Pavement	0.11	Full Depth Patching and 1.5" S9.5B	$22,000
2028	1	072-Perquimans	Resurfacing	SR 1338 (Wynne Fork Rd)	US 17	US 17 Bus. (S Edenton Road St.)	0.51	Full Depth Patching and 1.5" S9.5B	$102,000
2028	1	072-Perquimans	Preservation	SR 1104 (Bear Swamp Rd.)	SR 1110 (Center Hill Rd.)	Chowan County Line	0.08	Seal - Double	$4,000
2028	1	072-Perquimans	Preservation	SR 1214 (Swamp Rd.)	SR 1223 (Four Mile Desert Rd.)	SR 1001 (Sandy Cross Rd.)	3.87	Seal - Double	$193,000
2028	1	072-Perquimans	Preservation	SR 1223 (Four Mile Desert Rd.)	Pasquotank County Line	SR 1214 (Swamp Rd.)	4.96	Seal - Double	$248,000
2028	1	089-Tyrrell	Resurfacing	SR 1114 (Chappell Hill Rd.)	SR 1113 (Travis Rd.)	SR 1115 (Travis School Rd.)	0.75	Full Depth Patching and 1.5" S9.5B	$135,000
2028	1	089-Tyrrell	Resurfacing	SR 1115 (Chappell Hill Rd.)	SR 1116 (Woodley Station Rd)	SR 1114 (Chappell Hill Rd.)	1.25	Full Depth Patching and 1.5" S9.5B	$225,000
2028	1	089-Tyrrell	Resurfacing	SR 1321 (S. Gumneck Rd.)	SR 1320 (S. Gumneck Rd.)	NC 94	2.86	Full Depth Patching and 1.5" S9.5B	$571,000
2028	1	094-Washington	Resurfacing	SR 1156 (Mountain Canal Rd.)	SR 1165 (Mail Route Rd.)	SR 1166 (Lake Shore Dr.)	0.67	Full Depth Patching and 1.5" S9.5B	$134,000
2028	1	094-Washington	Resurfacing	SR 1161 (Tom Pepper Rd.)	Tyrrell Co	SR 1155 (Old Cherry Rd.)	1.50	Full Depth Patching and 1.5" S9.5B	$300,000
2028	1	094-Washington	Resurfacing	SR 1210 (Ausbon Dr.)	SR 1108 (Rosevelt Avenue)	SR 1211 (Buncombe Drive)	0.12	Full Depth Patching and 1.5" S9.5B	$24,000
2028	1	094-Washington	Resurfacing	SR 1211 (Buncombe Dr.)	SR 1210 (Ausbon Dr.)	EOM	0.10	Full Depth Patching and 1.5" S9.5B	$20,000
2028	1	094-Washington	Resurfacing	SR 1301 (Cross Rd.)	NC 308	NC 32	3.42	Full Depth Patching and 1.5" S9.5B	$683,000
2028	1	094-Washington	Resurfacing	SR 1315 (Breezy Banks Rd.)	SR 1302 (Pea Ridge Rd.)	NC 32	0.98	Full Depth Patching and 1.5" S9.5B	$197,000
2028	1	094-Washington	Resurfacing	SR 1321 (Mackey's Creek Rd.)	NC 308	End of Pavement	0.17	Full Depth Patching and 1.5" S9.5B	$28,000
2028	1	094-Washington	Resurfacing	SR 1358 (Industrial Park Rd.)	US 64	End of Pavement	0.34	Full Depth Patching and 1.5" S9.5B	$82,000
2028	1	094-Washington	Preservation	SR 1100 (Long Ridge Road)	350' South of SR1106 (Morratock Rd.)	Martin County Line	8.90	Seal - Double	$444,000
2028	1	094-Washington	Preservation	SR 1103 (Jerden Thicket Rd.)	SR 1100 (Long Ridge Rd.)	Martin County Line	0.59	Seal - Double	$30,000
2028	1	094-Washington	Preservation	SR 1109 (Roxie Reese Rd.)	NC 45	SR 1110 (Memory Lane)	0.83	Seal - Double	$42,000
2028	1	094-Washington	Preservation	SR 1110 (Roxie Reese Rd.)	US 64	End Of Maintenance	0.24	Seal - Double	$11,000
2028	1	094-Washington	Preservation	SR 1115 (White Oak Rd.)	SR 1181 (White Oak Loop Rd.)	End Of Pavement	1.19	Seal - Double	$57,000
2028	1	094-Washington	Preservation	SR 1116 (White Oak Lane)	SR 1115 (White Oak Rd.)	End Of Maintenance	0.91	Seal - Double	$46,000
2028	1	094-Washington	Preservation	SR 1177 (Lilly Of The Valley Rd.)	SR 1115 (White Oak Rd.)	End Of Pavement	0.20	Seal - Double	$9,000
2028	1	094-Washington	Preservation	SR 1197 (Edgewood Rd.)	SR 1115 (White Oak Rd.)	End Of Pavement	0.17	Seal - Double	$8,000
2028	1	094-Washington	Preservation	SR 1358 (Industrial Park Rd.)	US 64	End of Maintenance	0.34	Seal - Double	$21,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	2	007-Beaufort	Resurfacing	SR 1102	SR 1100	END MAINTENANCE	1.11	1.5" S9.5B	$310,000
2028	2	007-Beaufort	Resurfacing	SR 1107	SR 1100	DEAD END	0.80	1.25" S9.5B	$120,000
2028	2	007-Beaufort	Resurfacing	SR 1179	SR 1107	END MAINTENANCE	0.27	1.25" S9.5B	$40,500
2028	2	007-Beaufort	Resurfacing	SR 1192	SR 1102	SR 1198	0.25	1.5" S9.5B	$50,000
2028	2	007-Beaufort	Resurfacing	SR 1198	SR 1192	END MAINTENANCE	0.18	1.5" S9.5B	$36,000
2028	2	007-Beaufort	Resurfacing	SR 1318	NC 32	DEAD END	0.49	1.5" S9.5B	$97,400
2028	2	007-Beaufort	Resurfacing	SR 1726	SR 1725	DEAD END	1.14	1.25" S9.5B	$228,000
2028	2	007-Beaufort	Resurfacing	SR 1727	SR 1726	SR 1726	0.57	1.25" S9.5B	$114,000
2028	2	007-Beaufort	Resurfacing	SR 1728	SR 1725	DEAD END	0.38	1.25" S9.5B	$76,000
2028	2	007-Beaufort	Resurfacing	SR 1729	SR 1725	END MAINTENANCE	0.46	1.25" S9.5B	$91,800
2028	2	007-Beaufort	Resurfacing	SR 1734	SR 1732	END MAINTENANCE	0.60	1.5" S9.5B	$120,000
2028	2	007-Beaufort	Resurfacing	SR 1735	SR 1736	DEAD END	1.23	1.5" S9.5B	$246,000
2028	2	007-Beaufort	Resurfacing	SR 1736	SR 1732	SR 1732	1.90	1.5" S9.5B	$380,000
2028	2	007-Beaufort	Resurfacing	SR 1903	SR 1904	NC 33	0.13	1.5" S9.5B	$26,000
2028	2	007-Beaufort	Resurfacing	SR 1904	SR 1906	END MAINTENANCE	1.29	1.5" S9.5B	$260,000
2028	2	007-Beaufort	Resurfacing	SR 1905	SR 1906	NC 33	0.35	1.5" S9.5B	$82,000
2028	2	007-Beaufort	Resurfacing	SR 1906	SR 1903	SR 1912	1.94	1.5" S9.5B	$380,000
2028	2	007-Beaufort	Resurfacing	SR 1956	SR 1100	END MAINTENANCE	1.50	1.25" S9.5B	$299,000
2028	2	007-Beaufort	Resurfacing	US 264 EB	PITT CO	SR 1427	2.18	2.0" S9.5C	$825,000
2028	2	007-Beaufort	Resurfacing	US 264 WB	SR 1427	PITT CO	2.18	2.0" S9.5C	$825,000
2028	2	007-Beaufort	Rehabilitation	SR 1181	NC 33	DEAD END	0.73	2.5" I19.0C and 1.5" S9.5B	$310,250
2028	2	016-Carteret	Resurfacing	SR 1130	SR 1129	SR 1247	0.35	1.5" S9.5B	$70,600
2028	2	016-Carteret	Resurfacing	SR 1131	SR 1130	SR 1130	0.20	1.5" S9.5B	$40,800
2028	2	016-Carteret	Resurfacing	SR 1150	US 70	END MAINTENANCE	0.69	1.5" S9.5B	$137,400
2028	2	016-Carteret	Resurfacing	SR 1175	US 70	END MAINT	0.53	1.25" S9.5B	$106,800
2028	2	016-Carteret	Resurfacing	SR 1205	END MAINT	END MAINT	0.92	1.5" S9.5B	$183,800
2028	2	016-Carteret	Resurfacing	SR 1206	SR 1124	CUL-DE-SAC	0.10	1.5" S9.5B	$20,000
2028	2	016-Carteret	Resurfacing	SR 1211	SR 1247	END MAINTENANCE	0.50	1.5" S9.5B	$99,400
2028	2	016-Carteret	Resurfacing	SR 1224	SR 1205	END MAINTENANCE	0.11	1.5" S9.5B	$22,000
2028	2	016-Carteret	Resurfacing	SR 1252	BEGIN MAINTENANCE	US 70	0.16	1.5" S9.5B	$32,000
2028	2	016-Carteret	Resurfacing	SR 1266	SR 1155	DEAD END	0.21	1.5" S9.5B	$41,000
2028	2	016-Carteret	Resurfacing	SR 1267	SR 1155	DEAD END	0.22	1.5" S9.5B	$43,600
2028	2	016-Carteret	Resurfacing	SR 1268	NC 24	DEAD END	0.42	1.5" S9.5B	$83,800
2028	2	016-Carteret	Resurfacing	SR 1269	SR 1124	CUL-DE-SAC	0.44	1.5" S9.5B	$88,800
2028	2	016-Carteret	Resurfacing	SR 1270	SR 1269	SR 1271	0.05	1.5" S9.5B	$10,000
2028	2	016-Carteret	Resurfacing	SR 1271	SR 1270	CUL-DE-SAC	0.27	1.5" S9.5B	$54,200
2028	2	016-Carteret	Resurfacing	SR 1272	SR 1269	SR 1271	0.09	1.5" S9.5B	$17,000
2028	2	016-Carteret	Resurfacing	SR 1282	SR 1140	DEAD END	0.44	1.5" S9.5B	$88,000
2028	2	016-Carteret	Resurfacing	SR 1283	SR 1140	END MAINTENANCE	0.20	1.5" S9.5B	$40,000
2028	2	016-Carteret	Resurfacing	SR 1298	SR 1124	END MAINTENANCE	1.19	1.5" S9.5B	$238,000
2028	2	016-Carteret	Rehabilitation	SR 1276	SR 1140	END MAINTENANCE	0.25	2.5" I19.0C and 1.5" S9.5B	$106,250
2028	2	016-Carteret	Rehabilitation	SR 1290	SR 1140	END MAINTENANCE	0.21	2.5" I19.0C and 1.5" S9.5B	$89,250
2028	2	025-Craven	Resurfacing	NC 55	BACHELOR CREEK	ALLIGATOR BRANCH	19.28	Mill 1.5" and 1.5" S9.5C	$5,740,000
2028	2	025-Craven	Resurfacing	SR 1193	SR 1143	CUL-DE-SAC	0.80	1.5" S9.5B	$160,000
2028	2	025-Craven	Resurfacing	SR 1206	SR 1200	SR 1206	0.92	1.5" S9.5B	$183,200
2028	2	025-Craven	Resurfacing	SR 1299	END C&G	SR 1216	0.51	1.5" S9.5B	$102,600
2028	2	025-Craven	Resurfacing	SR 1372	SR 1206	SR 1206	0.22	1.5" S9.5B	$44,600
2028	2	025-Craven	Resurfacing	SR 1419	NC 55	NC 43	1.26	1.5" S9.5B	$251,400
2028	2	025-Craven	Resurfacing	SR 1436	SR 1628	US 17	0.22	1.5" S9.5B	$43,800
2028	2	025-Craven	Resurfacing	SR 1440	US 17 BUS	SR 1400	5.23	1.5" S9.5B	$1,046,000
2028	2	025-Craven	Resurfacing	SR 1441	SR 1440	CUL-DE-SAC	1.82	1.5" S9.5B	$362,000
2028	2	025-Craven	Resurfacing	SR 1628	US 17 BUS	SR 1621	5.23	2.0" S9.5C	$900,000
2028	2	025-Craven	Resurfacing	SR 1668	SR 1628	US 17	0.07	1.5" S9.5B	$14,000
2028	2	025-Craven	Resurfacing	SR 1838	NC 306	DEAD END	0.61	1.5" S9.5B	$122,000
2028	2	025-Craven	Resurfacing	SR 1839	SR 1839	CUL-DE-SAC	0.27	1.5" S9.5B	$54,000
2028	2	025-Craven	Resurfacing	SR 1840	SR 1838	CUL-DE-SAC	0.14	1.5" S9.5B	$28,000
2028	2	025-Craven	Resurfacing	SR 1841	NC 306	NC 306	0.78	1.5" S9.5B	$156,000
2028	2	025-Craven	Resurfacing	SR 1842	SR 1841	CUL-DE-SAC	0.13	1.5" S9.5B	$26,000
2028	2	025-Craven	Resurfacing	SR 1843	SR 1842	CUL-DE-SAC	0.08	1.5" S9.5B	$16,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	2	025-Craven	Resurfacing	SR 1844	SR 1841	SR 1845	0.09	1.5" S9.5B	$18,000
2028	2	025-Craven	Resurfacing	SR 1845	CUL-DE-SAC	CUL-DE-SAC	0.30	1.5" S9.5B	$60,000
2028	2	025-Craven	Resurfacing	SR 1846	NC 306	CUL-DE-SAC	0.16	1.5" S9.5B	$32,000
2028	2	025-Craven	Resurfacing	SR 1847	NC 306	CUL-DE-SAC	0.84	1.5" S9.5B	$167,600
2028	2	025-Craven	Resurfacing	SR 1848	SR 1847	CUL-DE-SAC	0.06	1.5" S9.5B	$12,000
2028	2	025-Craven	Resurfacing	SR 1849	SR 1847	CUL-DE-SAC	0.10	1.5" S9.5B	$20,000
2028	2	025-Craven	Resurfacing	SR 1850	NC 306	SR 1851	0.06	1.5" S9.5B	$12,000
2028	2	025-Craven	Resurfacing	SR 1851	SR 1850	SR 1853	0.33	1.5" S9.5B	$66,000
2028	2	025-Craven	Resurfacing	SR 1853	SR 1852	END MAINTENANCE	0.35	1.5" S9.5B	$70,000
2028	2	025-Craven	Resurfacing	SR 1874	SR 1841	SR 1875	0.09	1.5" S9.5B	$16,000
2028	2	025-Craven	Resurfacing	SR 1875	CUL-DE-SAC	CUL-DE-SAC	0.31	1.5" S9.5B	$60,000
2028	2	025-Craven	Resurfacing	SR 1876	SR 1841	CUL-DE-SAC	0.05	1.5" S9.5B	$8,000
2028	2	025-Craven	Resurfacing	SR 1877	SR 1841	CUL-DE-SAC	0.11	1.5" S9.5B	$20,000
2028	2	025-Craven	Rehabilitation	SR 1852	SR 1851	CUL-DE-SAC	0.24	2.5" I19.0C and 1.5" S9.5B	$102,000
2028	2	025-Craven	Preservation	SR 1448	SR 1444	SR 1400	4.07	Seal - Double	$154,660
2028	2	025-Craven	Preservation	SR 1451	SR 1444	SR 1448	1.35	Seal - Double	$51,300
2028	2	025-Craven	Preservation	SR 1465	PITT COUNTY	NC 118	0.59	Seal - Double	$22,420
2028	2	025-Craven	Preservation	SR 1470	SR 1472	SR 1400	0.59	Seal - Double	$22,382
2028	2	025-Craven	Preservation	SR 1470	SR 1472	SR 1400	0.29	Seal - Double	$11,172
2028	2	025-Craven	Preservation	SR 1471	NC 55	SR 1472	1.86	Seal - Double	$70,680
2028	2	025-Craven	Preservation	SR 1472	NC 55	NC 55	5.16	Seal - Double	$185,800
2028	2	025-Craven	Preservation	SR 1477	NC 43	NC 43	1.37	Seal - Double	$52,060
2028	2	025-Craven	Preservation	SR 1478	NC 118	NC 43	2.09	Seal - Double	$79,420
2028	2	025-Craven	Preservation	SR 1479	NC 118	END MAINTENANCE	0.40	Seal - Double	$15,200
2028	2	025-Craven	Preservation	SR 1628	US 17 BUS	SR 1621	5.23	FDR and Double Seal	$2,264,963
2028	2	025-Craven	Preservation	SR 1643	SR 1476	BEAUFORT COUNTY	2.46	Seal - Double	$93,518
2028	2	040-Greene	Resurfacing	SR 1229	US 264 ALT	SR 1225	5.86	1.5" S9.5B	$1,171,000
2028	2	040-Greene	Resurfacing	SR 1245	SR 1247	NC 91	1.81	2.0" S9.5C	$283,000
2028	2	040-Greene	Resurfacing	SR 1320	US 258	SR 1301	2.07	1.5" S9.5B	$414,000
2028	2	040-Greene	Resurfacing	SR 1345	SR 1335	US 13	2.30	2.0" S9.5C	$400,000
2028	2	040-Greene	Resurfacing	SR 1401	SR 1400	NC 903	2.20	1.5" S9.5B	$440,000
2028	2	040-Greene	Preservation	SR 1245	SR 1247	NC 91	1.81	FDR and Double Seal	$850,000
2028	2	040-Greene	Preservation	SR 1345	SR 1335	US 13	2.30	FDR and Double Seal	$1,250,000
2028	2	052-Jones	Resurfacing	SR 1134	SR 1003	NC 41	2.57	1.5" S9.5B	$513,600
2028	2	052-Jones	Resurfacing	SR 1137	NC 41	DEAD END	0.78	1.5" S9.5B	$156,800
2028	2	052-Jones	Resurfacing	SR 1169	NC 41	END MAINTENANCE	0.20	1.5" S9.5B	$40,000
2028	2	052-Jones	Resurfacing	SR 1171	NC 41	END MAINTENANCE	0.21	1.5" S9.5B	$42,600
2028	2	052-Jones	Resurfacing	SR 1172	NC 41	DEAD END	0.17	1.5" S9.5B	$32,000
2028	2	052-Jones	Resurfacing	SR 1308	SR 1002	DEAD END	0.49	1.5" S9.5B	$98,200
2028	2	052-Jones	Preservation	SR 1131	SR 1129	SR 1130	2.58	Seal - Double	$98,040
2028	2	052-Jones	Preservation	SR 1150	SR 1130	SR 1151	2.95	Seal - Double	$112,100
2028	2	052-Jones	Preservation	SR 1157	NC 58	SR 1130	4.23	Seal - Double	$160,740
2028	2	054-Lenoir	Resurfacing	NC 11	NC 55	RAB	4.95	Mill 1.5" and 1.5" S9.5C	$3,400,000
2028	2	054-Lenoir	Resurfacing	SR 1326	SR 1318	SR 1327	1.88	1.5" S9.5B	$372,000
2028	2	054-Lenoir	Resurfacing	SR 1504	NC 903	SR 1001	3.29	1.5" S9.5B	$656,000
2028	2	054-Lenoir	Resurfacing	SR 1514	SR 1532	NC 903	5.18	1.5" S9.5B	$1,034,000
2028	2	054-Lenoir	Resurfacing	SR 1717	NC 11	DEAD END	0.54	1.5" S9.5B	$102,000
2028	2	054-Lenoir	Resurfacing	SR 1744	NC 11	CUL-DE-SAC	0.61	1.5" S9.5B	$121,200
2028	2	054-Lenoir	Resurfacing	SR 1813	NC 11	SR 1810	0.64	1.5" S9.5B	$128,000
2028	2	069-Pamlico	Resurfacing	SR 1139	NC 55	END MAINTENANCE	0.50	1.5" S9.5B	$100,200
2028	2	069-Pamlico	Resurfacing	SR 1239	NC 304	END PAVEMENT	0.69	1.5" S9.5B	$137,600
2028	2	069-Pamlico	Resurfacing	SR 1241	NC 55	SR 1241	0.52	1.5" S9.5B	$104,800
2028	2	069-Pamlico	Resurfacing	SR 1337	NC 55	END PAVEMENT	0.35	1.5" S9.5B	$70,000
2028	2	069-Pamlico	Resurfacing	SR 1343	NC 55	END MAINTENANCE	1.45	1.5" S9.5B	$289,800
2028	2	069-Pamlico	Resurfacing	SR 1345	SR 1344	END MAINTENANCE	0.90	1.5" S9.5B	$180,000
2028	2	069-Pamlico	Resurfacing	SR 1356	SR 1348	DEAD END	0.18	1.5" S9.5B	$35,800
2028	2	069-Pamlico	Resurfacing	SR 1359	NC 55	DEAD END	0.26	1.5" S9.5B	$52,400
2028	2	069-Pamlico	Preservation	SR 1129	NC 55	END MAINTENANCE	0.15	Seal - Double	$5,662
2028	2	069-Pamlico	Preservation	SR 1206	NC 304	END PAVEMENT	0.40	Seal - Double	$15,162

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	2	069-Pamlico	Preservation	SR 1209	NC 304	NC 304	1.69	Seal - Double	$64,106
2028	2	069-Pamlico	Preservation	SR 1211	NC 304	NC 304	0.81	Seal - Double	$30,590
2028	2	069-Pamlico	Preservation	SR 1214	NC 304	SR 1213	0.17	Seal - Double	$6,498
2028	2	069-Pamlico	Preservation	SR 1215	NC 304	END PAVEMENT	0.50	Seal - Double	$19,038
2028	2	069-Pamlico	Preservation	SR 1216	NC 304	END MAINTENANCE	0.64	Seal - Double	$24,130
2028	2	069-Pamlico	Preservation	SR 1220	NC 304	NC 307	0.35	Seal - Double	$13,110
2028	2	069-Pamlico	Preservation	SR 1336	NC 55	END PAVEMENT	0.86	Seal - Double	$32,490
2028	2	069-Pamlico	Preservation	SR 1357	SR 1005	SR 1005	0.33	Seal - Double	$12,616
2028	2	074-Pitt	Resurfacing	NC 30	US 264	US 13 SOUTH	15.05	Mill 1.5" and 1.5" S9.5C	$5,000,000
2028	2	074-Pitt	Resurfacing	NC 903	BRIDGE 54	MARTIN COUNTY LINE	3.97	1.75" S9.5B	$1,026,376
2028	2	074-Pitt	Resurfacing	SR 1105	NC 11	SR 1900	0.74	1.5" S9.5B	$148,600
2028	2	074-Pitt	Resurfacing	SR 1151	SR 1125	DEAD END	0.21	1.5" S9.5B	$41,000
2028	2	074-Pitt	Resurfacing	SR 1162	CUL-DE-SAC	END MAINTENANCE	0.31	1.5" S9.5B	$61,800
2028	2	074-Pitt	Resurfacing	SR 1163	SR 1125	SR 1162	0.11	1.5" S9.5B	$21,200
2028	2	074-Pitt	Resurfacing	SR 1164	SR 1162	CUL-DE-SAC	0.07	1.5" S9.5B	$14,400
2028	2	074-Pitt	Resurfacing	SR 1165	SR 1116	DEAD END	0.16	1.5" S9.5B	$32,600
2028	2	074-Pitt	Resurfacing	SR 1504	SR 1500	MARTIN COUNTY	0.78	1.5" S9.5B	$156,000
2028	2	074-Pitt	Resurfacing	SR 1505	MARTIN COUNTY	SR 1500	4.13	1.5" S9.5B	$826,200
2028	2	074-Pitt	Resurfacing	SR 1506	SR 1505	MARTIN COUNTY	0.33	1.5" S9.5B	$66,000
2028	2	074-Pitt	Resurfacing	SR 1507	SR 1500	NC 30	2.23	1.5" S9.5B	$446,800
2028	2	074-Pitt	Resurfacing	SR 1512	US 13 / NC 11	SR 1514	2.49	1.5" S9.5B	$498,000
2028	2	074-Pitt	Resurfacing	SR 1529	SR 1591	NC 33	1.38	1.5" S9.5B	$276,000
2028	2	074-Pitt	Resurfacing	SR 1743	NC 43	SR 1744	1.02	1.5" S9.5B	$203,800
2028	2	074-Pitt	Resurfacing	SR 1772	SR 1755	SR 1774	2.14	1.5" S9.5B	$428,000
2028	2	074-Pitt	Resurfacing	SR 1774	SR 1777	SR 2241	3.92	1.5" S9.5B	$784,000
2028	2	074-Pitt	Resurfacing	SR 2232	SR 1726	SR 2233	0.30	1.5" S9.5B	$60,000
2028	2	074-Pitt	Resurfacing	SR 2233	SR 2232	END MAINTENANCE	0.24	1.5" S9.5B	$48,000
2028	2	074-Pitt	Resurfacing	SR 2234	SR 2232	CUL-DE-SAC	0.04	1.5" S9.5B	$8,000
2028	2	074-Pitt	Resurfacing	SR 2236	SR 1726	SR 1726	0.51	1.5" S9.5B	$101,600
2028	2	074-Pitt	Resurfacing	SR 2237	SR 2236	END MAINT	0.04	1.5" S9.5B	$8,000
2028	2	074-Pitt	Resurfacing	SR 2238	SR 2236	CUL-DE-SAC	0.10	1.5" S9.5B	$20,000
2028	2	074-Pitt	Resurfacing	US 264 EB	US 264 ALT	BEAUFORT CO	11.07	2.0" S9.5C	$2,870,000
2028	2	074-Pitt	Resurfacing	US 264 WB	BEAUFORT CO	US 264 ALT	11.07	2.0" S9.5C	$2,870,000
2028	3	010-Brunswick	Resurfacing	SR 1119	SR 1125	DEAD END	1.09	Full Depth Patching and 1.5" S9.5B and Widening	$420,420
2028	3	010-Brunswick	Resurfacing	SR 1303	US 17	S.C. STATE LINE	3.67	Full Depth Patching and 1.5" S9.5B	$1,026,200
2028	3	010-Brunswick	Resurfacing	SR 1425	US 74	SR 1419	0.72	Full Depth Patching and 1.5" S9.5B and Widening	$273,600
2028	3	010-Brunswick	Resurfacing	SR 1427	SR 1426	DEAD END	1.58	Full Depth Patching and 1.5" S9.5B and Widening	$600,020
2028	3	010-Brunswick	Resurfacing	SR 1428	SR 1426	SR 1426	1.77	Full Depth Patching and 1.5" S9.5B and Widening	$673,360
2028	3	010-Brunswick	Resurfacing	SR 1460	SR 1426	DEAD END	0.44	Full Depth Patching and 1.5" S9.5B and Widening	$167,200
2028	3	010-Brunswick	Resurfacing	SR1302	SR1303	US17	1.35	1.5" S9.5B and Widen	$404,700
2028	3	010-Brunswick	Resurfacing	SR1419	US74	SR1426	1.72	Mill 1.5" and 1.5" S9.5B	$309,960
2028	3	010-Brunswick	Resurfacing	US 17 N	Lula Trl SW	US 17 BUS	5.83	1.5" S9.5C	$2,361,150
2028	3	010-Brunswick	Resurfacing	US 17 S	US 17 BUS	Elder Bright Trl NW	5.92	1.5" S9.5C	$2,397,600
2028	3	010-Brunswick	Preservation	SR 1439	SR 1438	DEAD END	0.74	1.25" S9.5B	$81,400
2028	3	010-Brunswick	Preservation	SR 1458	SR 1426	DEAD END	0.13	1.25" S9.5B	$14,300
2028	3	010-Brunswick	Preservation	SR 1543	NC 133	SR 1544	0.07	1.25" S9.5B	$8,140
2028	3	010-Brunswick	Preservation	SR 1544	SR 1546	END OF MAINT	1.10	1.25" S9.5B	$120,670
2028	3	010-Brunswick	Preservation	SR 1546	SR 1544	SR 1544	0.21	1.25" S9.5B	$22,880
2028	3	010-Brunswick	Preservation	SR 1547	SR 1544	NC 133	0.37	1.25" S9.5B	$40,150
2028	3	010-Brunswick	Preservation	SR 1583	SR 1544	DEAD END	0.43	1.25" S9.5B	$46,860
2028	3	010-Brunswick	Preservation	SR 1719	SR 1426	DEAD END	0.14	1.25" S9.5B	$15,400
2028	3	010-Brunswick	Preservation	SR 1737	SR 1426	SR 1740	0.47	1.25" S9.5B	$51,700
2028	3	010-Brunswick	Preservation	SR 1738	SR 1737	SR 1739	0.06	1.25" S9.5B	$6,600
2028	3	010-Brunswick	Preservation	SR 1739	DEAD END	DEAD END	0.20	1.25" S9.5B	$22,000
2028	3	010-Brunswick	Preservation	SR 1740	DEAD END	DEAD END	0.07	1.25" S9.5B	$7,700
2028	3	010-Brunswick	Preservation	SR 1741	SR 1426	SR 1742	0.08	1.25" S9.5B	$8,800
2028	3	010-Brunswick	Preservation	SR 1742	SR 1741	DEAD END	0.20	1.25" S9.5B	$22,000
2028	3	010-Brunswick	Preservation	SR 1744	SR 1737	DEAD END	0.07	1.25" S9.5B	$7,700
2028	3	010-Brunswick	Preservation	SR 1745	SR 1426	END MAINT	0.95	1.25" S9.5B	$104,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	3	010-Brunswick	Preservation	SR 1746	SR 1745	DEAD END	0.14	1.25" S9.5B	$15,400
2028	3	010-Brunswick	Preservation	SR 1747	SR 1745	SR 1748	0.17	1.25" S9.5B	$18,700
2028	3	010-Brunswick	Preservation	SR 1748	DEAD END	DEAD END	0.19	1.25" S9.5B	$20,900
2028	3	010-Brunswick	Preservation	SR 1749	SR 1745	DEAD END	0.10	1.25" S9.5B	$11,000
2028	3	010-Brunswick	Preservation	SR 1750	SR 1745	DEAD END	0.15	1.25" S9.5B	$16,500
2028	3	010-Brunswick	Preservation	SR 1751	SR 1750	DEAD END	0.07	1.25" S9.5B	$7,700
2028	3	010-Brunswick	Preservation	SR 1763	SR 1745	DEAD END	0.09	1.25" S9.5B	$9,900
2028	3	010-Brunswick	Preservation	SR 1764	DEAD END	SR 1745	0.13	1.25" S9.5B	$14,300
2028	3	010-Brunswick	Preservation	SR 1765	DEAD END	SR 1745	0.18	1.25" S9.5B	$19,800
2028	3	010-Brunswick	Preservation	SR1100	NC133	END MAINT	3.13	1.25" S9.5B	$344,300
2028	3	031-Duplin	Resurfacing	NC 24 E	I-40	NC 903 /NC 24 BUS	5.85	Mill 1.5" and 1.5" S9.5C	$2,350,828
2028	3	031-Duplin	Resurfacing	NC 24 W	NC 903 /NC 24 BUS	NC 24	5.20	Mill 1.5" and 1.5" S9.5C	$2,106,810
2028	3	031-Duplin	Resurfacing	SR 1105	SR 1114	SR 1104	2.43	1.5" S9.5B	$486,000
2028	3	031-Duplin	Resurfacing	SR 1130	Sampson Co	SR 1129	1.54	#67 Mat Seal and 1.5" S9.5B	$1,127,280
2028	3	031-Duplin	Resurfacing	SR 1137	SR 1101	SR 1133	1.39	1.5" S9.5B	$312,750
2028	3	031-Duplin	Resurfacing	SR 1177	SR 1103	US 117	1.57	1.5" S9.5B	$353,250
2028	3	031-Duplin	Resurfacing	SR 1331	SR 130	US 117	0.72	1.5" S9.5B	$162,000
2028	3	031-Duplin	Resurfacing	SR 1347	NC 50	GUM ST	0.34	1.5" S9.5B	$68,000
2028	3	031-Duplin	Resurfacing	SR 1363	SR 1306	SR 1004	3.09	#67 Mat Seal and 1.5" S9.5B	$618,000
2028	3	031-Duplin	Resurfacing	SR 1836	SR 1801	SR 1715	1.70	1.5" S9.5B	$325,000
2028	3	031-Duplin	Resurfacing	SR 1918	SR 1141	NC 11	2.56	#67 Mat Seal and 1.5" S9.5B	$512,000
2028	3	031-Duplin	Resurfacing	SR 1945	NC 41	SR 1944	1.05	1.5" S9.5B	$236,250
2028	3	031-Duplin	Preservation	SR 1111	NC 24 Bus	Dead End	0.92	1.0" S4.75A	$179,400
2028	3	031-Duplin	Preservation	SR 1339	SR 1342	SR 1301	0.96	Patching	$187,200
2028	3	031-Duplin	Preservation	SR 1411	SR 1110	Dead Emd	0.95	Seal - Double and Fog Seal	$109,345
2028	3	031-Duplin	Preservation	SR 1737	SR 1957	NC 50	2.20	Seal - Double and Fog Seal	$198,000
2028	3	031-Duplin	Preservation	SR 1908	SR 1927	Dead End	1.17	Seal - Double and Fog Seal	$105,300
2028	3	031-Duplin	Preservation	SR 1931	SR 1102	SR 1148	1.63	Seal - Double and Fog Seal	$146,880
2028	3	031-Duplin	Preservation	SR 1943	SR 1944	SR 1945	0.92	Seal - Double and Fog Seal	$106,375
2028	3	065-New Hanover	Resurfacing	SR 1175	US 74 MLK	SR 2195	0.55	Full Depth Patching and 1.5" S9.5C	$151,250
2028	3	065-New Hanover	Resurfacing	SR 1276	US 421	SR 1576	1.45	Full Depth Patching and 1.25" S9.5B	$397,925
2028	3	065-New Hanover	Resurfacing	SR 1349	SR 1331	Dead end	0.28	Full Depth Patching and 1.25" S9.5B	$76,000
2028	3	065-New Hanover	Resurfacing	SR 1362	SR 1361	Dead End	0.10	Leveling and 1.25" S9.5B	$26,400
2028	3	065-New Hanover	Resurfacing	SR 1384	SR 1329	Dead End	0.15	Full Depth Patching and 1.25" S9.5B	$39,000
2028	3	065-New Hanover	Resurfacing	SR 1399	NC 133	SR 1302	0.35	1.5" S9.5C	$95,425
2028	3	065-New Hanover	Resurfacing	SR 1491	SR 1400	SR 1400 + 2miles	2.00	1.5" S9.5B and Widen	$550,000
2028	3	065-New Hanover	Resurfacing	SR 1630	SR 1628	X-Cross	0.04	Full Depth Patching and 1.25" S9.5B	$10,175
2028	3	065-New Hanover	Resurfacing	SR 1774	S College Rd	Mako Dr	1.31	Mill 1.5" and 1.5" S9.5B	$360,250
2028	3	065-New Hanover	Resurfacing	SR 1775	Crosswinds Dr	Wedgefield Dr	0.44	Mill 1.5" and 1.5" S9.5B	$120,175
2028	3	065-New Hanover	Resurfacing	SR 1776	Crosswinds Dr	Dead End	0.19	Mill 1.5" and 1.5" S9.5B	$52,250
2028	3	065-New Hanover	Resurfacing	SR 1953	Myrtle Grove Rd	Lydden Rd	0.79	Mill 1.5" and 1.5" S9.5B	$217,250
2028	3	065-New Hanover	Resurfacing	SR 1954	Sentry Oaks Dr	Dead End	0.35	Mill 1.5" and 1.5" S9.5B	$94,875
2028	3	065-New Hanover	Resurfacing	SR 1955	Sentry Oaks Dr	Lanham Dr	0.18	Mill 1.5" and 1.5" S9.5B	$49,500
2028	3	065-New Hanover	Resurfacing	SR 1956	Ambleside Dr	Rowsley St	0.20	Mill 1.5" and 1.5" S9.5B	$53,900
2028	3	065-New Hanover	Resurfacing	SR 1957	Ambleside Dr	Dead End	0.06	Mill 1.5" and 1.5" S9.5B	$16,500
2028	3	065-New Hanover	Resurfacing	SR 1967	Elgin St	Sentry Oaks Dr	0.25	Mill 1.5" and 1.5" S9.5B	$67,925
2028	3	065-New Hanover	Resurfacing	SR 2221	SR 2220	SR 2699	0.14	Mill 1.25" and 1.25" S9.5B	$39,600
2028	3	065-New Hanover	Resurfacing	SR 2346	Glenarthur Dr	Dead End	0.04	Mill 1.5" and 1.5" S9.5B	$11,000
2028	3	065-New Hanover	Resurfacing	SR 2346	Carolina Beach Road	Dorrington Dr	0.61	Mill 1.5" and 1.5" S9.5B	$167,750
2028	3	065-New Hanover	Resurfacing	SR 2347	Glenarthur Dr	Dead End	0.02	Mill 1.5" and 1.5" S9.5B	$5,225
2028	3	065-New Hanover	Resurfacing	SR 2363	CDS	End (non-sys Honey Dew)	0.34	Mill 1.25" and 1.25" S9.5B	$92,125
2028	3	065-New Hanover	Resurfacing	SR 2375	Glenarthur Dr	Dead End	0.07	Mill 1.5" and 1.5" S9.5B	$19,250
2028	3	065-New Hanover	Resurfacing	SR 2378	Glenarthur Dr	Bancroft Dr	0.05	Mill 1.5" and 1.5" S9.5B	$12,650
2028	3	065-New Hanover	Resurfacing	SR 2379	Chorley Rd	Danton	0.14	Mill 1.5" and 1.5" S9.5B	$39,325
2028	3	065-New Hanover	Resurfacing	SR 2528	Crosswinds Dr	Dead End	0.02	Mill 1.5" and 1.5" S9.5B	$5,500
2028	3	065-New Hanover	Resurfacing	SR 2529	Crosswinds Dr	Wedgefield Dr	0.15	Mill 1.5" and 1.5" S9.5B	$40,975
2028	3	065-New Hanover	Resurfacing	SR 2530	Windjammer Dr	Dead End	0.11	Mill 1.5" and 1.5" S9.5B	$30,250
2028	3	065-New Hanover	Resurfacing	SR 2531	Crosscurrent Pl	Dead End	0.06	Mill 1.5" and 1.5" S9.5B	$16,500
2028	3	065-New Hanover	Resurfacing	SR 2607	SR 2605	Dead End	0.25	Mill 1.25" and 1.25" S9.5B	$67,925

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	3	065-New Hanover	Resurfacing	SR 2608	SR 2607	Dead End	0.14	Mill 1.25" and 1.25" S9.5B	$38,500
2028	3	065-New Hanover	Resurfacing	SR 2609	SR 2607	Dead End	0.12	Mill 1.25" and 1.25" S9.5B	$33,000
2028	3	065-New Hanover	Resurfacing	SR 2639	CDS	Dead End	0.06	Mill 1.25" and 1.25" S9.5B	$17,050
2028	3	065-New Hanover	Resurfacing	SR 2641	SR 2640	DEADEND	0.29	Mill 1.25" and 1.25" S9.5B	$79,750
2028	3	065-New Hanover	Resurfacing	SR 2644	SR 2640	Dead End	0.07	Mill 1.25" and 1.25" S9.5B	$20,075
2028	3	065-New Hanover	Resurfacing	SR 2648	Dead End	Dead End	0.16	Mill 1.25" and 1.25" S9.5B	$44,825
2028	3	065-New Hanover	Resurfacing	SR 2678	SR 2206	DEAD END	0.31	Mill 1.25" and 1.25" S9.5B	$86,075
2028	3	065-New Hanover	Resurfacing	SR 2679	SR 2678	DEAD END	0.05	Mill 1.25" and 1.25" S9.5B	$12,650
2028	3	065-New Hanover	Resurfacing	SR 2680	SR 2641	DEAD END	0.17	Mill 1.25" and 1.25" S9.5B	$46,475
2028	3	065-New Hanover	Resurfacing	SR 2681	SR 2678	DEAD END	0.04	Mill 1.25" and 1.25" S9.5B	$11,000
2028	3	065-New Hanover	Resurfacing	SR 2694	SR 2600	SR 2697	0.31	Full Depth Patching and 1.25" S9.5B	$84,000
2028	3	065-New Hanover	Resurfacing	SR 2705	SR 2606	Dead End	0.42	Mill 1.25" and 1.25" S9.5B	$115,500
2028	3	065-New Hanover	Resurfacing	SR 2725	SR 1327	SR 2723	0.23	Mill 1.5" and 1.5" S9.5B	$62,975
2028	3	065-New Hanover	Resurfacing	SR 2789	Masonboro Loop	Dead End	0.32	Mill 1.5" and 1.5" S9.5B	$87,725
2028	3	065-New Hanover	Resurfacing	SR 2812	NC 133	Dead End	1.30	Full Depth Patching and 1.25" S9.5B	$357,500
2028	3	065-New Hanover	Resurfacing	SR 2864	SR 2267	Cul-De-Sac	0.06	Mill .75" and .75" S9.5A	$16,225
2028	3	065-New Hanover	Resurfacing	SR 2900	Lanham Dr	Sentry Oaks Dr	0.30	Mill 1.5" and 1.5" S9.5B	$82,500
2028	3	065-New Hanover	Resurfacing	SR 2902	Ambleside Dr	Lydden Rd	0.19	Mill 1.5" and 1.5" S9.5B	$51,425
2028	3	065-New Hanover	Resurfacing	SR 2903	Granby St	Dead End	0.05	Mill 1.5" and 1.5" S9.5B	$13,750
2028	3	065-New Hanover	Resurfacing	SR 3100	Wedgefield Dr	Crosswinds Dr	0.16	Mill 1.5" and 1.5" S9.5B	$42,625
2028	3	065-New Hanover	Resurfacing	SR 3101	Masonboro Loop	Long Point Rd	0.35	Mill 1.5" and 1.5" S9.5B	$94,875
2028	3	065-New Hanover	Resurfacing	SR 3102	Downrigger Dr	Crosswinds Dr	0.24	Mill 1.5" and 1.5" S9.5B	$66,000
2028	3	065-New Hanover	Resurfacing	SR 3111	CDS	SR 1774	0.05	1.0" S9.5B	$12,650
2028	3	065-New Hanover	Resurfacing	US 17 N	SR 1402	Pender County	1.74	1.5" S9.5C	$611,793
2028	3	065-New Hanover	Resurfacing	US 17 S	Pender County	SR 1402	1.79	1.5" S9.5C	$628,992
2028	3	065-New Hanover	Resurfacing	US 421	US 74	SR 2145	3.15	1.5" S9.5C	$2,381,400
2028	3	065-New Hanover	Resurfacing	US 421	Greenfield	US 17 W	0.61	1.5" S9.5C	$197,640
2028	3	065-New Hanover	Resurfacing	US 421 S	US 17 E	Greenfield	0.51	1.5" S9.5C	$165,240
2028	3	065-New Hanover	Rehabilitation	SR 2723	SR 2725	US 117 S	0.27	Mill 1.5" and 1.5" S9.5C	$75,075
2028	3	065-New Hanover	Preservation	SR 1564	DEAD END	CUL-DE-SAC	0.66	1.0" S4.75A	$180,400
2028	3	065-New Hanover	Preservation	SR 1628	SR 1573	DEAD END	1.10	1.0" S4.75A	$302,225
2028	3	065-New Hanover	Preservation	SR 1655	SR 1492	DEAD END	0.31	.75" S4.75A	$85,250
2028	3	065-New Hanover	Preservation	SR 1701	US 421	CUL-DE-SAC	0.34	1.0" S4.75A	$93,500
2028	3	065-New Hanover	Preservation	SR 1772	DEAD END	SR 1564	0.09	.75" S4.75A	$24,750
2028	3	065-New Hanover	Preservation	SR 2324	SR 2323	CUL-DE-SAC	0.07	1.0" S4.75A	$18,425
2028	3	065-New Hanover	Preservation	SR 2356	SR 2323	CUL-DE-SAC	0.10	.75" Sand Asphalt	$26,950
2028	3	065-New Hanover	Preservation	SR 2357	SR 2323	CUL-DE-SAC	0.07	.75" Sand Asphalt	$19,250
2028	3	065-New Hanover	Preservation	SR 2358	SR 2323	CUL-DE-SAC	0.09	.75" Sand Asphalt	$25,575
2028	3	065-New Hanover	Preservation	SR 2359	CUL-DE-SAC	CUL-DE-SAC	0.19	.75" Sand Asphalt	$53,350
2028	3	065-New Hanover	Preservation	SR 2567	SR 2566	Cul-De-Sac	0.32	1.0" S4.75A	$86,900
2028	3	065-New Hanover	Preservation	SR 2568	SR 2567	Cul-De-Sac	0.13	1.0" S4.75A	$30,000
2028	3	065-New Hanover	Preservation	SR 2594	SR 2568	Cul-De-Sac	0.10	1.0" S4.75A	$26,125
2028	3	065-New Hanover	Preservation	SR 2595	SR 2567	Cul-De-Sac	0.03	1.0" S4.75A	$9,350
2028	3	065-New Hanover	Preservation	SR 2606	SR 2605	DEAD END	0.07	1.0" S4.75A	$18,975
2028	3	065-New Hanover	Preservation	SR 2675	CDS	DEAD END	0.13	1.0" S4.75A	$34,650
2028	3	067-Onslow	Resurfacing	Agatha Ct	SR 2427	CDS	0.04	1.25" S9.5B	$8,800
2028	3	067-Onslow	Resurfacing	Andrea Ave	SR 1246	EOM	0.17	1.25" S9.5B	$37,400
2028	3	067-Onslow	Resurfacing	Backfield Pl	SR 1125	Dead End	0.54	1.25" S9.5B	$118,800
2028	3	067-Onslow	Resurfacing	Beaver Trl	SR 1603	EOM	0.17	1.5" S9.5B	$37,400
2028	3	067-Onslow	Resurfacing	Bumps Creek Rd	SR 1515	Dead End	0.58	1.25" S9.5B	$127,600
2028	3	067-Onslow	Resurfacing	Cedar Fork Rd	NC 111	Duplin County Line	3.10	1.25" S9.5B	$682,000
2028	3	067-Onslow	Resurfacing	Clearview Dr	SR 1531	SR 2231	0.30	1.5" S9.5B	$66,000
2028	3	067-Onslow	Resurfacing	Deer Run	SR 1603	EOM	0.17	1.5" S9.5B	$37,400
2028	3	067-Onslow	Resurfacing	Elijah Ct	SR 2427	CDS	0.05	1.25" S9.5B	$11,000
2028	3	067-Onslow	Resurfacing	Ennett Ln	SR 1518	Dead End	1.03	1.5" S9.5B	$226,600
2028	3	067-Onslow	Resurfacing	Fowler Manning Rd	NC 111	SR 1221	3.15	1.5" S9.5B	$693,000
2028	3	067-Onslow	Resurfacing	Fox Ln	SR 1603	EOM	0.17	1.5" S9.5B	$37,400
2028	3	067-Onslow	Resurfacing	Goose Creek Rd	SR 1503	SR 1659	1.08	1.5" S9.5B	$237,600
2028	3	067-Onslow	Resurfacing	Gould Rd	SR 1217	NC 53	0.94	1.5" S9.5B	$206,800

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	3	067-Onslow	Resurfacing	Lynchburg Dr	SR 1406	SR 2626	0.35	1.5" S9.5B	$76,340
2028	3	067-Onslow	Resurfacing	Lynn Ct	SR 1277	Dead End	0.07	1.25" S9.5B	$15,400
2028	3	067-Onslow	Resurfacing	Maple Dr	SR 1694	Dead End	0.24	1.25" S9.5B	$52,800
2028	3	067-Onslow	Resurfacing	NC 210	US 17	NC 172	4.06	1.5" S9.5C	$2,797,375
2028	3	067-Onslow	Resurfacing	NC 50	Pender County	US 17	1.84	1.5" S9.5C	$546,480
2028	3	067-Onslow	Resurfacing	Old US 17	US 17	US 17	0.97	Mill 1.25" and 1.25" S9.5B	$213,400
2028	3	067-Onslow	Resurfacing	Old Wilmington Hwy	SR 1192	Dead End	0.11	1.25" S9.5B	$24,200
2028	3	067-Onslow	Resurfacing	Onslow Pines Rd	SR 1157	NC 53	0.96	1.5" S9.5B and Widen	$211,200
2028	3	067-Onslow	Resurfacing	Onslow Pines Rd	US 17	SR 1157	1.15	1.5" S9.5B and Widen	$253,000
2028	3	067-Onslow	Resurfacing	Seagull Way	SR 1603	EOM	0.20	1.5" S9.5B	$44,000
2028	3	067-Onslow	Resurfacing	Silver Maple Ct	SR 2231	Dead End	0.08	1.25" S9.5B	$17,600
2028	3	067-Onslow	Resurfacing	Smith Rd	SR 1423	SR 1434	3.70	1.5" S9.5B	$814,000
2028	3	067-Onslow	Resurfacing	Tina Ln	SR 1246	Dead End	0.04	1.25" S9.5B	$8,800
2028	3	067-Onslow	Resurfacing	US 17 N BUS	US 17	US 258	1.27	Mill 2.0" and 2.0" S9.5C	$531,913
2028	3	067-Onslow	Resurfacing	US 17 S BUS	US 258	US 17	1.25	Mill 2.0" and 2.0" S9.5C	$658,125
2028	3	067-Onslow	Resurfacing	Westmoreland Dr	SR 1410	SR 1874	0.20	1.5" S9.5B	$43,340
2028	3	067-Onslow	Resurfacing	Winery Rd	SR 1518	NC 172	1.78	1.5" S9.5B	$391,600
2028	3	067-Onslow	Preservation	Bishop Dr	SR 1213	CDS	0.43	1.25" S9.5B	$80,000
2028	3	067-Onslow	Preservation	Chisholm Trl	SR 1386 (N. Bryan)	SR 2217 (N. Maready)	0.42	1.25" S9.5B	$78,000
2028	3	067-Onslow	Preservation	Eagle Ct	SR 1995	CDS	0.06	1.25" S9.5B	$11,160
2028	3	067-Onslow	Preservation	Falls Creek Ct	CDS	CDS	0.14	1.25" S9.5B	$26,000
2028	3	067-Onslow	Preservation	Howell Dr	SR 1261	SR 1263	0.10	1.25" S9.5B	$18,228
2028	3	067-Onslow	Preservation	Loblolly Ct	SR 1959 (Winter Rd)	CDS	0.06	1.25" S9.5B	$11,300
2028	3	067-Onslow	Preservation	N Stage Coach	SR 2217 (N. Maready)	CDS	0.17	1.25" S9.5B	$31,620
2028	3	067-Onslow	Preservation	Par Dr	SR 1389	SR 1995	0.75	1.25" S9.5B	$139,128
2028	3	067-Onslow	Preservation	Park Dr	SR 1576	SR 1668	0.15	1.25" S9.5B	$12,750
2028	3	067-Onslow	Preservation	Pineview Rd	NC 111	EOM	0.22	1.25" S9.5B	$40,900
2028	3	067-Onslow	Preservation	Pond Dr	SR 1576	SR 1668	0.13	1.25" S9.5B	$25,000
2028	3	067-Onslow	Preservation	Queens St	SR 1665	End Maint	0.25	1.25" S9.5B	$45,900
2028	3	067-Onslow	Preservation	Randy Ct	SR 1369	CDS	0.06	1.25" S9.5B	$11,160
2028	3	067-Onslow	Preservation	Redwood Ct	SR 1959 (Winter rd)	CDS	0.04	1.25" S9.5B	$7,000
2028	3	067-Onslow	Preservation	S Stage Coach	SR 2217 (N. Maready)	CDS	0.14	1.25" S9.5B	$26,000
2028	3	067-Onslow	Preservation	San Antonio Tr	SR 2217 (N. Maready)	CDS	0.05	1.25" S9.5B	$9,300
2028	3	067-Onslow	Preservation	Spice Dr	SR 1501	SR 1670	0.08	1.25" S9.5B	$15,066
2028	3	067-Onslow	Preservation	Stella Rd	SR 1434	County Line	1.21	Seal - Cape	$94,000
2028	3	067-Onslow	Preservation	Stillbrook Ct	SR 1260	CDS	0.15	1.25" S9.5B	$27,714
2028	3	067-Onslow	Preservation	Swinson Rd	SR 1201	SR 1203	2.06	Microsurface	$123,600
2028	3	067-Onslow	Preservation	Tar Kiln Dr	SR 1432	CDS	0.74	1.0" S9.5B	$111,000
2028	3	067-Onslow	Preservation	Vera Dr/Ct	US 258	CDS	0.22	1.25" S9.5B	$41,480
2028	3	067-Onslow	Preservation	Windy Bluff Ct	SR 1920	CDS	0.04	1.25" S9.5B	$7,440
2028	3	071-Pender	Resurfacing	NC 11/53	Bladen County	End C&G East of Whitehouse Ave	4.60	1.5" S9.5C	$1,366,200
2028	3	071-Pender	Resurfacing	NC 50	Little Kinston Rd	Onslow County	2.56	1.5" S9.5C	$897,507
2028	3	071-Pender	Resurfacing	SR 1520	NC 210	SR 1526	5.85	Full Depth Patching and 1.5" S9.5B and Widening	$1,800,000
2028	3	071-Pender	Resurfacing	SR 1526	NC 50	Duplin CL	3.60	Full Depth Patching and 1.5" S9.5B	$800,000
2028	3	071-Pender	Resurfacing	SR 1527	SR 1526	Onslow CL	1.20	Full Depth Patching and 1.5" S9.5B	$280,000
2028	3	071-Pender	Resurfacing	SR 1529	SR 1520	EOM	2.40	Full Depth Patching and 1.5" S9.5B	$530,000
2028	3	071-Pender	Resurfacing	SR 1530	SR 1529	Onslow CL	0.68	Full Depth Patching and 1.5" S9.5B	$150,000
2028	3	071-Pender	Resurfacing	SR 1531	SR 1530	EOM	0.40	Full Depth Patching and 1.5" S9.5B	$95,000
2028	3	071-Pender	Resurfacing	SR 1534	SR 1588	SR 1534	0.70	Full Depth Patching and 1.5" S9.5B and Widening	$400,000
2028	3	071-Pender	Resurfacing	SR 1535	SR 1534	EOM	0.70	Full Depth Patching and 1.5" S9.5B and Widening	$400,000
2028	3	071-Pender	Resurfacing	SR 1560	NC 210	EOM	2.15	Full Depth Patching and 1.5" S9.5B and Widening	$785,000
2028	3	071-Pender	Resurfacing	SR 1580	NC 50	SR 1529	1.30	Full Depth Patching and 1.5" S9.5B	$290,000
2028	3	071-Pender	Resurfacing	SR 1582	US 17	SR 1603	1.57	Full Depth Patching and 1.5" S9.5B	$350,000
2028	3	071-Pender	Resurfacing	SR 1588	NC 50	EOM	1.35	Full Depth Patching and 1.5" S9.5B and Widening	$500,000
2028	3	071-Pender	Resurfacing	SR 1597	SR 1529	EOM	0.28	Full Depth Patching and 1.5" S9.5B	$62,000
2028	3	071-Pender	Preservation	SR 1216	SR 1128	SR 1343	9.90	Full Depth Patching and 1.0" S4.75A	$986,750
2028	3	071-Pender	Preservation	SR 1786	SR 1560	SR 1787	0.60	Full Depth Patching and 1.0" S4.75A	$65,000
2028	3	071-Pender	Preservation	SR 1787	SR 1786	EOM	0.10	Full Depth Patching and 1.0" S4.75A	$12,000
2028	3	082-Sampson	Resurfacing	SR 1284	SR 1242	SR 1216	0.54	1.5" S9.5B	$148,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	3	082-Sampson	Resurfacing	SR 1336	US 421	SR 1338	1.18	1.5" S9.5B	$0
2028	3	082-Sampson	Resurfacing	SR 1606	SR 1602	SR 1002	3.07	1.5" S9.5B	$844,250
2028	3	082-Sampson	Resurfacing	SR 1610	SR 1002	SR 1602	0.89	1.5" S9.5B	$244,750
2028	3	082-Sampson	Resurfacing	SR 1716	SR 1722	NC 55	2.00	1.5" S9.5B	$550,000
2028	3	082-Sampson	Resurfacing	SR 1720	SR 1725	NC 50	1.72	1.5" S9.5B	$471,900
2028	3	082-Sampson	Resurfacing	SR 1724	US 701	SR 1711	1.74	1.5" S9.5B	$0
2028	3	082-Sampson	Resurfacing	SR 1741	US 701	SR 1742	2.91	1.5" S9.5B	$800,250
2028	3	082-Sampson	Resurfacing	SR 1802	SR 1845	SR 1843	0.89	1.5" S9.5B	$0
2028	3	082-Sampson	Resurfacing	SR 1809	US 421	SR 1636	3.36	1.5" S9.5B	$924,000
2028	3	082-Sampson	Resurfacing	SR 1810	SR 1805	SR 1636	0.65	1.5" S9.5B	$0
2028	3	082-Sampson	Resurfacing	SR 1814	SR1636	SR 1703	1.84	1.5" S9.5B	$506,000
2028	3	082-Sampson	Resurfacing	SR 1818	SR 1746	US 701	2.82	1.5" S9.5B	$775,500
2028	3	082-Sampson	Resurfacing	SR 1821	SR 1746	SR 1820	1.07	1.5" S9.5B	$294,250
2028	3	082-Sampson	Resurfacing	SR 1824	SR 1817	US 701	0.91	1.5" S9.5B	$250,250
2028	3	082-Sampson	Resurfacing	SR 1839	US 421	SR 1296	1.35	Mill Curb and 1.5" S9.5B	$371,250
2028	3	082-Sampson	Resurfacing	SR 1918	NC 24	SR 1904	3.06	1.5" S9.5B	$841,775
2028	3	082-Sampson	Resurfacing	SR 1922	NC 24	SR 1924	1.42	1.5" S9.5B	$390,500
2028	3	082-Sampson	Resurfacing	US 421	SR 1475	Harnett County	9.40	1.5" S9.5C	$3,299,049
2028	3	082-Sampson	Preservation	SR 1100	SR 1007	SR 1105	4.90	Seal - Double and Fog Seal	$196,000
2028	3	082-Sampson	Preservation	SR 1120	SR 1007	NC 411	4.69	Seal - Double and Fog Seal	$187,600
2028	3	082-Sampson	Preservation	SR 1131	NC 41	SR 1133	4.56	Seal - Double and Fog Seal	$182,400
2028	3	082-Sampson	Preservation	SR 1430	SR 1006	SR 1414	4.74	Seal - Double and Fog Seal	$189,600
2028	3	082-Sampson	Preservation	SR 1904	NC 403	Duplin Co. Line	7.72	Seal - Double and Fog Seal	$309,200
2028	4	033-Edgecombe	Resurfacing	NC 33	NC 97	SR 1423	7.94	Mill 1.5" and 1.5" S9.5B	$1,588,000
2028	4	033-Edgecombe	Resurfacing	NC-33	Tar River Bridge / Bells Bridge	nc-97	4.59	Mill 1.5" and 1.5" S9.5B	$918,000
2028	4	033-Edgecombe	Resurfacing	SR 1123	NC 42	NC 111	0.94	1.5" S9.5B	$126,900
2028	4	033-Edgecombe	Resurfacing	SR 1316	NC 33	Dead End	0.27	1.25" S9.5B	$30,375
2028	4	033-Edgecombe	Resurfacing	SR 1317	Cul-De-Sac	Dead End	0.23	1.25" S9.5B	$25,875
2028	4	033-Edgecombe	Resurfacing	SR 1318	SR 1316	Dead End	0.07	1.25" S9.5B	$7,875
2028	4	033-Edgecombe	Resurfacing	SR 1319	Cul-De-Sac	Dead End	0.12	1.25" S9.5B	$13,500
2028	4	033-Edgecombe	Resurfacing	SR 1410	SR 1404	End of Pavement	3.84	1.5" S9.5B	$518,400
2028	4	033-Edgecombe	Resurfacing	SR 1423	NC-33	SR 1429	3.90	1.5" S9.5B	$526,500
2028	4	033-Edgecombe	Resurfacing	SR 1428	SR 1409	NC-33	2.23	1.5" S9.5B and Widen	$587,525
2028	4	033-Edgecombe	Resurfacing	SR 1576	NC-33	Dead End	0.17	1.25" S9.5B	$19,125
2028	4	033-Edgecombe	Resurfacing	SR 1576	SR 1428	Dead End	0.34	1.5" S9.5B	$45,900
2028	4	033-Edgecombe	Resurfacing	SR 1601	US 258	NC 43	8.38	1.5" S9.5B	$1,382,700
2028	4	033-Edgecombe	Resurfacing	SR 1603	US 258	SR 1601	1.11	1.5" S9.5B	$149,850
2028	4	033-Edgecombe	Preservation	NC 97	SR 1278	NC 33	12.02	Crack Seal	$100,125
2028	4	033-Edgecombe	Preservation	SR 1429	NC 33	Halifax CL	7.85	Microsurface	$510,250
2028	4	033-Edgecombe	Preservation	SR 1431	SR 1429	SR 1430	1.57	Microsurface	$102,050
2028	4	042-Halifax	Resurfacing	NC 4	NC 48	NC 561	3.27	Mill 1.5" and 1.5" S9.5C	$662,175
2028	4	042-Halifax	Resurfacing	NC 4	Nash Co	NC 48	9.63	Mill 1.5" and 1.5" S9.5C	$1,901,925
2028	4	042-Halifax	Resurfacing	SR 1105	NC 125	SR 1100	7.16	1.5" S9.5B	$1,008,200
2028	4	042-Halifax	Resurfacing	SR 1207	SR 1206	SR 1210	1.84	1.25" S9.5B	$325,400
2028	4	042-Halifax	Resurfacing	SR 1235	SR 1216	End Maint.	1.13	1.25" S9.5B	$127,125
2028	4	042-Halifax	Resurfacing	SR 1432	US 158	NC 903	1.60	1.25" S9.5B	$180,000
2028	4	042-Halifax	Resurfacing	SR 1621	NC Highway 125	US Highway 301	2.91	1.5" S9.5B	$421,950
2028	4	042-Halifax	Resurfacing	SR 1804	SR 1118	NC 903	1.38	1.5" S9.5B	$200,100
2028	4	042-Halifax	Resurfacing	SR 1806	US 258	End of State Maintenance	1.01	1.5" S9.5B	$146,450
2028	4	042-Halifax	Resurfacing	SR 1817	SR 1815	Edgecombe County Line	1.86	1.5" S9.5B	$269,700
2028	4	042-Halifax	Resurfacing	SR 1818	SR 1817	Dead End	0.47	1.5" S9.5B	$142,100
2028	4	042-Halifax	Resurfacing	US 301	SR 1668	North Hampton City Limits	4.67	Mill 1.5" and 1.5" S9.5C	$943,650
2028	4	042-Halifax	Preservation	SR 1100	US 258	SR 1815	3.25	Crack Seal	$20,313
2028	4	042-Halifax	Preservation	SR 1103	SR 1105	SR 1003	2.06	Microsurface	$123,900
2028	4	042-Halifax	Preservation	SR 1103	SR 1008	NC 125	2.93	Crack Seal	$18,313
2028	4	042-Halifax	Preservation	SR 1137	NC Highway 561	NC Highway 561	1.55	Seal - Double and Fog Seal	$75,250
2028	4	042-Halifax	Preservation	SR 1300	SR 1001	NC 48	9.63	Crack Seal	$60,188
2028	4	042-Halifax	Preservation	SR 1424	US 158	SR 1400	1.88	Seal - Double and Fog Seal	$89,300
2028	4	042-Halifax	Preservation	SR 1429	NC 903	SR 1434	2.29	Seal - Double and Fog Seal	$108,775

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	4	042-Halifax	Preservation	SR 1601	NC 48	SR 1210	4.07	Seal - Double and Fog Seal	$184,325
2028	4	042-Halifax	Preservation	SR 1609	NC 48	Dead End	0.63	Microsurface	$40,950
2028	4	042-Halifax	Preservation	SR 1610	SR 1001	NC 48	3.19	Seal - Double and Fog Seal	$151,525
2028	4	042-Halifax	Preservation	SR 1657	SR 1651	SR 1655	0.92	Crack Seal	$5,750
2028	4	042-Halifax	Preservation	SR 1821	NC 122	Martin County Line	1.04	Seal - Double and Fog Seal	$49,400
2028	4	051-Johnston	Resurfacing	SR 1003	US 70 Bus	SR 1923	1.54	Mill 1.5" and 1.5" S9.5C	$454,300
2028	4	051-Johnston	Resurfacing	SR 1005	Harnett County Line	NC 96	6.03	1.5" S9.5B	$874,350
2028	4	051-Johnston	Resurfacing	SR 1104	NC 242	NC 50	1.48	1.5" S9.5B	$199,800
2028	4	051-Johnston	Resurfacing	SR 1130	SR 1122	SR 1008	0.50	1.5" S9.5B	$67,500
2028	4	051-Johnston	Resurfacing	SR 1133	SR 1116	SR 1132	0.54	1.5" S9.5B	$72,900
2028	4	051-Johnston	Resurfacing	SR 1152	SR 1150	SR 1151	0.57	1.5" S9.5B	$76,950
2028	4	051-Johnston	Resurfacing	SR 1154	NC 96	End of Pavement	0.53	1.5" S9.5B	$71,550
2028	4	051-Johnston	Resurfacing	SR 1177	SR 1143	NC 96	1.52	1.5" S9.5B	$205,200
2028	4	051-Johnston	Resurfacing	SR 1225	SR 1178	NC 96	0.92	1.5" S9.5B	$124,200
2028	4	051-Johnston	Resurfacing	SR 1338	NC 210	SR 1335	1.58	1.5" S9.5B	$213,165
2028	4	051-Johnston	Resurfacing	SR 1514	SR 1010	SR 1330	1.32	1.5" S9.5B	$177,525
2028	4	051-Johnston	Resurfacing	SR 1548	SR 1525	Dead End	1.31	1.5" S9.5B	$176,850
2028	4	051-Johnston	Resurfacing	SR 1556	NC 42	SR 1555	3.60	1.5" S9.5B	$594,000
2028	4	051-Johnston	Resurfacing	SR 2101	SR2102	NC 39	1.41	1.5" S9.5B	$190,350
2028	4	051-Johnston	Resurfacing	SR 2130	SR 2335	Micro Town Limits	1.27	Mill 1.5" and 1.5" S9.5B	$254,000
2028	4	051-Johnston	Resurfacing	SR 2133	SR 1934	US 301	1.07	1.5" S9.5B	$144,450
2028	4	051-Johnston	Resurfacing	SR 2141	SR 2312	US 70A	1.75	1.5" S9.5B	$236,250
2028	4	051-Johnston	Resurfacing	SR 2150	SR 2110	SR 2149	0.92	1.5" S9.5B	$124,200
2028	4	051-Johnston	Resurfacing	SR 2162	SR 2105	SR 2105	0.64	1.5" S9.5B	$86,400
2028	4	051-Johnston	Resurfacing	SR 2309	SR 1001	SR 1927	2.30	1.5" S9.5B	$333,500
2028	4	051-Johnston	Resurfacing	SR 2313	US 70	SR 2519	0.76	1.5" S9.5B	$102,600
2028	4	051-Johnston	Resurfacing	SR 2320	US 70	Wayne County Line	8.37	1.5" S9.5B	$1,129,950
2028	4	051-Johnston	Resurfacing	SR 2334	SR 1001	SR 2363	0.55	1.5" S9.5B	$74,250
2028	4	051-Johnston	Resurfacing	SR 2344	NC 222	SR 2341	2.19	1.5" S9.5B	$295,650
2028	4	051-Johnston	Resurfacing	SR 2354	SR 2341	SR 1002	6.69	1.5" S9.5B	$903,150
2028	4	051-Johnston	Resurfacing	SR 2359	SR 2356	SR 2320	1.05	1.5" S9.5B	$141,750
2028	4	051-Johnston	Resurfacing	SR 2366	SR 2363	SR 1001	1.44	1.5" S9.5B	$194,400
2028	4	051-Johnston	Resurfacing	SR 2406	SR 2307	SR 2305	0.63	1.5" S9.5B	$85,050
2028	4	051-Johnston	Resurfacing	US 301	US 70 Business	SR 2889	1.64	Mill 1.5" and 1.5" S9.5C	$824,100
2028	4	051-Johnston	Resurfacing	US 70 Bus	US 70 Bypass	NC 210	6.58	Mill 1.5" and 1.5" S9.5B	$1,776,100
2028	4	051-Johnston	Resurfacing	US 70 Bus	NC 210	US 70 Bypass	6.57	Mill 1.5" and 1.5" S9.5B	$1,782,650
2028	4	051-Johnston	Preservation	SR 1362	SR 1308	Dead End	0.43	1.25" S9.5B	$48,375
2028	4	051-Johnston	Preservation	SR 1379	SR 1331	Dead End	0.31	1.25" S9.5B	$34,875
2028	4	051-Johnston	Preservation	SR 1397	SR 1309	Cul-De-Sac	0.22	1.25" S9.5B	$24,750
2028	4	051-Johnston	Preservation	SR 1679	SR 1557	Cul-De-Sac	0.29	1.25" S9.5B	$32,625
2028	4	051-Johnston	Preservation	SR 1680	SR 1679	Cul-De-Sac	0.05	1.25" S9.5B	$5,625
2028	4	051-Johnston	Preservation	SR 1681	SR 1679	Cul-De-Sac	0.06	1.25" S9.5B	$6,750
2028	4	051-Johnston	Preservation	SR 1682	SR 1679	Cul-De-Sac	0.08	1.25" S9.5B	$9,000
2028	4	051-Johnston	Preservation	SR 1683	SR 1679	Cul-De-Sac	0.06	1.25" S9.5B	$6,750
2028	4	051-Johnston	Preservation	SR 1713	SR 1700	Dead End	0.99	1.25" S9.5B	$111,375
2028	4	051-Johnston	Preservation	SR 1791	SR 1003	SR 1792	0.10	1.25" S9.5B	$11,250
2028	4	051-Johnston	Preservation	SR 1792	Cul-De-Sac	Cul-De-Sac	0.40	1.25" S9.5B	$45,000
2028	4	051-Johnston	Preservation	SR 1793	Cul-De-Sac	Cul-De-Sac	0.12	1.25" S9.5B	$13,500
2028	4	051-Johnston	Preservation	SR 1808	SR 1571	Cul-De-Sac	0.31	1.25" S9.5B	$34,875
2028	4	051-Johnston	Preservation	SR 1809	SR 1808	Cul-De-Sac	0.52	1.25" S9.5B	$58,500
2028	4	051-Johnston	Preservation	SR 1810	SR 1809	Cul-De-Sac	0.09	1.25" S9.5B	$10,125
2028	4	051-Johnston	Preservation	SR 1811	SR 1809	Cul-De-Sac	0.05	1.25" S9.5B	$5,625
2028	4	051-Johnston	Preservation	SR 1872	SR 1517	Cul-De-Sac	0.65	1.25" S9.5B	$73,125
2028	4	051-Johnston	Preservation	SR 1873	SR 1872	Cul-De-Sac	0.05	1.25" S9.5B	$5,625
2028	4	051-Johnston	Preservation	SR 1874	SR 1872	Cul-De-Sac	0.08	1.25" S9.5B	$9,000
2028	4	051-Johnston	Preservation	SR 1875	SR 1782	Cul-De-Sac	0.10	1.25" S9.5B	$11,250
2028	4	051-Johnston	Preservation	SR 2091	NC 42	Cul-De-Sac	0.21	1.25" S9.5B	$23,513
2028	4	051-Johnston	Preservation	SR 2092	SR 2091	CUL-DE-SAC	0.05	1.25" S9.5B	$5,625
2028	4	051-Johnston	Preservation	SR 2093	SR 2091	CUL-DE-SAC	0.17	1.25" S9.5B	$19,125

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	4	051-Johnston	Preservation	SR 2094	SR 2093	CUL-DE-SAC	0.03	1.25" S9.5B	$3,375
2028	4	051-Johnston	Preservation	SR 2204	SR 1537	Dead End	0.17	1.25" S9.5B	$19,125
2028	4	051-Johnston	Preservation	SR 2261	NC 210	Dead End	0.20	1.25" S9.5B	$22,500
2028	4	051-Johnston	Preservation	SR 2275	SR 1530	SR 2276	0.12	1.25" S9.5B	$13,500
2028	4	051-Johnston	Preservation	SR 2276	SR 2278	End Maintenance	0.32	1.25" S9.5B	$36,000
2028	4	051-Johnston	Preservation	SR 2277	SR 2276	Wake County Line	0.03	1.25" S9.5B	$3,375
2028	4	051-Johnston	Preservation	SR 2278	SR 2276	Cul-De-Sac	0.49	1.25" S9.5B	$55,125
2028	4	051-Johnston	Preservation	SR 2279	SR 2278	Cul-De-Sac	0.09	1.25" S9.5B	$10,125
2028	4	051-Johnston	Preservation	SR 2280	SR 2278	Cul-De-Sac	0.25	1.25" S9.5B	$28,125
2028	4	051-Johnston	Preservation	SR 2281	SR 2278	Cul-De-Sac	0.21	1.25" S9.5B	$23,625
2028	4	051-Johnston	Preservation	SR 2282	SR 2278	Cul-De-Sac	0.20	1.25" S9.5B	$22,500
2028	4	051-Johnston	Preservation	SR 2283	SR 1578	SR 2286	0.59	1.25" S9.5B	$66,375
2028	4	051-Johnston	Preservation	SR 2284	SR 2283	Dead End	0.11	1.25" S9.5B	$12,375
2028	4	051-Johnston	Preservation	SR 2286	SR 2283	Dead End	0.09	1.25" S9.5B	$10,125
2028	4	051-Johnston	Preservation	SR 2287	SR 2283	Dead End	0.08	1.25" S9.5B	$9,000
2028	4	051-Johnston	Preservation	SR 2296	SR 1528	SR 2297	0.57	1.25" S9.5B	$64,125
2028	4	051-Johnston	Preservation	SR 2297	Cul-De-Sac	Cul-De-Sac	0.68	1.25" S9.5B	$76,500
2028	4	051-Johnston	Preservation	SR 2298	SR 2282	Cul-De-Sac	0.46	1.25" S9.5B	$51,750
2028	4	051-Johnston	Preservation	SR 2608	SR 1706	Cul-De-Sac	0.07	1.25" S9.5B	$7,875
2028	4	051-Johnston	Preservation	SR 2617	SR 1706	Cul-De-Sac	0.31	1.25" S9.5B	$34,875
2028	4	051-Johnston	Preservation	SR 2618	SR 2617	Cul-De-Sac	0.13	1.25" S9.5B	$14,625
2028	4	051-Johnston	Preservation	SR 2619	SR 2617	Cul-De-Sac	0.07	1.25" S9.5B	$7,875
2028	4	051-Johnston	Preservation	SR 2647	SR 1705	End of Maintenance	0.21	1.25" S9.5B	$23,625
2028	4	051-Johnston	Preservation	SR 2648	SR 2647	Cul-De-Sac	0.12	1.25" S9.5B	$13,500
2028	4	051-Johnston	Preservation	SR 2649	SR 2647	Cul-De-Sac	0.11	1.25" S9.5B	$12,375
2028	4	051-Johnston	Preservation	SR 2650	SR 2649	Cul-De-Sac	0.08	1.25" S9.5B	$9,000
2028	4	051-Johnston	Preservation	SR 2685	SR 2283	Dead End	0.20	1.25" S9.5B	$22,500
2028	4	051-Johnston	Preservation	SR 2688	SR 1706	Cul-De-Sac	0.64	1.25" S9.5B	$72,000
2028	4	051-Johnston	Preservation	SR 2689	SR 1706	Dead End	0.67	1.25" S9.5B	$75,375
2028	4	051-Johnston	Preservation	SR 2700	SR 1308	CUL-DE-SAC	0.13	1.25" S9.5B	$14,625
2028	4	051-Johnston	Preservation	SR 3105	SR 2297	Cul-De-Sac	0.59	1.25" S9.5B	$66,375
2028	4	051-Johnston	Preservation	SR 3106	SR 3105	Cul-De-Sac	0.24	1.25" S9.5B	$27,000
2028	4	051-Johnston	Preservation	SR 3107	SR 3105	Cul-De-Sac	0.15	1.25" S9.5B	$16,875
2028	4	051-Johnston	Preservation	SR 3108	SR 3105	Cul-De-Sac	0.22	1.25" S9.5B	$24,750
2028	4	051-Johnston	Preservation	SR 3121	SR 1536	End Maintenance	0.18	1.25" S9.5B	$20,250
2028	4	051-Johnston	Preservation	SR 3155	SR 1563	Cul-De-Sac	0.35	1.25" S9.5B	$39,375
2028	4	051-Johnston	Preservation	SR 3156	SR 1563	Cul-De-Sac	0.07	1.25" S9.5B	$7,875
2028	4	051-Johnston	Preservation	SR 3157	SR 1563	Cul-De-Sac	0.08	1.25" S9.5B	$9,000
2028	4	051-Johnston	Preservation	SR 3204	SR 1706	Cul-De-Sac	0.25	1.25" S9.5B	$28,125
2028	4	051-Johnston	Preservation	SR 3205	NC 42	Cul-De-Sac	0.23	1.25" S9.5B	$30,475
2028	4	051-Johnston	Preservation	SR 3206	SR 3205	SR 3207	0.06	1.25" S9.5B	$7,950
2028	4	051-Johnston	Preservation	SR 3207	SR 3206	Cul-De-Sac	0.08	1.25" S9.5B	$10,600
2028	4	051-Johnston	Preservation	SR 3208	SR 3206	Cul-De-Sac	0.08	1.25" S9.5B	$10,600
2028	4	051-Johnston	Preservation	SR 3222	SR 1713	Cul-De-Sac	0.59	1.25" S9.5B	$66,375
2028	4	051-Johnston	Preservation	SR 3223	SR 1713	Cul-De-Sac	0.63	1.25" S9.5B	$70,875
2028	4	051-Johnston	Preservation	SR 3224	SR 3223	Cul-De-Sac	0.22	1.25" S9.5B	$24,750
2028	4	051-Johnston	Preservation	SR 3241	SR 2689	Dead End	0.27	1.25" S9.5B	$30,375
2028	4	051-Johnston	Preservation	SR 3266	SR 2617	CUL-DE-SAC	0.06	1.25" S9.5B	$6,750
2028	4	051-Johnston	Preservation	SR 3267	SR 1517	Cul-De-Sac	0.11	1.25" S9.5B	$12,375
2028	4	051-Johnston	Preservation	SR 3268	SR 2688	Dead End	0.14	1.25" S9.5B	$15,750
2028	4	051-Johnston	Preservation	SR 3397	NC 50	SR 3398	0.20	1.25" S9.5B	$22,500
2028	4	051-Johnston	Preservation	SR 3398	SR 3397	Cul-De-Sac	0.19	1.25" S9.5B	$21,375
2028	4	051-Johnston	Preservation	SR 3399	SR 3397	Cul-De-Sac	0.12	1.25" S9.5B	$13,500
2028	4	064-Nash	Resurfacing	NC 58	Wilson County Line	SR 1717	5.07	Mill 1.5" and 1.5" S9.5B	$2,002,650
2028	4	064-Nash	Resurfacing	NC-43	US-264 Bypass	NC-97	5.92	Mill 1.5" and 1.5" S9.5B	$2,338,400
2028	4	064-Nash	Resurfacing	NC-581	East Nash St	Frankline County Line	4.44	Mill 1.5" and 1.5" S9.5B	$2,131,200
2028	4	064-Nash	Resurfacing	NC-581	NC-97	SR 1717	3.80	Mill 1.5" and 1.5" S9.5B	$1,501,000
2028	4	064-Nash	Resurfacing	SR 1748	SR 1717	Mile Marker 0.51	0.51	1.5" S9.5B	$73,950
2028	4	064-Nash	Resurfacing	SR 1947	Graham Brantley Road	Old Bailey Hwy	1.19	1.5" S9.5B	$174,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	4	064-Nash	Preservation	SR 1116	Johnston Co	NC 231	2.64	1.0" S4.75A	$297,000
2028	4	064-Nash	Preservation	SR 1412	SR 1411	SR 1004	1.31	1.0" S4.75A	$147,375
2028	4	064-Nash	Preservation	SR 1502	SR 1501	Halifax CL	3.29	1.0" S4.75A	$350,125
2028	4	064-Nash	Preservation	SR 1503	SR 1502	SR 1506	3.00	1.0" S4.75A	$337,500
2028	4	064-Nash	Preservation	SR 1532	SR 1524	SR 1531	1.02	Microsurface	$71,500
2028	4	096-Wayne	Resurfacing	SR 1115	SR 1183	Sampson County Line	2.80	1.25" S9.5B	$315,000
2028	4	096-Wayne	Resurfacing	SR 1313	US 117	SR 1300	0.93	1.5" S9.5B	$125,550
2028	4	096-Wayne	Resurfacing	SR 1320	US 117	SR 1336	5.10	1.5" S9.5B	$688,500
2028	4	096-Wayne	Resurfacing	SR 1520	NC 222	SR 1505	2.27	1.5" S9.5B	$306,450
2028	4	096-Wayne	Resurfacing	SR 1535	SR 1534	SR 1556	3.10	1.5" S9.5B	$418,500
2028	4	096-Wayne	Resurfacing	SR 1537	US 117	NC 222	5.60	1.5" S9.5B	$630,000
2028	4	096-Wayne	Resurfacing	SR 1614	SR 1537	Dead End	0.36	1.25" S9.5B	$40,500
2028	4	096-Wayne	Resurfacing	SR 1710	NC 111	Dead End	2.69	1.25" S9.5B	$363,150
2028	4	096-Wayne	Resurfacing	SR 1824	NC 111	Dead End	0.48	1.25" S9.5B	$54,000
2028	4	096-Wayne	Resurfacing	SR 1831	SR 1003	Dead End	0.29	1.25" S9.5B	$34,875
2028	4	096-Wayne	Resurfacing	SR 1909	SR 1710	Dead End	1.13	1.5" S9.5B	$152,550
2028	4	096-Wayne	Resurfacing	SR 1931	SR 1930	SR 2010	1.94	1.5" S9.5B	$261,900
2028	4	096-Wayne	Resurfacing	SR 1932	SR 1744	SR 1120	3.46	1.5" S9.5B	$467,100
2028	4	096-Wayne	Resurfacing	SR 1937	NC 55	SR 1932	4.17	1.25" S9.5B	$469,125
2028	4	096-Wayne	Resurfacing	Sr 1955	SR 1957	NC 55	1.54	1.25" S9.5B	$173,250
2028	4	096-Wayne	Resurfacing	SR 2018	NC 111	Dead End	0.21	1.25" S9.5B	$23,625
2028	4	096-Wayne	Resurfacing	SR 2225	SR 1719	Dead End	0.72	1.25" S9.5B	$81,000
2028	4	096-Wayne	Resurfacing	SR 2226	SR 2225	Dead End	0.04	1.25" S9.5B	$4,500
2028	4	096-Wayne	Resurfacing	SR 2227	SR 2225	Dead End	0.04	1.25" S9.5B	$4,500
2028	4	096-Wayne	Resurfacing	SR 2228	SR 2225	Dead end	0.04	1.25" S9.5B	$4,500
2028	4	096-Wayne	Resurfacing	SR 2229	SR 2225	SR 2225	0.33	1.25" S9.5B	$37,125
2028	4	096-Wayne	Resurfacing	SR 2230	SR 2229	Dead End	0.04	1.25" S9.5B	$4,500
2028	4	096-Wayne	Resurfacing	US 13	SR 1006	SR 1220	6.20	Mill 2.0" and 2.0" S9.5C	$1,798,000
2028	4	096-Wayne	Resurfacing	US 70	NC 581	SR 1326	2.87	Mill 1.5" and 1.5" S9.5D	$774,900
2028	4	096-Wayne	Resurfacing	US 70	NC 581	SR 1326	2.84	Mill 1.5" and 1.5" S9.5D	$766,800
2028	4	096-Wayne	Preservation	SR 1058	SR 1529	NC 111	2.84	Seal - Double and Fog Seal	$102,800
2028	4	096-Wayne	Preservation	SR 1105	SR 1008	US 13	3.25	1.25" S9.5B	$365,625
2028	4	096-Wayne	Preservation	SR 1126	US 13	US 13	2.01	Seal - Double and Fog Seal	$90,450
2028	4	096-Wayne	Preservation	SR 1127	SR 1120	US 13	2.57	Seal - Double and Fog Seal	$115,650
2028	4	096-Wayne	Preservation	SR 1132	SR 1120	SR 1127	1.67	Seal - Double and Fog Seal	$65,150
2028	4	096-Wayne	Preservation	SR 1536	NC-222	NC-22	2.24	1.25" S9.5B	$252,000
2028	4	096-Wayne	Preservation	SR 1740	NC 111	SR 1741	0.62	Microsurface	$38,300
2028	4	096-Wayne	Preservation	SR 1741	NC 111	Dead End	1.18	Microsurface	$76,700
2028	4	096-Wayne	Preservation	SR 1746	SR 1746	NC 111	0.94	Microsurface	$61,100
2028	4	096-Wayne	Preservation	SR 1956	SR 1754	NC 55	1.39	.75" S4.75A	$121,625
2028	4	098-Wilson	Resurfacing	NC 42	Joint Near Exum Road	I-95	4.80	Mill 1.5" and 1.5" S9.5B	$960,000
2028	4	098-Wilson	Resurfacing	SR 1103	Dead End	SR 1154	5.11	1.5" S9.5B	$689,850
2028	4	098-Wilson	Resurfacing	SR 1154	US-264 Alt	NC-42	3.85	1.5" S9.5B	$519,750
2028	4	098-Wilson	Resurfacing	SR 1320	NC Highway 58	US 264 Alt	2.00	Mill 1.5" and 1.5" S9.5B	$790,000
2028	4	098-Wilson	Resurfacing	SR 1382	NC 58	Dead End	3.20	1.5" S9.5B	$432,000
2028	4	098-Wilson	Resurfacing	SR 1432	SR 1002	Edgecombe CL	2.24	1.5" S9.5B and Widen	$616,000
2028	4	098-Wilson	Resurfacing	US 117	Wayne County Line	US 301	6.88	Mill 2.0" and 2.0" S9.5B	$1,923,600
2028	4	098-Wilson	Resurfacing	US 301	SR 1003	US 264	9.59	Mill 1.5" and 1.5" S9.5C	$2,500,000
2028	4	098-Wilson	Resurfacing	US 301	US 264	SR 1003	9.52	Mill 1.5" and 1.5" S9.5C	$2,500,000
2028	4	098-Wilson	Preservation	NC 58	County Line	SR 1622	6.20	Crack Seal	$38,750
2028	4	098-Wilson	Preservation	SR 1171	SR 1100	US 301	0.95	1.0" S4.75A	$103,325
2028	4	098-Wilson	Preservation	SR 1184	Ward Blvd	SR 1192	1.06	.75" S4.75A	$92,750
2028	4	098-Wilson	Preservation	SR 1197	NC 42	Dead End	1.18	1.0" S4.75A	$122,750
2028	4	098-Wilson	Preservation	SR 1357	SR 1323	SR 1358	0.15	Crack Seal	$937
2028	4	098-Wilson	Preservation	SR 1358	SR 1397	SR 1395	0.23	Crack Seal	$1,437
2028	4	098-Wilson	Preservation	SR 1395	SR 1396	SR 1323	0.17	Crack Seal	$1,062
2028	4	098-Wilson	Preservation	SR 1396	SR 1397	SR 1395	0.18	Crack Seal	$1,125
2028	4	098-Wilson	Preservation	SR 1397	SR 1446	SR 1369	0.14	Crack Seal	$875
2028	4	098-Wilson	Preservation	SR 1407	SR 1003	SR 1002	1.25	Crack Seal	$7,812

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	4	098-Wilson	Preservation	SR 1446	SR 1323	Dead End	0.26	Crack Seal	$1,625
2028	4	098-Wilson	Preservation	SR 1447	SR 1446	Dead End	0.06	Crack Seal	$375
2028	4	098-Wilson	Preservation	SR 1510	NC 42	SR 1506	2.55	.75" S4.75A	$223,125
2028	4	098-Wilson	Preservation	SR 1602	SR 1606	SR 1628	7.34	Crack Seal	$45,875
2028	4	098-Wilson	Preservation	SR 1643	US 117	SR 1649	3.33	Microsurface	$206,450
2028	5	032-Durham	Resurfacing	Cornwallis Rd.	SR 2028	Width Change	0.64	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$170,000
2028	5	032-Durham	Resurfacing	Cornwallis Rd.	Width Change	Width Change	0.56	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$301,000
2028	5	032-Durham	Resurfacing	Cornwallis Rd.	Width Change	SR 1959	0.74	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$380,000
2028	5	032-Durham	Resurfacing	Cortez Dr	SR 1926	Dead End	0.16	Full Depth Patching and 1.5" S9.5B	$35,000
2028	5	032-Durham	Resurfacing	Esther Dr.	END MAINT	Dead End	0.42	Full Depth Patching and 1.25" S9.5B	$78,000
2028	5	032-Durham	Resurfacing	Ferrell Rd	SR 1670	SR 1670	1.42	Full Depth Patching and 1.5" S9.5B	$311,000
2028	5	032-Durham	Resurfacing	Hinesley Dr.	US 70	END MAINT	0.22	Full Depth Patching and 1.25" S9.5B	$40,000
2028	5	032-Durham	Resurfacing	Hursey St	SR 1919	Dead End	0.29	Full Depth Patching and 1.5" S9.5B	$63,000
2028	5	032-Durham	Resurfacing	Miami Blvd	Begin Divided	US 70	0.10	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$0
2028	5	032-Durham	Resurfacing	Miami Blvd	US 70	SR 2028	1.82	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,223,000
2028	5	032-Durham	Resurfacing	MLK Pkwy	NC 751	SR 2220	0.77	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$415,000
2028	5	032-Durham	Resurfacing	NC 54	SR 1959	End Divided Hwy	1.04	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$289,000
2028	5	032-Durham	Resurfacing	NC 54	Begin Divided	Orange County	2.08	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$695,000
2028	5	032-Durham	Resurfacing	NC 54	Slater Rd	Finley Ave	1.06	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$769,000
2028	5	032-Durham	Resurfacing	NC 54	Begin Divided Hwy	SR 1959	1.03	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$312,000
2028	5	032-Durham	Resurfacing	NC 54	Rodbell St Park Dr	Begin Divided Hwy	0.06	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$32,000
2028	5	032-Durham	Resurfacing	NC 54	Orange County	Bridge #41	2.47	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$826,000
2028	5	032-Durham	Resurfacing	NC 54	NC 55	Rodbell St	1.89	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,372,000
2028	5	032-Durham	Resurfacing	Pickett Rd	Begin Pavement	US 15/501	1.91	Full Depth Patching and 1.5" S9.5B	$415,000
2028	5	032-Durham	Resurfacing	Quail Roost Farm Rd	US 501	End Pavement	0.47	Full Depth Patching and 1.5" S9.5B	$82,000
2028	5	032-Durham	Resurfacing	Stone Rd.	SR 1955	END MAINT	0.56	Full Depth Patching and 1.25" S9.5B	$109,000
2028	5	032-Durham	Preservation	Allister Rd	SR 2038	SR 2040	0.21	1.0" S9.5B	$26,000
2028	5	032-Durham	Preservation	Asbury Ct	SR 1905	Dead End	0.20	1.0" S9.5B	$25,000
2028	5	032-Durham	Preservation	Atwood Ct	SR 2031	Dead End	0.06	1.0" S9.5B	$7,000
2028	5	032-Durham	Preservation	Bandock Rd	SR 2042	SR 2044	0.56	1.0" S9.5B	$69,000
2028	5	032-Durham	Preservation	Bayard Rd.	SR 1811	SR 2111	0.22	1.0" S9.5B	$27,000
2028	5	032-Durham	Preservation	Bernard Dr	SR 2022	SR 2039	0.09	1.0" S9.5B	$11,000
2028	5	032-Durham	Preservation	Colony Rd.	SR 1303	Begin C&G	0.26	1.0" S9.5B	$32,000
2028	5	032-Durham	Preservation	Crystal Lake Rd	END MAINT	NC 157	0.09	1.0" S9.5B	$13,000
2028	5	032-Durham	Preservation	Cub Creek Rd	SR 1004	END MAINT	0.48	1.0" S9.5B	$48,000
2028	5	032-Durham	Preservation	Currin St	SR 1815	Dead End	0.33	1.0" S9.5B	$40,000
2028	5	032-Durham	Preservation	Danbury Dr	SR 1911	SR 2038	0.31	1.0" S9.5B	$38,000
2028	5	032-Durham	Preservation	Horseman Tr	SR 1902	END MAINT	0.06	1.0" S9.5B	$9,000
2028	5	032-Durham	Preservation	Hoyle St	SR 1004	SR 1653	0.13	1.0" S9.5B	$16,000
2028	5	032-Durham	Preservation	King William Ct	SR 2146	Dead End	0.07	1.0" S9.5B	$9,000
2028	5	032-Durham	Preservation	Morganton St	SR 1815	SR 1913	0.07	1.0" S9.5B	$8,000
2028	5	032-Durham	Preservation	Old Cole Mill Rd	SR 1401	END MAINT	0.22	1.0" S9.5B	$27,000
2028	5	032-Durham	Preservation	Old Orange Factory Rd	SR 1628	Dead End	0.14	1.0" S9.5B	$16,000
2028	5	032-Durham	Preservation	Paddock Dr	SR 1901	SR 1902	0.25	1.0" S9.5B	$31,000
2028	5	032-Durham	Preservation	Stratmore Dr	SR 1901	END MAINT	0.18	1.0" S9.5B	$22,000
2028	5	032-Durham	Preservation	Van Dr	SR 1911	Dead End	0.47	1.0" S9.5B	$58,000
2028	5	032-Durham	Preservation	Willow Springs Dr	SR 1815	END MAINT	0.15	1.0" S9.5B	$17,000
2028	5	035-Franklin	Resurfacing	Bunn Ave	NC 39	SR 1765	0.16	Full Depth Patching and 1.5" S9.5B	$35,000
2028	5	035-Franklin	Resurfacing	Claymont Rd	SR 1720	Cul-de-sac	0.38	Full Depth Patching and 1.5" S9.5B	$83,000
2028	5	035-Franklin	Resurfacing	Clifton Ridge Ct	Cul-de-sac	Cul-de-sac	0.17	Full Depth Patching and 1.25" S9.5B	$33,000
2028	5	035-Franklin	Resurfacing	Clifton Woods Dr	SR 1103	Cul-de-sac	0.30	Full Depth Patching and 1.25" S9.5B	$58,000
2028	5	035-Franklin	Resurfacing	County Day Dr	NC 39	Cul-de-sac	0.20	Full Depth Patching and 1.5" S9.5B	$44,000
2028	5	035-Franklin	Resurfacing	Leonard Rd.	NC 561	NC 561	4.77	Leveling and 1.25" S9.5B	$1,081,000
2028	5	035-Franklin	Resurfacing	N Pointe Drive	SR 1720	Dead End	0.28	Full Depth Patching and 1.5" S9.5B	$61,000
2028	5	035-Franklin	Resurfacing	NC 561	Pavement Joint	Nash County	6.25	Full Depth Patching and 1.5" S9.5B	$1,430,000
2028	5	035-Franklin	Resurfacing	NC 581	Nash Co	SR 1639	4.14	Full Depth Patching and 1.5" S9.5B	$903,000
2028	5	035-Franklin	Resurfacing	NC 98	US 401	NC 39	8.50	Full Depth Patching and 1.5" S9.5B	$2,250,000
2028	5	035-Franklin	Resurfacing	North Street	SR 1717	SR 1794	0.18	Full Depth Patching and 1.5" S9.5B	$39,000
2028	5	035-Franklin	Resurfacing	Oakside Ct	SR 1782	Cul-de-sac	0.08	Full Depth Patching and 1.5" S9.5B	$17,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	5	035-Franklin	Resurfacing	Perdues Road	NC 561	SR 1433	2.61	Full Depth Patching and 1.5" S9.5B	$569,000
2028	5	035-Franklin	Resurfacing	Pineview Dr	Cul-de-sac	Cul-de-sac	0.35	Full Depth Patching and 1.5" S9.5B	$76,000
2028	5	035-Franklin	Resurfacing	Ray Ave	SR 1765	Dead End	0.07	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$15,000
2028	5	035-Franklin	Resurfacing	Tollie Weldon	VANCE CO	US 401	3.89	Full Depth Patching and 1.25" S9.5B	$681,000
2028	5	035-Franklin	Resurfacing	Water Dr	NC 39	Dead End	0.12	Full Depth Patching and 1.5" S9.5B	$26,000
2028	5	035-Franklin	Resurfacing	Westport Ln	SR 1788	Cul-de-sac	0.09	Full Depth Patching and 1.5" S9.5B	$20,000
2028	5	035-Franklin	Preservation	AF Moore	SR 1002	End Pavement	0.59	Full Depth Patching and Double Seal	$53,000
2028	5	035-Franklin	Preservation	Arnold Rd.	NC 98	SR 1707	1.69	Full Depth Patching and Double Seal and Fog Seal	$158,000
2028	5	035-Franklin	Preservation	Arthur Wilder	SR 1002	NASH CO	0.94	Full Depth Patching and Double Seal	$85,000
2028	5	035-Franklin	Preservation	Floyd Rd	NC 98	SR 1716	0.60	Full Depth Patching and Double Seal and Fog Seal	$59,000
2028	5	035-Franklin	Preservation	John Winstead	SR 1700	SR 1001	1.60	Full Depth Patching and Triple Seal	$221,000
2028	5	035-Franklin	Preservation	Lake View	NC 39	SR 1401	1.49	Full Depth Patching and Double Seal	$134,000
2028	5	035-Franklin	Preservation	Lynch Evans	SR 1637	End Pavement	0.36	Full Depth Patching and Double Seal	$32,000
2028	5	035-Franklin	Preservation	Ransdell Rd.	SR 1707	SR 1001	1.95	Full Depth Patching and Double Seal and Fog Seal	$174,000
2028	5	039-Granville	Resurfacing	E. Industry Dr	US 15	NC 96	1.15	Full Depth Patching and 1.5" S9.5C	$304,000
2028	5	039-Granville	Resurfacing	Goshen Rd	SR 1309	SR 1315	1.70	Full Depth Patching and 1.5" S9.5B	$370,000
2028	5	039-Granville	Resurfacing	Moss Rd	NC 56	SR 1639	0.87	Full Depth Patching and 1.5" S9.5B	$171,000
2028	5	039-Granville	Resurfacing	NC 96	Pavement Joint	SR 1606	3.79	Full Depth Patching and 1.5" S9.5B	$950,000
2028	5	039-Granville	Resurfacing	NC 96	SR 1606	Third St	0.83	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$458,000
2028	5	039-Granville	Resurfacing	Old NC 75	Durham County Line	Ledge Creek	6.06	Full Depth Patching and 1.5" S9.5B	$1,635,000
2028	5	039-Granville	Resurfacing	Veasey Rd	SR 1004	SR 1174	1.37	Full Depth Patching and 1.5" S9.5B	$299,000
2028	5	039-Granville	Resurfacing	Warrior Rd	US 158	US 15	1.13	Full Depth Patching and 1.5" S9.5B	$296,000
2028	5	039-Granville	Resurfacing	Webb School Rd	SR 1422	US 15	0.81	Full Depth Patching and 1.5" S9.5B	$203,000
2028	5	039-Granville	Resurfacing	Westbrook Drive	SR 1239	SR 1115	0.59	Full Depth Patching and 1.5" S9.5B	$142,000
2028	5	039-Granville	Preservation	Buckhorn Rd	County Line	US-15	2.33	Full Depth Patching and 1.25" S9.5B	$453,000
2028	5	039-Granville	Preservation	Horner Siding Rd	SR 1525	SR 1522	2.85	Full Depth Patching and 1.25" S9.5B	$554,000
2028	5	039-Granville	Preservation	McDuffie Rd	SR 1445	SR 1501	2.49	Full Depth Patching and 1.25" S9.5B	$484,000
2028	5	073-Person	Resurfacing	Broad Rd	NC 49	SR 1601	1.98	Full Depth Patching and 1.5" S9.5B	$432,000
2028	5	073-Person	Resurfacing	Granite Drive	NC 57	NC 57	0.41	Full Depth Patching and 1.5" S9.5B	$80,000
2028	5	073-Person	Resurfacing	Halifax Rd	NC 49	SR 1536	2.03	Full Depth Patching and 1.5" S9.5B	$443,000
2028	5	073-Person	Resurfacing	McMahon-Faulkner Rd	SR 1534	Dead End	0.08	Full Depth Patching and 1.5" S9.5B	$20,000
2028	5	073-Person	Resurfacing	Mollie Mooney Rd	US 158	SR 1542	2.70	Full Depth Patching and 1.5" S9.5B	$618,000
2028	5	073-Person	Resurfacing	Old Allensville Rd	SR 1717	SR 1536	0.75	Full Depth Patching and 1.5" S9.5B	$171,000
2028	5	073-Person	Resurfacing	Younger Road	NC 57	SR 1333	1.19	Full Depth Patching and 1.5" S9.5B	$272,000
2028	5	073-Person	Preservation	C C Andrews Rd	US 501	SR 1125	1.04	Full Depth Patching and Double Seal and Fog Seal	$94,000
2028	5	073-Person	Preservation	Epps Martin Rd	SR 1505	SR 1509	1.70	Full Depth Patching and Double Seal and Fog Seal	$168,000
2028	5	073-Person	Preservation	High Plains School Rd	SR 1504	SR 1506	0.64	Full Depth Patching and Double Seal and Fog Seal	$63,000
2028	5	073-Person	Preservation	High View Church Rd	NC 49	VIRGINIA	1.76	Full Depth Patching and Double Seal and Fog Seal	$174,000
2028	5	073-Person	Preservation	Jack Ford Rd	SR 1348	Cul-de-sac	0.51	Full Depth Patching and Double Seal	$46,000
2028	5	073-Person	Preservation	Street Store Rd	NC 49	SR 1520	1.01	Full Depth Patching and Double Seal and Fog Seal	$100,000
2028	5	073-Person	Preservation	Thomas Humphries Rd	NC 49	END MAINT	0.89	Full Depth Patching and Double Seal and Fog Seal	$88,000
2028	5	073-Person	Preservation	Tom Webb Rd	SR 1519	End Pavement	1.43	Full Depth Patching and Double Seal and Fog Seal	$141,000
2028	5	091-Vance	Resurfacing	Bearpond Rd	SR 1519	US 1 Bus	2.15	Full Depth Patching and 1.5" S9.5B	$516,000
2028	5	091-Vance	Resurfacing	Graham Ave	SR 1162	Fairway Dr	0.68	Full Depth Patching and 1.25" S9.5B	$133,000
2028	5	091-Vance	Resurfacing	NC 39	US 158	Virginia State Line	16.27	Full Depth Patching and 1.5" S9.5B	$4,079,000
2028	5	091-Vance	Resurfacing	Poplar Creek	US 158 Bus	SR 1304	3.12	Full Depth Patching and 1.5" S9.5B	$613,000
2028	5	091-Vance	Resurfacing	Warrenton Road	WARREN CO	US 1 Bus	5.36	Full Depth Patching and 1.25" S9.5B	$1,043,000
2028	5	091-Vance	Resurfacing	Welcome-King Ave	US 1 Bus	SR 1148	0.95	1.0" S9.5B	$117,000
2028	5	091-Vance	Preservation	Weldons Mill	SR 1541	SR 1523	1.91	1.0" S9.5B	$213,000
2028	5	091-Vance	Preservation	Weldons Mill	SR 1533	SR 1541	2.39	1.0" S9.5B	$267,000
2028	5	092-Wake	Resurfacing	Adam Ln	SR 2411	SR 2423	0.27	Full Depth Patching and 1.25" S9.5B	$52,000
2028	5	092-Wake	Resurfacing	Afton Ln	SR 3805	Dead End	0.60	Full Depth Patching and 1.5" S9.5B	$118,000
2028	5	092-Wake	Resurfacing	Auburn Church Rd	SR 5225	SR 1004	1.11	Full Depth Patching and 1.5" S9.5B	$265,000
2028	5	092-Wake	Resurfacing	Austin Creek Dr	Cul-de-sac	Cul-de-sac	0.37	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$98,000
2028	5	092-Wake	Resurfacing	Ballot Rd	SR 1004	SR 4199	0.47	1.0" S9.5B	$58,000
2028	5	092-Wake	Resurfacing	Bashford Bluffs Ln	SR 2728	Cul-de-sac	0.12	Full Depth Patching and 1.25" S9.5B	$24,000
2028	5	092-Wake	Resurfacing	Belinda Dr	SR 3805	Cul-de-sac	0.14	Full Depth Patching and 1.5" S9.5B	$27,000
2028	5	092-Wake	Resurfacing	Beneventum Ct	Cul-de-sac	Cul-de-sac	0.12	Full Depth Patching and 1.25" S9.5B	$21,000
2028	5	092-Wake	Resurfacing	Bittbourg Ln	Cul-de-sac	Cul-de-sac	0.17	Full Depth Patching and 1.25" S9.5B	$29,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	5	092-Wake	Resurfacing	Black Creek Ct	SR 2988	Cul-de-sac	0.21	Full Depth Patching and 1.5" S9.5B	$41,000
2028	5	092-Wake	Resurfacing	Blue Ridge Rd	SR 1774	SR 1775	0.27	Mill 2.0" and 2.0" S9.5C	$86,000
2028	5	092-Wake	Resurfacing	Blue Ridge Rd	U-4437 Limits	SR 1774	0.48	Mill 2.0" and 2.0" S9.5C	$416,000
2028	5	092-Wake	Resurfacing	Blue Ridge Rd	SR 1775	SR 1774	0.27	Mill 2.0" and 2.0" S9.5C	$92,000
2028	5	092-Wake	Resurfacing	Blue Ridge to Wade Ramp	SR 1664	U-2719 Limits	0.18	Mill 2.0" and 2.0" S9.5C	$90,000
2028	5	092-Wake	Resurfacing	Blue Ridge to Wade Ramp	SR 1664	U-2719 Limits	0.19	Mill 2.0" and 2.0" S9.5C	$65,000
2028	5	092-Wake	Resurfacing	Bluffwind Dr	SR 1375	Dead End	0.23	Full Depth Patching and 1.5" S9.5B	$5,000
2028	5	092-Wake	Resurfacing	Bobbyfield Way	NC 96	Cul-de-sac	0.18	Full Depth Patching and 1.25" S9.5B	$32,000
2028	5	092-Wake	Resurfacing	Brack Penny Rd	JOHNSTON CO	SR 2731	1.45	Full Depth Patching and 1.5" S9.5B	$316,000
2028	5	092-Wake	Resurfacing	Bradford Grove Pl	SR 1386	Cul-de-sac	0.35	Full Depth Patching and 1.5" S9.5B	$76,000
2028	5	092-Wake	Resurfacing	Bridgemont Ln	SR 2750	Cul-de-sac	0.64	Full Depth Patching and 1.25" S9.5B	$112,000
2028	5	092-Wake	Resurfacing	Brilliant Dr	SR 2215	Dead End	0.39	1.0" S9.5B	$48,000
2028	5	092-Wake	Resurfacing	Buccaneer Ct	SR 4315	Cul-de-sac	0.11	Full Depth Patching and 1.25" S9.5B	$20,000
2028	5	092-Wake	Resurfacing	Burlington Mills Rd	SR 2019	US 401 Bus	2.03	Full Depth Patching and 1.5" S9.5B	$474,000
2028	5	092-Wake	Resurfacing	Callens Ln	SR 2742	Cul-de-sac	0.22	Full Depth Patching and 1.5" S9.5B	$43,000
2028	5	092-Wake	Resurfacing	Cartwright Cir	SR 2422	END MAINT	0.21	Full Depth Patching and 1.25" S9.5B	$40,000
2028	5	092-Wake	Resurfacing	Cascadia Dr	SR 5207	Cul-de-sac	0.12	Full Depth Patching and 1.25" S9.5B	$24,000
2028	5	092-Wake	Resurfacing	Chicora Wood Dr	SR 1382	SR 4768	0.15	Full Depth Patching and 1.25" S9.5B	$26,000
2028	5	092-Wake	Resurfacing	Cleveland School Rd	JOHNSTON CO	NC 50	0.95	Full Depth Patching and 1.5" S9.5B	$247,000
2028	5	092-Wake	Resurfacing	Colston Crossing	SR 2368	SR 2407	0.51	Full Depth Patching and 1.25" S9.5B	$100,000
2028	5	092-Wake	Resurfacing	Crestline Rd	SR 2320	Cul-de-sac	0.33	Full Depth Patching and 1.25" S9.5B	$63,000
2028	5	092-Wake	Resurfacing	Crestwood Dr	Dead End	Cul-de-sac	0.15	1.0" S9.5B	$19,000
2028	5	092-Wake	Resurfacing	Dan David Dr	SR 1384	SR 1524	0.21	Full Depth Patching and 1.25" S9.5B	$41,000
2028	5	092-Wake	Resurfacing	Davis Dr	Beg Div Hwy	End Divided	0.55	Mill 2.0" and 2.0" S9.5C	$153,000
2028	5	092-Wake	Resurfacing	Davis Dr	SR 1639	End Divided	5.85	Mill 2.0" and 2.0" S9.5C	$1,911,000
2028	5	092-Wake	Resurfacing	Davis Dr	Beg Div Hwy	SR 1639	5.86	Mill 2.0" and 2.0" S9.5C	$1,915,000
2028	5	092-Wake	Resurfacing	Davis Dr	Pavement Joint	Beg Div Hwy	0.16	Mill 2.0" and 2.0" S9.5C	$132,000
2028	5	092-Wake	Resurfacing	Davis Dr	Beg Div Hwy	End Divided	0.55	Mill 2.0" and 2.0" S9.5C	$155,000
2028	5	092-Wake	Resurfacing	Davis Dr	End Divided	Beg Div Hwy	0.14	Mill 2.0" and 2.0" S9.5C	$38,000
2028	5	092-Wake	Resurfacing	Deer Trace Ln	Cul-de-sac	Dead end	0.50	1.0" S9.5B	$61,000
2028	5	092-Wake	Resurfacing	Dolans Way	SR 2005	SR 4443	0.10	Full Depth Patching and 1.25" S9.5B	$28,000
2028	5	092-Wake	Resurfacing	Doyle Rd	NC 96	SR 2308	0.98	Full Depth Patching and 1.25" S9.5B	$191,000
2028	5	092-Wake	Resurfacing	Durham Rd	NC 98	End Divided Hwy	0.15	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$40,000
2028	5	092-Wake	Resurfacing	Durham Rd	Begin Divided Hwy	NC 98	0.14	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$37,000
2028	5	092-Wake	Resurfacing	Durham Rd	End Divided Hwy	Pvmt Jt E of US1	1.05	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$697,000
2028	5	092-Wake	Resurfacing	Durham Rd/Dr Calvin Jones Hwy	Vermilion Ct	US 1	1.74	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$544,000
2028	5	092-Wake	Resurfacing	Durham Rd/Dr Calvin Jones Hwy	US 1	End Divided Hwy	1.71	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$670,000
2028	5	092-Wake	Resurfacing	E Garner Rd	I-40	SR 2555	1.98	Full Depth Patching and 1.5" S9.5B	$475,000
2028	5	092-Wake	Resurfacing	E Millbrook Dr	SR 2000	SR 1005	1.62	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$785,000
2028	5	092-Wake	Resurfacing	Ellen Dr	SR 2516	SR 2602	0.19	Full Depth Patching and 1.25" S9.5B	$33,000
2028	5	092-Wake	Resurfacing	Ellen Dr	SR 2577	SR 2577	0.26	Full Depth Patching and 1.25" S9.5B	$46,000
2028	5	092-Wake	Resurfacing	Eric St	SR 1006	SR 5310	0.60	Full Depth Patching and 1.25" S9.5B	$105,000
2028	5	092-Wake	Resurfacing	Fields Dr	SR 2721	SR 2881	0.24	Full Depth Patching and 1.25" S9.5B	$47,000
2028	5	092-Wake	Resurfacing	Forest Glen Dr	SR 2732	SR 4844	0.42	Full Depth Patching and 1.5" S9.5B	$92,000
2028	5	092-Wake	Resurfacing	Fribourd Ct	Cul-de-sac	Dead End	0.30	Full Depth Patching and 1.25" S9.5B	$58,000
2028	5	092-Wake	Resurfacing	Garnet Cir	SR 3787	Cul-de-sac	0.05	Full Depth Patching and 1.5" S9.5B	$10,000
2028	5	092-Wake	Resurfacing	Glen Brack Ct	SR 4840	Cul-de-sac	0.05	Full Depth Patching and 1.25" S9.5B	$10,000
2028	5	092-Wake	Resurfacing	Glennevis Ln	SR 1003	SR 2470	0.38	Full Depth Patching and 1.25" S9.5B	$73,000
2028	5	092-Wake	Resurfacing	Green Farm Ln	SR 2224	Dead End	0.25	Full Depth Patching and 1.25" S9.5B	$43,000
2028	5	092-Wake	Resurfacing	Halifax Rd	NC 96	SR 2310	2.01	Full Depth Patching and 1.5" S9.5B	$438,000
2028	5	092-Wake	Resurfacing	Hayrick Ct	SR 5137	Cul-de-sac	0.05	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$12,000
2028	5	092-Wake	Resurfacing	Holiday Ave	SR 2337	Dead End	0.65	Full Depth Patching and 1.25" S9.5B	$127,000
2028	5	092-Wake	Resurfacing	Holly Springs New Hill Rd	Pavement Joint	SR 1149	1.12	Full Depth Patching and 1.5" S9.5B	$257,000
2028	5	092-Wake	Resurfacing	Horton Rd	SR 1101	Dead End	1.37	Full Depth Patching and 1.5" S9.5B	$283,000
2028	5	092-Wake	Resurfacing	Jicarilla Ln	NC 55	Cul-de-sac	0.25	Full Depth Patching and 1.25" S9.5B	$48,000
2028	5	092-Wake	Resurfacing	John Adams Rd	SR 2748	SR 1006	0.28	Full Depth Patching and 1.5" S9.5B	$58,000
2028	5	092-Wake	Resurfacing	Joseph Michael Ct	Cul-de-sac	Cul-de-sac	0.12	Full Depth Patching and 1.25" S9.5B	$23,000
2028	5	092-Wake	Resurfacing	Kapalua Way	SR 2555	Cul-de-sac	0.39	Full Depth Patching and 1.5" S9.5B	$85,000
2028	5	092-Wake	Resurfacing	Kinton Dr	SR 2756	Cul-de-sac	0.47	Full Depth Patching and 1.5" S9.5B	$92,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	5	092-Wake	Resurfacing	La Costa Way	SR 2555	END MAINT	0.96	Full Depth Patching and 1.5" S9.5B	$209,000
2028	5	092-Wake	Resurfacing	Labaron Dr	SR 2759	SR 3807	0.91	Full Depth Patching and 1.5" S9.5B	$178,000
2028	5	092-Wake	Resurfacing	Laurel Leaf Rd	SR 2369	Cul-de-sac	0.43	Full Depth Patching and 1.25" S9.5B	$83,000
2028	5	092-Wake	Resurfacing	Lone Holly Way	SR 5207	Cul-de-sac	0.08	Full Depth Patching and 1.25" S9.5B	$16,000
2028	5	092-Wake	Resurfacing	Long St	SR 2886	SR 2887	0.53	Full Depth Patching and 1.5" S9.5B	$115,000
2028	5	092-Wake	Resurfacing	Lullwater Dr	SR 1377	Cul-de-sac	0.18	Full Depth Patching and 1.5" S9.5B	$39,000
2028	5	092-Wake	Resurfacing	Mangum Dr	SR 2320	SR 2422	0.56	Full Depth Patching and 1.5" S9.5B	$122,000
2028	5	092-Wake	Resurfacing	Meadow Dr	US 401	Cul-de-sac	0.76	Full Depth Patching and 1.5" S9.5B	$166,000
2028	5	092-Wake	Resurfacing	Meadowview Ct	SR 1010	Cul-de-sac	0.08	Full Depth Patching and 1.25" S9.5B	$15,000
2028	5	092-Wake	Resurfacing	Merrimac Dr	SR 1010	Dead End	0.51	Full Depth Patching and 1.5" S9.5B	$111,000
2028	5	092-Wake	Resurfacing	Middle Ridge Dr	Dead End	Cul-de-sac	0.95	Full Depth Patching and 1.25" S9.5B	$166,000
2028	5	092-Wake	Resurfacing	NC 54	County Line	Watkins Rd	1.14	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$611,000
2028	5	092-Wake	Resurfacing	NC 55	Pavement Joint	Pavement Joint	5.28	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$3,535,000
2028	5	092-Wake	Resurfacing	New Oak St	SR 2303	SR 2447	0.57	Full Depth Patching and 1.25" S9.5B	$112,000
2028	5	092-Wake	Resurfacing	Norman Blalock Rd	NC 42	SR 1006	1.33	Full Depth Patching and 1.5" S9.5B	$290,000
2028	5	092-Wake	Resurfacing	North Manor Dr	SR 1001	Dead End	0.49	Full Depth Patching and 1.25" S9.5B	$95,000
2028	5	092-Wake	Resurfacing	North Way Dr	SR 2339	SR 2309	0.50	1.0" S9.5B	$62,000
2028	5	092-Wake	Resurfacing	Oak Bridge Dr	SR 5207	Cul-de-sac	0.37	Full Depth Patching and 1.25" S9.5B	$71,000
2028	5	092-Wake	Resurfacing	Oak Village Way	SR 1122	Cul-de-sac	0.47	1.0" S9.5B	$58,000
2028	5	092-Wake	Resurfacing	Oakton Dr	SR 1381	SR 4000	0.64	Full Depth Patching and 1.5" S9.5B	$139,000
2028	5	092-Wake	Resurfacing	Open Field Dr	END MAINT	SR 5324	0.69	Full Depth Patching and 1.5" S9.5B	$150,000
2028	5	092-Wake	Resurfacing	Overdale Ln	SR 5364	SR 2736	0.31	Full Depth Patching and 1.25" S9.5B	$54,000
2028	5	092-Wake	Resurfacing	Panther Hill Ln	SR 2736	Cul-de-sac	0.20	Full Depth Patching and 1.5" S9.5B	$39,000
2028	5	092-Wake	Resurfacing	Partridsge Berry Dr	SR 3999	Cul-de-sac	0.30	Full Depth Patching and 1.25" S9.5B	$58,000
2028	5	092-Wake	Resurfacing	Patrician Way	SR 2340	END MAINT	0.27	Full Depth Patching and 1.25" S9.5B	$52,000
2028	5	092-Wake	Resurfacing	Pembridge Ln	Cul-de-sac	Cul-de-sac	0.49	1.0" S9.5B	$61,000
2028	5	092-Wake	Resurfacing	Percussion Dr	SR 1303	Dead End	0.40	Full Depth Patching and 1.5" S9.5B	$88,000
2028	5	092-Wake	Resurfacing	Phillips Landing Dr	SR 1003	Cul-de-sac	0.38	Full Depth Patching and 1.25" S9.5B	$66,000
2028	5	092-Wake	Resurfacing	Phlox Rd	SR 4321	Dead End	0.15	Full Depth Patching and 1.25" S9.5B	$26,000
2028	5	092-Wake	Resurfacing	Pitty Pats Path	NC 97	Cul-de-sac	0.52	Full Depth Patching and 1.25" S9.5B	$102,000
2028	5	092-Wake	Resurfacing	Poplarwood Dr	SR 2419	Cul-de-sac	0.12	Full Depth Patching and 1.25" S9.5B	$23,000
2028	5	092-Wake	Resurfacing	Quail Covey Ln	SR 1003	Cul-de-sac	0.69	Full Depth Patching and 1.25" S9.5B	$135,000
2028	5	092-Wake	Resurfacing	Quail Marsh Dr	SR 4886	SR 2750	0.23	Full Depth Patching and 1.25" S9.5B	$40,000
2028	5	092-Wake	Resurfacing	Ramblewood Dr	SR 1308	Cul-de-sac	0.27	Full Depth Patching and 1.5" S9.5B	$59,000
2028	5	092-Wake	Resurfacing	Ravens Creek Ct	SR 4042	Cul-de-sac	0.09	Full Depth Patching and 1.25" S9.5B	$16,000
2028	5	092-Wake	Resurfacing	Ray Rd	SR 1829	SR 1822	3.21	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,004,000
2028	5	092-Wake	Resurfacing	Richard Dr	SR 1652	Cul-de-sac	0.32	Full Depth Patching and 1.25" S9.5B	$62,000
2028	5	092-Wake	Resurfacing	Ridgebrook Bluffs	SR 1375	Cul-de-sac	0.45	Full Depth Patching and 1.5" S9.5B	$88,000
2028	5	092-Wake	Resurfacing	Robertson Pond Rd	SR 1003	SR 2300	1.67	Full Depth Patching and 1.5" S9.5B	$365,000
2028	5	092-Wake	Resurfacing	Rock Service Station Rd	NC 42	JOHNSTON CO	0.96	Full Depth Patching and 1.5" S9.5B	$209,000
2028	5	092-Wake	Resurfacing	Royal Acres	SR 2551	Dead End	0.36	Full Depth Patching and 1.25" S9.5B	$63,000
2028	5	092-Wake	Resurfacing	Silver Spring Ct	SR 4887	Cul-de-sac	0.27	Full Depth Patching and 1.25" S9.5B	$47,000
2028	5	092-Wake	Resurfacing	Standing Timber Dr	SR 5434	Cul-de-sac	0.11	Full Depth Patching and 1.25" S9.5B	$21,000
2028	5	092-Wake	Resurfacing	Stevens Oaks Dr	NC 50	SR 5325	0.53	Full Depth Patching and 1.5" S9.5B	$115,000
2028	5	092-Wake	Resurfacing	Stoney Creek Dr	SR 2557	Cul-de-sac	0.32	1.0" S9.5B	$40,000
2028	5	092-Wake	Resurfacing	Strymon Ct	SR 2488	Cul-de-sac	0.03	Full Depth Patching and 1.25" S9.5B	$4,000
2028	5	092-Wake	Resurfacing	Tall Cane Cir	SR 5309	SR 5311	0.31	Full Depth Patching and 1.25" S9.5B	$54,000
2028	5	092-Wake	Resurfacing	Timpani Trl	SR 5805	END MAINT	0.12	Full Depth Patching and 1.25" S9.5B	$24,000
2028	5	092-Wake	Resurfacing	Trellis Ct	SR 2215	Cul-de-sac	0.26	Full Depth Patching and 1.25" S9.5B	$46,000
2028	5	092-Wake	Resurfacing	US 1	Veridea Pkwy Overpass	Pavement Joint	1.97	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$704,000
2028	5	092-Wake	Resurfacing	US 1	Pavement Joint	Veridea Pkwy Overpass	1.64	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$584,000
2028	5	092-Wake	Resurfacing	US 64 Bus	SR 2473	Schneider/Ametek Way	3.55	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,188,000
2028	5	092-Wake	Resurfacing	US 64 Bus	Morning Flyer Way	SR 2473	3.55	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,190,000
2028	5	092-Wake	Resurfacing	Village of Wakefield Dr	SR 2468	Cul-de-sac	0.31	Full Depth Patching and 1.25" S9.5B	$60,000
2028	5	092-Wake	Resurfacing	Vintners Ct	SR 5205	Cul-de-sac	0.06	Full Depth Patching and 1.25" S9.5B	$11,000
2028	5	092-Wake	Resurfacing	W Millbrook Rd	SR 1005	North Hills Dr	0.87	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$578,000
2028	5	092-Wake	Resurfacing	Wade to Blue Ridge Ramp	U-2719 Limits	SR 1664	0.16	Mill 2.0" and 2.0" S9.5C	$91,000
2028	5	092-Wake	Resurfacing	Wade to Blue Ridge Ramp	U-2719 Limits	SR 1664	0.16	Mill 2.0" and 2.0" S9.5C	$54,000
2028	5	092-Wake	Resurfacing	Wakefields Oak Grove Dr	SR 1001	Cul-de-sac	0.27	Full Depth Patching and 1.25" S9.5B	$52,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	5	092-Wake	Resurfacing	Walnut Glen Dr	Cul-de-sac	Cul-de-sac	0.46	Full Depth Patching and 1.25" S9.5B	$81,000
2028	5	092-Wake	Resurfacing	Westminster Ln	SR 1393	SR 1301	0.82	1.0" S9.5B	$102,000
2028	5	092-Wake	Resurfacing	Wetterhorn Way	NC 97	SR 2490	0.27	Full Depth Patching and 1.5" S9.5B	$53,000
2028	5	092-Wake	Resurfacing	Willowdell Dr	SR 5138	Cul-de-sac	0.13	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$35,000
2028	5	092-Wake	Resurfacing	Willowlawn Dr	SR 2053	SR 5139	0.42	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$140,000
2028	5	092-Wake	Resurfacing	Woodie Dr	SR 2320	SR 5435	0.80	Full Depth Patching and 1.5" S9.5B	$173,000
2028	5	092-Wake	Resurfacing	Woodslope Dr	SR 5207	Cul-de-sac	0.17	Full Depth Patching and 1.25" S9.5B	$33,000
2028	5	092-Wake	Resurfacing	Wortham Dr	Cul-de-sac	Cul-de-sac	0.21	Full Depth Patching and 1.25" S9.5B	$40,000
2028	5	092-Wake	Resurfacing	Yateswood Ct	SR 4748	Cul-de-sac	0.12	Full Depth Patching and 1.25" S9.5B	$23,000
2028	5	092-Wake	Preservation	Annsbury Ct	SR 4341	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2028	5	092-Wake	Preservation	Autumn Creek Dr	SR 4761	END MAINT	0.12	1.0" S9.5B	$14,000
2028	5	092-Wake	Preservation	Autumn Trace Dr	SR 1393	SR 4761	0.13	1.0" S9.5B	$16,000
2028	5	092-Wake	Preservation	Baronie Ct	SR 1243	Cul-de-sac	0.03	1.0" S9.5B	$4,000
2028	5	092-Wake	Preservation	Baucatcher Ln	SR 5447	Cul-de-sac	0.07	1.0" S9.5B	$7,000
2028	5	092-Wake	Preservation	Beaver Oaks Ct	SR 1384	Cul-de-sac	0.15	1.0" S9.5B	$19,000
2028	5	092-Wake	Preservation	Belleau Woods Dr	SR 5268	END MAINT	0.04	1.0" S9.5B	$5,000
2028	5	092-Wake	Preservation	Bishopgate Dr	SR 4264	Cul-de-sac	0.14	1.0" S9.5B	$17,000
2028	5	092-Wake	Preservation	Boulders View Way	SR 5207	Dead End	0.09	1.0" S9.5B	$11,000
2028	5	092-Wake	Preservation	Carriage Manor Ct	SR 5406	Cul-de-sac	0.09	1.0" S9.5B	$10,000
2028	5	092-Wake	Preservation	Carriage Manor Ct	SR 5406	Cul-de-sac	0.08	1.0" S9.5B	$10,000
2028	5	092-Wake	Preservation	Catkins Ct	SR 4341	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2028	5	092-Wake	Preservation	Cedar Tree St	SR 2988	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2028	5	092-Wake	Preservation	Cherrybark Ln	Cul-de-sac	Cul-de-sac	0.21	1.0" S9.5B	$23,000
2028	5	092-Wake	Preservation	Concerto Ct	SR 5805	Cul-de-sac	0.08	1.0" S9.5B	$10,000
2028	5	092-Wake	Preservation	Crickett Rd	SR 2511	Dead End	0.29	1.0" S9.5B	$33,000
2028	5	092-Wake	Preservation	Currigan Ct	SR 4071	Cul-de-sac	0.06	1.0" S9.5B	$7,000
2028	5	092-Wake	Preservation	Cut Glass Ct	SR 5434	Cul-de-sac	0.10	1.0" S9.5B	$12,000
2028	5	092-Wake	Preservation	Deer Fern Dr	SR 3999	Cul-de-sac	0.07	1.0" S9.5B	$9,000
2028	5	092-Wake	Preservation	Dollar Cir	SR 2441	Cul-de-sac	0.09	1.0" S9.5B	$12,000
2028	5	092-Wake	Preservation	Eagon Ct	SR 4078	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2028	5	092-Wake	Preservation	Farragon Hill Ln	SR 2470	Cul-de-sac	0.31	1.0" S9.5B	$34,000
2028	5	092-Wake	Preservation	Farthingale Ct	SR 5365	Cul-de-sac	0.15	1.0" S9.5B	$17,000
2028	5	092-Wake	Preservation	Glen Dean Ct	Sr 4840	Dead End	0.12	1.0" S9.5B	$14,000
2028	5	092-Wake	Preservation	Kelly Ct	SR 1530	Cul-de-sac	0.09	1.0" S9.5B	$11,000
2028	5	092-Wake	Preservation	Khaki Run	SR 4071	END MAINT	0.08	1.0" S9.5B	$10,000
2028	5	092-Wake	Preservation	La Manga Dr	SR 5207	SR 5209	0.34	1.0" S9.5B	$42,000
2028	5	092-Wake	Preservation	La Varra Dr	SR 1004	Cul-de-sac	0.19	1.0" S9.5B	$23,000
2028	5	092-Wake	Preservation	Lafayette Dr	SR 1393	Cul-de-sac	0.26	1.0" S9.5B	$32,000
2028	5	092-Wake	Preservation	Lake Jenn Dr	Cul-de-sac	Dead End	0.27	1.0" S9.5B	$33,000
2028	5	092-Wake	Preservation	Lake Pl	SR 2391	Cul-de-sac	0.19	1.0" S9.5B	$23,000
2028	5	092-Wake	Preservation	Lake St	SR 2886	Dead End	0.20	1.0" S9.5B	$25,000
2028	5	092-Wake	Preservation	Lilly Stream Ct	SR 5540	Cul-de-sac	0.09	1.0" S9.5B	$10,000
2028	5	092-Wake	Preservation	London Bridge Ct	SR 4264	Cul-de-sac	0.07	1.0" S9.5B	$9,000
2028	5	092-Wake	Preservation	Longacre Dr	NC 50	SR 4264	0.07	1.0" S9.5B	$13,000
2028	5	092-Wake	Preservation	Lost Acorn Way	Cul-de-sac	Cul-de-sac	0.12	1.0" S9.5B	$13,000
2028	5	092-Wake	Preservation	Marwick Ct	SR 5451	Cul-de-sac	0.20	1.0" S9.5B	$22,000
2028	5	092-Wake	Preservation	Mcelveen Ct	SR 4840	Cul-de-sac	0.02	1.0" S9.5B	$2,000
2028	5	092-Wake	Preservation	Morphus Bridge Rd	W Barbee St	Earpsboro Chamblee Rd	2.48	1.0" S9.5B	$308,000
2028	5	092-Wake	Preservation	New Dixie Ct	SR 2442	Cul-de-sac	0.08	1.0" S9.5B	$10,000
2028	5	092-Wake	Preservation	New Rebel Ct	SR 2442	Cul-de-sac	0.11	1.0" S9.5B	$13,000
2028	5	092-Wake	Preservation	New Ridge St	Cul-de-sac	Cul-de-sac	0.31	1.0" S9.5B	$38,000
2028	5	092-Wake	Preservation	Northgreen Dr	SR 4071	Cul-de-sac	0.16	1.0" S9.5B	$20,000
2028	5	092-Wake	Preservation	Norwood Oaks Dr	SR 1834	Cul-de-sac	0.20	1.0" S9.5B	$24,000
2028	5	092-Wake	Preservation	Orchestra Ct	SR 5098	SR 5412	0.10	1.0" S9.5B	$12,000
2028	5	092-Wake	Preservation	Orchestra Ct	Cul-de-sac	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2028	5	092-Wake	Preservation	Outcrop Ct	SR 5200	Cul-de-sac	0.08	1.0" S9.5B	$10,000
2028	5	092-Wake	Preservation	Pampass Trl	SR 2483	Dead End	0.04	1.0" S9.5B	$5,000
2028	5	092-Wake	Preservation	Pauley Ct	SR 5209	Cul-de-sac	0.03	1.0" S9.5B	$4,000
2028	5	092-Wake	Preservation	Pointers Glen Way	SR 2470	Cul-de-sac	0.17	1.0" S9.5B	$22,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	5	092-Wake	Preservation	Red Wing Ct	SR 4073	Cul-de-sac	0.11	1.0" S9.5B	$14,000
2028	5	092-Wake	Preservation	Rhythm Dr	SR 1302	Dead End	0.25	1.0" S9.5B	$32,000
2028	5	092-Wake	Preservation	Ridgebluffs Ct	SR 4042	Cul-de-sac	0.06	1.0" S9.5B	$7,000
2028	5	092-Wake	Preservation	River Dare Ave	Cul-de-sac	Dead End	0.26	1.0" S9.5B	$32,000
2028	5	092-Wake	Preservation	Rivercrest Dr	SR 2445	SR 2448	0.20	1.0" S9.5B	$25,000
2028	5	092-Wake	Preservation	Rossmore Dr	SR 4071	Cul-de-sac	0.22	1.0" S9.5B	$27,000
2028	5	092-Wake	Preservation	Ruddington Ct	SR 4887	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2028	5	092-Wake	Preservation	Silver Spring Ct	SR 4887	Cul-de-sac	0.13	1.0" S9.5B	$15,000
2028	5	092-Wake	Preservation	Starboard Ct	SR 4315	Cul-de-sac	0.06	1.0" S9.5B	$6,000
2028	5	092-Wake	Preservation	Stauffer Ct	SR 5200	Cul-de-sac	0.09	1.0" S9.5B	$11,000
2028	5	092-Wake	Preservation	Sumac Cir	SR 2483	Cul-de-sac	0.03	1.0" S9.5B	$3,000
2028	5	092-Wake	Preservation	Sunriver Pt	SR 5209	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2028	5	092-Wake	Preservation	Tibwin Dr	SR 4769	END MAINT	0.13	1.0" S9.5B	$15,000
2028	5	092-Wake	Preservation	Tinderbox Ln	SR 4840	Cul-de-sac	0.19	1.0" S9.5B	$24,000
2028	5	092-Wake	Preservation	Tomotley Ct	SR 4767	Cul-de-sac	0.14	1.0" S9.5B	$16,000
2028	5	092-Wake	Preservation	Trellis Ct	SR 2215	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2028	5	092-Wake	Preservation	Valley Pine Ct	SR 5406	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2028	5	092-Wake	Preservation	Waterloo Ct	SR 4264	Cul-de-sac	0.06	1.0" S9.5B	$7,000
2028	5	092-Wake	Preservation	Weathering Ct	SR 2451	Cul-de-sac	0.13	1.0" S9.5B	$16,000
2028	5	092-Wake	Preservation	Wheatridge Dr	SR 4071	Cul-de-sac	0.11	1.0" S9.5B	$14,000
2028	5	092-Wake	Preservation	Wild Honeysuckle St	SR 2483	Cul-de-sac	0.03	1.0" S9.5B	$4,000
2028	5	092-Wake	Preservation	Willow Crest Ln	SR 4887	SR 5539	0.13	1.0" S9.5B	$14,000
2028	5	092-Wake	Preservation	Winsters Fax Ct	SR 2436	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2028	5	092-Wake	Preservation	Wynne Trace Ct	SR 5365	Cul-de-sac	0.09	1.0" S9.5B	$9,000
2028	5	093-Warren	Resurfacing	Dove Manor Rd	NC 903	SR 1433	0.82	1.0" S9.5B	$92,000
2028	5	093-Warren	Resurfacing	Eaton Ferry Road	NC 903	SR 1318	5.72	Full Depth Patching and 1.25" S9.5B	$1,112,000
2028	5	093-Warren	Resurfacing	South Dove	Cul-de-sac	Cul-de-sac	0.56	1.0" S9.5B	$65,000
2028	5	093-Warren	Resurfacing	Warren Plains	SR 1300	US 158	6.30	1.0" S9.5B	$820,000
2028	5	093-Warren	Preservation	Fate Weaver	SR 1112	SR1001	1.37	Full Depth Patching and 1.25" S9.5B	$267,000
2028	5	093-Warren	Preservation	Old Bethlehem	NC 43	SR 1638	2.71	1.0" S9.5B	$353,000
2028	5	093-Warren	Preservation	Peter Stallings	SR 1314	SR 1309	1.69	1.0" S9.5B	$210,000
2028	6	009-Bladen	Resurfacing	NC 211 Bus	NC 131/242/410	NC 211 Bypass	4.40	Mill 1.5" and 1.5" S9.5C	$1,760,000
2028	6	009-Bladen	Resurfacing	SR 1131	NC 211 Bypass	NC 211 Bus.	0.71	1.5" S9.5A	$142,000
2028	6	009-Bladen	Resurfacing	SR 1150	NC 87 Bus	NC 87	1.96	1.5" S9.5B	$392,000
2028	6	009-Bladen	Resurfacing	SR 1237	NC 87	NC 242	0.24	1.5" S9.5B	$48,000
2028	6	009-Bladen	Resurfacing	SR 1325	NC 242	NC 53	7.44	1.5" S9.5B	$1,488,000
2028	6	009-Bladen	Resurfacing	US 701 Bus	End C&G (Clarkton)	US 701 Bypass	0.44	Mill 1.5" and 1.5" S9.5C	$176,000
2028	6	009-Bladen	Resurfacing	US 701 Bus	Columbus County	Beg C&G (Clarkton)	1.31	Mill 1.5" and 1.5" S9.5C	$524,000
2028	6	009-Bladen	Resurfacing	US 701 Bus	Beg C&G (Clarkton)	End C&G (Clarkton)	0.93	Mill 1.5" and 1.5" S9.5C	$372,000
2028	6	024-Columbus	Resurfacing	NC 242	US 76	SR 1574	6.37	1.5" S9.5B	$2,548,000
2028	6	024-Columbus	Resurfacing	NC 904	SR 1346	WCL Tabor City	5.19	1.5" S9.5C	$2,076,000
2028	6	024-Columbus	Resurfacing	SR 1001	NC 130	BRG 007	4.16	1.5" S9.5B	$832,000
2028	6	024-Columbus	Resurfacing	SR 1004	NC 410	SR 1005	3.08	1.5" S9.5B	$616,000
2028	6	024-Columbus	Resurfacing	SR 1514	SR 1574	NC 242	0.34	1.5" S9.5B	$68,000
2028	6	024-Columbus	Resurfacing	SR 1700	Begin 48' Pavement	US 74	0.18	Mill 1.5" and 1.5" S9.5B	$35,200
2028	6	024-Columbus	Resurfacing	SR 1916	US 74 Bus	US 701 Bus	1.50	Mill 1.5" and 1.5" S9.5B	$300,000
2028	6	024-Columbus	Resurfacing	SR 1953	US 701 Bus	US 74 Bus	1.62	Mill 1.5" and 1.5" S9.5B	$324,000
2028	6	024-Columbus	Resurfacing	SR 1972	SR 1001	NC 130	1.72	1.5" S9.5B and Widen	$344,000
2028	6	024-Columbus	Resurfacing	US 701 Bus	SR 1916	Railroad	0.36	Mill 1.5" and 1.5" S9.5C	$144,000
2028	6	024-Columbus	Resurfacing	US 74 Bus	End C&G	SR 1700	1.18	1.5" S9.5C and Widen	$500,400
2028	6	024-Columbus	Preservation	SR 1005	SR 1002	US 701	3.02	Seal - Triple	$100,000
2028	6	024-Columbus	Preservation	SR 1433	US 701	SR 1432	0.46	Seal - Double	$12,000
2028	6	024-Columbus	Preservation	SR 1457	US 74 BUS	DEAD END	0.32	Seal - Double	$11,000
2028	6	024-Columbus	Preservation	SR 1461	US 74 BUS	END MAINT	0.16	Seal - Double	$5,000
2028	6	024-Columbus	Preservation	SR 1533	SR 1002	SR 1003	1.16	Seal - Double	$40,200
2028	6	024-Columbus	Preservation	SR 1534	SR 1003	SR 1005	3.67	Seal - Double	$132,000
2028	6	024-Columbus	Preservation	SR 1535	NC 410	SR 1534	0.92	Seal - Double	$34,000
2028	6	024-Columbus	Preservation	SR 1536	NC 410	SR 1534	1.09	Seal - Double	$40,000
2028	6	024-Columbus	Preservation	SR 1537	SR 1002	SR 1534	2.06	Seal - Double	$75,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	6	024-Columbus	Preservation	SR 1538	SR 1002	SR 1002	0.57	Seal - Double	$18,800
2028	6	024-Columbus	Preservation	SR 1546	US 701	SR 1003	3.62	Seal - Double	$132,000
2028	6	024-Columbus	Preservation	SR 1547	SR 1552	SR 1005	3.11	Seal - Double	$115,500
2028	6	024-Columbus	Preservation	SR 1549	SR 1547	SR 1585	1.04	Seal - Double	$37,000
2028	6	024-Columbus	Preservation	SR 1550	US 701	SR 1549	1.67	Seal - Double	$55,000
2028	6	024-Columbus	Preservation	SR 1551	US 701	SR 1552	1.54	Seal - Double	$56,500
2028	6	024-Columbus	Preservation	SR 1553	SR 1552	Dead End	0.51	Seal - Double	$16,300
2028	6	024-Columbus	Preservation	SR 1554	NC 130	US 74 Bus	1.73	Seal - Double	$63,000
2028	6	024-Columbus	Preservation	SR 1555	SR 1585	SR 1552	1.72	Seal - Double	$64,000
2028	6	024-Columbus	Preservation	SR 1556	SR 1552	Dead End	0.74	Seal - Double	$27,500
2028	6	024-Columbus	Preservation	SR 1557	SR 1585	SR 1558	1.50	Seal - Double	$50,200
2028	6	024-Columbus	Preservation	SR 1558	SR 1005	Dead End	1.90	Seal - Double	$71,000
2028	6	024-Columbus	Preservation	SR 1561	Dead End	SR 1572	0.86	Seal - Double	$31,400
2028	6	024-Columbus	Preservation	SR 1568	US 701	Dead End	0.46	Seal - Cape	$15,000
2028	6	024-Columbus	Preservation	SR 1569	SR 1551	SR 1568	0.19	Seal - Cape	$6,000
2028	6	024-Columbus	Preservation	SR 1570	SR 1551	SR 1568	0.19	Seal - Cape	$6,000
2028	6	024-Columbus	Preservation	SR 1571	SR 1551	SR 1568	0.20	Seal - Cape	$6,000
2028	6	024-Columbus	Preservation	SR 1576	Dead End	SR 1572	0.33	Seal - Double	$12,300
2028	6	024-Columbus	Preservation	SR 1584	US 74 BUS	DEAD END	0.25	Seal - Double	$6,500
2028	6	024-Columbus	Preservation	SR 1584	NC 130	Dead End	0.25	Seal - Double	$7,500
2028	6	024-Columbus	Preservation	SR 1585	SR 1552	SR 1002	2.43	Seal - Double	$88,000
2028	6	024-Columbus	Preservation	SR 1586	SR 1585	SR 1558	0.72	Seal - Double	$25,000
2028	6	024-Columbus	Preservation	SR 1587	SR 1550	Dead End	0.20	Seal - Double	$6,000
2028	6	024-Columbus	Preservation	SR 1591	SR 1552	CDS	0.43	Seal - Cape	$12,000
2028	6	024-Columbus	Preservation	SR 1592	SR 1591	CDS	0.44	Seal - Cape	$14,000
2028	6	024-Columbus	Preservation	SR 1593	NC 130	Dead End	0.27	Seal - Cape	$8,000
2028	6	024-Columbus	Preservation	SR 1594	SR 1552	CDS	0.10	Seal - Cape	$3,000
2028	6	024-Columbus	Preservation	SR 1595	SR 1002	SR 1596	0.29	Seal - Cape	$8,000
2028	6	024-Columbus	Preservation	SR 1596	SR 1002	CDS	0.27	Seal - Cape	$8,000
2028	6	024-Columbus	Preservation	SR 1597	SR 1592	SR 1601	0.18	Seal - Cape	$6,000
2028	6	024-Columbus	Preservation	SR 1598	SR 1003	SR 1537	1.08	Seal - Double	$40,000
2028	6	024-Columbus	Preservation	SR 1600	US 701 Bus	Dead End	0.40	Seal - Double	$17,500
2028	6	024-Columbus	Preservation	SR 1601	SR 1592	SR 1591	0.16	Seal - Cape	$6,000
2028	6	024-Columbus	Preservation	SR 1602	US 701	CDS	0.35	Seal - Cape	$10,000
2028	6	024-Columbus	Preservation	SR 1603	SR 1594	CDS	0.06	Seal - Cape	$1,900
2028	6	024-Columbus	Preservation	SR 1605	SR 1572	SR 1561	1.56	Seal - Double	$56,500
2028	6	024-Columbus	Preservation	SR 1709	US 701	Dead End	0.70	Seal - Double	$25,000
2028	6	024-Columbus	Preservation	SR 1749	US 701	Dead End	0.83	Seal - Cape	$25,000
2028	6	024-Columbus	Preservation	SR 1760	SR 1749	Dead End	0.48	Seal - Cape	$15,000
2028	6	024-Columbus	Preservation	SR 1761	SR 1780	End Pavement	0.41	Seal - Cape	$12,000
2028	6	024-Columbus	Preservation	SR 1764	US 701 Bus	US 701 Bypass	0.38	Seal - Double	$15,000
2028	6	024-Columbus	Preservation	SR 1765	US 701	End Pavement	0.22	Seal - Cape	$7,000
2028	6	024-Columbus	Preservation	SR 1766	SR 1765	Dead End	0.17	Seal - Cape	$5,000
2028	6	024-Columbus	Preservation	SR 1767	SR 1761	CDS	0.16	Seal - Cape	$5,000
2028	6	026-Cumberland	Resurfacing	SR 1408	SR 1415	SR 1404	0.93	Mill 1.5" and 1.5" S9.5B	$511,500
2028	6	026-Cumberland	Resurfacing	SR 1409	SR 1400	US 401	1.62	1.5" S9.5B	$267,300
2028	6	026-Cumberland	Resurfacing	SR 1410	SR 1400	SR 1409	0.79	1.5" S9.5B	$130,185
2028	6	026-Cumberland	Resurfacing	SR 1411	SR 1410	US 401	1.09	1.5" S9.5B	$239,800
2028	6	026-Cumberland	Resurfacing	SR 1712	US 401	SR 2800	0.59	2.0" S9.5C	$97,350
2028	6	026-Cumberland	Resurfacing	SR 1714	SR 1728	NC 295	6.07	1.5" S9.5B and Widen	$1,669,250
2028	6	026-Cumberland	Resurfacing	SR 2022	NC 210	SR 1971	4.12	1.5" S9.5B and Widen	$1,133,000
2028	6	026-Cumberland	Resurfacing	SR 2221	NC 87	SR 2233	0.23	1.5" S9.5B and Widen	$63,250
2028	6	026-Cumberland	Resurfacing	SR 2233	SR 2221	SR 2232	5.38	1.5" S9.5B and Widen	$1,479,500
2028	6	026-Cumberland	Resurfacing	SR 2242	SR 3968	SR 2243	1.84	1.5" S9.5A and Widen	$504,900
2028	6	026-Cumberland	Resurfacing	SR 2284	SR 2242	Pavement Change	0.63	1.5" S9.5A and Widen	$172,975
2028	6	026-Cumberland	Resurfacing	US 13	PEMBROKE LN	SAMPSON CO	6.91	Mill 1.5" and 1.5" S9.5B	$1,520,200
2028	6	026-Cumberland	Preservation	SR 1716	SR 1714	SR 1719	2.52	Seal - Split	$90,500
2028	6	026-Cumberland	Preservation	SR 1719	US 301	SR 1716	5.93	Seal - Split	$220,000
2028	6	026-Cumberland	Preservation	SR 1721	SR 1719	SR 1720	1.81	Seal - Split	$62,800

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	6	026-Cumberland	Preservation	SR 1722	SR 1714	SR 1725	3.94	Seal - Split	$144,500
2028	6	026-Cumberland	Preservation	SR 1723	SR 1722	SR 1730	2.54	Seal - Split	$94,000
2028	6	026-Cumberland	Preservation	SR 1725	SR 1838	SR 1722	0.40	Seal - Split	$12,500
2028	6	026-Cumberland	Preservation	SR 1730	SR 1725	SR 1728	2.02	Seal - Split	$75,000
2028	6	026-Cumberland	Preservation	SR 1731	SR 1728	US 301	0.19	Seal - Split	$6,300
2028	6	026-Cumberland	Preservation	SR 1734	US 301	Dead End	0.19	Seal - Split	$6,300
2028	6	026-Cumberland	Preservation	SR 1736	SR 1733	Ramp	0.20	Seal - Split	$6,300
2028	6	026-Cumberland	Preservation	SR 1737	SR 1738	SR 1714	0.71	Seal - Split	$25,000
2028	6	026-Cumberland	Preservation	SR 1797	SR 1725	End Maintenance	0.20	Seal - Split	$6,300
2028	6	026-Cumberland	Preservation	SR 2833	SR 1730	Dead End	0.27	Seal - Split	$9,000
2028	6	043-Harnett	Resurfacing	SR 1415	SR 1412	US 401	2.54	1.5" S9.5B	$419,100
2028	6	043-Harnett	Resurfacing	SR 1441	NC 55	US 401	4.23	1.5" S9.5B	$697,785
2028	6	043-Harnett	Resurfacing	SR 1718	S POWELL AVE	NC 82/217	2.84	1.5" S9.5B	$744,000
2028	6	043-Harnett	Resurfacing	SR 1844	SR 1735	SR 1860	0.82	1.5" S9.5B	$135,300
2028	6	043-Harnett	Resurfacing	US 421	NC 55/217	ELEANOR AVE	3.31	Mill 1.5" and 1.5" S9.5B	$728,200
2028	6	043-Harnett	Resurfacing	US 421	SR 1291	LEE CO	13.21	Mill 1.5" and 1.5" S9.5B	$2,908,400
2028	6	043-Harnett	Resurfacing	US 421	ELEANOR AVE	NC 55/217	3.31	Mill 1.5" and 1.5" S9.5B	$728,200
2028	6	043-Harnett	Resurfacing	US 421	WASHINGTON AVE	ELEANOR AVE	1.26	Mill 1.5" and 1.5" S9.5B	$554,400
2028	6	043-Harnett	Resurfacing	US 421	SAMPSON CO	NC 55	1.59	Mill 1.5" and 1.5" S9.5B	$393,800
2028	6	043-Harnett	Preservation	SR 1741	SR 1746	SR 1735	1.13	Seal - Double	$37,500
2028	6	043-Harnett	Preservation	SR 1774	NC 82	END PAVEMENT	0.72	Seal - Double	$25,000
2028	6	043-Harnett	Preservation	SR 1775	NC 82	END MAINTENANCE	1.00	Seal - Double	$32,500
2028	6	043-Harnett	Preservation	SR 1776	SR 1735	NC 82	1.86	Seal - Double	$69,000
2028	6	043-Harnett	Preservation	SR 1778	NC 82	SR 1780	1.25	Seal - Double	$44,000
2028	6	043-Harnett	Preservation	SR 1780	SR 1781	NC 82	1.24	Seal - Double	$44,000
2028	6	043-Harnett	Preservation	SR 1781	CUMBERLAND CO	SR 1780	1.87	Seal - Double	$56,500
2028	6	043-Harnett	Preservation	SR 1783	SR 1781	NC 82	1.16	Seal - Double	$37,500
2028	6	043-Harnett	Preservation	SR 1786	SR 1811	CUMBERLAND CO	0.65	Seal - Double	$23,800
2028	6	043-Harnett	Preservation	SR 1787	SR 1811	CUMBERLAND CO	1.22	Seal - Double	$44,000
2028	6	043-Harnett	Preservation	SR 1788	US 301	US 301	1.02	Seal - Double	$37,500
2028	6	043-Harnett	Preservation	SR 1791	SR 1785	SR 1002	1.15	Seal - Double	$40,000
2028	6	043-Harnett	Preservation	SR 1794	SR 1793	US 421	0.36	Seal - Double	$12,500
2028	6	043-Harnett	Preservation	SR 1814	DEAD END	END OF MAINTENANCE	0.20	Seal - Double	$7,500
2028	6	043-Harnett	Preservation	SR 1837	SR 1793	PAVEMENT CHANGE	0.49	Seal - Double	$17,500
2028	6	043-Harnett	Preservation	SR 1844	SR 1735	SR 1790	1.50	Seal - Double	$65,300
2028	6	043-Harnett	Preservation	SR 1908	NC 82	END OF MAINTENANCE	0.48	Seal - Double	$17,500
2028	6	043-Harnett	Preservation	SR 1915	US 301	SR 1926	0.20	Seal - Double	$7,500
2028	6	043-Harnett	Preservation	SR 1926	SR 1002	SR 1915	0.26	Seal - Double	$11,300
2028	6	078-Robeson	Resurfacing	NC 130	SR 2489	SR 2460	4.76	1.5" S9.5B	$952,000
2028	6	078-Robeson	Resurfacing	NC 20	Hoke Co	SR 1732	9.03	1.5" S9.5C	$1,806,000
2028	6	078-Robeson	Resurfacing	NC 904	NC 130	NC 41	6.93	1.5" S9.5B	$1,386,000
2028	6	078-Robeson	Resurfacing	SR 1105	SR 1104	SR 1106	2.36	1.5" S9.5B	$432,000
2028	6	078-Robeson	Resurfacing	SR 1136	SR 1138	SR1101	4.10	1.5" S9.5B	$738,000
2028	6	078-Robeson	Resurfacing	SR 1150	SR 1146	Dead End	3.20	1.5" S9.5B	$576,000
2028	6	078-Robeson	Resurfacing	SR 1599	NC 72	SR 1600	0.10	1.5" S9.5B	$20,000
2028	6	078-Robeson	Resurfacing	SR 1600	NC 72	Water St.	0.48	1.5" S9.5B	$90,000
2028	6	078-Robeson	Resurfacing	SR 1712	Hoke County Line	SR 1710	1.80	1.5" S9.5B	$325,000
2028	6	078-Robeson	Resurfacing	SR 1723	Cumberland County Line	US 301	3.15	1.5" S9.5B	$567,000
2028	6	078-Robeson	Resurfacing	SR 1902	US 301	Dead End	0.80	1.5" S9.5B	$160,000
2028	6	078-Robeson	Resurfacing	SR 1919	NC 20	SR 1907	1.14	1.5" S9.5B	$200,000
2028	6	078-Robeson	Resurfacing	SR 1927	SR 1005	SR 1928	1.08	1.5" S9.5B	$180,000
2028	6	078-Robeson	Resurfacing	SR 1932	SR 1924	SR 1005	1.32	1.5" S9.5B	$234,000
2028	6	078-Robeson	Resurfacing	SR 1935	US 301	SR 1963	8.96	1.5" S9.5B	$1,620,000
2028	6	078-Robeson	Resurfacing	SR 1974	SR 1935	SR 1975	0.67	1.5" S9.5B	$120,000
2028	6	078-Robeson	Resurfacing	SR 2042	NC 20	Dead End	0.25	1.5" S9.5B	$50,000
2028	6	078-Robeson	Resurfacing	SR 2047	SR 1907	End State Maintenance	0.19	1.5" S9.5B	$36,000
2028	6	078-Robeson	Resurfacing	SR 2113	SR 2110	SR 2104	0.91	1.5" S9.5B	$162,000
2028	6	078-Robeson	Resurfacing	SR 2204	SR 2207	SR 2212	2.54	1.5" S9.5B	$457,000
2028	6	078-Robeson	Resurfacing	SR 2225	US 74	NC 130	1.78	1.5" S9.5B	$324,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	6	078-Robeson	Resurfacing	SR 2239	SR 2235	NC 41	2.00	1.5" S9.5B	$360,000
2028	6	078-Robeson	Resurfacing	SR 2457	US 301	SR 2422	1.70	1.5" S9.5B	$340,000
2028	6	078-Robeson	Resurfacing	SR 2478	SR 2477	SR 2472	0.63	1.5" S9.5B	$115,000
2028	6	078-Robeson	Resurfacing	SR 2519	SR 2455	Dead End	0.19	1.5" S9.5A	$35,000
2028	6	078-Robeson	Preservation	SR 1708	SR 1709	Hoke County	1.77	Seal - Split	$65,000
2028	6	078-Robeson	Preservation	SR 1710	Cumberland Co.	SR 1709	4.50	Seal - Split	$163,000
2028	6	078-Robeson	Preservation	SR 1711	Hoke County	SR 1712	1.65	Seal - Split	$50,260
2028	6	078-Robeson	Preservation	SR 1712	Hoke County	SR 1713	2.75	Seal - Split	$120,000
2028	6	078-Robeson	Preservation	SR 1714	SR 1712	SR 1731	2.27	Seal - Split	$81,600
2028	6	078-Robeson	Preservation	SR 1715	PARKTON TL	SR 1710	1.54	Seal - Split	$50,200
2028	6	078-Robeson	Preservation	SR 1718	Cumberland County	US 301	1.02	Seal - Split	$45,000
2028	6	078-Robeson	Preservation	SR 1718	SR 1978 + 0.47 miles	SR 1900	1.07	Seal - Split	$39,000
2028	6	078-Robeson	Preservation	SR 1720	US 301	PARKTON TL	1.82	Seal - Split	$62,800
2028	6	078-Robeson	Preservation	SR 1723	Cumberland County	I 95 South	2.39	Seal - Split	$88,000
2028	6	078-Robeson	Preservation	SR 1724	SR 1723	SR 1723	1.61	Seal - Split	$56,500
2028	6	078-Robeson	Preservation	SR 1726	US 301	I 95	0.73	Seal - Split	$25,000
2028	6	078-Robeson	Preservation	SR 1727	SR 1725	US 301	1.53	Seal - Split	$69,000
2028	6	078-Robeson	Preservation	SR 1728	SR 1729	SR 1725	0.71	Seal - Split	$25,000
2028	6	078-Robeson	Preservation	SR 1729	SR 1727	NC 20	1.28	Seal - Split	$56,500
2028	6	078-Robeson	Preservation	SR 1731	SR 1727	RXR Tracks	3.18	Seal - Split	$125,500
2028	6	078-Robeson	Preservation	SR 1758	US 301	I 95	0.84	Seal - Split	$28,000
2028	6	078-Robeson	Preservation	SR 1759	SR 1006	SR 1758	1.49	Seal - Split	$56,500
2028	6	078-Robeson	Preservation	SR 1764	US 301	End Maintenance	0.47	Seal - Split	$16,300
2028	6	078-Robeson	Preservation	SR 1788	US 301	SR 1759	0.36	Seal - Split	$12,500
2028	6	078-Robeson	Preservation	SR 1789	US 301	Dead End	0.41	Seal - Split	$12,500
2028	6	078-Robeson	Preservation	SR 1793	NC 71	DEAD END	0.30	Seal - Split	$11,000
2028	6	078-Robeson	Preservation	SR 1900	Cumberland County	SR 1723	1.54	Seal - Split	$56,500
2028	6	078-Robeson	Preservation	SR 1901	SR 1978	SR 1978 + 0.21 miles	0.21	Seal - Split	$9,000
2028	6	078-Robeson	Preservation	SR 1902	US 301 PVMT JT	DEAD END	0.64	Seal - Split	$25,000
2028	6	078-Robeson	Preservation	SR 1905	SR 1904	SR 1906	1.92	Seal - Split	$69,000
2028	6	078-Robeson	Preservation	SR 1906	SR 1723	SR 1907	3.10	Seal - Split	$113,000
2028	6	078-Robeson	Preservation	SR 1908	SR 1980	SR 1726	0.49	Seal - Split	$17,500
2028	6	078-Robeson	Preservation	SR 1916	CL	SR 1988 + 0.451	0.88	Seal - Split	$32,500
2028	6	078-Robeson	Preservation	SR 1920	SR 1919	NC 20	2.01	Seal - Split	$75,000
2028	6	078-Robeson	Preservation	SR 1921	SR 1907 + 0.783	Dead End	0.59	Seal - Split	$21,300
2028	6	078-Robeson	Preservation	SR 1922	SR 1907	SR 1921	0.50	Seal - Split	$17,500
2028	6	078-Robeson	Preservation	SR 1924	SR 1006	SR 1935	4.18	Seal - Split	$170,000
2028	6	078-Robeson	Preservation	SR 1925	SR 1006	SR 1006	1.79	Seal - Split	$65,000
2028	6	078-Robeson	Preservation	SR 1926	SR 1006	SR 1006 + 0.52	0.52	Seal - Split	$19,000
2028	6	078-Robeson	Preservation	SR 1927	SR 1005	SR 1928	1.08	Seal - Split	$40,000
2028	6	078-Robeson	Preservation	SR 1928	SR 1006	SR 1005	1.74	Seal - Split	$64,000
2028	6	078-Robeson	Preservation	SR 1929	SR 1928	SR 1924	1.53	Seal - Split	$56,000
2028	6	078-Robeson	Preservation	SR 1932	SR 1924	SR 1005	1.32	Seal - Split	$44,000
2028	6	078-Robeson	Preservation	SR 1934	SR 1924	SR 1936	1.22	Seal - Split	$46,500
2028	6	078-Robeson	Preservation	SR 1937	SR 1931	SR 1936	1.72	Seal - Split	$64,000
2028	6	078-Robeson	Preservation	SR 1938	SR 1931	SR 1936	2.56	Seal - Split	$95,500
2028	6	078-Robeson	Preservation	SR 1939	US 301	SR 1006	1.33	Seal - Split	$50,200
2028	6	078-Robeson	Preservation	SR 1941	US 301	SR 1936	0.72	Seal - Split	$26,300
2028	6	078-Robeson	Preservation	SR 1963	SR 1004	SR 1955	2.88	Seal - Split	$96,700
2028	6	078-Robeson	Preservation	SR 1969	SR 1004	SR 1955	3.49	Seal - Split	$113,000
2028	6	078-Robeson	Preservation	SR 1972	SR 1004	END PVMT	0.71	Seal - Split	$27,500
2028	6	078-Robeson	Preservation	SR 1974	SR 1935	SR 1971	1.90	Seal - Split	$70,300
2028	6	078-Robeson	Preservation	SR 1975	SR 1974	SR 1935	0.62	Seal - Split	$21,300
2028	6	078-Robeson	Preservation	SR 1976	SR 1005	SR 1005	1.38	Seal - Split	$44,000
2028	6	078-Robeson	Preservation	SR 1979	US 301	DEAD END	0.43	Seal - Split	$15,000
2028	6	078-Robeson	Preservation	SR 1980	SR 1907	SR 1726 + 1.213 miles	3.23	Seal - Split	$126,000
2028	6	078-Robeson	Preservation	SR 1982	SR 1006	SR 1006 + 0.54 miles	0.54	Seal - Split	$19,000
2028	6	078-Robeson	Preservation	SR 1985	SR 1006	SR 1927	0.67	Seal - Split	$24,000
2028	6	078-Robeson	Preservation	SR 2006	SR 1937	SR 1938	0.59	Seal - Split	$21,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	6	078-Robeson	Preservation	SR 2057	SR 1006	SR 1006 + 0.46 miles	0.46	Seal - Split	$16,000
2028	7	001-Alamance	Resurfacing	Adder Ridge Ln.	SR 2040	DEAD END	0.39	#78 Mat Seal and 1.5" S9.5B	$106,010
2028	7	001-Alamance	Resurfacing	Alamance Church St.	SR 1002	SR 1571	0.15	#78 Mat Seal and 1.5" S9.5B	$39,752
2028	7	001-Alamance	Resurfacing	Alamance Church St.	Cherokee Rd.	Race Track Rd.	0.19	#78 Mat Seal and 1.5" S9.5B	$50,350
2028	7	001-Alamance	Resurfacing	Alzora Ct.	SR 1136	DEAD END	0.30	#78 Mat Seal and 1.5" S9.5B	$79,550
2028	7	001-Alamance	Resurfacing	Canterwood Dr.	SR 1921	DEAD END	0.50	#78 Mat Seal and 1.5" S9.5B	$132,507
2028	7	001-Alamance	Resurfacing	Carriage Ct.	SR 2024	DEAD END	0.04	#78 Mat Seal and 1.5" S9.5B	$26,501
2028	7	001-Alamance	Resurfacing	Creekwood Dr.	SR 2467	DEAD END	0.07	#78 Mat Seal and 1.5" S9.5B	$18,550
2028	7	001-Alamance	Resurfacing	Crescent Square Dr.	SR 2304	NC 87	0.16	Mill 1.5" and 1.5" S9.5B	$47,007
2028	7	001-Alamance	Resurfacing	Durham Meadows Ct.	SR 1803	DEAD END	0.06	Mill 1.5" and 1.5" S9.5B	$26,500
2028	7	001-Alamance	Resurfacing	Durham Meadows Dr.	SR 1529	DEAD END	0.54	Mill 1.5" and 1.5" S9.5B	$142,760
2028	7	001-Alamance	Resurfacing	Ervin Newlin Dr.	SR 2153	SR 2661	0.10	#78 Mat Seal and 1.5" S9.5B	$26,501
2028	7	001-Alamance	Resurfacing	Falls Leaves Ct.	SR 2661	DEAD END	0.12	#78 Mat Seal and 1.5" S9.5B	$31,801
2028	7	001-Alamance	Resurfacing	Farm View Dr.	SR 1901	DEAD END	0.60	#78 Mat Seal and 1.5" S9.5B	$159,008
2028	7	001-Alamance	Resurfacing	Forest Lake Ct.	SR 1952	DEAD END	0.20	Mill 1.5" and 1.5" S9.5B	$39,172
2028	7	001-Alamance	Resurfacing	Forest Lake Dr.	SR 1951	SR 2046	0.60	#78 Mat Seal and 1.5" S9.5B	$160,000
2028	7	001-Alamance	Resurfacing	Foster Store Rd.	SR 1005	SR 1115	2.00	#78 Mat Seal and 1.5" S9.5B	$524,730
2028	7	001-Alamance	Resurfacing	Int. Service Rd. (E)	End C/G	SR 2100	0.47	#78 Mat Seal and 1.5" S9.5B	$124,557
2028	7	001-Alamance	Resurfacing	Int. Service Rd. (E)	NC 87	End C/G	0.23	Mill 1.5" and 1.5" S9.5B	$67,572
2028	7	001-Alamance	Resurfacing	Landi Lane	NC 119	DEAD END	0.40	#78 Mat Seal and 1.5" S9.5B	$70,971
2028	7	001-Alamance	Resurfacing	Lindley Mill Rd.	SR 1005	NC 87	3.50	#78 Mat Seal and 1.5" S9.5B	$620,993
2028	7	001-Alamance	Resurfacing	Mocking Bird Tr.	SR 2467	DEAD END	0.11	#78 Mat Seal and 1.5" S9.5B	$29,200
2028	7	001-Alamance	Resurfacing	Mrs. Fuller Rd.	SR 1918	DEAD END	0.21	#78 Mat Seal and 1.5" S9.5B	$70,971
2028	7	001-Alamance	Resurfacing	Mrs. White Lane	NC 119	DEAD END	0.80	#78 Mat Seal and 1.5" S9.5B	$114,941
2028	7	001-Alamance	Resurfacing	NC 49	US 70	END C&G	0.08	Mill 1.5" and 1.5" S9.5C	$36,277
2028	7	001-Alamance	Resurfacing	NC 49	END C&G	NC 49 (Split)	6.80	#78 Mat Seal and 1.5" S9.5C	$1,799,446
2028	7	001-Alamance	Resurfacing	NC 49	NC 49 Split	SR 2029 Old NC	0.08	#78 Mat Seal and 1.5" S9.5C	$34,800
2028	7	001-Alamance	Resurfacing	Nesters Ct.	SR 2467	DEAD END	0.12	#78 Mat Seal and 1.5" S9.5B	$31,801
2028	7	001-Alamance	Resurfacing	Oscela Rd.	GCL	SR 1558	1.53	#78 Mat Seal and 1.5" S9.5B	$405,471
2028	7	001-Alamance	Resurfacing	Peggy Way Rd.	SR 2660	DEAD END	0.10	#78 Mat Seal and 1.5" S9.5B	$26,501
2028	7	001-Alamance	Resurfacing	Pleasant Hill Liberty Rd.	SR 2371	NC 49	2.07	#67 Mat Seal and 1.5" S9.5B	$550,000
2028	7	001-Alamance	Resurfacing	Raven Wood Rd.	SR 2309	DEAD END	0.47	#78 Mat Seal and 1.5" S9.5B	$124,600
2028	7	001-Alamance	Resurfacing	Rock Castle Ct.	SR 2467	DEAD END	0.24	#78 Mat Seal and 1.5" S9.5B	$63,610
2028	7	001-Alamance	Resurfacing	Rolling Meadows Ct.	SR 1806	DEAD END	0.12	Mill 1.5" and 1.5" S9.5B	$31,750
2028	7	001-Alamance	Resurfacing	Rolling Meadows Lane	SR 1803	SR 1807	0.10	Mill 1.5" and 1.5" S9.5B	$26,700
2028	7	001-Alamance	Resurfacing	Spring Flowers Dr.	DEAD END	DEAD END	0.20	#78 Mat Seal and 1.5" S9.5B	$53,100
2028	7	001-Alamance	Resurfacing	SR 1129 Downs Rd	NC 51 Rock Hill-Pineville Rd	EOM pas Ammon Ln	1.26	Full Depth Patching and 1.5" S9.5C	$252,000
2028	7	001-Alamance	Resurfacing	West Lake Tr.	SR 1952	SR 1921	0.40	#78 Mat Seal and 1.5" S9.5B	$70,971
2028	7	001-Alamance	Preservation	Allen Baynes Rd.	US 70 (W. Center St.)	DEAD END	0.30	Seal - Double and Fog Seal	$14,412
2028	7	001-Alamance	Preservation	Barnett Rd.	SR 1912	SR 1912	3.20	Seal - Double and Fog Seal	$153,728
2028	7	001-Alamance	Preservation	Bo Fuller Rd.	NC 49 (N)	DEAD END	0.60	Seal - Double and Fog Seal	$28,824
2028	7	001-Alamance	Preservation	Byrd Rd.	SR 1904	CCL	2.50	Seal - Double and Fog Seal	$120,100
2028	7	001-Alamance	Preservation	Chapel Trail	SR 1927	DEAD END	0.40	Seal - Double and Fog Seal	$19,216
2028	7	001-Alamance	Preservation	Corbett Rd.	NC 119 (N)	CCL	2.40	Seal - Double and Fog Seal	$115,296
2028	7	001-Alamance	Preservation	Dailey Store Rd.	SR 1904	NC 119 (N)	1.50	Seal - Double and Fog Seal	$72,060
2028	7	001-Alamance	Preservation	Dewitt Dr.	SR 1927	SR 1756	0.30	Seal - Double and Fog Seal	$14,412
2028	7	001-Alamance	Preservation	Dickey Mill Rd.	NC 119 (N)	NC 49 (N)	4.10	Seal - Double and Fog Seal	$196,964
2028	7	001-Alamance	Preservation	Edgewood Church Rd.	SR 1948	US 70 (W. Center St.)	0.70	Seal - Double and Fog Seal	$33,628
2028	7	001-Alamance	Preservation	Hester Rd.	NC 49 (N)	DEAD END	0.40	Seal - Double and Fog Seal	$19,216
2028	7	001-Alamance	Preservation	High Rock Rd.	SR 1913	OCL	0.20	Seal - Double and Fog Seal	$9,608
2028	7	001-Alamance	Preservation	John Lewis Rd.	NC 49 (N)	SR 1910	1.10	Seal - Double and Fog Seal	$52,844
2028	7	001-Alamance	Preservation	Johnson Rd.	SR 1921	SR 1912	1.10	Seal - Double and Fog Seal	$52,844
2028	7	001-Alamance	Preservation	Miles Chapel Rd.	SR 1912	SR 1921	1.60	Seal - Double and Fog Seal	$76,864
2028	7	001-Alamance	Preservation	Mt. Zion Church Rd.	NC 49 (N)	OCL	0.20	Seal - Double and Fog Seal	$9,608
2028	7	001-Alamance	Preservation	Neighbors Rd.	SR 1902	DEAD END	0.60	Seal - Double and Fog Seal	$28,824
2028	7	001-Alamance	Preservation	Oscar Gammon Rd.	SR 1902	CCL	0.47	Seal - Double and Fog Seal	$24,020
2028	7	001-Alamance	Preservation	Preacher Hayes Rd.	CCL	SR 1901	2.35	Seal - Double and Fog Seal	$115,296
2028	7	001-Alamance	Preservation	Sellars Rd.	NC 119 (N)	DEAD END	0.39	Seal - Double and Fog Seal	$19,216
2028	7	001-Alamance	Preservation	SR 1602 Richard Road	SR 1601 Drye Road	SR 1603 Thomas Road	0.66	Seal - Double	$25,080

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	7	001-Alamance	Preservation	St. Luke's Church Rd.	(US 70) W. Center St.	DEAD END	0.09	Seal - Double and Fog Seal	$4,804
2028	7	001-Alamance	Preservation	Thomas Rd.	NC 119 (N)	DEAD END	0.40	Seal - Double and Fog Seal	$19,216
2028	7	001-Alamance	Preservation	Tom Anderson Rd.	SR 1901	DEAD END	0.20	Seal - Double and Fog Seal	$9,608
2028	7	001-Alamance	Preservation	Vaughn Rd.	NC 49 (N)	DEAD END	0.30	Seal - Double and Fog Seal	$14,412
2028	7	001-Alamance	Preservation	Water Plant Rd.	Us 70 (E. Main St.)	DEAD END	0.10	Seal - Double and Fog Seal	$4,804
2028	7	001-Alamance	Preservation	Woodlawn Dr.	SR 1952	SR 1996	0.17	Seal - Double and Fog Seal	$8,167
2028	7	017-Caswell	Resurfacing	NC 62 (S)	ACL	US 158	2.78	#67 Mat Seal and 1.5" S9.5B	$780,887
2028	7	017-Caswell	Resurfacing	NC 62 (S)	ACL	US 158	5.12	#67 Mat Seal and 1.5" S9.5B	$1,439,823
2028	7	017-Caswell	Resurfacing	NC 62 (S)	ACL	US 158	0.56	#67 Mat Seal and 1.5" S9.5B	$158,482
2028	7	017-Caswell	Resurfacing	Red Marshall Rd.	NC 700	RCL	3.18	#78 Mat Seal and 1.5" S9.5B	$850,000
2028	7	017-Caswell	Resurfacing	US 158 (E) / Yanceyville	SR 1163	NC 86	2.06	#67 Mat Seal and 1.5" S9.5B	$552,300
2028	7	017-Caswell	Preservation	Brown Rd.	US 158	END MAINT	1.45	Seal - Double and Fog Seal	$43,500
2028	7	017-Caswell	Preservation	Chambers Rd.	SR 1554	END MAINT	0.10	Seal - Double and Fog Seal	$3,933
2028	7	017-Caswell	Preservation	Clyde Baker Rd.	SR 1547	VSL	0.20	Seal - Double and Fog Seal	$7,866
2028	7	017-Caswell	Preservation	Cobb Rd.	US 158	END MAINT	0.95	Seal - Double and Fog Seal	$38,150
2028	7	017-Caswell	Preservation	Collie Rd.	NC 57	END MAINT	0.50	Seal - Double and Fog Seal	$19,665
2028	7	017-Caswell	Preservation	Cotton Pointer Rd.	NC 119	END MAINT	0.30	Seal - Double and Fog Seal	$10,000
2028	7	017-Caswell	Preservation	Covington Rd.	SR 1559	END MAINT	1.20	Seal - Double and Fog Seal	$47,196
2028	7	017-Caswell	Preservation	Cunningham Rd.	NC 119	PCL	0.40	Seal - Double and Fog Seal	$12,400
2028	7	017-Caswell	Preservation	Daniels Dairy Rd.	SR 1565	END MAINT	0.48	Seal - Double and Fog Seal	$14,880
2028	7	017-Caswell	Preservation	Elmore Rd.	SR 1561	END MAINT	0.80	Seal - Double and Fog Seal	$31,464
2028	7	017-Caswell	Preservation	Everette Rd.	SR 1600	END MAINT	0.40	Seal - Double and Fog Seal	$12,000
2028	7	017-Caswell	Preservation	Hamlett Rd.	NC 57	END MAINT	0.40	Seal - Double and Fog Seal	$15,732
2028	7	017-Caswell	Preservation	High Rock School Rd.	NC 62	BRIDGE	3.61	Seal - Double and Fog Seal	$43,800
2028	7	017-Caswell	Preservation	Hudson Rd.	NC 62	END MAINT	1.09	Seal - Double and Fog Seal	$43,263
2028	7	017-Caswell	Preservation	Jack Pointer Rd.	NC 119	SR 1554	3.20	Seal - Double and Fog Seal	$98,340
2028	7	017-Caswell	Preservation	John Long Rd.	SR 1597	END MAINT	1.33	Seal - Double and Fog Seal	$55,062
2028	7	017-Caswell	Preservation	Longs Mill Rd.	SR 1564	NC 62	4.20	Seal - Double and Fog Seal	$127,610
2028	7	017-Caswell	Preservation	McCann Rd.	SR 1554	END MAINT	0.68	Seal - Double and Fog Seal	$27,531
2028	7	017-Caswell	Preservation	Osmond Rd.	SR 1561	NC 119	2.03	Seal - Double and Fog Seal	$60,900
2028	7	017-Caswell	Preservation	Snatchburg Rd.	NC 119	SR 1542	1.81	Seal - Double and Fog Seal	$54,420
2028	7	017-Caswell	Preservation	Stephentown Rd.	NC 119	US 158	5.94	Seal - Double and Fog Seal	$235,980
2028	7	017-Caswell	Preservation	Steve Smith Rd.	SR 1311	END MAINT	0.30	Seal - Double and Fog Seal	$15,732
2028	7	017-Caswell	Preservation	Taylor Rd.	NC 119	END MAINT	0.77	Seal - Double and Fog Seal	$23,190
2028	7	017-Caswell	Preservation	William Barker Rd.	NC 119	PCL	0.51	Seal - Double and Fog Seal	$27,531
2028	7	017-Caswell	Preservation	Zimmerman Rd.	NC 62	END MAINT	1.40	Seal - Double and Fog Seal	$45,000
2028	7	041-Guilford	Resurfacing	Alamance Church Rd.	ACL	Greensboro City Limits	13.86	#78 Mat Seal and 1.5" S9.5B	$3,715,500
2028	7	041-Guilford	Resurfacing	Alamance Rd.	SR 1375	SR 4193	0.98	#78 Mat Seal and 1.5" S9.5B	$259,800
2028	7	041-Guilford	Resurfacing	Antler Ct.	SR 3274	CUL-DE-SAC	0.08	Mill 1.5" and 1.5" S9.5B	$21,160
2028	7	041-Guilford	Resurfacing	Ardsley ct.	SR 4224	END MAINT	0.14	#78 Mat Seal and 1.5" S9.5B	$37,200
2028	7	041-Guilford	Resurfacing	Arlington Rd.	SR 3801	SR 3850	0.30	#78 Mat Seal and 1.5" S9.5B	$78,990
2028	7	041-Guilford	Resurfacing	Auburn Hills Dr.	SR 1129	END MAINT	0.42	#78 Mat Seal and 1.5" S9.5B	$110,800
2028	7	041-Guilford	Resurfacing	Barbour Rd.	SR 3145	CUL-DE-SAC	0.39	#78 Mat Seal and 1.5" S9.5B	$104,500
2028	7	041-Guilford	Resurfacing	Barton Ct.	SR 2010	CUL-DE-SAC	0.16	#78 Mat Seal and 1.5" S9.5B	$43,500
2028	7	041-Guilford	Resurfacing	Baswell Rd.	SR 3402	DEAD END	0.10	#78 Mat Seal and 1.5" S9.5B	$43,900
2028	7	041-Guilford	Resurfacing	Bellwick Dr.	SR 3264	CUL-DE-SAC	0.20	Mill 1.5" and 1.5" S9.5B	$52,900
2028	7	041-Guilford	Resurfacing	Berwyn Ct.	SR 4225	END MAINT	0.09	#78 Mat Seal and 1.5" S9.5B	$22,900
2028	7	041-Guilford	Resurfacing	Blenheim Ct.	SR 2132	END MAINT	0.08	#78 Mat Seal and 1.5" S9.5B	$21,000
2028	7	041-Guilford	Resurfacing	Bridgehill Ct.	SR 3670	CUL-DE-SAC	0.11	#78 Mat Seal and 1.5" S9.5B	$28,500
2028	7	041-Guilford	Resurfacing	Bridgehill Ct.	SR 3670	CUL-DE-SAC	0.11	#78 Mat Seal and 1.5" S9.5B	$27,900
2028	7	041-Guilford	Resurfacing	Bridgestone Court	SR 3670	CUL-DE-SAC	0.06	#78 Mat Seal and 1.5" S9.5B	$15,371
2028	7	041-Guilford	Resurfacing	Bridgestone Ct.	SR 3670	CUL-DE-SAC	0.06	#78 Mat Seal and 1.5" S9.5B	$15,500
2028	7	041-Guilford	Resurfacing	Bridgeview Dr.	SR 3670	DEAD END	0.19	#78 Mat Seal and 1.5" S9.5B	$49,900
2028	7	041-Guilford	Resurfacing	Bridgeview Dr.	SR 3670	DEAD END	0.19	#78 Mat Seal and 1.5" S9.5B	$49,900
2028	7	041-Guilford	Resurfacing	Bridgeway Dr.	SR 3681	SR 3691	0.29	#78 Mat Seal and 1.5" S9.5B	$76,600
2028	7	041-Guilford	Resurfacing	Bridgeway Dr.	SR 3681	SR3691	0.29	#78 Mat Seal and 1.5" S9.5B	$76,600
2028	7	041-Guilford	Resurfacing	Britley Ct.	SR 3252	CUL-DE-SAC	0.14	Mill 1.5" and 1.5" S9.5B	$37,012
2028	7	041-Guilford	Resurfacing	Bull Rd.	SR 2007	END MAINT	0.45	#78 Mat Seal and 1.5" S9.5B	$119,600
2028	7	041-Guilford	Resurfacing	Cabin Ct.	SR 3242	CUL-DE-SAC	0.08	Mill 1.5" and 1.5" S9.5B	$21,149

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	7	041-Guilford	Resurfacing	Carnwell Ct.	SR 4225	END MAINT	0.13	#78 Mat Seal and 1.5" S9.5B	$34,200
2028	7	041-Guilford	Resurfacing	Carson Ridge Dr.	SR 2007	CUL-DE-SAC	0.20	#78 Mat Seal and 1.5" S9.5B	$61,800
2028	7	041-Guilford	Resurfacing	Chamberlain Rd.	SR 3180	SR 3182	0.10	#78 Mat Seal and 1.5" S9.5B	$26,510
2028	7	041-Guilford	Resurfacing	Chelsea Acres Ct.	SR 1424	END MAINT	0.11	#78 Mat Seal and 1.5" S9.5B	$28,700
2028	7	041-Guilford	Resurfacing	Chrisfield Ct.	SR 2010	CUL-DE-SAC	0.12	#78 Mat Seal and 1.5" S9.5B	$32,900
2028	7	041-Guilford	Resurfacing	Citron Dr.	SR 4330	END MAINT	0.20	#78 Mat Seal and 1.5" S9.5B	$50,400
2028	7	041-Guilford	Resurfacing	Clairese Ct.	SR 4400	DEAD END	0.17	#78 Mat Seal and 1.5" S9.5B	$44,500
2028	7	041-Guilford	Resurfacing	Clovelly Ct.	SR 3242	CUL-DE-SAC	0.04	Mill 1.5" and 1.5" S9.5B	$10,580
2028	7	041-Guilford	Resurfacing	Clovelly Dr.	SR 3029	SR 3262	1.04	Mill 1.5" and 1.5" S9.5B	$274,950
2028	7	041-Guilford	Resurfacing	Cobblestone Ct.	SR 3682	CUL-DE-SAC	0.04	#78 Mat Seal and 1.5" S9.5B	$10,100
2028	7	041-Guilford	Resurfacing	Cobblestone Ct.	SR 3682	CUL-DE-SAC	0.04	#78 Mat Seal and 1.5" S9.5B	$10,100
2028	7	041-Guilford	Resurfacing	Cravenwood Dr.	SR 2026	CUL-DE-SAC	0.47	#78 Mat Seal and 1.5" S9.5B	$125,100
2028	7	041-Guilford	Resurfacing	Deboe Rd.	NC 150	END MAINT	0.93	#78 Mat Seal and 1.5" S9.5B	$245,500
2028	7	041-Guilford	Resurfacing	Deep Valley Rd.	SR 2302	SR 4987	0.28	#78 Mat Seal and 1.5" S9.5B	$75,300
2028	7	041-Guilford	Resurfacing	E. Lee St.	I-40	SR 3180	1.01	#78 Mat Seal and 1.5" S9.5B	$267,670
2028	7	041-Guilford	Resurfacing	Eastridge Rd.	NC 150	END MAINT	0.24	#78 Mat Seal and 1.5" S9.5B	$62,900
2028	7	041-Guilford	Resurfacing	Edgemont Rd.	SR 3505	US 421	0.73	#78 Mat Seal and 1.5" S9.5B	$194,600
2028	7	041-Guilford	Resurfacing	Edgewood Dr.	DEAD END	SR 3138	0.37	#78 Mat Seal and 1.5" S9.5B	$98,900
2028	7	041-Guilford	Resurfacing	Edgewood Terrace Rd.	SR 3134	MP 0.328	0.33	#78 Mat Seal and 1.5" S9.5B	$86,900
2028	7	041-Guilford	Resurfacing	Endicott Rd.	SR 1850	SR 1906	0.37	#78 Mat Seal and 1.5" S9.5A	$98,100
2028	7	041-Guilford	Resurfacing	Evanstown	SR 1116	END MAINT	0.34	#78 Mat Seal and 1.5" S9.5B	$90,700
2028	7	041-Guilford	Resurfacing	Fairlawn Dr.	SR 2104	END MAINT	0.31	#78 Mat Seal and 1.5" S9.5B	$80,900
2028	7	041-Guilford	Resurfacing	Flatiron Ct.	SR 3262	CUL-DE-SAC	0.06	Mill 1.5" and 1.5" S9.5B	$15,900
2028	7	041-Guilford	Resurfacing	Flora Vista Ct.	SR 3242	CUL-DE-SAC	0.12	Mill 1.5" and 1.5" S9.5B	$31,730
2028	7	041-Guilford	Resurfacing	Frogs Leap Way Rd.	SR 5003	CUL-DE-SAC	0.22	#78 Mat Seal and 1.5" S9.5B	$58,900
2028	7	041-Guilford	Resurfacing	Gate City Blvd.	US 29	I-40	0.42	#78 Mat Seal and 1.5" S9.5B	$209,130
2028	7	041-Guilford	Resurfacing	Gatwick Dr.	SR 3265	CUL-DE-SAC	0.04	Mill 1.5" and 1.5" S9.5B	$10,600
2028	7	041-Guilford	Resurfacing	Glen Laurel Dr.	SR 3242	SR 3037	0.25	Mill 1.5" and 1.5" S9.5B	$66,092
2028	7	041-Guilford	Resurfacing	Gramercy Park Dr.	SR 3036	SR 3242	0.58	Mill 1.5" and 1.5" S9.5B	$153,333
2028	7	041-Guilford	Resurfacing	Gramerly Park Ct.	SR 3261	CUL-DE-SAC	0.04	Mill 1.5" and 1.5" S9.5B	$10,575
2028	7	041-Guilford	Resurfacing	Greenlawn Dr.	SR 2120	SR 2123	0.50	#78 Mat Seal and 1.5" S9.5B	$86,213
2028	7	041-Guilford	Resurfacing	Grey Fox Rd.	NC 150	CUL-DE-SAC	0.30	#78 Mat Seal and 1.5" S9.5B	$79,800
2028	7	041-Guilford	Resurfacing	Greybark Dr.	SR 3670	DEAD END	0.09	#78 Mat Seal and 1.5" S9.5B	$23,600
2028	7	041-Guilford	Resurfacing	Greybark Dr.	SR 3670	DEAD END	0.09	#78 Mat Seal and 1.5" S9.5B	$23,600
2028	7	041-Guilford	Resurfacing	Greywood Dr.	SR 3430	EOP	0.52	#78 Mat Seal and 1.5" S9.5B	$140,500
2028	7	041-Guilford	Resurfacing	Harbor Ridge Dr.	SR 3029	DEAD END	0.58	Mill 1.5" and 1.5" S9.5B	$153,333
2028	7	041-Guilford	Resurfacing	Hickory Hollow Rd.	SR 1546	END MAINT	0.22	#78 Mat Seal and 1.5" S9.5B	$57,600
2028	7	041-Guilford	Resurfacing	Horse Farm Rd.	SR 2104	DEAD END	0.25	#78 Mat Seal and 1.5" S9.5B	$66,000
2028	7	041-Guilford	Resurfacing	Joywood Ct.	SR 2008	END MAINT	0.36	#78 Mat Seal and 1.5" S9.5B	$63,879
2028	7	041-Guilford	Resurfacing	Julius Ct.	SR 3273	CUL-DE-SAC	0.22	Mill 1.5" and 1.5" S9.5B	$58,161
2028	7	041-Guilford	Resurfacing	Kearns-Hackett Rd.	SR 3738	SR 3402	1.50	#78 Mat Seal and 1.5" S9.5B	$398,200
2028	7	041-Guilford	Resurfacing	Kinross Dr.	SR 3802	DEAD END	0.27	#78 Mat Seal and 1.5" S9.5B	$71,600
2028	7	041-Guilford	Resurfacing	Koala Dr.	SR 2127	CUL-DE-SAC	0.04	#78 Mat Seal and 1.5" S9.5B	$97,300
2028	7	041-Guilford	Resurfacing	Labrador Ct.	SR 3242	CUL-DE-SAC	0.06	Mill 1.5" and 1.5" S9.5B	$15,870
2028	7	041-Guilford	Resurfacing	Lanier Rd.	SR 2113	SR 2114	0.53	#78 Mat Seal and 1.5" S9.5B	$140,200
2028	7	041-Guilford	Resurfacing	Lannigan Dr.	SR 3261	SR 3242	0.28	Mill 1.5" and 1.5" S9.5B	$74,023
2028	7	041-Guilford	Resurfacing	Laurel Acres Ct.	SR 4401	DEAD END	0.19	#78 Mat Seal and 1.5" S9.5B	$49,100
2028	7	041-Guilford	Resurfacing	Laurel Forest Ct.	SR 4413	DEAD END	0.10	#78 Mat Seal and 1.5" S9.5B	$26,500
2028	7	041-Guilford	Resurfacing	Laurel Knoll Dr.	SR 3426	SR 3505	0.50	#78 Mat Seal and 1.5" S9.5A	$131,720
2028	7	041-Guilford	Resurfacing	Lochwood Dr.	SR 3036	SR 3274	0.15	Mill 1.5" and 1.5" S9.5B	$39,700
2028	7	041-Guilford	Resurfacing	Maccarron Ct.	SR 3252	CUL-DE-SAC	0.15	Mill 1.5" and 1.5" S9.5B	$39,656
2028	7	041-Guilford	Resurfacing	Mcginty Rd.	SR 3262	SR 3277	0.10	Mill 1.5" and 1.5" S9.5B	$26,450
2028	7	041-Guilford	Resurfacing	McLaughlin Dr.	SR 3295	CUL-DE-SAC	0.34	Mill 1.5" and 1.5" S9.5B	$89,885
2028	7	041-Guilford	Resurfacing	Minglewood Tr.	SR 2228	CUL-DE-SAC	0.25	#78 Mat Seal and 1.5" S9.5B	$64,950
2028	7	041-Guilford	Resurfacing	NC 62	SR 1129	SR 1162	2.40	#78 Mat Seal and 1.25" S9.5A and Widen	$801,722
2028	7	041-Guilford	Resurfacing	NC 68	SR 2016	US 150	5.35	#78 Mat Seal and 1.5" S9.5B	$461,309
2028	7	041-Guilford	Resurfacing	Norcross Rd.	SR 1850	END MAINT	0.38	#78 Mat Seal and 1.5" S9.5A	$110,000
2028	7	041-Guilford	Resurfacing	Old Onslow Rd.	SR 1372	SR1479	0.90	#78 Mat Seal and 1.5" S9.5B	$238,000
2028	7	041-Guilford	Resurfacing	Old Randleman Rd.	SR 1113	SR 1007	2.00	#78 Mat Seal and 1.5" S9.5B	$530,100

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	7	041-Guilford	Resurfacing	Old Randleman Rd.	SR 1113	SR 1007	1.94	#78 Mat Seal and 1.5" S9.5B	$682,200
2028	7	041-Guilford	Resurfacing	Panda Ct.	SR 5068	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$177,600
2028	7	041-Guilford	Resurfacing	Pawnee Rd.	SR 4871	DEAD END	0.18	#78 Mat Seal and 1.5" S9.5B	$47,500
2028	7	041-Guilford	Resurfacing	Peabody Rd.	SR 1855	FCL	0.20	#78 Mat Seal and 1.5" S9.5B	$201,500
2028	7	041-Guilford	Resurfacing	Pepperdine Rd.	SR 4871	DEAD END	0.36	#78 Mat Seal and 1.5" S9.5B	$95,500
2028	7	041-Guilford	Resurfacing	Pine Meadows Ct.	SR 3270	CUL-DE-SAC	0.07	Mill 1.5" and 1.5" S9.5B	$18,506
2028	7	041-Guilford	Resurfacing	Polar Dr.	SR 5068	DEAD END	0.09	#78 Mat Seal and 1.5" S9.5B	$22,900
2028	7	041-Guilford	Resurfacing	Rankin Mill Rd.	Hicone Rd.	Huffine Mill Rd.	3.73	#78 Mat Seal and 1.5" S9.5B	$987,707
2028	7	041-Guilford	Resurfacing	Red Hill Ct.	SR 4225	END MAINT	0.16	#78 Mat Seal and 1.5" S9.5B	$41,200
2028	7	041-Guilford	Resurfacing	River Farm Rd.	SR 4639	DEADEND	0.17	#78 Mat Seal and 1.5" S9.5B	$43,800
2028	7	041-Guilford	Resurfacing	Rockbridge Rd.	SR 1482	SR 1495	0.10	#78 Mat Seal and 1.5" S9.5B	$25,990
2028	7	041-Guilford	Resurfacing	Rothwood Acres Rd.	SR 3037	MP 0.183	0.18	Mill 1.5" and 1.5" S9.5B	$47,590
2028	7	041-Guilford	Resurfacing	Rothwood Acres Rd.	SR 3242	DEAD END	0.13	Mill 1.5" and 1.5" S9.5B	$34,370
2028	7	041-Guilford	Resurfacing	Rush Springs Ct.	SR 4988	CUL-DE-SAC	0.06	#78 Mat Seal and 1.5" S9.5B	$16,200
2028	7	041-Guilford	Resurfacing	Sedgegrove Rd.	SR 1129	END MAINT	0.31	#78 Mat Seal and 1.5" S9.5B	$80,900
2028	7	041-Guilford	Resurfacing	Sedgewood Ln.	SR 1129	END MAINT	0.29	#78 Mat Seal and 1.5" S9.5B	$77,200
2028	7	041-Guilford	Resurfacing	Sharpe Acres Dr.	SR 3036	SR 3134	0.17	#78 Mat Seal and 1.5" S9.5B	$46,115
2028	7	041-Guilford	Resurfacing	Sheree Ln.	SR 3036	SR 3134	0.15	#78 Mat Seal and 1.5" S9.5B	$39,500
2028	7	041-Guilford	Resurfacing	Stirup Dr.	SR 4224	SR 1129	0.43	#78 Mat Seal and 1.5" S9.5B	$112,700
2028	7	041-Guilford	Resurfacing	Suffolk Trail	SR 1375	END MAINT	0.53	#78 Mat Seal and 1.5" S9.5B	$140,500
2028	7	041-Guilford	Resurfacing	Summer Breeze Ct.	SR 4984	END MAINT	0.06	#78 Mat Seal and 1.5" S9.5B	$15,500
2028	7	041-Guilford	Resurfacing	Summer Wind Ct.	SR 4984	END MAINT	0.10	#78 Mat Seal and 1.5" S9.5B	$26,900
2028	7	041-Guilford	Resurfacing	Tadpole Ct.	SR 5003	CUL-DE-SAC	0.05	#78 Mat Seal and 1.5" S9.5B	$13,000
2028	7	041-Guilford	Resurfacing	Thornscrest Dr.	SR 4224	END MAINT	0.08	#78 Mat Seal and 1.5" S9.5B	$22,500
2028	7	041-Guilford	Resurfacing	Timkermill Ct.	SR 3274	DEAD END	0.06	Mill 1.5" and 1.5" S9.5B	$15,890
2028	7	041-Guilford	Resurfacing	Village View Dr.	SR 3261	DEAD END	0.06	Mill 1.5" and 1.5" S9.5B	$15,870
2028	7	041-Guilford	Resurfacing	W. Cabarrus Ct.	SR 1482	END MAINT	0.09	#78 Mat Seal and 1.5" S9.5B	$24,990
2028	7	041-Guilford	Resurfacing	W. English Rd.	SR 1961	SR 1988	1.55	#78 Mat Seal and 1.5" S9.5B	$411,350
2028	7	041-Guilford	Resurfacing	W. English Rd.	SR 1970	SR 1009	0.99	#78 Mat Seal and 1.5" S9.5B	$261,100
2028	7	041-Guilford	Resurfacing	W. Lexington Ave.	FCL	SR 1009	1.59	#78 Mat Seal and 1.5" S9.5B	$339,300
2028	7	041-Guilford	Resurfacing	W. Martin Luther King Dr.	SR 1009	SR 1988	0.95	#78 Mat Seal and 1.5" S9.5C	$251,500
2028	7	041-Guilford	Resurfacing	Waterbridge Ct.	SR 2770	CUL-DE-SAC	0.08	#78 Mat Seal and 1.5" S9.5B	$23,851
2028	7	041-Guilford	Resurfacing	Wiley Lewis Rd.	SR 3505	DEAD END	3.66	#78 Mat Seal and 1.5" S9.5B	$969,960
2028	7	041-Guilford	Resurfacing	Williams Dairy Rd.	Liberty Rd.	SE School Rd.	3.06	#78 Mat Seal and 1.5" S9.5B	$8,111,000
2028	7	041-Guilford	Preservation	Agate Rd.	SR 2755	DEAD END	0.24	Seal - Double	$11,000
2028	7	041-Guilford	Preservation	Agate Rd.	SR 2755	DEAD END	0.06	Seal - Double	$2,636
2028	7	041-Guilford	Preservation	Ambling Rd.	US 70	END PVMT	0.24	Seal - Double and Fog Seal	$9,000
2028	7	041-Guilford	Preservation	Anderland Rd.	SR 2800	End Pvmt.	0.45	Seal - Double and Fog Seal	$13,500
2028	7	041-Guilford	Preservation	Apple Wyrick Rd.	SR 2770	SR 2770	1.64	Seal - Double and Fog Seal	$49,200
2028	7	041-Guilford	Preservation	Apple-Little Rd.	SR 2765	END MAINT	0.66	Seal - Double	$20,000
2028	7	041-Guilford	Preservation	Athens Rd.	US 158	END MAINT.	1.20	Seal - Double and Fog Seal	$144,261
2028	7	041-Guilford	Preservation	Baldwin Rd.	SR 2735	SR 2737	0.90	Seal - Double and Fog Seal	$29,100
2028	7	041-Guilford	Preservation	Bell Rd.	SR 2724	END MAINT	0.99	Seal - Double	$30,000
2028	7	041-Guilford	Preservation	Bell Road (South)	SR 2755	DEAD END	0.20	Seal - Double	$23,000
2028	7	041-Guilford	Preservation	Benedict Rd.	SR 1104	END MAINT	0.13	Seal - Double and Fog Seal	$3,900
2028	7	041-Guilford	Preservation	Bittle Rd.	SR 2746	MP 1.724	1.73	Seal - Double and Fog Seal	$51,600
2028	7	041-Guilford	Preservation	Blubonnet Rd.	SR 1129	END MAINT	0.20	Seal - Double and Fog Seal	$21,060
2028	7	041-Guilford	Preservation	Bobolink Rd.	SR 2826	END MAINT	0.51	Seal - Double	$13,000
2028	7	041-Guilford	Preservation	Brandy Rd.	SR 1129	END MAINT	0.60	Seal - Double and Fog Seal	$63,180
2028	7	041-Guilford	Preservation	Brook Rd.	SR 4025	END MAINT	0.15	Seal - Double and Fog Seal	$5,100
2028	7	041-Guilford	Preservation	Burke Clubhouse Rd.	SR 1550	DEAD END	0.55	Seal - Double and Fog Seal	$16,500
2028	7	041-Guilford	Preservation	Butler Rd.	SR 2819	SR 2746	1.97	Seal - Double and Fog Seal	$59,100
2028	7	041-Guilford	Preservation	Campground Rd.	SR 1117	SR 1328	0.50	Seal - Double and Fog Seal	$14,910
2028	7	041-Guilford	Preservation	Cedar Park Rd.	SR 4240	SR 3028	0.80	Seal - Double and Fog Seal	$25,000
2028	7	041-Guilford	Preservation	Centenary Ct.	SR 4024	SR 4026	0.05	Seal - Double and Fog Seal	$2,400
2028	7	041-Guilford	Preservation	Chuckwood Rd.	SR 1113	END MAINT	0.14	Seal - Double and Fog Seal	$6,200
2028	7	041-Guilford	Preservation	Cimmaron Ct.	SR 1129	END MAINT	0.46	Seal - Double and Fog Seal	$20,410
2028	7	041-Guilford	Preservation	Coefield Rd.	SR 1109	SR 1104	0.17	Seal - Double and Fog Seal	$11,400
2028	7	041-Guilford	Preservation	Colony Rd.	SR 2746	SR 2755	1.51	Seal - Double and Fog Seal	$45,300

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	7	041-Guilford	Preservation	Concord Church Rd.	SR 1104	END MAINT	0.77	Seal - Double and Fog Seal	$23,100
2028	7	041-Guilford	Preservation	Cone Club Rd.	NC 100	SR 2758	0.94	Seal - Double	$28,000
2028	7	041-Guilford	Preservation	Cornerhouse Rd.	SR 2746	DEAD END	0.10	Seal - Double and Fog Seal	$4,386
2028	7	041-Guilford	Preservation	Cotton Rd.	SR 2746	SR 2801	1.50	Seal - Double and Fog Seal	$45,000
2028	7	041-Guilford	Preservation	Country Lake Dr.	SR 1104	END MAINT	0.50	Seal - Double and Fog Seal	$15,120
2028	7	041-Guilford	Preservation	Cullen Rd.	SR 2755	SR 2746	1.94	Seal - Double	$58,000
2028	7	041-Guilford	Preservation	Drew Sharpe Rd.	NC 100	DEAD END	0.56	Seal - Double and Fog Seal	$16,800
2028	7	041-Guilford	Preservation	Dunntown Rd.	SR 2744	DEAD END	0.42	Seal - Double and Fog Seal	$12,600
2028	7	041-Guilford	Preservation	Eaglesfield Rd.	SR 2746	NC 61	1.00	Seal - Double	$30,000
2028	7	041-Guilford	Preservation	Easthurst Rd.	SR 2746	SR 2898	0.18	Seal - Double and Fog Seal	$7,876
2028	7	041-Guilford	Preservation	Endwell Rd.	SR 2768	SR 3111	1.17	Seal - Double	$35,000
2028	7	041-Guilford	Preservation	Falcon Rd.	SR 2755	DEAD END	0.36	Seal - Double and Fog Seal	$10,800
2028	7	041-Guilford	Preservation	Fernway Dr.	SR 2759	END MAINT	0.46	Seal - Cape	$27,221
2028	7	041-Guilford	Preservation	Flowers Rd.	SR 2737	DEAD END	0.89	Seal - Double and Fog Seal	$26,700
2028	7	041-Guilford	Preservation	Frank Rd.	SR 2752	SR 2755	0.55	Seal - Double	$16,000
2028	7	041-Guilford	Preservation	Friendly Farm Rd.	SR 1104	END MAINT	1.10	Seal - Double and Fog Seal	$125,307
2028	7	041-Guilford	Preservation	Gantwood Lane	SR 2808	PVMT CHANGE	0.59	Seal - Double	$18,000
2028	7	041-Guilford	Preservation	Gateway Dr.	SR 2922	DEAD END	0.21	Seal - Double and Fog Seal	$9,487
2028	7	041-Guilford	Preservation	Graystone Ct.	SR 1113	END MAINT	0.74	Seal - Double and Fog Seal	$33,100
2028	7	041-Guilford	Preservation	Halsbrook Rd.	SR 1007	END MAINT	0.33	Seal - Double and Fog Seal	$9,900
2028	7	041-Guilford	Preservation	Hines Andrew Rd.	SR 2930	MP .075	0.21	Seal - Double and Fog Seal	$2,100
2028	7	041-Guilford	Preservation	Honeycutt Ct.	SR 1127	END MAINT	0.25	Seal - Double and Fog Seal	$28,431
2028	7	041-Guilford	Preservation	Howerton Rd.	BEG PVMT	END PVMT	0.20	Seal - Double and Fog Seal	$6,000
2028	7	041-Guilford	Preservation	Howerton Rd.	BEG PVMT	SR 2768	0.30	Seal - Double and Fog Seal	$9,000
2028	7	041-Guilford	Preservation	Hudson-James Rd.	US 158	END MAINT.	1.13	Seal - Double and Fog Seal	$118,989
2028	7	041-Guilford	Preservation	Huffine Farm Rd.	SR 2817	SR 2770	1.30	Seal - Double and Fog Seal	$39,000
2028	7	041-Guilford	Preservation	Ira Dr.	SR 1008	END MAINT.	0.10	Seal - Double and Fog Seal	$15,795
2028	7	041-Guilford	Preservation	J. L. Martin Rd.	SR 2814	END MAINT	0.20	Seal - Double	$9,000
2028	7	041-Guilford	Preservation	Jennie Dr.	SR 2808	DEAD END	0.17	Seal - Double and Fog Seal	$5,100
2028	7	041-Guilford	Preservation	Jesse Rd.	SR 2798	DEAD END	0.40	Seal - Double and Fog Seal	$14,100
2028	7	041-Guilford	Preservation	Keansburg Rd.	SR 2772	SR 2767	0.99	Seal - Double	$30,000
2028	7	041-Guilford	Preservation	Keller Dr.	US158	RCL	0.10	Seal - Double and Fog Seal	$10,530
2028	7	041-Guilford	Preservation	Kentmere Rd.	SR 1107	END MAINT	0.46	Seal - Double and Fog Seal	$13,800
2028	7	041-Guilford	Preservation	Kivette House Dr.	SR 2758	DEAD END	0.87	Seal - Cape	$82,650
2028	7	041-Guilford	Preservation	Lamarr Valley Rd.	SR 2746	MP .387	0.39	Seal - Double and Fog Seal	$11,700
2028	7	041-Guilford	Preservation	Loire Dr.	SR 2220	END MAINT	0.14	Seal - Cape	$13,300
2028	7	041-Guilford	Preservation	Longacers Rd.	SR 1237	END MAINT	0.42	Seal - Double and Fog Seal	$18,900
2028	7	041-Guilford	Preservation	Lookout Place	US 70	SR 2814	0.52	Seal - Double and Fog Seal	$9,000
2028	7	041-Guilford	Preservation	Lou Dr.	US 70	END MAINT	0.18	Seal - Double	$1,000
2028	7	041-Guilford	Preservation	Ludgate Rd.	NC 61	SR 2739	1.92	Seal - Double and Fog Seal	$57,600
2028	7	041-Guilford	Preservation	Mcintyre Rd.	SR 2746	DEAD END	1.66	Seal - Double	$50,000
2028	7	041-Guilford	Preservation	Meadowlane Circle	SR 2950	SR 2882	0.42	Seal - Double	$232,000
2028	7	041-Guilford	Preservation	Moritz Dr.	SR 2103	US 158	0.47	Seal - Double and Fog Seal	$49,491
2028	7	041-Guilford	Preservation	Norman Park Rd.	SR 1392	END MAINT	0.20	Seal - Double and Fog Seal	$9,200
2028	7	041-Guilford	Preservation	Old Kivett Loop	SR 1113	SR 1145	0.28	Seal - Double and Fog Seal	$12,500
2028	7	041-Guilford	Preservation	Painter Lakes Rd.	SR 2752	SR 2755	1.34	Seal - Double	$3,000
2028	7	041-Guilford	Preservation	Patricia Dr.	US 158	SR 2239	0.03	Seal - Double and Fog Seal	$3,159
2028	7	041-Guilford	Preservation	Piney Rd.	SR 2807	DEAD END	0.46	Seal - Double	$14,000
2028	7	041-Guilford	Preservation	Pitman Rd.	SR 1007	END MAINT	0.24	Seal - Double and Fog Seal	$7,200
2028	7	041-Guilford	Preservation	Powerline Rd.	SR 2724	RR CROSSING	1.08	Seal - Double	$32,000
2028	7	041-Guilford	Preservation	Purdue Rd.	SR 1113	SR 4025	0.09	Seal - Double and Fog Seal	$3,982
2028	7	041-Guilford	Preservation	Ranhurst Rd.	SR 2746	END MAINT	0.25	Seal - Double and Fog Seal	$11,300
2028	7	041-Guilford	Preservation	Rehobeth Church Rd.	SR 1104	SR 1104	0.28	Seal - Double and Fog Seal	$12,500
2028	7	041-Guilford	Preservation	Riverview Dr.	SR 2938	SR 2987	0.17	Seal - Double and Fog Seal	$7,600
2028	7	041-Guilford	Preservation	Roberts Court Rd.	SR 1392	END MAINT	0.34	Seal - Double and Fog Seal	$15,300
2028	7	041-Guilford	Preservation	Robinson Rd.	SR 1002	END MAINT.	0.71	Seal - Double and Fog Seal	$74,763
2028	7	041-Guilford	Preservation	Rock Quarry Rd.	SR 2746	END MAINT	0.47	Seal - Double	$14,000
2028	7	041-Guilford	Preservation	Rolling Acres Dr.	BEG MAINT	SR 2987	0.49	Seal - Double and Fog Seal	$21,800
2028	7	041-Guilford	Preservation	Rolling Acres Dr.	SR 2938	SR 2996	0.20	Seal - Double and Fog Seal	$9,200

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	7	041-Guilford	Preservation	Rumbley Rd.	US 158	END MAINT.	0.40	Seal - Double and Fog Seal	$52,650
2028	7	041-Guilford	Preservation	Rusty Lane	US 70	SR 2895	0.11	Seal - Double and Fog Seal	$5,500
2028	7	041-Guilford	Preservation	Scarlet Oak Drive	SR 2814	SR 2810	0.30	Seal - Double and Fog Seal	$10,500
2028	7	041-Guilford	Preservation	Sedgehill Ct.	SR 1129	END MAINT	0.43	Seal - Double and Fog Seal	$19,300
2028	7	041-Guilford	Preservation	Short Farm Rd	SR 1004	END MAINT	0.59	Seal - Double and Fog Seal	$26,320
2028	7	041-Guilford	Preservation	Simmons Lake Dr.	SR 2886	SR 2809	0.38	Seal - Double and Fog Seal	$16,900
2028	7	041-Guilford	Preservation	Smith Dairy Rd.	Sr 2779	END MAINT	0.42	Seal - Double and Fog Seal	$12,600
2028	7	041-Guilford	Preservation	Southview Dr.	SR 1257	END MAINT	0.70	Seal - Double and Fog Seal	$78,975
2028	7	041-Guilford	Preservation	St. John Church Rd.	SR 2752	SR 2755	0.54	Seal - Double	$16,000
2028	7	041-Guilford	Preservation	Sue Dr.	US 70	DEAD END	0.27	Seal - Double	$11,000
2028	7	041-Guilford	Preservation	Suits Rd.	NC 61	SR 2741	0.83	Seal - Double and Fog Seal	$24,900
2028	7	041-Guilford	Preservation	Summerdale Rd.	NC 61	ACL	1.80	Seal - Double and Fog Seal	$54,000
2028	7	041-Guilford	Preservation	Sweetgum Rd.	SR 2746	DEAD END	0.35	Seal - Double and Fog Seal	$10,500
2028	7	041-Guilford	Preservation	Sweetwater Ct.	SR 1129	END MAINT	0.80	Seal - Double and Fog Seal	$35,800
2028	7	041-Guilford	Preservation	Thoroughbred Dr.	SR 2314	END MAINT.	0.07	Seal - Double and Fog Seal	$7,371
2028	7	041-Guilford	Preservation	Timbermill Rd.	SR 2819	END MAINT.	0.60	Seal - Double and Fog Seal	$19,200
2028	7	041-Guilford	Preservation	Tokay Ct./BifPoplar Ln.	SR 1128	END MAINT	0.23	Seal - Double and Fog Seal	$6,900
2028	7	041-Guilford	Preservation	Viewmont Dr. (South)	SR 1116	END MAINT	0.60	Seal - Double and Fog Seal	$68,445
2028	7	041-Guilford	Preservation	Wadena Ct.	SR 1129	SR 1271	0.10	Seal - Double and Fog Seal	$4,400
2028	7	041-Guilford	Preservation	Wadena Ct.	SR 1271	END MAINT	0.10	Seal - Double and Fog Seal	$10,530
2028	7	041-Guilford	Preservation	Weeping Willow Circle	US 70	DEAD END	0.09	Seal - Double and Fog Seal	$2,700
2028	7	041-Guilford	Preservation	Windswept Rd.	SR 2321	END MAINT.	0.40	Seal - Double and Fog Seal	$44,226
2028	7	041-Guilford	Preservation	Winford Rd.	SR 1129	END MAINT	0.50	Seal - Double and Fog Seal	$65,286
2028	7	041-Guilford	Preservation	Woodard Dr.	US 70	END MAINT	0.31	Seal - Double	$57,000
2028	7	068-Orange	Resurfacing	Bethel Hickory Rd.	SR 1112	NC 54	3.16	#67 Mat Seal and 1.5" S9.5B	$837,500
2028	7	068-Orange	Resurfacing	Dumont Dr.	SR 1002	DEAD END	1.12	#78 Mat Seal and 1.25" S9.5A	$296,816
2028	7	068-Orange	Resurfacing	Gemena Rd.	SR 1103	SR 2147	0.70	#78 Mat Seal and 1.5" S9.5B	$204,100
2028	7	068-Orange	Resurfacing	Hawkins Rd.	NC 86	SR 1001	3.56	#78 Mat Seal and 1.5" S9.5B	$943,500
2028	7	068-Orange	Resurfacing	Joe Mac Rd.	SR 1104	DEAD END	1.42	#78 Mat Seal and 1.5" S9.5B	$376,320
2028	7	068-Orange	Resurfacing	Mill Creek Rd.	SR 1004	SR 1306	5.45	#78 Mat Seal and 1.5" S9.5A	$1,444,330
2028	7	068-Orange	Resurfacing	Phelps Rd.	NC 86	NC 57	2.24	#78 Mat Seal and 1.5" S9.5B	$662,540
2028	7	068-Orange	Preservation	Meacham Rd.	SR 1940	CCL	0.48	Seal - Double and Fog Seal	$14,400
2028	7	068-Orange	Preservation	Moonridge Rd.	SR 1942	SR 1941	0.46	Seal - Double and Fog Seal	$16,100
2028	7	068-Orange	Preservation	Old School Rd.	SR 1942	CUL-DE-SAC	0.72	Seal - Double and Fog Seal	$21,480
2028	7	079-Rockingham	Resurfacing	Bailey Rd.	NC 704	SR 2308	1.42	#78 Mat Seal and 1.5" S9.5B	$250,000
2028	7	079-Rockingham	Resurfacing	Cardwell Rd.	NC 135	DEAD END	0.40	#78 Mat Seal and 1.5" S9.5B	$90,000
2028	7	079-Rockingham	Resurfacing	Crutchfield Rd.	US 29 Bus.	SR 1980	3.40	#78 Mat Seal and 1.5" S9.5B	$560,000
2028	7	079-Rockingham	Resurfacing	Mark Rd.	NC 65	DEAD END	0.71	#78 Mat Seal and 1.5" S9.5B	$96,979
2028	7	079-Rockingham	Resurfacing	McCollum Rd.	NC 704	SR 2316	3.06	#78 Mat Seal and 1.5" S9.5B	$426,870
2028	7	079-Rockingham	Resurfacing	Norman Farm Rd.	SR 2349	CUL-DE-SAC	0.50	#78 Mat Seal and 1.5" S9.5B	$132,600
2028	7	079-Rockingham	Resurfacing	Rhodes Rd.	SR 1605	SR 1555	1.50	#78 Mat Seal and 1.5" S9.5B	$232,485
2028	7	079-Rockingham	Resurfacing	US 220 (S)	Off Ramp at Us 220 Bus	SR 110	5.79	#67 Mat Seal and 2.0" S9.5C	$1,651,308
2028	7	079-Rockingham	Resurfacing	US 220N	SR 1110	On Ramp US 220 Bus.	5.79	#67 Mat Seal and 2.0" S9.5C	$1,651,400
2028	7	079-Rockingham	Resurfacing	Westerly Park Rd.	SR 1501	SR 1553	1.85	#78 Mat Seal and 1.5" S9.5B	$295,000
2028	7	079-Rockingham	Preservation	Barker Rd.	NC 65	SR 2392	1.18	Seal - Double and Fog Seal	$35,400
2028	7	079-Rockingham	Preservation	Bass Rd.	SR 2669	DEAD END	0.10	Seal - Double and Fog Seal	$3,000
2028	7	079-Rockingham	Preservation	Benaja Rd.	SR 2426	US 29	3.75	Seal - Double and Fog Seal	$112,500
2028	7	079-Rockingham	Preservation	Beville Rd.	SR 2427	DEAD-END	0.78	Seal - Double and Fog Seal	$23,520
2028	7	079-Rockingham	Preservation	Brown Rd.	SR 2937	SR 2351	3.83	Seal - Double and Fog Seal	$114,900
2028	7	079-Rockingham	Preservation	Bud Rd.	SR 2409	END MAINT	0.63	Seal - Double and Fog Seal	$18,900
2028	7	079-Rockingham	Preservation	Butler Dairy Rd.	SR 2406	END MAINT.	0.79	Seal - Double and Fog Seal	$23,700
2028	7	079-Rockingham	Preservation	City Heights Loop	SR 3130	END MAINT	0.09	Seal - Double and Fog Seal	$2,250
2028	7	079-Rockingham	Preservation	Conner Rd.	NC 65	DEAD END	0.17	Seal - Double and Fog Seal	$5,100
2028	7	079-Rockingham	Preservation	Country Farm Rd.	US 158	SR 2468	1.00	Seal - Double and Fog Seal	$30,000
2028	7	079-Rockingham	Preservation	Country Lane	SR 2414	DEAD END	1.43	Seal - Double and Fog Seal	$42,900
2028	7	079-Rockingham	Preservation	Crabapple Rd.	SR 2695	END MAINT	0.40	Seal - Double and Fog Seal	$13,200
2028	7	079-Rockingham	Preservation	Cross Key Rd.	SR 2437	SR 2421	1.12	Seal - Double and Fog Seal	$33,600
2028	7	079-Rockingham	Preservation	Donothan Rd.	E DEAD END	W DEAD END	0.42	Seal - Double	$12,600
2028	7	079-Rockingham	Preservation	Edwards Rd.	SR 2041	DEAD END	0.05	Seal - Double and Fog Seal	$1,250

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	7	079-Rockingham	Preservation	Fairfield Rd.	SR 2437	END MAINT	0.47	Seal - Double and Fog Seal	$14,100
2028	7	079-Rockingham	Preservation	Fairview Church Rd.	US 158	SR 2432	0.42	Seal - Double and Fog Seal	$12,600
2028	7	079-Rockingham	Preservation	Falcon Rd.	SR 1987	DEAD END	0.87	Seal - Double and Fog Seal	$21,750
2028	7	079-Rockingham	Preservation	Gibbs Lake Rd.	US 29 BUS	END MAINT	0.39	Seal - Double and Fog Seal	$11,700
2028	7	079-Rockingham	Preservation	Gibbs Rd.	NC 65	US 29 BUS	2.14	Seal - Double and Fog Seal	$53,500
2028	7	079-Rockingham	Preservation	Gull Rd.	SR 1998	END MAINT	0.15	Seal - Double and Fog Seal	$4,500
2028	7	079-Rockingham	Preservation	Harvest Rd.	SR 2392	DEAD END	0.30	Seal - Double and Fog Seal	$9,000
2028	7	079-Rockingham	Preservation	Jewel Rd.	SR 2687	DEAD END	0.25	Seal - Double and Fog Seal	$7,500
2028	7	079-Rockingham	Preservation	Koger Rd.	SR 2423	END MAINT.	0.49	Seal - Double and Fog Seal	$14,700
2028	7	079-Rockingham	Preservation	Lovings Rd.	SR 2406	END MAINT	0.86	Seal - Double and Fog Seal	$25,800
2028	7	079-Rockingham	Preservation	McWalker Rd.	US 29	END MAINT	0.90	Seal - Double and Fog Seal	$27,000
2028	7	079-Rockingham	Preservation	Meadow Branch Rd.	SR 2422	US 158	1.51	Seal - Double and Fog Seal	$45,300
2028	7	079-Rockingham	Preservation	Miles Rd.	SR 1001	DEAD END	0.20	Seal - Double and Fog Seal	$6,000
2028	7	079-Rockingham	Preservation	Miller Chapel Rd.	SR 1001	SR 2406	2.47	Seal - Double and Fog Seal	$74,100
2028	7	079-Rockingham	Preservation	Monroeton Golf Course	US 158	END MAINT	0.75	Seal - Double and Fog Seal	$18,775
2028	7	079-Rockingham	Preservation	Monroeton Golf Course	US 158	END MAINT	0.07	Seal - Double and Fog Seal	$1,825
2028	7	079-Rockingham	Preservation	North Benaja Rd.	SR 2427	GCL	0.14	Seal - Double and Fog Seal	$4,200
2028	7	079-Rockingham	Preservation	O'Bryant Rd.	US 158	END MAINT	0.88	Seal - Double and Fog Seal	$26,400
2028	7	079-Rockingham	Preservation	Palmer Rd.	US 29 BUS	DEAD END	0.14	Seal - Double and Fog Seal	$3,500
2028	7	079-Rockingham	Preservation	Pinewood Rd.	SR 2392	END MAINT	0.38	Seal - Double and Fog Seal	$11,500
2028	7	079-Rockingham	Preservation	Quail Loop	NC 14	NC 14	0.29	Seal - Split	$7,250
2028	7	079-Rockingham	Preservation	Reid Lake Rd.	US 29 BUS	DEAD END	0.30	Seal - Double and Fog Seal	$9,000
2028	7	079-Rockingham	Preservation	Richardswood Rd.	GCL	END MAINT	0.22	Seal - Double and Fog Seal	$11,700
2028	7	079-Rockingham	Preservation	Speedway Dr.	US 29 BUS	DEAD END	0.56	Seal - Double and Fog Seal	$16,800
2028	7	079-Rockingham	Preservation	Speedwell Hill Rd.	SR 2406	DEAD END	0.16	Seal - Double and Fog Seal	$4,800
2028	7	079-Rockingham	Preservation	Styer Dairy Rd.	BEG MAINT	END PVMT	0.30	Seal - Double and Fog Seal	$9,000
2028	7	079-Rockingham	Preservation	Troublesome Rd.	SR 2937	END MAINT.	1.85	Seal - Double and Fog Seal	$55,500
2028	7	079-Rockingham	Preservation	Unicorn Rd.	SR 1001	END MAINT	0.70	Seal - Double and Fog Seal	$21,000
2028	7	079-Rockingham	Preservation	Van Hook Rd.	SR 2427	DEAD-END	1.20	Seal - Double and Fog Seal	$36,000
2028	7	079-Rockingham	Preservation	Walnut St.	PVMT CHANGE	END MAINT	1.00	Seal - Double and Fog Seal	$25,000
2028	7	079-Rockingham	Preservation	Waynick Rd.	US 158	END MAINT	1.02	Seal - Double and Fog Seal	$30,600
2028	7	079-Rockingham	Preservation	Wheeler Rd.	US 29 BUS	END MAINT	0.84	Seal - Double and Fog Seal	$30,000
2028	7	079-Rockingham	Preservation	Wheeler Rd.	US 29 BUS	END MAINT	0.23	Seal - Double and Fog Seal	$6,900
2028	8	019-Chatham	Resurfacing	NC 751	US 64	DURHAM CO	9.30	2.0" S9.5B	$1,544,500
2028	8	019-Chatham	Resurfacing	NC 87	SR 1516	US 64	2.00	1.5" S9.5B	$310,000
2028	8	019-Chatham	Resurfacing	SR 1006	SR 1130	SR 1005	2.63	1.5" S9.5B	$300,000
2028	8	019-Chatham	Resurfacing	SR 1008	SR 1011	SR 1972	3.50	1.25" S9.5B	$525,000
2028	8	019-Chatham	Resurfacing	SR 1009	SR 2303	NC 902	3.81	1.25" S9.5B	$670,000
2028	8	019-Chatham	Resurfacing	SR 1011	HAW RIVER	LEE CO	2.22	1.25" S9.5B	$333,000
2028	8	019-Chatham	Resurfacing	SR 1572	US 64	END PVMT	0.75	1.25" S9.5B	$113,000
2028	8	019-Chatham	Resurfacing	SR 1716	US 64	SR 1717	6.37	1.25" S9.5B	$956,000
2028	8	019-Chatham	Resurfacing	SR 1736	NC 751	SR 1733	2.07	1.25" S9.5B	$311,000
2028	8	019-Chatham	Resurfacing	SR 1809	RUSSET RUN	END MAINT	1.71	1.25" S9.5B	$257,000
2028	8	019-Chatham	Resurfacing	SR 1848	SR 1008	SR 1847	0.08	Mill 1.5" and 2.0" S9.5B	$12,000
2028	8	019-Chatham	Resurfacing	SR 1910	SR 1011	SR 1972	2.56	1.25" S9.5B	$384,000
2028	8	019-Chatham	Resurfacing	SR 1924	SR 1916	END PVMT	1.94	1.25" S9.5B	$291,000
2028	8	019-Chatham	Resurfacing	SR 1927	SR 1011	SR 1928	0.32	1.25" S9.5B	$48,000
2028	8	019-Chatham	Resurfacing	SR 1928	SR 1927	SR 1927	0.55	1.25" S9.5B	$83,000
2028	8	019-Chatham	Resurfacing	SR 1930	SR 1011	END MAINT	0.30	1.25" S9.5B	$45,000
2028	8	019-Chatham	Resurfacing	SR 1931	JORDAN LAKE SP	SR 1011	1.57	1.25" S9.5B	$236,000
2028	8	019-Chatham	Resurfacing	SR 1943	BRIDGE	SR 1012	3.10	1.25" S9.5B	$465,000
2028	8	019-Chatham	Resurfacing	SR 1955	SR 1012	SR 2218	3.55	1.25" S9.5B	$533,000
2028	8	019-Chatham	Resurfacing	SR 1958	BEGIN PVMT	END PVMT	2.50	1.25" S9.5B	$375,000
2028	8	019-Chatham	Resurfacing	SR 1962	SR 1012	CUL DE SAC	0.31	1.25" S9.5B	$47,000
2028	8	019-Chatham	Resurfacing	SR 1970	SR 1012	SR 1931	0.93	1.25" S9.5B	$140,000
2028	8	019-Chatham	Resurfacing	SR 1972	SR 1008	SR 1974	2.27	1.25" S9.5B	$341,000
2028	8	019-Chatham	Resurfacing	SR 1974	END MAINT	SR 1972	0.52	1.25" S9.5B	$78,000
2028	8	019-Chatham	Resurfacing	SR 1980	SR 1011	END MAINT	0.19	1.25" S9.5B	$29,000
2028	8	019-Chatham	Resurfacing	SR 1991	CUL DE SAC	US 64	1.19	1.25" S9.5B	$179,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	8	019-Chatham	Resurfacing	SR 2110	SR 2208	US 421	1.50	#67 Mat Seal and 1.5" S9.5B	$270,000
2028	8	019-Chatham	Resurfacing	SR 2217	US 15/501	SR 1958	2.57	1.25" S9.5B	$386,000
2028	8	019-Chatham	Resurfacing	SR 2318	NC 42	SR 2320	1.67	1.25" S9.5B	$300,000
2028	8	019-Chatham	Resurfacing	US 421	LEE CO	RXR BRIDGE	2.39	Mill 1.5" and 2.0" S9.5C	$650,000
2028	8	019-Chatham	Resurfacing	US 421	RXR BRIDGE	LEE CO	1.98	Mill 1.5" and 2.0" S9.5C	$500,000
2028	8	019-Chatham	Resurfacing	US 64 WB	HAW RIVER	SR 1578	6.60	2.0" S9.5C	$1,400,000
2028	8	019-Chatham	Preservation	SR 1100	SR 1005	SR 1129	2.31	Seal - Double	$70,000
2028	8	019-Chatham	Preservation	SR 1131	SR 1130	END MAINT	0.50	Crack Seal	$3,000
2028	8	019-Chatham	Preservation	SR 1161	NC 22	SR 1157	0.56	Seal - Double	$17,000
2028	8	019-Chatham	Preservation	SR 1334	SR 1003	END MAINT	0.90	Seal - Double	$33,000
2028	8	019-Chatham	Preservation	SR 1338	SR 1337	SR 1339	1.28	Seal - Double	$40,000
2028	8	019-Chatham	Preservation	SR 1339	ALAMANCE CO	SR 1003	0.51	Seal - Double	$20,000
2028	8	019-Chatham	Preservation	SR 1350	SR 1349	ALAMANCE CO	0.34	Seal - Double	$10,000
2028	8	019-Chatham	Preservation	SR 1509	SR 1511	SR 1508	1.87	Seal - Double	$57,000
2028	8	019-Chatham	Preservation	SR 1511	SR 1561	US 64	2.21	Seal - Double	$67,000
2028	8	019-Chatham	Preservation	SR 1557	SR 1346	END PVMT	0.31	Seal - Double	$10,000
2028	8	019-Chatham	Preservation	SR 1657	SR 1527	SR 1527	0.45	Seal - Double	$18,000
2028	8	019-Chatham	Preservation	SR 1661	SR 1527	CUL DE SAC	0.11	Seal - Double	$4,400
2028	8	019-Chatham	Preservation	SR 1666	SR 1530	SR 2543	0.30	Seal - Double and Fog Seal	$12,000
2028	8	019-Chatham	Preservation	SR 1762	SR 1717	DEAD END	0.76	Seal - Double	$22,800
2028	8	019-Chatham	Preservation	SR 1917	NC 42	END MAINT	0.73	Seal - Double	$22,000
2028	8	019-Chatham	Preservation	SR 1953	SR 2153	SR 2151	2.54	Seal - Double	$77,000
2028	8	019-Chatham	Preservation	SR 1971	SR 1970	END MAINT	1.01	Crack Seal	$7,000
2028	8	019-Chatham	Preservation	SR 2113	US 421	SR 2110	1.90	Seal - Double	$57,000
2028	8	019-Chatham	Preservation	SR 2119	US 421	SR 2120	1.39	Seal - Double	$42,000
2028	8	019-Chatham	Preservation	SR 2129	SR 2189	SR 2184	2.15	Seal - Double	$65,000
2028	8	019-Chatham	Preservation	SR 2129	US 421	SR 2189	1.46	Seal - Double	$44,000
2028	8	019-Chatham	Preservation	SR 2135	US 421	SR 2142	2.82	Seal - Double	$85,000
2028	8	019-Chatham	Preservation	SR 2135	SR 2133	US 421	0.80	Seal - Double	$24,000
2028	8	019-Chatham	Preservation	SR 2170	SR 2172	SR 2175	1.32	Seal - Double	$40,000
2028	8	019-Chatham	Preservation	SR 2222	SR 2218	SR 1953	1.50	Seal - Double	$45,000
2028	8	019-Chatham	Preservation	SR 2305	SR 2303	SR 2306	3.52	Seal - Double	$106,000
2028	8	019-Chatham	Preservation	US 15 NB	BEG DIV HWY	ORANGE CO	9.32	Crack Seal	$47,000
2028	8	019-Chatham	Preservation	US 15 NB	POWELL PLACE	BEG DIV HWY	0.82	Crack Seal	$4,000
2028	8	047-Hoke	Resurfacing	SR1001	SR1105	ROBESON CO	3.47	1.5" S9.5B	$513,560
2028	8	047-Hoke	Resurfacing	SR1303	US401	SR1304	2.17	1.5" S9.5B	$320,524
2028	8	047-Hoke	Resurfacing	SR1406	US401	SR1408	1.37	1.5" S9.5B	$209,150
2028	8	047-Hoke	Resurfacing	SR1422	SR1412	SR1406	3.52	1.5" S9.5B	$648,860
2028	8	047-Hoke	Resurfacing	US401	Start of Multi-Lane	SR1661	2.88	Mill 1.5" and 1.5" S9.5C	$505,500
2028	8	047-Hoke	Preservation	SR1113	SR 1105	ROBESON CO	3.68	Crack Seal	$36,840
2028	8	047-Hoke	Preservation	SR1116	NC211	SR1105	9.05	Crack Seal	$100,000
2028	8	047-Hoke	Preservation	SR1226	SR1225	SR1228	1.95	Seal - Double	$81,900
2028	8	047-Hoke	Preservation	SR1227	SR1228	SR1226	0.44	Seal - Double	$18,312
2028	8	047-Hoke	Preservation	SR1228	END PAVT	SR1225	4.76	Seal - Double	$175,000
2028	8	047-Hoke	Preservation	SR1235	SR1228	MOORE CO	1.65	Seal - Double	$76,426
2028	8	047-Hoke	Preservation	SR1246	SR1235	DEAD END	0.79	Seal - Double	$33,180
2028	8	047-Hoke	Preservation	SR1252	ROB CO	DEAD END	0.26	Seal - Double	$10,836
2028	8	053-Lee	Resurfacing	NC 42	SR 1736	SR 1322	3.14	Mill 1.5" and 1.5" S9.5C	$370,000
2028	8	053-Lee	Resurfacing	SR 1144	SR 1178	SR 1001	4.85	1.5" S9.5B	$751,750
2028	8	053-Lee	Resurfacing	SR 1144	SR 1179	SR 1178	6.07	1.5" S9.5B	$940,850
2028	8	053-Lee	Resurfacing	SR 1146	SR 1133	BRIDGE	1.21	1.25" SF9.5A	$187,500
2028	8	053-Lee	Resurfacing	SR 1157	US 1	SR 1293	2.69	1.5" S9.5B	$416,950
2028	8	053-Lee	Resurfacing	SR 1157	SR 1293	NC 78	0.83	1.5" S9.5B	$124,500
2028	8	053-Lee	Resurfacing	SR 1320	SR 1007	SR 1319	2.35	Full Depth Patching and 1.5" S9.5B	$536,000
2028	8	053-Lee	Resurfacing	SR 1403	BRIDGE	SR 1400	0.79	1.25" SF9.5A	$123,500
2028	8	053-Lee	Resurfacing	SR 1425	SR 1002	END MAINT	0.50	Full Depth Patching and 1.5" S9.5A	$99,800
2028	8	053-Lee	Resurfacing	SR 1434	SR 1002	Cul de Sac	0.76	Mill 1.5" and 1.5" S9.5A	$137,700
2028	8	053-Lee	Resurfacing	SR 1752	SR 1181	US 1 BUS	1.78	1.5" S9.5B	$288,000
2028	8	053-Lee	Resurfacing	US 1	SR 1333	US 1 BUS	1.39	Mill 1.5" and 1.5" S9.5C	$245,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	8	053-Lee	Resurfacing	US 1	US 15 SOUTH	SR 1181	1.50	Mill 1.5" and 1.5" S9.5C	$235,000
2028	8	053-Lee	Resurfacing	US 1	US 421 Bus	US 421 + .813 miles	1.70	Mill 1.5" and 1.5" S9.5C	$543,000
2028	8	053-Lee	Resurfacing	US 1 S	SR 1466 + 1.629 miles	SR 1426	1.75	Mill 1.5" and 1.5" S9.5C	$647,500
2028	8	053-Lee	Resurfacing	US 15	SR 1471+.504 MILES	US 1 SOUTH	0.28	Mill 1.5" and 1.5" S9.5C	$55,350
2028	8	053-Lee	Preservation	SR 1179	SR 1176	DEAD END	1.36	Crack Seal	$13,750
2028	8	053-Lee	Preservation	SR 1180	US 1	SR 1179	1.09	Seal - Double	$41,400
2028	8	053-Lee	Preservation	SR 1181	PVMT GHG	SR 1182	0.97	Seal - Double	$41,000
2028	8	053-Lee	Preservation	SR 1249	SR 1248	SR 1248	0.52	Seal - Double	$10,750
2028	8	053-Lee	Preservation	SR 1264	SR 1157	SR 1265	0.17	Seal - Double	$6,500
2028	8	053-Lee	Preservation	SR 1278	SR 1197	DEAD END	0.11	Seal - Double	$4,000
2028	8	053-Lee	Preservation	SR 1289	SR 1199	CUL DE SAC	0.40	Seal - Double	$15,200
2028	8	053-Lee	Preservation	SR 1301	SR 1300	SR 1303	0.96	Seal - Double	$36,500
2028	8	053-Lee	Preservation	SR 1302	US 1	SR 1300	0.31	Seal - Double	$12,250
2028	8	053-Lee	Preservation	SR 1318	SR 1335	SR 1319	3.59	Seal - Double	$186,680
2028	8	053-Lee	Preservation	SR 1371	SR 1370	DEAD END	0.10	Crack Seal and Double Seal	$4,500
2028	8	053-Lee	Preservation	SR 1426	SR 1466	SR 1423	1.90	Seal - Double	$57,000
2028	8	053-Lee	Preservation	SR 1427	SR 1466	DEAD END	0.42	Seal - Double	$11,000
2028	8	053-Lee	Preservation	SR 1427	SR 1466	DEAD END	0.50	Seal - Double	$18,975
2028	8	053-Lee	Preservation	SR 1456	SR 1415	SR 1415	0.26	Seal - Single	$8,000
2028	8	053-Lee	Preservation	SR 1468	SR 1420	DEAD END	0.16	Seal - Double	$6,250
2028	8	062-Montgomery	Resurfacing	NC 109	SR 1633	SR 1546	1.45	1.5" S9.5B	$350,000
2028	8	062-Montgomery	Resurfacing	NC 134	SR 1377	SR 1311	3.29	1.5" S9.5B	$600,000
2028	8	062-Montgomery	Resurfacing	NC 211	Moore Co	US 220 ALT	2.12	1.5" S9.5B	$771,300
2028	8	062-Montgomery	Resurfacing	NC 73	NC 731	NC 731 + 2 miles	2.00	1.5" S9.5B	$450,000
2028	8	062-Montgomery	Resurfacing	SR 1103	NC 731	SR 1103	0.16	1.5" S9.5B	$30,000
2028	8	062-Montgomery	Resurfacing	SR 1110	SR 1103	SR 1188	0.78	1.5" S9.5B	$146,000
2028	8	062-Montgomery	Resurfacing	SR 1403	SR 1333	NC-24	0.31	1.5" S9.5B	$60,088
2028	8	062-Montgomery	Resurfacing	SR 1519	Bridge	SR 1636	0.36	1.5" S9.5B	$67,000
2028	8	062-Montgomery	Resurfacing	SR 1519	Bridge	Bridge	2.20	1.5" S9.5B	$459,000
2028	8	062-Montgomery	Resurfacing	SR 1647	SR 1554 + 1.123 mi	NC 27 South	0.25	1.5" S9.5B	$68,000
2028	8	062-Montgomery	Preservation	NC 211	Moore County Line	US 220A	2.12	Crack Seal	$90,000
2028	8	062-Montgomery	Preservation	NC 24	End of Island	SR 1577	0.41	Crack Seal	$18,000
2028	8	062-Montgomery	Preservation	SR 1118	SR 1116	NC 73	0.54	Seal - Double	$24,000
2028	8	062-Montgomery	Preservation	SR 1145	SR 1139	Dead End	1.10	Seal - Double and Fog Seal	$47,000
2028	8	062-Montgomery	Preservation	SR 1147	SR 1146	NC 109	1.86	Seal - Double	$80,000
2028	8	062-Montgomery	Preservation	SR 1152	SR 1150	End of Maint.	0.65	Seal - Double	$28,000
2028	8	062-Montgomery	Preservation	SR 1212	SR 1197	DEAD END	0.09	Seal - Double	$3,245
2028	8	062-Montgomery	Preservation	SR 1309	SR 1311	SR 1310	1.85	Seal - Double	$72,000
2028	8	062-Montgomery	Preservation	SR 1310	SR 1306	SR 1307	1.51	Seal - Double	$54,000
2028	8	062-Montgomery	Preservation	SR 1348	SR 1349	US 220 ALT	0.38	Seal - Double	$13,000
2028	8	062-Montgomery	Preservation	SR 1570	SR 1568	SR 1005	1.39	Seal - Double	$62,000
2028	8	062-Montgomery	Preservation	SR 1578	SR 1636	SR 1519	0.33	Seal - Double	$13,000
2028	8	063-Moore	Resurfacing	NC 211	US 15	NC 73	7.60	Mill 1.5" and 1.5" S9.5B	$1,830,000
2028	8	063-Moore	Resurfacing	NC 22	NC 2 WEST	SR 1853 +.623	4.63	Crack Seal and 1.5" S9.5B	$750,000
2028	8	063-Moore	Resurfacing	SR 1002	BEG C&G	SR 1434	1.06	1.5" S9.5B	$159,000
2028	8	063-Moore	Resurfacing	SR 1002	BEG C&G	BEG C&G	0.02	1.5" S9.5B	$3,500
2028	8	063-Moore	Resurfacing	SR 1002	NC 705	BEG C&G	0.31	1.5" S9.5B	$63,000
2028	8	063-Moore	Resurfacing	SR 1002	SR 1450	SR 1498	7.45	1.5" S9.5B	$1,075,250
2028	8	063-Moore	Resurfacing	SR 1002	SR 1498	SR 1275	1.65	1.5" S9.5B	$236,000
2028	8	063-Moore	Resurfacing	SR 1002	SR 1434	SR 1450	1.47	1.5" S9.5B	$214,000
2028	8	063-Moore	Resurfacing	SR 1003	SR 1421	RAND. CO	1.30	1.5" S9.5B	$186,000
2028	8	063-Moore	Resurfacing	SR 1102	MP 5.00	BRIDGE	3.97	1.5" S9.5B	$486,200
2028	8	063-Moore	Resurfacing	SR 1103	SR 1112	PVMT CHG	0.97	1.5" S9.5B	$147,000
2028	8	063-Moore	Resurfacing	SR 1103	PVMT CHG	SR 1112	0.74	1.5" S9.5B	$100,000
2028	8	063-Moore	Resurfacing	SR 1129	SR 1136	SR 1130	1.40	1.5" S9.5A	$197,810
2028	8	063-Moore	Resurfacing	SR 1210	SR 1290	SR 1240	1.46	1.5" S9.5B	$198,000
2028	8	063-Moore	Resurfacing	SR 1229	SR 1238	NC 73	1.17	1.5" S9.5B	$180,000
2028	8	063-Moore	Resurfacing	SR 1440	NC 705	SR 1439	1.00	1.5" S9.5B	$135,000
2028	8	063-Moore	Resurfacing	SR 1456	SR 1419	SR 1457	1.44	1.5" S9.5B	$202,520

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	8	063-Moore	Resurfacing	SR 1456	SR 1461	SR 1419	0.97	1.5" S9.5B	$130,000
2028	8	063-Moore	Resurfacing	SR 1456	SR 1457	SR 1003	0.81	1.5" S9.5B	$110,000
2028	8	063-Moore	Resurfacing	SR 1644	SR 1643	MP 0.36	2.26	1.5" S9.5B	$305,000
2028	8	063-Moore	Resurfacing	US 15	SR 1203	SR 1205 +.23	3.74	Mill 1.5" and 1.5" S9.5B	$622,950
2028	8	063-Moore	Preservation	SR 1130	SR 1129	DEAD END	0.50	Seal - Double	$19,000
2028	8	063-Moore	Preservation	SR 1131	NC 73	DEAD END	1.06	Seal - Double	$44,520
2028	8	063-Moore	Preservation	SR 1136	RR	SR 1135	2.12	Seal - Double	$72,000
2028	8	063-Moore	Preservation	SR 1138	NC 211	SR 1139	2.00	Seal - Double	$42,750
2028	8	063-Moore	Preservation	SR 1146	NC 211	SR 1143	1.15	Seal - Double	$42,500
2028	8	063-Moore	Preservation	SR 1258	SR 1240	DEAD END	0.20	Seal - Double	$7,500
2028	8	063-Moore	Preservation	SR 1410	NC 705	SR 1411	3.80	Seal - Double	$67,000
2028	8	063-Moore	Preservation	SR 1516	SR 1470	DEAD END	0.15	Seal - Double	$5,750
2028	8	063-Moore	Preservation	SR 1600	SR 1614	SR 1604	2.75	Seal - Double	$92,500
2028	8	063-Moore	Preservation	SR 1653	SR 1651	SR 1805	1.88	Seal - Double	$62,500
2028	8	063-Moore	Preservation	SR 1655	SR 1654	DEAD END	0.40	Seal - Double	$15,250
2028	8	063-Moore	Preservation	SR 1660	SR 1625	SR 1651	3.10	Crack Seal	$32,250
2028	8	063-Moore	Preservation	SR 1661	SR 1663	SR 1814	4.20	Seal - Double	$120,859
2028	8	063-Moore	Preservation	SR 1827	MP 1.30	SR 1828	2.66	Seal - Double	$97,500
2028	8	063-Moore	Preservation	SR 1828	SR 1805	SR 1827	0.40	Seal - Double	$15,250
2028	8	063-Moore	Preservation	SR 1897	NC 22	PVMT CHG	0.83	Seal - Double	$32,757
2028	8	063-Moore	Preservation	SR 2000	SR 2111	SR 2001	1.00	Seal - Double	$35,000
2028	8	063-Moore	Preservation	SR 2002	SR 2005	SR 2004	2.90	Crack Seal	$35,450
2028	8	063-Moore	Preservation	SR 2005	SR 2007	SR 1947	1.48	Crack Seal	$15,250
2028	8	063-Moore	Preservation	SR 2005	SR 1825	SR 2010	6.35	Seal - Double	$275,000
2028	8	063-Moore	Preservation	SR 2007	SR 2005	SR 1947	2.02	Crack Seal	$23,000
2028	8	063-Moore	Preservation	SR 2009	SR 2005	SR 2010	0.60	Crack Seal	$6,580
2028	8	063-Moore	Preservation	SR 2010	SR 2005	SR 2009	2.02	Crack Seal	$25,250
2028	8	063-Moore	Preservation	SR 2024	SR 2175	SR 2175 +1.3	2.10	Seal - Double	$54,750
2028	8	063-Moore	Preservation	SR 2033	SR 2080	SR 2035	3.13	Seal - Double	$120,500
2028	8	063-Moore	Preservation	SR 2063	NC 211	PVMT CHG	1.42	Crack Seal	$17,500
2028	8	063-Moore	Preservation	SR 2086	NC 690	DEAD END	0.58	Seal - Double	$21,000
2028	8	076-Randolph	Resurfacing	NC 134	Montgomery County Line	SR 1138 Dawson Miller Rd.	7.95	Full Depth Patching and 1.5" S9.5C	$1,650,000
2028	8	076-Randolph	Resurfacing	NC 159	MM 4.24	US 64	3.09	Full Depth Patching and 1.5" S9.5C	$650,000
2028	8	076-Randolph	Resurfacing	NC 62	Davidson County Line	Guilford County Line	6.41	Full Depth Patching and 1.5" S9.5C	$1,365,000
2028	8	076-Randolph	Resurfacing	SR 1002	SR 2907 Little Beane Store Rd.	NC 705	5.59	Full Depth Patching and 1.5" S9.5B	$1,000,000
2028	8	076-Randolph	Resurfacing	SR 1002	SR 2877 Howard Mill Rd.	SR 1003 Erect Rd.	6.77	Full Depth Patching and 1.5" S9.5B	$1,150,000
2028	8	076-Randolph	Resurfacing	SR 1006	CHATHAM COUNTY	GUILFORD COUNTY	10.00	Full Depth Patching and 1.5" S9.5B	$1,800,000
2028	8	076-Randolph	Resurfacing	SR 1107	SR 1105 Burney Mill Rd.	SR 1193 Old NC 49	11.87	Full Depth Patching and 1.5" S9.5B	$2,000,000
2028	8	076-Randolph	Resurfacing	SR 2101	GUILFORD COUNTY	SR 1007 RANDLEMAN RD.	2.47	Full Depth Patching and 1.5" S9.5B	$469,300
2028	8	076-Randolph	Resurfacing	SR 2102	GUILFORD COUNTY	SR 2101 BRANSON MILL RD.	1.47	Full Depth Patching and 1.5" S9.5B	$265,000
2028	8	076-Randolph	Resurfacing	SR 2138	SR 2106	SR 2136	0.95	1.25" SF9.5A	$165,000
2028	8	076-Randolph	Resurfacing	SR 2230	SR 2106 RACINE RD.	END OF MAINTENANCE	0.59	Full Depth Patching and 1.5" S9.5B	$112,100
2028	8	076-Randolph	Resurfacing	SR 2394	SR 2230 BERRY LN.	END OF MAINTENANCE	0.63	Full Depth Patching and 1.5" S9.5B	$113,000
2028	8	076-Randolph	Resurfacing	SR 2402	NC-22 N	SR 2402 OLD RED CROSS RD.	1.05	Full Depth Patching and 1.5" S9.5B	$199,500
2028	8	076-Randolph	Resurfacing	SR 2407	GUILFORD COUNTY	US HWY 421	0.40	Full Depth Patching and 1.5" S9.5B	$76,000
2028	8	076-Randolph	Resurfacing	SR 2415	SR 1006 OLD 421 RD.	GUILFORD COUNTY	0.82	Full Depth Patching and 1.5" S9.5B	$155,800
2028	8	076-Randolph	Resurfacing	SR 2424	SR 2424 SILK HOPE RD.	SR 2464 PIKE FARM RD.	1.67	Full Depth Patching and 1.5" S9.5B	$300,000
2028	8	076-Randolph	Resurfacing	SR 2470	SR 2469 S. MAIN ST.	NC HWY 49	2.72	Full Depth Patching and 1.5" S9.5B	$489,000
2028	8	076-Randolph	Resurfacing	SR 2641	CHATHAM COUNTY	NC HWY 22	3.91	Full Depth Patching and 1.5" S9.5B	$742,900
2028	8	076-Randolph	Resurfacing	SR 2863	NC 705	SR 1002 Fork Creek Mill Rd.	3.77	Full Depth Patching and 1.5" S9.5B	$700,000
2028	8	076-Randolph	Resurfacing	SR 2864	SR 2866 Brower Mill Rd.	SR 2863 Union Grove Ch. Rd.	1.80	Full Depth Patching and 1.5" S9.5B	$325,000
2028	8	076-Randolph	Resurfacing	SR 2868	SR 2869 Meadowbranch Rd.	Dead End	0.64	Full Depth Patching and 1.5" S9.5B	$145,000
2028	8	076-Randolph	Resurfacing	SR 2869	SR 2866 Brower Mill Rd.	SR 2863 Union Grove Ch. Rd.	2.63	Full Depth Patching and 1.5" S9.5B	$500,000
2028	8	076-Randolph	Resurfacing	SR 2870	SR 1003 Erect Rd.	SR 2863 Union Grove Ch. Rd.	2.95	Full Depth Patching and 1.5" S9.5B	$525,000
2028	8	076-Randolph	Resurfacing	SR 2874	SR 2871 Riverside Rd.	Dead End	1.19	Full Depth Patching and 1.5" S9.5B	$215,000
2028	8	076-Randolph	Resurfacing	SR 2875	SR 1002 Bennett Rd.	SR 2874 Waddells Ferry Rd.	1.21	Full Depth Patching and 1.5" S9.5B	$225,000
2028	8	076-Randolph	Preservation	SR 2280	SR 2101 Branson Mill Rd.	Dead End	0.37	Full Depth Patching and Double Seal and Fog Seal	$31,000
2028	8	076-Randolph	Preservation	SR 2281	SR 2280 Farley Dr.	SR 2280 Farley Dr.	0.61	Full Depth Patching and Double Seal and Fog Seal	$45,000
2028	8	076-Randolph	Preservation	SR 2282	SR 2101 Branson Mill Rd.	SR 2281 Georgia Dr.	0.21	Full Depth Patching and Double Seal and Fog Seal	$20,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	8	076-Randolph	Preservation	SR 2342	SR 2101 Branson Mill Rd.	SR 2101 Branson Mill Rd.	0.48	Full Depth Patching and Double Seal and Fog Seal	$38,000
2028	8	076-Randolph	Preservation	SR 2350	SR 2101 Branson Mill Rd.	SR 2101 Branson Mill Rd.	0.68	Full Depth Patching and Double Seal and Fog Seal	$52,500
2028	8	076-Randolph	Preservation	SR 2387	SR 2350 Kerr Dr.	Dead End	0.10	Full Depth Patching and Double Seal and Fog Seal	$8,500
2028	8	076-Randolph	Preservation	SR 2445	NC HWY 22 N	SR 2261 OLD LIBERTY RD.	2.29	Full Depth Patching and Double Seal	$140,000
2028	8	076-Randolph	Preservation	SR 2453	SR 2442 RAMSEUR JULIAN RD.	NC HWY 22 N	3.46	Full Depth Patching and Double Seal	$225,000
2028	8	076-Randolph	Preservation	SR 2479	SR 2191 PATTERSON GROVE RD.	NC 49	3.81	Full Depth Patching and Double Seal	$250,000
2028	8	076-Randolph	Preservation	SR 2634	CHATHAM COUNTY	NC HWY 22	7.01	Full Depth Patching and Double Seal	$450,000
2028	8	076-Randolph	Preservation	SR 2643	NC HWY 22	SR 2645 LEWIS BROWN RD.	1.66	Full Depth Patching and Double Seal	$110,000
2028	8	076-Randolph	Preservation	SR 2873	SR 1003 Erect Rd.	SR 1002 Bennett Rd.	3.21	Full Depth Patching and Double Seal	$210,000
2028	8	076-Randolph	Preservation	SR 2905	SR 2903 Osborn Mill Rd.	SR 2909 Woodfern Rd.	0.78	Full Depth Patching and Double Seal	$75,000
2028	8	076-Randolph	Preservation	SR 2909	SR 2845 Old NC Hwy. 13	SR 2903 Osborn Mill Rd.	2.36	Full Depth Patching and Double Seal	$160,000
2028	8	077-Richmond	Resurfacing	74 BYP E	SR1103 overpass	SR 1900 overpass	4.30	Mill 1.5" and 1.5" S9.5C	$1,500,000
2028	8	077-Richmond	Resurfacing	74 BYP W	SR1900 overpass	OP@SR1103	4.20	Mill 1.5" and 1.5" S9.5C	$1,500,000
2028	8	077-Richmond	Resurfacing	EB off ramp	74 byp	US 1	0.34	Mill 1.5" and 1.5" S9.5B	$58,000
2028	8	077-Richmond	Resurfacing	EB on loop	US 1	74 byp	0.22	Mill 1.5" and 1.5" S9.5B	$43,000
2028	8	077-Richmond	Resurfacing	EB on Ramp	US 1	74 byp	0.26	Mill 1.5" and 1.5" S9.5B	$48,000
2028	8	077-Richmond	Resurfacing	SR 1005	SR 1146	SR 1148	1.61	1.5" S9.5B	$228,000
2028	8	077-Richmond	Resurfacing	SR 1108	SR 1966	SR 1103	3.40	1.5" S9.5B	$493,000
2028	8	077-Richmond	Resurfacing	SR 1124	US 74 Bus	US 74 bus	3.24	1.5" S9.5B	$470,000
2028	8	077-Richmond	Resurfacing	SR 1556	US 1	SR 1601	0.40	1.5" S9.5B	$58,000
2028	8	077-Richmond	Resurfacing	SR 1960	SR 1966	SR 1903	0.36	1.5" S9.5B	$53,000
2028	8	077-Richmond	Resurfacing	SR 1992	SR 1108	SR 2038 + 1.426	2.52	1.5" S9.5B	$360,000
2028	8	077-Richmond	Resurfacing	SR1153	SR 1005	SR1005+0.83 MILES	0.83	1.5" S9.5B	$119,000
2028	8	077-Richmond	Resurfacing	WB off ramp	74 byp	US 1	0.26	Mill 1.5" and 1.5" S9.5B	$45,000
2028	8	077-Richmond	Resurfacing	WB on ramp	US 1	74 byp	0.17	Mill 1.5" and 1.5" S9.5B	$30,000
2028	8	077-Richmond	Preservation	SR 1103	SR 1124	US 1	7.90	Seal - Double	$331,800
2028	8	077-Richmond	Preservation	SR 1151	NC 73	SR 1148	2.39	Seal - Double	$100,400
2028	8	077-Richmond	Preservation	SR 1161	NC 73	SR 1159	0.94	Seal - Double	$25,000
2028	8	077-Richmond	Preservation	SR 1161	NC 73	SR 1159	0.94	Seal - Double	$39,500
2028	8	077-Richmond	Preservation	SR 1241	SR 1108	SR 1966	1.75	Seal - Double	$74,000
2028	8	077-Richmond	Preservation	SR 1242	SR 1994	dead end	0.50	Seal - Double	$21,000
2028	8	077-Richmond	Preservation	SR 1316	NC 73	SR 1310	0.82	Seal - Double	$22,000
2028	8	077-Richmond	Preservation	SR 1344	SR 1343	US 220	1.60	Seal - Double	$68,000
2028	8	077-Richmond	Preservation	SR 1478	SR 1475	SR 1489	1.00	Seal - Double	$42,000
2028	8	077-Richmond	Preservation	SR 1523	US 220	End PVMT	0.56	Seal - Double	$23,600
2028	8	077-Richmond	Preservation	SR 1525	US 220	dead end	0.46	Seal - Double	$19,320
2028	8	083-Scotland	Resurfacing	NC144	SR1416	US401	2.55	1.5" S9.5B	$403,500
2028	8	083-Scotland	Resurfacing	SR1108	US15	US15 BUS	1.00	1.5" S9.5B	$177,000
2028	8	083-Scotland	Resurfacing	SR1108	SR1105	US15	0.74	Mill 1.5" and 1.5" S9.5B	$197,300
2028	8	083-Scotland	Resurfacing	SR1407	SR1435	ROBESON CO	0.90	1.5" S9.5B	$155,100
2028	8	083-Scotland	Resurfacing	SR1435	SR1407	SR1434	1.56	1.5" S9.5B	$218,635
2028	8	083-Scotland	Preservation	SR1145	US74	NC381	4.32	Seal - Double	$172,957
2028	8	083-Scotland	Preservation	SR1173	SR1174	DEAD END	0.13	Crack Seal	$1,260
2028	8	083-Scotland	Preservation	SR1174	US15/401	US15/401 BUS	0.27	Crack Seal	$14,660
2028	8	083-Scotland	Preservation	SR1176	SR1174	DEAD END	0.09	Crack Seal	$900
2028	8	083-Scotland	Preservation	SR1328	SR1334	END PAVT	4.35	Seal - Double	$182,700
2028	8	083-Scotland	Preservation	SR1329	SR1324	SR1408	0.91	Seal - Double	$38,136
2028	8	083-Scotland	Preservation	SR1334	SR1335	SR1324	0.96	Seal - Double	$40,362
2028	8	083-Scotland	Preservation	SR1413	SR1412	SR1400	2.36	Crack Seal	$23,600
2028	8	083-Scotland	Preservation	SR1434	SR1407	SR1435	3.20	Seal - Double	$144,442
2028	8	083-Scotland	Preservation	SR1614	SR1615	SR1670	1.25	Crack Seal	$12,500
2028	8	083-Scotland	Preservation	SR1616	ROBESON CO	SR1612	0.66	Seal - Double	$27,888
2028	8	083-Scotland	Preservation	SR1684	SR1622	SR1695	0.08	Seal - Double and Fog Seal	$3,950
2028	8	083-Scotland	Preservation	SR1685	SR1622	SR1695	0.14	Seal - Double and Fog Seal	$6,950
2028	8	083-Scotland	Preservation	SR1694	SR1622	SR1695	0.09	Seal - Double and Fog Seal	$4,350
2028	8	083-Scotland	Preservation	SR1695	SR1685	SR1684	0.39	Seal - Double and Fog Seal	$19,250
2028	9	029-Davidson	Resurfacing	NC 150	SR 1155	SR 1231	11.60	Mill 1.5" and 1.5" S9.5C	$4,083,904
2028	9	029-Davidson	Resurfacing	SR 1243	NC 8	SR 2205	2.04	Mill 1.5" and 1.5" S9.5C	$717,728
2028	9	029-Davidson	Resurfacing	SR 1508	SR 2932	FORSYTH CO	3.53	Mill 1.5" and 1.5" S9.5B	$1,397,880

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	9	029-Davidson	Resurfacing	SR 1716	SR 1711	SR 1800	3.76	#67 Mat Seal and 1.5" S9.5B	$1,102,933
2028	9	029-Davidson	Resurfacing	SR 1735	SR 1741	FORSYTH CO	3.57	1.5" S9.5C	$804,250
2028	9	029-Davidson	Resurfacing	SR 1737	SR 1735	FORSYTH CO	0.27	1.5" S9.5C	$60,826
2028	9	029-Davidson	Resurfacing	SR 1738	SR 1735	HIGH POINT CL	1.11	1.5" S9.5C	$249,385
2028	9	029-Davidson	Resurfacing	SR 1739	SR 1755	EOM	1.21	1.5" S9.5B	$268,858
2028	9	029-Davidson	Resurfacing	SR 1740	SR 1739	SR 1755	0.14	1.5" S9.5B	$24,969
2028	9	029-Davidson	Resurfacing	SR 1752	SR 1751	SR 1700	1.94	1.5" S9.5C	$363,264
2028	9	029-Davidson	Resurfacing	SR 1753	NC 109	SR 1752	0.50	#67 Mat Seal and 1.5" S9.5B	$146,960
2028	9	029-Davidson	Resurfacing	SR 1892	SR 1735	HIGH POINT CL	1.00	1.5" S9.5C	$225,280
2028	9	029-Davidson	Resurfacing	SR 1913	SR 1739	SR 1914	0.20	1.5" S9.5B	$39,727
2028	9	029-Davidson	Resurfacing	SR 1914	EOM	EOM	0.17	1.5" S9.5B	$34,109
2028	9	029-Davidson	Resurfacing	SR 1915	SR 1914	EOM	0.07	1.5" S9.5B	$13,042
2028	9	029-Davidson	Resurfacing	SR 1960	SR 1739	EOM	0.10	1.5" S9.5B	$22,293
2028	9	029-Davidson	Resurfacing	SR 2206	SR 1243	SR 2205	0.23	1.5" S9.5B	$46,147
2028	9	029-Davidson	Resurfacing	SR 2219	SR 2205	SR 2783	0.99	1.5" S9.5B	$264,845
2028	9	029-Davidson	Resurfacing	SR 2783	SR 2010	SR 2219	1.16	1.5" S9.5B	$310,323
2028	9	029-Davidson	Resurfacing	SR 3159	SR 1147	NC 47	2.46	Mill 1.5" and 1.5" S9.5C	$866,976
2028	9	029-Davidson	Preservation	NC 47	I-285	NC 8	5.47	Crack Seal	$38,516
2028	9	029-Davidson	Preservation	SR 1105	SR 1396	SR 1106	0.76	Seal - Double and Fog Seal	$71,339
2028	9	029-Davidson	Preservation	SR 1106	SR 1105	SR 3108	0.80	Seal - Double and Fog Seal	$75,093
2028	9	029-Davidson	Preservation	SR 1136	SR 1265	EOM	0.90	Seal - Double and Fog Seal	$84,480
2028	9	029-Davidson	Preservation	SR 1151	SR 1147	NC 150	1.64	Seal - Double and Fog Seal	$153,941
2028	9	029-Davidson	Preservation	SR 1153	SR 1147	EOM	0.20	Seal - Double and Fog Seal	$16,896
2028	9	029-Davidson	Preservation	SR 1155	NC 150	NC 150	4.20	Crack Seal	$295,668
2028	9	029-Davidson	Preservation	SR 1158	NC 150	NC 150	2.38	Seal - Double and Fog Seal	$201,062
2028	9	029-Davidson	Preservation	SR 1202	SR 1192	EOM	0.29	Seal - Double and Fog Seal	$27,221
2028	9	029-Davidson	Preservation	SR 1208	SR 1205	SR 1213	1.25	Seal - Double and Fog Seal	$93,116
2028	9	029-Davidson	Preservation	SR 1211	SR 1208	EOM	0.31	Seal - Double and Fog Seal	$29,193
2028	9	029-Davidson	Preservation	SR 1296	City Limit	EOM	0.30	Seal - Double and Fog Seal	$28,160
2028	9	029-Davidson	Preservation	SR 2286	SR 2287	SR 2287	1.10	Seal - Double and Fog Seal	$93,181
2028	9	029-Davidson	Preservation	SR 2287	NC 8	SR 2288	0.93	Seal - Double and Fog Seal	$78,313
2028	9	029-Davidson	Preservation	SR 2288	SR 2287	EOM	0.24	Seal - Double and Fog Seal	$20,275
2028	9	029-Davidson	Preservation	SR 2472	SR 2287	EOM	0.12	Seal - Double and Fog Seal	$10,138
2028	9	029-Davidson	Preservation	SR 2477	SR 2286	EOM	0.60	Seal - Double and Fog Seal	$56,320
2028	9	029-Davidson	Preservation	SR 2478	SR 2477	EOM	0.25	Seal - Double and Fog Seal	$23,467
2028	9	029-Davidson	Preservation	SR 3342	SR 2287	EOM	0.15	Seal - Double and Fog Seal	$14,080
2028	9	029-Davidson	Preservation	SR 3350	NC 8	EOM	2.46	Seal - Double and Fog Seal	$230,912
2028	9	030-Davie	Resurfacing	NC 801	US 64	SR 1653	5.96	Mill 1.5" and 1.5" S9.5C	$1,921,480
2028	9	030-Davie	Resurfacing	NC 901	US 64	IREDELL CO	0.85	Mill 1.5" and 1.5" S9.5B	$228,195
2028	9	030-Davie	Resurfacing	SR 1400	US 158	SR 1461	1.27	1.5" S9.5B	$446,336
2028	9	030-Davie	Resurfacing	US 601	SR 1800	US 64	0.90	Mill 1.5" and 1.5" S9.5C	$316,800
2028	9	030-Davie	Resurfacing	US 601	SR 1801	SR 1800	1.24	Mill 1.5" and 1.5" S9.5C	$655,776
2028	9	030-Davie	Resurfacing	US 601	NC 801	SR 1801	2.44	Mill 1.5" and 1.5" S9.5C	$859,936
2028	9	030-Davie	Preservation	SR 1123	SR 1121	EOM	0.50	Seal - Double and Fog Seal	$47,309
2028	9	030-Davie	Preservation	SR 1135	US 601	US 601	0.87	Seal - Double and Fog Seal	$73,582
2028	9	030-Davie	Preservation	SR 1136	SR 1135	EOM	2.74	Seal - Fog	$40,172
2028	9	030-Davie	Preservation	SR 1142	SR 1143	SR 1139	0.32	Seal - Double and Fog Seal	$29,850
2028	9	030-Davie	Preservation	SR 1142	ROWAN CO	SR 1143	2.22	Seal - Double and Fog Seal	$208,290
2028	9	030-Davie	Preservation	SR 1143	SR 1142	SR 1147	1.91	Seal - Double and Fog Seal	$179,098
2028	9	030-Davie	Preservation	SR 1193	SR 1136	EOM	0.27	Seal - Double and Fog Seal	$25,062
2028	9	030-Davie	Preservation	SR 1196	SR 1136	EOM	0.12	Seal - Double and Fog Seal	$11,170
2028	9	030-Davie	Preservation	SR 1321	SR1324	SR 1320	2.55	Seal - Double and Fog Seal	$239,172
2028	9	030-Davie	Preservation	SR 1721	NC 801	EOM	0.43	1.25" S4.75A	$62,468
2028	9	030-Davie	Preservation	SR 1723	SR 1721	EOM	0.34	1.25" S4.75A	$46,851
2028	9	030-Davie	Preservation	SR 1727	EOM	EOM	0.23	1.25" S4.75A	$31,234
2028	9	030-Davie	Preservation	US 64	IREDELL CO	I-40	7.13	Crack Seal	$44,967
2028	9	034-Forsyth	Resurfacing	NC 65	US 52	NC 66	1.97	Mill 1.5" and 1.5" S9.5C	$1,040,160
2028	9	034-Forsyth	Resurfacing	SR 1156	SR 1001	SR 1103	2.31	Mill 1.5" and 1.5" S9.5C	$809,600
2028	9	034-Forsyth	Resurfacing	SR 1173	SR 1711	Winding Oaks Trl (N/S)	4.57	1.5" S9.5B	$1,120,686

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	9	034-Forsyth	Resurfacing	SR 1631	NC 65	SR 1611	2.94	1.5" S9.5B	$720,966
2028	9	034-Forsyth	Resurfacing	SR 1639	SR 1807	SR 1636	1.49	1.5" S9.5B	$365,388
2028	9	034-Forsyth	Resurfacing	SR 1763	Reynold Blvd. (N/S)	SR 1528	1.32	Mill 1.5" and 1.5" S9.5C	$1,161,600
2028	9	034-Forsyth	Resurfacing	SR 1977	US 311	NC 65	6.08	1.5" S9.5B	$1,490,978
2028	9	034-Forsyth	Resurfacing	SR 2632	NC 66	SR 2643	2.32	Mill 1.5" and 1.5" S9.5C	$816,640
2028	9	034-Forsyth	Resurfacing	SR 2640	NC 66	SR 2643	1.27	1.5" S9.5B	$339,215
2028	9	034-Forsyth	Resurfacing	SR 4315	SR 1003	US 421	4.79	Mill 1.5" and 1.5" S9.5C	$1,827,731
2028	9	034-Forsyth	Resurfacing	SR 4463	SR 1528	NC 67	0.39	Mill 1.5" and 1.5" S9.5B	$264,000
2028	9	034-Forsyth	Preservation	SR 1442	SR 1525	SR 1443	1.69	Seal - Double and Fog Seal	$158,635
2028	9	034-Forsyth	Preservation	SR 1443	SR 1465	SR 1465	2.89	Seal - Double and Fog Seal	$298,092
2028	9	034-Forsyth	Preservation	SR 1444	SR 1443	EOM	0.79	Seal - Double and Fog Seal	$66,908
2028	9	034-Forsyth	Preservation	SR 1445	SR 1443	EOM	0.27	Seal - Double and Fog Seal	$22,810
2028	9	034-Forsyth	Preservation	SR 1446	SR 1465	EOM	0.50	Seal - Double and Fog Seal	$42,493
2028	9	034-Forsyth	Preservation	SR 1466	SR 1465	EOM	0.49	Seal - Double and Fog Seal	$33,840
2028	9	034-Forsyth	Preservation	SR 1763	SR 1528	SR 4001	1.36	Crack Seal	$19,149
2028	9	034-Forsyth	Preservation	SR 1849	SR 1444	EOM	0.16	Seal - Double and Fog Seal	$14,549
2028	9	034-Forsyth	Preservation	SR 2705	NC 109	EOM	1.59	Crack Seal	$8,938
2028	9	034-Forsyth	Preservation	SR 3290	SR 1455	EOM	0.29	Seal - Double and Fog Seal	$21,965
2028	9	034-Forsyth	Preservation	SR 3291	SR 1466	EOM	0.12	Seal - Double and Fog Seal	$8,771
2028	9	034-Forsyth	Preservation	SR 3391	SR 1443	EOM	0.55	Seal - Double and Fog Seal	$51,439
2028	9	034-Forsyth	Preservation	SR 4103	SR 1443	EOM	0.33	Seal - Double and Fog Seal	$27,456
2028	9	034-Forsyth	Preservation	SR 4114	SR 4113	EOM	0.05	Seal - Double and Fog Seal	$4,042
2028	9	080-Rowan	Resurfacing	NC 150	SR 1825	US 29	1.60	Mill 1.5" and 1.5" S9.5B	$1,149,867
2028	9	080-Rowan	Resurfacing	SR 1001	US 70	IEDELL CO	4.69	1.5" S9.5B	$1,150,113
2028	9	080-Rowan	Resurfacing	SR 1007	US 601/I-85 Bridge	SR1004	1.73	1.5" S9.5B	$906,335
2028	9	080-Rowan	Resurfacing	SR 1221	SR 2352	SR 2338	2.49	1.5" S9.5C	$490,237
2028	9	080-Rowan	Resurfacing	SR 1221	SR 2350	SR 2352	1.08	1.5" S9.5C	$223,440
2028	9	080-Rowan	Resurfacing	SR 1743	US 70	NC 801	3.35	#67 Mat Seal and 1.5" S9.5B	$1,079,643
2028	9	080-Rowan	Resurfacing	SR 1911	US 601	SR 1915	2.76	1.5" S9.5B	$676,826
2028	9	080-Rowan	Resurfacing	SR 1957	SR 1847	SR 1972	2.07	1.5" S9.5B	$508,600
2028	9	080-Rowan	Resurfacing	SR 1962	SR 1847	US 70	0.29	1.5" S9.5B	$70,380
2028	9	080-Rowan	Resurfacing	SR 2351	US 52	SR 2350	0.11	1.5" S9.5B	$21,468
2028	9	080-Rowan	Resurfacing	SR 2356	SR 1221	SR 1004	4.52	1.5" S9.5C	$847,804
2028	9	080-Rowan	Resurfacing	US 70	Iredell County Line	SR 1962	3.90	Mill 1.5" and 1.5" S9.5B	$1,544,400
2028	9	080-Rowan	Resurfacing	US 70	SR 1962	Iredell County Liine	3.91	Mill 1.5" and 1.5" S9.5B	$1,548,360
2028	9	080-Rowan	Preservation	NC 152	SR 1227	N FRANKLIN ST	0.58	Crack Seal	$1,388
2028	9	080-Rowan	Preservation	NC 152	IREDELL CO	SR 2811	5.88	Crack Seal	$14,074
2028	9	080-Rowan	Preservation	NC 152	N FRANKLIN ST	US 29	0.61	Crack Seal	$1,794
2028	9	080-Rowan	Preservation	NC 153	NC 152	END C&G	2.50	Crack Seal	$6,233
2028	9	080-Rowan	Preservation	SR 1129	SR 1124	EOM	0.29	Seal - Double and Fog Seal	$24,339
2028	9	080-Rowan	Preservation	SR 1130	SR 1129	CABARUS CO	0.16	Seal - Double and Fog Seal	$13,268
2028	9	080-Rowan	Preservation	SR 1367	SR 1363	SR 1351	0.34	Seal - Double and Fog Seal	$32,302
2028	9	080-Rowan	Preservation	SR 1368	SR 1367	SR 1363	0.21	Seal - Double and Fog Seal	$19,719
2028	9	080-Rowan	Preservation	SR 1370	SR 1124	EOM	0.14	Seal - Double and Fog Seal	$10,442
2028	9	080-Rowan	Preservation	SR 1371	SR 1124	EOM	0.20	Seal - Double and Fog Seal	$18,968
2028	9	080-Rowan	Preservation	SR 1372	SR 1124	EOM	0.12	Seal - Double and Fog Seal	$8,639
2028	9	080-Rowan	Preservation	SR 1373	SR 1124	SR 1374	0.06	Seal - Double and Fog Seal	$4,507
2028	9	080-Rowan	Preservation	SR 1374	EOM	EOM	0.07	Seal - Double and Fog Seal	$4,958
2028	9	080-Rowan	Preservation	SR 1375	SR 1124	SR 1124	0.49	Seal - Double and Fog Seal	$41,073
2028	9	080-Rowan	Preservation	SR 1376	SR 1375	SR 1375	0.12	Seal - Double and Fog Seal	$9,803
2028	9	080-Rowan	Preservation	SR 1377	SR 1376	SR 1375	0.06	Seal - Double and Fog Seal	$4,507
2028	9	080-Rowan	Preservation	SR 1378	SR 1124	EOM	0.16	Seal - Double and Fog Seal	$13,099
2028	9	080-Rowan	Preservation	SR 1379	SR 1124	EOM	0.25	Seal - Double and Fog Seal	$19,006
2028	9	080-Rowan	Preservation	SR 1380	SR 1371	EOM	0.11	Seal - Double and Fog Seal	$8,263
2028	9	080-Rowan	Preservation	SR 1381	SR 1380	SR 1124	0.08	Seal - Double and Fog Seal	$5,706
2028	9	080-Rowan	Preservation	SR 1431	SR 1351	SR 1124	0.76	Seal - Double and Fog Seal	$85,864
2028	9	080-Rowan	Preservation	SR 1432	SR 1370	EOM	0.23	Seal - Double and Fog Seal	$21,128
2028	9	080-Rowan	Preservation	SR 1456	SR 1431	SR 1457	0.29	Seal - Double and Fog Seal	$27,044
2028	9	080-Rowan	Preservation	SR 1457	SR 1431	SR 1458	0.18	Seal - Double and Fog Seal	$16,902

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	9	080-Rowan	Preservation	SR 1458	SR 1351	EOM	0.10	Seal - Double and Fog Seal	$11,268
2028	9	080-Rowan	Preservation	SR 1465	SR 1371	EOM	0.19	Seal - Double and Fog Seal	$21,522
2028	9	080-Rowan	Preservation	SR 1466	END C&G	SR 2702	0.13	Seal - Double and Fog Seal	$12,489
2028	9	080-Rowan	Preservation	SR 1466	SR 1465	END C&G	0.07	Seal - Double and Fog Seal	$6,667
2028	9	080-Rowan	Preservation	SR 1484	SR 1124	EOM	0.32	Seal - Double and Fog Seal	$30,049
2028	9	080-Rowan	Preservation	SR 1499	SR 1351	EOM	0.23	Seal - Double and Fog Seal	$21,598
2028	9	080-Rowan	Preservation	SR 2164	SR 1002	SR 1002	2.66	Seal - Double and Fog Seal	$249,404
2028	9	080-Rowan	Preservation	SR 2211	SR 2164	SR 2212	0.56	Seal - Double and Fog Seal	$41,768
2028	9	080-Rowan	Preservation	SR 2212	SR 2216	SR 2211	0.10	Seal - Double and Fog Seal	$7,587
2028	9	080-Rowan	Preservation	SR 2213	SR 2216	EOM	0.21	Seal - Double and Fog Seal	$17,663
2028	9	080-Rowan	Preservation	SR 2214	SR 2216	SR 2214	0.21	Seal - Double and Fog Seal	$17,409
2028	9	080-Rowan	Preservation	SR 2215	SR 2216	EOM	0.10	Seal - Double and Fog Seal	$8,113
2028	9	080-Rowan	Preservation	SR 2216	SR 2215	SR 2212	0.34	Seal - Double and Fog Seal	$28,481
2028	9	080-Rowan	Preservation	SR 2267	SR 2164	EOM	0.75	Seal - Double and Fog Seal	$70,802
2028	9	080-Rowan	Preservation	SR 2268	SR 2267	SR 2269	0.24	Seal - Double and Fog Seal	$22,161
2028	9	080-Rowan	Preservation	SR 2269	SR 2268	EOM	0.10	Seal - Double and Fog Seal	$9,015
2028	9	080-Rowan	Preservation	SR 2702	SR 1371	SR 2763	0.15	Seal - Double and Fog Seal	$13,804
2028	9	080-Rowan	Preservation	SR 2726	SR 1351	SR 1351	0.22	Seal - Double and Fog Seal	$18,170
2028	9	080-Rowan	Preservation	SR 2763	SR 2702	EOM	0.12	Seal - Double and Fog Seal	$11,174
2028	9	080-Rowan	Preservation	US 52	Granite Quarry CL	SR 2126 +.432MI	1.66	Crack Seal	$6,291
2028	9	080-Rowan	Preservation	US 52	SR 2319	Granite Quarry CL	2.44	Crack Seal	$5,840
2028	9	085-Stokes	Resurfacing	NC 8	SR 1496	STATE LINE	3.88	1.5" S9.5B	$1,037,978
2028	9	085-Stokes	Resurfacing	NC 8	SR 8 & 89	SR 1496	4.54	1.5" S9.5B	$1,214,541
2028	9	085-Stokes	Resurfacing	SR 1496	NC 8	NC 89	4.99	1.5" S9.5B	$1,333,587
2028	9	085-Stokes	Resurfacing	SR 1497	SR 1496	NC 704	4.62	1.5" S9.5B	$1,030,398
2028	9	085-Stokes	Resurfacing	SR 1499	SR 1496	SR 1496	2.90	1.5" S9.5B	$776,611
2028	9	085-Stokes	Preservation	NC 66	Forsyth Co	SR 1219	6.85	Crack Seal	$46,215
2028	9	085-Stokes	Preservation	SR 1152	SURRY CO	SR 1154	1.05	Seal - Double and Fog Seal	$98,935
2028	9	085-Stokes	Preservation	SR 1153	SR 1152	SURRY CO	0.17	Seal - Double and Fog Seal	$14,362
2028	9	085-Stokes	Preservation	SR 1159	SR 1236	SR 1236	0.55	Seal - Double and Fog Seal	$40,926
2028	9	085-Stokes	Preservation	SR 1162	SR 1224	EOM	0.67	Seal - Double and Fog Seal	$56,348
2028	9	085-Stokes	Preservation	SR 1164	SR 1166	SR 1166	2.28	Seal - Double and Fog Seal	$213,922
2028	9	085-Stokes	Preservation	SR 1165	SR 1166	SR 1166	0.64	Seal - Double and Fog Seal	$60,262
2028	9	085-Stokes	Preservation	SR 1170	SR 1166	EOM	0.79	Seal - Double and Fog Seal	$66,739
2028	9	085-Stokes	Preservation	SR 1176	SR 1182	SR 1175	0.74	Seal - Double and Fog Seal	$69,461
2028	9	085-Stokes	Preservation	SR 1297	SR 1147	SR 1298	0.55	Seal - Double and Fog Seal	$46,802
2028	9	085-Stokes	Preservation	SR 1298	SR 1148	EOM	0.41	Seal - Double and Fog Seal	$34,552
2028	9	085-Stokes	Preservation	SR 1346	S 1136	EOM	0.37	Seal - Double and Fog Seal	$31,511
2028	9	085-Stokes	Preservation	SR 1984	SR 1985	EOM	0.52	Seal - Double and Fog Seal	$43,761
2028	9	085-Stokes	Preservation	SR 1985	NC 8	NC 8	2.73	Seal - Double and Fog Seal	$255,974
2028	10	004-Anson	Resurfacing	NC 218	SR 1412 Maske Rd	SR 1416 Moore St	4.14	Full Depth Patching and 1.5" S9.5D	$1,305,045
2028	10	004-Anson	Resurfacing	SR 1224 Austin Road	SR 1253 Watts Road	SR 1220 Long Pine Road	2.06	1.5" S9.5C and Widen	$521,180
2028	10	004-Anson	Resurfacing	SR 1227 Pear Orchard	SC Line	SR 1220 Long Pine Church Rd	1.09	Full Depth Patching and 1.5" S9.5C	$341,775
2028	10	004-Anson	Resurfacing	SR 1234 Strawn Rd	SR 1236 Upper White Stoe Rd	Union County Line	0.48	1.5" S9.5C and Widen	$121,440
2028	10	004-Anson	Resurfacing	SR 1414 Savannah Rd	SR 1411 Deep Springs Church Rd	SR 1413 Newton-Moore Rd	1.27	1.5" S9.5C and Widen	$320,804
2028	10	004-Anson	Resurfacing	SR 1621 Plank Road	Fries Blvd	Smith St	0.55	Mill 1.5" and 1.5" S9.5C	$220,000
2028	10	004-Anson	Resurfacing	US 74 W	Pvmt Jt before Brown Creek	SR 1419 Old Route 74 E	1.25	Full Depth Patching and 1.5" S9.5C	$393,750
2028	10	004-Anson	Resurfacing	US 74 WB	Begin 4 lane at Walmart	Pvmt Jt before Brown Creek	4.39	#67 Mat Seal and 2.0" S9.5C	$1,679,269
2028	10	004-Anson	Preservation	SR 1441 Faulkner Rd	SR 1002	dead end	1.20	Seal - Double	$45,600
2028	10	004-Anson	Preservation	SR 1445 Cappadocia Church	SR 1456	SR 1438	4.72	Seal - Double	$179,360
2028	10	004-Anson	Preservation	SR 1449 Traywick Rd	NC 218	SR 1455 Edwards Store Rd	1.47	Seal - Double	$55,860
2028	10	004-Anson	Preservation	SR 1453 Nance	SR 1455	SR 1455	1.50	Seal - Double	$56,738
2028	10	004-Anson	Preservation	SR 1455 Edwards Store	SR 1459	SR 1456	1.29	Seal - Double	$49,096
2028	10	004-Anson	Preservation	SR 1456 Olive Branch Rd	Union County line	SR1455 Edwards Store Rd	0.56	Seal - Double	$21,280
2028	10	004-Anson	Preservation	SR 1457 Jerusalem Church	SR 1459 Jerusalem Church	SR 1455 Blonnie Ross	0.21	Seal - Double	$7,790
2028	10	004-Anson	Preservation	SR 1459 Blonnie Ross	Union County line	NC 742	2.06	Seal - Double	$78,090
2028	10	004-Anson	Preservation	SR 1459 Jerusalem Church	SR 1457 Jerusalem Church	SR 1455 Blonnie Ross	0.40	Seal - Double	$15,010
2028	10	004-Anson	Preservation	SR 1460 New Salem Rd	Union County line	SR 1459	0.13	Seal - Double	$4,976
2028	10	004-Anson	Preservation	SR 1554 Pine Log	NC 742	SR 1459	1.16	Seal - Double	$44,080

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	10	004-Anson	Preservation	SR 1600 Rocky Mount Church Rd	SR 1608 Burnsville Church Rd	Union County Line	5.55	Seal - Double	$211,070
2028	10	004-Anson	Preservation	SR 1601 Ashley-Allen	SR 1600	SR 1600	0.96	Seal - Double	$36,480
2028	10	004-Anson	Preservation	SR 1601 Drye Road	SR 1600 Rocky Mount Church Rd	Union County Line	1.23	Seal - Double	$46,740
2028	10	004-Anson	Preservation	SR 1603 Thomas Road	NC 742 North	SR 1600 Rocky Mount Church Road	2.10	Seal - Double	$79,800
2028	10	004-Anson	Preservation	SR 1604 Bennett Martin Road	SR 1603 Thomas Road	SR 1606 George Wright Road	0.83	Seal - Double	$31,540
2028	10	004-Anson	Preservation	SR 1606 George Wright Road	SR 1600 Rocky Mount Church Road	Bridge at Richardson Creek	1.57	Seal - Double	$55,000
2028	10	004-Anson	Preservation	SR 1606 George Wright Road	Bridge at Richardson Creek	SR 1608 Burnsville Church Road	1.57	Seal - Double	$55,000
2028	10	004-Anson	Preservation	SR 1608 Burnsville Church Road	NC 742 North	SR 1454 Poplin Road	0.78	Seal - Double	$29,754
2028	10	004-Anson	Preservation	SR 1658 Curlee	SR 10601	dead end	0.67	Seal - Double	$25,460
2028	10	013-Cabarrus	Resurfacing	SR 1006 Mt Pleasant Rd	NC 49	NC 73	0.81	Full Depth Patching and 1.5" S9.5C	$526,845
2028	10	013-Cabarrus	Resurfacing	SR 1154 Piney Ch Rd	SR 2910 Scottland Dr	SR 1132 Flowe Store Rd	1.37	Mill 1.5" and 1.5" S9.5B	$733,447
2028	10	013-Cabarrus	Resurfacing	SR 1154 Piney Ch Rd	SR 1153 Zion Ch Rd	SR 2910 Scottland Dr	0.92	1.5" S9.5B	$345,000
2028	10	013-Cabarrus	Resurfacing	SR 1394 Poplar Tent	SR 1414 Rock Hill Ch Rd	SR 1430 George Liles Pkwy	1.57	Full Depth Patching and 1.5" S9.5C	$838,225
2028	10	013-Cabarrus	Resurfacing	SR 1394 Poplar Tent	US 29	SR 1414 Rock Hill Ch Rd	1.53	1.5" S9.5C	$517,500
2028	10	013-Cabarrus	Resurfacing	SR 1414 Rock Hill Ch Rd	SR 1431 Weddington Rd	SR 1394 Poplar Tent Rd	1.16	Mill 1.5" and 1.5" S9.5B	$628,669
2028	10	013-Cabarrus	Resurfacing	SR 1643 Rainbow Dr	Bethpage	NC 3	0.66	1.5" S9.5B	$241,500
2028	10	013-Cabarrus	Resurfacing	SR 1643 Rainbow Dr	bridge	Rowan County line	1.51	Full Depth Patching and 1.5" S9.5B	$236,110
2028	10	013-Cabarrus	Resurfacing	SR 1643 Rainbow Dr	SR 1008 S Main St	Bethpage	0.39	Mill 1.5" and 1.5" S9.5B	$209,556
2028	10	013-Cabarrus	Resurfacing	SR 1706 East First St.	US 29	SR 1947 East First St	0.13	Full Depth Patching and 1.5" S9.5C	$60,000
2028	10	013-Cabarrus	Resurfacing	SR 1865 Odell Cr	SR 1864 Hills Dell Dr	SR 1864 Hills Dell Dr	0.18	1.25" S4.75A	$69,000
2028	10	013-Cabarrus	Resurfacing	SR 2000 Brantley Rd	MP 3.34	SR 1002 Concord Salisbury Rd	0.56	1.5" S9.5B	$207,000
2028	10	013-Cabarrus	Resurfacing	SR 2000 Brantley Rd	Eastminster Dr	MP 3.34	1.35	Mill 1.5" and 2.0" S9.5B	$707,253
2028	10	013-Cabarrus	Resurfacing	SR 2000 Brantley Rd	SR 2180 Lane St	Eastminster Dr	1.30	1.5" S9.5B	$448,500
2028	10	013-Cabarrus	Resurfacing	SR 2384 Avery Ct	SR 1154 Piney Church Rd	Cul-de-sac	0.11	Mill 1.5" and 1.5" S9.5B	$53,000
2028	10	013-Cabarrus	Resurfacing	SR 2385 Lofton Ct	SR 2382 Brigadoon Ct	Cul-de-sac	0.03	Mill 1.25" and 1.25" S9.5B	$18,053
2028	10	013-Cabarrus	Resurfacing	SR 2414 St John's Church Rd	NC 73	SR 2415 Cress Rd	1.44	Mill 1.25" and 1.25" S9.5A	$619,787
2028	10	013-Cabarrus	Resurfacing	SR 2894 Bruton Smith Blvd	End Divided Median	US 29	0.69	2.0" S9.5C	$243,697
2028	10	013-Cabarrus	Resurfacing	SR 2894 Bruton Smith Blvd	I-85 NB Ramp	End Divided Median	1.22	2.0" S9.5C	$417,767
2028	10	013-Cabarrus	Resurfacing	SR 2894 Christenbury Prkwy	Begin Divided Island	I-85 Entry Ramp	1.38	Full Depth Patching and 2.0" S9.5C	$733,447
2028	10	013-Cabarrus	Resurfacing	SR 2894 Christenbury Prkwy	Meck Co Line, TrafficCir	I-85 SB Exit Ramp	1.94	Full Depth Patching and 2.0" S9.5C	$1,047,782
2028	10	013-Cabarrus	Resurfacing	SR 2894 Concord Mills Blvd	I-85 SB Exit Ramp	I-85 NB Entry Ramp	0.15	Mill 2.0" and 2.0" S9.5C	$104,778
2028	10	013-Cabarrus	Resurfacing	SR 2911 Piney Ct	SR 1154 Piney Church Rd	Cul-de-sac	0.03	Mill 1.5" and 1.5" S9.5B	$15,716
2028	10	013-Cabarrus	Resurfacing	SR 3011 McFarley Pl	SR 1154 Piney Church Rd	SR 3012 Hendrix Ct	0.07	Mill 1.25" and 1.25" S9.5B	$31,433
2028	10	013-Cabarrus	Resurfacing	SR 3012 Hendrix Ct	cul-de-sac	cul-de-sac	0.19	Mill 1.25" and 1.25" S9.5B	$104,778
2028	10	013-Cabarrus	Resurfacing	SR 3013 Loch Lomond Cir	SR 1154 Piney Church Rd	SR 1154 Piney Ch Rd	0.62	Mill 1.25" and 1.25" S9.5B	$290,529
2028	10	013-Cabarrus	Resurfacing	SR 3014 Carol Ct	SR 3013 Loch Lomond Cir	Cul-de-sac	0.07	Mill 1.25" and 1.25" S9.5B	$26,194
2028	10	013-Cabarrus	Resurfacing	SR 3016 Amberdeen Ct	SR 3013 Loch Lomond Cir	Cul-de-sac	0.06	Mill 1.25" and 1.25" S9.5B	$26,195
2028	10	013-Cabarrus	Resurfacing	SR 3041 Highlander Ct	SR 1154 Piney Church Rd	Cul-de-sac	0.17	Mill 1.25" and 1.25" S9.5B	$104,778
2028	10	013-Cabarrus	Resurfacing	SR 3042 Carly Ct	SR 1154 Piney Church Rd	Cul-de-sac	0.21	Mill 1.25" and 1.25" S9.5B	$127,000
2028	10	013-Cabarrus	Resurfacing	SR 3047 Ellie Ct	Cul-de-sac	Cul-de-sac	0.13	Mill 1.25" and 1.25" S9.5B	$78,500
2028	10	013-Cabarrus	Preservation	SR 1129 Ramble Rd	SR 1121	SR 1128	0.44	Seal - Double and Fog Seal	$28,600
2028	10	013-Cabarrus	Preservation	SR 1283 Cimarron Cr	SR 1193 Peppercorn Rd	dead end	0.05	Seal - Double and Fog Seal	$19,667
2028	10	013-Cabarrus	Preservation	SR 1526 Cottonwood Trail	Scaleybark	End Maint	0.19	Seal - Double and Fog Seal	$13,000
2028	10	013-Cabarrus	Preservation	SR 1612 Archer Rd	SR 1613 Earnhardt Lake Rd	Rowan Co L	2.26	Seal - Double and Fog Seal	$156,109
2028	10	013-Cabarrus	Preservation	SR 1941 Ashbury Ln	SR 1939 Terrill Ridge Dr	SR 1939 Terrill Ridge Dr	0.49	Seal - Double and Fog Seal	$42,630
2028	10	013-Cabarrus	Preservation	SR 2206 Goldfish Rd	SR 1002 Old Concord Salisbury Rd	Rowan County line	0.09	Seal - Double and Fog Seal	$7,000
2028	10	013-Cabarrus	Preservation	SR 2413 Liberty Ridge Rd	SR 2408 GoldHill Rd	EOP	0.59	Seal - Double and Fog Seal	$54,475
2028	10	013-Cabarrus	Preservation	SR 2415	St. Johns	Cline School Rd.	1.93	Seal - Double and Fog Seal	$129,660
2028	10	013-Cabarrus	Preservation	SR 2427	Mt. Olive	Rimmer	3.48	Seal - Double and Fog Seal	$226,905
2028	10	013-Cabarrus	Preservation	SR 2432 Pless Rd	SR 2402	SR 2433 Phaniels Ch Rd	1.02	Seal - Double and Fog Seal	$65,000
2028	10	013-Cabarrus	Preservation	SR 2455 Short Cut Rd	SR 2450	SR 2456	0.86	Seal - Double and Fog Seal	$58,347
2028	10	013-Cabarrus	Preservation	SR 2458 RR Crossing Rd	US 52	SR 2457 Glenmore Rd	0.03	Seal - Double and Fog Seal	$2,000
2028	10	013-Cabarrus	Preservation	SR 2614 Paige Rd	Cauble Rd.SR2616	Lambert Rd.SR2611	1.70	Seal - Double and Fog Seal	$118,211
2028	10	013-Cabarrus	Preservation	SR 2618 Long Run Farm	Hahn Scott Rd. SR2617	Bowman Barrier.SR2610	2.09	Seal - Double and Fog Seal	$120,000
2028	10	013-Cabarrus	Preservation	SR 2656 Atando rd	NC 49	NS-96257	0.69	Seal - Double and Fog Seal	$40,645
2028	10	013-Cabarrus	Preservation	SR 2661 Tilley Rd	NC 49	END PVMT	0.67	Seal - Double and Fog Seal	$45,381
2028	10	060-Mecklenburg	Resurfacing	NC 27 Mt Holly Road	SR 1666 Mt Holly Huntersville Road	SR 1784 Mt Holly Road	3.11	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$738,000
2028	10	060-Mecklenburg	Resurfacing	NC 49 NB	John Kirk Dr	Cabarrus County Line	2.48	Mill 1.5" and 1.5" S9.5D	$900,000
2028	10	060-Mecklenburg	Resurfacing	NC 49 SB	Cabarrus County Line	John Kirk Dr	2.48	Mill 1.5" and 1.5" S9.5D	$900,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	10	060-Mecklenburg	Resurfacing	NC 51 NB Pineville-Matthews Rd	Carmel Commons Blvd	SR 4931 Carolina Place Pkwy	1.65	Mill 1.5" and 1.5" S9.5D	$350,000
2028	10	060-Mecklenburg	Resurfacing	NC 51 Pineville Matthews EB	NC 16 Providence Rd	Median after Charing Cross Dr	1.99	Mill 1.5" and 1.5" S9.5D	$426,000
2028	10	060-Mecklenburg	Resurfacing	NC 51 Pineville Matthews WB	Median before Charing Cross Dr	NC 16 Providence Rd	1.89	Mill 1.5" and 1.5" S9.5D	$405,000
2028	10	060-Mecklenburg	Resurfacing	NC 51 SB Pineville-Matthews Rd	Carmel Commons Blvd	Pavement Divide	0.24	Mill 1.5" and 1.5" S9.5D	$305,000
2028	10	060-Mecklenburg	Resurfacing	NC 51 SB Pineville-Matthews Rd	Pavement Divide	SR 4931 Carolina Place Pkwy	0.00	Mill 1.5" and 1.5" S9.5D	$2,179
2028	10	060-Mecklenburg	Resurfacing	NC 51 SB Pineville-Matthews Rd	Pavement Divide	SR 4931 Carolina Place Pkwy	0.56	Mill 1.5" and 1.5" S9.5D	$302,821
2028	10	060-Mecklenburg	Resurfacing	SR 1333 Soldier Road	Elena Drive	SR 1113 Pine Harbor Road	1.07	Full Depth Patching and 1.5" S9.5C	$410,500
2028	10	060-Mecklenburg	Resurfacing	SR 1592 Robbie Circle	Shopton Rd	Shopton	0.30	Full Depth Patching and 1.5" S9.5B	$55,000
2028	10	060-Mecklenburg	Resurfacing	SR 1609 Rhyne Rd	NC 27 Mt Holly Rd	SR 1601 Moores Chapel Rd	1.33	Full Depth Patching and 1.5" S9.5C	$266,000
2028	10	060-Mecklenburg	Resurfacing	SR 1676 Old Moores Chapel	SR 6102 Rhyne Station Rd	EOM	0.11	Full Depth Patching and 1.5" S9.5B	$14,000
2028	10	060-Mecklenburg	Resurfacing	SR 1681 N McDowell St	NC 16 S / East 4th St	East 7th St / Monroe Rd	0.33	Mill 3.0" and 3.0" S9.5C	$86,866
2028	10	060-Mecklenburg	Resurfacing	SR 2025 Miranda Rd	SR 2108 Sunset Rd	SR 2074 Beatties Ford Rd	1.89	Full Depth Patching and 1.5" S9.5C	$380,000
2028	10	060-Mecklenburg	Resurfacing	SR 2074 Beatties Ford Rd	SR 2004 Mt Holly Huntersville Rd	SR 2120 McCoy Rd	0.55	Full Depth Patching and 1.5" S9.5C	$125,000
2028	10	060-Mecklenburg	Resurfacing	SR 2074 Beatties Ford Rd	Pauline Lane	SR 2004 Mt Holly Huntersville Rd	3.04	Full Depth Patching and 1.5" S9.5C	$608,000
2028	10	060-Mecklenburg	Resurfacing	SR 2074 Neck Rd	SR 2165 Johnson Davis Rd	eom	1.72	1.5" S9.5B and Widen	$345,000
2028	10	060-Mecklenburg	Resurfacing	SR 2137 Ervin Cook Rd	SR 2136 Gilead Rd	EOM	0.75	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$140,000
2028	10	060-Mecklenburg	Resurfacing	SR 2234 Stonegate Dr	SR 2037 Kelly Rd	EOM	0.26	Full Depth Patching and 1.25" S9.5B	$38,000
2028	10	060-Mecklenburg	Resurfacing	SR 2417 Grey Rd	Iredell County line	Charden Rd	1.02	Full Depth Patching and 1.5" S9.5B	$190,000
2028	10	060-Mecklenburg	Resurfacing	SR 2417 Grey Rd	Charden Rd	Davidson-Concord Rd	1.51	Full Depth Patching and 1.5" S9.5B	$300,000
2028	10	060-Mecklenburg	Resurfacing	SR 2445 Trails End Lane	Asbury Chapel Rd	eom	0.53	Full Depth Patching and 1.25" S9.5B	$100,000
2028	10	060-Mecklenburg	Resurfacing	SR 2467 Mallard Creek	Beg Divide Grace Lane	End Divide Odell School	1.01	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$190,000
2028	10	060-Mecklenburg	Resurfacing	SR 2467 Mallard Creek	County Line	Medical Plaza Dr	4.63	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,400,000
2028	10	060-Mecklenburg	Resurfacing	SR 2472 W Mallard Creek Ch Rd	Pavement Divide	I-85	0.16	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$40,000
2028	10	060-Mecklenburg	Resurfacing	SR 2472 W Mallard Creek Ch Rd	SR 2467 Mallard Creek	Pavement Divide	1.08	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$440,000
2028	10	060-Mecklenburg	Resurfacing	SR 2472 W Mallard Creek Ch Rd	I-85	SR 2467 Mallard Creek	1.49	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$500,000
2028	10	060-Mecklenburg	Resurfacing	SR 2475 Benfield Rd	SR 2479 Dearmon Dr	EOM	0.18	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$24,500
2028	10	060-Mecklenburg	Resurfacing	SR 2475 Benfield Rd	EOM	SR 2479 Dearmon Dr	0.18	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$24,500
2028	10	060-Mecklenburg	Resurfacing	SR 2848 Orr Rd	SR 2853 Newell Hickory Grove Rd	EOM	0.28	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5C	$145,000
2028	10	060-Mecklenburg	Resurfacing	SR 2853 Newell Hickory Grove Rd	Newell Acres Dr	EOM	0.78	Mill 2.0" and 2.0" S9.5C	$225,000
2028	10	060-Mecklenburg	Resurfacing	SR 3047 Morningstar Place Dr	NC 29 N Tryon St	EOM	0.44	Mill 1.5" and 1.5" S9.5C	$226,000
2028	10	060-Mecklenburg	Resurfacing	SR 3235 Pine Grove Ave	NC 24	Oak Hill Dr	0.45	Full Depth Patching and 1.5" S9.5C	$110,000
2028	10	060-Mecklenburg	Resurfacing	SR 3370 Graymist Dr	Rocky River Church Rd	cul-de-sac	0.59	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$100,000
2028	10	060-Mecklenburg	Resurfacing	SR 3815 E Morehead St	NC 49 S Tryon St	NC 27 S McDowell St	0.62	Mill 3.0" and 3.0" S9.5C	$347,000
2028	10	060-Mecklenburg	Resurfacing	SR 4201 Fieldlark Ln	Allen Black Rd	SR 4212	0.33	Full Depth Patching and 1.25" S9.5B	$46,000
2028	10	060-Mecklenburg	Resurfacing	SR 4221 Spicewood Dr	SR 3128 Lawyers Rd	SR 4222 Redbud Dr	0.69	Full Depth Patching and 1.5" S9.5B	$162,400
2028	10	060-Mecklenburg	Resurfacing	SR 4222 Redbud Dr	SR 4221 Spicewood Dr	EOM	0.09	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$5,000
2028	10	060-Mecklenburg	Resurfacing	SR 4862 Alumni Way	NC 24 E WT Harris Blvd	Cameron Blvd	0.51	Mill 2.0" and 2.0" S9.5C	$280,000
2028	10	060-Mecklenburg	Resurfacing	SR 5217 Connell Mill Lane	Cabarrus Rd	cul de sac	0.36	Full Depth Patching and 1.25" S9.5B	$39,000
2028	10	060-Mecklenburg	Resurfacing	SR 5222 Cedar Grove Rd	Pine Grove Ave	eom	0.09	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$10,000
2028	10	060-Mecklenburg	Resurfacing	SR 5223 Wilgrove-Mint Hill Rd	NC 24	Wilson Grove Rd	0.22	Full Depth Patching and 1.5" S9.5C	$28,000
2028	10	060-Mecklenburg	Resurfacing	SR 5223 Wilgrove-Mint Hill Rd	SR 3135 Wilson Grove Rd	NC 51 Blair Rd	2.20	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$505,500
2028	10	060-Mecklenburg	Resurfacing	SR 5435 Old Nations Ford Rd	E Westinghouse Blvd	EOM	0.17	Mill 1.5" and 2.5" I19.0C and 1.5" S9.5C	$131,000
2028	10	060-Mecklenburg	Resurfacing	SR 6000 Sweetfield Dr	SR 2459 Eastfield Rd	EOM	0.48	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$94,000
2028	10	060-Mecklenburg	Resurfacing	SR 6001 McCahan Ln	EOM	Cul de sac	0.05	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$13,500
2028	10	060-Mecklenburg	Resurfacing	SR 6002 Ryddell Ct	SR 6000 Sweetfield Dr	Cul de sac	0.04	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$9,100
2028	10	060-Mecklenburg	Resurfacing	SR 6003 McGinnis Ln	SR 6000 Sweetfield Dr	Cul de sac	0.13	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$25,000
2028	10	060-Mecklenburg	Resurfacing	SR 6004 Glassonby Ct	SR 6000 Sweetfield Dr	Cul de sac	0.04	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$9,800
2028	10	060-Mecklenburg	Resurfacing	SR 6005 McGinnis Woods Dr	SR 6000 Sweetfield Dr	Cul de sac	0.04	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$9,800
2028	10	060-Mecklenburg	Resurfacing	US 29	Mallard Creek Church Rd	SR 2469 +.722	2.00	Full Depth Patching and 1.5" S9.5C	$367,000
2028	10	060-Mecklenburg	Resurfacing	US 29	Sugar Creek Rd	I-277 +.173 miles	0.81	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$200,000
2028	10	060-Mecklenburg	Resurfacing	US 29	SR 2469 +.722	Cabarrus County line	0.93	Full Depth Patching and 1.5" S9.5C	$200,000
2028	10	060-Mecklenburg	Resurfacing	US 29 N Tryon St	Cabarrus County line	I-485	1.51	Full Depth Patching and 1.5" S9.5C	$475,000
2028	10	060-Mecklenburg	Resurfacing	US 29 West Morehead St	NC 27 Freedom Dr	US 29 South Mint St	0.90	Mill 1.5" and 1.5" S9.5D	$425,000
2028	10	060-Mecklenburg	Resurfacing	US 29/74 Wilkinson Blvd EBL	Fieldridge Rd	SR 1981 Little Rock Rd	1.70	Mill 1.5" and 1.5" S9.5D	$564,000
2028	10	060-Mecklenburg	Resurfacing	US 29/74 Wilkinson Blvd WBL	SR 1981 Little Rock Rd	Fieldridge Rd	1.71	Mill 1.5" and 1.5" S9.5D	$564,000
2028	10	060-Mecklenburg	Resurfacing	US 74 EB Independence	NC 27 +1.039 miles	Briar Creek	1.74	Mill 1.5" and 1.5" S9.5D	$638,000
2028	10	060-Mecklenburg	Rehabilitation	SR 2679 US 29 Access Rd	US 29 N Tryon St	EOM	0.57	FDR and 1.5" S9.5C	$200,956
2028	10	060-Mecklenburg	Preservation	SR 1101 Youngblood Rd W	SR 1102	EOM	0.52	Rejuvenator	$5,610
2028	10	060-Mecklenburg	Preservation	SR 1103 Capps Rd	End of Curb & Gutter	EOM	0.12	Rejuvenator	$1,489

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	10	060-Mecklenburg	Preservation	SR 1104 Thomas Rd	SR 1105 Zoar Rd	EOM	0.84	Rejuvenator	$13,902
2028	10	060-Mecklenburg	Preservation	SR 1116 Shopton Rd W	Kirkwyrd Commons Dr	Dan Caudle Rd	0.86	Rejuvenator	$11,540
2028	10	060-Mecklenburg	Preservation	SR 1126 Nations Ford Rd	RR	Westinghouse Blvd.	0.43	Rejuvenator	$5,200
2028	10	060-Mecklenburg	Preservation	SR 1333 Soldier Road	Elena Drive	SR 1113 Pine Harbor Road	1.07	Rejuvenator	$12,700
2028	10	060-Mecklenburg	Preservation	SR 1347 Nevada Blvd	NC 49 S Tryon St	dead end (Granite St)	1.21	Rejuvenator	$17,960
2028	10	060-Mecklenburg	Preservation	SR 1481 Trace Chain Ln	SR 1100 Mckee Rd	Eom	0.19	Rejuvenator	$3,430
2028	10	060-Mecklenburg	Preservation	SR 1496 Halter Dr	SR 1481 Trace Chain Ln	Cul-De-Sac	0.04	Rejuvenator	$722
2028	10	060-Mecklenburg	Preservation	SR 1557 Red Buckboard Ln	SR 1100 Mckee Rd	EOM	0.19	Rejuvenator	$3,430
2028	10	060-Mecklenburg	Preservation	SR 1785 Valleydale Rd	Homestead Glen Blvd	Bellhaven Blvd /Rozzelles Ferry Rd	1.34	Rejuvenator	$21,700
2028	10	060-Mecklenburg	Preservation	SR 2126 Arthur Auten Rd	Neck Rd	EOM	0.87	Rejuvenator	$11,740
2028	10	060-Mecklenburg	Preservation	SR 2130 McIlwaine Rd	SR 2128 Beatties Ford Rd	Sr 2138 McCoy Rd	2.43	Rejuvenator	$32,790
2028	10	060-Mecklenburg	Preservation	SR 2133 Cashion Rd	pvmt change	Gate	0.43	Rejuvenator	$5,200
2028	10	060-Mecklenburg	Preservation	SR 2133 Cashion Rd	Beatties Ford Rd	pvmt change	1.27	Rejuvenator	$16,270
2028	10	060-Mecklenburg	Preservation	SR 2136 Gilead Rd	Bud Henderson / Old Bud Henderson	Beatties Ford Rd	1.56	Rejuvenator	$18,900
2028	10	060-Mecklenburg	Preservation	SR 2138 McCoy Rd	SR 2117 Hambright Rd	SR 2136 Gilead Rd	1.66	Rejuvenator	$22,360
2028	10	060-Mecklenburg	Preservation	SR 2181 Brown Mill Rd	NC 73	NC 73	0.54	Rejuvenator	$7,312
2028	10	060-Mecklenburg	Preservation	SR 2182 Hagers Ferry Rd	NC 73	EOM	0.47	Rejuvenator	$7,071
2028	10	060-Mecklenburg	Preservation	SR 2433 Mayes Rd	NC 115	pvmt change	1.01	Rejuvenator	$12,230
2028	10	060-Mecklenburg	Preservation	SR 2444 Hus McGinnis Rd	Asbury Chapel Rd	EOM	0.90	Rejuvenator	$12,130
2028	10	060-Mecklenburg	Preservation	SR 2805 Harrisburg Rd	Starnes Randall rd	end of paint island	0.47	Rejuvenator	$6,330
2028	10	060-Mecklenburg	Preservation	SR 2822 Robinson Ch Rd	Plot Rd	Hood Rd	0.64	Rejuvenator	$8,640
2028	10	060-Mecklenburg	Preservation	SR 3106 Brief Rd	Clear Meadow Ln	Union County line	1.35	Rejuvenator	$18,160
2028	10	060-Mecklenburg	Preservation	SR 3108 Ira Flowe Rd	SR 3181 Ferguson Rd	SR 3106 Brief Rd	0.50	Rejuvenator	$6,025
2028	10	060-Mecklenburg	Preservation	SR 3174 Idlewild Rd	SR 3125 Thompson Rd	Hoods Village Dr	0.52	Rejuvenator	$8,420
2028	10	060-Mecklenburg	Preservation	SR 3645 Downs Cir	SR 1129 Downs Rd	EOM	0.24	Rejuvenator	$3,560
2028	10	060-Mecklenburg	Preservation	SR 4415 Amanda Dr	Union County Line	EOM	0.31	Rejuvenator	$4,897
2028	10	060-Mecklenburg	Preservation	SR 4422 Bounty Ct	SR 4415 Amanda Dr	SR 4434 Oak Berry Ct	0.45	Rejuvenator	$7,267
2028	10	060-Mecklenburg	Preservation	SR 4434 Oak Berry Ct	SR 4422 Bounty Ct	EOM	0.06	Rejuvenator	$903
2028	10	060-Mecklenburg	Preservation	SR 4982 North Polk Street	I-485	End Divide	0.25	Rejuvenator	$6,320
2028	10	060-Mecklenburg	Preservation	SR 5223 Wilgrove-Mint Hill Rd	SR 3135 Wilson Grove Rd	NC 51 Blair Rd	2.20	Rejuvenator	$29,650
2028	10	060-Mecklenburg	Preservation	SR 5469 Shopton Rd	NC 160	Pleasant Way Ln	1.15	Rejuvenator	$14,010
2028	10	060-Mecklenburg	Preservation	US 74 Wilkinson Blvd	Suttle Ave	Alleghany St	1.94	Microsurface	$357,368
2028	10	060-Mecklenburg	Preservation	US 74 Wilkinson Blvd	Alleghany St	Suttle Ave	2.37	Microsurface	$412,392
2028	10	084-Stanly	Resurfacing	NC 24/27	Bridge .15 mp before SR 1115 Liberty Hill Ch Rd	0 mp before SR 1216 Smith Grove I	2.10	1.5" S9.5C	$656,500
2028	10	084-Stanly	Resurfacing	NC 24/27	.10 mp past SR 1216 Smith Grove Rd	.5 mp past SR 1115 Liberty Hill Ch F	2.11	1.5" S9.5C	$696,075
2028	10	084-Stanly	Resurfacing	NC 73 West main St	SR 1274 West Main St	US 52	0.23	Mill 1.5" and 1.5" S9.5C	$57,500
2028	10	084-Stanly	Resurfacing	NC 740	Pvt Joint at Highland Drive	NC 8	0.46	Mill 1.5" and 1.5" S9.5C	$197,000
2028	10	084-Stanly	Resurfacing	NC 8/740	US 52 Hwy	SR 1817 Main St	0.20	Mill 1.5" and 1.5" S9.5C	$64,000
2028	10	084-Stanly	Resurfacing	SR 1274 West Main St	Old Charlotte	NC 73	0.66	Mill 1.5" and 1.5" S9.5B	$342,500
2028	10	084-Stanly	Resurfacing	SR 1474 Salisbury Ave	US 52	N First St	0.33	Mill 1.5" and 1.5" S9.5B	$90,750
2028	10	084-Stanly	Resurfacing	SR 1573 Salisbury/ n Second St	N First	US 52 N	0.83	Mill 1.5" and 1.5" S9.5B	$280,000
2028	10	084-Stanly	Resurfacing	SR 1922 South Stanly School Rd	SR 2001 Old Aquadale Rd	SR 1923 Old Cottonville Rd	4.60	Mill 1.5" and 1.5" S9.5B	$946,940
2028	10	084-Stanly	Resurfacing	SR 1923 South Stanly School Rd	SR 1923 Old Cottonville Rd	US 52	3.51	Mill 1.5" and 1.5" S9.5B	$818,000
2028	10	084-Stanly	Resurfacing	US 52 North	NC 740 Hwy-W Gold St	Old US 52	1.28	1.5" S9.5C	$754,000
2028	10	084-Stanly	Preservation	SR 1109 Philadelphia Ch Rd	NC 200	SR 1118 Buster Rd	2.83	Seal - Double	$99,050
2028	10	084-Stanly	Preservation	SR 1134 Running Creek Ch Rd	NC 24/27	SR 1134 Millingport Rd	3.18	Seal - Double	$94,573
2028	10	084-Stanly	Preservation	SR 1143 Nance Rd	County Line	SR 1140 Renee Ford Rd	1.07	Seal - Double	$45,000
2028	10	084-Stanly	Preservation	SR 1147 Polk Ford Rd	SR 1001 Love Mill Ch Rd	EOM	4.49	Seal - Double	$126,827
2028	10	084-Stanly	Preservation	SR 1150 Smith Rd	SR 1149 Talley Rd	SR 1140 Renee Ford Rd	1.47	Seal - Double	$46,640
2028	10	084-Stanly	Preservation	SR 1151 Yow Rd	SR 1149 Talley Rd	SR 1152 Tite Rd	1.26	Seal - Double	$44,100
2028	10	084-Stanly	Preservation	SR 1152 Tite Rd	SR 1147 Polk Ford Rd	SR 1001 Love Mill Rd	3.65	Seal - Double	$108,551
2028	10	084-Stanly	Preservation	SR 1161 Math Rd	SR 1001 Love Mill Ch Rd	EOM	0.48	Seal - Double	$16,800
2028	10	084-Stanly	Preservation	SR 1174 Jungle Rd	SR 1148 Smith Rd	EOM	0.27	Seal - Double	$8,100
2028	10	084-Stanly	Preservation	SR 1201 Scout Rd	SR 1200 Meadow Creek Ch	EOM	0.34	Seal - Double	$10,200
2028	10	084-Stanly	Preservation	SR 1215 Joes Rd	SR 1216 Smith Grove Rd	SR 1214 Austin Rd	0.57	Seal - Double	$17,480
2028	10	084-Stanly	Preservation	SR 1216 Smith Grove Rd	NC 24/27	SR 1200 Bethel Ch Rd	2.20	Seal - Double	$71,649
2028	10	084-Stanly	Preservation	SR 1217 Jacob Rd	SR 1227 Ridgecrest	SR 1214 Austin Rd	1.31	Seal - Double	$45,850
2028	10	084-Stanly	Preservation	SR 1219 Newsome Rd	NC 24/27	SR 1221 Frog Pond Rd	0.32	Seal - Double	$8,000
2028	10	084-Stanly	Preservation	SR 1222 Newsome Rd	SR 1221 Frog Pond Rd	SR 1214 Austin Rd	1.28	Seal - Double	$44,800

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	10	084-Stanly	Preservation	SR 1224 Joy Rd	SR 1214 Austin Rd	SR 1227 Ridgecrest Rd	1.41	Seal - Double	$49,350
2028	10	084-Stanly	Preservation	SR 1231 Lambert	SR 1206 Five Point Rd	SR 1231 Bridge Rd	0.78	Seal - Double	$27,300
2028	10	084-Stanly	Preservation	SR 1252 Burris Rd	SR 1214 Austin Rd	SR 1253 Sam Rd	1.24	Seal - Double	$43,400
2028	10	084-Stanly	Preservation	SR 1275 Oscar Rd	SR 1211 Coley Store Rd	SR 1206 Mission Ch Rd	1.37	Seal - Double	$47,600
2028	10	084-Stanly	Preservation	SR 1283 Stony Rd	SR 1214 Austin Rd	SR 1134 Running Creek Ch RD	0.90	Seal - Double	$35,000
2028	10	084-Stanly	Preservation	SR 1286 Tucker Rd	SR 1216 Smith Grove Rd	EOM	0.68	Seal - Double	$35,000
2028	10	084-Stanly	Preservation	SR 1297 Brattain	SR 1200 Bethel Ch Rd	NC 24/27	0.65	Seal - Double	$35,000
2028	10	084-Stanly	Preservation	SR 1309 Woodfield Rd	SR 1221 Frog Pond Rd	EOM	0.30	Seal - Double	$11,360
2028	10	084-Stanly	Preservation	SR 1319 Bee Tree Rd	SR 1228 Rowland	SR 1320 Red Barn Trail	0.16	Seal - Double	$8,500
2028	10	084-Stanly	Preservation	SR 1320 Red Barn Trail Rd	EOM	EOM	0.37	Seal - Double	$19,500
2028	10	084-Stanly	Preservation	SR 1325 Substation Rd	SR 1134 Millingport Rd	SR 1227 Ridgecrest Rd	0.86	Seal - Double	$28,000
2028	10	090-Union	Resurfacing	NC 200 N	Stanly County line	SR 1660 Honey Bee Rd	1.48	1.5" S9.5C	$518,000
2028	10	090-Union	Resurfacing	NC 218	SR 1543 Clontz Rd	pvt jnt US 601 N	1.27	#67 Mat Seal and 2.0" S9.5C	$600,000
2028	10	090-Union	Resurfacing	NC 84	SR 1334 Willoughby Rd	NC 200 MLK Blvd	2.60	1.5" S9.5B	$900,000
2028	10	090-Union	Resurfacing	SR 1002 Ansonville Rd	SR 1720 Lanesboro Rd	Anson County line	0.87	1.5" S9.5C	$375,000
2028	10	090-Union	Resurfacing	SR 1002 Ansonville Rd	SR 1726 Old Goldmine	SR 1719 Marshville/Olive Branch Rc	1.64	1.5" S9.5C	$550,000
2028	10	090-Union	Resurfacing	SR 1008 Waxhaw-Indian Trail Rd	SR 1515 Newtown Rd	NC 84	1.27	1.5" S9.5C	$450,000
2028	10	090-Union	Resurfacing	SR 1009 Old Charlotte Hwy	NC 200 Dickerson Blvd	Rocky River Rd	2.74	1.5" S9.5A	$1,410,000
2028	10	090-Union	Resurfacing	SR 1306 Gray Byrum Rd	NC 16	SR 1301 Waxhaw-Marvin Rd	1.04	1.5" S9.5B	$350,000
2028	10	090-Union	Resurfacing	SR 1365 Stallings Rd	pvt jnt	SR 1009 Old Charlotte Rd	1.03	#67 Mat Seal and 1.5" S9.5B	$450,000
2028	10	090-Union	Resurfacing	SR 1518 Faith Ch	SR 1367 Unionville-Indian Trail	pvt jt	0.33	1.5" S9.5B	$120,000
2028	10	090-Union	Resurfacing	SR 1901 Hasty Rd	SR 1005 Landsford Rd	bridge	1.75	1.5" S9.5B and Widen	$660,000
2028	10	090-Union	Resurfacing	SR 1922 Kelly Autry Rd	SR 1919 Canal Rd	SR 1005 Landsford Rd	0.60	1.5" S9.5B	$225,000
2028	10	090-Union	Resurfacing	SR 1961 Love St	US 74	SR 1961 Sycamore Grove Rd	0.50	1.5" S9.5B and Widen	$200,000
2028	10	090-Union	Resurfacing	SR 2412 Brook Stone Tr	SR 1367 Unionville- Indian Trail	eom	0.52	Mill 1.25" and 1.25" S9.5A	$230,000
2028	10	090-Union	Resurfacing	SR 2413 Rocky Medow W	SR 2415 Brooktree Ln	eom	0.08	Mill 1.25" and 2.5" S9.5A	$35,000
2028	10	090-Union	Resurfacing	SR 2414 Hard Rock Ct	SR 2413 Rocky Medow Way	eom	0.13	Mill 1.25" and 1.25" S9.5A	$60,000
2028	10	090-Union	Resurfacing	SR 2415 Brooktree Ln	SR 1367 Unionville- Indian Trail	eom	0.37	Mill 1.25" and 2.5" S9.5A	$160,000
2028	10	090-Union	Resurfacing	SR 2459 Crystal Creek Ct	SR 2145 Brooktree Ln	eom	0.04	Mill 1.25" and 1.25" S9.5A	$20,000
2028	10	090-Union	Resurfacing	SR 2460 Babbling Brook Ct	SR 2412 Brook Stone Tr	eom	0.03	Mill 1.25" and 1.25" S9.5A	$15,000
2028	10	090-Union	Resurfacing	SR 2461 Granite Ct	SR 2412 Brook Stone Tr	eom	0.11	Mill 1.25" and 1.25" S9.5A	$50,000
2028	10	090-Union	Resurfacing	SR 2462 Rocky Pine Ct	SR 2412 Brook Stone Tr	eom	0.05	Mill 1.25" and 1.25" S9.5A	$22,000
2028	10	090-Union	Resurfacing	SR 2762 Hadley Park	SR 3146 Beauth Ch Rd	SR 2763 Garden View	0.31	Mill 1.25" and 1.25" S9.5A	$135,000
2028	10	090-Union	Resurfacing	SR 2763 Garden View	SR 2762 Hadley Park	eom	0.54	Mill 1.25" and 1.25" S9.5A	$230,000
2028	10	090-Union	Resurfacing	SR 3188 Schiller Dr	SR 1162 S Potters Rd	eom	0.32	Mill 1.25" and 1.25" S9.5A	$150,000
2028	10	090-Union	Resurfacing	SR 3190 Voltair Dr	SR 3297 Vaugelas Ct	eom	0.10	Mill 1.25" and 1.25" S9.5A	$50,000
2028	10	090-Union	Resurfacing	SR 3191 Perrault Cir	SR 3297 Vaugelas Ct	eom	0.07	Mill 1.25" and 1.25" S9.5A	$40,000
2028	10	090-Union	Resurfacing	SR 3202 Titus Ct	SR 3204 Damascus Dr	eom	0.12	Mill 1.25" and 1.25" S9.5A	$55,000
2028	10	090-Union	Resurfacing	SR 3204 Damascus Dr	SR 1353 Rogers Rd	SR 3206 Capstone Dr	0.23	Mill 1.25" and 1.25" S9.5A	$100,000
2028	10	090-Union	Resurfacing	SR 3205 Jacobs Ct	SR 3206 Capstone Dr	eom	0.13	Mill 1.25" and 1.25" S9.5A	$60,000
2028	10	090-Union	Resurfacing	SR 3206 Capstone Dr	SR 3207 Genesis Dr	SR 1353 Rogers Rd	0.47	Mill 1.25" and 1.25" S9.5A	$200,000
2028	10	090-Union	Resurfacing	SR 3207 Genesis Dr	eom	eom	0.50	Mill 1.25" and 1.25" S9.5A	$215,000
2028	10	090-Union	Resurfacing	SR 3265 Mossy Oak	SR 3266 Paper Bark	eom	0.22	Mill 1.25" and 1.25" S9.5A	$100,000
2028	10	090-Union	Resurfacing	SR 3266 Paper Bark	SR 1353 Rogers Rd	eom	0.23	1.5" S9.5B	$90,000
2028	10	090-Union	Resurfacing	SR 3267 Odessa Pl	eom	eom	0.25	Mill 1.25" and 1.25" S9.5A	$110,000
2028	10	090-Union	Resurfacing	SR 3271 Kings Manor Dr	NC 16	eom	1.53	Mill 1.25" and 1.25" S9.5A	$600,000
2028	10	090-Union	Resurfacing	SR 3271 Kings Manor Dr	SR 3491 Pine Laurel Rd	NC 16	1.01	Mill 1.25" and 1.25" S9.5A	$400,000
2028	10	090-Union	Resurfacing	SR 3296 Coral Bell	SR 3297 Blazing Star	eom	0.17	Mill 1.25" and 1.25" S9.5A	$75,000
2028	10	090-Union	Resurfacing	SR 3297 Blazing Star	SR 3267 Odessa Pl	eom	0.13	Mill 1.25" and 1.25" S9.5A	$60,000
2028	10	090-Union	Resurfacing	SR 3297 Vaugelas Ct	SR 3188 Schiller Dr	eom	0.18	Mill 1.25" and 2.5" S9.5A	$80,000
2028	10	090-Union	Resurfacing	SR 3325 Avocet Dr	SR 1349 Airport Rd	SR 3326 Dexter Pl	0.04	Mill 1.25" and 1.25" S9.5A	$20,000
2028	10	090-Union	Resurfacing	SR 3326 Dexter Pl	eom	eom	0.23	Mill 1.25" and 1.25" S9.5A	$100,000
2028	10	090-Union	Resurfacing	SR 3346 Trellis Ln	SR 3350 Counselors Dr	eom	0.17	Mill 1.25" and 1.25" S9.5A	$75,000
2028	10	090-Union	Resurfacing	SR 3347 Unity Ct	SR 3350 Counselors Dr	eom	0.03	Mill 1.25" and 1.25" S9.5A	$15,000
2028	10	090-Union	Resurfacing	SR 3348 Solomons Ct	SR 3350 Counselors Dr	eom	0.03	Mill 1.25" and 1.25" S9.5A	$15,000
2028	10	090-Union	Resurfacing	SR 3349 Revelation Way	SR 3350 Counselors Dr	eom	0.21	Mill 1.25" and 1.25" S9.5A	$90,000
2028	10	090-Union	Resurfacing	SR 3350 Counselors Dr	SR 3207 Genesis Dr	eom	0.42	Mill 1.25" and 1.25" S9.5A	$180,000
2028	10	090-Union	Resurfacing	SR 3685 Bronte Ln	SR 3188 Schiller Dr	eom	0.09	Mill 1.25" and 1.25" S9.5A	$40,000
2028	10	090-Union	Resurfacing	SR 3686 Dickens Ln	SR 3685 Bronte Ln	eom	0.06	Mill 1.25" and 1.25" S9.5A	$30,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	10	090-Union	Resurfacing	US 74 E	SR 1377 Wesley Chapel Stouts	Rocky River Rd	2.56	#67 Mat Seal and 2.0" S9.5C	$685,000
2028	10	090-Union	Resurfacing	US 74 E	pavement jt	SR 1740 W Main St	0.91	Mill 1.5" and 1.5" S9.5C	$400,000
2028	10	090-Union	Resurfacing	US 74 W	SR 1740 W Main St	pavement jt	0.90	Mill 1.5" and 1.5" S9.5C	$400,000
2028	10	090-Union	Rehabilitation	SR 1957 Monroe-Marshville RD	SR 1740 Old Hwy 74	SR 1903 Gilboa	1.58	FDR and 1.0" S9.5A and Widen	$650,000
2028	10	090-Union	Preservation	SR 1541 Russell Rd	NC 218	SR 1539 Rock Hill Rd	0.80	Seal - Double and Fog Seal	$57,000
2028	10	090-Union	Preservation	SR 1725 Deep Springs Rd	SR 1719 Marsh. Olive Branch	Anson Co Line	1.78	Seal - Double	$83,660
2028	10	090-Union	Preservation	SR 1729 Jim Nash Store Rd	SR 1735 Old Peachland rd	SR 1736 Old Lawyers rd	0.48	Seal - Double	$22,560
2028	10	090-Union	Preservation	SR 1732 High Rd	US 74	SR 1735 Old Peachland rd	0.60	Seal - Double	$28,200
2028	10	090-Union	Preservation	SR 1733 Gaddy Rd	US 74	SR 1735 Old Peachland rd	0.98	Seal - Double	$46,060
2028	10	090-Union	Preservation	SR 1737 Hamilton Cir	SR 1736 Old Lawyers rd	SR 1736 Old Lawyers rd	0.67	Seal - Double	$31,490
2028	10	090-Union	Preservation	SR 1784 Acme Rd	SR 1719 Marsh. Olive Branch	SR 1807 Brice Griffin rd	0.45	Seal - Double	$21,150
2028	10	090-Union	Preservation	SR 1807 Brice Griffin Rd	SR 1719 Marsh. Olive Branch	EOM	0.48	Seal - Double	$22,560
2028	10	090-Union	Preservation	SR 1966 C M James	SR 1901 Hasty Rd	EOM	0.60	Seal - Double	$28,200
2028	10	090-Union	Preservation	SR 1977 Green Acers	SR 1901 Hasty Rd	EOM	0.25	Seal - Double	$12,220
2028	10	090-Union	Preservation	SR 1989 Phillip Sanders Rd	SR 1740 Old Hwy 74	EOM	0.28	Seal - Double	$13,160
2028	10	090-Union	Preservation	SR 2227 Arcadia Ln	SR 2133 E Sandy Ridge Rd	eom	0.24	Seal - Double and Fog Seal	$17,000
2028	10	090-Union	Preservation	SR 2548 High Gate Dr	SR 1317 Weddington Ch	SR 2549 Steeplechase Cir	0.06	Seal - Double and Fog Seal	$4,000
2028	10	090-Union	Preservation	SR 2672 Lake Providence	SR 1346 Beauth Church Rd	eom	0.57	Seal - Double and Fog Seal	$40,500
2028	10	090-Union	Preservation	SR 2690 Valley Glen Dr	SR 2549 Steeplechase Cir	cul de sac	0.38	Seal - Double and Fog Seal	$27,000
2028	10	090-Union	Preservation	SR 2691 Chasestone Ln	SR 2690 Valley Glen	cul de sac	0.09	Seal - Double and Fog Seal	$7,000
2028	10	090-Union	Preservation	SR 2692 Kee Ct	SR 2690 Valley Glen	cul de sac	0.10	Seal - Double and Fog Seal	$7,000
2028	10	090-Union	Preservation	SR 2694 Lago Vista	SR 2672 Lake Providence	eom	0.10	Seal - Double and Fog Seal	$7,000
2028	10	090-Union	Preservation	SR 2695 Lake Point Dr	SR 2672 Lake Providence	eom	0.06	Seal - Double and Fog Seal	$4,000
2028	11	003-Alleghany	Resurfacing	SR 1113	SR 1114	US 21	1.98	Leveling and 1.5" S9.5B	$696,960
2028	11	003-Alleghany	Resurfacing	SR 1118	US 21	SR 1120	1.32	Leveling and 1.5" S9.5B	$417,540
2028	11	003-Alleghany	Resurfacing	SR 1120	US 21	SR 1118	0.65	Leveling and 1.5" S9.5B	$228,800
2028	11	003-Alleghany	Resurfacing	SR 1451	SR 1453	SR 1450	0.72	1.5" S9.5B	$253,440
2028	11	003-Alleghany	Preservation	SR 1134	SR 1133	DE	0.40	Seal - Triple and Fog Seal	$33,790
2028	11	003-Alleghany	Preservation	SR 1157	NC 113	SR 1158	1.99	Seal - Triple and Fog Seal	$149,430
2028	11	003-Alleghany	Preservation	SR 1158	SR 1157	MP 2.57	0.93	Seal - Triple and Fog Seal	$78,560
2028	11	003-Alleghany	Preservation	SR 1407	SR 1415	SR 1410	1.16	Seal - Triple and Fog Seal	$108,890
2028	11	003-Alleghany	Preservation	SR 1410	SR 1407	SR 1411	0.48	Seal - Triple and Fog Seal	$45,060
2028	11	003-Alleghany	Preservation	SR 1411	SR 1412	EOP	1.14	Seal - Triple and Fog Seal	$107,000
2028	11	003-Alleghany	Preservation	SR 1415	SR 1407	SR 1412	0.49	Seal - Triple and Fog Seal	$46,000
2028	11	003-Alleghany	Preservation	SR 1495	NC 18	EOM	0.37	Seal - Triple and Fog Seal	$27,780
2028	11	005-Ashe	Resurfacing	NC 16	SR 1162	SR 1158	2.68	1.5" S9.5C	$1,131,610
2028	11	005-Ashe	Resurfacing	NC 16	WILKES CO	SR 1162	1.92	1.5" S9.5C	$811,430
2028	11	005-Ashe	Resurfacing	SR 1133	SR 1248	SR 1134	0.86	1.5" S9.5B	$438,944
2028	11	005-Ashe	Resurfacing	SR 1361	SR 1359	MP 1.60	1.60	1.5" S9.5B	$506,800
2028	11	005-Ashe	Preservation	SR 1100	SR 1106	SR 1284	1.23	Seal - Triple and Fog Seal	$92,365
2028	11	005-Ashe	Preservation	SR 1100	SR 1284	NC 194	2.90	FDR and 2.0" S9.5B	$714,560
2028	11	005-Ashe	Preservation	SR 1331	SR 1339	EOM	0.99	Seal - Triple and Fog Seal	$83,635
2028	11	006-Avery	Resurfacing	NC 181	Begin Rt Turn Taper at SR 1547	Begin Curb & Gutter	2.26	Full Depth Patching and 1.5" S9.5C	$1,113,730
2028	11	006-Avery	Resurfacing	NC 181	Begin Curb & Gutter	NC 194	0.82	Mill 1.5" and 1.5" S9.5C	$692,740
2028	11	006-Avery	Resurfacing	SR 1121	BEG 17'PVT	SR 1138	0.94	Full Depth Patching and 1.5" S9.5B	$281,250
2028	11	006-Avery	Resurfacing	SR 1121	SR 1114	BEG 17'PVT	1.25	Full Depth Patching and 1.5" S9.5B	$396,000
2028	11	006-Avery	Preservation	SR 1169	US 19E	EOM	0.40	Seal - Triple and Fog Seal	$30,040
2028	11	006-Avery	Preservation	SR 1171	SR 1178	END PAVEMENT	1.48	Seal - Triple and Fog Seal	$111,140
2028	11	006-Avery	Preservation	SR 1206	SR 1143	END MAINTENANCE	0.39	Seal - Triple and Fog Seal	$36,610
2028	11	006-Avery	Preservation	SR 1546	SR 1525	END MAINTENANCE	0.92	Seal - Triple and Fog Seal	$69,080
2028	11	014-Caldwell	Resurfacing	NC 90	SR 1353	SR 1341	1.75	1.5" S9.5C	$554,400
2028	11	014-Caldwell	Resurfacing	SR 1751	SR 1748	SR 1002	1.66	1.5" S9.5B	$584,320
2028	11	014-Caldwell	Resurfacing	SR 1751	SR 1002	MP 6.8	4.24	1.5" S9.5B	$1,492,480
2028	11	014-Caldwell	Resurfacing	SR 1760	US 321	SR 1777	0.20	1.5" S9.5B	$63,360
2028	11	014-Caldwell	Resurfacing	SR 1776	SR 1778	EOM	0.20	1.5" S9.5B	$56,320
2028	11	014-Caldwell	Resurfacing	SR 1777	SR 1778	EOM	0.29	1.5" S9.5B	$81,664
2028	11	014-Caldwell	Resurfacing	SR 1778	SR 1776	SR 1777	0.10	1.5" S9.5B	$28,160
2028	11	014-Caldwell	Resurfacing	SR 1782	US 321 SB	EOM	0.52	Leveling and 1.5" S9.5B	$164,740
2028	11	014-Caldwell	Resurfacing	SR 1935	US 321 SB	EOM	0.21	1.5" S9.5B	$66,528

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	11	014-Caldwell	Resurfacing	US 64	SR 1933	US 321	2.79	Mill 1.5" and 1.5" S9.5C	$3,044,448
2028	11	014-Caldwell	Preservation	SR 1141	BURKE CO LINE	SR 1134	1.38	Seal - Triple and Fog Seal	$129,536
2028	11	014-Caldwell	Preservation	SR 1145	SR 1143	EOM	1.04	Seal - Triple and Fog Seal	$87,859
2028	11	014-Caldwell	Preservation	SR 1195	SR 1115	EOP	0.88	Seal - Triple and Fog Seal	$74,342
2028	11	014-Caldwell	Preservation	SR 1301	SR 1309	SR 1307	0.96	Seal - Triple and Fog Seal	$90,112
2028	11	014-Caldwell	Preservation	SR 1301	SR 1310	SR 1309	0.55	Seal - Triple and Fog Seal	$51,627
2028	11	014-Caldwell	Preservation	SR 1305	SR 1310	EOM	0.86	Seal - Triple and Fog Seal	$72,653
2028	11	014-Caldwell	Preservation	SR 1309	SR 1301	SR 1310	1.20	Seal - Triple and Fog Seal	$101,376
2028	11	014-Caldwell	Preservation	SR 1340	SR 1310	NC 90	1.75	Seal - Triple and Fog Seal	$164,267
2028	11	014-Caldwell	Preservation	SR 1372	MP 1.94	EOM	1.10	Seal - Triple and Fog Seal	$92,675
2028	11	014-Caldwell	Preservation	SR 1428	SR 1353	NC 90	0.90	Seal - Triple and Fog Seal	$84,480
2028	11	086-Surry	Resurfacing	I 74 WB	US 52 NB	Br # 372	0.16	Full Depth Patching and 1.5" S9.5C	$126,720
2028	11	086-Surry	Resurfacing	US 52	avement Joint ~ 50' S of Exit 140 Overhead Sign	Pavement Joint at I-74 EB/US 52 N	1.24	Mill 1.5" and 1.5" S9.5C	$654,720
2028	11	086-Surry	Resurfacing	US 52	RXR at US 601	Hickory Street (NS)	2.33	Mill 1.5" and 1.5" S9.5C	$1,148,224
2028	11	086-Surry	Resurfacing	US 601	BR # 54 Over Yadkin River	NC 268	4.28	1.5" S9.5C	$1,657,216
2028	11	086-Surry	Resurfacing	US 601	Begin SB Rt Turn Taper at US 601	Begin NB Lt Turn Taper at SR 1357	3.44	Full Depth Patching and 1.5" S9.5C	$1,816,320
2028	11	086-Surry	Preservation	SR 1693	SR 1396	EOM	0.30	Seal - Triple and Fog Seal	$28,160
2028	11	086-Surry	Preservation	SR 1752	NC 103	SR 1727	0.35	Seal - Triple and Fog Seal	$26,283
2028	11	086-Surry	Preservation	SR 1788	SR 1787	SR 1848	0.79	Seal - Triple and Fog Seal	$66,739
2028	11	086-Surry	Preservation	SR 1804	NC 89	EOP	0.97	Seal - Triple and Fog Seal	$91,332
2028	11	086-Surry	Preservation	SR 1804	NC 89	EOP	0.56	Seal - Triple and Fog Seal	$52,096
2028	11	086-Surry	Preservation	SR 1848	SR 1789	SR 1788	1.38	Seal - Triple and Fog Seal	$116,582
2028	11	086-Surry	Preservation	SR 1886	NC 268	END MAINTENANCE	0.17	Seal - Triple and Fog Seal	$14,362
2028	11	086-Surry	Preservation	SR 1905	SR 1701	EOM	0.53	Seal - Triple and Fog Seal	$44,774
2028	11	086-Surry	Preservation	SR 1922	SR 1701	EOM	0.05	Seal - Triple and Fog Seal	$4,693
2028	11	086-Surry	Preservation	SR 2033	Bridge	SR 2038	1.68	Seal - Triple and Fog Seal	$157,414
2028	11	086-Surry	Preservation	SR 2036	SR 2037	SR 2035	1.25	Seal - Triple and Fog Seal	$117,333
2028	11	086-Surry	Preservation	SR 2051	SR 1855	PVMT CHNAGE	0.32	Seal - Triple and Fog Seal	$30,037
2028	11	086-Surry	Preservation	SR 2051	PVMT CHANGE	STOKES CO LINE	1.02	Seal - Triple and Fog Seal	$76,595
2028	11	086-Surry	Preservation	SR 2054	SR 2048	END MAINTENANCE	0.86	Seal - Triple and Fog Seal	$72,653
2028	11	086-Surry	Preservation	SR 2099	NC 268	EOM	0.18	Seal - Triple and Fog Seal	$15,206
2028	11	086-Surry	Preservation	SR 2123	SR 2035	SR 2035	0.13	Seal - Triple and Fog Seal	$9,762
2028	11	086-Surry	Preservation	SR 2132	SR 2035	CUL-DE-SAC	0.15	Seal - Triple and Fog Seal	$11,264
2028	11	086-Surry	Preservation	SR 2134	SR 2165	SR 2165	0.09	Seal - Triple and Fog Seal	$8,448
2028	11	086-Surry	Preservation	SR 2159	SR 2165	CUL-DE-SAC	0.19	Seal - Triple and Fog Seal	$17,835
2028	11	086-Surry	Preservation	SR 2230	DETROIT SALT	SR 1003	0.31	Seal - Triple and Fog Seal	$32,009
2028	11	086-Surry	Preservation	SR 2231	SR 2230	SR 1003	1.70	Seal - Triple and Fog Seal	$159,573
2028	11	086-Surry	Preservation	SR 2251	SR 2258	EOM	0.20	Seal - Triple and Fog Seal	$18,773
2028	11	086-Surry	Preservation	SR 2252	SR 2251	EOM	0.13	Seal - Triple and Fog Seal	$12,203
2028	11	086-Surry	Preservation	SR 2253	SR 2252	EOM	0.10	Seal - Triple and Fog Seal	$9,387
2028	11	086-Surry	Preservation	SR 2254	SR 2253	SR 2255	0.07	Seal - Triple and Fog Seal	$6,571
2028	11	086-Surry	Preservation	SR 2255	BOM	EOM	0.10	Seal - Triple and Fog Seal	$9,387
2028	11	086-Surry	Preservation	SR 2262	SR 2223	DE	0.20	Seal - Triple and Fog Seal	$18,773
2028	11	086-Surry	Preservation	SR 2401	SR 1624	EOM	0.31	Seal - Triple and Fog Seal	$29,099
2028	11	086-Surry	Preservation	SR 2408	SR 1625	SR 2409	0.42	Seal - Triple and Fog Seal	$39,424
2028	11	086-Surry	Preservation	SR 2409	CUL-DE-SAC	SR 2430	0.72	Seal - Triple and Fog Seal	$67,584
2028	11	086-Surry	Preservation	SR 2413	SR 1624	CUL-DE-SAC	0.28	Seal - Triple and Fog Seal	$26,283
2028	11	086-Surry	Preservation	SR 2414	SR 2401	SR 2413	0.09	Seal - Triple and Fog Seal	$8,448
2028	11	086-Surry	Preservation	SR 2416	SR 1625	SR 2417	0.11	Seal - Triple and Fog Seal	$10,325
2028	11	086-Surry	Preservation	SR 2417	SR 2416	EOM	0.15	Seal - Triple and Fog Seal	$14,080
2028	11	086-Surry	Preservation	SR 2418	SR 1622	DE	0.34	Seal - Triple and Fog Seal	$25,532
2028	11	086-Surry	Preservation	SR 2421	NC 89	EOM	0.11	Seal - Triple and Fog Seal	$12,390
2028	11	086-Surry	Preservation	SR 2422	SR 2409	DE	0.13	Seal - Triple and Fog Seal	$10,982
2028	11	086-Surry	Preservation	SR 2424	SR 1682	EOM	0.11	Seal - Triple and Fog Seal	$10,325
2028	11	086-Surry	Preservation	SR 2429	SR 2409	DE	0.22	Seal - Triple and Fog Seal	$20,651
2028	11	086-Surry	Preservation	SR 2430	SR 2409	CUL-DE-SAC	0.06	Seal - Triple and Fog Seal	$4,506
2028	11	086-Surry	Preservation	SR 2434	SR 1624	EOM	0.57	Seal - Triple and Fog Seal	$53,504
2028	11	086-Surry	Preservation	SR 2441	SR 1605	SR 2442	0.20	Seal - Triple and Fog Seal	$18,773
2028	11	086-Surry	Preservation	SR 2442	SR 2441	CUL-DE-SAC	0.08	Seal - Triple and Fog Seal	$7,509

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	11	086-Surry	Preservation	SR 2451	SR 1627	EOM	0.24	Seal - Triple and Fog Seal	$20,275
2028	11	086-Surry	Preservation	SR 2452	SR 1627	EOM	0.13	Seal - Triple and Fog Seal	$10,982
2028	11	086-Surry	Preservation	SR 2454	SR 1605	CuldeSac	0.36	Seal - Triple and Fog Seal	$33,792
2028	11	095-Watauga	Resurfacing	SR 1130	SR 1122	SR 1182	1.99	1.5" S9.5B	$630,430
2028	11	095-Watauga	Resurfacing	SR 1328	SR 1401	EOP	1.66	1.5" S9.5B	$525,888
2028	11	095-Watauga	Resurfacing	SR 1511	SR 1510	EOM	2.24	Leveling and 1.5" S9.5B	$630,220
2028	11	095-Watauga	Resurfacing	SR 1557	SR 1568	SR 1552	2.57	1.5" S9.5B	$814,170
2028	11	095-Watauga	Resurfacing	US 321	SR 1128	Avery Co	2.06	1.5" S9.5C	$870,144
2028	11	095-Watauga	Preservation	SR 1136	NC 105	SR 1137	2.25	Seal - Triple and Fog Seal	$190,080
2028	11	095-Watauga	Preservation	SR 1166	SR 1222	END MAINTENANCE	0.51	Seal - Triple and Fog Seal	$38,298
2028	11	095-Watauga	Preservation	SR 1320	SR 1306	EOM	0.72	Seal - Triple and Fog Seal	$54,067
2028	11	095-Watauga	Preservation	SR 1384	SR 1340	END Maintenance	1.17	Seal - Triple and Fog Seal	$99,095
2028	11	095-Watauga	Preservation	SR 1399	SR 1340	EOM	0.28	Seal - Triple and Fog Seal	$21,026
2028	11	095-Watauga	Preservation	SR 1414	SR 1335	END Maintenance	0.60	Seal - Triple and Fog Seal	$45,281
2028	11	095-Watauga	Preservation	SR 1501	PVMT Change	SR 1505	0.94	Seal - Triple and Fog Seal	$88,047
2028	11	095-Watauga	Preservation	SR 1541	BRIDGE # 0016	SR 1547/END PVMT	1.30	Seal - Triple and Fog Seal	$122,214
2028	11	097-Wilkes	Resurfacing	NC 16	SR 1191	SR 1190	1.91	1.5" S9.5C	$874,016
2028	11	097-Wilkes	Resurfacing	NC 18	SR 1106	NC 16	2.83	1.5" S9.5C	$1,444,430
2028	11	097-Wilkes	Resurfacing	RMP 5902	US 421 NB	SR 2309	0.36	Full Depth Patching and 1.5" S9.5C	$202,752
2028	11	097-Wilkes	Resurfacing	SR 1317	SR 1368	SR 1346	1.75	1.5" S9.5B	$616,000
2028	11	097-Wilkes	Resurfacing	SR 1372	SR 1500	SR 1510/RCI Project Limits	0.82	1.5" S9.5B	$317,504
2028	11	097-Wilkes	Resurfacing	SR 1517	SR 1518	SR 1502	1.31	1.5" S9.5B	$461,120
2028	11	097-Wilkes	Resurfacing	SR 1713	SR 1002	SR 1707	1.52	1.5" S9.5B	$481,536
2028	11	097-Wilkes	Resurfacing	US 421	Yadkin Co Line	BR # 762 Over Clingman Rd	3.21	Full Depth Patching and 1.5" S9.5C	$1,694,880
2028	11	097-Wilkes	Preservation	SR 1148	SR 1150	END 20' PVMT	0.76	Seal - Triple and Fog Seal	$71,339
2028	11	097-Wilkes	Preservation	SR 1148	SR 1154	SR 1150	2.47	Seal - Triple and Fog Seal	$208,666
2028	11	097-Wilkes	Preservation	SR 1148	END 20' PVMT	CUL-DE-SAC	1.20	Seal - Triple and Fog Seal	$100,954
2028	11	097-Wilkes	Preservation	SR 1165	Caldwell Co Line	END PVMT	0.05	Seal - Triple and Fog Seal	$3,802
2028	11	097-Wilkes	Preservation	SR 1178	NC 268	EOM	0.50	Seal - Triple and Fog Seal	$56,320
2028	11	097-Wilkes	Preservation	SR 1326	SR 1325	SR 1446	0.39	Seal - Triple and Fog Seal	$36,608
2028	11	097-Wilkes	Preservation	SR 1394	NC 16	DE	0.30	Seal - Triple and Fog Seal	$28,160
2028	11	097-Wilkes	Preservation	SR 1552	SR 1372	SR 1550	1.16	Seal - Triple and Fog Seal	$97,997
2028	11	097-Wilkes	Preservation	SR 1578	SR 1500	EOM	0.50	Seal - Triple and Fog Seal	$46,933
2028	11	097-Wilkes	Preservation	SR 1757	SR 1756	DE	0.10	Seal - Triple and Fog Seal	$7,509
2028	11	097-Wilkes	Preservation	SR 2055	SR 2051	SR 2026	0.18	Seal - Triple and Fog Seal	$13,517
2028	11	097-Wilkes	Preservation	SR 2068	SR 1002	DE	0.30	Seal - Triple and Fog Seal	$22,528
2028	11	097-Wilkes	Preservation	SR 2075	SR 1701	EOP	0.20	Seal - Triple and Fog Seal	$15,019
2028	11	097-Wilkes	Preservation	SR 2112	SR 1002	CUL-DE-SAC	0.20	Seal - Triple and Fog Seal	$18,773
2028	11	097-Wilkes	Preservation	SR 2132	SR 1916	EOM	0.30	Seal - Triple and Fog Seal	$22,528
2028	11	097-Wilkes	Preservation	SR 2409	Yadkin Co Line	SR 2408	0.91	Seal - Triple and Fog Seal	$76,877
2028	11	097-Wilkes	Preservation	SR 2417	SR 2416	EOM	0.91	Seal - Triple and Fog Seal	$68,335
2028	11	097-Wilkes	Preservation	SR 2451	SR 2510	EOM	0.20	Seal - Triple and Fog Seal	$15,019
2028	11	097-Wilkes	Preservation	SR 2481	SR 2480	EOM	1.30	Seal - Triple and Fog Seal	$109,824
2028	11	097-Wilkes	Preservation	SR 2517	SR 2418	EOM	0.18	Seal - Triple and Fog Seal	$15,206
2028	11	097-Wilkes	Preservation	SR 2527	SR 2526	EOM	0.13	Seal - Triple and Fog Seal	$10,982
2028	11	097-Wilkes	Preservation	SR 2538	SR 2467	EOM	0.43	Seal - Triple and Fog Seal	$36,326
2028	11	097-Wilkes	Preservation	SR 2543	US 421 B	EOM	0.16	Seal - Triple and Fog Seal	$27,034
2028	11	097-Wilkes	Preservation	SR 2546	SR 2538	SR 2550	0.51	Seal - Triple and Fog Seal	$43,085
2028	11	097-Wilkes	Preservation	SR 2550	SR 2546	EOM	0.41	Seal - Triple and Fog Seal	$34,637
2028	11	097-Wilkes	Preservation	SR 2566	SR 2433	SR 2433	0.48	Seal - Triple and Fog Seal	$40,550
2028	11	097-Wilkes	Preservation	SR 2576	YADKIN Co Line	BEG 36'	3.01	Seal - Triple and Fog Seal	$324,919
2028	11	097-Wilkes	Preservation	SR 2576	BEG 36'	END 36'	0.29	Seal - Triple and Fog Seal	$48,998
2028	11	099-Yadkin	Resurfacing	SR 1316	SR 1434	US 21	1.69	1.5" S9.5B	$594,880
2028	11	099-Yadkin	Resurfacing	SR 1331	SR 1314	SR 1361	6.91	1.5" S9.5B	$2,310,700
2028	11	099-Yadkin	Resurfacing	SR 1331	SR 1361	SR 1352	2.79	1.5" S9.5B	$932,760
2028	11	099-Yadkin	Preservation	SR 1128	SR 1126	CUL-DE-SAC	0.60	Seal - Triple and Fog Seal	$50,688
2028	11	099-Yadkin	Preservation	SR 1131	EOM	US 21	0.50	Seal - Triple and Fog Seal	$46,933
2028	11	099-Yadkin	Preservation	SR 1133	SR 1132	EOM	0.80	Seal - Triple and Fog Seal	$67,584
2028	11	099-Yadkin	Preservation	SR 1156	SR 1002	IREDELL CO LINE	0.60	Seal - Triple and Fog Seal	$56,320

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	11	099-Yadkin	Preservation	SR 1157	SR 1002	IREDELL CO LINE	0.42	Seal - Triple and Fog Seal	$35,482
2028	11	099-Yadkin	Preservation	SR 1208	SR 1175	END MAINT	0.06	Seal - Triple and Fog Seal	$5,069
2028	11	099-Yadkin	Preservation	SR 1312	US 21 Bus	SR 1311	0.88	Seal - Triple and Fog Seal	$82,603
2028	11	099-Yadkin	Preservation	SR 1377	SR 1370	CUL-DE-SAC	0.80	Seal - Triple and Fog Seal	$67,584
2028	11	099-Yadkin	Preservation	SR 1411	SR 1312	SR 1312	0.49	Seal - Triple and Fog Seal	$45,995
2028	11	099-Yadkin	Preservation	SR 1415	US 601	MP 0.28	0.28	Seal - Triple and Fog Seal	$31,539
2028	11	099-Yadkin	Preservation	SR 1415	MP 0.28	SR 1134	1.20	Seal - Triple and Fog Seal	$112,640
2028	11	099-Yadkin	Preservation	SR 1437	SR 1311	EOM	0.14	Seal - Triple and Fog Seal	$11,827
2028	11	099-Yadkin	Preservation	SR 1451	SR 1134	SR 1452	0.09	Seal - Triple and Fog Seal	$8,448
2028	11	099-Yadkin	Preservation	SR 1452	SR 1451	EOM	0.08	Seal - Triple and Fog Seal	$7,509
2028	11	099-Yadkin	Preservation	SR 1453	SR 1452	EOM	0.10	Seal - Triple and Fog Seal	$9,387
2028	11	099-Yadkin	Preservation	SR 1501	SR 1500	EOM	0.18	Seal - Triple and Fog Seal	$13,517
2028	11	099-Yadkin	Preservation	SR 1714	SR 1605	CUL-DE-SAC	1.10	Seal - Triple and Fog Seal	$92,928
2028	12	002-Alexander	Resurfacing	SR 1005	NC 90	SR 1617	1.41	1.0" S9.5B	$200,220
2028	12	002-Alexander	Resurfacing	SR 1130	SR 1124	DEAD END	0.50	1.5" S9.5C	$76,347
2028	12	002-Alexander	Resurfacing	SR 1148	SR 1137	Lake Point Circle (Non-System)	1.50	1.5" S9.5C	$228,888
2028	12	002-Alexander	Resurfacing	SR 1182	SR 1150	DEAD END	0.18	1.0" S9.5B	$26,128
2028	12	002-Alexander	Resurfacing	SR 1195	NC 127	DEAD END	0.22	1.0" S9.5B	$31,098
2028	12	002-Alexander	Resurfacing	SR 1292	SR 1809	DEAD END	0.06	1.0" S9.5B	$8,804
2028	12	002-Alexander	Resurfacing	SR 1293	SR 1809	DEAD END	0.10	1.0" S9.5B	$13,490
2028	12	002-Alexander	Resurfacing	SR 1294	SR 1137	DEAD END	0.21	1.0" S9.5B	$29,536
2028	12	002-Alexander	Resurfacing	SR 1295	SR 1294	DEAD END	0.05	1.0" S9.5B	$6,674
2028	12	002-Alexander	Resurfacing	SR 1302	SR 1348	END PVMT.	3.74	1.5" S9.5B	$521,849
2028	12	002-Alexander	Resurfacing	SR 1462	SR 1456	IREDELL CO.	2.52	1.5" S9.5B	$316,204
2028	12	002-Alexander	Resurfacing	SR 1470	SR 1461	SR 1461	0.72	1.5" S9.5B	$111,135
2028	12	002-Alexander	Resurfacing	SR 1472	SR 1456	SR 1468	1.78	1.5" S9.5B	$223,476
2028	12	002-Alexander	Resurfacing	SR 1498	SR 1502	SR 1422	2.39	1.5" S9.5B	$333,353
2028	12	002-Alexander	Resurfacing	SR 1549	SR 1409	END PVMT.	0.47	1.0" S9.5B	$66,030
2028	12	002-Alexander	Resurfacing	SR 1554	SR 1549	DEAD END	0.10	1.0" S9.5B	$14,626
2028	12	002-Alexander	Resurfacing	SR 1600	SR 1605	NC 90	0.81	1.5" S9.5C	$123,777
2028	12	002-Alexander	Resurfacing	SR 1601	SR 1600	SR 1604	0.47	1.5" S9.5C	$72,063
2028	12	002-Alexander	Resurfacing	SR 1605	SR 1610	SR 1600	4.52	1.5" S9.5C	$691,560
2028	12	002-Alexander	Resurfacing	SR 1610	SR 1605	NC 16	3.34	1.5" S9.5C	$511,020
2028	12	002-Alexander	Resurfacing	SR 1611	SR 1682	END PVMT.	0.48	1.0" S9.5B	$67,876
2028	12	002-Alexander	Resurfacing	SR 1622	SR 1605	END PVMT.	1.31	1.5" S9.5B	$165,000
2028	12	002-Alexander	Resurfacing	SR 1622	BEGIN PVMT.	SR 1605	0.27	1.5" S9.5B	$105,350
2028	12	002-Alexander	Resurfacing	SR 1646	SR 1601	SR 1646	0.33	1.0" S9.5B	$46,860
2028	12	002-Alexander	Resurfacing	SR 1656	NC 90	END PVMT.	0.50	1.0" S9.5B	$70,858
2028	12	002-Alexander	Resurfacing	SR 1669	SR 1630	END PVMT.	0.27	1.0" S9.5B	$38,908
2028	12	002-Alexander	Resurfacing	SR 1676	SR 1005	END PVMT.	0.22	1.0" S9.5B	$30,530
2028	12	002-Alexander	Resurfacing	SR 1682	NC 16	Dead End	1.04	1.5" S9.5B	$144,578
2028	12	002-Alexander	Resurfacing	SR 1693	SR 1604	SR 1694	0.12	1.0" S9.5B	$17,324
2028	12	002-Alexander	Resurfacing	SR 1694	CUL DE SAC	CUL DE SAC	0.23	1.0" S9.5B	$23,944
2028	12	002-Alexander	Resurfacing	SR 1809	SR 1149	SR 1294	0.19	1.0" S9.5B	$26,412
2028	12	002-Alexander	Resurfacing	SR 1813	SR 1149	DEAD END	0.08	1.0" S9.5B	$10,792
2028	12	002-Alexander	Resurfacing	SR 1854	SR 1137	END MAINT.	0.47	1.0" S9.5B	$66,740
2028	12	002-Alexander	Resurfacing	SR 1855	SR 1854	SR 1856	0.26	1.0" S9.5B	$36,920
2028	12	002-Alexander	Resurfacing	SR 1856	SR 1855	DEAD END	0.42	1.0" S9.5B	$59,214
2028	12	002-Alexander	Resurfacing	SR 1857	SR 1855	DEAD END	0.11	1.0" S9.5B	$15,620
2028	12	002-Alexander	Resurfacing	SR 1905	SR 1656	DEAD END	0.06	1.0" S9.5B	$8,378
2028	12	002-Alexander	Resurfacing	US 64	SR 1165 Caldwell Pond Rd	SR 1348 Old NC 90	2.39	2.0" S9.5C	$466,499
2028	12	002-Alexander	Preservation	SR 1153	NC 127	SR 1152	1.76	.75" S4.75A	$176,533
2028	12	002-Alexander	Preservation	SR 1155	SR 1153	SR 1150	0.66	Seal - Double and Fog Seal	$23,100
2028	12	002-Alexander	Preservation	SR 1162	NC 127	End Of Maint.	0.60	.75" S4.75A	$57,205
2028	12	002-Alexander	Preservation	SR 1163	NC127	Dead End	0.48	.75" S4.75A	$45,573
2028	12	002-Alexander	Preservation	SR 1264	SR 1150	Dead End	0.50	.75" S4.75A	$50,180
2028	12	002-Alexander	Preservation	SR 1331	SR 1334	SR 1332	0.99	Seal - Double and Fog Seal	$34,650
2028	12	002-Alexander	Preservation	SR 1331	SR 1329	SR 1334	1.51	Seal - Double and Fog Seal	$52,850
2028	12	002-Alexander	Preservation	SR 1331	NC 16	SR 1329	1.07	Seal - Double and Fog Seal	$37,450

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	12	002-Alexander	Preservation	SR 1333	SR 1332 (Minus 0.11 Miles)	SR 1311	0.62	Seal - Double and Fog Seal	$21,700
2028	12	002-Alexander	Preservation	SR 1335	PVMT CHANGE	WILKES CO	0.73	Seal - Double	$25,550
2028	12	002-Alexander	Preservation	SR 1337	SR 1338	NC 16	1.79	Seal - Double and Fog Seal	$62,650
2028	12	002-Alexander	Preservation	SR 1338	NC 16	SR 1331	1.89	Seal - Double and Fog Seal	$66,150
2028	12	002-Alexander	Preservation	SR 1344	SR 1138	End of Maint.	0.60	Seal - Double and Fog Seal	$21,000
2028	12	002-Alexander	Preservation	SR 1353	SR 1365	Dead End	0.53	Seal - Double and Fog Seal	$18,550
2028	12	002-Alexander	Preservation	SR 1365	NC 16	NC 16	0.53	Seal - Double and Fog Seal	$18,550
2028	12	002-Alexander	Preservation	SR 1441	SR 1442	SR 1001	1.15	Seal - Double	$40,180
2028	12	002-Alexander	Preservation	SR 1521	SR 1403	SR 1431	0.62	Seal - Double	$21,735
2028	12	002-Alexander	Preservation	SR 1547	SR 1419	DEAD END	0.57	Seal - Double	$19,775
2028	12	002-Alexander	Preservation	SR 1621	SR 1605	SR 1620	2.06	Seal - Double	$72,030
2028	12	002-Alexander	Preservation	SR 1665	SR 1682	Blue Grass Lane (Private)	0.97	.75" S4.75A	$96,847
2028	12	018-Catawba	Resurfacing	SR 1005	SR 2007	SR 2932	7.76	Full Depth Patching and 1.5" S9.5C	$1,940,000
2028	12	018-Catawba	Resurfacing	SR 1402	SR 1404	SR 1453	1.51	Full Depth Patching and 1.5" S9.5B	$378,500
2028	12	018-Catawba	Resurfacing	SR 1485	SR 1007	SR 1484	0.52	Full Depth Patching and 1.5" S9.5B	$161,250
2028	12	018-Catawba	Resurfacing	SR 1485	SR 1484	NC 16 BUS	0.65	Full Depth Patching and 1.5" S9.5B	$130,000
2028	12	018-Catawba	Resurfacing	SR 1712	NC 16	SR 1709	1.09	Full Depth Patching and 1.5" S9.5B	$272,500
2028	12	018-Catawba	Resurfacing	SR 1762	SR 1722	DEAD END	0.22	Patching and 1.0" S9.5A	$54,500
2028	12	018-Catawba	Resurfacing	SR 1827	SR 1004	END MAINT	0.50	Patching and 1.0" S9.5A	$124,000
2028	12	018-Catawba	Resurfacing	SR 1830	SR 1004	END MAINT	0.79	Patching and 1.0" S9.5A	$196,750
2028	12	018-Catawba	Resurfacing	SR 1913	NC 16	SR 1914	0.09	Full Depth Patching and 1.5" S9.5B	$21,250
2028	12	018-Catawba	Resurfacing	SR 1914	SR 1913	DEAD END	0.27	Patching and 1.0" S9.5A	$66,500
2028	12	018-Catawba	Resurfacing	SR 1927	US 321 BUS	END MAINT	0.12	Full Depth Patching and 1.5" S9.5C	$30,000
2028	12	018-Catawba	Resurfacing	SR 1947	SR 1880	End Maint	0.71	Patching and 1.0" S9.5A	$177,500
2028	12	018-Catawba	Resurfacing	SR 2066	US 321 Bus	Dead End	0.37	Full Depth Patching and 1.5" S9.5C	$92,500
2028	12	018-Catawba	Resurfacing	SR 2096	SR 2008	SR 2097	0.15	Full Depth Patching and 1.25" S9.5B	$37,500
2028	12	018-Catawba	Resurfacing	SR 2097	SR 2098	SR 2098	0.30	Full Depth Patching and 1.25" S9.5B	$75,750
2028	12	018-Catawba	Resurfacing	SR 2098	SR 2097	DEAD END	0.38	Patching and 1.0" S9.5A	$95,500
2028	12	018-Catawba	Resurfacing	SR 2119	SR 2007	DEAD END	0.14	Full Depth Patching and 1.25" S9.5A	$35,000
2028	12	018-Catawba	Resurfacing	SR 2136	SR 1880	DEAD END	0.28	Patching and 1.0" S9.5A	$70,000
2028	12	018-Catawba	Resurfacing	SR 2137	SR 1947	SR 2136	0.37	Patching and 1.0" S9.5A	$91,250
2028	12	018-Catawba	Resurfacing	SR 2138	SR 1947	SR 2136	0.34	Patching and 1.0" S9.5A	$85,000
2028	12	018-Catawba	Resurfacing	SR 2139	SR 2138	DEAD END	0.04	Patching and 1.0" S9.5A	$10,000
2028	12	018-Catawba	Resurfacing	SR 2140	SR 2138	DEAD END	0.06	Patching and 1.0" S9.5A	$14,750
2028	12	018-Catawba	Resurfacing	SR 2438	SR 1715	US 70	1.87	Full Depth Patching and 1.5" S9.5B	$466,250
2028	12	018-Catawba	Resurfacing	SR 2612	SR 1947	SR 2617	0.22	Patching and 1.0" S9.5A	$55,000
2028	12	018-Catawba	Resurfacing	SR 2617	SR 1880	SR 2721	0.30	Patching and 1.0" S9.5A	$74,000
2028	12	018-Catawba	Resurfacing	SR 2654	SR 1947	SR 2617	0.28	Patching and 1.0" S9.5A	$70,000
2028	12	018-Catawba	Resurfacing	SR 2704	SR 2654	END MAINT	0.23	Patching and 1.0" S9.5A	$57,500
2028	12	018-Catawba	Resurfacing	SR 2720	SR 2704	SR 2617	0.19	Patching and 1.0" S9.5A	$47,500
2028	12	018-Catawba	Resurfacing	SR 2721	SR 2720	SR 2617	0.22	Patching and 1.0" S9.5A	$54,500
2028	12	018-Catawba	Resurfacing	SR 2743	US 70	DEAD END	0.16	Patching and 1.0" S9.5A	$40,000
2028	12	018-Catawba	Resurfacing	US 321	LINCOLN CO	MM 3.33	6.70	Mill 1.5" and 1.5" S9.5C	$1,675,000
2028	12	018-Catawba	Resurfacing	US 321	NC 10	Jacobs Fork River	7.02	Mill 1.5" and 1.5" S9.5C	$1,755,000
2028	12	018-Catawba	Preservation	SR 1002	SR 1124	SR 1104	5.80	Microsurface	$311,750
2028	12	018-Catawba	Preservation	SR 1104	NC 10	SR 1002	3.06	Microsurface	$164,313
2028	12	018-Catawba	Preservation	SR 1107	SR 1002	SR 1105	1.31	Microsurface	$70,412
2028	12	018-Catawba	Preservation	SR 1113	SR 1002	Burke Co	0.68	Microsurface	$36,550
2028	12	018-Catawba	Preservation	SR 1114	SR 1113	Burke Co	0.38	Microsurface	$20,425
2028	12	018-Catawba	Preservation	SR 1124	SR 1266	BURKE CO	4.62	Microsurface	$248,325
2028	12	018-Catawba	Preservation	SR 1125	SR 1002	SR 1124	1.29	Microsurface	$69,068
2028	12	018-Catawba	Preservation	SR 3103	SR 1003	Dead End	0.64	.75" S4.75A	$71,232
2028	12	018-Catawba	Preservation	SR 3104	SR 3105	SR 3105	0.43	.75" S4.75A	$48,048
2028	12	018-Catawba	Preservation	SR 3105	SR 3103	SR 3104	0.58	.75" S4.75A	$64,960
2028	12	023-Cleveland	Resurfacing	40001001	NC 182	NC 150	6.20	1.5" S9.5B	$786,439
2028	12	023-Cleveland	Resurfacing	40002016	SR 2033	SR 2033	0.61	1.5" S9.5B	$231,398
2028	12	023-Cleveland	Resurfacing	NC 150	US. 74 business	US 74 bypass	0.90	1.5" S9.5C	$492,398
2028	12	023-Cleveland	Resurfacing	NC 182	S.R. 1001	Lincoln Co Line	2.18	1.5" S9.5B	$686,117
2028	12	023-Cleveland	Resurfacing	NC 226	US 29	SR 2226	2.00	1.5" S9.5B	$506,941

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	12	023-Cleveland	Resurfacing	SR 1110	1105	NC 18	1.37	1.5" S9.5B	$330,398
2028	12	023-Cleveland	Resurfacing	SR 1127	SR 1121	NC 150	0.79	1.5" S9.5B	$248,774
2028	12	023-Cleveland	Resurfacing	SR 1345	NC 226	EOP	0.45	1.5" S9.5B	$209,878
2028	12	023-Cleveland	Resurfacing	SR 1373	SR 1376	NC 226	1.56	1.5" S9.5B	$336,633
2028	12	023-Cleveland	Resurfacing	SR 1533	RUTHERFORD CO	NC 10	3.95	1.5" S9.5B	$609,706
2028	12	023-Cleveland	Resurfacing	SR 1601	NC 18	CUL DE SAC	0.60	1.5" S9.5B	$225,894
2028	12	023-Cleveland	Resurfacing	SR 1637	SR 1650	SR 1635	5.22	1.5" S9.5B and Widen	$755,566
2028	12	023-Cleveland	Resurfacing	SR 1639	SR 1637	SR 1004	3.90	1.5" S9.5B and Widen	$604,558
2028	12	023-Cleveland	Resurfacing	SR 2018	SR 2014	SR 2015	1.43	1.5" S9.5B	$322,447
2028	12	023-Cleveland	Resurfacing	SR 2169	SR 2167	SR 2194	0.61	1.5" S9.5B	$227,953
2028	12	023-Cleveland	Resurfacing	SR 2201	US 74	SR 2201	2.11	1.5" S9.5B	$429,398
2028	12	023-Cleveland	Resurfacing	SR 2218	SR 2224	SR 2225	1.60	1.5" S9.5B	$341,438
2028	12	023-Cleveland	Resurfacing	SR 2221	SR 2220	SR 2224	1.06	1.5" S9.5B	$279,547
2028	12	023-Cleveland	Resurfacing	SR 2654	SR 2002	GASTON CO	0.38	1.5" S9.5B	$207,990
2028	12	023-Cleveland	Resurfacing	US 29	SR 2276	I-85	1.45	1.5" S9.5C	$666,534
2028	12	023-Cleveland	Preservation	40001514	SR 1004	SR 1509	1.48	Seal - Double	$63,412
2028	12	023-Cleveland	Preservation	40001519	EOP	SR 1518	0.69	Seal - Double	$36,613
2028	12	023-Cleveland	Preservation	40001526	SR 1523	D.E.	0.89	Seal - Double	$43,648
2028	12	023-Cleveland	Preservation	40001529	SR 1533	EOP	2.43	Seal - Double	$81,400
2028	12	023-Cleveland	Preservation	40001531	SR 1530	SR 1529	0.78	Seal - Double	$39,628
2028	12	023-Cleveland	Preservation	40001544	SR 1544	D.E.	0.61	Seal - Double	$69,000
2028	12	023-Cleveland	Preservation	40001817	NC 182	SR 1364	1.97	Seal - Double	$79,491
2028	12	023-Cleveland	Preservation	Bachelor Rd	SR 1198	NC 150	0.66	Seal - Double and Fog Seal	$23,775
2028	12	023-Cleveland	Preservation	Fox Place	SR 1209	DE	0.47	Seal - Double	$40,431
2028	12	023-Cleveland	Preservation	Hamrick Sand Rd	SR 1198	DE	0.95	Seal - Double and Fog Seal	$47,722
2028	12	023-Cleveland	Preservation	Mort Rd	SC Line	BS000902	1.60	Seal - Double and Fog Seal	$74,380
2028	12	023-Cleveland	Preservation	Mt. Sinai /Riverhill Rd	NC 18	SR 1148	5.84	Seal - Double and Fog Seal	$192,961
2028	12	023-Cleveland	Preservation	S.R. 1651	NC 18	SR 1653	1.10	Seal - Double	$55,000
2028	12	023-Cleveland	Preservation	SR 1186	SR 1003	SR 1003	1.11	Seal - Double	$52,350
2028	12	023-Cleveland	Preservation	SR 1619	NC 18	SR 1603	1.50	Seal - Double	$96,000
2028	12	036-Gaston	Resurfacing	NC 273	LANIER ST	SR 1992	5.95	1.5" S9.5B	$1,100,000
2028	12	036-Gaston	Resurfacing	NC 7	I-85	SR 2230	2.00	1.0" S9.5B	$600,000
2028	12	036-Gaston	Resurfacing	SR 1800	SR1804	SR1001	1.24	1.5" S9.5B	$164,000
2028	12	036-Gaston	Resurfacing	SR 1901	LINC CO	SR 1820	0.40	1.5" S9.5B	$72,700
2028	12	036-Gaston	Resurfacing	SR 1902	SR 1820	LINC CO	0.48	1.5" S9.5B	$85,500
2028	12	036-Gaston	Resurfacing	SR 1923	SR 1918	BRIDGE	4.15	1.5" S9.5B	$730,250
2028	12	036-Gaston	Resurfacing	SR 2200	NC 279	SR 2446	2.02	1.5" S9.5B	$762,500
2028	12	036-Gaston	Resurfacing	SR 2209	NC 7	US 29	0.62	1.5" S9.5B	$125,500
2028	12	036-Gaston	Resurfacing	SR 2436	NC 279	D. END	0.95	1.5" S9.5B	$36,000
2028	12	036-Gaston	Resurfacing	SR 2445	SR 2200	SR 2439	1.42	1.5" S9.5B	$248,500
2028	12	036-Gaston	Resurfacing	SR 2534	NC 273	D END	0.71	1.5" S9.5B	$124,900
2028	12	036-Gaston	Resurfacing	SR 2680	US 321	D END	0.30	1.5" S9.5B	$52,500
2028	12	036-Gaston	Resurfacing	SR 2799	SR 2680	D END	0.28	1.5" S9.5B	$49,000
2028	12	036-Gaston	Resurfacing	SR 3078	SR 2799	D END	0.10	1.5" S9.5B	$16,000
2028	12	036-Gaston	Resurfacing	SR1306	NC274	SR1309	0.83	1.5" S9.5B	$109,800
2028	12	036-Gaston	Resurfacing	SR2200	SR2446	NC279	1.11	1.5" S9.5B	$310,000
2028	12	036-Gaston	Resurfacing	SR2209	SR 2491	SR 2439	1.07	1.5" S9.5B	$187,200
2028	12	036-Gaston	Resurfacing	SR2349	NC 7	US 29	0.65	1.5" S9.5B	$100,000
2028	12	036-Gaston	Resurfacing	SR2431	S.C.	SR2435	2.59	1.5" S9.5C	$292,000
2028	12	036-Gaston	Resurfacing	SR2445	SR2446	SR2200	1.52	1.5" S9.5B	$209,800
2028	12	036-Gaston	Resurfacing	SR2650	SR2431	S.C.	2.43	1.5" S9.5C	$285,400
2028	12	036-Gaston	Resurfacing	SR2663	SR2420	D.END	0.30	1.5" S9.5B	$40,400
2028	12	036-Gaston	Resurfacing	SR2715	SR2711	SR2442	0.46	1.5" S9.5B	$85,500
2028	12	036-Gaston	Resurfacing	US 321 N	SC LINE	SR 1136	3.73	1.5" S9.5C	$1,100,000
2028	12	036-Gaston	Resurfacing	US29/74	S. FORK BRIDGE	MECK CL	3.75	1.5" S9.5C	$800,000
2028	12	036-Gaston	Resurfacing	US29/74	LINEBERGER RD	S.FORK BRIDGE	2.95	1.5" S9.5C	$800,000
2028	12	036-Gaston	Preservation	SR 1262	SR 1201	D END	0.30	1.0" S9.5B	$30,000
2028	12	036-Gaston	Preservation	SR 1280	SR 1195	SR 1283	0.24	1.0" S9.5B	$17,900
2028	12	036-Gaston	Preservation	SR 1281	SR 1131	D END	0.15	1.0" S9.5B	$11,200

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	12	036-Gaston	Preservation	SR 1283	D END	D END	0.20	1.0" S9.5B	$20,000
2028	12	036-Gaston	Preservation	SR 1291	SR 1125	D END	1.11	Microsurface	$46,000
2028	12	036-Gaston	Preservation	SR 1295	SR 1112	D.END	0.22	1.0" S9.5B	$21,000
2028	12	036-Gaston	Preservation	SR 1299	SR 1103	DEAD END	0.36	1.0" S9.5B	$36,000
2028	12	036-Gaston	Preservation	SR 1313	SR 11312	D E	0.29	1.0" S9.5B	$22,500
2028	12	036-Gaston	Preservation	SR 1378	US 29	D END	0.21	1.0" S9.5B	$11,275
2028	12	036-Gaston	Preservation	SR 1420	NC 274	NC 274	0.21	1.0" S9.5B	$7,300
2028	12	036-Gaston	Preservation	SR 1439	SR 1440	D E	0.50	1.0" S9.5B	$27,500
2028	12	036-Gaston	Preservation	SR 1474	SR 1443	SR 1441	0.93	Microsurface	$39,200
2028	12	036-Gaston	Preservation	SR 1488	NC 275	D END	0.27	1.0" S9.5B	$20,000
2028	12	036-Gaston	Preservation	SR 1489	SR 1400	D END	0.30	1.0" S9.5B	$29,500
2028	12	036-Gaston	Preservation	SR 1491	SR 1440	DEAD END	0.20	1.0" S9.5B	$20,000
2028	12	036-Gaston	Preservation	SR 1492	SR 1436	D END	0.34	1.0" S9.5B	$33,900
2028	12	036-Gaston	Preservation	SR 1499	SR 1438	CDS	0.20	1.0" S9.5B	$20,000
2028	12	036-Gaston	Preservation	SR 1505	SR 1421	D END	0.27	1.0" S9.5B	$27,000
2028	12	036-Gaston	Preservation	SR 1506	SR 1504	CDS	0.29	1.0" S9.5B	$28,000
2028	12	036-Gaston	Preservation	SR 1512	SR 1456	D END	0.47	Microsurface	$17,700
2028	12	036-Gaston	Preservation	SR 1532	SR 1412	CDS	0.12	1.0" S9.5B	$12,000
2028	12	036-Gaston	Preservation	SR 1533	CDS	CDS	0.29	1.0" S9.5B	$23,200
2028	12	036-Gaston	Preservation	SR 1534	NC 274	CDS	0.58	1.0" S9.5B	$58,000
2028	12	036-Gaston	Preservation	SR 1665	SR 1609	D END	0.81	Microsurface	$32,500
2028	12	036-Gaston	Preservation	SR 1666	NC 279	SR 1620	1.11	Microsurface	$45,000
2028	12	036-Gaston	Preservation	SR 1743	SR 1713	D END	0.29	1.0" S9.5B	$11,100
2028	12	036-Gaston	Preservation	SR 1744	SR 1743	D END	0.08	1.0" S9.5B	$4,300
2028	12	036-Gaston	Preservation	SR 1745	CLEV CO.	SR 1651	0.28	1.0" S9.5B	$16,800
2028	12	036-Gaston	Preservation	SR 1755	SR 1607	SR 1756	0.30	1.0" S9.5B	$15,500
2028	12	036-Gaston	Preservation	SR 1756	SR 1755	SR 1757	0.16	1.0" S9.5B	$8,300
2028	12	036-Gaston	Preservation	SR 1757	SR 1755	SR 1756	0.16	1.0" S9.5B	$8,300
2028	12	036-Gaston	Preservation	SR 1802	SR 1806	SR 1807	1.51	Microsurface	$60,300
2028	12	036-Gaston	Preservation	SR 1812	US 321B	SR 1001	1.46	Microsurface	$63,000
2028	12	036-Gaston	Preservation	SR 2055	SR 2000	DE	0.47	1.0" S9.5B	$46,000
2028	12	036-Gaston	Preservation	SR 2056	SR 2000	DE	0.30	1.0" S9.5B	$22,700
2028	12	036-Gaston	Preservation	SR 2057	SR 2000	SR 2057	0.57	1.0" S9.5B	$45,000
2028	12	036-Gaston	Preservation	SR 2060	SR 1924	SR 1924+.119	0.12	1.0" S9.5B	$9,000
2028	12	036-Gaston	Preservation	SR 2078	SR 2070	D END	0.20	1.0" S9.5B	$20,000
2028	12	036-Gaston	Preservation	SR 2373	SR 2003	SR 2374	0.10	1.0" S9.5B	$7,200
2028	12	036-Gaston	Preservation	SR 2374	SR 2373	D END	0.08	1.0" S9.5B	$5,900
2028	12	036-Gaston	Preservation	SR 2375	SR 2374	D END	0.19	1.0" S9.5B	$19,000
2028	12	036-Gaston	Preservation	SR 2376	SR 2375	D END	0.04	1.0" S9.5B	$3,000
2028	12	036-Gaston	Preservation	SR 2377	SR 2375	D END	0.07	1.0" S9.5B	$5,600
2028	12	036-Gaston	Preservation	SR 2406	SR 2403	US 321	0.88	1.0" S9.5B	$66,000
2028	12	036-Gaston	Preservation	SR 2407	SR 2406	SR 2408	0.54	1.0" S9.5B	$54,000
2028	12	036-Gaston	Preservation	SR 2409	SR 2406	D END	0.10	1.0" S9.5B	$10,000
2028	12	036-Gaston	Preservation	SR 2410	SR 2406	SR 2411	0.27	1.0" S9.5B	$27,000
2028	12	036-Gaston	Preservation	SR 2668	SR 2520	D END	0.59	Microsurface	$28,300
2028	12	036-Gaston	Preservation	SR1278	SR1118	D END	0.29	1.0" S9.5B	$28,000
2028	12	036-Gaston	Preservation	SR1309	SR1306	DE	0.70	Microsurface	$31,500
2028	12	036-Gaston	Preservation	SR1404	NC274	NC274	1.02	Microsurface	$44,400
2028	12	036-Gaston	Preservation	SR1528	SR1409	D END	0.63	1.0" S9.5B	$63,200
2028	12	036-Gaston	Preservation	SR1607	BUS321	SR1611	1.84	Microsurface	$75,000
2028	12	036-Gaston	Preservation	SR1608	NC279	NC279	0.63	Microsurface	$35,300
2028	12	036-Gaston	Preservation	SR1611	SR1609	SR1607	0.95	Microsurface	$44,100
2028	12	036-Gaston	Preservation	SR1648	SR1649	LINC CO	1.48	Microsurface	$69,700
2028	12	036-Gaston	Preservation	SR1803	SR1802	SR1001	0.76	Microsurface	$42,000
2028	12	049-Iredell	Resurfacing	NC 115	NC 115	Wilkes County	10.05	1.5" S9.5C	$2,250,000
2028	12	049-Iredell	Resurfacing	NC 901	Davie Co.	I-77	10.74	1.5" S9.5C	$1,879,675
2028	12	049-Iredell	Resurfacing	SR 1108	SR 1206	DE	1.48	1.0" S9.5B	$333,000
2028	12	049-Iredell	Resurfacing	SR 1181	SR 1108	DE	1.06	1.0" S9.5B	$210,000
2028	12	049-Iredell	Resurfacing	SR 1216	SR 1102	SR 1102	0.97	1.0" S9.5B	$121,250

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	12	049-Iredell	Resurfacing	SR 1461	SR 1330	DE	1.34	1.5" S9.5C	$221,595
2028	12	049-Iredell	Resurfacing	SR 1544	SR 1543	SR 1551	1.73	1.5" S9.5C	$285,945
2028	12	049-Iredell	Resurfacing	SR 1621	NC 115	US 64	1.94	1.0" S9.5B	$242,750
2028	12	049-Iredell	Resurfacing	SR 1639	SR 1359	SR 1621	0.66	1.5" S9.5C	$109,560
2028	12	049-Iredell	Resurfacing	SR 1681	SR 1645	SR 1736	0.40	1.0" S9.5B	$50,250
2028	12	049-Iredell	Resurfacing	SR 1682	SR 1681	DE	0.13	1.0" S9.5B	$16,250
2028	12	049-Iredell	Resurfacing	SR 1695	SR 1681	SR 1736	0.31	1.0" S9.5B	$38,500
2028	12	049-Iredell	Resurfacing	SR 1736	SR 1645	SR 1681	0.24	1.0" S9.5B	$30,125
2028	12	049-Iredell	Resurfacing	SR 1814	SR 1816	NC 901	0.65	1.0" S9.5B	$146,250
2028	12	049-Iredell	Resurfacing	SR 1980	SR 1886	Dead End	0.09	1.0" S9.5B	$10,625
2028	12	049-Iredell	Resurfacing	SR 2000	SR 1832	DE	0.21	1.0" S9.5B	$45,000
2028	12	049-Iredell	Resurfacing	SR 2108	SR 2105	Davie County	1.64	1.5" S9.5C	$371,250
2028	12	049-Iredell	Resurfacing	SR 2113	SR 2165	Pavement End	1.66	1.5" S9.5C	$373,500
2028	12	049-Iredell	Resurfacing	SR 2259	SR 2165	SR 2260	0.13	1.0" S9.5B	$15,750
2028	12	049-Iredell	Resurfacing	SR 2260	Cul-de-sac	Cul-de-sac	0.64	1.0" S9.5B	$80,000
2028	12	049-Iredell	Resurfacing	SR 2303	US 64	SR 2304	0.12	1.0" S9.5B	$15,375
2028	12	049-Iredell	Resurfacing	SR 2304	Begin Maint.	SR 2305	0.84	1.0" S9.5B	$104,500
2028	12	049-Iredell	Resurfacing	SR 2305	US 64	Rowan County	3.27	1.5" S9.5C	$735,750
2028	12	049-Iredell	Resurfacing	SR 2306	SR 2305	DE	0.42	1.0" S9.5B	$52,375
2028	12	049-Iredell	Resurfacing	SR 2314	US 64	DE	2.60	1.5" S9.5C	$429,000
2028	12	049-Iredell	Resurfacing	SR 2474	SR 2305	DE	0.68	1.0" S9.5B	$153,000
2028	12	049-Iredell	Resurfacing	SR 2527	SR 2638	SR 2593	0.58	1.5" S9.5C	$95,040
2028	12	049-Iredell	Resurfacing	SR 2591	SR 2314	DE	0.29	1.0" S9.5B	$36,500
2028	12	049-Iredell	Resurfacing	SR 2601	SR 2342	DE	0.14	1.5" S9.5C	$23,100
2028	12	049-Iredell	Resurfacing	SR 2738	SR 1401	Cul-de-sac	0.57	1.0" S9.5B	$112,875
2028	12	049-Iredell	Resurfacing	SR 2739	SR 2738	Cul-de-sac	0.06	1.0" S9.5B	$7,500
2028	12	049-Iredell	Resurfacing	US 21	US 21	Yadkin County	6.07	1.5" S9.5C	$1,365,750
2028	12	049-Iredell	Preservation	SR 1267	SR 1112	SR 1112	1.04	.75" S4.75A	$88,400
2028	12	049-Iredell	Preservation	SR 1268	SR 1267	SR 1267	0.11	.75" S4.75A	$9,350
2028	12	049-Iredell	Preservation	SR 1269	Sr 1267	SR 1267	0.14	.75" S4.75A	$11,900
2028	12	049-Iredell	Preservation	SR 1270	SR 1267	SR 1267	0.05	.75" S4.75A	$3,400
2028	12	049-Iredell	Preservation	SR 1396	NC 150	Cul-de-sac	1.55	.75" S4.75A	$131,750
2028	12	049-Iredell	Preservation	SR 1558	SR 1571	End of Maint.	0.71	.75" S4.75A	$78,100
2028	12	049-Iredell	Preservation	SR 1584	NC 115	SR 1583	0.20	Seal - Double	$9,135
2028	12	049-Iredell	Preservation	SR 1586	SR 1583	SR 1585	0.36	Seal - Double	$15,975
2028	12	049-Iredell	Preservation	SR 1591	SR 1614	SR 1611	2.07	Seal - Double	$93,285
2028	12	049-Iredell	Preservation	SR 1612	SR 1591	DE	0.41	Seal - Double	$18,585
2028	12	049-Iredell	Preservation	SR 1651	NC 115	SR 1651	0.37	.75" S4.75A	$45,000
2028	12	049-Iredell	Preservation	SR 1796	SR 1558	End of Maint	0.31	.75" S4.75A	$40,000
2028	12	049-Iredell	Preservation	SR 1809	SR 1807	NC 901	0.16	Seal - Double	$7,290
2028	12	049-Iredell	Preservation	SR 1854	SR 1852	SR 1892	1.71	Seal - Double	$76,770
2028	12	049-Iredell	Preservation	SR 1857	NC 901	SR 1852	3.03	Seal - Double	$136,485
2028	12	049-Iredell	Preservation	SR 1889	SR 1845	DE	0.70	Seal - Double	$31,455
2028	12	049-Iredell	Preservation	SR 1898	NC 115	SR 1873	2.39	Seal - Double	$107,550
2028	12	049-Iredell	Preservation	SR 1908	Begin Pvmt.	NC 115	1.48	Seal - Double	$66,420
2028	12	049-Iredell	Preservation	SR 1909	SR 1908	NC 115	1.52	Seal - Double	$68,400
2028	12	049-Iredell	Preservation	SR 1962	SR 1958	End of Maint.	0.22	.75" S4.75A	$22,000
2028	12	049-Iredell	Preservation	SR 2007	SR 1962	DE	0.09	.75" S4.75A	$11,000
2028	12	049-Iredell	Preservation	SR 2765	SR 1302	Cul-de-sac	0.31	.75" S4.75A	$26,350
2028	12	049-Iredell	Preservation	SR 2766	SR 2765	Cul-de-sac	0.03	.75" S4.75A	$2,550
2028	12	049-Iredell	Preservation	SR 2767	SR 2765	Cul-de-sac	0.03	.75" S4.75A	$2,550
2028	12	049-Iredell	Preservation	SR 2768	SR 2765	Cul-de-sac	0.26	.75" S4.75A	$22,100
2028	12	049-Iredell	Preservation	SR 2769	SR 2768	Cul-de-sac	0.10	.75" S4.75A	$8,500
2028	12	049-Iredell	Preservation	SR 2770	SR 2768	Cul-de-sac	0.12	.75" S4.75A	$10,200
2028	12	049-Iredell	Preservation	SR 2771	SR 2768	Cul-de-sac	0.13	.75" S4.75A	$11,050
2028	12	049-Iredell	Preservation	SR 2846	SR 2847	SR 2846	0.49	.75" S4.75A	$41,650
2028	12	049-Iredell	Preservation	SR 2847	SR 1321	SR 2846	0.51	.75" S4.75A	$43,350
2028	12	055-Lincoln	Resurfacing	NC 150	PVMT JOINT	US 321 BUS	3.42	Full Depth Patching and 1.5" S9.5C	$666,900
2028	12	055-Lincoln	Resurfacing	NC 73	NC 27	SR 1360	6.14	Full Depth Patching and 1.5" S9.5C	$1,197,300

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	12	055-Lincoln	Resurfacing	SR 1266	SR 1405	END MAINT	0.23	Full Depth Patching and 1.5" S9.5C	$44,850
2028	12	055-Lincoln	Resurfacing	SR 1355	NC 73	SR 1354	2.55	Full Depth Patching and 1.5" S9.5C	$497,250
2028	12	055-Lincoln	Resurfacing	SR 1358	NC 27	SR 1360	2.79	Full Depth Patching and 1.5" S9.5B	$544,050
2028	12	055-Lincoln	Resurfacing	SR 1360	NC 73	SR 1383	3.54	Full Depth Patching and 1.5" S9.5B	$690,300
2028	12	055-Lincoln	Resurfacing	SR 1382	SR 1360	SR 1362	2.71	Full Depth Patching and 1.5" S9.5C	$528,450
2028	12	055-Lincoln	Resurfacing	SR 1445	SR 1003	DEAD END	0.72	Full Depth Patching and 1.25" S9.5B	$139,425
2028	12	055-Lincoln	Resurfacing	SR 1522	US 321 BUS	SR 1267	0.29	Full Depth Patching and 1.5" S9.5B	$56,550
2028	12	055-Lincoln	Resurfacing	SR 1673	SR 1445	SR 1508	0.52	Full Depth Patching and 1.5" S9.5B	$101,400
2028	12	055-Lincoln	Resurfacing	SR 1750	NC 73	END MAINT	1.34	Full Depth Patching and 1.5" S9.5B	$261,105
2028	12	055-Lincoln	Resurfacing	SR 1759	SR 1003	DEAD END	0.23	Full Depth Patching and 1.25" S9.5B	$44,365
2028	12	055-Lincoln	Resurfacing	US 321 B	NC 150	NC 27	1.65	Full Depth Patching and 1.5" S9.5B	$321,750
2028	12	055-Lincoln	Preservation	SR 1178	SR 1177	SR 1180	1.19	Seal - Double and Fog Seal	$63,962
2028	12	055-Lincoln	Preservation	SR 1272	SR 1271	CATAWBA CO	0.20	Seal - Double	$10,750
2028	12	055-Lincoln	Preservation	SR 1275	SR 1274	SR 1276	1.10	Seal - Double	$59,125
2028	12	055-Lincoln	Preservation	SR 1277	US 321 BUS	DEAD END	1.76	Seal - Double	$94,600
2028	12	055-Lincoln	Preservation	SR 1299	US 321 BUS	US 321 BUS	1.72	Seal - Double and Fog Seal	$92,450
2028	12	055-Lincoln	Preservation	SR 1311	27	Dead End	1.21	Microsurface	$65,037
2028	12	055-Lincoln	Preservation	SR 1361	SR 1360	Dead End	1.11	Microsurface	$59,662
2028	12	055-Lincoln	Preservation	SR 1364	SR 1362	Cul-de-sac	0.56	Microsurface	$30,100
2028	12	055-Lincoln	Preservation	SR 1365	SR 1355	SR 1362	1.05	Microsurface	$56,437
2028	12	055-Lincoln	Preservation	SR 1368	150	SR 1349	1.95	Microsurface	$104,812
2028	12	055-Lincoln	Preservation	SR 1404	Gaston Co	SR 1511	3.78	Microsurface	$203,175
2028	12	055-Lincoln	Preservation	SR 1446	SR 1349	Dead End	0.73	Microsurface	$39,237
2028	12	055-Lincoln	Preservation	SR1274	SR 1005	SR 1274	1.98	Seal - Double	$106,263
2028	13	011-Buncombe	Resurfacing	2519 (AVENA ROAD)	SR 2515 (FLAT CREEK ROAD)	SR 2522 (PADGETTOWN ROAD)	0.18	Full Depth Patching	$5,750
2028	13	011-Buncombe	Resurfacing	SR 2032 (NEW HAW CREEK ROAD)	US 70	HAW CREEK CIRCLE (CITY STREET)	2.40	Full Depth Patching and 1.5" S9.5C	$442,000
2028	13	011-Buncombe	Resurfacing	SR 2236 (NEW HAW CREEK ROAD)	R 2032 (NEW HAW CREEK ROAD/ CROCKETT AV	HAW CREEK ROAD) + .315 MILES /	0.32	Full Depth Patching and 1.5" S9.5C	$55,459
2028	13	011-Buncombe	Resurfacing	SR 2289 (HUNTINGTON CHASE DRIVE)	SR 2032 (NEW HAW CREEK ROAD)	CUL DE SAC	0.36	Full Depth Patching and 1.0" S4.75A	$67,999
2028	13	011-Buncombe	Resurfacing	SR 2403 (LOWER GRASSY BRANCH ROAD)	SR 2002 (RICEVILLE ROAD)	US 70	2.18	Full Depth Patching and 1.5" S9.5C	$392,400
2028	13	011-Buncombe	Resurfacing	SR 2405 (HICKORY TREE ROAD)	SR 2403 (LOWER GRASSY BRANCH ROAD)	END OF MAINTENANCE	0.46	Full Depth Patching and 1.0" S4.75A	$77,090
2028	13	011-Buncombe	Resurfacing	2407 (UPPER GRASSY BRANCH EXTENSIO	SR 2002 (RICEVILLE ROAD)	2400 UPPER GRASSY BRANCH ROA	0.60	Full Depth Patching and 1.25" S9.5B	$99,579
2028	13	011-Buncombe	Resurfacing	FFITT BRANCH/MOFFITT ROAD/RIVER VIE	US 70	END OF MAINTENANCE	1.57	Full Depth Patching and 1.5" S9.5C	$378,900
2028	13	011-Buncombe	Resurfacing	SR 2410 (MOFFITT BRANCH ROAD)	SR 2409 (MOFFIT ROAD)	MP 0.094	0.09	Mill 1.0" and 1.0" S9.5A	$22,250
2028	13	011-Buncombe	Resurfacing	SR 2410 (MOFFITT BRANCH)	MP 0.094	END OF MAINTENANCE	0.28	Mill 1.0" and 1.0" S9.5A	$55,575
2028	13	011-Buncombe	Resurfacing	SR 2414 (ROGER AVENUE)	US 70	SR2552 (ROWLAND ROAD	0.38	Full Depth Patching and 1.0" S4.75A	$74,322
2028	13	011-Buncombe	Resurfacing	SR 2416 (WARREN WILSON ROAD)	SR 2002 (RICEVILLE ROAD)	SR 2427 (BEE TREE ROAD)	1.38	Full Depth Patching and 1.5" S9.5C	$234,459
2028	13	011-Buncombe	Resurfacing	SR 2420 (DILLINGHAM CIRCLE)	SR 2002 (RICEVILLE ROAD	SR 2002 (RICEVILLE ROAD)	2.01	Full Depth Patching and 1.5" S9.5C	$319,090
2028	13	011-Buncombe	Resurfacing	SR 2427 (BEE TREE ROAD)	SR 2416 (WARREN WILSON ROAD)	SR 2427 (SUMMER HAVEN ROAD)	3.11	Full Depth Patching and 1.5" S9.5C	$625,450
2028	13	011-Buncombe	Resurfacing	SR 2435 (OLD US 70 HIGHWAY)	SR 2416 (BEE TREE ROAD)	SR 2467 (SUMMER STREET)	0.78	Full Depth Patching and 1.5" S9.5C	$135,445
2028	13	011-Buncombe	Resurfacing	SR 2435 (OLD US 70)	BEG. 24' PAVEMENT	BEGIN 18' PAVEMENT	0.54	Full Depth Patching and 1.5" S9.5C	$129,090
2028	13	011-Buncombe	Resurfacing	SR 2435 (OLD US 70)	BEG. 18' PAVEMENT	US 70	1.33	Full Depth Patching and 1.5" S9.5C	$289,977
2028	13	011-Buncombe	Resurfacing	2458 (ANDREW PLACE / MARION AVENU	SR 2457 (SUMMER STREET)	SR 2435 (OLD US 70 HIGHWAY)	0.40	Full Depth Patching and 1.5" S9.5C	$64,323
2028	13	011-Buncombe	Resurfacing	SR 2471 (TABERNACLE ROAD)	SR 2435 (OLD 70 WEST)	SR 2473 (CRAIGMONT ROAD)	0.86	Full Depth Patching and 1.25" S9.5B	$172,233
2028	13	011-Buncombe	Resurfacing	SR 2472 (GROVESTONE ROAD)	SR 2435 (OLD US 70 HIGHWAY)	US 70	0.35	Full Depth Patching and 1.5" S9.5C	$102,577
2028	13	011-Buncombe	Resurfacing	SR 2476 (NORTH FORK RIGHT FORK ROAD	SR 2474 (NORTH FORK ROAD)	END OF PAVEMENT	1.36	Full Depth Patching and 1.5" S9.5C	$259,245
2028	13	011-Buncombe	Resurfacing	SR 2500 (CRAGMOUNT ROAD)	SR 2495 (HIWASSEE AVENUE)	BOYER DRIVE	0.28	Full Depth Patching and 1.5" S9.5C	$76,000
2028	13	011-Buncombe	Resurfacing	SR 2500 (NORTH BLUE RIDGE ROAD)	LOCUST STREET	US 70	0.66	Full Depth Patching and 1.5" S9.5C	$190,000
2028	13	011-Buncombe	Resurfacing	SR 2515 (FLAT CREEK ROAD)	NC 9	US 70	1.24	Full Depth Patching and 1.25" S9.5B	$289,999
2028	13	011-Buncombe	Resurfacing	22 (PADGETTOWN/AVENA/MCOY COVE R	SR 2519 (AVENA ROAD)	SR 2542 (OLD 70 EAST)	1.72	Full Depth Patching	$60,990
2028	13	011-Buncombe	Resurfacing	SR 2527 (OLD TOLL ROAD)	SR 2542 (OLD US 70)	SR 2528 (OLD TOLL CIRCLE)	0.42	Full Depth Patching	$15,550
2028	13	011-Buncombe	Resurfacing	SR 2528 (OLD TOLL CIRCLE / EXTENSION)	SR 2527 (OLD TOLL ROAD)	END OF MAINTENANCE	0.61	Full Depth Patching	$16,550
2028	13	011-Buncombe	Resurfacing	SR 2530 (OLD TOLL CIRCLE)	SR 2542 (OLD 70 EAST)	SR 2528 (OLD TOLL CIRCLE)	0.44	Full Depth Patching	$12,925
2028	13	011-Buncombe	Resurfacing	SR 2533 (MEEKS ROAD)	SR 2532 (BUCKNER ROAD)	END OF MAINTENANCE)	0.20	Full Depth Patching and 1.25" S9.5B	$39,999
2028	13	011-Buncombe	Resurfacing	37(BROAD HEIGHTS ROAD / RIDGECREST D	OLD US 70 E	END OF MAINTENANCE	0.19	Full Depth Patching and 1.5" S9.5C	$77,899
2028	13	011-Buncombe	Resurfacing	SR 2551 (SHERWOOD ROAD)	US 70	SR 2552 (ROWLAND ROAD)	0.26	Full Depth Patching and 1.0" S4.75A	$56,450
2028	13	011-Buncombe	Resurfacing	SR 2552 (ROWLAND ROAD)	SR 2551 (SHERWOOD ROAD)	END OF STATE MAINTENANCE	0.33	Full Depth Patching and 1.0" S4.75A	$69,250
2028	13	011-Buncombe	Resurfacing	SR 2556 (SUNSET LANE)	SR 2555 (SUNSET LANE)	CUL DE SAC	0.06	Full Depth Patching and 1.0" S4.75A	$9,800
2028	13	011-Buncombe	Resurfacing	SR 2557 (HARBIN DRIVE)	SR 2552 (ROWLAND ROAD)	SR 2414 (ROGER AVENUE)	0.08	Full Depth Patching and 1.0" S4.75A	$13,999
2028	13	011-Buncombe	Resurfacing	SR 2558 (CHAPMAN DRIVE)	SR 2420 (DILLINGHAN CIRCLE)	CUL DE SAC	0.11	Full Depth Patching and 1.0" S4.75A	$17,799

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	13	011-Buncombe	Resurfacing	SR 2559 (CHAPMAN DRIVE)	SR 2558 (CHAPMAN DRIVE)	SR 2560 (CHAPMAN DRIVE)	0.07	Full Depth Patching and 1.0" S4.75A	$12,000
2028	13	011-Buncombe	Resurfacing	SR 2560 (CHAPMAN DRIVE)	DEAD END	DEAD END	0.09	Full Depth Patching and 1.0" S4.75A	$19,000
2028	13	011-Buncombe	Resurfacing	SR 2565 (TABERNACLE ROAD)	SR 2435 (OLD US 70)	2471 (TABERNACLE ROAD)	0.28	Full Depth Patching and 1.25" S9.5B	$58,000
2028	13	011-Buncombe	Resurfacing	SR 2584 (CREEK DRIVE)	SR 2423 (PARKER ROAD)	SR 2585 (ARROW PLACE)	0.21	Full Depth Patching and 1.0" S4.75A	$43,250
2028	13	011-Buncombe	Resurfacing	SR 2585 (ARROW PLACE)	CUL DE SAC	CUL DE SAC	0.07	Full Depth Patching and 1.0" S4.75A	$14,422
2028	13	011-Buncombe	Resurfacing	SR 2586 (INDIAN PLACE)	SR 2584 (CREEK DRIVE)	CUL DE SAC	0.18	Full Depth Patching and 1.5" S9.5C	$36,450
2028	13	011-Buncombe	Resurfacing	SR 2588 (INDEPENDENCE BOULEVARD)	SR 2002 (RICEVILLE ROAD)	SR 2660 (LAFAYETTE AVENUE)	0.61	Full Depth Patching and 1.5" S9.5C	$129,007
2028	13	011-Buncombe	Resurfacing	SR 2593 (FEATHER DRIVE)	SR 2584 (CREEK DRIVE)	CUL DE SAC	0.07	Full Depth Patching and 1.5" S9.5C	$14,900
2028	13	011-Buncombe	Resurfacing	SR 2601 (BEE TREE VILLAGE PARKWAY)	SR 2427 (BEE TREE ROAD)	END OF MAINTENANCE	0.21	Full Depth Patching and 1.0" S4.75A	$43,999
2028	13	011-Buncombe	Resurfacing	SR 2603 (NECTAR WAY)	SR 2602 (BEE LINE DRIVE)	DEAD END	0.03	Full Depth Patching and 1.0" S4.75A	$5,940
2028	13	011-Buncombe	Resurfacing	SR 2604 (GOLDEN HARVEST TRAIL)	SR 2602 (BEE LINE DRIVE)	DEAD END	0.03	Full Depth Patching and 1.25" S9.5B	$4,822
2028	13	011-Buncombe	Resurfacing	SR 2605 (LINN GARDEN LANE)	SR 2432 (DAVIDSON ROAD)	CUL DE SAC	0.13	Full Depth Patching and 1.5" S9.5C	$21,999
2028	13	011-Buncombe	Resurfacing	SR 2714 (LYNCH COVE ROAD)	SR 2713 (OLD LAKEY GAP ROAD)	END OF MAINTENANCE	0.40	Full Depth Patching and 1.25" S9.5B	$88,999
2028	13	011-Buncombe	Resurfacing	SR 2727 (WHITSON AVENUE)	BEG. 48 PAVEMENT	SR 2728 (RAILROAD STREET)	0.21	Full Depth Patching and 1.5" S9.5B	$58,989
2028	13	011-Buncombe	Resurfacing	SR 2727 (WHITSON AVENUE)	SR 2435 (OLD US 70 HIGHWAY)	BEGIN 48' PAVEMENT.	0.10	Full Depth Patching and 1.5" S9.5C	$46,775
2028	13	011-Buncombe	Resurfacing	SR 2734 (SOUTH AVENUE)	SR 2727 (WHITSON AVENUE)	SR 2861 (PARK STREET)	0.11	Full Depth Patching and 1.5" S9.5C	$17,012
2028	13	011-Buncombe	Resurfacing	SR 2735 (ALEXANDER PLACE)	SR 2727 (WHITSON AVENUE)	SR 2861 (PARK STREET)	0.11	Full Depth Patching and 1.5" S9.5C	$17,775
2028	13	011-Buncombe	Resurfacing	(SAUNOOKE ROAD /JIMS BRANCH ACCESS	SR 2750 (JIMS BRANCH ROAD)	END OF MAINTENANCE	0.16	Full Depth Patching and 1.5" S9.5C	$33,869
2028	13	011-Buncombe	Resurfacing	45 (OLD JIMS BRANCH ROAD/SLEEPY HOL	SR 2750 (JIMS BRANCH ROAD)	END OF MAINTENANCE	0.22	Full Depth Patching and 1.5" S9.5C	$47,445
2028	13	011-Buncombe	Resurfacing	SR 2849 (OLD PATTON COVE ROAD)	US 70	END OF MAINTENANCE	0.23	Full Depth Patching and 1.5" S9.5C	$48,099
2028	13	011-Buncombe	Resurfacing	SR 2854 (BARKER AVENUE)	SR 2739 (RICHMOND AVENUE)	SR 2855 (YOUNG STREET)	0.09	Full Depth Patching and 1.5" S9.5C	$15,999
2028	13	011-Buncombe	Resurfacing	SR 2855 (YOUNG STREET)	SR 2854 (BARKER STREET)	END OF MAINTENANCE	0.03	Full Depth Patching and 1.0" S4.75A	$5,770
2028	13	011-Buncombe	Resurfacing	SR 2861 (PARK STREET)	US 70	SR 2728 (RAILROAD STREET)	0.26	Full Depth Patching and 1.25" S9.5B	$60,777
2028	13	011-Buncombe	Resurfacing	SR 2868 (DILLINGHAM / PANOVIEW ROAD	SR 2730 (HARRISON STREET)	DEAD END	0.36	Full Depth Patching and 1.5" S9.5C	$77,450
2028	13	011-Buncombe	Resurfacing	SR 2868 (DILLINGHAM / PANOVIEW ROAD	SR 2856 (DENNIS STREET)	SR 2730 (HARRISON STREET)	0.24	Full Depth Patching and 1.5" S9.5C	$49,997
2028	13	011-Buncombe	Resurfacing	SR2602 (VILLAGE OVERLOOK LOOP)	SR 2601 (BEE TREE VILLAGE PARKWAY)	SR 2603 (GOLDEN HARVEST TRAIL)	0.05	Full Depth Patching and 1.0" S4.75A	$7,945
2028	13	011-Buncombe	Resurfacing	US 70	I-240	NC 694 + .127 MILE	0.43	Full Depth Patching and 1.5" S9.5C	$199,899
2028	13	011-Buncombe	Resurfacing	US 70	SR 2861	2724 (LYTLE COVE ROAD) + .138 M	1.99	Full Depth Patching and 1.5" S9.5C	$805,499
2028	13	011-Buncombe	Resurfacing	US 74	US 70	SR 2881 + .455 MILE	0.48	Full Depth Patching and 1.5" S9.5C	$259,399
2028	13	011-Buncombe	Preservation	SR 1100 (CHESTNUT CREEK ROAD)	NC 151	END OF PAVEMENT	0.70	Full Depth Patching and Double Seal and Fog Seal	$52,500
2028	13	011-Buncombe	Preservation	SR 1104 (PISGAH VIEW RANCH ROAD)	SR 1103 (DAVIS CREEK ROAD)	END OF MAINTENANCE	0.22	Full Depth Patching and Double Seal and Fog Seal	$15,559
2028	13	011-Buncombe	Preservation	SR 1106 (BENS COVE ROAD)	SR 1103 (DAVIS CREEK ROAD)	END OF MAINTENANCE	0.60	Full Depth Patching and Double Seal and Fog Seal	$45,455
2028	13	011-Buncombe	Preservation	SR 1107 (SAW BRANCH ROAD)	SR 1103 (DAVIS CREEK ROAD)	END OF MAINTENANCE	1.01	Full Depth Patching and Double Seal and Fog Seal	$72,275
2028	13	011-Buncombe	Preservation	SR 1109 (PISGAH VIEW DRIVE)	NC 151	END OF MAINTENANCE	0.30	Full Depth Patching and 1.0" S4.75A	$55,650
2028	13	011-Buncombe	Preservation	SR 1110 (WARREN CREEK ROAD)	NC 151	PAVEMENT CHANGE	0.96	Full Depth Patching and 1.25" S9.5B	$175,775
2028	13	011-Buncombe	Preservation	SR 1111 (WHITE ROCK BRANCH ROAD)	SR 1110 (WARREN CREEK ROAD)	END OF MAINTENANCE	0.53	Full Depth Patching and Double Seal and Fog Seal	$49,995
2028	13	011-Buncombe	Preservation	SR 1114 (WHITE ROCK CHURCH ROAD)	NC 151	END OF MAINTENANCE	0.16	Full Depth Patching and Double Seal and Fog Seal	$8,184
2028	13	011-Buncombe	Preservation	SR 1121 (MUSTER GROUND HILL ROAD)	SR 3652 (CAROLINA MOUNTAIN DRIVE)	END OF MAINTENANCE	0.22	Full Depth Patching and 1.0" S4.75A	$46,775
2028	13	011-Buncombe	Preservation	SR 1131 (GEORGES BRANCH ROAD)	SR 1203 (GRASSY VIEW ROAD)	SR 1200 (WIGGINS ROAD)	0.46	Full Depth Patching and Double Seal and Fog Seal	$36,450
2028	13	011-Buncombe	Preservation	SR 1142 (WELCH ROAD)	SR 1141 (MORGAN COVE ROAD)	END OF MAINTENANCE	0.38	Full Depth Patching and Double Seal and Fog Seal	$19,955
2028	13	011-Buncombe	Preservation	SR 1143 (PLEASANT HILL)	US 19	SR 1141 (LUTHER ROAD)	0.18	Full Depth Patching and 1.25" S9.5B	$35,455
2028	13	011-Buncombe	Preservation	SR 1146 (MILLER ROAD)	SR 1130 (OLD US 19 23 HIGHWAY)	END OF MAINTENANCE	0.20	Full Depth Patching and 1.0" S4.75A	$39,995
2028	13	011-Buncombe	Preservation	SR 1147 (WALTER CRAWFORD ROAD)	SR 1113 (CURTIS CREEK ROAD)	DEAD END	0.13	Full Depth Patching and Double Seal and Fog Seal	$7,228
2028	13	011-Buncombe	Preservation	SR 1150 (WNC BAPTIST CAMP ROAD)	SR 1130 OLD US 19 23 HIGHWAY	END OF PAVEMENT	0.29	Full Depth Patching and 1.0" S4.75A	$34,000
2028	13	011-Buncombe	Preservation	SR 1151 (MOUNTAIN DRIVE)	SR 1120 (YOUNGS COVE ROAD)	END OF MAINTENANCE	0.23	Full Depth Patching and Double Seal and Fog Seal	$16,611
2028	13	011-Buncombe	Preservation	SR 1154 (LITTLE PINEY MOUNTAIN)	SR 1116 (PINEY MOUNTAIN CHURCH ROAD)	END OF MAINTENANCE	0.18	Full Depth Patching and 1.0" S4.75A	$21,000
2028	13	011-Buncombe	Preservation	SR 1202 (CHILDERS ROAD)	SR 1200 (WIGGINS ROAD)	END OF MAINTENANCE	0.11	Full Depth Patching and 1.0" S4.75A	$18,000
2028	13	011-Buncombe	Preservation	SR 1205 (NORTH LUTHER ROAD)	SR 1203 (GRASSY VIEW ROAD)	LOOP ROAD	0.28	Full Depth Patching and 1.0" S4.75A	$53,350
2028	13	011-Buncombe	Preservation	SR 1207 (BIG COVE ROAD)	SR 1141 (LUTHER ROAD)	SR 1141 (LUTHER ROAD)	2.09	Full Depth Patching and 1.5" S9.5B	$399,950
2028	13	011-Buncombe	Preservation	SR 1215 (CATHY ROAD)	SR 1208 (JUSTICE RIDGE ROAD)	R 1219 (SNOW HILL CHURCH ROAD	0.84	Full Depth Patching and Double Seal and Fog Seal	$65,999
2028	13	011-Buncombe	Preservation	SR 1217 (OLD CATHY ROAD)	SR 1215 (CATHY ROAD)	SR 1210 (MORGAN ROAD)	0.33	Full Depth Patching and 1.0" S4.75A	$38,000
2028	13	011-Buncombe	Preservation	SR 1218 (SNOW HILL CHRUCH ROAD)	SR 1219 (WINDY CANYON ROAD)	SR 1210 (DOGWOOD ROAD)	0.32	Full Depth Patching and Double Seal and Fog Seal	$27,755
2028	13	011-Buncombe	Preservation	SR 1219 (SNOW HILL CHURCH ROAD)	SR 1215 (MILKSICK COVE ROAD)	R 1218 (SNOW HILL CHURCH ROAD	0.14	Full Depth Patching and Double Seal and Fog Seal	$12,255
2028	13	011-Buncombe	Preservation	SR 1220 (HOOKERS GAP ROAD)	PAVEMENT CHANGE	SR 1289 (RIDGE ROAD)	1.77	Full Depth Patching and 1.25" S9.5B	$379,250
2028	13	011-Buncombe	Preservation	SR 1220 (HOOKERS GAP ROAD)	SR 1289 (RIDGE ROAD)	SR 1210 (DOGWOOD ROAD)	0.73	Full Depth Patching and 1.25" S9.5B	$62,000
2028	13	011-Buncombe	Preservation	SR 1493 (FIELDCREST DRIVE)	SR 1208 (JUSTICE RIDGE ROAD)	CUL DE SAC	0.12	Full Depth Patching and 1.25" S9.5B	$14,000
2028	13	011-Buncombe	Preservation	SR 3448 (PALLET ROAD)	US 19	END OF MAINTENANCE	0.20	Microsurface	$10,499
2028	13	011-Buncombe	Preservation	SR 3449 (BEAVERDAM ROAD)	SR 3446 (BENNETT ROAD)	SR 3467 (WISE ROAD)	1.06	Full Depth Patching and 1.25" S9.5B	$120,000
2028	13	011-Buncombe	Preservation	SR 3454 (BAILEY ROAD)	SR 3466 (MCFEE ROAD)	PAVEMENT CHANGE	0.12	Full Depth Patching and 1.25" S9.5B	$17,775

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	13	011-Buncombe	Preservation	SR 3454 (BAILEY ROAD)	PAVEMENT CHANGE	SR 3466 (MCFEE ROAD)	1.67	Full Depth Patching and 1.25" S9.5B	$300,000
2028	13	011-Buncombe	Preservation	SR 3457 (WARREN ROAD)	SR 3454 (GLADYS FORK ROAD)	END OF PAVEMENT	0.11	Full Depth Patching and 1.0" S4.75A	$13,000
2028	13	011-Buncombe	Preservation	SR 3464 (BLACK OAK COVE ROAD)	SR 3452 (UPPER GLADYS FORK ROAD)	NC 151	2.65	Full Depth Patching and Double Seal and Fog Seal	$100,000
2028	13	011-Buncombe	Preservation	SR 3466 (MCFEE ROAD)	SR 3449 (LOWER BEAVERDAM LOOP ROAD)	SR 3454 (BAILEY ROAD)	1.07	Full Depth Patching and Double Seal	$54,550
2028	13	011-Buncombe	Preservation	SR 3647 (SHADOW BROOK DRIVE	SR 3437 (CASE COVE ROAD)	END OF MAINTENANCE	0.34	Full Depth Patching and 1.0" S4.75A	$51,000
2028	13	012-Burke	Resurfacing	1001 (MINERAL SPRINGS MOUNTAIN ROA	SR 1899 (GW ABEE STREET)	NC 18 SOUTH	5.41	Full Depth Patching and 1.25" S9.5B	$1,299,235
2028	13	012-Burke	Resurfacing	SR 1111 (OLD SALEM ROAD)	US 64	SR 1110 (GARRISON ROAD.)	0.12	Full Depth Patching and 1.0" S4.75A	$19,900
2028	13	012-Burke	Resurfacing	SR 1117 (BILL DALE ROAD)	SR 1116 (JEETER CARSWELL ROAD)	SR 1149 (CONLEY ROAD)	1.01	Full Depth Patching and 1.5" S9.5C	$199,000
2028	13	012-Burke	Resurfacing	SR 1127 (SCOTT ROAD/BENNETT ROAD)	SR 1142 (JAMESTOWN ROAD)	SR 1149 (CONLEY ROAD)	2.96	1.5" S9.5C and Widen	$560,099
2028	13	012-Burke	Resurfacing	SR 1183 (HOLLAND STREET)	END OF MAINT	SR 1168 (CONLEY ROAD)	0.14	Full Depth Patching and 1.0" S4.75A	$26,899
2028	13	012-Burke	Resurfacing	AROLINA STREET SOUTH EAST/MILLSTONI	US 70	END OF MAINTENANCE	1.71	Full Depth Patching and 1.5" S9.5C	$717,590
2028	13	012-Burke	Resurfacing	SR 1905 (MOUNT GILEAD CHURCH ROAD)	SR 1924 (OLD NC 18)	SR 1906 (GUS PEELER ROAD)	1.11	Full Depth Patching and 1.5" S9.5C	$270,099
2028	13	012-Burke	Resurfacing	SR 1909 (RED FOX TRAIL)	SR 1907 (RHONEY ROAD)	SR 1907 (RHONEY ROAD)	0.94	Full Depth Patching and 1.5" S9.5C	$206,000
2028	13	012-Burke	Resurfacing	SR 1916 (RIVER ROAD)	NC 18	SR 1924 (OLD NC 18)	5.38	Full Depth Patching and 1.5" S9.5C	$1,198,000
2028	13	012-Burke	Resurfacing	SR 1918 (CHESTER AVENUE)	SR 1924 (OLD NC 18)	SR 1939 (RALPH PATTON ROAD)	0.08	Full Depth Patching and 1.5" S9.5C	$16,996
2028	13	012-Burke	Resurfacing	SR 1922 (ENOLA ROAD)	SR 2026 (ARNOLD DRIVE)	TRAFFIC LIGHT @ MP 6.34	0.93	Full Depth Patching and 1.5" S9.5C	$401,675
2028	13	012-Burke	Resurfacing	SR 1927 (ADVANT STREET)	SR 1924 (OLD NC 18)	END OF PAVEMENT	0.31	Full Depth Patching and 1.5" S9.5C	$69,933
2028	13	012-Burke	Resurfacing	SR 1933 (SKYLAND DRIVE)	SR 1924 (OLD NC 18)	DEAD END	0.66	Full Depth Patching and 1.5" S9.5C	$135,777
2028	13	012-Burke	Resurfacing	SR 1934 (COOPERS LOOP)	SR 1933 (SKYLAND DRIVE)	DEAD END	0.25	Full Depth Patching and 1.5" S9.5C	$53,150
2028	13	012-Burke	Resurfacing	SR 1937 (BROWNING STREET)	SR 1924 (OLD NC 18)	SR 1933 (SKYLAND DRIVE)	0.18	Full Depth Patching and 1.5" S9.5C	$34,000
2028	13	012-Burke	Resurfacing	SR 1949 (SALEM ROAD)	SR 1956 (BURKEMONT ROAD)	US 64	1.04	Full Depth Patching and 1.5" S9.5C	$267,775
2028	13	012-Burke	Resurfacing	SR 1972 (BROOKWOOD ROAD)	NC 18	OLD NC 18	0.90	Full Depth Patching and 1.5" S9.5C	$180,063
2028	13	012-Burke	Resurfacing	SR 2026 (ARNOLD DRIVE)	SR 1922 (ENOLA ROAD)	END OF MAINTENANCE	0.35	Full Depth Patching and 1.0" S4.75A	$67,444
2028	13	012-Burke	Resurfacing	SR 2105 (CRESTWOOD DRIVE)	SR 1112 (PROPST ROAD)	CUL DE SAC	0.61	Full Depth Patching and 1.0" S4.75A	$145,900
2028	13	012-Burke	Resurfacing	SR 2106 (KNOLLWOOD CIRCLE)	SR 2105 (CRESTWOOD DRIVE)	CUL DE SAC	0.09	Full Depth Patching and 1.0" S4.75A	$20,099
2028	13	012-Burke	Resurfacing	SR 2127 (SKYLAND LOOP)	SR 1934 (COOPERS LOOP EXT)	SR 1933 (SKYLAND DRIVE)	0.06	Full Depth Patching and 1.5" S9.5C	$10,080
2028	13	012-Burke	Resurfacing	SR1137 (TALLENT ROAD)	SR 1142 (JAMESTOWN ROAD)	L134 (MORNING STAR CHURCH RO	1.52	Full Depth Patching and 1.25" S9.5B	$330,000
2028	13	012-Burke	Resurfacing	US 64	SR 1949 (SALEM ROAD)	I 40 E RAMP	0.74	Mill 1.5" and 1.5" S9.5C	$399,975
2028	13	012-Burke	Resurfacing	US 64	RUTHERFORD COUNTY LINE	SR 1149 (CONLEY ROAD) +.32 MILE	3.99	Mill 1.5" and 1.5" S9.5C	$1,169,900
2028	13	012-Burke	Preservation	SR 1748 (LAUREL CREEK STREET)	NC 18	END OF MAINTENANCE	0.30	Full Depth Patching and Double Seal and Fog Seal	$23,400
2028	13	012-Burke	Preservation	SR 1796 (OLD LAUREL ROAD)	CATAWBA COUNTY	SR 1786 (MILLER BRIDGE ROAD)	3.51	Full Depth Patching and Triple Seal and Fog Seal	$255,550
2028	13	012-Burke	Preservation	SR 1858 (JOHN ABEE STREET)	NC 18	END OF MAINTENANCE	0.20	Full Depth Patching and Double Seal and Fog Seal	$12,250
2028	13	012-Burke	Preservation	SR 1867 (BUZZ LOMAN STREET)	SR 1796 (OLD LAUREL ROAD)	END OF MAINTENANCE	0.71	Full Depth Patching and Double Seal and Fog Seal	$58,000
2028	13	012-Burke	Preservation	SR 1901 (WARDS GAP ROAD)	SR 1904 (SOUTH NMOUNTAIN PARK AVENUE)	L905 (MOUNT GILEAD CHURCH RO	0.84	Full Depth Patching and Double Seal and Fog Seal	$72,500
2028	13	012-Burke	Preservation	R 1904 (SOUTH MOUNTAIN PARK AVENUE	SR 1901 (WARDS GAP ROAD)	PARK GATE	0.95	Full Depth Patching and Double Seal and Fog Seal	$75,000
2028	13	012-Burke	Preservation	SR 1906 (GUS PEELER ROAD)	CLEVELAND COUNTY LINE	L905 (MOUNT GILEAD CHURCH RO	1.60	Full Depth Patching and Double Seal and Fog Seal	$133,550
2028	13	012-Burke	Preservation	SR 1908 (PERSIMMON ROAD)	SR 1907 (RHONEY ROAD)	SR 1924 (OLD NC 18)	1.53	Full Depth Patching and Double Seal and Fog Seal	$125,450
2028	13	012-Burke	Preservation	SR 1911 (ROGER HILL ROAD)	SR 1910 (WILL HUDSON ROAD)	CATAWBA COUNTY LINE	1.32	Full Depth Patching and Double Seal and Fog Seal	$54,450
2028	13	012-Burke	Preservation	SR 1915 (WALKER CHAPEL ROAD)	SR 1916 (RIVER ROAD)	SR 1913 (SUGAR LOAF ROAD)	2.76	Full Depth Patching and Double Seal and Fog Seal	$232,000
2028	13	012-Burke	Preservation	SR 1919 (RICH MOUNTAIN ROAD)	SR 1918 (WATERSHED ROAD)	END OF MAINTENANCE	0.80	Full Depth Patching and Double Seal and Fog Seal	$30,995
2028	13	012-Burke	Preservation	SR 1932 (DUCKWORTH AVENUE)	SR 1924 (OLD NC 18)	END OF MAINTENANCE	0.40	Full Depth Patching and Double Seal and Fog Seal	$29,250
2028	13	012-Burke	Preservation	SR 1981 (BRADSHAW ROAD)	SR 1924 (OLD NC 18)	SR 1906 (GUS PEELER ROAD)	0.71	Full Depth Patching and Double Seal and Fog Seal	$32,225
2028	13	057-Madison	Resurfacing	NC 212	SR 1316 (CHAPEL HILL ROAD)	SR 1314 (CUTSHALL TOWN ROAD)	4.65	Full Depth Patching and 1.5" S9.5C	$1,329,799
2028	13	057-Madison	Resurfacing	SR 1151 (BALTIMORE BRANCH)	SR 1153 (RECTOR BRANCH ROAD)	SR 1158 (SOUTH FORK ROAD)	5.40	Full Depth Patching and 1.5" S9.5B	$895,450
2028	13	057-Madison	Resurfacing	SR 1395 (WALNUT CREEK ROAD)	MP 8.66	SR 1318 (BIG LAUREL ROAD)	1.01	Full Depth Patching and 1.5" S9.5B	$199,752
2028	13	057-Madison	Preservation	SR 1300 (PAINT ROCK ROAD)	US25	END OF PAVEMENT	1.38	Full Depth Patching and Double Seal and Fog Seal	$102,214
2028	13	057-Madison	Preservation	SR 1542 (LITTLE IVY CHURCH ROAD)	SR 1631 (CROSSROADS PARKWAY)	END OF PAVEMENT	0.47	Full Depth Patching and Double Seal and Fog Seal	$34,000
2028	13	057-Madison	Preservation	SR 1548 (CALVIN EDNEY ROAD)	SR 1540 (BEECH GLEN ROAD)	SR 1549 (CALVIN EDNEY ROAD)	1.11	Full Depth Patching and Double Seal and Fog Seal	$82,225
2028	13	057-Madison	Preservation	SR 1561 (UPPER WHITE OAK ROAD)	SR 1569 (BULL CREEK ROAD)	SR 1565 (GABRIELS CREEK ROAD)	1.66	Full Depth Patching and Double Seal and Fog Seal	$152,225
2028	13	059-McDowell	Resurfacing	(GREENLEE ROAD)	SR 1206 (RESERVOIR ROAD)	MP 0.62	0.35	Full Depth Patching and 1.5" S9.5B	$69,448
2028	13	059-McDowell	Resurfacing	(PARKER PADGETT ROAD)	PAVEMENT CHANGE	SR 1349 (DENVER RIDGE ROAD)	1.89	Full Depth Patching and 1.5" S9.5C	$411,090
2028	13	059-McDowell	Resurfacing	SR 1164 (SHADY LANE)	SR 1001 (SUGAR HILL ROAD)	SR 1168 (ASHWORTH ROAD)	1.51	Full Depth Patching and 1.5" S9.5C	$299,950
2028	13	059-McDowell	Resurfacing	SR 1168 (ASHWORTH ROAD)	I-40	US 221	1.01	Full Depth Patching and 1.5" S9.5C	$185,000
2028	13	059-McDowell	Resurfacing	SR 1168 (ASHWORTH ROAD)	SR 1169 (BURMA ROAD WEST)	I-40	1.87	Full Depth Patching and 1.5" S9.5C	$302,494
2028	13	059-McDowell	Resurfacing	SR 1183 (STROUD STREET)	SR 1168 (REID STREET)	SR 1001 (SUGAR HILL ROAD)	0.64	Full Depth Patching and 1.5" S9.5C	$140,000
2028	13	059-McDowell	Resurfacing	SR 1192 (BEN STREET)	SR 1193 (LUKIN STREET)	DEAD END	0.17	Full Depth Patching and 1.5" S9.5C	$32,799
2028	13	059-McDowell	Resurfacing	SR 1215 (LENA STREET)	SR 1216 (RENA STREET)	DEAD END	0.13	Full Depth Patching and 1.5" S9.5C	$26,595
2028	13	059-McDowell	Resurfacing	SR 1246 (GREENLEE ROAD)	BRIDGE	US 70	1.08	Full Depth Patching and 1.5" S9.5C	$199,599
2028	13	059-McDowell	Resurfacing	SR 1264 (GILBERT STREET)	SR 1197 (GREENLEE ROAD WEST)	DEAD END	0.12	Full Depth Patching and 1.5" S9.5C	$19,885

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	13	059-McDowell	Resurfacing	SR 1316 (WEST PARK PLACE)	SR 1315 (WEST PARK DRIVE)	0.085 (END OF STATE MAINTENAN	0.09	Full Depth Patching and 1.5" S9.5C	$15,400
2028	13	059-McDowell	Resurfacing	SR 1342 (OAK CREST DRIVE)	SR 1001 (SUGAR HILL ROAD)	END OF MAINTENANCE	0.18	Full Depth Patching and 1.5" S9.5C	$37,249
2028	13	059-McDowell	Resurfacing	SR 1424 (SHADY STREET)	SR 1422 (CLEAR CREEK ROAD)	SR 1425 (WEST VIEW STREET)	0.18	Full Depth Patching and 1.5" S9.5C	$28,788
2028	13	059-McDowell	Resurfacing	SR 1425 (WEST VIEW STREET)	US 70	END OF PAVEMENT	0.30	Full Depth Patching and 1.5" S9.5C	$62,999
2028	13	059-McDowell	Resurfacing	SR 1449 (CIRCLE DRIVE)	US 70	SR 1465	0.11	Full Depth Patching and 1.5" S9.5C	$23,000
2028	13	059-McDowell	Resurfacing	SR 1465 (CREEKWAY DRIVE)	BEGIN PAVEMENT	DEAD END	0.14	Full Depth Patching and 1.5" S9.5C	$30,600
2028	13	059-McDowell	Resurfacing	SR 1500 (AIRPORT ROAD)	SR 1510 (HOLLY STREET)	SR 1504 (VICTORY DRIVE)	1.21	Full Depth Patching and 1.5" S9.5C	$260,000
2028	13	059-McDowell	Resurfacing	SR 1505 (ROBINSON ROAD)	US 70	DEAD END	0.16	Full Depth Patching and 1.5" S9.5C	$39,990
2028	13	059-McDowell	Resurfacing	SR 1515 (OLD MORGANTON ROAD)	SR 1514 (RIDGE ROAD)	DEAD END	0.44	Full Depth Patching and 1.5" S9.5C	$89,990
2028	13	059-McDowell	Resurfacing	SR 1538 (UPTONS LANDING ROAD)	SR 1536 (OLD NC 10 EAST)	END OF PAVEMENT	0.56	Full Depth Patching and 1.5" S9.5C	$117,999
2028	13	059-McDowell	Resurfacing	SR 1599 (SOMERSET PLACE)	SR 1500 (AIRPORT ROAD)	DEAD END	0.20	Full Depth Patching and 1.5" S9.5C	$43,966
2028	13	059-McDowell	Resurfacing	SR 1600 (DEEP WOODS DRIVE)	SR 1501 (HANKINS ROAD)	CUL DE SAC	1.12	Full Depth Patching and 1.5" S9.5C	$239,090
2028	13	059-McDowell	Resurfacing	SR 1734 (GLENWOOD AVENUE)	SR 1713 (MARION STREET)	SR 1806 (HUNTER DRIVE)	0.32	Full Depth Patching and 1.5" S9.5C	$70,409
2028	13	059-McDowell	Resurfacing	SR 1741 (FAIRVIEW ROAD)	SR 1736 (TONEY ROAD)	SR 1747 (STACEY HILL ROAD)	1.82	Full Depth Patching and 1.5" S9.5C	$390,994
2028	13	059-McDowell	Resurfacing	SR 1810 (BRADLEY STREET)	SR 1807	SR 1813 (EAST HUNT DRIVE)	0.25	Full Depth Patching and 1.5" S9.5C	$49,090
2028	13	059-McDowell	Resurfacing	SR 1826 (FAITH BAPTIST CHURCH ROAD)	SR 1743 (FAITH BAPTIST CHURCH ROAD)	MP 0.123	0.12	Full Depth Patching and 1.5" S9.5C	$32,299
2028	13	059-McDowell	Resurfacing	SR 1840 (MOSTELLER DRIVE)	SR 1786 (OLD US 221 SOUTH)	CUL DE SAC	0.11	Full Depth Patching and 1.5" S9.5C	$24,100
2028	13	059-McDowell	Resurfacing	US 221	SR 1442	SR 1442 + .107 MILES	0.11	Full Depth Patching and 1.5" S9.5C	$82,000
2028	13	059-McDowell	Resurfacing	US 221	I-40	US 221 Bus	1.73	2.5" I19.0B and 1.5" S9.5C	$899,500
2028	13	059-McDowell	Resurfacing	US 70	US 221 Bus	SR 1591 (EASTBROOK CIRCLE)	1.95	Full Depth Patching and 1.5" S9.5C	$789,500
2028	13	059-McDowell	Resurfacing	US 70	US 221 Bus	US 221 Bus	1.77	Full Depth Patching and 1.5" S9.5C	$969,999
2028	13	059-McDowell	Preservation	SR 1110 (MOFFITT HILL ROAD)	SR 1106 (PINE COVE ROAD)	1111 (MOFFITT HILL CHURCH ROA	1.01	Full Depth Patching and Double Seal and Fog Seal	$73,225
2028	13	059-McDowell	Preservation	SR 1127 (HARLOW NOBLITT ROAD)	SR 1128 (SILVERS WELCH ROAD)	SR 1103 (BAT CAVE ROAD)	0.81	Full Depth Patching and Double Seal and Fog Seal	$32,255
2028	13	059-McDowell	Preservation	SR 1150 (SPOOKY HOLLOW ROAD)	Mp 1.17	DEAD END	0.24	Full Depth Patching and Double Seal and Fog Seal	$15,000
2028	13	059-McDowell	Preservation	SR 1196 (HILLTOP DRIVE)	SR 1195 (NIX CREEK ROAD)	MP 0.287	0.29	Full Depth Patching and Double Seal and Fog Seal	$23,335
2028	13	059-McDowell	Preservation	SR 1248 (CANNON FARM ROAD)	SR 1191 (NIX CREEK ROAD)	DEAD END	0.73	Full Depth Patching and Double Seal and Fog Seal	$63,422
2028	13	059-McDowell	Preservation	SR 1287 (ELLIOTT STREET)	SR 1169 (BURMA ROAD WEST)	CUL DE SAC	0.13	Full Depth Patching and Double Seal and Fog Seal	$5,852
2028	13	059-McDowell	Preservation	SR 1310 (EDWARDS LOOP)	SR 1235 (LACKEYTOWN ROAD)	SR 1235 (LACKEYTOWN ROAD)	0.24	Full Depth Patching and Double Seal and Fog Seal	$17,000
2028	13	059-McDowell	Preservation	SR 1543 (JACK CORPENING ROAD)	NC 126	SR 1544 (NED MCGIMSEY ROAD)	0.57	Full Depth Patching and Double Seal and Fog Seal	$32,225
2028	13	059-McDowell	Preservation	SR 1568 (HONEYCUTT ROAD)	BRIDGE	DEAD END	0.48	Full Depth Patching and Double Seal and Fog Seal	$34,450
2028	13	059-McDowell	Preservation	SR 1568 (HONEYCUTT ROAD)	US 221	BRIDGE	1.68	Full Depth Patching and Double Seal and Fog Seal	$72,225
2028	13	059-McDowell	Preservation	SR 1582 (DAVIS STREET)	SR 1514 (RIDGE ROAD)	END OF MAINTENANCE	0.26	Full Depth Patching and Double Seal and Fog Seal	$12,345
2028	13	059-McDowell	Preservation	SR 1739 (OWL HOLLOW ROAD)	SR 1737 (JACKTOWN ROAD)	END OF PAVEMENT	0.17	Full Depth Patching and Double Seal and Fog Seal	$13,000
2028	13	059-McDowell	Preservation	SR 1763 (GILBERT BYRD ROAD)	BURKE COUNTY LINE	SR 1803 (SOUTH CREEK ROAD)	1.58	Full Depth Patching and Double Seal and Fog Seal	$135,450
2028	13	059-McDowell	Preservation	SR 1770 (TRINITY CHURCH LOOP)	NC 226	NC 226	0.47	Full Depth Patching and Double Seal and Fog Seal	$33,450
2028	13	059-McDowell	Preservation	SR 1795 (CARRAWAY DRIVE)	SR 1786 (OLD US 221 SOUTH)	END OF PAVEMENT	0.31	Full Depth Patching and Double Seal and Fog Seal	$25,000
2028	13	059-McDowell	Preservation	SR 1802 (VEIN MOUNTAIN ROAD)	NC 226	३ 1783 (MACEDONIA CHURCH LOO	3.38	Full Depth Patching and Double Seal and Fog Seal	$239,995
2028	13	061-Mitchell	Resurfacing	NC 226	३ 1403 (ATTY JOHN PETERSON ROAD)+ .227 mile	३ 1194 (BEAR CREEK CHURCH ROAI	2.00	Full Depth Patching and 1.5" S9.5C	$599,450
2028	13	061-Mitchell	Resurfacing	SR 1116 (OLD NC 226)	NC 226	NC 226	0.57	Full Depth Patching and 1.5" S9.5C	$100,999
2028	13	061-Mitchell	Resurfacing	SR 1152 (DEER PARK LAKE ROAD)	PAVEMENT CHANGE	NC 226 + 1.646 MILES	1.46	Full Depth Patching and 1.5" S9.5C	$286,799
2028	13	061-Mitchell	Resurfacing	SR 1260 (SOUTH MITCHELL AVENUE)	NC 226	NC 226	0.51	Full Depth Patching and 1.5" S9.5C	$93,995
2028	13	061-Mitchell	Resurfacing	SR 1271 (EARLS REPAIR SHOP ROAD)	US 19 E	US 19 E + .14 MILES	0.13	Full Depth Patching and 1.5" S9.5C	$27,999
2028	13	061-Mitchell	Resurfacing	SR 1274 (GREENWOOD ROAD)	US 19 E	US 19 E + .143 MILES	0.14	Full Depth Patching and 1.5" S9.5C	$25,790
2028	13	061-Mitchell	Resurfacing	SR 1321 (POPLAR CREEK ROAD)	NC 197	1322 (PETERSON ROAD)+ 1.23 MIL	1.40	Full Depth Patching and 1.5" S9.5C	$304,632
2028	13	061-Mitchell	Resurfacing	SR 1348 (ROAN MOUNTAIN ROAD)	NC 261	NC 261	1.88	Full Depth Patching and 1.5" S9.5C	$379,099
2028	13	061-Mitchell	Preservation	SR 1122 (TEMPIE MOUNTAIN ROAD)	US 19 E	SR 1121 (ALTAPASS HIGHWAY)	1.48	Full Depth Patching and Double Seal and Fog Seal	$135,550
2028	13	061-Mitchell	Preservation	SR 1140 (UPPER HANGING ROCK ROAD)	PAVEMENT CHANGE	) (LOWER HANGING ROCK ROAD)+	0.52	Full Depth Patching and Double Seal and Fog Seal	$43,000
2028	13	061-Mitchell	Preservation	SR 1142 (BIGGERSTAFF ROAD)	US 19E	1265 (WASBURN ROAD) + .59 MIL	1.02	Full Depth Patching and Double Seal and Fog Seal	$68,755
2028	13	061-Mitchell	Preservation	SR 1156 (BRUSHY CREEK ROAD)	SR 1235 (OLD US 19E)	SR 1157 (HOOT OWL ROAD)	1.55	Full Depth Patching and Double Seal and Fog Seal	$99,950
2028	13	061-Mitchell	Preservation	SR 1182 (WATER STREET)	NC 80	1261 (GRINDSTAFF ROAD)+ .41 MI	0.74	Full Depth Patching and Double Seal and Fog Seal	$56,675
2028	13	061-Mitchell	Preservation	SR 1192 (WILSON ROAD)	NC 226	DEAD END	1.01	Full Depth Patching and Double Seal and Fog Seal	$65,550
2028	13	061-Mitchell	Preservation	SR 1217 (McKINNEY COVE ROAD)	SR 1216 (DALLAS YOUNG ROAD)	SR 1214 (YOUNG COVE ROAD)	0.15	Full Depth Patching and Double Seal and Fog Seal	$10,995
2028	13	061-Mitchell	Preservation	SR 1261 (GRINDSTAFF ROAD)	SR 1182 (WATER STREET)	DEAD END	0.17	Full Depth Patching and Double Seal and Fog Seal	$14,000
2028	13	061-Mitchell	Preservation	SR 1269 (VELVIS HOLLIFIELD ROAD)	SR 1106 (DALE ROAD)	SR 1106 (DALE ROAD)+ .25 MILES	0.16	Full Depth Patching and Double Seal and Fog Seal	$11,000
2028	13	061-Mitchell	Preservation	SR 1354 (HOBSON ROAD)	NC 261	NC 261 + 1.02 MILES	1.02	Full Depth Patching and Double Seal and Fog Seal	$75,550
2028	13	081-Rutherford	Resurfacing	SR 1325 (NANNNEYTOWN ROAD)	US 221	SR 1328 (PAINTERS GAP ROAD)	3.45	Full Depth Patching and 1.5" S9.5C	$685,000
2028	13	081-Rutherford	Resurfacing	SR 1595 (OLD US 74 HIGHWAY)	US 74 BUSINESS	US 74 BUSINESS	2.66	Full Depth Patching and 1.5" S9.5C	$588,299
2028	13	081-Rutherford	Resurfacing	SR 1596 (CROSS OVER ROAD)	SR 1595 (OLD US 74 HWY)	US 74 BUSINESS	0.21	Full Depth Patching and 1.25" S9.5B	$44,944
2028	13	081-Rutherford	Resurfacing	SR 1723 (LUCKADOO MOUNTAIN ROAD)	SR 1726 (GOLDEN VALLEY CHURCH ROAD)	1006 (BOSTIC SUNSHINE HIGHWA	3.44	1.5" S9.5C	$575,255

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	13	081-Rutherford	Resurfacing	SR 1726 (GOLDEN VALLEY CHURCH ROAD)	NC 226	1723 (LUCKADOO MOUNTAIN ROA	0.90	1.5" S9.5C	$168,000
2028	13	081-Rutherford	Resurfacing	SR 1727 (HUNT ROAD)	NC 226	SR 1809 (CEMETERY ROAD)	0.62	1.25" S9.5C	$116,400
2028	13	081-Rutherford	Resurfacing	SR 1730 (JOHN HUDSON ROAD)	SR 1733 (JONESTOWN ROAD)	END OF MAINTENANCE	0.69	1.25" S9.5C	$129,823
2028	13	081-Rutherford	Resurfacing	SR 1733 (JONESTOWN ROAD)	CLEVELAND COUNTY LINE	NC 226	4.64	1.25" S9.5C	$759,299
2028	13	081-Rutherford	Resurfacing	SR 1809 (CEMETERY ROAD)	NC 226	END OF MAINTENANCE	0.28	1.25" S9.5C	$49,975
2028	13	081-Rutherford	Resurfacing	SR 2102 (HINES ROAD)	US 221 ALTERNATE	SR 2103 (CAMP FERRY ROAD)	1.47	Full Depth Patching and 1.5" S9.5C	$279,995
2028	13	081-Rutherford	Resurfacing	US 64	SR 1515 (STALLINGS ROAD)	1512 (CAMP CREEK ROAD) + .54 MI	2.00	Full Depth Patching and 1.5" S9.5C	$437,900
2028	13	081-Rutherford	Resurfacing	US 64	US 221	.592 (SILVERS LAKE ROAD) + .533 m	2.00	Mill 1.5" and 1.5" S9.5C	$589,000
2028	13	081-Rutherford	Resurfacing	US 64	SR 1592 (SILVERS LAKE ROAD) + .533 MILES	1510 (HUDLOW ROAD) + .291 MIL	2.00	Full Depth Patching and 1.5" S9.5C	$495,950
2028	13	081-Rutherford	Resurfacing	US 64	SR 1510 (HUDLOW ROAD) + .291 MILES	3 (MACKEY FREEMAN ROAD) + .068	2.00	Full Depth Patching and 1.5" S9.5C	$495,995
2028	13	081-Rutherford	Resurfacing	US 64	SR 1558 (MACKEY FREEMAN ROAD)+ .068 MILES	SR 1516 (ROBERTSON ROAD)	2.00	Full Depth Patching and 1.5" S9.5C	$495,490
2028	13	081-Rutherford	Resurfacing	US 64	SR 1512 (CAMP CREEK ROAD) + .54 MILES	MCDOWELL COUNTY LINE	1.87	Full Depth Patching and 1.5" S9.5C	$465,900
2028	13	081-Rutherford	Resurfacing	US 64	SR 1516 (ROBERTSON ROAD)	SR 1515 (STALLINGS ROAD)	1.76	Full Depth Patching and 1.5" S9.5C	$415,450
2028	13	081-Rutherford	Preservation	SR 1738 (ROMEY CAMPBELL ROAD)	NC 226	END OF PAVEMENT	1.53	Seal - Double and Fog Seal	$62,225
2028	13	081-Rutherford	Preservation	SR 1767 (DYCUS ROAD)	SR 1749 (HOLLIS ROAD)	SR 1794 (HARVEY LOGAN ROAD)	1.96	Seal - Double and Fog Seal	$89,950
2028	13	081-Rutherford	Preservation	SR 1776 (OLD HOLLIS ROAD)	SR 1007 (PINEY MOUNTAIN CHURCH ROAD)	SR 1770 (WALLS CHURCH ROAD)	1.93	Seal - Double and Fog Seal	$78,950
2028	13	081-Rutherford	Preservation	SR 2113 (GROVER SCRUGGS ROAD)	SR 2114 (GOODES CREEK CHURCH ROAD)	SR 2117 (FERRY ROAD)	0.83	Full Depth Patching and Double Seal and Fog Seal	$58,000
2028	13	100-Yancey	Resurfacing	SR 1128 (POSSUM TROT ROAD)	MADISON COUNTY LINE	US 19 E	3.70	Full Depth Patching and 1.5" S9.5C	$766,255
2028	13	100-Yancey	Resurfacing	R 1136 (BANKS CREEK/PHIPPS CREEK ROAI	SR 1126 (PRICES CREEK ROAD)	US 19 E PAVEMENT JOINT	3.18	Full Depth Patching and 1.5" S9.5C	$679,550
2028	13	100-Yancey	Preservation	SR 1334 (LONG BRANCH ROAD)	SR 1335 (SHORT BRANCH ROAD)	LE POST +.16 MILE IS END OF PAVE	0.21	Full Depth Patching and Double Seal and Fog Seal	$17,850
2028	13	100-Yancey	Preservation	SR 1335 (SHORT/ LONG BRANCH ROAD)	SR 1336 (JACKS CREEK / TOE RIVER ROAD)	END OF PAVEMENT	1.06	Full Depth Patching and Double Seal and Fog Seal	$85,550
2028	13	100-Yancey	Preservation	SR 1337 (SMITH JOHNSON ROAD)	SR 1336 (JACKS CREEK ROAD)	END OF PAVEMENT	0.71	Full Depth Patching and Double Seal and Fog Seal	$53,250
2028	13	100-Yancey	Preservation	SR 1345 (PETERSON BRANCH ROAD)	SR 1336 (JACKS CREEK ROAD)	END OF PAVEMENT	1.06	Full Depth Patching and Double Seal and Fog Seal	$89,500
2028	13	100-Yancey	Preservation	SR 1346 (HILL ROAD)	SR 1339 (NORTH BEE BRANCH)	R 1345 (PETERSON BRANCH ROAD	1.10	Full Depth Patching and Double Seal and Fog Seal	$85,500
2028	13	100-Yancey	Preservation	SR 1347 (PARSON BRANCH ROAD)	SR 1345 (PETERSON BRANCH ROAD)	END OF MAINTENANCE	0.79	Full Depth Patching and Double Seal and Fog Seal	$65,250
2028	13	100-Yancey	Preservation	SR 1349 (SWEETWATER ROAD)	SR 1336 (JACKS CREEK ROAD)	.71MP +.05MI TO CUL DE SAC	0.71	Full Depth Patching and Double Seal and Fog Seal	$53,250
2028	13	100-Yancey	Preservation	1 (PATTERSON BRANCH/HOWELL BRANCH	SR 1336 (JACKS CREEK ROAD)	END OF PAVEMENT	1.81	Full Depth Patching and Double Seal and Fog Seal	$145,750
2028	13	100-Yancey	Preservation	SR 1352 (PATTERSON BRANCH ROAD)	SR 1351 (HOWELL BRANCH ROAD)	END OF PAVEMENT	0.67	Full Depth Patching and Double Seal and Fog Seal	$50,250
2028	13	100-Yancey	Preservation	SR 1419 (POUND MILL BRANCH ROAD)	SR 1416 (CLEARMONT SCHOOL ROAD)	POST 1 +.07 MILE IS END OF PAVEI	1.00	Full Depth Patching and Double Seal and Fog Seal	$82,500
2028	14	020-Cherokee	Resurfacing	SR 1556	SR 1564	US 129	3.85	Leveling and 1.25" S9.5B	$1,058,750
2028	14	020-Cherokee	Resurfacing	SR 1564	SR 1556	SR 1100	4.86	Leveling and 1.25" S9.5B	$1,336,500
2028	14	020-Cherokee	Resurfacing	US 19	SR 1390	Begin Divided Hwy	1.23	Full Depth Patching and 1.5" S9.5C	$338,250
2028	14	020-Cherokee	Resurfacing	US 19 Bus	Bridge 71	SR 1390	1.41	Full Depth Patching and 1.5" S9.5B	$387,750
2028	14	020-Cherokee	Resurfacing	US 64/74 E	.33 miles west of SR 1131	Pvmt change @ Bridge #9	6.72	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5C	$4,000,000
2028	14	020-Cherokee	Resurfacing	US 64/74 W	Pvmt change @ Bridge #10	.33 miles west of SR 1131	6.71	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5C	$4,000,000
2028	14	020-Cherokee	Preservation	SR 1132	SR 1131	EOM	0.48	Seal - Double and Fog Seal	$33,600
2028	14	020-Cherokee	Preservation	SR 1520	NC 141	EOM	2.43	Seal - Double and Fog Seal	$170,100
2028	14	020-Cherokee	Preservation	SR 1554	SR 1651	EOM	1.48	Seal - Double and Fog Seal	$103,600
2028	14	020-Cherokee	Preservation	SR 1582	SR 1580	EOM	0.62	Seal - Double and Fog Seal	$43,400
2028	14	020-Cherokee	Preservation	SR 1598	NC 60	SR 1597	0.78	Seal - Double and Fog Seal	$54,600
2028	14	020-Cherokee	Preservation	SR 1643	US 19	EOM	0.38	Seal - Double and Fog Seal	$26,600
2028	14	022-Clay	Resurfacing	SR 1308	Tusquittee St.	Hiawassee St.	0.49	Leveling and 1.5" S9.5B	$134,750
2028	14	022-Clay	Resurfacing	SR 1309	Down town us 64 business	HWY 64	2.64	Leveling and 1.5" S9.5B	$726,000
2028	14	022-Clay	Resurfacing	US 64	SR 1304+0.08	SR 1343 (Truett Camp Rd) + 0.37	3.13	Mill 1.5" and 1.5" S9.5C	$860,750
2028	14	022-Clay	Preservation	Ed Moore Rd.	SR 1140	End of Maint.	0.30	Seal - Double and Fog Seal	$21,000
2028	14	022-Clay	Preservation	Garnett Swanson Rd.	SR 1141	End of Maint.	0.31	Seal - Double and Fog Seal	$21,700
2028	14	022-Clay	Preservation	McClure Rd.	SR 1115	End of Maint.	0.84	Seal - Double and Fog Seal	$58,800
2028	14	022-Clay	Preservation	Nicely Rd.	SR 1140	End of Maint.	0.93	Seal - Double and Fog Seal	$65,100
2028	14	022-Clay	Preservation	West Cherry Rd.	US 64 W	End of Maint.	0.60	Seal - Double and Fog Seal	$42,000
2028	14	038-Graham	Resurfacing	SR 1112	Snowbird Rd	EOM	2.11	1.25" S9.5B	$580,250
2028	14	038-Graham	Resurfacing	SR 1275	US 129	BRIDGE #20	0.04	Crack Seal and 1.5" S9.5B	$11,000
2028	14	038-Graham	Resurfacing	SR 1275	BRIDGE #20	NC 143	0.52	Crack Seal and 1.5" S9.5B	$143,275
2028	14	038-Graham	Preservation	SR 1103	NC 129	EOP	0.93	Seal - Double and Fog Seal	$65,100
2028	14	038-Graham	Preservation	SR 1114	NC 143	SR 1112	1.17	Seal - Double and Fog Seal	$81,900
2028	14	038-Graham	Preservation	SR 1156	NC 143	SR 1117	0.25	Seal - Double and Fog Seal	$17,500
2028	14	038-Graham	Preservation	SR 1208	SR 1277	SR 1206	1.40	Seal - Double and Fog Seal	$98,000
2028	14	038-Graham	Preservation	SR 1218	NC 143	EOP	0.69	Seal - Double and Fog Seal	$48,300
2028	14	038-Graham	Preservation	SR 1221	NC 143	EOP	1.27	Seal - Double and Fog Seal	$88,900
2028	14	044-Haywood	Resurfacing	NC 110	US 276	North St	4.94	Full Depth Patching and 1.5" S9.5C	$1,358,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	14	044-Haywood	Resurfacing	SR 1142	SR 1140	DEAD END	0.60	Full Depth Patching and 1.25" S9.5A	$165,000
2028	14	044-Haywood	Resurfacing	SR 1346	SR 1338	EOM	3.79	1.25" S9.5B	$1,042,250
2028	14	044-Haywood	Resurfacing	SR 1350	SR 1355	EOM	2.06	1.25" S9.5B	$565,125
2028	14	044-Haywood	Resurfacing	SR 1823	NC 215	SR 1818	3.44	1.25" S9.5B	$945,725
2028	14	044-Haywood	Preservation	SR 1365	NC 209	SR 1363	1.41	Seal - Double and Fog Seal	$98,980
2028	14	044-Haywood	Preservation	SR 1371	NC 209	END PVMT	0.10	Seal - Double and Fog Seal	$6,930
2028	14	044-Haywood	Preservation	SR 1381	SR 1363	EOM	0.68	Seal - Double and Fog Seal	$47,600
2028	14	044-Haywood	Preservation	SR 1526	NC 209	SR 1523	0.21	Seal - Double and Fog Seal	$14,910
2028	14	044-Haywood	Preservation	SR 1530	SR 1529	SR 1523	0.31	Seal - Double and Fog Seal	$21,700
2028	14	044-Haywood	Preservation	SR 1552	SR 1513	EOP	0.10	Seal - Double and Fog Seal	$6,790
2028	14	044-Haywood	Preservation	SR 1568	SR 1523	SR 1568	0.76	Seal - Double and Fog Seal	$52,850
2028	14	044-Haywood	Preservation	SR 1592	NC 215	DEAD END	0.97	Seal - Double and Fog Seal	$67,830
2028	14	044-Haywood	Preservation	SR 1615	SR 1613	SR 1613	0.15	Seal - Double and Fog Seal	$10,360
2028	14	044-Haywood	Preservation	SR 1634	SR 1534	DEAD END	0.21	Seal - Double and Split Seal	$14,840
2028	14	044-Haywood	Preservation	SR 1653	SR 1513	DEAD END	0.54	Seal - Double and Fog Seal	$37,800
2028	14	044-Haywood	Preservation	SR 1654	SR 1513	DEAD END	0.84	Seal - Double and Fog Seal	$58,730
2028	14	044-Haywood	Preservation	SR 1825	SR 1823	EOM	0.42	Seal - Double and Fog Seal	$29,050
2028	14	044-Haywood	Preservation	SR 1847	SR 1937	SR 1937	2.91	Seal - Double and Fog Seal	$203,350
2028	14	044-Haywood	Preservation	SR 1850	SR 1854	DEAD END	0.39	Seal - Double and Fog Seal	$27,090
2028	14	044-Haywood	Preservation	SR 1866	SR 1865	DEAD END	0.20	Seal - Double and Fog Seal	$13,860
2028	14	044-Haywood	Preservation	SR 1902	SR 1869	DEAD END	0.16	Seal - Double and Fog Seal	$11,270
2028	14	044-Haywood	Preservation	SR 1904	SR 1868	EOP	0.54	Seal - Double and Fog Seal	$37,800
2028	14	044-Haywood	Preservation	SR 1939	SR 1802	DEAD END	0.17	Seal - Double and Fog Seal	$12,180
2028	14	045-Henderson	Resurfacing	SR 1195	SR 1194	SR 1191	0.86	1.25" S9.5B	$236,500
2028	14	045-Henderson	Resurfacing	SR 1285	SR 1123	X-Cross	2.24	1.25" S9.5B	$614,900
2028	14	045-Henderson	Resurfacing	SR 1513	SR 1006	SR 1503	1.11	Mill 1.25" and 1.25" S9.5B	$304,150
2028	14	045-Henderson	Resurfacing	SR 1602	US 64	SR 1602	3.03	Full Depth Patching and 1.5" S9.5B	$833,250
2028	14	045-Henderson	Resurfacing	SR 1614	SR 1602	SR 1591	0.93	1.25" S9.5B	$255,750
2028	14	045-Henderson	Resurfacing	SR 1803	SR 1722	SR 1804	1.96	1.5" S9.5B	$539,000
2028	14	045-Henderson	Resurfacing	SR 1804	SR 1803	SR 1783	0.44	1.25" SF9.5A	$121,000
2028	14	045-Henderson	Resurfacing	SR 1807	US 176	SR 1812	1.01	1.25" S9.5B	$277,750
2028	14	045-Henderson	Resurfacing	SR 1893	SR1525	SR 1793	0.88	1.5" S9.5B	$242,000
2028	14	045-Henderson	Resurfacing	SR 2044	NC 191	CUL-DE-SAC	1.69	1.5" S9.5B	$464,750
2028	14	045-Henderson	Resurfacing	SR 2056	SR 2054	SR 2055	0.10	Full Depth Patching and 1.25" S9.5A	$28,050
2028	14	045-Henderson	Resurfacing	SR 2162	US 64	NC 191	0.77	Mill 1.5" and 1.5" S9.5B	$211,750
2028	14	045-Henderson	Resurfacing	SR 2413	SR 1345	SR 2408	0.27	Mill 1.25" and 1.25" S9.5A	$75,350
2028	14	045-Henderson	Resurfacing	US 25	Bridge #216	Buncombe CL	1.67	Mill 1.5" and 1.5" S9.5C	$457,875
2028	14	045-Henderson	Resurfacing	US 64 E.	SR 1364 Carolina Village	End Dvd Hwy	1.40	Mill 1.5" and 1.5" S9.5C	$385,000
2028	14	045-Henderson	Resurfacing	US 64 W.	Begin Dvd Hwy	SR 1364 Carolina Village	1.40	Mill 1.5" and 1.5" S9.5C	$385,000
2028	14	045-Henderson	Preservation	SR 1194	SR 1195	END PVMT	0.36	Seal - Double and Fog Seal	$25,200
2028	14	045-Henderson	Preservation	SR 1208	SR 1207	Dead End	0.46	Seal - Double and Fog Seal	$31,920
2028	14	045-Henderson	Preservation	SR 1284	SR 1203	SR 1284	0.78	Seal - Double and Fog Seal	$54,460
2028	14	045-Henderson	Preservation	SR 1336	SR 1338	SR 1335	0.37	Seal - Double and Fog Seal	$25,550
2028	14	045-Henderson	Preservation	SR 1392	Hendersonville CL	US 25 Bus	0.89	Seal - Double and Fog Seal	$62,300
2028	14	045-Henderson	Preservation	SR 1520	US 64	SR 1508	0.16	Seal - Double and Fog Seal	$11,200
2028	14	045-Henderson	Preservation	SR 1566	SR 1556	END MAINT	0.41	Seal - Double and Fog Seal	$28,700
2028	14	045-Henderson	Preservation	SR 1602	SR 1708	EOM	1.16	Seal - Double and Fog Seal	$80,990
2028	14	045-Henderson	Preservation	SR 1819	US 176	SR 1821	0.52	Seal - Double and Fog Seal	$36,400
2028	14	045-Henderson	Preservation	SR 1836	SR 1857	US 176	2.10	Seal - Double and Fog Seal	$146,650
2028	14	045-Henderson	Preservation	SR 1850	SR 1852	EOM	3.65	Seal - Double and Fog Seal	$255,780
2028	14	045-Henderson	Preservation	SR 1946	SR 1716	EOM	0.76	Seal - Double and Fog Seal	$53,270
2028	14	045-Henderson	Preservation	SR 1973	SR 1602	POLK CL	1.14	Seal - Double and Fog Seal	$79,730
2028	14	045-Henderson	Preservation	SR 1990	SR 1686	SR 1991	0.13	Seal - Double and Fog Seal	$9,100
2028	14	045-Henderson	Preservation	SR 2052	SR 1426	SR 2053	0.10	Seal - Double and Fog Seal	$6,860
2028	14	045-Henderson	Preservation	SR 2053	EOM	EOM	0.27	Seal - Double and Fog Seal	$19,110
2028	14	045-Henderson	Preservation	SR 2094	SR 1461	SR 1455	0.16	Seal - Double and Fog Seal	$11,200
2028	14	045-Henderson	Preservation	SR 2402	SR 1316	SR 2403	0.30	Seal - Double and Fog Seal	$21,000
2028	14	045-Henderson	Preservation	SR 2511	SR 1719	SR 1783	2.39	Seal - Double and Fog Seal	$167,090
2028	14	045-Henderson	Preservation	SR 2512	SR 1006	EOM	0.21	Seal - Double and Fog Seal	$14,350

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2028	14	045-Henderson	Preservation	SR 2513	SR 2512	EOM	0.11	Seal - Double and Fog Seal	$7,350
2028	14	045-Henderson	Preservation	SR 2514	SR 2512	SR 2512	0.30	Seal - Double and Fog Seal	$21,000
2028	14	050-Jackson	Resurfacing	SR 1105	NC 107	EOP	0.84	Full Depth Patching and 1.5" S9.5B	$231,000
2028	14	050-Jackson	Resurfacing	SR 1409	SR 1405	SR 1406	1.25	Full Depth Patching and 1.25" S9.5B	$343,750
2028	14	050-Jackson	Resurfacing	SR 1424	US 441	SR 1427	1.74	Full Depth Patching and 1.25" S9.5B	$478,500
2028	14	050-Jackson	Resurfacing	SR 1737	SR 1744	EOP	3.17	Full Depth Patching and 1.25" S9.5A	$871,750
2028	14	050-Jackson	Preservation	SR 1109	SR 1107	EOP	0.56	Seal - Double and Fog Seal	$39,200
2028	14	050-Jackson	Preservation	SR 1124	SR 1120	NC 107	2.83	Seal - Double and Fog Seal	$198,100
2028	14	050-Jackson	Preservation	SR 1314	SR 1313	EOM	0.30	Seal - Double and Fog Seal	$21,070
2028	14	050-Jackson	Preservation	SR 1317	SR 1313	DEAD END	0.26	Seal - Double and Fog Seal	$18,410
2028	14	050-Jackson	Preservation	SR 1364	SR 1501	US 23	0.12	Seal - Double and Fog Seal	$8,190
2028	14	050-Jackson	Preservation	SR 1369	SR 1432	EOM	2.54	Seal - Double and Fog Seal	$177,590
2028	14	050-Jackson	Preservation	SR 1545	SR 1329	END MAINT	0.05	Seal - Double and Fog Seal	$3,150
2028	14	050-Jackson	Preservation	SR 1547	SR 1001	END MAINT	0.23	Seal - Double and Fog Seal	$16,100
2028	14	050-Jackson	Preservation	SR 1779	BGN PVMT	END MAINT	0.14	Seal - Double and Fog Seal	$9,800
2028	14	056-Macon	Resurfacing	SR 1448	US 64	US 64	8.61	Patching and 1.25" S9.5A	$2,367,750
2028	14	056-Macon	Preservation	SR 1116	US 23	EOM	0.52	Seal - Double and Fog Seal	$36,400
2028	14	056-Macon	Preservation	SR 1124	SR 1122	EOM	1.58	Seal - Double and Fog Seal	$110,600
2028	14	056-Macon	Preservation	SR 1128	SR 1122	SR 1448	5.88	Seal - Double and Fog Seal	$411,460
2028	14	056-Macon	Preservation	SR 1130	SR 1128	END MAINT	1.23	Seal - Double and Fog Seal	$86,100
2028	14	056-Macon	Preservation	SR 1177	US 23	EOM	0.17	Seal - Double and Fog Seal	$11,900
2028	14	075-Polk	Resurfacing	SR 1334	NC 9	SR 1333	1.07	1.25" S9.5B	$321,000
2028	14	075-Polk	Resurfacing	SR 1354	SR 1353	SR 1355	0.98	1.25" S9.5B	$294,000
2028	14	075-Polk	Resurfacing	SR 1519	SR 1521	SR 1572	1.13	1.25" S9.5B	$339,000
2028	14	075-Polk	Resurfacing	SR 1519	BRIDGE	SR 1521	1.91	1.25" S9.5B	$573,000
2028	14	075-Polk	Resurfacing	SR 1572	SR 1521	SR 1519	1.33	1.25" S9.5B	$399,000
2028	14	075-Polk	Resurfacing	US 74 E.	0042 Over Houston RdBridge 0042 Over Houstc	Bridge 0221 @ Exit 163	1.28	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5C	$1,200,000
2028	14	075-Polk	Resurfacing	US 74 W.	Bridge 0222 @ Exit 163Bridge 0222 @ Exit 163	Bridge 046 Over Houston Rd	1.31	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5C	$1,200,000
2028	14	075-Polk	Preservation	SR 1501	SR 1502	SR 1519	6.17	Seal - Double and Fog Seal	$431,900
2028	14	087-Swain	Resurfacing	SR 1311	SR 1312	SR 1386	1.91	Patching and 1.25" S9.5A	$525,250
2028	14	087-Swain	Preservation	SR 1110	SR 1113	EOP	1.10	Seal - Double	$77,000
2028	14	087-Swain	Preservation	SR 1118	SR 1117	EOM	0.80	Seal - Double	$55,930
2028	14	087-Swain	Preservation	SR 1193	SR 1173	EOM	1.74	Seal - Double	$121,450
2028	14	087-Swain	Preservation	SR 1330	SR 1329	EOM	0.44	Seal - Double and Fog Seal	$31,080
2028	14	088-Transylvania	Resurfacing	SR 1506	US 64	US 64	1.10	1.25" S9.5B	$302,500
2028	14	088-Transylvania	Resurfacing	SR 1591	SR 1536	Henderson County Line	4.28	1.25" S9.5B	$1,176,175
2028	14	088-Transylvania	Resurfacing	US 64/276	Begin Divided Hwy	NC 280	1.14	Full Depth Patching and 1.5" S9.5C	$650,000
2028	14	088-Transylvania	Resurfacing	US 64/276 WestUS 64/276 West	NC 280	End of Divided Hwy	1.13	Mill 1.5" and 1.5" S9.5C	$800,000
2028	14	088-Transylvania	Preservation	SR 1104	SR 1107	EOP	1.07	Seal - Double and Fog Seal	$75,040
2028	14	088-Transylvania	Preservation	SR 1327	SR 1328	EOP	2.30	Seal - Double and Fog Seal	$160,860
2028	14	088-Transylvania	Preservation	SR 1500	SR 1501	County Line	1.09	Seal - Double and Fog Seal	$76,300
2028	14	088-Transylvania	Preservation	SR 1562	SR 1528	EOP	0.80	Seal - Double and Fog Seal	$56,000
2028	14	088-Transylvania	Preservation	SR 1577	SR 1527	SR 1527	0.56	Seal - Double and Fog Seal	$39,200
2028	14	088-Transylvania	Preservation	SR 1579	US 64	EOP	0.17	Seal - Double and Fog Seal	$11,900
2028	14	088-Transylvania	Preservation	SR 1607	SR 1528	EOP	0.16	Seal - Double and Fog Seal	$11,200
2028	14	088-Transylvania	Preservation	SR 1608	US 64	US 64	0.88	Seal - Double and Fog Seal	$61,250
2029	1	008-Bertie	Resurfacing	SR 1108 (Indian Woods Rd.)	SR 1122 (Broad Neck Rd.)	SR 1100 (Grabtown Rd.)	6.29	Full Depth Patching and 1.5" S9.5B	$1,255,000
2029	1	008-Bertie	Resurfacing	SR 1201 (Piney Woods Rd.)	NC 308	NC 308	3.82	Full Depth Patching and 1.5" S9.5B	$840,000
2029	1	008-Bertie	Resurfacing	SR 1209 (Old NC 11 Bus.)	SR 1200 (Connaritsa Rd.)	NC 11	1.10	Full Depth Patching and 1.5" S9.5B	$200,000
2029	1	008-Bertie	Resurfacing	SR 1228 (Earley Station Rd.)	SR 1246 (Sheriff Garrett Rd.)	SR 1229 (Burden fire Lane)	1.99	Full Depth Patching and 1.5" S9.5B	$420,000
2029	1	008-Bertie	Resurfacing	SR 1347 (Basnight Rd.)	SR 1344	NC 45	1.03	Full Depth Patching and 1.5" S9.5B	$200,000
2029	1	008-Bertie	Resurfacing	SR 1509 (Jimmie Love Rd.)	End Maint	NC 45	0.96	Full Depth Patching and 1.5" S9.5B	$195,000
2029	1	008-Bertie	Resurfacing	SR 1511 (Sutton Rd.)	Pavement Change	SR 1502	0.90	Full Depth Patching and 1.5" S9.5B	$180,000
2029	1	008-Bertie	Resurfacing	SR 1511 (Sutton Rd.)	SR 1510	NC 45	1.11	Full Depth Patching and 1.5" S9.5B	$200,000
2029	1	008-Bertie	Preservation	SR 1105 (Pollocks Rd.)	Dead End	US 13	1.11	Seal - Double	$56,000
2029	1	008-Bertie	Preservation	SR 1217 (White Rd.)	SR 1221 (Charles Taylor Rd.)	Dead End	0.51	Seal - Double	$26,000
2029	1	008-Bertie	Preservation	SR 1234 (South Dunning Rd.)	Hertford Co	NC 305	0.25	Seal - Double	$13,000
2029	1	008-Bertie	Preservation	SR 1237 (Williford Rd.)	Hertford Co	SR 1235 (Center Grove Rd.)	0.76	Seal - Double	$38,000
2029	1	008-Bertie	Preservation	SR 1341 (Perry's School Rd.)	SR 1342 (Morris Food Rd.)	SR 1001 (Wakelon Rd.)	1.60	Seal - Double	$80,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	1	008-Bertie	Preservation	SR 1520 (Gurley Rd.)	SR 1521 (Cedar Landing Rd.)	Dead End	1.03	Seal - Double	$62,000
2029	1	008-Bertie	Preservation	SR 1522 (Davenport Road)	SR 1521 (Cedar Landing Rd.)	Dead End	0.11	Seal - Double	$6,000
2029	1	008-Bertie	Preservation	SR 1523 (George Leggett Rd.)	SR 1521 (Cedar Landing Rd.)	US 13	2.03	Seal - Double	$102,000
2029	1	008-Bertie	Preservation	SR 1526 (Outlaw Farm Rd.)	US 13	EOP	0.43	Seal - Double	$22,000
2029	1	008-Bertie	Preservation	SR 1542 (Gilliam Rd.)	Dead End	SR 1521 (Cedar Landing Rd.)	0.40	Seal - Double	$20,000
2029	1	015-Camden	Resurfacing	SR 1107 (Sandy Hook Rd.)	NC343	SR 1116 (Bartlett Rd.)	3.11	Full Depth Patching and 1.5" S9.5B	$621,000
2029	1	015-Camden	Resurfacing	SR 1201 (Runswamp Rd.)	SR 1204 (Whitehurst Ln)	SR 1145 (Lambs Rd.)	1.35	Full Depth Patching and 1.5" S9.5B	$269,000
2029	1	015-Camden	Preservation	SR 1100 (Texas Rd.)	SR 1101 (One Mill Rd.)	Dead End	3.38	Seal - Double	$152,000
2029	1	015-Camden	Preservation	SR 1102 (Thome Point Rd.)	SR 1101 (One Mill Rd.)	Dead End	0.90	Seal - Double	$45,000
2029	1	021-Chowan	Resurfacing	SR 1315 (Greenhall Rd.)	SR 1316 (Coffield Rd.)	SR 1303 (Sandy Ridge Rd.)	3.48	Full Depth Patching and 1.5" S9.5B	$695,000
2029	1	021-Chowan	Resurfacing	SR 1316 (Greenhall Rd.)	NC 32	SR 1316 (Coffield Rd.)	2.84	Full Depth Patching and 1.5" S9.5B	$567,000
2029	1	021-Chowan	Resurfacing	SR 1329 (Sub Station Rd.)	SR 1328 (N. Broad St.)	EOM	0.45	Full Depth Patching and 1.5" S9.5B	$91,000
2029	1	021-Chowan	Resurfacing	SR 1330 (Shannonhouse Rd.)	US 17 Bus.	US 17 Bypass	0.89	Full Depth Patching and 1.5" S9.5B	$196,000
2029	1	021-Chowan	Preservation	SR 1223 (Evans Church Rd.)	SR 1222 (Rocky Hock Rd.)	NC 32	1.48	1.25" S9.5B	$162,000
2029	1	021-Chowan	Preservation	SR 1315 (Mavaton Rd.)	SR 1303 (Sandy Ridge Rd.)	NC 32	1.15	1.25" S9.5B	$141,000
2029	1	027-Currituck	Resurfacing	SR 1131 (Poplar Branch Rd.)	US 158	NC 136	2.47	1.5" S9.5B	$444,000
2029	1	027-Currituck	Resurfacing	SR 1142 (Waterlilly Rd.)	SR 1145 (Piney Island Rd.)	SR 1154 (S. Waterlilly Rd.)	0.84	Full Depth Patching and 1.5" S9.5B	$168,000
2029	1	027-Currituck	Resurfacing	SR 1142 (Waterlilly Rd.)	SR 1141 (Waterlilly Rd.)	SR 1145 (Piney Island Rd.)	2.28	Full Depth Patching and 1.5" S9.5B	$455,000
2029	1	027-Currituck	Resurfacing	SR 1145 (S. Waterlilly Rd.)	SR 1142 (Waterlilly Rd.)	End Pavement	0.52	Full Depth Patching and 1.5" S9.5B	$104,000
2029	1	027-Currituck	Resurfacing	SR 1516 (Shingle Landing Rd.)	SR 1222 (Tulls Creek Rd.)	NC 168	1.69	Full Depth Patching and 1.5" S9.5B	$337,000
2029	1	027-Currituck	Preservation	SR 1387 (Wildwood Dr.)	SR 1216 (Puddin Ridge Rd.)	Dead End	0.57	1.25" S9.5B	$70,000
2029	1	027-Currituck	Preservation	SR 1388 (Providence Dr.)	SR 1502 (Queen Anne Rd.)	Dead End	0.55	Microsurface	$33,000
2029	1	027-Currituck	Preservation	SR 1389 (Oxford Rd. Ext.)	SR 1502 (Queen Anne Rd.)	Dead End	1.00	1.25" S9.5B	$122,000
2029	1	027-Currituck	Preservation	SR 1389 (Oxford Rd.)	SR 1388 (Providence Rd.)	SR 1502 (Queen Anne Rd.)	0.19	1.25" S9.5B	$24,000
2029	1	027-Currituck	Preservation	SR 1502 (Queen Anne Rd.)	SR 1387 (Wildwood Dr.)	SR 1388 (Providence Dr.)	0.38	Microsurface	$23,000
2029	1	028-Dare	Resurfacing	NC 12	SR 1467 (Park Dr.)	700' North of SR 1464 (Pamlico Ct.)	3.45	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,213,000
2029	1	028-Dare	Resurfacing	NC 12	Ramp 23	SR 1498 (Sea Oat Dr.)	4.54	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,755,000
2029	1	028-Dare	Resurfacing	SR 1120 (Mother Vineyard)	US 64	End of Maintenance	1.30	Full Depth Patching and 1.5" S9.5B	$234,000
2029	1	028-Dare	Resurfacing	SR 1128 (Sir Walter Raleigh St.)	US 64	SR 1123 (Bideford St.)	0.28	Mill 1.5" and 1.5" S9.5B	$79,000
2029	1	028-Dare	Resurfacing	SR 1167 (Old NC 345)	US 64	SR 1160 (Dare Ave.)	0.33	Full Depth Patching and 1.5" S9.5B	$70,000
2029	1	028-Dare	Resurfacing	SR 1244 (CC Gray Rd.)	SR 1224 (Harbor Rd.)	SR 1224 (Harbor Rd.)	0.26	Full Depth Patching and 1.5" S9.5B	$37,000
2029	1	028-Dare	Resurfacing	SR 1278 (Albacore Ln.)	Cul-de-sac	Cul-de-sac	0.40	Full Depth Patching and 1.5" S9.5B	$72,000
2029	1	028-Dare	Resurfacing	SR 1281 (Drum Rd.)	SR 1284 (Seashore Ln.)	Cul-de-sac	0.09	Full Depth Patching and 1.5" S9.5B	$17,000
2029	1	028-Dare	Resurfacing	SR 1412 (Bold Dune Dr.)	NC 12	End of Maintenance	0.27	Full Depth Patching and 1.5" S9.5B	$49,000
2029	1	028-Dare	Resurfacing	SR 1448 (Holiday Blvd.)	NC 12	End of Maintenance	0.28	Full Depth Patching and 1.5" S9.5B	$51,000
2029	1	028-Dare	Resurfacing	SR 1449 (Sea Vista Dr.)	NC 12	Cul-de-sac	0.41	Full Depth Patching and 1.5" S9.5B	$82,000
2029	1	028-Dare	Resurfacing	SR 1450 (Sea Vista Ct.)	SR 1449 (Sea Vista Dr.)	Cul-de-sac	0.09	Full Depth Patching and 1.5" S9.5B	$18,000
2029	1	028-Dare	Resurfacing	SR 1470 (Ocean Spray Rd.)	NC 12	End of Maintenance	0.26	Full Depth Patching and 1.5" S9.5B	$47,000
2029	1	028-Dare	Resurfacing	SR 1522 (Wimble Shores North)	NC 12	End of Maintenance	0.26	Full Depth Patching and 1.5" S9.5B	$42,000
2029	1	028-Dare	Resurfacing	SR 1525-Yucca St.	NC 12	SR 1421-Ocean View Dr.	0.05	Full Depth Patching and 1.5" S9.5B	$10,000
2029	1	028-Dare	Resurfacing	SR 1537 (Dean Ave.)	NC 12	End of Maintenance	0.32	Full Depth Patching and 1.5" S9.5B	$64,000
2029	1	028-Dare	Resurfacing	SR1462 (Holiday Blvd.)	NC 12	End of Maintenance	0.30	Full Depth Patching and 1.5" S9.5B	$54,000
2029	1	028-Dare	Resurfacing	US 64	SR 1118 (Harriot St.)	250' NW of Marshall C Collins Dr.	1.76	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$827,000
2029	1	028-Dare	Preservation	SR 1224 (Harbor Rd.)	NC 12	SR 1226 (McMullen Rd.)	0.73	1.25" S9.5B	$80,000
2029	1	028-Dare	Preservation	SR 1224-Harbor Rd.	SR 1226-McMullen St.	NC 12	0.73	Crack Seal	$5,000
2029	1	028-Dare	Preservation	SR 1225 (Williams Rd.)	SR 1226 (McMullen Rd.)	CDS	0.22	1.25" S9.5B	$25,000
2029	1	028-Dare	Preservation	SR 1225-Williams Rd.	Dead End	SR 1226-McMullen St.	0.22	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1227-Methodist Church St.	SR 1226-McMullen St.	SR 1224-Harbor Rd.	0.24	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1228-Scarborough Rd.	SR 1229	SR 1224-Harbor Rd.	0.18	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1244-CC Gray Rd.	SR 1224	SR 1224	0.26	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1245-Avalona Ave.	Dead End	SR 1225-Williams Rd.	0.12	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1262-Dolphin Lane	CDS	NC 12	0.11	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1267-Beach Comber Rd.	NC 12	NC 12	0.31	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1268-Wahoo Circle	NC 12	Dead End	0.09	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1271-Scarborough Rd..	Dead End	SR 1229	0.11	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1278-Albacore Lane	CDS	CDS	0.40	Crack Seal	$3,000
2029	1	028-Dare	Preservation	SR 1281-Drum Rd.	Dead End	SR 1284-Seashore Blvd.	0.09	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1283-Pompano Dr.	SR 1285-Tarpan Dr.	SR 1278-S. Albacore Lane	0.16	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1286-Weakfish Rd.	CDS	NC 12	0.21	Crack Seal	$2,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	1	028-Dare	Preservation	SR 1291-Cape Point Way	SR 1231-Old Lighthouse Rd.	Dead End	0.26	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1405-Sunfish Court	Dead End	NC 12	0.11	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1412-Bold Dune Dr.	Dead End	NC 12	0.27	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1413-Dune Way	CDS	NC 12	0.09	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1415-Antillas Road E.	SR 1416	NC 12	0.10	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1415-Antillas Road W.	NC 12	Dead End	0.09	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1416	Dead End	Dead End	0.07	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1442-Rampart St.	SR 1431-Colony Dr.	NC 12	0.25	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1444 (Porpoise Pt.)	SR 1278 (Albacore Rd.)	CDS	0.07	1.25" S9.5B	$26,000
2029	1	028-Dare	Preservation	SR 1444-Porpoise Place	CDS	SR 1278-S. Albacore Lane	0.07	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1445-Avalona Ave.	Dead End	NC 12	0.10	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1449-Sea Vista Dr.	CDS	NC 12	0.41	Crack Seal	$3,000
2029	1	028-Dare	Preservation	SR 1450-Sea Vista Ct.	CDS	SR 1449-Sea Vista Dr.	0.09	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1460-Cobia Way	CDS	SR 1285-Tarpan Dr.	0.06	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1461-Marlin Dr.	SR 1267-Beachcomber Dr.	SR 1267-Beachcomber Dr.	0.14	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1464-Pamlico Ct.	CDS	NC 12	0.14	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1470-Ocean Spray	Dead End	NC 12	0.26	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1471-Due East West Rd.	CDS	NC 12	0.14	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1472-Due East Rd.	Dead End	NC 12	0.11	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1479-Widgeon Dr.	SR 1473-Bufflehead Rd.	NC 12	0.29	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1481 (Sunfish Ct.)	SR 1278 (Albacore Rd.)	CDS	0.09	1.25" S9.5B	$26,000
2029	1	028-Dare	Preservation	SR 1481-Sunfish Court	CDS	SR 1278-S. Albacore Lane	0.09	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1502-Amberjack Lane	CDS	SR 1444-Porpoise Place	0.03	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1515-Tuna Terrace Rd.	Dead End	NC 12	0.08	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1522-Wimble Shore Dr.	Dead End	NC 12	0.26	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1527-Diamond Shoals Dr.	SR 1231-Old Lighthouse Rd.	SR 1291-Cape Point Way	0.42	Crack Seal	$3,000
2029	1	028-Dare	Preservation	SR 1528-Park Rd.	End Maint	NC 12	0.16	Crack Seal	$1,000
2029	1	028-Dare	Preservation	SR 1529-Lost Tree Trail	SR 1232-Buxton Back Rd.	CDS	1.00	Crack Seal	$7,000
2029	1	028-Dare	Preservation	SR 1530-Crooked Ridge Trail	SR 1529-Lost Tree Trail	End Maint	0.22	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1531-Middle Ridge Trail	SR 1529-Lost Tree Trail	Dead End	0.48	Crack Seal	$3,000
2029	1	028-Dare	Preservation	SR 1532-Sand St.	NC 12	Dead End	0.24	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1537-Dean Ave.	NC 12	Dead End	0.32	Crack Seal	$2,000
2029	1	028-Dare	Preservation	SR 1555-Osprey Ridge Rd.	CDS	NC 12	0.20	Crack Seal	$2,000
2029	1	037-Gates	Resurfacing	SR 1118 (Taylor Mill Rd.)	SR 1120 (Fort Island Rd.)	NC 137	4.44	Full Depth Patching and 1.5" S9.5B	$975,000
2029	1	037-Gates	Resurfacing	SR 1211 (Smith Rd.)	US 13	NC 37	1.83	Full Depth Patching and 1.5" S9.5B	$366,000
2029	1	037-Gates	Resurfacing	SR 1220 (Hackley Rd.)	US 158	NC 37	2.68	Full Depth Patching and 1.5" S9.5B	$535,000
2029	1	037-Gates	Resurfacing	US 158	SR 1300 (Medical Center Rd.)	SR 1319 (Clay Hill Rd.)	1.90	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$558,000
2029	1	037-Gates	Preservation	SR 1124 (Eure Loop Rd.)	SR 1125 (Eure Loop Rd.)	NC 137	0.03	1.25" S9.5B	$4,000
2029	1	037-Gates	Preservation	SR 1125 (Eure Loop Rd.)	SR 1124 (Eure Loop Rd.)	NC 137	0.22	1.25" S9.5B	$25,000
2029	1	037-Gates	Preservation	SR 1132 (Parker Lane)	Dead End	NC 137	0.10	1.25" S9.5B	$11,000
2029	1	037-Gates	Preservation	SR 1136 (Depot Rd.)	SR 1137 (Depot Rd.)	NC 137	0.09	1.25" S9.5B	$9,000
2029	1	037-Gates	Preservation	SR 1137 (Depot Rd.)	SR 1126 (Corner High Rd.)	SR 1136 (Depot Rd.)	0.12	1.25" S9.5B	$14,000
2029	1	037-Gates	Preservation	SR 1138 (Sun Lane)	Dead End	SR 1124 (Eure Loop Rd.)	0.07	1.25" S9.5B	$9,000
2029	1	046-Hertford	Resurfacing	NC 45	NC 461	SR 1458 (N. Main St.)	0.46	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$227,000
2029	1	046-Hertford	Resurfacing	NC 461	US 13	NC 45	1.60	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$526,000
2029	1	046-Hertford	Resurfacing	SR 1167 (Tom Brown Rd.)	NC 11	SR 1176 (Mr. Tabor Church Rd.)	1.45	Full Depth Patching and 1.5" S9.5B	$290,000
2029	1	046-Hertford	Resurfacing	SR 1176 (Mt. Tabor Church Rd.)	US 158	SR 1167 (Tom Brown Rd.)	1.60	Full Depth Patching and 1.5" S9.5B	$319,000
2029	1	046-Hertford	Resurfacing	SR 1300 (Wises Store Rd.)	Northampton Co	US 158	1.61	Full Depth Patching and 1.5" S9.5B	$322,000
2029	1	046-Hertford	Resurfacing	SR 1301 (Vaughan Rd.)	SR 1300 (Wises Store Rd.)	Northampton County	1.69	Full Depth Patching and 1.5" S9.5B	$354,000
2029	1	046-Hertford	Resurfacing	SR 1302 (Vaughans Creek Rd.)	SR 1301 (Vaughan Mill Rd.)	End Maint	1.50	Full Depth Patching and 1.5" S9.5B	$299,000
2029	1	046-Hertford	Resurfacing	SR 1438 (Christian Harbor Rd.)	NC 45	SR 1441 (Swains Mill Rd.)	1.51	Full Depth Patching and 1.5" S9.5B	$305,000
2029	1	046-Hertford	Resurfacing	US 13 North	Begin Median Divided Hwy	Gates County Line	1.68	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$671,000
2029	1	046-Hertford	Resurfacing	US 13 South	Gates County Line	End Median Divided Hwy	1.68	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$671,000
2029	1	046-Hertford	Resurfacing	US 158 EBL	NC 11	SR 1218 (Industrial Park Rd.)	8.81	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$3,180,000
2029	1	046-Hertford	Resurfacing	US 158 WBL	SR 1218 (Industrial Park Rd.)	NC 11	8.83	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$3,111,000
2029	1	046-Hertford	Preservation	SR 1100 (Jernigan Airport Rd.)	SR 1104 (South Church Rd.)	SR 1101 (Lee Jernigan Rd.)	1.95	Seal - Double	$98,000
2029	1	046-Hertford	Preservation	SR 1100 (South Williford Rd.)	SR 1101 (Lee Jernigan Rd.)	Bertie Co	1.78	Seal - Double	$89,000
2029	1	046-Hertford	Preservation	SR 1104 (South Church Rd.)	Bertie Co	SR 1106 (South Early Station Rd.)	1.78	Seal - Double	$89,000
2029	1	046-Hertford	Preservation	SR 1130 (East Modlin Rd.)	NC 11	US 13	0.91	Seal - Double	$46,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	1	046-Hertford	Preservation	SR 1130 (West Modlin Rd.)	SR 1108 (Union Rd.)	NC 11	1.33	Seal - Double	$67,000
2029	1	046-Hertford	Preservation	SR 1141 (Henry Brown Rd.)	SR 1146 (Menola St. Johns Rd.)	SR 1146 (Menola St. Johns Rd.)	0.57	1.25" S9.5B	$63,000
2029	1	048-Hyde	Resurfacing	SR 1124 (Quarter Rd.)	Begin Pavement	SR 1128 (Oyster Creek Rd.)	5.53	Full Depth Patching and 1.5" S9.5A	$993,000
2029	1	058-Martin	Resurfacing	SR 1303 (Dixon Rd.)	NC 11	US 64 Alt	3.58	Full Depth Patching and 1.5" S9.5B	$715,000
2029	1	058-Martin	Resurfacing	SR 1312 (Salisbury Rd)	SR 1313 (Robert Everett Rd)	SR 1310 (Chapman Rd)	1.05	Full Depth Patching and 1.5" S9.5B	$210,000
2029	1	058-Martin	Resurfacing	SR 1312 (Salisbury Rd)	SR 1310 (Chapman Rd)	NC 142	1.04	Full Depth Patching and 1.5" S9.5B	$208,000
2029	1	058-Martin	Resurfacing	SR 1313 (Robert Everett Rd)	SR 1314 (Perkins Rd)	SR 1002 (Hassell Rd)	1.12	Full Depth Patching and 1.5" S9.5B	$202,000
2029	1	058-Martin	Resurfacing	SR 1349 (Roberson Dr.)	SR 1315 (Spring Green Rd)	End of Pavement	0.25	Full Depth Patching and 1.5" S9.5B	$45,000
2029	1	058-Martin	Resurfacing	SR 1352 (Dixon Rd.)	SR 1303 (Dixon Rd.)	Dead End	0.02	Full Depth Patching and 1.5" S9.5B	$4,000
2029	1	058-Martin	Resurfacing	SR 1403 (Ross Rd)	NC 903	SR 1309 (Winslow Rd)	2.00	Full Depth Patching and 1.5" S9.5B	$360,000
2029	1	058-Martin	Resurfacing	SR 1413 (Log Cabin Rd)	SR 1409 (Spring Green Rd.)	NC 125	0.74	Full Depth Patching and 1.5" S9.5B	$133,000
2029	1	058-Martin	Resurfacing	SR 1501 (Big Mill Rd.)	SR 1500 (Holly Springs Church Rd.)	US 17	2.20	Full Depth Patching and 1.5" S9.5B	$439,000
2029	1	058-Martin	Resurfacing	SR 1528 (Yarrell Creek Rd.)	SR 1500 (Holly Springs Church Rd.)	SR 1527 (Arthur Corey Rd.)	1.66	Full Depth Patching and 1.5" S9.5B	$331,000
2029	1	058-Martin	Preservation	SR 1109 (Harrison Rd.)	SR 1106 (Ed's Grocery Rd.)	SR 1113 (Leggett Mill Rd.)	1.94	Seal - Double	$97,000
2029	1	058-Martin	Preservation	SR 1111 (Jack Cowan Rd.)	Dead End	SR 1109 (Harrison Rd.)	0.57	Seal - Double	$29,000
2029	1	058-Martin	Preservation	SR 1413 (Log Cabin Rd.)	SR 1409 (Spring Green Rd.)	NC 125	0.74	1.25" S9.5A and Widen	$34,000
2029	1	058-Martin	Preservation	SR 1533 (Godard Town Rd.)	SR 1106 (Smithwick Creek Church Rd.)	₹ 1106 (Smithwick Creek Church Rc	2.64	Seal - Double	$132,000
2029	1	058-Martin	Preservation	SR 1539 (Evan Perry Rd.)	SR 1538 (Wainwright Rd.)	SR 1541 (Dymond City Rd.)	1.10	Seal - Double	$55,000
2029	1	058-Martin	Preservation	SR 1542 (Noah Robertson Rd.)	SR 1538 (EH Williams Rd.)	NC 171	1.38	Seal - Double	$69,000
2029	1	058-Martin	Preservation	SR 1545 (Seymour Price Rd.)	SR 1538 (Manning Rd.)	EOP	0.70	Seal - Double	$35,000
2029	1	058-Martin	Preservation	SR 1546 (Barber Cutoff Rd.)	SR 1538 (Manning Rd.)	SR 1547 (Barber Rd.)	0.63	Seal - Double	$32,000
2029	1	066-Northampton	Resurfacing	SR 1311 (Jackson Bypass Rd.)	NC 305	SR 1313 (Hargraves Rd.)	2.66	Full Depth Patching and 1.5" S9.5B	$558,000
2029	1	066-Northampton	Resurfacing	SR 1314 (Pleasant Grove Rd.)	SR 1311 (Jackson Bypass Rd.)	NC 305	1.59	Full Depth Patching and 1.5" S9.5B	$318,000
2029	1	066-Northampton	Resurfacing	SR 1333 (Mt. Carmel Rd.)	US 158	SR1311 (Jackson Bypass)	2.43	Full Depth Patching and 1.5" S9.5B	$485,000
2029	1	066-Northampton	Resurfacing	SR 1358 (Deloatch Mill Rd.)	US 158	NC 35	2.09	Full Depth Patching and 1.5" S9.5B	$376,000
2029	1	066-Northampton	Resurfacing	SR 1501 (Dusty Hill Rd.)	SR 1503 (Lasker Rd.)	NC 305	3.81	Full Depth Patching and 1.5" S9.5B	$798,000
2029	1	066-Northampton	Resurfacing	SR 1537 (Perdue Hatchery Rd.)	SR 1536 (Ashleys Grove Rd.)	US 158	1.80	Full Depth Patching and 1.5" S9.5B	$360,000
2029	1	066-Northampton	Resurfacing	US 158	Halifax Co	US 301	1.76	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$579,000
2029	1	066-Northampton	Resurfacing	US 258	NC 305	US 158	14.59	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$4,840,000
2029	1	066-Northampton	Resurfacing	US 301	US 158	NC 186	0.66	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$202,000
2029	1	066-Northampton	Preservation	SR 1100 (Tyler Rd.)	Bertie Co	NC 305	4.00	Crack Seal	$25,000
2029	1	066-Northampton	Preservation	SR 1200 (James Jones Rd.)	NC 48	VA Line	1.75	Crack Seal	$11,000
2029	1	066-Northampton	Preservation	SR 1201 (Macon Price Rd.)	NC 186	NC 48	0.97	Crack Seal	$6,000
2029	1	066-Northampton	Preservation	SR 1214 (River Rd.)	SR 1244 (Cove Manor)	Warren Co	2.04	Crack Seal	$14,000
2029	1	066-Northampton	Preservation	SR 1215 (Bradley Rd.)	NC 46	SR 1214 (River Rd.)	0.46	Crack Seal	$3,000
2029	1	066-Northampton	Preservation	SR 1218 (Willey Lane)	Dead End	NC 46	1.25	Crack Seal	$7,000
2029	1	066-Northampton	Preservation	SR 1220 (Hickory Hollow Rd.)	NC 46	End Pavment	1.57	Crack Seal	$9,000
2029	1	066-Northampton	Preservation	SR 1222 (Gus Smith Rd.)	NC 46	Dead End	1.20	Crack Seal	$8,000
2029	1	066-Northampton	Preservation	SR 1249 (Smith Rd.)	SR 1220 (Hickory Hollow Rd.)	Dead End	0.40	Crack Seal	$3,000
2029	1	066-Northampton	Preservation	SR 1250 (Edwards Beach Rd.)	SR 1214 (River Rd.)	Dead End	0.89	Crack Seal	$6,000
2029	1	066-Northampton	Preservation	SR 1251 (Old Gaston Ext.)	SR 1213 (Old Gaston Rd.)	Dead End	0.51	Crack Seal	$3,000
2029	1	066-Northampton	Preservation	SR 1259 (Josey St.)	SR 1200 (James Jones Rd.)	SR 1260 (Brown St.)	0.08	Crack Seal	$1,000
2029	1	066-Northampton	Preservation	SR 1260 (Brown St.)	Dead End	Dead End	0.13	Crack Seal	$1,000
2029	1	066-Northampton	Preservation	SR 1303 (Reid Rd.)	SR 1304 (Elam Church Rd.)	US 301	0.73	Crack Seal	$5,000
2029	1	066-Northampton	Preservation	SR 1311 (Jackson Bypass Rd.)	US 158	NC 305	3.92	Crack Seal	$24,000
2029	1	066-Northampton	Preservation	SR 1333 (Severn Rd.)	SR 1334 (Main St.)	NC 35	0.98	Crack Seal	$6,000
2029	1	066-Northampton	Preservation	SR 1334 (Main St.)	SR 1333 (Severn Rd.)	NC 35	1.03	Crack Seal	$7,000
2029	1	066-Northampton	Preservation	SR 1347 (Bynum Rd.)	SR 1344 (Galatia Rd.)	SR 1333 (Mt. Carmel Rd.)	3.65	Seal - Double	$164,000
2029	1	066-Northampton	Preservation	SR 1356 (Willis Hare Rd.)	NC 35	SR 1341 (Vaughans Creek Rd.)	3.56	Seal - Double	$187,000
2029	1	066-Northampton	Preservation	SR 1501 (Dusty Hill Rd.)	SR 1503 (Lasker Rd.)	NC 35	3.58	Crack Seal	$22,000
2029	1	066-Northampton	Preservation	SR 1501 (Dusty Hill Rd.)	SR 1503 (Lasker Rd.)	NC 305	3.81	Crack Seal	$24,000
2029	1	066-Northampton	Preservation	SR 1510 (Jenkins Mill Rd.)	SR 1504 (Creeksville Rd.)	NC 35	4.31	Seal - Double	$226,000
2029	1	066-Northampton	Preservation	SR 1534 (Lassiter Mill Rd.)	NC 35	Dead End	0.20	Crack Seal	$2,000
2029	1	066-Northampton	Preservation	SR 1543 (Gilmer Ricks Rd.)	SR 1545 (Buck Boone Rd.)	US 158	2.55	Crack Seal	$16,000
2029	1	066-Northampton	Preservation	SR 1545 (Buck Boone Rd.)	SR 1543 (Gilmer Ricks Rd.)	NC 35	1.76	Crack Seal	$11,000
2029	1	066-Northampton	Preservation	SR 1550 (Magnolia St.)	Dead End	US 258	0.19	Crack Seal	$2,000
2029	1	066-Northampton	Preservation	SR 1561 (West Main St.)	Dead End	US 158 Bus	0.38	Crack Seal	$3,000
2029	1	066-Northampton	Preservation	SR 1562 (Decharmarnel Dr.)	US 158	Dead End	0.25	Crack Seal	$2,000
2029	1	070-Pasquotank	Resurfacing	SR 1121 (John White Rd.)	SR 1100 (Nixonton Rd.)	SR 1122 (New Rd.)	1.09	Full Depth Patching and 1.5" S9.5B	$196,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	1	070-Pasquotank	Resurfacing	SR 1122 (New Rd.)	SR 1100 (Nixonton Rd.)	SR 1182 (Meadstown Rd.)	1.45	Full Depth Patching and 1.5" S9.5B	$290,000
2029	1	070-Pasquotank	Resurfacing	SR 1124 (Crocker Hill Rd.)	NC 344	NC 344	1.54	Full Depth Patching and 1.5" S9.5B	$307,000
2029	1	070-Pasquotank	Resurfacing	SR 1140 (Okisko Rd.)	SR 1450 (Megan Dr)	SR 1144 (Foreman Bundy Rd)	2.95	Full Depth Patching and 1.5" S9.5B	$529,000
2029	1	070-Pasquotank	Resurfacing	SR 1149 (Selby Rd.)	SR 1139 (Body Rd.)	Dead End	0.57	Full Depth Patching and 1.5" S9.5B	$103,000
2029	1	070-Pasquotank	Resurfacing	SR 1197 (Old US 17)	US 17	County Line	1.59	Full Depth Patching and 1.5" S9.5B	$451,000
2029	1	070-Pasquotank	Resurfacing	SR 1465 (Linwood Dr.)	SR 1354	Dead End	0.49	Full Depth Patching and 1.5" S9.5B	$98,000
2029	1	070-Pasquotank	Preservation	SR 1123 Twiford Rd	SR 1101 Peartree Rd	SR 1100 Nixonton Rd	0.24	Microsurface	$13,000
2029	1	070-Pasquotank	Preservation	SR 1147 (Cooper Ln. / Savin Rd.)	SR 1145 (Oak Stump Rd.)	End of Maintenance	0.52	1.25" S9.5B	$57,000
2029	1	070-Pasquotank	Preservation	SR 1180 Commander RD	SR 1123 Twiford Rd	SR 1100 Nixonton rd	0.17	Microsurface	$10,000
2029	1	070-Pasquotank	Preservation	SR 1184 Graves Ave	SR 1101 Peartree rd	SR 1185 Hines Ave	0.13	Microsurface	$8,000
2029	1	070-Pasquotank	Preservation	SR 1185 Hines Ave	SR 1186 Bailey St	SR 1193 Harvey St	0.21	Microsurface	$12,000
2029	1	070-Pasquotank	Preservation	SR 1186 Bailey St	SR 1187 Lafayette Ave	SR 1185 Hines Ave	0.06	Microsurface	$4,000
2029	1	070-Pasquotank	Preservation	SR 1187 Lafayette Ave	SR 1186 Bailey St	SR 1193 Harvey St	0.19	Microsurface	$11,000
2029	1	070-Pasquotank	Preservation	SR 1191 (Chesterfield Dr.)	SR 1145 (Oak Stump Rd.)	SR 1198 (Oakdale Dr.)	0.28	1.25" S9.5B	$35,000
2029	1	070-Pasquotank	Preservation	SR 1192 (Bruce Dr.)	SR 1191 (Chesterfield Dr.)	Dead End	0.12	1.25" S9.5B	$15,000
2029	1	070-Pasquotank	Preservation	SR 1192 (Burlington Dr.)	Dead End	SR 1191 (Chesterfield Dr.)	0.20	1.25" S9.5B	$25,000
2029	1	070-Pasquotank	Preservation	SR 1193 Harvey St	SR 1187 Lafayette Ave	SR 1185 Hines Ave	0.06	Microsurface	$4,000
2029	1	070-Pasquotank	Preservation	SR 1198 (Oakdale St.)	SR 1199 (Briarwood Rd.)	SR 1211 (Cedar Point Cir.)	0.20	1.25" S9.5B	$25,000
2029	1	070-Pasquotank	Preservation	SR 1199 (Briarwood Rd.)	SR 1147 (Cooper Ln.)	SR 1213 (Evergreen Dr.)	0.34	1.25" S9.5B	$42,000
2029	1	070-Pasquotank	Preservation	SR 1211 (Cedar Point Rd.)	SR 1199 (Briarwood Rd.)	SR 1213 (Evergreen Dr.)	0.22	1.25" S9.5B	$27,000
2029	1	070-Pasquotank	Preservation	SR 1212 (Cedar Point Cir.)	SR 1211 (Cedar Point Cir.)	CDS	0.03	1.25" S9.5B	$5,000
2029	1	070-Pasquotank	Preservation	SR 1213 (Evergreen Rd.)	SR 1199 (Briarwood Rd.)	SR 1211 (Cedar Point Cir.)	0.15	1.25" S9.5B	$18,000
2029	1	070-Pasquotank	Preservation	SR 1233 (Dennis Dr.)	SR 1192 (Bruce Dr.)	Dead End	0.12	1.25" S9.5B	$15,000
2029	1	072-Perquimans	Resurfacing	SR 1217 (Doll Harrell Rd)	SR 1215 (Bagley Swamp Rd.)	End of Pavement	0.66	Full Depth Patching and 1.5" S9.5B	$119,000
2029	1	072-Perquimans	Resurfacing	SR 1305 (Body Rd.)	SR 1303 (Woodland Church Rd.)	SR 1367 (Old US 17)	3.19	Full Depth Patching and 1.5" S9.5B	$637,000
2029	1	072-Perquimans	Resurfacing	SR 1317 (Camp Perry Rd.)	SR 1300 (New Hope Rd.)	End of Maintenance	1.87	Full Depth Patching and 1.5" S9.5B	$374,000
2029	1	072-Perquimans	Resurfacing	SR 1367 (Old US 17)	US 17	Pasquotank County Line	1.33	Full Depth Patching and 1.5" S9.5B	$318,000
2029	1	072-Perquimans	Resurfacing	SR 1481 (E. Camp Perry Rd.)	SR 1317 (Camp Perry Rd.)	Dead End	0.44	Full Depth Patching and 1.5" S9.5B	$88,000
2029	1	072-Perquimans	Preservation	SR 1002 (County Line Rd.)	NC 37	SR 1115 (Poplar Neck Rd.)	4.17	1.25" S9.5B	$507,000
2029	1	089-Tyrrell	Resurfacing	NC 94	US 64	Washington County	6.37	Full Depth Patching and 1.5" S9.5B	$1,462,000
2029	1	089-Tyrrell	Preservation	SR 1104 (Newlands Rd.)	NC 94	SR 1105 (Riders Creek Rd.)	1.02	Seal - Double	$46,000
2029	1	089-Tyrrell	Preservation	SR 1105 (Crosslanding Rd. / Newlands Rd.)	SR 1115 (Chapel Hill Rd.)	SR 1122 (South Fork Creek Rd.)	3.68	Seal - Double	$184,000
2029	1	089-Tyrrell	Preservation	SR 1105 (Newlands Rd. / Riders Creek Rd.)	SR 1108 (Bodwell Rd.)	NC 94	2.79	Seal - Double	$140,000
2029	1	089-Tyrrell	Preservation	SR 1108 (Bodwell Rd.)	SR 1105 (Crosslanding Rd.)	SR 1105 (Newlands Rd.)	3.37	Seal - Double	$152,000
2029	1	089-Tyrrell	Preservation	SR 1114 (Chapel Hill Rd.)	SR 1113 (Travis Rd.)	SR 1115 (Travis School Rd.)	0.75	Seal - Double	$34,000
2029	1	089-Tyrrell	Preservation	SR 1115 (Chapel Hill Rd.)	SR 1116 (Woodley Station Rd.)	End of Pavement	1.60	Seal - Double	$72,000
2029	1	089-Tyrrell	Preservation	SR 1122 (South Fork Creek Rd.)	SR 1105 (Newlands Rd.)	SR 1121 (South Fork Loop)	2.05	Seal - Double	$102,000
2029	1	094-Washington	Resurfacing	NC 32	US 64	NC 37	12.88	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$3,800,000
2029	1	094-Washington	Resurfacing	NC 45	NC 32	Bertie County	3.27	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$915,000
2029	1	094-Washington	Resurfacing	NC 94	SR 1304 (Scuppernong Rd.)	NC 37	4.99	Full Depth Patching and 1.5" S9.5C	$1,160,000
2029	2	007-Beaufort	Resurfacing	NC 306	BAYVIEW FERRY	NC 92	0.25	Mill 1.5" and 1.5" S9.5C	$150,000
2029	2	007-Beaufort	Resurfacing	NC 92	BACK CREEK DRIVE	NC 99	5.31	Mill 1.5" and 1.5" S9.5C	$1,750,000
2029	2	007-Beaufort	Resurfacing	NC 99	NC 92	BELHAVEN BRIDGE	10.53	Mill 1.5" and 1.5" S9.5C	$3,500,000
2029	2	007-Beaufort	Resurfacing	SR 1128	SR 1127	SR 1129	1.05	1.5" S9.5B	$210,000
2029	2	007-Beaufort	Resurfacing	SR 1134	US 17	SR 1152	2.80	1.5" S9.5B	$559,600
2029	2	007-Beaufort	Resurfacing	SR 1135	SR 1134	DEAD END	0.37	1.5" S9.5B	$74,000
2029	2	007-Beaufort	Resurfacing	SR 1143	NC 33	US 17	2.95	1.5" S9.5B	$589,800
2029	2	007-Beaufort	Resurfacing	SR 1152	US 17	SR 1154	1.60	1.5" S9.5B	$320,600
2029	2	007-Beaufort	Resurfacing	SR 1152	SR 1136	US 17	1.77	1.5" S9.5B	$354,200
2029	2	007-Beaufort	Resurfacing	SR 1153	SR 1152	DEAD END	0.65	1.5" S9.5B	$130,000
2029	2	007-Beaufort	Resurfacing	SR 1163	NC 33	NC 33	2.00	1.5" S9.5B	$400,800
2029	2	007-Beaufort	Resurfacing	SR 1164	SR 1163	PITT COUNTY	0.34	1.5" S9.5B	$68,000
2029	2	007-Beaufort	Resurfacing	SR 1168	US 17	SR 1134	0.19	1.5" S9.5B and Widen	$56,700
2029	2	007-Beaufort	Resurfacing	SR 1714	NC 99	US 264	3.03	1.5" S9.5B	$620,000
2029	2	007-Beaufort	Preservation	SR 1109	SR 1106	END MAINTENANCE	0.60	Seal - Double	$21,500
2029	2	007-Beaufort	Preservation	SR 1152	SR 1136	SR 1154	3.37	Patching and Double Seal	$121,500
2029	2	007-Beaufort	Preservation	SR 1179	SR 1107	END MAINTENANCE	0.27	Seal - Double	$9,700
2029	2	007-Beaufort	Preservation	SR 1311	NC 32	US 264	1.91	Seal - Double	$72,694
2029	2	007-Beaufort	Preservation	SR 1313	SR 1311	NC 32	1.65	Seal - Double	$62,852

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	2	007-Beaufort	Preservation	SR 1326	SR 1311	SR 1328	1.63	Full Depth Patching and Double Seal	$61,940
2029	2	007-Beaufort	Preservation	SR 1439	US 17	END MAINTENANCE	0.34	Seal - Double	$10,000
2029	2	007-Beaufort	Preservation	SR 1622	SR 1619	SR 1609	2.17	Seal - Double	$82,460
2029	2	007-Beaufort	Preservation	SR 1927	NC 306	SR 1932	1.44	Seal - Double	$54,834
2029	2	007-Beaufort	Preservation	SR 1933	SR 1932	SR 1934	1.56	Seal - Double	$59,204
2029	2	007-Beaufort	Preservation	SR 1934	SR 1932	CRAVEN COUNTY	2.79	Seal - Double	$105,830
2029	2	016-Carteret	Resurfacing	SR 1324	US 70	END MAINTENANCE	0.50	1.5" S9.5B	$100,000
2029	2	016-Carteret	Resurfacing	SR 1326	US 70	END MAINTENANCE	0.36	1.5" S9.5B	$71,600
2029	2	016-Carteret	Resurfacing	SR 1327	US 70	DEAD END	0.40	1.5" S9.5B	$80,200
2029	2	016-Carteret	Resurfacing	SR 1338	SR 1337	SR 1335	0.17	1.5" S9.5B	$33,400
2029	2	016-Carteret	Resurfacing	SR 1350	US 70	DEAD END	0.20	1.5" S9.5A	$40,000
2029	2	016-Carteret	Resurfacing	SR 1351	US 70	DEAD END	0.34	1.5" S9.5B	$68,000
2029	2	016-Carteret	Resurfacing	SR 1397	SR 1355	DEAD END	0.18	1.5" S9.5B	$35,600
2029	2	016-Carteret	Resurfacing	SR 1403	SR 1378	END MAINTENANCE	0.44	1.5" S9.5B	$88,600
2029	2	016-Carteret	Resurfacing	SR 1404	US 70	DEAD END	0.11	1.5" S9.5B	$22,000
2029	2	016-Carteret	Resurfacing	SR 1416	SR 1414	END MAINTENANCE	1.37	1.5" S9.5B	$273,000
2029	2	016-Carteret	Resurfacing	SR 1419	SR 1399	SR 1335	1.76	1.5" S9.5B	$351,400
2029	2	016-Carteret	Resurfacing	SR 1420	SR 1439	SR 1419	0.10	1.5" S9.5B	$19,600
2029	2	016-Carteret	Resurfacing	SR 1422	SR 1419	SR 1421	0.09	1.5" S9.5B	$18,000
2029	2	016-Carteret	Resurfacing	SR 1423	SR 1419	SR 1421	0.09	1.5" S9.5B	$18,000
2029	2	016-Carteret	Resurfacing	SR 1425	SR 1421	SR 1424	0.19	1.5" S9.5B	$38,200
2029	2	016-Carteret	Resurfacing	SR 1439	SR 1419	END MAINTENANCE	0.28	1.5" S9.5B	$56,000
2029	2	016-Carteret	Resurfacing	SR 1440	SR 1335	END MAINTENANCE	0.07	1.5" S9.5B	$13,800
2029	2	016-Carteret	Resurfacing	SR 1444	SR 1335	SR 1457	0.37	1.5" S9.5B	$73,800
2029	2	016-Carteret	Resurfacing	SR 1450	SR 1336	SR 1451	0.06	1.5" S9.5B	$12,000
2029	2	016-Carteret	Resurfacing	SR 1451	SR 1399	DEAD END	0.20	1.5" S9.5B	$40,800
2029	2	016-Carteret	Resurfacing	SR 1452	SR 1444	DEAD END	0.11	1.5" S9.5B	$21,000
2029	2	016-Carteret	Resurfacing	SR 1453	SR 1416	END MAINTENANCE	0.27	1.5" S9.5B	$53,400
2029	2	016-Carteret	Resurfacing	SR 1456	SR 1444	DEAD END	0.08	1.5" S9.5B	$16,000
2029	2	016-Carteret	Resurfacing	SR 1457	SR 1444	DEAD END	0.07	1.5" S9.5B	$14,000
2029	2	016-Carteret	Resurfacing	SR 1463	SR 1444	SR 1419	0.18	1.5" S9.5B	$36,400
2029	2	016-Carteret	Resurfacing	SR 1478	SR 1416	END MAINTENANCE	0.14	1.5" S9.5B	$28,000
2029	2	016-Carteret	Resurfacing	SR 1482	SR 1351	END MAINTENANCE	0.06	1.5" S9.5B	$12,800
2029	2	016-Carteret	Resurfacing	SR 1483	SR 1333	END MAINTENANCE	0.14	1.5" S9.5B	$28,000
2029	2	016-Carteret	Resurfacing	SR 1484	SR 1483	DEAD END	0.24	1.5" S9.5B	$47,800
2029	2	016-Carteret	Resurfacing	SR 1486	SR 1347	DEAD END	0.27	1.5" S9.5B	$54,000
2029	2	025-Craven	Resurfacing	SR 1199	SR 1004	DEAD END	0.46	1.5" S9.5B	$91,200
2029	2	025-Craven	Resurfacing	SR 1477	NC 43	NC 43	1.37	1.5" S9.5B	$274,000
2029	2	025-Craven	Resurfacing	SR 1478	NC 118	NC 43	2.09	1.5" S9.5B	$418,000
2029	2	025-Craven	Resurfacing	SR 1479	NC 118	END MAINTENANCE	0.40	1.5" S9.5B	$80,000
2029	2	025-Craven	Resurfacing	SR 1481	NC 43	END MAINTENANCE	0.70	1.5" S9.5B	$140,800
2029	2	025-Craven	Resurfacing	SR 1505	SR 1440	END MAINTENANCE	0.34	1.5" S9.5B	$68,000
2029	2	025-Craven	Resurfacing	SR 1510	SR 1477	CUL-DE-SAC	0.16	1.5" S9.5B	$32,000
2029	2	025-Craven	Resurfacing	SR 1520	NC 55	CUL-DE-SAC	0.15	1.5" S9.5B	$30,400
2029	2	025-Craven	Resurfacing	SR 1643	SR 1476	BEAUFORT COUNTY	2.46	1.5" S9.5B	$492,200
2029	2	025-Craven	Resurfacing	SR 1648	DEAD END	DEAD END	0.20	1.5" S9.5B	$40,000
2029	2	025-Craven	Resurfacing	SR 1663	NC 55	END MAINTENANCE	1.30	1.5" S9.5B	$260,000
2029	2	025-Craven	Resurfacing	SR 1664	SR 1663	DEAD END	0.07	1.5" S9.5B	$14,000
2029	2	025-Craven	Resurfacing	SR 1665	SR 1600	END MAINTENANCE	1.01	1.5" S9.5B	$201,400
2029	2	025-Craven	Resurfacing	SR 1669	SR 1600	CUL-DE-SAC	0.29	1.5" S9.5B	$57,200
2029	2	025-Craven	Resurfacing	SR 1670	SR 1669	CUL-DE-SAC	0.03	1.5" S9.5B	$5,400
2029	2	025-Craven	Resurfacing	SR 1924	SR 1199	DEN TREE COURT	0.08	1.5" S9.5B	$15,800
2029	2	025-Craven	Resurfacing	SR 1925	CUL-DE-SAC	CUL-DE-SAC	0.21	1.5" S9.5B	$42,800
2029	2	025-Craven	Resurfacing	SR 1935	SR 2048	CUL-DE-SAC	0.28	1.5" S9.5B	$55,800
2029	2	025-Craven	Resurfacing	SR 1938	SR 1004	SR 1940	0.69	1.5" S9.5B	$138,600
2029	2	025-Craven	Resurfacing	SR 1939	SR 1938	SR 1940	0.34	1.5" S9.5B	$68,200
2029	2	025-Craven	Resurfacing	SR 1940	SR 1004	SR 1938	0.39	1.5" S9.5B	$78,800
2029	2	025-Craven	Resurfacing	SR 1941	SR 1938	DEAD END	0.31	1.5" S9.5B	$62,000
2029	2	025-Craven	Resurfacing	SR 1942	SR 1938	SR 1941	0.21	1.5" S9.5B	$42,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	2	025-Craven	Resurfacing	SR 1943	SR 1938	DEAD END	0.04	1.5" S9.5B	$8,000
2029	2	025-Craven	Resurfacing	SR 1944	SR 1938	DEAD END	0.05	1.5" S9.5B	$10,000
2029	2	025-Craven	Rehabilitation	SR 1488	SR 1400	CUL-DE-SAC	0.20	2.5" I19.0C and 1.5" S9.5B	$85,000
2029	2	025-Craven	Rehabilitation	SR 1489	SR 1488	CUL-DE-SAC	0.20	2.5" I19.0C and 1.5" S9.5B	$85,000
2029	2	040-Greene	Resurfacing	NC 58	LENOIR COUNTY	US 258	5.49	Mill 1.5" and 1.5" S9.5C	$1,750,000
2029	2	040-Greene	Resurfacing	SR 1239	NC 91	SR 1247	4.00	1.5" S9.5B	$800,000
2029	2	040-Greene	Resurfacing	SR 1430	SR 1432	SR 1091	1.38	Full Depth Patching and 1.5" S9.5B	$432,250
2029	2	052-Jones	Resurfacing	SR 1110	SR 1004	DEAD END	2.79	2.0" S9.5C	$378,800
2029	2	052-Jones	Resurfacing	SR 1142	SR 1130	NC 41	3.39	1.5" S9.5B	$678,000
2029	2	052-Jones	Resurfacing	SR 1143	SR 1142	DEAD END	0.48	1.5" S9.5B	$96,000
2029	2	052-Jones	Resurfacing	SR 1318	NC 58	NC 58	2.02	1.5" S9.5B	$402,000
2029	2	052-Jones	Resurfacing	SR 1347	BEGIN MAINTENANCE	DEAD END	0.08	1.5" S9.5B	$16,200
2029	2	052-Jones	Resurfacing	SR 1355	BEGIN MAINTENANCE	END MAINTENANCE	0.15	1.5" S9.5B	$30,000
2029	2	052-Jones	Resurfacing	SR 1365	SR 1327	DEAD END	0.55	1.5" S9.5B	$109,200
2029	2	052-Jones	Preservation	SR 1110	SR 1004	DEAD END	2.79	FDR and Double Seal	$1,750,000
2029	2	054-Lenoir	Resurfacing	NC 58	CUNNINGHAM ROAD	GREENE COUNTY	6.45	Mill 1.5" and 1.5" S9.5C	$2,000,000
2029	2	054-Lenoir	Resurfacing	SR 1105	JONES CO	DUPLIN CO	9.26	1.5" S9.5B	$1,850,000
2029	2	054-Lenoir	Resurfacing	SR 1157	SR 1111	NC 55	4.87	1.5" S9.5B	$974,000
2029	2	054-Lenoir	Resurfacing	SR 1314	NC 903	WAYNE CO	0.70	2.0" S9.5C	$150,000
2029	2	054-Lenoir	Resurfacing	SR 1318	WAYNE CO	SR 1311	3.90	2.0" S9.5C	$550,000
2029	2	054-Lenoir	Resurfacing	SR 1320	NC 903	WAYNE CO	1.11	1.5" S9.5B	$222,000
2029	2	054-Lenoir	Resurfacing	SR 1632	SR 1554	END MAINTENANCE	0.28	1.5" S9.5B	$56,000
2029	2	054-Lenoir	Resurfacing	SR 1671	BEGIN MAINTENANCE	END MAINTENANCE	0.54	1.5" S9.5B	$81,000
2029	2	054-Lenoir	Resurfacing	SR 1808	SR 1803	JONES CO	1.59	1.5" S9.5B	$318,000
2029	2	054-Lenoir	Rehabilitation	SR 1630	SR 1554	DEAD END	0.31	2.5" I19.0C and 1.5" S9.5B	$131,750
2029	2	054-Lenoir	Rehabilitation	SR 1631	CUL-DE-SAC	CUL-DE-SAC	0.26	2.5" I19.0C and 1.75" S9.5B	$110,500
2029	2	054-Lenoir	Rehabilitation	SR 1633	SR 1632	CUL-DE-SAC	0.04	2.5" I19.0C and 1.5" S9.5B	$17,000
2029	2	054-Lenoir	Rehabilitation	SR 1670	CUL-DE-SAC	DEAD END	0.09	2.5" I19.0B and 1.5" S9.5B	$29,250
2029	2	054-Lenoir	Rehabilitation	SR 1672	SR 1671	DEAD END	0.25	2.5" I19.0B and 1.5" S9.5B	$81,250
2029	2	054-Lenoir	Rehabilitation	SR 2029	PVMT CHG	SR 1557	0.88	2.5" I19.0C and 1.5" S9.5B	$374,000
2029	2	054-Lenoir	Preservation	SR 1314	NC 903	WAYNE CO	0.70	FDR and Double Seal	$500,000
2029	2	054-Lenoir	Preservation	SR 1318	WAYNE CO	SR 1311	3.90	FDR and Double Seal	$2,227,778
2029	2	069-Pamlico	Resurfacing	SR 1108	SR 1005	NC 306	2.82	1.5" S9.5B	$564,800
2029	2	069-Pamlico	Resurfacing	SR 1127	NC 55	DEAD END	1.33	1.5" S9.5B	$265,800
2029	2	069-Pamlico	Resurfacing	SR 1360	NC 55	NC 55	1.32	1.5" S9.5B	$263,400
2029	2	074-Pitt	Resurfacing	NC 11 BYPASS	NC 11	US 13	7.59	Mill 1.5" and 1.5" S9.5C	$2,763,700
2029	2	074-Pitt	Resurfacing	NC 11 BYPASS	CLOVERLEAF	NC 11	4.20	Mill 1.5" and 1.5" S9.5C	$1,702,870
2029	2	074-Pitt	Resurfacing	NC 11 BYPASS	CLOVERLEAF	NC 11	0.01	Mill 1.5" and 1.5" S9.5C	$2,003
2029	2	074-Pitt	Resurfacing	NC 11 BYPASS	CLOVERLEAF	NC 11	7.01	Mill 1.5" and 1.5" S9.5C	$2,714,753
2029	2	074-Pitt	Resurfacing	NC 33	SR 1440	EDGECOMBE COUNTY	11.02	Mill 1.5" and 1.5" S9.5C	$4,000,000
2029	2	074-Pitt	Resurfacing	SR 1177	SR 1127	CUL-DE-SAC	0.56	1.5" S9.5B	$112,800
2029	2	074-Pitt	Resurfacing	SR 1261	NC 121	SR 1212	1.89	1.5" S9.5B	$377,600
2029	2	074-Pitt	Resurfacing	SR 1301	SR 1200	SR 1303	0.15	1.0" S4.75A	$18,750
2029	2	074-Pitt	Resurfacing	SR 1302	SR 1200	SR 1303	0.18	1.0" S4.75A	$22,500
2029	2	074-Pitt	Resurfacing	SR 1303	CUL-DE-SAC	DEAD END	0.22	1.0" S4.75A	$26,250
2029	2	074-Pitt	Resurfacing	SR 1307	SR 1200	CUL-DE-SAC	0.30	1.0" S4.75A	$37,500
2029	2	074-Pitt	Resurfacing	SR 1308	SR 1307	CUL-DE-SAC	0.07	1.5" S9.5B	$7,500
2029	2	074-Pitt	Resurfacing	SR 1404	SR 1409	NC 33	4.14	1.5" S9.5B	$828,000
2029	2	074-Pitt	Resurfacing	SR 1405	SR 1404	SR 1400	1.16	1.5" S9.5B	$232,000
2029	2	074-Pitt	Resurfacing	SR 1406	SR 1404	SR 1400	1.21	1.5" S9.5B	$242,000
2029	2	074-Pitt	Resurfacing	SR 1407	NC 33	SR 1404	0.96	1.5" S9.5B	$192,600
2029	2	074-Pitt	Resurfacing	SR 1408	SR 1409	NC 33	3.20	1.5" S9.5B	$640,200
2029	2	074-Pitt	Resurfacing	SR 1409	SR 1400	NC 33	3.65	1.5" S9.5B	$730,000
2029	2	074-Pitt	Resurfacing	SR 1410	SR 1409	EDGECOMBE COUNTY	1.50	1.5" S9.5B	$300,000
2029	2	074-Pitt	Resurfacing	SR 1451	SR 1415	SR 1417	1.30	1.5" S9.5B	$260,000
2029	2	074-Pitt	Resurfacing	SR 1579	US 13	US 264	1.05	1.5" S9.5B	$210,000
2029	2	074-Pitt	Preservation	SR 1400	US 264	NC 33	6.99	Seal - Double	$265,506
2029	2	074-Pitt	Preservation	SR 1403	SR 1401	SR 1401	2.44	Seal - Double	$69,000
2029	2	074-Pitt	Preservation	SR 1551	NC 903	BEAUFORT CO	4.17	Seal - Double	$163,905

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	2	074-Pitt	Preservation	SR 1553	SR 1588	SR 1550	1.22	Seal - Double	$46,170
2029	2	074-Pitt	Preservation	SR 1558	NC 30	DEAD END	0.87	Seal - Double	$32,984
2029	3	010-Brunswick	Resurfacing	NC 211	NC 906	SR 1114	6.24	1.5" S9.5C	$3,000,000
2029	3	010-Brunswick	Resurfacing	NC 906	US 17 BUS	US 17	1.27	1.5" S9.5C	$394,335
2029	3	010-Brunswick	Resurfacing	NC 906	Boat Lane	US 17 BUS	1.49	1.5" S9.5C	$482,760
2029	3	010-Brunswick	Resurfacing	SR 1138	SR 1137	DEAD END	0.83	Full Depth Patching and 1.5" S9.5B and Widening	$228,250
2029	3	010-Brunswick	Resurfacing	SR 1154	SR 1163	NC 179	1.66	Full Depth Patching and 1.5" S9.5B and Widening	$637,560
2029	3	010-Brunswick	Resurfacing	SR 1163	NC 904	SR 1184	2.56	Full Depth Patching and 1.5" S9.5B	$729,600
2029	3	010-Brunswick	Resurfacing	SR 1165	US 17	NC 179	3.53	Full Depth Patching and 1.5" S9.5B	$988,960
2029	3	010-Brunswick	Resurfacing	SR 1167	NC 179	US 17	1.89	Full Depth Patching and 1.5" S9.5B and Widening	$718,960
2029	3	010-Brunswick	Resurfacing	SR 1168	US 17	NC 179	1.19	Full Depth Patching and 1.5" S9.5B and Widening	$453,720
2029	3	010-Brunswick	Resurfacing	SR 1504	SR 1501	NC 211	4.22	Full Depth Patching and 1.5" S9.5B and Widening	$1,160,225
2029	3	010-Brunswick	Resurfacing	SR 1515	NC 87	DEAD END	2.69	Full Depth Patching and 1.5" S9.5B and Widening	$739,475
2029	3	010-Brunswick	Preservation	SR 1246	NC 179	END OF MAINT.	0.66	1.25" S9.5B	$72,710
2029	3	010-Brunswick	Preservation	SR 1247	NC 179	DEAD END	0.56	1.25" S9.5B	$61,930
2029	3	010-Brunswick	Preservation	SR 1260	NC 179	DEAD END	0.58	1.25" S9.5B	$63,360
2029	3	010-Brunswick	Preservation	SR 1269	NC 904	SR 1273	0.61	1.25" S9.5B	$67,210
2029	3	010-Brunswick	Preservation	SR 1273	NC 179	DEAD END	0.06	1.25" S9.5B	$6,600
2029	3	010-Brunswick	Preservation	SR 1277	NC 179	DEAD END	0.56	1.25" S9.5B	$61,710
2029	3	010-Brunswick	Preservation	SR 1278	NC 179	SR 1277	0.61	1.25" S9.5B	$67,210
2029	3	010-Brunswick	Preservation	SR 1306	SR 1308	END MAINT.	1.20	1.25" S9.5B	$132,220
2029	3	010-Brunswick	Preservation	SR 1314	NC 904	SR 1313	0.90	1.25" S9.5B	$99,110
2029	3	010-Brunswick	Preservation	SR 1350	SR 1308	DEAD END	0.92	1.25" S9.5B	$100,980
2029	3	010-Brunswick	Preservation	SR 1365	SR 1315	END MAINT.	0.67	1.25" S9.5B	$73,920
2029	3	010-Brunswick	Preservation	SR 1367	SR 1366	DEAD END	0.06	1.25" S9.5B	$6,600
2029	3	010-Brunswick	Preservation	SR 1372	SR 1304	DEAD END	0.22	1.25" S9.5B	$24,200
2029	3	010-Brunswick	Preservation	SR 1810	NC 179	DEAD END	0.28	1.25" S9.5B	$30,470
2029	3	010-Brunswick	Preservation	SR 1822	NC 904	SR 1273	0.60	1.25" S9.5B	$66,330
2029	3	010-Brunswick	Preservation	SR 1846	NC 179	DEAD END	0.72	1.25" S9.5B	$79,640
2029	3	010-Brunswick	Preservation	SR 1934	NC 179	DEAD END	0.44	1.25" S9.5B	$48,180
2029	3	031-Duplin	Resurfacing	NC 41	NC 41	SR 1154	8.90	1.5" S9.5C	$2,763,450
2029	3	031-Duplin	Resurfacing	NC 903	NC 111	Lenoir County	3.87	1.5" S9.5C	$1,097,428
2029	3	031-Duplin	Resurfacing	SR 1147	US 117	SR 1141	0.80	1.5" S9.5B	$160,000
2029	3	031-Duplin	Resurfacing	SR 1148	SR 1146	NC 11	5.40	1.5" S9.5B	$1,215,000
2029	3	031-Duplin	Resurfacing	SR 1317	US 117	Second Street	0.62	1.5" S9.5B	$124,000
2029	3	031-Duplin	Resurfacing	SR 1325	NC 403	SR 1327	0.47	1.5" S9.5B	$114,250
2029	3	031-Duplin	Resurfacing	SR 1513	SR 1306	SR 1500	0.78	1.5" S9.5B	$554,140
2029	3	031-Duplin	Resurfacing	SR 1554	SR 1555	NC 11	1.38	#67 Mat Seal and 1.5" S9.5B	$345,000
2029	3	031-Duplin	Resurfacing	SR 1715	NC 111	NC 50	8.21	1.5" S9.5B	$1,801,150
2029	3	031-Duplin	Resurfacing	SR 1726	SR 1702	NC 24	2.15	1.5" S9.5B	$483,750
2029	3	031-Duplin	Preservation	SR 1326	SR 1327	DEAD END	0.70	Seal - Double and Fog Seal	$63,000
2029	3	031-Duplin	Preservation	SR 1408	SR 1330	SCL Calypso	0.08	1.0" Sand Asphalt	$17,550
2029	3	031-Duplin	Preservation	SR 1420	SR 1387	Cul De Sac	1.02	Seal - Double and Fog Seal	$91,800
2029	3	031-Duplin	Preservation	SR 1503	SR 1501	SR 1004	2.95	Patching	$67,250
2029	3	031-Duplin	Preservation	SR 1701	NC 24	NC 111	5.95	Seal - Triple and Fog Seal	$535,500
2029	3	031-Duplin	Preservation	SR 1819	SR 1818	NC 50	1.32	Patching	$257,400
2029	3	065-New Hanover	Resurfacing	NC 140 E	I-40	US 17	5.27	1.5" S9.5C	$2,701,458
2029	3	065-New Hanover	Resurfacing	NC 140 W	US 17	I-140	5.57	1.5" S9.5C	$2,855,871
2029	3	065-New Hanover	Resurfacing	SR 1516	Masonboro Loop Road	Masonboro Loop Road	1.14	Full Depth Patching and 1.5" S9.5B	$313,500
2029	3	065-New Hanover	Resurfacing	SR 1519	SR 1492	SR 1492 + 0.3 miles	0.30	Full Depth Patching and 1.25" S9.5B	$82,500
2029	3	065-New Hanover	Resurfacing	SR 1524	US 421	Myrtle Grove Road	0.80	Full Depth Patching and 1.5" S9.5B	$220,000
2029	3	065-New Hanover	Resurfacing	SR 1526	Myrtle Grove Road	Dead End	0.43	Full Depth Patching and 1.5" S9.5B	$113,250
2029	3	065-New Hanover	Resurfacing	SR 1565	NC 132 College Road	Masonboro Loop Road	1.31	Full Depth Patching and 1.5" S9.5B	$360,250
2029	3	065-New Hanover	Resurfacing	SR 1595	Masonboro Loop Road	Sierra Dr	0.40	Full Depth Patching and 1.5" S9.5B	$110,000
2029	3	065-New Hanover	Resurfacing	SR 1596	Monterey Dr	Sierra Dr	0.09	Full Depth Patching and 1.5" S9.5B	$24,200
2029	3	065-New Hanover	Resurfacing	SR 1597	Granada Ave	Monterey Dr	0.61	Full Depth Patching and 1.5" S9.5B	$166,375
2029	3	065-New Hanover	Resurfacing	SR 1598	Monterey Dr	Dead End	0.09	Full Depth Patching and 1.5" S9.5B	$24,475
2029	3	065-New Hanover	Resurfacing	SR 1599	Masonboro Loop Road	Cherokee Trail	0.50	Full Depth Patching and 1.5" S9.5B	$137,500
2029	3	065-New Hanover	Resurfacing	SR 1600	Masonboro Loop Road	Cherokee Trail	0.51	Full Depth Patching and 1.5" S9.5B	$139,425

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	3	065-New Hanover	Resurfacing	SR 1601	Mohican Trail	Masonboro Loop Road	0.74	Full Depth Patching and 1.5" S9.5B	$202,950
2029	3	065-New Hanover	Resurfacing	SR 1611	Monterey Dr	Sierra Dr	0.11	Full Depth Patching and 1.5" S9.5B	$30,250
2029	3	065-New Hanover	Resurfacing	SR 1676	Mohican Trail	Cheyenne Trail	0.43	Full Depth Patching and 1.5" S9.5B	$117,150
2029	3	065-New Hanover	Resurfacing	SR 1705	Masonboro Loop Road	Navaho Trail	0.53	Full Depth Patching and 1.5" S9.5B	$145,750
2029	3	065-New Hanover	Resurfacing	SR 1961	Masonboro Loop Road	Chalice Lane	0.27	Full Depth Patching and 1.5" S9.5B	$73,700
2029	3	065-New Hanover	Resurfacing	SR 1975	Myrtle Grove Road	Dead End	0.46	Full Depth Patching and 1.5" S9.5B	$126,500
2029	3	065-New Hanover	Resurfacing	SR 1976	Grove Point Road	Dead End	0.04	Full Depth Patching and 1.5" S9.5B	$11,000
2029	3	065-New Hanover	Resurfacing	SR 1977	Grove Point Road	Dead End	0.03	Full Depth Patching and 1.5" S9.5B	$8,250
2029	3	065-New Hanover	Resurfacing	SR 1978	Grove Point Road	Cul-De-Sac	0.04	Full Depth Patching and 1.5" S9.5B	$10,450
2029	3	065-New Hanover	Resurfacing	SR 2134	US 421	End Maintenance	0.19	Full Depth Patching and 1.5" S9.5B	$51,975
2029	3	065-New Hanover	Resurfacing	SR 2168	SR 2165	SR 2166	0.11	Full Depth Patching and 1.25" S9.5B	$28,875
2029	3	065-New Hanover	Resurfacing	SR 2505	US 421	Lacewood Ct	0.32	Full Depth Patching and 1.5" S9.5B	$88,000
2029	3	065-New Hanover	Resurfacing	SR 2506	Grove Point Road	Wellborn Road	0.60	Full Depth Patching and 1.5" S9.5B	$165,000
2029	3	065-New Hanover	Resurfacing	SR 2507	Wellborn Road	Dead End	0.23	Full Depth Patching and 1.5" S9.5B	$63,250
2029	3	065-New Hanover	Resurfacing	SR 2508	Wellborn Road	Cul-De-Sac	0.02	Full Depth Patching and 1.5" S9.5B	$5,500
2029	3	065-New Hanover	Resurfacing	SR 2558	Wellborn Road	gammon ct	0.04	Full Depth Patching and 1.5" S9.5B	$11,000
2029	3	065-New Hanover	Resurfacing	SR 2559	Lacewood Ct	Cul-De-Sac	0.12	Full Depth Patching and 1.5" S9.5B	$32,175
2029	3	065-New Hanover	Resurfacing	SR 2560	Cul-De-Sac	Cul-De-Sac	0.21	Full Depth Patching and 1.5" S9.5B	$57,750
2029	3	065-New Hanover	Resurfacing	SR 2561	Lacewood Ct	Cul-De-Sac	0.03	Full Depth Patching and 1.5" S9.5B	$6,875
2029	3	065-New Hanover	Resurfacing	SR 2562	faulkenberry rd	Dead End	0.08	Full Depth Patching and 1.5" S9.5B	$22,000
2029	3	065-New Hanover	Resurfacing	SR 2729	SR 2605	SR 2676	0.12	Mill 1.25" and 1.25" S9.5B	$32,450
2029	3	065-New Hanover	Preservation	SR 2009	Dead End	SR 2018	0.78	1.0" S4.75A	$214,500
2029	3	065-New Hanover	Preservation	SR 2059	SR 2061	SR 1380	0.71	1.0" S4.75A	$195,250
2029	3	065-New Hanover	Preservation	SR 2061	N College Rd	SR 2058	0.65	1.0" S4.75A	$178,750
2029	3	065-New Hanover	Preservation	SR 2348	SR 1276	SR 2374	1.31	1.0" S4.75A	$360,800
2029	3	065-New Hanover	Preservation	SR 2642	SR 2640	DEAD END	0.05	1.0" S4.75A	$20,000
2029	3	065-New Hanover	Preservation	SR 2643	SR 2640	DEAD END	0.06	1.0" S4.75A	$13,750
2029	3	065-New Hanover	Preservation	SR 2645	SR 2607	DEAD END	0.08	1.0" S4.75A	$20,000
2029	3	065-New Hanover	Preservation	SR 2646	SR 2648	DEAD END	0.08	1.0" S4.75A	$31,175
2029	3	065-New Hanover	Preservation	SR 2647	SR 2605	DEAD END	0.05	1.0" S4.75A	$13,475
2029	3	065-New Hanover	Preservation	SR 2677	SR 2640	DEAD END	0.10	1.0" S4.75A	$30,000
2029	3	067-Onslow	Resurfacing	Deppe Loop Rd	US 17	US 17	1.90	1.5" S9.5B	$418,000
2029	3	067-Onslow	Resurfacing	Deppe Rd	SR 1428	US 17	3.60	1.5" S9.5B	$792,000
2029	3	067-Onslow	Resurfacing	Gum Branch Rd	NC 24	New Pavement	1.60	1.5" S9.5B	$352,000
2029	3	067-Onslow	Resurfacing	Hammocks Beach Rd	NC 24	End of Maint	2.19	1.5" S9.5B and Widen	$481,800
2029	3	067-Onslow	Resurfacing	Howell Rd	NC 24	SR 1433	1.08	1.5" S9.5B	$237,600
2029	3	067-Onslow	Resurfacing	Hubert Blvd	NC 24	NC 24	2.98	1.5" S9.5B	$655,600
2029	3	067-Onslow	Resurfacing	Jim Blake Rd	SR 1213	SR 1211	1.05	1.25" S9.5B	$231,000
2029	3	067-Onslow	Resurfacing	NC 24 E	NC 53	US 17	1.65	1.5" S9.5C	$602,518
2029	3	067-Onslow	Resurfacing	NC 24 EB off Ramp	NC 24 E	US 17 S BUS	0.42	1.5" S9.5C	$136,080
2029	3	067-Onslow	Resurfacing	NC 24 EB on Ramp	US 17 S BUS	NC 24 E	0.25	1.5" S9.5C	$81,000
2029	3	067-Onslow	Resurfacing	NC 24 W	US 17	NC 53	1.61	1.5" S9.5C	$801,697
2029	3	067-Onslow	Resurfacing	NC 24 WB off Ramp	NC 24 W	US 17 BUS	0.27	1.5" S9.5C	$87,480
2029	3	067-Onslow	Resurfacing	NC 24 WB on Ramp	US 17 BUS	NC 24 W	0.48	1.5" S9.5C	$155,520
2029	3	067-Onslow	Resurfacing	Old 30 Rd	SR 1406	SR 1428	5.36	Patching and Leveling and 1.5" S9.5B	$1,179,200
2029	3	067-Onslow	Resurfacing	Old Hammocks Beach	NC 24	SR 1511	1.41	1.5" S9.5B	$310,200
2029	3	067-Onslow	Resurfacing	Parkertown Rd	SR 1744	SR 1434	4.60	1.5" S9.5B	$1,012,000
2029	3	067-Onslow	Resurfacing	Quaker Bridge Rd	SR 1308	Dead End	1.26	1.5" S9.5B	$277,200
2029	3	067-Onslow	Resurfacing	US 17 BUS	Chaney Ave	Montford Ln	1.67	Mill 2.0" and 2.0" S9.5C	$1,082,808
2029	3	067-Onslow	Rehabilitation	Belgrade Ext	US 17	SR 1434	0.15	Mill 1.25" and 1.25" S9.5B	$31,000
2029	3	067-Onslow	Rehabilitation	Pittman Rd	NC 24	SR 1463	0.85	Mill 1.25" and 1.25" S9.5B	$168,000
2029	3	067-Onslow	Preservation	Charcoal Ct	SR 1887	EOM	0.07	1.0" S9.5B	$10,500
2029	3	067-Onslow	Preservation	Fairbanks Ct	SR 1874	CDS	0.09	1.0" S4.75A	$8,400
2029	3	067-Onslow	Preservation	Fox Run Rd	SR 1407	CDS	0.16	1.0" S4.75A	$14,250
2029	3	067-Onslow	Preservation	Hunters Trl	NC 24	SR 2329	1.31	Microsurface	$101,000
2029	3	067-Onslow	Preservation	Madison Ct	SR 1873	End Maint	0.06	1.0" S4.75A	$4,275
2029	3	067-Onslow	Preservation	Marina Ct	SR 1982	CDS	0.08	1.0" S4.75A	$7,800
2029	3	067-Onslow	Preservation	Meadow Ln E	SR 1767	EOM	0.43	1.0" S9.5B	$64,500
2029	3	067-Onslow	Preservation	Meadow Ln W	NC 24	EOM	0.95	1.0" S9.5B	$142,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	3	067-Onslow	Preservation	Riggs Rd	SR 1434	SR 1746	8.79	Seal - Cape	$645,145
2029	3	067-Onslow	Preservation	Royal Ct	SR 1711	CDS	0.04	1.0" S9.5B	$3,780
2029	3	067-Onslow	Preservation	Wolverine Pl	SR 1846	CDS	0.09	1.0" S4.75A	$8,100
2029	3	071-Pender	Resurfacing	NC 210	US 421	SR 1102	8.01	1.5" S9.5C	$2,300,000
2029	3	071-Pender	Resurfacing	SR 1115	SR 1114	NC 210	4.30	Full Depth Patching and 1.5" S9.5B	$950,000
2029	3	071-Pender	Resurfacing	SR 1121	NC 210	US 421	6.45	Full Depth Patching and 1.5" S9.5B and Widening	$1,600,000
2029	3	071-Pender	Resurfacing	SR 1315	SR 1318	SR 1347	3.73	Full Depth Patching and 1.5" S9.5B	$900,000
2029	3	071-Pender	Resurfacing	SR 1315	US 117	SR 1315	2.60	Full Depth Patching and 1.5" S9.5B	$580,000
2029	3	071-Pender	Resurfacing	SR 1520	SR 1520	SR 1526	11.20	Full Depth Patching and 1.5" S9.5B	$2,464,000
2029	3	071-Pender	Preservation	SR 1001	NC 11	CL	7.40	Full Depth Patching and 1.0" S4.75A	$1,063,750
2029	3	082-Sampson	Resurfacing	SR 1001	US 421	Duplin County	3.22	1.5" S9.5B	$0
2029	3	082-Sampson	Resurfacing	SR 1114	SR 1113	US 421	1.11	1.5" S9.5B	$305,250
2029	3	082-Sampson	Resurfacing	SR 1130	SR 1004	NC 903	3.53	1.5" S9.5B	$970,750
2029	3	082-Sampson	Resurfacing	SR 1135	NC 411	US 701	3.05	1.5" S9.5B	$838,750
2029	3	082-Sampson	Resurfacing	SR 1162	SR 1105	SR 1105	0.61	1.0" S9.5B	$167,750
2029	3	082-Sampson	Resurfacing	SR 1214	SR 1219	SR 1222	9.76	1.5" S9.5B and Widen	$2,684,275
2029	3	082-Sampson	Resurfacing	SR 1463	US 421	SR 1456	3.10	1.5" S9.5B	$852,500
2029	3	082-Sampson	Resurfacing	SR 1942	SR 1927	SR 1943	2.73	1.5" S9.5B	$0
2029	3	082-Sampson	Resurfacing	US 421	SR 1834	SR 1475	13.76	1.5" S9.5C	$4,830,462
2029	3	082-Sampson	Preservation	SR 1332	SR 1338	SR 1832	4.50	Seal - Double and Fog Seal	$180,000
2029	3	082-Sampson	Preservation	SR 1333	SR 1332	SR 1006	0.84	Seal - Double and Fog Seal	$33,600
2029	3	082-Sampson	Preservation	SR 1346	SR 1323	SR 1333	0.68	Seal - Double and Fog Seal	$27,200
2029	3	082-Sampson	Preservation	SR 1456	SR 1473	NC 242	6.87	Seal - Double and Fog Seal	$274,800
2029	3	082-Sampson	Preservation	SR 1636	SR 1002	NC 55	13.33	Seal - Double and Fog Seal	$533,200
2029	4	033-Edgecombe	Resurfacing	NC-124	NC-42	NC-42/43	9.22	Mill 1.5" and 1.5" S9.5B	$1,819,000
2029	4	033-Edgecombe	Resurfacing	SR 1006	SR 1006	SR 1205	0.24	1.5" S9.5B	$32,400
2029	4	033-Edgecombe	Resurfacing	SR 1100	Pitt County Line	SR 1102	2.56	1.5" S9.5B	$345,600
2029	4	033-Edgecombe	Resurfacing	SR 1101	Wilson County Line	Pitt County Line	1.58	1.5" S9.5B	$213,300
2029	4	033-Edgecombe	Resurfacing	SR 1111	SR 1004	NC 124	0.73	1.5" S9.5B	$98,550
2029	4	033-Edgecombe	Resurfacing	SR 1116	NC 124	NC 42	1.08	1.5" S9.5B	$145,800
2029	4	033-Edgecombe	Resurfacing	SR 1133	SR 1124	Wilson County Line	0.70	1.5" S9.5B	$94,500
2029	4	033-Edgecombe	Resurfacing	SR 1135	Wilson County Line	SR 1002	6.45	1.5" S9.5B	$870,750
2029	4	033-Edgecombe	Resurfacing	SR 1137	NC-42	Wilson County Line	0.41	1.5" S9.5B	$55,350
2029	4	033-Edgecombe	Resurfacing	SR 1205	SR 1003	SR 1006	2.17	1.5" S9.5B	$292,950
2029	4	033-Edgecombe	Resurfacing	SR 1343	US 258	Dead End	0.26	1.25" S9.5B	$29,250
2029	4	033-Edgecombe	Resurfacing	SR 1356	SR 1343	Dead End	0.05	1.25" S9.5B	$5,625
2029	4	033-Edgecombe	Resurfacing	SR 1357	SR 1343	Dead End	0.10	1.25" S9.5B	$11,250
2029	4	033-Edgecombe	Resurfacing	SR 1361	US 258	Dead End	0.49	1.25" S9.5B	$55,125
2029	4	033-Edgecombe	Resurfacing	SR 1362	SR 1361	Dead End	0.08	1.25" S9.5B	$9,000
2029	4	033-Edgecombe	Resurfacing	SR 1363	SR 1205	Dead End	0.14	1.25" S9.5B	$15,750
2029	4	033-Edgecombe	Resurfacing	SR 1412	SR 1407	SR 1404	2.94	1.5" S9.5B	$396,900
2029	4	033-Edgecombe	Resurfacing	SR 1626	US-258	US-258	0.42	1.25" S9.5B	$47,250
2029	4	033-Edgecombe	Resurfacing	US 258	NC-42/43	SR 1344	7.01	Mill 1.5" and 1.5" S9.5B	$1,402,000
2029	4	033-Edgecombe	Preservation	NC-42	NC-43	NC-33	2.64	Crack Seal	$22,565
2029	4	033-Edgecombe	Preservation	NC-97	NC-33	Halifax County Line	8.26	Crack Seal	$53,625
2029	4	033-Edgecombe	Preservation	SR 1124	NC-42	NC-43	8.97	Microsurface	$535,290
2029	4	033-Edgecombe	Preservation	SR 1129	SR 1124	SR 1003	1.57	Microsurface	$102,050
2029	4	042-Halifax	Resurfacing	NC-125	NC-48	NC-125	2.31	Mill 1.5" and 1.5" S9.5B	$891,250
2029	4	042-Halifax	Resurfacing	NC-561	US-301	SR-1114	5.56	Mill 1.5" and 1.5" S9.5C	$1,090,825
2029	4	042-Halifax	Resurfacing	SR 1003	NC-301	SR 1100	4.78	1.5" S9.5B	$668,900
2029	4	042-Halifax	Resurfacing	SR 1114	NC-481	NC-125	5.35	1.25" S9.5B	$615,250
2029	4	042-Halifax	Resurfacing	SR 1222	SR 1002	NC 581	3.62	1.5" S9.5B	$362,000
2029	4	042-Halifax	Resurfacing	SR 1327	SR 1338	Nash County Line	0.89	1.25" S9.5B	$102,350
2029	4	042-Halifax	Resurfacing	SR 1329	NC-561	Warren County Line	1.05	1.25" S9.5B	$120,750
2029	4	042-Halifax	Resurfacing	SR 1338	SR 1327	NC-48	6.24	1.5" S9.5B	$967,200
2029	4	042-Halifax	Resurfacing	SR 1626	SR 1627	NC-48	1.66	1.5" S9.5B	$240,700
2029	4	042-Halifax	Resurfacing	US 301	NC 561	SR 1668	2.43	Mill 1.5" and 1.5" S9.5C	$514,350
2029	4	042-Halifax	Resurfacing	US 301	I-95	NC 581	4.86	1.5" S9.5B	$753,300
2029	4	042-Halifax	Preservation	SR 1104	SR 1003	NC-125	0.42	.75" S4.75A	$32,550

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	4	042-Halifax	Preservation	SR 1104	NC-125	SR 1103	4.16	Crack Seal	$26,000
2029	4	042-Halifax	Preservation	SR 1117	SR 1117	Edge of Pavement	0.52	Seal - Double	$27,300
2029	4	042-Halifax	Preservation	SR 1120	SR 1117	Edge of Pavement	0.60	Seal - Double	$31,500
2029	4	042-Halifax	Preservation	SR 1122	SR 1003	SR 1117	1.11	Seal - Double and Fog Seal	$58,275
2029	4	042-Halifax	Preservation	SR 1131	SR 1133	SR 1139	4.09	Crack Seal	$25,563
2029	4	042-Halifax	Preservation	SR 1131	NC-561	SR 1133	0.59	.75" S4.75A	$45,725
2029	4	042-Halifax	Preservation	SR 1133	NC-561	SR 1131	0.66	.75" S4.75A	$51,150
2029	4	042-Halifax	Preservation	SR 1149	NC-561	Dead End	0.84	Seal - Double	$44,100
2029	4	042-Halifax	Preservation	SR 1204	NC-561	SR 1001	2.73	Crack Seal	$17,063
2029	4	042-Halifax	Preservation	SR 1215	SR 1214	End of Pavement	1.13	Microsurface	$73,450
2029	4	042-Halifax	Preservation	SR 1237	SR 1206	EOP	1.53	Seal - Double	$80,325
2029	4	042-Halifax	Preservation	SR 1605	SR 1615	Dead End	0.77	1.0" S4.75A	$77,000
2029	4	042-Halifax	Preservation	SR 1607	NC-561	Dead End	0.93	.75" S4.75A	$85,250
2029	4	042-Halifax	Preservation	SR 1671	SR 1600	NC 125	1.71	Crack Seal	$10,688
2029	4	042-Halifax	Preservation	SR 1804	NC-903	NC-125	1.06	Crack Seal	$6,625
2029	4	042-Halifax	Preservation	SR 1816	SR 1815	NC-97	3.74	1.25" S9.5B	$233,450
2029	4	051-Johnston	Resurfacing	SR 1120	NC 55	NC 96	2.53	1.5" S9.5B	$341,550
2029	4	051-Johnston	Resurfacing	SR 1132	US-701	SR 1116	3.12	1.5" S9.5B	$421,740
2029	4	051-Johnston	Resurfacing	SR 1157	SR 1143	SR 1159	2.04	1.5" S9.5B	$275,400
2029	4	051-Johnston	Resurfacing	SR 1177	SR 1143	NC-96	1.52	1.5" S9.5B	$205,200
2029	4	051-Johnston	Resurfacing	SR 1178	SR 1225	SR 1182	0.55	Mill 1.5" and 1.5" S9.5B	$162,250
2029	4	051-Johnston	Resurfacing	SR 1178	US-701	SR 1225	2.20	1.5" S9.5B	$297,000
2029	4	051-Johnston	Resurfacing	SR 1209	SR 1159	SR 1169	1.61	1.5" S9.5B	$217,350
2029	4	051-Johnston	Resurfacing	SR 1305	SR 1303	NC 50	1.23	1.5" S9.5B	$166,050
2029	4	051-Johnston	Resurfacing	SR 1328	SR 1399	SR 1330	1.22	1.5" S9.5B	$164,700
2029	4	051-Johnston	Resurfacing	SR 1331	SR 1356	SR 1330	4.55	1.5" S9.5B	$614,250
2029	4	051-Johnston	Resurfacing	SR 1361	SR 1381	NC 50	1.91	1.5" S9.5B	$257,850
2029	4	051-Johnston	Resurfacing	SR 1550	SR 1551	Joint West of Lower Winston Pkwy	1.40	Mill 1.5" and 1.5" S9.5B	$413,000
2029	4	051-Johnston	Resurfacing	SR 1551	Wake County Line	NC 42	3.25	Mill 1.5" and 1.5" S9.5B	$958,750
2029	4	051-Johnston	Resurfacing	SR 1720	Wake County Line	NC-96	11.49	1.5" S9.5B	$1,451,150
2029	4	051-Johnston	Resurfacing	SR 1722	NC-96	SR 1720	3.38	1.5" S9.5B	$456,300
2029	4	051-Johnston	Resurfacing	SR 1913	US 70	SR 1907	3.01	1.5" S9.5B	$406,350
2029	4	051-Johnston	Resurfacing	SR 1928	SR 1927	SR 1003	1.12	1.5" S9.5B	$151,200
2029	4	051-Johnston	Resurfacing	SR 2129	SR 1934	SR 1934	3.01	1.5" S9.5B	$406,350
2029	4	051-Johnston	Resurfacing	SR 2137	SR 1001	US 301	1.65	1.5" S9.5B	$222,750
2029	4	051-Johnston	Resurfacing	SR 2317	SR 2318	SR 2316	1.33	1.5" S9.5B	$179,550
2029	4	051-Johnston	Resurfacing	SR 2357	SR 2354	Wayne County Line	0.82	1.5" S9.5B	$103,700
2029	4	051-Johnston	Resurfacing	SR 2541	SR 1007	Dead End	2.09	1.5" S9.5B	$282,150
2029	4	051-Johnston	Resurfacing	US 301	Wayne County Line	US 301 Two Lane	1.00	Mill 1.5" and 1.5" S9.5C	$500,000
2029	4	051-Johnston	Resurfacing	US 301	SR 2332	SR 2165	6.90	Mill 1.5" and 1.5" S9.5C	$1,366,250
2029	4	051-Johnston	Resurfacing	US 301	SR 1377	US 701	2.47	Mill 1.5" and 1.5" S9.5C	$728,650
2029	4	051-Johnston	Resurfacing	US 301	Wayne County Line	US 301 Two Lane	1.35	Mill 1.5" and 1.5" S9.5C	$500,000
2029	4	051-Johnston	Resurfacing	US 301	I-40	SR 1377	6.13	Mill 1.5" and 1.5" S9.5C	$1,250,750
2029	4	051-Johnston	Resurfacing	US 70	Wake County Line	SR 1533	4.59	Mill 1.5" and 1.5" S9.5C	$1,200,000
2029	4	051-Johnston	Resurfacing	US 70	Wake County Line	SR 1533	4.61	Mill 1.5" and 1.5" S9.5C	$1,200,000
2029	4	051-Johnston	Resurfacing	US 701	SR 1179	SR 1242	2.90	Mill 1.5" and 1.5" S9.5C	$595,975
2029	4	051-Johnston	Preservation	SR 1357	SR 1356	US 301	1.09	1.25" S9.5B	$144,425
2029	4	051-Johnston	Preservation	SR 1381	SR 1380	SR 1168	0.90	1.25" S9.5B	$119,250
2029	4	051-Johnston	Preservation	SR 1388	SR 1361	Cul-De-Sac	0.38	1.25" S9.5B	$42,750
2029	4	051-Johnston	Preservation	SR 1389	SR 1388	Cul-De-Sac	0.32	1.25" S9.5B	$36,000
2029	4	051-Johnston	Preservation	SR 2122	NC 39	SR 2123	1.37	1.25" S9.5B	$157,550
2029	4	051-Johnston	Preservation	SR 2123	NC 39	SR 1934	2.02	1.25" S9.5B	$227,250
2029	4	051-Johnston	Preservation	SR 2326	SR 2327	SR 2387	1.39	1.25" S9.5B	$156,375
2029	4	051-Johnston	Preservation	SR 2328	SR 2388	SR 1001	0.30	1.25" S9.5B	$33,750
2029	4	051-Johnston	Preservation	SR 2329	SR 2381	SR 2392	0.71	1.25" S9.5B	$79,875
2029	4	051-Johnston	Preservation	SR 2367	SR 2366	SR 2309	1.80	1.25" S9.5B	$202,500
2029	4	051-Johnston	Preservation	SR 2368	SR 2320	SR 2367	0.49	1.25" S9.5B	$55,125
2029	4	051-Johnston	Preservation	SR 2380	SR 1927	Dead End	0.61	1.25" S9.5B	$68,625
2029	4	051-Johnston	Preservation	SR 2382	SR 2137	SR 2391	0.32	1.25" S9.5B	$36,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	4	051-Johnston	Preservation	SR 2384	SR 2339	Dead End	0.89	1.25" S9.5B	$100,125
2029	4	051-Johnston	Preservation	SR 2387	SR 1927	SR 2326	0.57	1.25" S9.5B	$64,125
2029	4	051-Johnston	Preservation	SR 2388	SR 2328	RMP-307	0.79	1.25" S9.5B	$88,875
2029	4	051-Johnston	Preservation	SR 2389	I-95 Ramp	End of Pavement	0.26	1.25" S9.5B	$29,250
2029	4	051-Johnston	Preservation	SR 2391	I-95 Ramp	I-95 Ramp	0.94	1.25" S9.5B	$105,750
2029	4	051-Johnston	Preservation	SR 2418	SR 2366	Dead End	0.14	1.25" S9.5B	$15,750
2029	4	051-Johnston	Preservation	SR 2424	SR 2326	Cul-De-Sac	0.33	1.25" S9.5B	$37,125
2029	4	051-Johnston	Preservation	SR 2436	SR 2384	Dead End	0.27	1.25" S9.5B	$30,375
2029	4	051-Johnston	Preservation	SR 2512	SR 2510	SR 2597	1.74	1.25" S9.5B	$195,750
2029	4	064-Nash	Resurfacing	NC 231	Middlesex Corp Parkway	US 264 Alt	0.85	Mill 1.5" and 1.5" S9.5B	$153,000
2029	4	064-Nash	Resurfacing	NC 43	MP 2.00	MP 2.63	0.63	Mill 1.5" and 1.5" S9.5B	$113,400
2029	4	064-Nash	Resurfacing	NC-97	Mile Post 1.61	Mile post 3.4	1.79	1.5" S9.5B	$492,250
2029	4	064-Nash	Resurfacing	SR 1004	NC-561	SR 1401	3.42	1.5" S9.5B	$384,750
2029	4	064-Nash	Resurfacing	SR 1100	Wilson County Line	Dead End	2.98	1.25" S9.5B	$335,250
2029	4	064-Nash	Resurfacing	SR 1111	SR 1101	SR 1113	2.12	1.25" S9.5B	$238,500
2029	4	064-Nash	Resurfacing	SR 1120	End C&G	Johnston County Line	2.34	1.25" S9.5B	$263,250
2029	4	064-Nash	Resurfacing	SR 1123	Mile Marker 0.84	US 264 Alt	0.36	1.25" S9.5B	$40,500
2029	4	064-Nash	Resurfacing	SR 1134	SR 1941	SR 1949	1.85	1.25" S9.5B	$226,625
2029	4	064-Nash	Resurfacing	SR 1134	SR 1941	NC 581	1.85	1.25" S9.5B	$360,150
2029	4	064-Nash	Resurfacing	SR 1148	Webbs Mill Road	NC-581	3.50	1.25" S9.5B	$393,750
2029	4	064-Nash	Resurfacing	SR 1151	Franklin County Line	NC 97	2.77	1.25" S9.5B	$311,625
2029	4	064-Nash	Resurfacing	SR 1165	NC 97	Franklin County Line	0.64	1.25" S9.5B	$72,000
2029	4	064-Nash	Resurfacing	SR 1165	NC-97	SR 1164	0.29	Mill 1.5" and 1.5" S9.5B	$139,200
2029	4	064-Nash	Resurfacing	SR 1175	SR 1174	NC 581	1.28	1.25" S9.5B	$169,600
2029	4	064-Nash	Resurfacing	SR 1429	SR 1426	SR 1428	1.04	1.25" S9.5B	$117,000
2029	4	064-Nash	Resurfacing	SR 1431	SR 1004	SR 1426	1.52	1.25" S9.5B	$171,000
2029	4	064-Nash	Resurfacing	SR 1432	SR 1417	End of Pavement	1.92	1.25" S9.5B	$254,400
2029	4	064-Nash	Resurfacing	SR 1438	SR 1437	SR 1003	1.86	1.25" S9.5B	$209,250
2029	4	064-Nash	Resurfacing	SR 1518	End C&G	SR 1510	1.65	1.25" S9.5B	$185,625
2029	4	064-Nash	Resurfacing	SR 1519	US 301	SR 1518	1.07	1.25" S9.5B	$120,375
2029	4	064-Nash	Resurfacing	SR 1544	SR 1733	SR 1770	5.55	1.5" S9.5B	$804,750
2029	4	064-Nash	Resurfacing	SR 1604	I-95	SR 1613	1.95	1.5" S9.5B	$282,750
2029	4	064-Nash	Resurfacing	SR 1606	SR 1607	NC 43	1.14	1.25" S9.5B	$139,650
2029	4	064-Nash	Resurfacing	SR 1714	Arbor Lane	NC-97	0.67	Mill 1.5" and 1.5" S9.5B	$128,700
2029	4	064-Nash	Resurfacing	SR 1770	Windstead Ave	Buck Leonard Blvd	1.19	Mill 1.5" and 1.5" S9.5B	$232,050
2029	4	064-Nash	Resurfacing	SR 1945	Wilson County Line	Bloomery Road	4.48	1.25" S9.5B	$504,000
2029	4	064-Nash	Resurfacing	SR 1948	SR 1943	SR 1946	1.89	1.25" S9.5B	$212,625
2029	4	064-Nash	Resurfacing	SR 1956	SR 1949	SR 1941	2.02	1.25" S9.5B	$227,250
2029	4	064-Nash	Resurfacing	SR 1957	SR 1956	SR 1109	0.57	1.25" S9.5B	$64,125
2029	4	064-Nash	Resurfacing	SR 1961	SR 1102	SR 1962	1.22	1.25" S9.5B	$137,250
2029	4	064-Nash	Resurfacing	SR 1964	SR 1961	Wilson County Line	1.60	1.5" S9.5B	$196,000
2029	4	064-Nash	Resurfacing	SR 1968	NC 581	Dead End	1.87	1.25" S9.5B	$229,075
2029	4	064-Nash	Resurfacing	SR 2314	NC 4	Mile Post 0.11	0.11	Mill 1.5" and 1.5" S9.5B	$19,800
2029	4	064-Nash	Resurfacing	US 64 Alt	NC 581	US 64	1.90	1.25" S9.5B	$256,500
2029	4	064-Nash	Preservation	NC-43	Red Oak Battleboro Rd	Woodruf Rd	4.50	Microsurface	$292,500
2029	4	064-Nash	Preservation	SR 1404	SR 1004	SR 1403	2.97	1.0" S4.75A	$334,125
2029	4	064-Nash	Preservation	SR 1425	NC 58	NC 43	7.22	Microsurface	$469,300
2029	4	064-Nash	Preservation	SR 1944	SR 1941	SR 1945	0.88	1.0" S4.75A	$99,000
2029	4	096-Wayne	Resurfacing	NC-111	SR 1547	NC 222	7.82	Mill 1.5" and 1.5" S9.5B	$1,446,700
2029	4	096-Wayne	Resurfacing	SR 1002	NC-581	SR 1366	4.00	1.5" S9.5B	$540,000
2029	4	096-Wayne	Resurfacing	SR 1003	SR 1731	SR 1719	2.55	1.5" S9.5B	$344,250
2029	4	096-Wayne	Resurfacing	SR 1003	US 13	SR 1731	2.91	Mill 1.5" and 1.5" S9.5B	$480,150
2029	4	096-Wayne	Resurfacing	SR 1120	SR 1932	SR 1915	3.50	1.5" S9.5B	$472,500
2029	4	096-Wayne	Resurfacing	SR 1316	US 117	SR 1300	0.67	1.5" S9.5B	$90,585
2029	4	096-Wayne	Resurfacing	SR 1389	US 117	Dead End	0.11	1.25" S9.5B	$12,375
2029	4	096-Wayne	Resurfacing	SR 1406	SR 1316	Dead End	0.30	1.25" S9.5B	$33,750
2029	4	096-Wayne	Resurfacing	SR 1437	SR 1300	Dead End	0.19	1.25" S9.5B	$20,813
2029	4	096-Wayne	Resurfacing	SR 1438	SR 1316	Dead End	0.07	1.25" S9.5B	$7,875
2029	4	096-Wayne	Resurfacing	SR 1525	NC 111	SR 1534	3.42	1.5" S9.5B	$461,700

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	4	096-Wayne	Resurfacing	SR 1549	SR 1537	SR 1547	1.07	1.25" S9.5B	$120,375
2029	4	096-Wayne	Resurfacing	SR 1599	US 117	Dead End	0.21	1.25" S9.5B	$23,513
2029	4	096-Wayne	Resurfacing	SR 1913	NC 111	SR 1744	2.21	1.5" S9.5B	$298,350
2029	4	096-Wayne	Resurfacing	SR 1914	SR 1915	SR 1913	1.89	1.5" S9.5B	$449,750
2029	4	096-Wayne	Resurfacing	SR 1917	SR 1932	NC-581	1.76	1.5" S9.5B	$237,600
2029	4	096-Wayne	Resurfacing	SR 1928	SR 1918	SR 1932	2.13	1.5" S9.5B	$585,750
2029	4	096-Wayne	Resurfacing	US 70	SR 1721	Lenoir County Line	4.40	Mill 1.5" and 1.5" S9.5D	$1,188,000
2029	4	096-Wayne	Resurfacing	US 70	SR 1721	Lenior County Line	4.40	Mill 1.5" and 1.5" S9.5D	$1,188,000
2029	4	096-Wayne	Preservation	SR 1118	NC-55	SR 1117	2.16	Crack Seal	$13,500
2029	4	096-Wayne	Preservation	SR 1123	SR 1122	SR 1120	0.30	Crack Seal	$1,875
2029	4	096-Wayne	Preservation	SR 1141	NC-55	US-117	0.69	Crack Seal	$4,313
2029	4	096-Wayne	Preservation	SR 1172	US-117	Dead End	0.39	Crack Seal	$2,438
2029	4	096-Wayne	Preservation	SR 1200	US-13	Johnston County Line	2.81	Crack Seal	$17,563
2029	4	096-Wayne	Preservation	SR 1207	SR 1205	US 13	1.67	Crack Seal	$10,438
2029	4	096-Wayne	Preservation	SR 1214	US 70	SR 1219	0.99	Crack Seal	$6,188
2029	4	096-Wayne	Preservation	SR 1229	SR 1229	SR 1226	2.19	Crack Seal	$13,688
2029	4	096-Wayne	Preservation	SR 1230	SR 1229	Johnston County Line	0.13	Crack Seal	$813
2029	4	096-Wayne	Preservation	SR 1231	SR 1234	SR 1229	1.43	Crack Seal	$8,938
2029	4	096-Wayne	Preservation	SR 1506	NC-222	Wilson County Line	4.06	Seal - Double and Fog Seal	$182,700
2029	4	096-Wayne	Preservation	SR 1512	SR 1505	Wilson County Line	1.35	Seal - Double and Fog Seal	$50,750
2029	4	096-Wayne	Preservation	SR 1524	NC-111	SR 1525	0.93	1.25" S9.5B	$104,625
2029	4	096-Wayne	Preservation	SR 1526	NC-222	SR 1525	1.48	.75" S4.75A	$129,500
2029	4	096-Wayne	Preservation	SR 1742	NC-111	SR 1744	1.49	Microsurface	$86,850
2029	4	096-Wayne	Preservation	SR 1743	NC-111	SR 1742	0.34	Microsurface	$20,100
2029	4	096-Wayne	Preservation	SR 1745	SR 1744	NC-111	1.22	Crack Seal	$7,625
2029	4	096-Wayne	Preservation	SR 1746	SR 1744	SR 1752	1.71	Microsurface	$111,150
2029	4	096-Wayne	Preservation	SR 1747	SR 1746	SR 1739	1.35	Microsurface	$84,750
2029	4	096-Wayne	Preservation	SR 1750	SR 1746	SR 1739	1.17	Microsurface	$71,050
2029	4	096-Wayne	Preservation	SR 1784	NC-55	NC-111	0.97	Crack Seal	$6,063
2029	4	096-Wayne	Preservation	SR 1916	SR 1915	Dead End	0.40	Microsurface	$23,000
2029	4	096-Wayne	Preservation	SR 1932	SR 1744	SR 1745	2.66	1.25" S9.5B	$299,250
2029	4	096-Wayne	Preservation	SR 1983	SR 1120	End Maintenance	0.59	Microsurface	$34,350
2029	4	098-Wilson	Resurfacing	NC 42	Bridge JT @ US 301	Edgecombe	8.88	Mill 2.0" and 2.0" S9.5B	$2,508,600
2029	4	098-Wilson	Resurfacing	SR 1165	Raleigh Rd Pkwy	US 301	3.20	Mill 1.5" and 1.5" S9.5B	$1,264,000
2029	4	098-Wilson	Resurfacing	SR 1512	NC 42	Edgecombe County Line	1.22	1.5" S9.5B	$164,700
2029	4	098-Wilson	Resurfacing	SR 1523	SR 1524	SR 1507	1.82	1.5" S9.5B	$245,700
2029	4	098-Wilson	Resurfacing	SR 1537	NC 111	Greene County Line	2.96	1.5" S9.5B and Widen	$661,600
2029	4	098-Wilson	Resurfacing	SR 1579	Bar Tee Bridge Rd	NC 111 / 222	2.30	1.5" S9.5B	$310,500
2029	4	098-Wilson	Resurfacing	SR 1612	Us 301	SR 1613	1.97	1.5" S9.5B	$270,000
2029	4	098-Wilson	Resurfacing	SR 1649	US 301	SR 1658	4.46	1.5" S9.5B	$501,750
2029	4	098-Wilson	Resurfacing	US 301	SR 1649	US 264	3.74	Mill 1.5" and 1.5" S9.5C	$1,000,000
2029	4	098-Wilson	Resurfacing	US 301	Wilson County Line	US 301 Two Lane	1.35	Mill 1.5" and 1.5" S9.5C	$500,000
2029	4	098-Wilson	Preservation	SR 1002	SR 1195	Dead End	0.82	1.0" S9.5A	$91,750
2029	4	098-Wilson	Preservation	SR 1003	Edgecombe County Line	US 301	6.10	1.0" S4.75A	$671,250
2029	4	098-Wilson	Preservation	SR 1357	SR 1323	SR 1358	0.15	Crack Seal	$937
2029	4	098-Wilson	Preservation	SR 1368	US 301	US 301	3.54	Crack Seal	$11,125
2029	4	098-Wilson	Preservation	SR 1447	SR 1323	SR 1358	0.06	Crack Seal	$375
2029	4	098-Wilson	Preservation	SR 1607	SR 1602	NC 58	1.88	Crack Seal	$11,750
2029	4	098-Wilson	Preservation	SR 1618	US 117	SR 1621	0.88	Crack Seal	$5,500
2029	4	098-Wilson	Preservation	SR 1619	SR 1621	US 117	1.51	Crack Seal	$9,437
2029	4	098-Wilson	Preservation	SR 1628	SR 1621	NC 222	7.58	Crack Seal	$47,356
2029	5	032-Durham	Resurfacing	Bivins Rd.	ORANGE CO	SR 1521	1.79	Full Depth Patching and 1.5" S9.5B	$390,000
2029	5	032-Durham	Resurfacing	Continental Dr.	SR 1556	SR 1449	0.18	Full Depth Patching and 1.25" S9.5B	$35,000
2029	5	032-Durham	Resurfacing	Continental Dr.	SR 1449	SR 1557	1.24	Full Depth Patching and 1.25" S9.5B	$241,000
2029	5	032-Durham	Resurfacing	Country Club Dr.	SR 1449	SR 1449	0.77	Full Depth Patching and 1.25" S9.5B	$150,000
2029	5	032-Durham	Resurfacing	Fayetteville Rd	I-40	Renaisance Pkwy	0.64	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$217,000
2029	5	032-Durham	Resurfacing	Fayetteville Rd	Woodcroft Pkwy	I-40	1.18	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$400,000
2029	5	032-Durham	Resurfacing	Green Lane Dr.	SR 1556	SR 1486	0.42	Full Depth Patching and 1.25" S9.5B	$82,000
2029	5	032-Durham	Resurfacing	Intercross Rd	Ramp 2326	Ramp 2367	1.70	Mill 1.5" and 2.5" I19.0C and 1.5" S9.5C	$746,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	5	032-Durham	Resurfacing	Lake Winds Trl	SR 1601	Dead End	0.86	1.0" S9.5B	$107,000
2029	5	032-Durham	Resurfacing	Lark Ln	SR 1557	Cul De Sac	0.09	Full Depth Patching and 1.25" S9.5B	$16,000
2029	5	032-Durham	Resurfacing	Lynn Rd	US 70	SR 1919	0.43	Full Depth Patching and 1.5" S9.5B	$111,000
2029	5	032-Durham	Resurfacing	Lynn Rd	NC 98	SR 2021	0.92	Full Depth Patching and 1.5" S9.5B	$201,000
2029	5	032-Durham	Resurfacing	NC 147 NB	Concrete Pvmt.	Fulton St	1.06	Mill 2.0" and 2.0" S9.5C	$664,000
2029	5	032-Durham	Resurfacing	NC 147 SB	Fulton St	Concrete Pvmt.	1.05	Mill 2.0" and 2.0" S9.5C	$657,000
2029	5	032-Durham	Resurfacing	NC 751	I 40 West + .333 mi	NC 54	0.69	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$436,000
2029	5	032-Durham	Resurfacing	NC 751	Chatham Co	SR 1118	0.67	Full Depth Patching and 1.5" S9.5C	$185,000
2029	5	032-Durham	Resurfacing	NC 751	SR 1118	SR 1192 + .457 mi	1.86	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$567,000
2029	5	032-Durham	Resurfacing	NC 751	SR 1192 + .457 mi	I 40 West + .333 mi	0.62	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$367,000
2029	5	032-Durham	Resurfacing	Ninth St	US 70 Bus	SR 2800	0.03	Mill 1.5" and 3.0" S9.5B	$17,500
2029	5	032-Durham	Resurfacing	Olive Branch Rd	NC 98	NC 98	3.85	Full Depth Patching and 1.5" S9.5B	$839,000
2029	5	032-Durham	Resurfacing	RMP-2374	US 15 SB	15/501 BUS	0.77	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$189,000
2029	5	032-Durham	Resurfacing	RMP-2377	US 15 NB	SR 1308	0.12	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$21,000
2029	5	032-Durham	Resurfacing	RMP-2378	SR 1308	US 15 NB	0.19	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$34,000
2029	5	032-Durham	Resurfacing	RMP-2379	US 15 SB	SR 1308	0.18	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$38,000
2029	5	032-Durham	Resurfacing	RMP-2380	SR 1308	US 15 SB	0.19	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$42,000
2029	5	032-Durham	Resurfacing	RMP-2381	US 15 NB	NC 751	0.10	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$33,000
2029	5	032-Durham	Resurfacing	RMP-2382	NC 751	US 15 NB	0.16	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$29,000
2029	5	032-Durham	Resurfacing	RMP-2383	US 15 SB	NC 751	0.16	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$54,000
2029	5	032-Durham	Resurfacing	RMP-2384	NC 751	US 15 SB	0.15	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$36,000
2029	5	032-Durham	Resurfacing	RMP-2385	US 15 NB	70 BUS	0.17	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$28,000
2029	5	032-Durham	Resurfacing	RMP-2386	70 BUS	US 15 NB	0.27	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$45,000
2029	5	032-Durham	Resurfacing	RMP-2387	US 15 SB	70 BUS	0.22	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$59,000
2029	5	032-Durham	Resurfacing	RMP-2388	70 BUS	US 15 SB	0.26	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$44,000
2029	5	032-Durham	Resurfacing	RMP-2389	US 15 NB	147 SB	0.34	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$77,000
2029	5	032-Durham	Resurfacing	RMP-2390	US 15 SB	US 15 SB	0.33	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$120,000
2029	5	032-Durham	Resurfacing	RMP-2391	147 NB	US 15 NB	0.28	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$63,000
2029	5	032-Durham	Resurfacing	RMP-2392	US 15 SB	147 NB	0.33	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$89,000
2029	5	032-Durham	Resurfacing	RMP-2393	147 SB	US 15 NB	0.27	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$66,000
2029	5	032-Durham	Resurfacing	RMP-2394	US 15 NB	147 NB	0.18	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$45,000
2029	5	032-Durham	Resurfacing	RMP-2395	147 NB	US 15 SB	0.24	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$54,000
2029	5	032-Durham	Resurfacing	RMP-2396	US 15 SB	147 SB	0.25	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$56,000
2029	5	032-Durham	Resurfacing	RMP-2397	US 15 NB	70 BUS	0.09	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$40,000
2029	5	032-Durham	Resurfacing	RMP-2398	70 BUS	US 15 SB	0.14	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$38,000
2029	5	032-Durham	Resurfacing	RMP-2399	70 BUS	US 15 NB	0.20	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$68,000
2029	5	032-Durham	Resurfacing	RMP-2400	US 15 SB	70 BUS	0.19	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$63,000
2029	5	032-Durham	Resurfacing	RMP-2403	Fulton St NB	NC 147 SB	0.19	Mill 2.0" and 2.0" S9.5C	$91,000
2029	5	032-Durham	Resurfacing	RMP-2404	Fulton St SB	NC 147 SB	0.05	Mill 2.0" and 2.0" S9.5C	$14,000
2029	5	032-Durham	Resurfacing	RMP-2405	NC 147 NB	Hillandale Rd NB	0.28	Mill 2.0" and 2.0" S9.5C	$78,000
2029	5	032-Durham	Resurfacing	RMP-2406	NC 147 NB	Fulton St NB	0.10	Mill 2.0" and 2.0" S9.5C	$27,000
2029	5	032-Durham	Resurfacing	RMP-2410	Elba St.	NC 147 SB	0.37	Mill 2.0" and 2.0" S9.5C	$183,000
2029	5	032-Durham	Resurfacing	RMP-2411	NC 147 NB	Elba St	0.39	Mill 2.0" and 2.0" S9.5C	$148,000
2029	5	032-Durham	Resurfacing	RMP-2412	NC 147 SB	Concrete Pvmt.	0.15	Mill 2.0" and 2.0" S9.5C	$37,000
2029	5	032-Durham	Resurfacing	RMP-2415	Swift Ave	NC 147 NB	0.17	Mill 2.0" and 2.0" S9.5C	$43,000
2029	5	032-Durham	Resurfacing	South Lowell Rd	SR 1461	US501	1.93	Full Depth Patching and 1.5" S9.5B and Widening	$724,000
2029	5	032-Durham	Resurfacing	South Lowell Rd	NC 157	SR 1461	2.98	Full Depth Patching and 1.5" S9.5B and Widening	$1,119,000
2029	5	032-Durham	Resurfacing	Todd Rd	SR 1641	SR 1646	0.89	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$177,000
2029	5	032-Durham	Resurfacing	US 15 NB	15/501 on ramp	I-85	1.86	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$811,000
2029	5	032-Durham	Resurfacing	US 15 NB	SR 1116	15/501 on ramp	3.20	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,136,000
2029	5	032-Durham	Resurfacing	US 15 NB	SR 2294	SR 1116	1.17	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$483,000
2029	5	032-Durham	Resurfacing	US 15 SB	SR 1116	SR 2294	1.15	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$629,000
2029	5	032-Durham	Resurfacing	US 15 SB	I-85 Brg	751 Off ramp	1.74	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$697,000
2029	5	032-Durham	Resurfacing	US 15 SB	751 off ramp	SR 1116	3.12	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,041,000
2029	5	032-Durham	Preservation	Breedlove Ave.	SR 1825	NC 98	0.31	1.0" S9.5B	$38,000
2029	5	032-Durham	Preservation	Brightwood Ln.	SR 1815	Dead End	0.65	1.0" S9.5B	$81,000
2029	5	032-Durham	Preservation	Creech Rd	SR 1637	SR 1800	0.95	1.0" S9.5B	$100,000
2029	5	032-Durham	Preservation	Dunnlee Falls	NC 98	NC 98	0.40	1.0" S9.5B	$45,000
2029	5	032-Durham	Preservation	Glen Garnock Cir	SR 2148	Cul-de-sac	0.15	1.0" S9.5B	$19,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	5	032-Durham	Preservation	Gus Rd	SR 1910	END MAINT	0.13	1.0" S9.5B	$16,000
2029	5	032-Durham	Preservation	Gus Rd	SR 2052	END MAINT	0.11	1.0" S9.5B	$15,000
2029	5	032-Durham	Preservation	Hanford Rd	SR 2056	Dead End	0.14	1.0" S9.5B	$16,000
2029	5	032-Durham	Preservation	Hazelwood St	SR 1911	END MAINT	0.16	1.0" S9.5B	$18,000
2029	5	032-Durham	Preservation	Hester Rd	SR 1905	SR 2073	0.38	1.0" S9.5B	$50,000
2029	5	032-Durham	Preservation	Hilden Rd	SR 1471	Person Co	0.44	1.0" S9.5B	$50,000
2029	5	032-Durham	Preservation	Hoverhill St	SR 1911	END MAINT	0.15	1.0" S9.5B	$18,000
2029	5	032-Durham	Preservation	Keith St.	SR 2052	SR 2047	0.16	1.0" S9.5B	$25,000
2029	5	032-Durham	Preservation	Kintail Dr	SR 2148	Cul-de-sac	0.31	1.0" S9.5B	$36,795
2029	5	032-Durham	Preservation	Moray Dr	SR 1901	SR 2139	0.13	1.0" S9.5B	$15,000
2029	5	032-Durham	Preservation	Pamela Dr	SR 1637	Dead End	0.27	1.0" S9.5B	$33,000
2029	5	032-Durham	Preservation	Weatherly Dr	SR 2041	Dead End	0.13	1.0" S9.5B	$16,000
2029	5	032-Durham	Preservation	Wexford Woods Trl	SR 1901	Cul-de-sac	0.30	1.0" S9.5B	$36,000
2029	5	035-Franklin	Resurfacing	Bridle Trail	SR 1101	SR 1907	0.86	Full Depth Patching and 1.25" S9.5B	$151,000
2029	5	035-Franklin	Resurfacing	Derby Place	SR 1907	Cul-de-sac	0.06	Full Depth Patching and 1.25" S9.5B	$11,000
2029	5	035-Franklin	Resurfacing	Flat Rock Church Rd	US 401	SR 1105	4.07	Full Depth Patching and 1.25" S9.5B	$950,000
2029	5	035-Franklin	Resurfacing	Gordon Moore	NC 56	SR 1127	3.31	Full Depth Patching and 1.25" S9.5B	$677,000
2029	5	035-Franklin	Resurfacing	John Sandling	Begin Pavement	GRANVILLE CO	1.82	Full Depth Patching and 1.25" S9.5B	$354,000
2029	5	035-Franklin	Resurfacing	Wes Sandling	NC 56	GRANVILLE CO	1.92	Full Depth Patching and 1.25" S9.5B	$374,000
2029	5	035-Franklin	Preservation	Barnette Rd	NC 98	SR 1709	1.38	Full Depth Patching and Double Seal and Fog Seal	$123,000
2029	5	035-Franklin	Preservation	Collins Mill	SR 1425	NC 561	7.40	Microsurface	$539,000
2029	5	035-Franklin	Preservation	Hillard Rd	NC 561	Cul-de-sac	0.21	Full Depth Patching and Double Seal and Fog Seal	$21,000
2029	5	035-Franklin	Preservation	Hugh Perry	Dead End	NC 561	0.07	Full Depth Patching and Double Seal and Fog Seal	$6,000
2029	5	035-Franklin	Preservation	Moose Loop	NC 561	NC 561	0.48	Full Depth Patching and Double Seal and Fog Seal	$42,000
2029	5	035-Franklin	Preservation	Reynolds	NC 561	End Pavement	1.20	Full Depth Patching and Double Seal	$108,000
2029	5	035-Franklin	Preservation	Simon Collie	SR 1002	Cul-de-sac	0.75	Full Depth Patching and Double Seal	$67,000
2029	5	035-Franklin	Preservation	Terrell Lane Rd	SR 1419	NC 561	1.27	Full Depth Patching and Double Seal and Fog Seal	$113,000
2029	5	039-Granville	Resurfacing	Brogden Rd	NC 56	SR 1004	5.71	Full Depth Patching and 1.5" S9.5B	$1,245,000
2029	5	039-Granville	Resurfacing	Davis Chapel	SR 1300	SR 1431	4.04	Full Depth Patching and 1.5" S9.5B	$881,000
2029	5	039-Granville	Resurfacing	Hawley School Rd	NC 56	SR 1700	0.98	Full Depth Patching and 1.5" S9.5B	$256,000
2029	5	039-Granville	Resurfacing	Hester Rd	SR 1127	SR 1636	3.25	Full Depth Patching and 1.5" S9.5B	$708,000
2029	5	039-Granville	Resurfacing	US 15	SR 1239	Jt. N of Oxford Loop	2.20	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$1,119,000
2029	5	039-Granville	Resurfacing	US 158	SR 1195	US 15	1.20	Full Depth Patching and 1.5" S9.5B	$301,000
2029	5	039-Granville	Resurfacing	Wilson Town	US 15	Dead End	1.88	Full Depth Patching and 1.5" S9.5B	$368,000
2029	5	039-Granville	Preservation	Charlie Stovall Rd	SR-1331	NC 49	1.38	Full Depth Patching and 1.25" S9.5B	$268,000
2029	5	039-Granville	Preservation	Herman Wilkerson	SR 1432	SR 1430	1.12	Full Depth Patching and 1.25" S9.5B	$359,000
2029	5	039-Granville	Preservation	Sam Hall	SR 1429	SR 1426	2.31	Full Depth Patching and 1.25" S9.5B	$449,000
2029	5	039-Granville	Preservation	Sam Young	SR 1426	US 15	2.31	Full Depth Patching and 1.25" S9.5B	$449,000
2029	5	073-Person	Resurfacing	Depot Street	SR 1601	Lake Drive	0.17	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$49,000
2029	5	073-Person	Resurfacing	Depot Street	Lake Drive	Sr 1537	0.21	Full Depth Patching and 1.5" S9.5B	$46,000
2029	5	073-Person	Resurfacing	Edwin Robertson Road	SR 1326	SR 1333	1.89	Full Depth Patching and 1.5" S9.5B	$543,000
2029	5	073-Person	Resurfacing	NC 49	US 501	Granville Co	12.63	Full Depth Patching and 1.5" S9.5B	$3,305,000
2029	5	073-Person	Resurfacing	North Foushee Street	SR 1536	East Morehead	0.12	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$53,000
2029	5	073-Person	Resurfacing	Shiloh Church Rd	US 501	SR 1326	2.51	Full Depth Patching and 1.5" S9.5C	$610,000
2029	5	073-Person	Resurfacing	Todd Rd	NC 49	SR 1520	1.99	Full Depth Patching and 1.5" S9.5B	$434,000
2029	5	073-Person	Resurfacing	US 158 BUS	Old Durham Rd	SR 1576	3.89	Full Depth Patching and 1.5" S9.5B	$1,118,000
2029	5	073-Person	Resurfacing	Woody Store Rd	SR 1329	VIRGINIA	2.71	Full Depth Patching and 1.5" S9.5B	$590,000
2029	5	073-Person	Preservation	Briggs Rd	SR 1111	SR 1107	0.93	Full Depth Patching and Double Seal and Fog Seal	$92,000
2029	5	073-Person	Preservation	Dan Winstead Rd	SR 1157	Cul-de-sac	0.33	Full Depth Patching and Double Seal and Fog Seal	$33,000
2029	5	073-Person	Preservation	Etzold Painter Rd	SR 1001	Cul-de-sac	0.28	Full Depth Patching and Double Seal and Fog Seal	$28,000
2029	5	073-Person	Preservation	Faulkner-Long Rd	SR 1542	Cul-de-sac	0.77	Full Depth Patching and Double Seal and Fog Seal	$77,000
2029	5	073-Person	Preservation	Hal Melton Rd	NC 49	Cul-de-sac	0.44	Full Depth Patching and Double Seal and Fog Seal	$43,000
2029	5	073-Person	Preservation	Medford Oakley Rd	SR 1721	End of Maintenance	0.82	Full Depth Patching and Double Seal and Fog Seal	$74,000
2029	5	073-Person	Preservation	Newton-Pheasant Loop Rd	SR 1102	SR 1183	2.13	Full Depth Patching and Double Seal and Fog Seal	$211,000
2029	5	073-Person	Preservation	Newton-Pheasant Loop Rd	SR 1162	SR 1176	1.18	Full Depth Patching and Double Seal and Fog Seal	$117,000
2029	5	073-Person	Preservation	Oliver Loop Rd	SR 1162	SR 1163	0.82	Full Depth Patching and Double Seal and Fog Seal	$81,000
2029	5	073-Person	Preservation	Vance Wrenn Rd	NC 49	Cul-de-sac	0.35	Full Depth Patching and Double Seal and Fog Seal	$35,000
2029	5	073-Person	Preservation	Weldon Wrenn Rd	SR 1162	Cul-de-sac	0.62	Full Depth Patching and Double Seal and Fog Seal	$61,000
2029	5	091-Vance	Resurfacing	New Bethel Church	SR 1533	NC 39	5.74	Full Depth Patching and 1.25" S9.5B	$1,006,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	5	091-Vance	Resurfacing	North Cokesbury	SR 1513	SR 1001	0.54	Full Depth Patching and 1.25" S9.5B	$94,000
2029	5	091-Vance	Resurfacing	Tiny Broadwick Blvd	Exit 212 S on Ramp	Exit 212 N on Ramp	0.17	1.0" S9.5B	$27,000
2029	5	091-Vance	Resurfacing	Tiny Broadwick Blvd	SR 1218	SR 1101	2.43	1.0" S9.5B	$376,000
2029	5	091-Vance	Resurfacing	Tiny Broadwick Blvd	Zeb Robinson Rd	End Div Hwy	0.07	1.0" S9.5B	$10,000
2029	5	091-Vance	Resurfacing	Tiny Broadwick Blvd	SR 1162	Begin 5 Lane	0.19	1.0" S9.5B	$43,000
2029	5	091-Vance	Resurfacing	Tiny Broadwick Blvd	Begin div hwy	SR 1162	0.20	1.0" S9.5B	$29,000
2029	5	091-Vance	Resurfacing	Tiny Broadwick Blvd	N Cooper Dr	end 5 lane	0.43	1.0" S9.5B	$159,000
2029	5	091-Vance	Resurfacing	Tiny Broadwick Blvd	Exit 212 N on Ramp	N Cooper Dr	0.31	1.0" S9.5B	$44,000
2029	5	091-Vance	Resurfacing	Tiny Broadwick Blvd	SR 1218	Exit 212 N on Ramp	0.11	1.0" S9.5B	$37,000
2029	5	091-Vance	Resurfacing	Tiny Broadwick Blvd	SR 1101	SR 1218	2.42	1.0" S9.5B	$390,000
2029	5	091-Vance	Resurfacing	Walter Bowen	SR 1523	SR 1542	1.49	1.0" S9.5B	$185,000
2029	5	091-Vance	Preservation	Bill Bragg Morton	SR 1501	SR 1503	0.94	1.0" S9.5B	$117,000
2029	5	091-Vance	Preservation	Cobble Creek Dr	SR 1296	Cul-de-sac	0.34	1.0" S9.5B	$42,000
2029	5	091-Vance	Preservation	Cobble Way	US 1	SR 1288	0.07	1.0" S9.5B	$9,000
2029	5	091-Vance	Preservation	George Floyd Rd	SR 1319	Cul de sac	0.66	Full Depth Patching and 1.25" S9.5B	$128,000
2029	5	091-Vance	Preservation	John H Bullock	US 1	Cul-de-sac	1.33	1.0" S9.5B	$165,000
2029	5	091-Vance	Preservation	Johnny Evans Rd	SR 1365	END MAINT	0.71	1.0" S9.5B	$88,000
2029	5	091-Vance	Preservation	Moody Rd	SR 1319	End Pavement	0.48	1.0" S9.5B	$60,000
2029	5	091-Vance	Preservation	Ryans Way Ln	SR 1296	End Maint	0.12	1.0" S9.5B	$15,000
2029	5	091-Vance	Preservation	Stonebridge	SR 1288	SR 1290	0.08	1.0" S9.5B	$10,000
2029	5	091-Vance	Preservation	Stonehenge	Begin Maint	Cul-de-sac	0.27	1.0" S9.5B	$35,000
2029	5	091-Vance	Preservation	Stoneridge Dr	SR 1289	Cul-de-sac	0.10	1.0" S9.5B	$12,000
2029	5	092-Wake	Resurfacing	401 Bus	SR 1945	End Curb and Gutter	0.48	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$228,000
2029	5	092-Wake	Resurfacing	401 Bus	End Curb and Gutter	US 401	1.48	Full Depth Patching and 1.5" S9.5B	$386,000
2029	5	092-Wake	Resurfacing	64 Bus	End Curb and Gutter	SR 2233	2.06	Mill 2.0" and 2.0" S9.5C	$1,011,000
2029	5	092-Wake	Resurfacing	64 Bus	SR 2233	End Curb and Gutter	2.04	Mill 2.0" and 2.0" S9.5C	$997,000
2029	5	092-Wake	Resurfacing	Abalone Way	SR 2488	Cul-de-sac	0.06	Full Depth Patching and 1.5" S9.5B	$12,000
2029	5	092-Wake	Resurfacing	Angier Rd	Spring St	SR 2768	0.86	Full Depth Patching and 1.5" S9.5B	$262,000
2029	5	092-Wake	Resurfacing	Applegarth Ln	SR 1834	SR 3463	0.44	Full Depth Patching and 1.25" S9.5B	$86,000
2029	5	092-Wake	Resurfacing	Balbirnie Ct	SR 1913	Cul-de-sac	0.18	Full Depth Patching and 1.25" S9.5B	$34,000
2029	5	092-Wake	Resurfacing	Ballston Pl	SR 5261	SR 5261	0.31	1.0" S9.5B	$35,000
2029	5	092-Wake	Resurfacing	Ballston Pl	SR 4194	SR 5260	0.25	1.0" S9.5B	$28,000
2029	5	092-Wake	Resurfacing	Barrett Ridge Dr	SR 5742	Cul-de-sac	0.43	Full Depth Patching and 1.5" S9.5B	$89,000
2029	5	092-Wake	Resurfacing	Batnam Pond Dr	SR 1923	GRANVILLE CO	0.38	Full Depth Patching and 1.25" S9.5B	$82,000
2029	5	092-Wake	Resurfacing	Beane Dr	SR 2953	SR 2274	0.34	Full Depth Patching and 1.25" S9.5B	$66,000
2029	5	092-Wake	Resurfacing	Betts Ln	SR 4606	Cul-de-sac	0.18	Full Depth Patching and 1.25" S9.5B	$32,000
2029	5	092-Wake	Resurfacing	Bowspirit	SR 2463	Cul-de-sac	0.06	Full Depth Patching and 1.5" S9.5B	$11,000
2029	5	092-Wake	Resurfacing	Brass Kettle Rd	Dead End	Cul-de-sac	1.23	Full Depth Patching and 1.5" S9.5B	$269,000
2029	5	092-Wake	Resurfacing	Broadhaven Dr	SR 2736	SR 5558	0.45	Full Depth Patching and 1.5" S9.5B	$100,000
2029	5	092-Wake	Resurfacing	Carpenter Pond Rd	SR 1831	DURHAM CO	0.14	Full Depth Patching and 1.5" S9.5B	$36,000
2029	5	092-Wake	Resurfacing	Chalk Rd	SR 4476	SR 1945	1.76	Full Depth Patching and 1.5" S9.5B	$383,000
2029	5	092-Wake	Resurfacing	Cheviot Hills Dr	END MAINT	US 1	0.14	Full Depth Patching and 1.5" S9.5B	$36,000
2029	5	092-Wake	Resurfacing	Cinabar Rd	SR 2542	SR 2606	0.09	Full Depth Patching and 1.25" S9.5B	$14,000
2029	5	092-Wake	Resurfacing	Claflin Ct	SR 4606	Cul-de-sac	0.09	Full Depth Patching and 1.25" S9.5B	$16,000
2029	5	092-Wake	Resurfacing	Clifton Ct	SR 2947	Cul-de-sac	0.09	Full Depth Patching and 1.25" S9.5B	$18,000
2029	5	092-Wake	Resurfacing	Covington Ridge Rd	SR 1909	Cul-de-sac	0.52	Full Depth Patching and 1.5" S9.5B	$113,000
2029	5	092-Wake	Resurfacing	Cranesbill Dr	SR 1833	SR 1831	0.67	Full Depth Patching and 1.25" S9.5B	$136,000
2029	5	092-Wake	Resurfacing	Creek Pine Dr	US 401 Bus	Dead End	0.55	Full Depth Patching and 1.5" S9.5B	$120,000
2029	5	092-Wake	Resurfacing	Crenshaw Dr	SR 1929	END MAINT	0.19	Full Depth Patching and 1.25" S9.5B	$36,000
2029	5	092-Wake	Resurfacing	Deergrass Ct	SR 4696	SR 4923	0.49	Full Depth Patching and 1.25" S9.5B	$96,000
2029	5	092-Wake	Resurfacing	Diamond Dr	SR 2607	SR 2550	0.43	1.0" S9.5B	$43,000
2029	5	092-Wake	Resurfacing	Durbin Way	NC 55	Dead end	0.19	Full Depth Patching and 1.5" S9.5B	$42,000
2029	5	092-Wake	Resurfacing	Dusty Winds Ct	SR 2742	Cul-de-sac	0.08	Full Depth Patching and 1.5" S9.5B	$17,000
2029	5	092-Wake	Resurfacing	Dwight Rowland Rd	SR 2754	NC 42	0.69	Full Depth Patching and 1.5" S9.5B	$142,000
2029	5	092-Wake	Resurfacing	E Garner Rd	SR 2713	I-40	2.22	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$881,000
2029	5	092-Wake	Resurfacing	Eagle Bend Ct	SR 5652	Cul-de-sac	0.03	Full Depth Patching and 1.25" S9.5B	$5,000
2029	5	092-Wake	Resurfacing	Eagle View Dr	SR 5655	Dead End	0.36	Full Depth Patching and 1.25" S9.5B	$63,000
2029	5	092-Wake	Resurfacing	Eagles Crossing Dr	SR 1003	Dead End	0.50	Full Depth Patching and 1.25" S9.5B	$97,000
2029	5	092-Wake	Resurfacing	Flying Eagle Ct	SR 5652	Cul-de-sac	0.09	Full Depth Patching and 1.25" S9.5B	$18,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	5	092-Wake	Resurfacing	Glenhurst North Dr	SR 4876	Dead End	0.10	Full Depth Patching and 1.5" S9.5B	$22,000
2029	5	092-Wake	Resurfacing	Grassy Field Dr	SR 5215	SR 5253	0.24	Full Depth Patching and 1.5" S9.5B	$47,000
2029	5	092-Wake	Resurfacing	Gresham Lake Rd	SR 2012	US 1	1.77	Full Depth Patching and 1.5" S9.5B	$695,000
2029	5	092-Wake	Resurfacing	Haven Hill Ct	SR 4876	Cul-de-sac	0.06	Full Depth Patching and 1.5" S9.5B	$17,000
2029	5	092-Wake	Resurfacing	Havenhurst Ct	SR 4876	Cul-de-sac	0.06	Full Depth Patching and 1.5" S9.5B	$16,000
2029	5	092-Wake	Resurfacing	High Spring Cir	SR 5101	Cul-de-sac	0.14	Full Depth Patching and 1.25" S9.5B	$25,000
2029	5	092-Wake	Resurfacing	Holland Church Rd	SR 1010	SR 2737	2.38	Full Depth Patching and 1.5" S9.5B	$519,000
2029	5	092-Wake	Resurfacing	Honeycutt Rd	SR 2002	SR 2007	1.45	Full Depth Patching and 1.5" S9.5B	$348,000
2029	5	092-Wake	Resurfacing	Hopkins Chapel Rd	SR 2308	NC 96	0.96	Full Depth Patching and 1.5" S9.5B	$210,000
2029	5	092-Wake	Resurfacing	Huntdell Main Dr	SR 2405	SR 2405	0.83	Full Depth Patching and 1.5" S9.5B	$182,000
2029	5	092-Wake	Resurfacing	Jenkins Rd	SR 1923	US 1	1.58	Full Depth Patching and 1.5" S9.5B	$362,000
2029	5	092-Wake	Resurfacing	Kingsbrook Ct	Cul-de-sac	Cul-de-sac	0.19	Full Depth Patching and 1.25" S9.5B	$38,000
2029	5	092-Wake	Resurfacing	Knightdale-Eagle Rock Rd	Pavement Joint	SR 1003	1.92	Full Depth Patching and 1.5" S9.5B	$377,000
2029	5	092-Wake	Resurfacing	Liatris Ln	SR 1833	Cul-de-sac	0.63	Full Depth Patching and 1.25" S9.5B	$110,000
2029	5	092-Wake	Resurfacing	Linnet Rd	SR 2463	Cul-de-sac	0.04	Full Depth Patching and 1.5" S9.5B	$8,000
2029	5	092-Wake	Resurfacing	Lockhart Ln	SR 2002	Cul-de-sac	0.55	Full Depth Patching and 1.5" S9.5B	$120,000
2029	5	092-Wake	Resurfacing	Lowery Dr	SR 1844	Cul-de-sac	0.27	Full Depth Patching and 1.25" S9.5B	$53,000
2029	5	092-Wake	Resurfacing	Macon Rd	SR 1834	SR 1826	1.70	Full Depth Patching and 1.5" S9.5B	$370,000
2029	5	092-Wake	Resurfacing	Mailwood Dr	SR 5259	SR 4194	0.22	Full Depth Patching and 1.5" S9.5B	$48,000
2029	5	092-Wake	Resurfacing	Mailwood Dr	SR 5251	SR 5258	0.48	Full Depth Patching and 1.5" S9.5B	$94,000
2029	5	092-Wake	Resurfacing	Mill Glen Cir	SR 4995	END MAINT	0.22	1.0" S9.5B	$28,000
2029	5	092-Wake	Resurfacing	Millstone Ridge Ct	SR 4995	Cul-de-sac	0.28	Full Depth Patching and 1.25" S9.5B	$49,000
2029	5	092-Wake	Resurfacing	Moneypenny Ct	SR 1006	Dead End	0.06	Full Depth Patching and 1.5" S9.5B	$16,000
2029	5	092-Wake	Resurfacing	Moresham Way	SR 1968	SR 1967	0.75	Full Depth Patching and 1.5" S9.5B	$164,000
2029	5	092-Wake	Resurfacing	NC 55	SR 1110	Apex Peakway	9.33	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,917,000
2029	5	092-Wake	Resurfacing	NC 55	Marco Dr	Lufkin Rd	0.34	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$137,000
2029	5	092-Wake	Resurfacing	NC 55	Pvmt Joint	SR 1110	7.77	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,429,000
2029	5	092-Wake	Resurfacing	Nesting Eagle Dr	SR 5650	Cul-de-sac	0.18	Full Depth Patching and 1.25" S9.5B	$35,000
2029	5	092-Wake	Resurfacing	New Century Rd	SR 1910	Cul-de-sac	0.25	Full Depth Patching and 1.25" S9.5B	$44,000
2029	5	092-Wake	Resurfacing	New Light Rd	Bridge 910092	SR 1901	1.96	Full Depth Patching and 1.5" S9.5B	$534,000
2029	5	092-Wake	Resurfacing	Norwood Rd	SR 3499	NC 50	1.65	Full Depth Patching and 1.5" S9.5B	$397,000
2029	5	092-Wake	Resurfacing	Over Hadden Ct	SR 3463	Cul-de-sac	0.23	1.0" S4.75A	$26,000
2029	5	092-Wake	Resurfacing	Panther Lake Rd	NC 42	SR 1006	2.69	Full Depth Patching and 1.5" S9.5B	$556,000
2029	5	092-Wake	Resurfacing	Pearl Rd	End C&G	SR 2542	0.59	Full Depth Patching and 1.5" S9.5B	$129,000
2029	5	092-Wake	Resurfacing	Pine Rock Ct	SR 5178	Cul-de-sac	0.07	Full Depth Patching and 1.25" S9.5B	$13,000
2029	5	092-Wake	Resurfacing	Prairie Pond Cir	SR 5692	SR 4995	0.38	1.0" S9.5B	$48,000
2029	5	092-Wake	Resurfacing	Purnell Rd	SR 1917	SR 1907	3.71	Full Depth Patching and 1.5" S9.5B	$890,000
2029	5	092-Wake	Resurfacing	Quiet Ridge Dr	SR 4995	Cul-de-sac	0.29	Full Depth Patching and 1.25" S9.5B	$56,000
2029	5	092-Wake	Resurfacing	Rachel Dr	SR 1927	END MAINT	0.32	Full Depth Patching and 1.5" S9.5B	$63,000
2029	5	092-Wake	Resurfacing	Ridgeline Dr	NC 98	Cul-de-sac	0.22	Full Depth Patching and 1.5" S9.5B	$42,000
2029	5	092-Wake	Resurfacing	River Dance Dr	Cul-de-sac	SR 5670	0.51	Full Depth Patching and 1.25" S9.5B	$100,000
2029	5	092-Wake	Resurfacing	Rivermead Ln	SR 1917	Cul-de-sac	0.43	Full Depth Patching and 1.25" S9.5B	$83,000
2029	5	092-Wake	Resurfacing	Rogers Rd	SR 5114	Heritage Gates Dr	1.56	Full Depth Patching and 1.5" S9.5B	$443,000
2029	5	092-Wake	Resurfacing	S New Hope Rd	Beg Div Hwy	US 64 Bus	1.13	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$299,000
2029	5	092-Wake	Resurfacing	S New Hope Rd	US 64 Bus	SR 1007	2.31	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$612,000
2029	5	092-Wake	Resurfacing	Sand Hollow Cir	SR 4476	SR 5102	0.34	Full Depth Patching and 1.5" S9.5B	$67,000
2029	5	092-Wake	Resurfacing	Sandybrook Ln	Cul-de-sac	END MAINT	0.30	Full Depth Patching and 1.5" S9.5B	$65,000
2029	5	092-Wake	Resurfacing	Seward Dr	SR 5258	Cul-de-sac	0.20	Full Depth Patching and 1.5" S9.5B	$44,000
2029	5	092-Wake	Resurfacing	Shady Glen Ln	SR 1915	Dead End	0.45	Full Depth Patching and 1.25" S9.5B	$78,000
2029	5	092-Wake	Resurfacing	Siemens Rd	NC 97	END MAINT	0.53	Full Depth Patching and 1.5" S9.5B	$147,000
2029	5	092-Wake	Resurfacing	Siler Star Dr	SR 2555	Cul-de-sac	0.25	Full Depth Patching and 1.5" S9.5B	$49,000
2029	5	092-Wake	Resurfacing	Six Forks Rd	NC 98	SR 1847	1.49	Full Depth Patching and 1.5" S9.5B	$356,000
2029	5	092-Wake	Resurfacing	Six Forks Rd	SR 1884	SR 3497	1.00	Full Depth Patching and 1.5" S9.5B	$241,000
2029	5	092-Wake	Resurfacing	Soaring Eagle Ct	Dead End	Dead End	0.21	Full Depth Patching and 1.25" S9.5B	$37,000
2029	5	092-Wake	Resurfacing	Stonewyck Ln	SR 1917	Cul-de-sac	0.21	Full Depth Patching and 1.5" S9.5B	$46,000
2029	5	092-Wake	Resurfacing	Streeter Ln	SR 4617	SR 2005	0.12	Full Depth Patching and 1.5" S9.5B	$26,000
2029	5	092-Wake	Resurfacing	Sun Star Dr	SR 5217	Cul-de-sac	0.24	1.0" S9.5B	$26,000
2029	5	092-Wake	Resurfacing	Swans Mill Xing	SR 4606	Cul-de-sac	0.65	Full Depth Patching and 1.5" S9.5B	$141,000
2029	5	092-Wake	Resurfacing	Tackett Pond Dr	SR 4992	Cul-de-sac	1.06	Full Depth Patching and 1.5" S9.5B	$232,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	5	092-Wake	Resurfacing	Thaarrington Rd	SR 1967	Dead End	0.51	Full Depth Patching and 1.5" S9.5B	$110,000
2029	5	092-Wake	Resurfacing	Tharps Ln	SR 4606	END MAINT	0.34	Full Depth Patching and 1.25" S9.5B	$60,000
2029	5	092-Wake	Resurfacing	Twinleaf Ct	SR 4695	Dead End	0.39	1.0" S9.5B	$49,000
2029	5	092-Wake	Resurfacing	Varcroft	SR 4194	SR 4194	0.38	1.0" S9.5B	$43,000
2029	5	092-Wake	Resurfacing	W Millbrook Rd	Gardencrest Cir	SR 1820	0.38	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$214,000
2029	5	092-Wake	Resurfacing	W Millbrook Rd	SR 1822	Pleasant Grove Ch Rd	0.54	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$292,000
2029	5	092-Wake	Resurfacing	W Millbrook Rd	SR 3466	SR 3466	0.42	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$121,000
2029	5	092-Wake	Resurfacing	W Millbrook Rd	Old Towne Rd	N Hills Dr	0.58	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$161,000
2029	5	092-Wake	Resurfacing	W Millbrook Rd	N Hills Dr	Gardencrest Cir	0.59	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$170,000
2029	5	092-Wake	Resurfacing	W Millbrook Rd	SR 1822	NC 50+ .069 mi	0.93	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$257,000
2029	5	092-Wake	Resurfacing	W Millbrook Rd	Pleasant Grove Ch Rd	US 70	0.51	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$135,000
2029	5	092-Wake	Resurfacing	W Millbrook Rd	SR 1820	SR 1822	1.40	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$821,000
2029	5	092-Wake	Resurfacing	Waterline Dr	SR 1908	Cul-de-sac	0.22	Full Depth Patching and 1.5" S9.5B	$47,000
2029	5	092-Wake	Resurfacing	Weeping Glen Ct	SR 4995	Cul-de-sac	0.23	1.0" S9.5B	$30,000
2029	5	092-Wake	Resurfacing	West Lake Rd	SR 1010	Begin C&G	1.08	Full Depth Patching and 1.5" S9.5B	$271,000
2029	5	092-Wake	Resurfacing	West Lake Rd	Begin C&G	SR 1390	0.56	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$371,000
2029	5	092-Wake	Resurfacing	White Fir Dr	SR 5177	Cul-de-sac	0.21	Full Depth Patching and 1.25" S9.5B	$36,000
2029	5	092-Wake	Resurfacing	Widespan Dr	SR 2558	END MAINT	0.25	Full Depth Patching and 1.5" S9.5B	$55,000
2029	5	092-Wake	Resurfacing	Wood Henge Dr	SR 4912	SR 5668	0.16	Full Depth Patching and 1.25" S9.5B	$31,000
2029	5	092-Wake	Resurfacing	Yew Pine Ct	SR 5178	Cul-de-sac	0.04	Full Depth Patching and 1.25" S9.5B	$7,000
2029	5	092-Wake	Preservation	Andiron Ln	SR 3463	SR 1005	0.25	1.0" S9.5B	$28,000
2029	5	092-Wake	Preservation	Annonhill St	SR 5710	Dead End	0.08	1.0" S9.5B	$9,000
2029	5	092-Wake	Preservation	Arbor Rose Ln	SR 2224	Cul-de-sac	0.09	1.0" S9.5B	$11,000
2029	5	092-Wake	Preservation	Atherton Bridge Rd	SR1833	Cul-de-sac	0.17	1.0" S9.5B	$21,000
2029	5	092-Wake	Preservation	Azure Ln	SR 4923	Cul-de-sac	0.10	1.0" S9.5B	$11,000
2029	5	092-Wake	Preservation	Bagshiot Ct	SR 4509	Cul-de-sac	0.18	1.0" S9.5B	$22,000
2029	5	092-Wake	Preservation	Baslow Brook Ct	SR 4956	Cul de sac	0.08	1.0" S9.5B	$10,000
2029	5	092-Wake	Preservation	Beechtree Camp Dr	Dead End	Cul-de-sac	0.11	1.0" S9.5B	$12,000
2029	5	092-Wake	Preservation	Bridlespur Ln	SR 2947	Cul-de-sac	0.09	1.0" S9.5B	$9,000
2029	5	092-Wake	Preservation	Buteo Ct	SR 1421	Cul-de-sac	0.09	1.0" S9.5B	$11,000
2029	5	092-Wake	Preservation	Cabin Creek Ln	SR 4995	Cul-de-sac	0.07	1.0" S9.5B	$9,000
2029	5	092-Wake	Preservation	Clear Cut Ct	Cul-de-sac	Cul-de-sac	0.15	1.0" S9.5B	$18,000
2029	5	092-Wake	Preservation	Conly Dr	SR 1375	Dead End	0.08	1.0" S9.5B	$8,000
2029	5	092-Wake	Preservation	Cosmos Ct	SR 4923	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2029	5	092-Wake	Preservation	Covey Rise Ln	SR 4817	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2029	5	092-Wake	Preservation	Cross Clay Ct	SR 3463	Cul-de-sac	0.05	1.0" S9.5B	$6,000
2029	5	092-Wake	Preservation	Cypress Wood Ct	SR 1386	Cul-de-sac	0.14	1.0" S9.5B	$17,000
2029	5	092-Wake	Preservation	Dickinson Cir	SR 3463	Cul-de-sac	0.12	1.0" S9.5B	$15,000
2029	5	092-Wake	Preservation	Fire Pink Way	SR 4923	Cul-de-sac	0.05	1.0" S9.5B	$5,000
2029	5	092-Wake	Preservation	Flower Blossom Cir	Dead End	Cul-de-sac	0.13	1.0" S9.5B	$15,000
2029	5	092-Wake	Preservation	Fox Knoll Dr	SR 2764	Cul-de-sac	0.24	1.0" S9.5B	$30,000
2029	5	092-Wake	Preservation	Gelfield Rd	SR 5263	Cul-de-sac	0.11	1.0" S9.5B	$12,000
2029	5	092-Wake	Preservation	Glen Dean Ct	SR 4840	Cul-de-sac	0.12	1.0" S9.5B	$15,000
2029	5	092-Wake	Preservation	High Glen Pt	SR 4995	Cul-de-sac	0.09	1.0" S9.5B	$10,000
2029	5	092-Wake	Preservation	Hunter Hill Rd	SR 2214	SR 2951	0.19	1.0" S9.5B	$21,000
2029	5	092-Wake	Preservation	Hunters Meadow Ln	SR 1379	Cul-de-sac	0.20	1.0" S9.5B	$22,000
2029	5	092-Wake	Preservation	Hunters Meadow Ln	SR 1379	Cul-de-sac	0.16	1.0" S9.5B	$18,000
2029	5	092-Wake	Preservation	Jefferys Ln	SR 2052	END MAINT	0.18	1.0" S9.5B	$22,000
2029	5	092-Wake	Preservation	Karbas Rd	SR 5742	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2029	5	092-Wake	Preservation	Linkside Ct	SR 1393	Cul-de-sac	0.11	1.0" S9.5B	$14,000
2029	5	092-Wake	Preservation	Little Beaverdam Ct	SR 1111	Cul-de-sac	0.21	1.0" S9.5B	$26,000
2029	5	092-Wake	Preservation	Longstone Way	SR 4956	Cul-de-sac	0.12	1.0" S9.5B	$15,000
2029	5	092-Wake	Preservation	Mandrake Ct	SR 4695	Cul-de-sac	0.09	1.0" S9.5B	$11,000
2029	5	092-Wake	Preservation	Milan CT	SR 4695	Cul-de-sac	0.03	1.0" S9.5B	$3,000
2029	5	092-Wake	Preservation	Mill Creek Ct	SR 1371	Cul-de-sac	0.07	1.0" S9.5B	$7,000
2029	5	092-Wake	Preservation	Mollington Ct	SR 4953	Cul-de-sac	0.09	1.0" S9.5B	$11,000
2029	5	092-Wake	Preservation	Mossy Glen Ct	SR 4992	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2029	5	092-Wake	Preservation	Mossy Ridge Ct	Cul-de-sac	Cul de sac	0.10	1.0" S9.5B	$12,000
2029	5	092-Wake	Preservation	Naylor Rd	SR 5263	Cul-de-sac	0.09	1.0" S9.5B	$10,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	5	092-Wake	Preservation	Neighbors Dr	SR 4593	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2029	5	092-Wake	Preservation	Old Lantern Ct	SR 3463	Cul-de-sac	0.16	1.0" S9.5B	$18,000
2029	5	092-Wake	Preservation	Old Mill Creek Ct	SR 4999	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2029	5	092-Wake	Preservation	Oriole Dr	SR 4588	Cul de sac	0.16	1.0" S9.5B	$18,000
2029	5	092-Wake	Preservation	Oxalis Dr	SR 4695	Dead End	0.09	1.0" S9.5B	$11,000
2029	5	092-Wake	Preservation	Parker Falls Dr	SR 1831	2R 5668	0.14	1.0" S9.5B	$17,000
2029	5	092-Wake	Preservation	Paulawood Ln	SR 2725	Cul-de-sac	0.08	1.0" S9.5B	$10,000
2029	5	092-Wake	Preservation	Pile Rd	SR 2555	Dead End	0.11	1.0" S9.5B	$9,000
2029	5	092-Wake	Preservation	Printice Pl	SR 2947	Cul-de-sac	0.06	1.0" S9.5B	$7,000
2029	5	092-Wake	Preservation	Quail Bluff Ct	SR 2044	Cul-de-sac	0.06	1.0" S9.5B	$7,000
2029	5	092-Wake	Preservation	Quail Landing Ct	SR 5057	Cul-de-sac	0.06	1.0" S9.5B	$7,000
2029	5	092-Wake	Preservation	Ridgeford Rd	SR 1375	Cul-de-sac	0.09	1.0" S9.5B	$10,000
2029	5	092-Wake	Preservation	Roseland Ct	SR 4695	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2029	5	092-Wake	Preservation	Ruby Dr	SR 2542	SR 2606	0.09	1.0" S9.5B	$9,000
2029	5	092-Wake	Preservation	Rustic Brick Rd	SR 2723	Cul-de-sac	0.22	1.0" S9.5B	$27,000
2029	5	092-Wake	Preservation	Settlers Ridge Ln	SR 4999	SR 4995	0.18	1.0" S9.5B	$20,000
2029	5	092-Wake	Preservation	Sextons Creek Dr	SR 1846	SR 4995	0.33	1.0" S9.5B	$37,000
2029	5	092-Wake	Preservation	Shinleaf Ct	SR 4900	Cul-de-sac	0.05	1.0" S9.5B	$5,000
2029	5	092-Wake	Preservation	Silver Mist Ct	SR 5668	Cul-de-sac	0.14	1.0" S9.5B	$17,000
2029	5	092-Wake	Preservation	Silverling Way	SR 4697	END MAINT	0.12	1.0" S9.5B	$13,000
2029	5	092-Wake	Preservation	Skeenes Ct	SR 4607	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2029	5	092-Wake	Preservation	Small Ridge Cir	SR 4992	Cul-de-sac	0.08	1.0" S9.5B	$8,000
2029	5	092-Wake	Preservation	Sonesta Court	SR 1833	Cul-de-sac	0.09	1.0" S9.5B	$15,000
2029	5	092-Wake	Preservation	Spring Meadows Ln	SR 1379	Cul-de-sac	0.14	1.0" S9.5B	$17,000
2029	5	092-Wake	Preservation	Stargrass Ct	SR 4696	Dead End	0.11	1.0" S9.5B	$14,000
2029	5	092-Wake	Preservation	Stoneglen Ln	SR 1392	Cul-de-sac	0.17	1.0" S9.5B	$19,000
2029	5	092-Wake	Preservation	Sunset Glen Pt	SR 4995	SR 5691	0.16	1.0" S9.5B	$18,000
2029	5	092-Wake	Preservation	Turning Brook Ln	SR 2227	Cul-de-sac	0.21	1.0" S9.5B	$23,000
2029	5	092-Wake	Preservation	Van Dorn Rd	SR 5258	SR 5260	0.23	1.0" S9.5B	$25,000
2029	5	092-Wake	Preservation	Vermillion Ct	NC 98	Cul-de-sac	0.09	1.0" S9.5B	$10,000
2029	5	092-Wake	Preservation	White Dove Ct	SR 5055	Cul-de-sac	0.14	1.0" S9.5B	$17,000
2029	5	092-Wake	Preservation	Wildmarsh Dr	SR 4695	SR 4905	0.16	1.0" S9.5B	$20,000
2029	5	092-Wake	Preservation	Willow Crest Ln	SR 4887	Cul-de-sac	0.09	1.0" S9.5B	$10,000
2029	5	092-Wake	Preservation	Willow Croft Dr	SR 2754	Cul-de-sac	0.29	1.0" S9.5B	$36,000
2029	5	092-Wake	Preservation	Winding Stream Dr	SR 5215	Dead End	0.14	1.0" S9.5B	$15,000
2029	5	092-Wake	Preservation	Woodoak Trl	SR 2728	Cul-de-sac	0.13	1.0" S9.5B	$15,000
2029	5	092-Wake	Preservation	Worthing Ct	SR 4509	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2029	5	093-Warren	Resurfacing	Doc Thompson	US 158	SR 1309	1.72	Full Depth Patching and 1.25" S9.5B	$367,000
2029	5	093-Warren	Resurfacing	Hummingbird Ln	SR 1395	Cul-de-sac	0.55	Full Depth Patching and 1.25" S9.5B	$107,000
2029	5	093-Warren	Resurfacing	Laurel Bluff Dr	SR 1395	Cul-de-sac	0.27	Full Depth Patching and 1.25" S9.5B	$53,000
2029	5	093-Warren	Resurfacing	Mill Creek Dr	NC 903	END MAINT	1.18	Full Depth Patching and 1.25" S9.5B	$229,000
2029	5	093-Warren	Resurfacing	Oine	SR 1231	SR 1213	1.35	Full Depth Patching and 1.5" S9.5B	$337,000
2029	5	093-Warren	Resurfacing	Oine	SR 1210	US 1	1.89	Full Depth Patching and 1.5" S9.5B	$494,000
2029	5	093-Warren	Resurfacing	Pine Bluff Rd	SR 1389	SR 1458	0.85	Full Depth Patching and 1.25" S9.5B	$165,000
2029	5	093-Warren	Resurfacing	Pine Cove Ln	Cul-de-sac	End Pavement	0.21	Full Depth Patching and 1.25" S9.5B	$43,000
2029	5	093-Warren	Resurfacing	SR 1735	SR 1306	SR 1741	0.84	Full Depth Patching and 1.5" S9.5B	$183,000
2029	5	093-Warren	Resurfacing	SR 1741	SR 1735	Cul-de-sac	0.70	Full Depth Patching and 1.5" S9.5B	$153,000
2029	5	093-Warren	Resurfacing	SR 1742	SR 1741	Cul-de-sac	0.05	Full Depth Patching and 1.5" S9.5B	$11,000
2029	5	093-Warren	Resurfacing	SR 1742	SR 1741	Cul-de-sac	0.10	Full Depth Patching and 1.5" S9.5B	$21,000
2029	5	093-Warren	Preservation	County Home Road	SR 1606	NC 58	1.48	1.0" S9.5B	$184,000
2029	5	093-Warren	Preservation	Davis Bugg Rd	NC 58	SR 1515	6.80	1.0" S9.5B	$759,000
2029	6	009-Bladen	Resurfacing	NC 41 / 87	NC 87	NC 87 Bus	1.77	Mill 1.5" and 1.5" S9.5C	$708,000
2029	6	009-Bladen	Resurfacing	NC 41 / 87	NC 87 Bus	NC 87	1.77	Mill 1.5" and 1.5" S9.5C	$708,000
2029	6	009-Bladen	Resurfacing	NC 41 / NC 87 Bus	WCL Elizabethtown	Harwood Street	0.79	Mill 1.5" and 1.5" S9.5C	$316,000
2029	6	009-Bladen	Resurfacing	NC 41 / NC 87 Bus	Joint	WCL Elizabethtown	1.60	Mill 1.5" and 1.5" S9.5C	$640,000
2029	6	009-Bladen	Resurfacing	NC 53	SR 1326	Cumberland Co.	7.03	Mill 1.5" and 1.5" S9.5C	$2,812,000
2029	6	009-Bladen	Preservation	SR 1001	NC 211	Columbus Co	1.85	Seal - Double	$65,000
2029	6	009-Bladen	Preservation	SR 1700	US 701 BUS	NC 87	9.15	Seal - Double	$320,250
2029	6	009-Bladen	Preservation	SR 1708	SR 1712	Columbus Co	8.36	Seal - Double	$260,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	6	009-Bladen	Preservation	SR 1710	NC 211	SR 1712	4.11	Seal - Double	$120,000
2029	6	009-Bladen	Preservation	SR 1712	NC 87	SR 1700	10.70	Seal - Double	$350,000
2029	6	009-Bladen	Preservation	SR 1713	SR 1712	NC 211	5.53	Seal - Double	$162,000
2029	6	009-Bladen	Preservation	SR 1721	SR 1712	End Pvmt	1.01	Seal - Double	$30,000
2029	6	009-Bladen	Preservation	SR 1723	SR 1712	End Pvmt	1.20	Seal - Double	$35,000
2029	6	009-Bladen	Preservation	SR 1750	NC 211	SR 1752	2.44	Seal - Double	$70,000
2029	6	009-Bladen	Preservation	SR 1751	SR 1750	End Pvmt	0.32	Seal - Double	$10,000
2029	6	009-Bladen	Preservation	SR 1752	NC 211	Columbus Co	2.16	Seal - Double	$62,000
2029	6	009-Bladen	Preservation	SR 1753	SR 1752	SR 1708	1.27	Seal - Double	$35,000
2029	6	009-Bladen	Preservation	SR 1755	NC 211	SR 1001	2.35	Seal - Double	$60,000
2029	6	009-Bladen	Preservation	SR 1756	SR 1755	Columbus Co	0.87	Seal - Double	$35,000
2029	6	009-Bladen	Preservation	SR 1757	NC 211	SR 1755	1.56	Seal - Double	$45,000
2029	6	009-Bladen	Preservation	SR 1758	SR 1001	Columbus Co	1.04	Seal - Double	$25,000
2029	6	009-Bladen	Preservation	SR 1759	SR 1001	NC 211	1.88	Seal - Double	$50,000
2029	6	009-Bladen	Preservation	SR 1760	US 701 Bus	SR 1708	6.87	Seal - Double	$205,000
2029	6	009-Bladen	Preservation	SR 1761	SR 1710	SR 1760	1.56	Seal - Double	$45,000
2029	6	009-Bladen	Preservation	SR 1763	NC 211	Dead End	1.00	Seal - Double	$30,000
2029	6	009-Bladen	Preservation	SR 1764	SR 1760	SR 1713	2.27	Seal - Double	$65,000
2029	6	009-Bladen	Preservation	SR 1765	SR 1713	CDS	1.14	Seal - Double	$30,000
2029	6	009-Bladen	Preservation	SR 1769	NC 211	End Pvmt	0.60	Seal - Double	$15,000
2029	6	009-Bladen	Preservation	SR 1773	SR 1713	Dead End	0.32	Seal - Double	$10,000
2029	6	009-Bladen	Preservation	SR 1775	NC 211	M.P.0.5	0.50	Seal - Double	$14,000
2029	6	009-Bladen	Preservation	SR 1778	SR 1760	0.69	0.69	Seal - Double	$20,000
2029	6	009-Bladen	Preservation	SR 1798	SR 1764	0.3	0.30	Seal - Double	$8,500
2029	6	024-Columbus	Resurfacing	SR 1004	NC 410	SR1005	1.30	1.5" S9.5B	$260,000
2029	6	024-Columbus	Resurfacing	SR 1005	US 701	US 74 Bus	9.92	1.5" S9.5B	$1,984,000
2029	6	024-Columbus	Resurfacing	SR 1967	SR 1901	Dead End	2.77	1.5" S9.5B	$554,000
2029	6	024-Columbus	Resurfacing	US 701	NC 410	SR 1198	12.31	1.5" S9.5C	$4,924,000
2029	6	026-Cumberland	Resurfacing	NC 162	SR 1141	SR 1132	3.02	Mill 1.5" and 1.5" S9.5B	$664,400
2029	6	026-Cumberland	Resurfacing	NC 162	SR 1132	SR 1141	3.02	Mill 1.5" and 1.5" S9.5B	$664,400
2029	6	026-Cumberland	Resurfacing	SR 1006	SR 2000	SR 2093	2.06	1.5" S9.5B	$339,900
2029	6	026-Cumberland	Resurfacing	SR 1400	SR 1007	SR 1404	1.23	Mill 1.5" and 1.5" S9.5B	$488,000
2029	6	026-Cumberland	Resurfacing	SR 1437	SR 1408	PLANTATION GARDEN	0.95	Mill 1.5" and 1.5" S9.5B	$522,500
2029	6	026-Cumberland	Resurfacing	SR 1437	NC 24	NC 210	1.89	1.5" S9.5B	$311,850
2029	6	026-Cumberland	Resurfacing	SR 1596	SR 1400	SR 1404	0.70	Mill 1.5" and 1.5" S9.5B	$154,000
2029	6	026-Cumberland	Resurfacing	SR 1596	SR 1404	SR 1400	0.71	Mill 1.5" and 1.5" S9.5B	$156,200
2029	6	026-Cumberland	Resurfacing	SR 1614	NC 210	SR 1615	0.99	1.5" S9.5B	$163,350
2029	6	026-Cumberland	Resurfacing	SR 1615	US 401	US 401	3.99	1.5" S9.5B	$658,350
2029	6	026-Cumberland	Resurfacing	SR 1615	BEG DIV HWY	US 401	0.31	1.5" S9.5B	$51,150
2029	6	026-Cumberland	Resurfacing	SR 2000	SR 1006	NC 53	3.95	1.5" S9.5B	$651,750
2029	6	026-Cumberland	Resurfacing	SR 2093	SR 1006	CUL-DE-SAC	0.25	1.5" S9.5B	$41,250
2029	6	026-Cumberland	Resurfacing	SR1400	US 401	SR 1403	4.60	Mill 1.5" and 1.5" S9.5B	$1,840,000
2029	6	026-Cumberland	Resurfacing	US 401	END CURB AND GUTTER	HARNETT CO	7.53	Mill 1.5" and 1.5" S9.5B	$1,656,600
2029	6	043-Harnett	Resurfacing	NC 24	LEE CO	BEG DIVIDED	8.44	Mill 1.5" and 1.5" S9.5B	$1,856,800
2029	6	043-Harnett	Resurfacing	SR 1006	WAKE CO	NC 55	4.17	1.5" S9.5B	$688,050
2029	6	043-Harnett	Resurfacing	SR 1128	NC 210	SR 1117	4.96	1.5" S9.5B	$818,235
2029	6	043-Harnett	Resurfacing	SR 1130	SR 1128	NC 27	3.24	1.5" S9.5B	$534,600
2029	6	043-Harnett	Resurfacing	SR 1291	SR 1274	US 421	8.71	1.5" S9.5B	$1,437,150
2029	6	043-Harnett	Resurfacing	SR 1502	WAKE CO	N BROAD ST	1.35	1.5" S9.5B	$222,750
2029	6	043-Harnett	Resurfacing	SR 2005	NC 27	NC 55	3.38	1.5" S9.5B	$557,205
2029	6	043-Harnett	Resurfacing	SR 2048	SR 2045	NC 210	3.45	1.5" S9.5B	$569,250
2029	6	043-Harnett	Preservation	SR 1120	SR 1121	NC210	3.27	Seal - Split	$115,000
2029	6	043-Harnett	Preservation	SR 2013	US 421	SR 1769	0.81	Seal - Double	$25,000
2029	6	043-Harnett	Preservation	SR 2021	US 401	NC 217	6.68	Seal - Double	$215,000
2029	6	043-Harnett	Preservation	SR 2026	SR 2042	US 401	3.06	Seal - Split	$90,000
2029	6	043-Harnett	Preservation	SR 2026	NC 217	US 401	3.58	Seal - Double	$105,000
2029	6	043-Harnett	Preservation	SR 2027	SR 2031	US 401	2.40	Seal - Split	$75,000
2029	6	043-Harnett	Preservation	SR 2030	US 401	SR 2045	5.77	Seal - Split	$170,000
2029	6	043-Harnett	Preservation	SR 2032	US 401	SR 2072	0.88	Seal - Split	$27,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	6	043-Harnett	Preservation	SR 2034	NC 210	US 401	2.81	Seal - Split	$90,000
2029	6	043-Harnett	Preservation	SR 2035	US 401	SR 2034	1.28	Seal - Split	$35,000
2029	6	043-Harnett	Preservation	SR 2036	SR 2030	SR 2072	3.54	Seal - Split	$100,000
2029	6	043-Harnett	Preservation	SR 2038	NC 210	SR 2036	1.32	Seal - Split	$40,000
2029	6	043-Harnett	Preservation	SR 2039	SR 2030	SR 2031	4.03	Seal - Split	$115,000
2029	6	043-Harnett	Preservation	SR 2040	SR 2030	Dead End	1.01	Seal - Split	$30,000
2029	6	043-Harnett	Preservation	SR 2041	SR 2030	End of Pavement	0.75	Seal - Split	$22,000
2029	6	043-Harnett	Preservation	SR 2042	SR 2030	SR 2045	3.38	Seal - Split	$100,000
2029	6	043-Harnett	Preservation	SR 2043	SR 2045	Dead End	1.01	Seal - Split	$30,000
2029	6	043-Harnett	Preservation	SR 2044	SR 2045	SR 2031	3.06	Seal - Split	$100,000
2029	6	043-Harnett	Preservation	SR 2045	NC 210	Cumberland County	6.62	Seal - Split	$225,000
2029	6	043-Harnett	Preservation	SR 2046	NC 210	SR 1120	1.10	Seal - Split	$30,000
2029	6	043-Harnett	Preservation	SR 2047	SR 2045	NC 210	2.24	Seal - Split	$65,000
2029	6	043-Harnett	Preservation	SR 2048	NC 210	SR 2045	3.45	Seal - Split	$90,000
2029	6	043-Harnett	Preservation	SR 2052	NC 210	Pvmt End	0.98	Seal - Split	$30,000
2029	6	043-Harnett	Preservation	SR 2067	NC 210	SR 2030	1.64	Seal - Split	$40,000
2029	6	043-Harnett	Preservation	SR 2072	NC 210	SR 2033	3.89	Seal - Split	$135,000
2029	6	043-Harnett	Preservation	SR 2083	SR 2031	Dead End	0.86	Seal - Split	$25,000
2029	6	043-Harnett	Preservation	SR 2085	SR 2023	Dead End	0.48	Seal - Split	$14,000
2029	6	043-Harnett	Preservation	SR 2337	SR 2067	SR 2036	0.58	Seal - Split	$17,000
2029	6	078-Robeson	Resurfacing	NC 211	SR 1505	NC 71	2.10	1.5" S9.5C	$420,000
2029	6	078-Robeson	Resurfacing	NC 83	SC LINE	US 501	5.00	1.5" S9.5B	$1,000,000
2029	6	078-Robeson	Resurfacing	SR 1002	SR 2104	NC 211	2.35	1.5" S9.5B	$423,000
2029	6	078-Robeson	Resurfacing	SR 1002	NC 41	SR 2104	1.42	1.5" S9.5B	$284,000
2029	6	078-Robeson	Resurfacing	SR 1106	Scotland County	NC 83	1.54	1.5" S9.5B	$277,000
2029	6	078-Robeson	Resurfacing	SR 1148	NC 710	SR1146	1.80	1.5" S9.5B	$324,000
2029	6	078-Robeson	Resurfacing	SR 1149	NC 710	SR 1148	0.47	1.5" S9.5B	$84,600
2029	6	078-Robeson	Resurfacing	SR 1153	SR 1166	US 74 Alt.	4.04	1.5" S9.5B	$720,000
2029	6	078-Robeson	Resurfacing	SR 1156	SR 1155	SR 1154	1.20	1.5" S9.5B	$216,000
2029	6	078-Robeson	Resurfacing	SR 1339	NC 711	NC 710	10.16	1.5" S9.5B	$1,828,800
2029	6	078-Robeson	Resurfacing	SR 1377	SR 1347	SR 1353	0.61	1.5" S9.5A	$109,000
2029	6	078-Robeson	Resurfacing	SR 1393	SR 1312	0.2 MILES S OF R/R	1.16	1.5" S9.5B	$473,242
2029	6	078-Robeson	Resurfacing	SR 1393	0.2 MILES S OF R/R	US 74 ALT	0.82	1.5" S9.5B	$326,600
2029	6	078-Robeson	Resurfacing	SR 1526	SR 1003	NC 72	2.83	1.5" S9.5B	$566,000
2029	6	078-Robeson	Resurfacing	SR 1556	SR 1339	NC 711	0.91	1.5" S9.5A	$162,000
2029	6	078-Robeson	Resurfacing	SR 1577	SR 1340	SR 1578	1.50	1.5" S9.5A	$180,000
2029	6	078-Robeson	Resurfacing	SR 1614	SR 1340	SR 1340 + 0.4 miles	0.40	1.5" S9.5B	$72,000
2029	6	078-Robeson	Resurfacing	SR 1673	SR 1563	SR 1003	2.27	1.5" S9.5A	$272,400
2029	6	078-Robeson	Resurfacing	SR 1758	US 301	SR 1828	1.53	1.5" S9.5B	$275,400
2029	6	078-Robeson	Resurfacing	SR 1766	SR 1752	SR 1531	0.79	1.5" S9.5B	$144,000
2029	6	078-Robeson	Resurfacing	SR 1777	SR 1780	SR 1505	2.36	1.5" S9.5B	$424,000
2029	6	078-Robeson	Resurfacing	SR 1812	SR 1774	SR 1594	0.16	1.5" S9.5A	$28,000
2029	6	078-Robeson	Resurfacing	SR 1916	SCL St. Paul's	SR 1006	0.87	1.5" S9.5B	$162,000
2029	6	078-Robeson	Resurfacing	SR 2012	SR 1948	SR 2013	0.18	1.0" S9.5B	$27,000
2029	6	078-Robeson	Resurfacing	SR 2013	SR 1945	SR 2031	0.13	1.0" S9.5B	$19,500
2029	6	078-Robeson	Resurfacing	SR 2031	SR 1948	SR 2013	0.17	1.0" S9.5B	$25,500
2029	6	078-Robeson	Resurfacing	SR 2130	SR 2112	SR 2110	0.51	1.5" S9.5B	$91,800
2029	6	078-Robeson	Resurfacing	SR 2147	NC 211	DEAD END	0.34	1.0" S9.5B	$51,000
2029	6	078-Robeson	Resurfacing	SR 2225	NC 130	SR 2262	6.69	1.5" S9.5B	$1,204,200
2029	6	078-Robeson	Resurfacing	SR 2233	NC 130	SR 2230	1.45	1.5" S9.5B	$261,000
2029	6	078-Robeson	Resurfacing	SR 2326	SR 2216	DEAD END	0.19	1.0" S9.5B	$28,500
2029	6	078-Robeson	Resurfacing	SR 2335	SR 2214	DEAD END	0.08	1.0" S9.5B	$12,000
2029	6	078-Robeson	Resurfacing	SR 2337	SR 2218	DEAD END	0.46	1.0" S9.5B	$69,000
2029	6	078-Robeson	Resurfacing	SR 2338	SR 2337	DEAD END	0.10	1.0" S9.5B	$15,000
2029	6	078-Robeson	Resurfacing	SR 2339	SR 2337	DEAD END	0.08	1.0" S9.5B	$12,000
2029	6	078-Robeson	Resurfacing	SR 2442	SR 2455	NC 130 Bus.	3.80	1.5" S9.5B	$760,000
2029	6	078-Robeson	Preservation	SR 1545	SR 2104	NC 41	0.48	Seal - Split	$15,000
2029	6	078-Robeson	Preservation	SR 1935	SR 1004	SR 1963	1.52	Seal - Split	$40,000
2029	6	078-Robeson	Preservation	SR 1960	SR 1004	NC 41	1.04	Seal - Split	$30,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	6	078-Robeson	Preservation	SR 1961	SR 1004	SR 1962	1.26	Seal - Split	$35,000
2029	6	078-Robeson	Preservation	SR 1962	NC 41	SR 1935	1.45	Seal - Split	$40,000
2029	6	078-Robeson	Preservation	SR 1963	NC 41	SR 1004	3.61	Seal - Split	$115,000
2029	6	078-Robeson	Preservation	SR 1966	SR 1963	NC 41	1.58	Seal - Split	$45,000
2029	6	078-Robeson	Preservation	SR 1967	SR 1966	SR 1966	2.24	Seal - Split	$65,000
2029	6	078-Robeson	Preservation	SR 1968	SR 1004	SR 1963	1.37	Seal - Split	$40,000
2029	6	078-Robeson	Preservation	SR 2027	NC 41	DEAD END	0.24	Seal - Split	$12,000
2029	6	078-Robeson	Preservation	SR 2100	NC 41	NC 211	5.30	Seal - Split	$185,000
2029	6	078-Robeson	Preservation	SR 2101	NC 41	SR 2100	2.49	Seal - Split	$66,000
2029	6	078-Robeson	Preservation	SR 2103	SR 2104	SR 2101	1.30	Seal - Split	$35,000
2029	6	078-Robeson	Preservation	SR 2104	SR 2100	NC 41	6.17	Seal - Split	$216,020
2029	6	078-Robeson	Preservation	SR 2105	SR 1002	NC 98249	0.60	Seal - Split	$17,000
2029	6	078-Robeson	Preservation	SR 2106	SR 1002	SR 2104	2.65	Seal - Split	$78,000
2029	6	078-Robeson	Preservation	SR 2107	SR 1002	SR 2106	1.29	Seal - Split	$35,000
2029	6	078-Robeson	Preservation	SR 2108	NC 211	SR 1002	1.47	Seal - Split	$43,000
2029	6	078-Robeson	Preservation	SR 2109	NC 41	SR 2104	1.25	Seal - Split	$37,000
2029	6	078-Robeson	Preservation	SR 2110	NC 41	NC 211	2.90	Seal - Split	$95,000
2029	6	078-Robeson	Preservation	SR 2111	SR 2104	SR 2110	0.98	Seal - Split	$30,000
2029	6	078-Robeson	Preservation	SR 2112	SR 2110	SR 2148	0.82	Seal - Split	$25,000
2029	6	078-Robeson	Preservation	SR 2113	SR 2110	SR 2104	0.91	Seal - Split	$25,000
2029	6	078-Robeson	Preservation	SR 2120	SR 2100	SR 211	1.14	Seal - Split	$40,000
2029	6	078-Robeson	Preservation	SR 2126	SR 2104	NC 41	1.14	Seal - Split	$40,000
2029	6	078-Robeson	Preservation	SR 2128	NC 211	SR 2126	0.79	Seal - Split	$23,000
2029	7	001-Alamance	Resurfacing	Bellemont-Mt. Herman Rd.	SR 2326	Bridge W-SAHS	2.54	#78 Mat Seal and 1.5" S9.5B	$1,587,433
2029	7	001-Alamance	Resurfacing	Brookvalley Ct.	SR 2279	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$18,600
2029	7	001-Alamance	Resurfacing	Drake Ct.	SR 2296	CUL-DE-SAC	0.02	#78 Mat Seal and 1.5" S9.5B	$5,300
2029	7	001-Alamance	Resurfacing	Duck Crossing Dr.	SR 2296	SR 2299	0.18	#78 Mat Seal and 1.5" S9.5B	$47,800
2029	7	001-Alamance	Resurfacing	Duckhead Ct.	SR 2296	CUL-DE-SAC	0.03	#78 Mat Seal and 1.5" S9.5B	$8,000
2029	7	001-Alamance	Resurfacing	Eider Ct.	SR 2296	CUL-DE-SAC	0.05	#78 Mat Seal and 1.5" S9.5B	$13,300
2029	7	001-Alamance	Resurfacing	Fox Hall Lane	SR 2279	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$18,600
2029	7	001-Alamance	Resurfacing	Mallard Creek Dr.	NC 87	CUL-DE-SAC	0.53	#78 Mat Seal and 1.5" S9.5B	$140,460
2029	7	001-Alamance	Resurfacing	NC 119	SR 2133	US 70	3.81	#67 Mat Seal and 1.5" S9.5B	$1,500,000
2029	7	001-Alamance	Resurfacing	NC 54	Non-System Johnson Ave.	NC 119	3.46	Mill 1.5" and 1.5" S9.5C	$1,300,000
2029	7	001-Alamance	Resurfacing	NC 62	SR 1001	CCL	10.50	#78 Mat Seal and 1.5" S9.5C	$2,777,430
2029	7	001-Alamance	Resurfacing	Old NC49 Location	NC 49	NC 62	0.11	#78 Mat Seal and 1.5" S9.5C	$47,015
2029	7	001-Alamance	Resurfacing	Royce Dr.	SR 2279	CUL-DE-SAC	0.13	#78 Mat Seal and 1.5" S9.5B	$34,550
2029	7	001-Alamance	Resurfacing	Timber Line Ct.	SR 2279	CUL-DE-SAC	0.35	#78 Mat Seal and 1.5" S9.5B	$92,760
2029	7	001-Alamance	Resurfacing	Webster Grove Dr.	SR 2133	CUL-DE-SAC	0.64	#78 Mat Seal and 1.5" S9.5B	$169,700
2029	7	001-Alamance	Resurfacing	Woodduck Dr.	SR 2296	CUL-DE-SAC	0.36	#78 Mat Seal and 1.5" S9.5B	$95,410
2029	7	001-Alamance	Preservation	Alberta St.	Holt St.	DEAD END	0.05	Seal - Double and Fog Seal	$2,405
2029	7	001-Alamance	Preservation	Anna Drive	SR 1936	SR 1940	0.35	Seal - Double and Fog Seal	$10,500
2029	7	001-Alamance	Preservation	Ball Park Lane	SR 1936	DEAD END	0.09	Seal - Double and Fog Seal	$4,810
2029	7	001-Alamance	Preservation	Broadwood Acres	SR 2186	DEAD END	0.21	Seal - Double and Fog Seal	$6,300
2029	7	001-Alamance	Preservation	Burgess Dr.	SR 2131	DEAD END	0.11	Seal - Double and Fog Seal	$3,390
2029	7	001-Alamance	Preservation	Calloway Dr.	SR 2131	SR 2135	1.73	Seal - Double and Fog Seal	$82,212
2029	7	001-Alamance	Preservation	Clifford Ray Rd.	NC 54	NC 119	0.50	Seal - Double and Fog Seal	$15,510
2029	7	001-Alamance	Preservation	Culberson Lane	SR 2138	DEAD END	0.52	Seal - Double and Fog Seal	$15,600
2029	7	001-Alamance	Preservation	Curry St.	SR 1963	DEAD END	0.16	Seal - Double and Fog Seal	$7,969
2029	7	001-Alamance	Preservation	Dodson Lane	SR 2142	DEAD END	0.36	Seal - Double and Fog Seal	$17,316
2029	7	001-Alamance	Preservation	Farrell Rd.	SR 2133	END AST	0.62	Seal - Double and Fog Seal	$29,822
2029	7	001-Alamance	Preservation	Freshwater Rd.	NC 54	SR 2135	1.08	Seal - Double and Fog Seal	$32,400
2029	7	001-Alamance	Preservation	Haywood St.	SR 1928	SR 2015	0.33	Seal - Double and Fog Seal	$9,900
2029	7	001-Alamance	Preservation	Holmes Lane	SR 2126	END MAINT.	0.68	Seal - Double and Fog Seal	$20,400
2029	7	001-Alamance	Preservation	Lake Latham Rd.	SR 1940	SR 1963	0.73	Seal - Split	$19,345
2029	7	001-Alamance	Preservation	Mackenzie Lane	NC 54	DEAD END	0.21	Seal - Double and Fog Seal	$10,101
2029	7	001-Alamance	Preservation	Mary's Grove Church Rd.	SR 2142	OCL	0.90	Seal - Double and Fog Seal	$24,539
2029	7	001-Alamance	Preservation	Mebane Oaks Ct.	SR 1007	END MAINT.	0.18	Seal - Double and Fog Seal	$5,400
2029	7	001-Alamance	Preservation	Moore Rd.	US 70	END MAINT	0.29	Seal - Double and Fog Seal	$7,685
2029	7	001-Alamance	Preservation	Moore Rd.	SR 1963	DEAD END	0.09	Seal - Double and Fog Seal	$4,810

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	7	001-Alamance	Preservation	Nelson Lane	SR 2106	END PVMT.	0.25	Seal - Double and Fog Seal	$7,500
2029	7	001-Alamance	Preservation	Thom Rd.	CUL-DE-SAC	OCL	3.05	Seal - Double and Fog Seal	$79,665
2029	7	001-Alamance	Preservation	Tyndall St.	SR 2014	SR 1928	0.39	Seal - Double and Fog Seal	$11,700
2029	7	001-Alamance	Preservation	Wagoner Lane	NC 54	DEAD END	0.53	Seal - Double and Fog Seal	$15,900
2029	7	001-Alamance	Preservation	White Lane	SR 2138	DEAD END	0.20	Seal - Double and Fog Seal	$6,000
2029	7	001-Alamance	Preservation	Woody Dr.	SR 2270	END PVMT	0.17	Seal - Double and Fog Seal	$11,050
2029	7	001-Alamance	Preservation	Worth Lane	SR 2154	CUL-DE-SAC	0.21	Seal - Double and Fog Seal	$6,300
2029	7	017-Caswell	Resurfacing	County Home Rd.	NC 86	SR 1521	3.70	#78 Mat Seal and 1.5" S9.5B	$980,600
2029	7	017-Caswell	Resurfacing	NC 86 (N)	US 158	VSL	0.02	Mill 1.5" and 1.5" S9.5B	$4,289
2029	7	017-Caswell	Resurfacing	NC 86 (N)	US 158	VSL	8.96	Mill 1.5" and 1.5" S9.5B	$2,402,475
2029	7	017-Caswell	Resurfacing	Rock Quarry Rd.	SR 1360	END MAINT	0.71	#67 Mat Seal and 1.5" S9.5B	$355,200
2029	7	017-Caswell	Preservation	Bill Smith Rd.	SR 1503	END MAINT	0.49	Seal - Double and Fog Seal	$21,144
2029	7	017-Caswell	Preservation	Carroll Rd.	SR 1503	END MAINT	1.00	Seal - Double and Fog Seal	$43,948
2029	7	017-Caswell	Preservation	Chaney Store Rd.	SR 1527	END MAINT	0.10	Seal - Double and Fog Seal	$7,091
2029	7	017-Caswell	Preservation	Corbett Ridge Rd.	NC 86	ACL	5.25	Seal - Cape	$400,000
2029	7	017-Caswell	Preservation	Culver Rd.	SR 1523	NC 62	3.70	Seal - Double and Fog Seal	$167,998
2029	7	017-Caswell	Preservation	Daniel Jeffries Rd.	SR 1500	END MAINT	0.46	Seal - Double and Fog Seal	$19,450
2029	7	017-Caswell	Preservation	Dix Rd.	SR 1527	END MAINT	1.50	Seal - Double and Fog Seal	$70,714
2029	7	017-Caswell	Preservation	Easy St.	SR 1503	END MAINT	0.30	Seal - Double and Fog Seal	$15,217
2029	7	017-Caswell	Preservation	Ed Rowland Rd.	SR 1523	END MAINT	0.60	Seal - Double and Fog Seal	$36,000
2029	7	017-Caswell	Preservation	Farmer Rd.	SR 1523	SR 1500	1.80	Seal - Double and Fog Seal	$54,000
2029	7	017-Caswell	Preservation	Gatewood Bus. Park Dr.	SR 1501	END MAINT	0.19	Seal - Double and Fog Seal	$10,029
2029	7	017-Caswell	Preservation	Hunt Rd.	SR 1527	END MAINT	0.20	Seal - Double and Fog Seal	$11,560
2029	7	017-Caswell	Preservation	Husk Rd.	SR 1511	END MAINT	0.48	Seal - Double and Fog Seal	$18,000
2029	7	017-Caswell	Preservation	Jeffries Rd. Ext.	SR 1631	END MAINT	0.23	Seal - Double and Fog Seal	$11,141
2029	7	017-Caswell	Preservation	Mt. Hill/Riverbend Rd.	NC 62	VSL	6.72	Seal - Double and Fog Seal	$328,907
2029	7	017-Caswell	Preservation	New Walter's Mill Rd.	SR 1503	SR 1503	1.59	Seal - Double and Fog Seal	$74,136
2029	7	017-Caswell	Preservation	Old Montgomery Rd.	NC 62	END MAINT	0.20	Seal - Double and Fog Seal	$9,355
2029	7	017-Caswell	Preservation	Old Satterfield Rd.	SR 1523	NC 62	1.70	Seal - Double and Fog Seal	$51,000
2029	7	017-Caswell	Preservation	Park Springs Rd.	SR 1500	US 158	11.87	Seal - Cape	$886,600
2029	7	017-Caswell	Preservation	Pinewood Rd.	SR 1503	END MAINT	0.30	Seal - Double and Fog Seal	$13,734
2029	7	017-Caswell	Preservation	Scott Rd.	SR 1503	END MAINT	0.80	Seal - Double and Fog Seal	$29,563
2029	7	017-Caswell	Preservation	Short St.	SR 1500	END MAINT	0.14	Seal - Double and Fog Seal	$7,336
2029	7	017-Caswell	Preservation	Slade Ct.	NC 86	END MAINT	0.10	Seal - Double and Fog Seal	$8,421
2029	7	017-Caswell	Preservation	Stephen Rd.	SR 1503	END MAINT	0.83	Seal - Double and Fog Seal	$32,669
2029	7	017-Caswell	Preservation	Talbott Rd.	SR 1523	END MAINT	1.40	Seal - Double and Fog Seal	$42,000
2029	7	041-Guilford	Resurfacing	ASA Lane	SR 1104	END MAINT	0.11	#78 Mat Seal and 1.5" S9.5B	$29,700
2029	7	041-Guilford	Resurfacing	Ashcroft Rd.	SR 1007	SR 3700	0.07	Mill 1.5" and 1.5" S9.5B	$18,900
2029	7	041-Guilford	Resurfacing	Bame Rd.	SR 1850	SR 1852	0.24	#78 Mat Seal and 1.5" S9.5A	$168,900
2029	7	041-Guilford	Resurfacing	Barn Owl Ct.	SR 3706	END MAINT	0.09	Mill 1.5" and 1.5" S9.5B	$22,500
2029	7	041-Guilford	Resurfacing	Bear Ridge Ct.	SR 3701	END MAINT	0.09	Mill 1.5" and 1.5" S9.5B	$24,900
2029	7	041-Guilford	Resurfacing	Bethel Church Rd.	Whitsett Ave.	Know Rd.	5.43	#78 Mat Seal and 1.5" S9.5B	$1,439,030
2029	7	041-Guilford	Resurfacing	Birkhaven Dr.	NC 150	SR 5079	0.67	#78 Mat Seal and 1.5" S9.5B	$178,100
2029	7	041-Guilford	Resurfacing	Blagdon Ct.	SR 5241	CUL-DE-SAC	0.09	#78 Mat Seal and 1.5" S9.5B	$23,852
2029	7	041-Guilford	Resurfacing	Boulder Rd.	SR 1552	END MAINT	0.22	#78 Mat Seal and 1.5" S9.5A	$168,600
2029	7	041-Guilford	Resurfacing	Braelands Dr.	SR 5081	END MAINT	0.49	#78 Mat Seal and 1.5" S9.5B	$131,200
2029	7	041-Guilford	Resurfacing	Briarcrest Dr.	SR 3421	SR 3505	0.17	#78 Mat Seal and 1.5" S9.5B	$45,500
2029	7	041-Guilford	Resurfacing	Briardenn Dr.	SR 5081	END MAINT	0.37	#78 Mat Seal and 1.5" S9.5B	$98,400
2029	7	041-Guilford	Resurfacing	Brushy Fork Dr.	END MAINT	END MAINT off SR 3701	0.26	Mill 1.5" and 1.5" S9.5B	$67,952
2029	7	041-Guilford	Resurfacing	Bunker Hill Rd. (North)	SR 1008	SR 1860	2.27	#78 Mat Seal and 1.5" S9.5B	$601,600
2029	7	041-Guilford	Resurfacing	Carmon Rd.	NC	SR 2814	5.43	#78 Mat Seal and 1.5" S9.5B	$1,439,030
2029	7	041-Guilford	Resurfacing	Cornerrock Dr.	SR 3265	CUL-DE-SAC	0.23	Mill 1.5" and 1.5" S9.5B	$60,805
2029	7	041-Guilford	Resurfacing	Dehaven Dr.	END MAINT	END MAINT	0.33	#78 Mat Seal and 1.5" S9.5B	$87,500
2029	7	041-Guilford	Resurfacing	Dicks Mill Rd.	SR 2770	SR 2819	1.21	#78 Mat Seal and 1.5" S9.5B	$321,000
2029	7	041-Guilford	Resurfacing	Dover Church Rd.	SR 4456	END MAINT	0.27	#78 Mat Seal and 1.5" S9.5B	$71,900
2029	7	041-Guilford	Resurfacing	Fallswood Ct.	SR 4456	END MAINT	0.16	#78 Mat Seal and 1.5" S9.5B	$41,100
2029	7	041-Guilford	Resurfacing	Fisher Hill Rd.	SR 1115	SR 1269	0.08	#78 Mat Seal and 1.5" S9.5B	$19,900
2029	7	041-Guilford	Resurfacing	Four Oaks Ct.	SR 2135	END MAINT	0.21	#78 Mat Seal and 1.5" S9.5B	$56,800
2029	7	041-Guilford	Resurfacing	Foxridge Rd.	SR 1007	SR 3706	0.31	Mill 1.5" and 1.5" S9.5B	$81,900

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	7	041-Guilford	Resurfacing	Freida Lane	SR 4009	SR 1268	0.19	#78 Mat Seal and 1.5" S9.5B	$50,900
2029	7	041-Guilford	Resurfacing	Greycrest Dr.	SR 1112	SR 3701	0.06	Mill 1.5" and 1.5" S9.5B	$16,000
2029	7	041-Guilford	Resurfacing	Hicone Rd.	Summit Ave.	Huffine Mill Rd.	6.28	#78 Mat Seal and 1.5" S9.5B	$1,664,818
2029	7	041-Guilford	Resurfacing	Horseshoe Dr.	SR 2135	END MAINT	0.32	#78 Mat Seal and 1.5" S9.5B	$83,500
2029	7	041-Guilford	Resurfacing	I-74 W	SR 1154	US 29/70	2.00	#78 Mat Seal and 1.5" S9.5B	$1,100,500
2029	7	041-Guilford	Resurfacing	I-74W	SR 1154	US 29/70	1.80	#78 Mat Seal and 1.5" S9.5B	$1,100,500
2029	7	041-Guilford	Resurfacing	Kivett Dr.	SR 1131	SR 1104	2.36	#78 Mat Seal and 1.5" S9.5B	$625,500
2029	7	041-Guilford	Resurfacing	Lancelot Dr.	SR 3426	END MAINT	0.36	#78 Mat Seal and 1.5" S9.5B	$95,550
2029	7	041-Guilford	Resurfacing	Lariat Dr.	SR 1002	END MAINT	0.52	#78 Mat Seal and 1.5" S9.5B	$138,100
2029	7	041-Guilford	Resurfacing	Meadowcroft Rd.	SR 3707	SR 3701	0.36	Mill 1.5" and 1.5" S9.5B	$95,200
2029	7	041-Guilford	Resurfacing	NC 150	SR 2619+ 0.16MI	SR 2730 + .05MI	2.00	#67 Mat Seal and 1.5" S9.5B	$398,751
2029	7	041-Guilford	Resurfacing	NC 150	4 Lane	SR 2730 + .05MI	0.88	#67 Mat Seal and 1.5" S9.5B	$235,910
2029	7	041-Guilford	Resurfacing	NC 150	4 Lane	4 Lane	0.12	#67 Mat Seal and 1.5" S9.5B	$32,200
2029	7	041-Guilford	Resurfacing	NC 62	SR 1006	SR 3332	2.85	#67 Mat Seal and 1.5" S9.5B	$1,394,126
2029	7	041-Guilford	Resurfacing	NC 65	FCL	SR 2053	3.27	#67 Mat Seal and 1.5" S9.5B	$880,100
2029	7	041-Guilford	Resurfacing	North Main St.	NC 68	SR 1003	1.48	#78 Mat Seal and 1.5" S9.5B	$800,000
2029	7	041-Guilford	Resurfacing	Oak Forest Ct.	SR 2135	END MAINT	0.26	#78 Mat Seal and 1.5" S9.5B	$52,585
2029	7	041-Guilford	Resurfacing	Oak Forest Dr.	SR 3812	END MAINT	0.06	#78 Mat Seal and 1.5" S9.5B	$87,200
2029	7	041-Guilford	Resurfacing	Pleasant Valley Rd.	SR 3706	END MAINT	0.42	Mill 1.5" and 1.5" S9.5B	$111,900
2029	7	041-Guilford	Resurfacing	Point Oak Dr. (E)	SR 2007	END MAINT	0.34	#78 Mat Seal and 1.5" S9.5B	$91,200
2029	7	041-Guilford	Resurfacing	Point Oak Dr. (W)	SR 2007	END MAINT	0.35	#78 Mat Seal and 1.5" S9.5B	$93,600
2029	7	041-Guilford	Resurfacing	Quail Cove Ct.	SR 3700	END MAINT	0.10	Mill 1.5" and 1.5" S9.5B	$25,700
2029	7	041-Guilford	Resurfacing	Rehobeth Church Rd.	SR 1467	SR 1104	2.19	#78 Mat Seal and 1.5" S9.5B	$579,400
2029	7	041-Guilford	Resurfacing	Ritters Lake Rd.	SR 1007	SR 3505	1.51	#78 Mat Seal and 1.5" S9.5B	$400,500
2029	7	041-Guilford	Resurfacing	Shadow Creek Dr.	END MAINT	END MAINT	0.39	#78 Mat Seal and 1.5" S9.5B	$103,700
2029	7	041-Guilford	Resurfacing	Shoeline Rd.	SR 2107	END MAINT	0.53	#78 Mat Seal and 1.5" S9.5B	$165,700
2029	7	041-Guilford	Resurfacing	Smith Ridge Ct.	SR 4657	END MAINT	0.16	#78 Mat Seal and 1.5" S9.5B	$42,700
2029	7	041-Guilford	Resurfacing	Summit Ave.	US 29	US 70	4.34	#78 Mat Seal and 1.5" S9.5B	$1,238,500
2029	7	041-Guilford	Resurfacing	Tyndale Ct.	SR 3701	END MAINT	0.06	Mill 1.5" and 1.5" S9.5B	$158,650
2029	7	041-Guilford	Resurfacing	US 158	US 220	RCL	1.20	#67 Mat Seal and 1.5" S9.5B	$318,100
2029	7	041-Guilford	Resurfacing	Vernondale Rd.	SR 1115	END MAINT	0.26	#78 Mat Seal and 1.5" S9.5B	$68,400
2029	7	041-Guilford	Resurfacing	Windcreek Ct.	Sr 1148	CUL-DE-SAC	0.01	#78 Mat Seal and 1.5" S9.5B	$26,300
2029	7	041-Guilford	Resurfacing	Windcrest Dr.	SR2135	END MAINT	0.31	#78 Mat Seal and 1.5" S9.5B	$83,500
2029	7	041-Guilford	Resurfacing	Windhaven Ct.	SR 1148	END MAINT	0.15	#78 Mat Seal and 1.5" S9.5B	$39,700
2029	7	041-Guilford	Preservation	Abb Rd.	SR 2717	SR 2705	1.40	Seal - Double and Fog Seal	$43,200
2029	7	041-Guilford	Preservation	Bame Rd.	SR 1852	END MAINT	0.40	Seal - Double and Fog Seal	$12,500
2029	7	041-Guilford	Preservation	Brann Rd.	SR 2705	RCL	1.29	Seal - Double and Fog Seal	$38,700
2029	7	041-Guilford	Preservation	Brooks Bridge Rd.	SR 2705	ACL	1.90	Seal - Double and Fog Seal	$57,900
2029	7	041-Guilford	Preservation	Busick Quarry Rd.	SR 2705	DEAD END	1.49	Seal - Double and Fog Seal	$44,700
2029	7	041-Guilford	Preservation	Chicory Lane	SR 2835	DEAD END	0.24	Seal - Double and Fog Seal	$7,200
2029	7	041-Guilford	Preservation	Crossmill Rd.	SR 2784	DEAD END	0.60	Seal - Double and Fog Seal	$18,000
2029	7	041-Guilford	Preservation	Crouse Rd.	SR 2000	END MAINT.	0.10	Seal - Double and Fog Seal	$21,060
2029	7	041-Guilford	Preservation	Deer Stand Ct.	SR 5328	CDS	0.07	Seal - Double and Fog Seal	$3,400
2029	7	041-Guilford	Preservation	Desmond Rd.	PVMT CHG	END MAINT	0.04	Seal - Double and Fog Seal	$3,000
2029	7	041-Guilford	Preservation	East Sandylea Rd.	NC 150	END MAINT	0.15	Seal - Double and Fog Seal	$6,000
2029	7	041-Guilford	Preservation	Everson Rd.	NC 150	END MAINT	0.22	Seal - Double and Fog Seal	$10,000
2029	7	041-Guilford	Preservation	Fairbluff Ct.	SR 2347	END MAINT	0.18	Seal - Double and Fog Seal	$7,000
2029	7	041-Guilford	Preservation	Flatrock Rd.	US1580	END MAINT	0.82	Seal - Double and Fog Seal	$30,377
2029	7	041-Guilford	Preservation	Highfill Rd.	SR 1002	END MAINT	0.63	Seal - Double and Fog Seal	$25,000
2029	7	041-Guilford	Preservation	Hollywood Dr.	SR 2835	SR 2866	0.10	Seal - Double and Fog Seal	$8,300
2029	7	041-Guilford	Preservation	Hopkins Rd.	SR 2514	END PVMT	1.02	Seal - Double and Fog Seal	$30,600
2029	7	041-Guilford	Preservation	Hudson-James Rd. (N)	US 158	RCL	0.15	Seal - Double and Fog Seal	$6,000
2029	7	041-Guilford	Preservation	Hudson-James Rd. (S)	US 158	END MAINT	1.13	Seal - Double and Fog Seal	$45,000
2029	7	041-Guilford	Preservation	Hunsucker Rd.	SR 2565	DEAD END	0.10	Seal - Double and Fog Seal	$5,100
2029	7	041-Guilford	Preservation	Ivy Lane	SR 2279	END MAINT	0.10	Seal - Double and Fog Seal	$5,000
2029	7	041-Guilford	Preservation	Jackson School Rd.	NC 150	SR 2733	1.99	Seal - Double and Fog Seal	$59,700
2029	7	041-Guilford	Preservation	Keller Dr.	US 158	RCL	0.10	Seal - Double and Fog Seal	$5,000
2029	7	041-Guilford	Preservation	Kerner Dr.	SR 2111	SR 2066	0.09	Seal - Double and Fog Seal	$5,000
2029	7	041-Guilford	Preservation	Kidd Dr.	SR 1008	END MAINT.	0.50	Seal - Double and Fog Seal	$57,915

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	7	041-Guilford	Preservation	Millbrook Rd.	SR 1002	END MAINT	0.50	Seal - Double and Fog Seal	$19,000
2029	7	041-Guilford	Preservation	Miller Dr.	DEAD END	DEAD END	0.39	Seal - Double and Fog Seal	$17,540
2029	7	041-Guilford	Preservation	Miller Dt.	DEAD END	DEAD END	0.39	Seal - Double and Fog Seal	$11,700
2029	7	041-Guilford	Preservation	Molly Rd.	SR 2717	SR 2715	0.45	Seal - Double and Fog Seal	$13,500
2029	7	041-Guilford	Preservation	Moritz Rd.	SR 2103	US 158	0.47	Seal - Double and Fog Seal	$18,000
2029	7	041-Guilford	Preservation	Murphy Rd.	US 220	US 158	0.78	Seal - Double and Fog Seal	$30,000
2029	7	041-Guilford	Preservation	Oldway Rd.	NC 150	SR 2819	0.40	Seal - Double and Fog Seal	$14,400
2029	7	041-Guilford	Preservation	Parnell Dr.	SR 2867	SR 2865	0.20	Seal - Double and Fog Seal	$6,900
2029	7	041-Guilford	Preservation	Pate Dr.	END MAINT	END MAINT-Off 2065	0.20	Seal - Double and Fog Seal	$7,500
2029	7	041-Guilford	Preservation	Patricia Dr.	US 158	SR 2239	0.30	Seal - Double and Fog Seal	$12,000
2029	7	041-Guilford	Preservation	Poley Rd.	NC 150	SR 2703	1.50	Seal - Double and Fog Seal	$47,400
2029	7	041-Guilford	Preservation	Pratt Rd.	SR 1008	FCL	0.52	Seal - Double and Fog Seal	$66,339
2029	7	041-Guilford	Preservation	Pritchett Rd.	SR 2705	RCL	1.74	Seal - Double and Fog Seal	$52,200
2029	7	041-Guilford	Preservation	Spotswood Rd.	US 220	US 158	0.50	Seal - Double and Fog Seal	$19,000
2029	7	041-Guilford	Preservation	Stone Quarry Rd.	SR 2790	DEAD END	0.30	Seal - Double and Fog Seal	$10,500
2029	7	041-Guilford	Preservation	Streamside Dr.	SR 2732	NC 93268	0.29	Seal - Double and Fog Seal	$13,100
2029	7	041-Guilford	Preservation	Taylorcrest Rd.	SR 2835	SR 2866	0.29	Seal - Double and Fog Seal	$8,700
2029	7	041-Guilford	Preservation	Tickle Rd.	NC 61	SR 2705	2.58	Seal - Double and Fog Seal	$77,400
2029	7	041-Guilford	Preservation	Triangle Dr.	SR 2868	SR 2867	0.17	Seal - Double and Fog Seal	$5,100
2029	7	041-Guilford	Preservation	Troxler Mill Rd.	SR 4732	ACL	1.19	Seal - Double and Fog Seal	$37,800
2029	7	041-Guilford	Preservation	Turner North Dr.	SR 2733	DEAD END	0.44	Seal - Double and Fog Seal	$19,500
2029	7	041-Guilford	Preservation	Vernon Owen Ct.	SR 2946	DEAD END	0.10	Seal - Double and Fog Seal	$4,600
2029	7	041-Guilford	Preservation	Waterfall Ln	SR 2719	DEAD END	0.20	Seal - Double and Fog Seal	$8,950
2029	7	041-Guilford	Preservation	Winfree Rd.	US 220	END MAINT	0.69	Seal - Double and Fog Seal	$26,000
2029	7	068-Orange	Resurfacing	Acorn Ridge Rd.	SR 1646	END MAINT	0.30	#78 Mat Seal and 1.25" S9.5A	$108,700
2029	7	068-Orange	Resurfacing	Adams Place	SR 1821	SR 1820	0.22	#78 Mat Seal and 1.25" S9.5A	$58,400
2029	7	068-Orange	Resurfacing	Alex Dr.	SR 1595	DEAD END	0.40	#78 Mat Seal and 1.25" S9.5A	$129,900
2029	7	068-Orange	Resurfacing	Big Oak Rd.	SR 1567	CUL-DE-SAC	0.23	#78 Mat Seal and 1.25" S9.5A	$60,960
2029	7	068-Orange	Resurfacing	Boulder Bluff Rd.	SR 2020	CUL-DE-SAC	0.40	#78 Mat Seal and 1.25" S9.5A	$106,100
2029	7	068-Orange	Resurfacing	Brookfiled Dr.	NC 54	SR 1944	0.27	#78 Mat Seal and 1.25" S9.5A	$71,600
2029	7	068-Orange	Resurfacing	Carolina Loop Rd.	SR 1002	CUL-DE-SAC	0.48	#78 Mat Seal and 1.25" S9.5A	$127,300
2029	7	068-Orange	Resurfacing	Cascade Dr.	SR 1718	SR 1874	0.72	#78 Mat Seal and 1.25" S9.5A	$190,900
2029	7	068-Orange	Resurfacing	Cedar Pointe Rd.	SR 1306	CUL-DE-SAC	0.15	#78 Mat Seal and 1.25" S9.5A	$39,750
2029	7	068-Orange	Resurfacing	Cedronella Dr.	SR 1873	SR 1875	0.36	#78 Mat Seal and 1.25" S9.5A	$95,500
2029	7	068-Orange	Resurfacing	Celastrus Ln.	SR 1875	SR 1876	0.16	#78 Mat Seal and 1.25" S9.5A	$42,500
2029	7	068-Orange	Resurfacing	Charlock Ct.	SR 1895	SR 1874	0.11	#78 Mat Seal and 1.25" S9.5A	$29,200
2029	7	068-Orange	Resurfacing	Country Lane	SR 1567	SR 1601	0.35	#78 Mat Seal and 1.25" S9.5A	$92,800
2029	7	068-Orange	Resurfacing	Crabapple Rd.	SR 1880	CUL-DE-SAC	0.06	#78 Mat Seal and 1.25" S9.5A	$15,900
2029	7	068-Orange	Resurfacing	Crabtree Creek Rd.	SR 1692	CUL-DE-SAC	0.13	#78 Mat Seal and 1.25" S9.5A	$34,500
2029	7	068-Orange	Resurfacing	Crescent Ridge Dr.	SR 1113	CUL-DE-SAC	0.42	#78 Mat Seal and 1.25" S9.5A	$111,400
2029	7	068-Orange	Resurfacing	Deer Haven Ct.	SR 1641	CUL-DE-SAC	0.17	#78 Mat Seal and 1.25" S9.5A	$45,100
2029	7	068-Orange	Resurfacing	Dickerson Mill Rd.	SR 1567	SR 1601	0.37	#78 Mat Seal and 1.25" S9.5A	$98,100
2029	7	068-Orange	Resurfacing	Eastgate Service Rd.	DEAD END	US 15	0.10	#78 Mat Seal and 1.25" S9.5A	$79,600
2029	7	068-Orange	Resurfacing	Elin Ct.	SR 1588	CUL-DE-SAC	0.10	#78 Mat Seal and 1.25" S9.5A	$26,600
2029	7	068-Orange	Resurfacing	End Woods Trail	SR 1686	CUL-DE-SAC	0.39	#78 Mat Seal and 1.25" S9.5A	$103,400
2029	7	068-Orange	Resurfacing	Falls Dr.	SR 1873	SR 1876	0.39	#78 Mat Seal and 1.25" S9.5A	$103,400
2029	7	068-Orange	Resurfacing	Farmgate Dr.	SR 1538	Foxhill Rd	0.10	#78 Mat Seal and 1.25" S9.5A	$29,200
2029	7	068-Orange	Resurfacing	Fews Ford Lane	SR 1685	CUL-DE-SAC	0.06	#78 Mat Seal and 1.25" S9.5A	$16,000
2029	7	068-Orange	Resurfacing	Forest Ridge Rd.	SR 1602	CUL-DE-SAC	0.10	#78 Mat Seal and 1.25" S9.5A	$26,600
2029	7	068-Orange	Resurfacing	Gentry Ln.	SR 1606	CUL-De-SAC	0.47	#78 Mat Seal and 1.25" S9.5A	$124,600
2029	7	068-Orange	Resurfacing	Grand Oaks Dr.	SR 1002	SR 1631	0.55	#78 Mat Seal and 1.25" S9.5A	$145,800
2029	7	068-Orange	Resurfacing	Habitat Rd.	SR 1247	CUL-DE-SAC	0.10	#78 Mat Seal and 1.5" S9.5B	$26,600
2029	7	068-Orange	Resurfacing	Harper Rd.	SR 1395	SR 1396	0.58	#78 Mat Seal and 1.25" S9.5A	$153,800
2029	7	068-Orange	Resurfacing	HAyes Dr.	SR 1831	SR 1831	0.20	#78 Mat Seal and 1.25" S9.5A	$53,100
2029	7	068-Orange	Resurfacing	Hemlock Dr.	SR 1710	DEAD END	0.14	#78 Mat Seal and 1.25" S9.5A	$37,200
2029	7	068-Orange	Resurfacing	Hemlock Dr.	SR 1845	DEAD END	0.07	#78 Mat Seal and 1.25" S9.5A	$18,600
2029	7	068-Orange	Resurfacing	Hepowil Trace	SR 1002	CUL-DE-SAC	0.59	#78 Mat Seal and 1.25" S9.5A	$156,400
2029	7	068-Orange	Resurfacing	Holiday Park Rd.	US 70	CUL-DE-SAC	0.25	#78 Mat Seal and 1.25" S9.5A	$66,300
2029	7	068-Orange	Resurfacing	Homewood Dr.	SR 1731	CUL-DE-SAC	0.13	#78 Mat Seal and 1.5" S9.5B	$34,600

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	7	068-Orange	Resurfacing	Jay Circle	SR 1831	SR 1831	0.24	#78 Mat Seal and 1.25" S9.5A	$63,700
2029	7	068-Orange	Resurfacing	Joshua Dr.	SR 1635	CUL-DE-SAC	0.17	#78 Mat Seal and 1.25" S9.5A	$45,100
2029	7	068-Orange	Resurfacing	Kennedy Circle	SR 1821	SR 1820	0.32	#78 Mat Seal and 1.25" S9.5A	$84,900
2029	7	068-Orange	Resurfacing	La Mesa Ln.	SR 1531	CUL-DE-SAC	0.49	#78 Mat Seal and 1.25" S9.5A	$129,900
2029	7	068-Orange	Resurfacing	Laurel Creek Way	SR 1685	CUL-DE-SAC	0.26	#78 Mat Seal and 1.25" S9.5A	$69,000
2029	7	068-Orange	Resurfacing	Lee Fox Lane	SR 2311	CUL-DE-SAC	0.10	#78 Mat Seal and 1.25" S9.5A	$39,800
2029	7	068-Orange	Resurfacing	Linden Ct.	SR 1433	CUL-DE-SAC	0.04	#78 Mat Seal and 1.5" S9.5B	$8,000
2029	7	068-Orange	Resurfacing	Little Leaf Lane	SR 1553	CUL-DE-SAC	0.20	#78 Mat Seal and 1.25" S9.5A	$60,960
2029	7	068-Orange	Resurfacing	Locust Rd.	SR 1395	SR 1397	0.30	#78 Mat Seal and 1.25" S9.5A	$79,600
2029	7	068-Orange	Resurfacing	Lystra Ln.	SR 1915	CUL-DE-SAC	0.20	#78 Mat Seal and 1.25" S9.5A	$60,960
2029	7	068-Orange	Resurfacing	Malvern Ln.	SR 1606	END PVMT	0.10	#78 Mat Seal and 1.25" S9.5A	$26,500
2029	7	068-Orange	Resurfacing	Manning Dr.	NC 86	US 15-501	1.25	#67 Mat Seal and 1.5" S9.5B	$331,270
2029	7	068-Orange	Resurfacing	Martin Ct.	SR 1432	CUL-DE-SAC	0.04	#78 Mat Seal and 1.5" S9.5B	$6,000
2029	7	068-Orange	Resurfacing	Meadow Rd.	SR 1602	DEAD END	0.03	#78 Mat Seal and 1.25" S9.5A	$8,000
2029	7	068-Orange	Resurfacing	Mimosa Dr.	SR 1731	CUL-DE-SAC	0.68	#78 Mat Seal and 1.25" S9.5A	$180,300
2029	7	068-Orange	Resurfacing	Moon Ridge Rd.	SR 1941	SR 1942	0.47	#78 Mat Seal and 1.25" S9.5A	$124,600
2029	7	068-Orange	Resurfacing	Mountain View Ct.	SR 1706	SR 1706	0.14	#78 Mat Seal and 1.25" S9.5A	$37,200
2029	7	068-Orange	Resurfacing	Mt. Herman Rd.	SR 1710	SR 1716	0.90	#78 Mat Seal and 1.25" S9.5A	$258,600
2029	7	068-Orange	Resurfacing	Oak Knob Ct.	SR 1595	CUL-DE-SAC	0.37	#78 Mat Seal and 1.25" S9.5A	$98,100
2029	7	068-Orange	Resurfacing	Oakview Ct.	SR 1574	CUL-DE-SAC	0.18	#78 Mat Seal and 1.25" S9.5A	$47,800
2029	7	068-Orange	Resurfacing	Old Forest Dr.	SR 2292	NEW PVMT.	0.15	#78 Mat Seal and 1.25" S9.5A	$108,700
2029	7	068-Orange	Resurfacing	Old Oak Place	DEAD END	DEAD END	0.20	#78 Mat Seal and 1.25" S9.5A	$66,300
2029	7	068-Orange	Resurfacing	Park Lane	SR 1706	SR 1706	0.19	#78 Mat Seal and 1.25" S9.5A	$50,400
2029	7	068-Orange	Resurfacing	Percussion Dr.	SR 1553	CUL-DE-SAC	0.34	#78 Mat Seal and 1.25" S9.5A	$90,200
2029	7	068-Orange	Resurfacing	Piney Grove Church Rd.	SR 1832	US 70A	0.35	#78 Mat Seal and 1.25" S9.5A	$92,800
2029	7	068-Orange	Resurfacing	Ponderosa Dr.	SR 1844	DEAD END	0.20	#78 Mat Seal and 1.25" S9.5A	$53,100
2029	7	068-Orange	Resurfacing	Prophet Dr.	SR 1595	CUL-DE-SAC	0.30	#78 Mat Seal and 1.25" S9.5A	$82,200
2029	7	068-Orange	Resurfacing	Running Pine Ct.	SR 2266	DEAD END	0.07	#78 Mat Seal and 1.25" S9.5A	$18,600
2029	7	068-Orange	Resurfacing	Sam Miller Dr.	SR 1458	CUL-DE-SAC	0.10	#78 Mat Seal and 1.25" S9.5A	$29,200
2029	7	068-Orange	Resurfacing	Settler Trace	SR 1692	CUL-DE-SAC	0.06	#78 Mat Seal and 1.25" S9.5A	$15,900
2029	7	068-Orange	Resurfacing	Seven Springs Rd.	US 70	END MAINT	0.44	#78 Mat Seal and 1.5" S9.5B	$116,700
2029	7	068-Orange	Resurfacing	Springview Trail	SR 1567	DEAD END	0.23	#78 Mat Seal and 1.25" S9.5A	$61,000
2029	7	068-Orange	Resurfacing	Spruce Pine Trail	SR 1710	SR 1845	0.42	#78 Mat Seal and 1.25" S9.5A	$111,400
2029	7	068-Orange	Resurfacing	Stillwater Lane	SR 1659	CUL-DE-SAC	0.09	#78 Mat Seal and 1.25" S9.5A	$23,900
2029	7	068-Orange	Resurfacing	Trading Path Rd.	SR 1685	CUL-DE-SAC	0.08	#78 Mat Seal and 1.25" S9.5A	$21,300
2029	7	068-Orange	Resurfacing	Tulip Tree	SR 1395	SR 1396	0.37	#78 Mat Seal and 1.25" S9.5A	$98,100
2029	7	068-Orange	Resurfacing	Valinda Dr.	SR 1875	CUL-DE-SAC	0.11	#78 Mat Seal and 1.25" S9.5A	$29,200
2029	7	068-Orange	Resurfacing	Victoria Dr.	SR 1588	CUL-DE-SAC	0.11	#78 Mat Seal and 1.25" S9.5A	$29,200
2029	7	068-Orange	Resurfacing	Washington Dr.	SR 1709	SR 1820	0.38	#78 Mat Seal and 1.25" S9.5A	$100,800
2029	7	068-Orange	Resurfacing	Whispering Pines	SR 1700	CUL-DE-SAC	0.05	#78 Mat Seal and 1.25" S9.5A	$13,300
2029	7	068-Orange	Resurfacing	Wild Harvest Ct.	SR 1685	CUL-DE-SAC	0.08	#78 Mat Seal and 1.25" S9.5A	$21,300
2029	7	068-Orange	Resurfacing	Wolfs Ct.	SR 2018	CUL-DE-SAC	0.17	#78 Mat Seal and 1.25" S9.5A	$45,100
2029	7	068-Orange	Resurfacing	Wyngate Dr.	SR 1709	SR 2268	0.33	#78 Mat Seal and 1.25" S9.5A	$84,900
2029	7	068-Orange	Resurfacing	Zapata Ln.	SR 1915	CUL-DE-SAC	0.20	#78 Mat Seal and 1.25" S9.5A	$60,960
2029	7	068-Orange	Preservation	Lystra Lane	Old Lystra Rd.	DEAD END	0.23	Seal - Double and Fog Seal	$10,272
2029	7	068-Orange	Preservation	Mangum Ct.	Mt. Caramel Rd.	DEAD END	0.60	Seal - Double and Fog Seal	$22,030
2029	7	068-Orange	Preservation	Walnut Grove Ch. Rd.	NC 86	PCL	7.56	Seal - Cape	$604,800
2029	7	079-Rockingham	Resurfacing	Bald Hill Loop	SR 2319	NC 704	3.01	#78 Mat Seal and 1.5" S9.5B	$797,700
2029	7	079-Rockingham	Resurfacing	Dogwood Rd.	SR 2145	CUL-DE-SAC	0.18	#78 Mat Seal and 1.5" S9.5B	$47,750
2029	7	079-Rockingham	Resurfacing	Fireman Club Rd.	SR 1581	SR 1570	0.20	#78 Mat Seal and 1.5" S9.5B	$53,100
2029	7	079-Rockingham	Resurfacing	Harrison St.	US 29 (Bus)	SR 2817	1.93	Mill 1.5" and 1.5" S9.5B	$510,330
2029	7	079-Rockingham	Resurfacing	Hash Lane	SR 2349	END MAINT	0.26	Mill 1.5" and 1.5" S9.5B	$68,900
2029	7	079-Rockingham	Resurfacing	Henry St.	US 220 BUS	NC 770	2.20	Mill 1.5" and #67 Mat Seal and 1.5" S9.5B	$497,108
2029	7	079-Rockingham	Resurfacing	Holiday Loop	SR 3103	NC 87	1.28	#78 Mat Seal and 1.25" S9.5A and Widen	$617,200
2029	7	079-Rockingham	Resurfacing	Knowles Rd.	SR 2571	SR 2579	1.66	#78 Mat Seal and 1.5" S9.5B	$273,000
2029	7	079-Rockingham	Resurfacing	Meadow Rd. (W)	SR 3004	US 311	0.96	Mill 1.5" and 1.5" S9.5B	$253,800
2029	7	079-Rockingham	Resurfacing	N.E. Market Rd.	SR 2552	SR 2545	1.35	#78 Mat Seal and 1.5" S9.5B	$357,800
2029	7	079-Rockingham	Resurfacing	Oak Level Ct.	SR 2399	CUL-DE-SAC	0.25	#78 Mat Seal and 1.5" S9.5B	$66,300
2029	7	079-Rockingham	Resurfacing	Smith Acres Rd.	SR 1569	SR 1565	0.33	#78 Mat Seal and 1.5" S9.5B	$87,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	7	079-Rockingham	Resurfacing	US 220 (N)	On-Ramp @ US220BUS	VSL	6.50	#67 Mat Seal and 2.0" S9.5C	$1,640,867
2029	7	079-Rockingham	Resurfacing	US 220 (S)	VSL	Off Ramp @ US 220(Bus.)	6.50	#67 Mat Seal and 2.0" S9.5C	$1,640,867
2029	7	079-Rockingham	Resurfacing	Witty Rd.	US 158	NC 65	2.50	#78 Mat Seal and 1.5" S9.5B	$662,600
2029	7	079-Rockingham	Preservation	Beeson Rd.	SR 1501	END PVMT	0.60	Seal - Double and Fog Seal	$26,700
2029	7	079-Rockingham	Preservation	Beeson Rd. (S)	SR1501	END MAINT	0.32	Seal - Double and Fog Seal	$14,240
2029	7	079-Rockingham	Preservation	Berry Hill Bridge Rd.	VSL	SR 1763	2.48	Seal - Double and Fog Seal	$110,360
2029	7	079-Rockingham	Preservation	Birch Rd.	SR 1753	DEAD END	0.07	Seal - Double and Fog Seal	$3,115
2029	7	079-Rockingham	Preservation	Birch Rd.	SR 1753	DEAD END	0.07	Seal - Double and Fog Seal	$3,132
2029	7	079-Rockingham	Preservation	Black Bottom Rd.	SR 1535	DEAD END	0.24	Seal - Double and Fog Seal	$10,680
2029	7	079-Rockingham	Preservation	Boxwood Rd.	SR 1700	DEAD END	0.18	Seal - Double and Fog Seal	$8,010
2029	7	079-Rockingham	Preservation	Buck Rd.	SR 1555	DEAD END	0.09	Seal - Double and Fog Seal	$4,005
2029	7	079-Rockingham	Preservation	Buffalo Rd.	NC 770	VSL	0.23	Seal - Double and Fog Seal	$10,235
2029	7	079-Rockingham	Preservation	Chumney Loop	NC 700	NC 700	2.40	Seal - Double and Fog Seal	$106,800
2029	7	079-Rockingham	Preservation	Clearview Rd.	SR 1533	DEAD END	0.19	Seal - Double and Fog Seal	$8,455
2029	7	079-Rockingham	Preservation	Cricket Rd.	SR 1535	END MAINT	0.09	Seal - Double and Fog Seal	$4,005
2029	7	079-Rockingham	Preservation	Crouch Rd.	SR 1719	DEAD END	0.26	Seal - Double and Fog Seal	$11,570
2029	7	079-Rockingham	Preservation	Denson Rd.	SR 1702	DEAD END	0.50	Seal - Double and Fog Seal	$26,700
2029	7	079-Rockingham	Preservation	Dodson Rd.	SR 1759	END MAINT	0.49	Seal - Double and Fog Seal	$21,805
2029	7	079-Rockingham	Preservation	Easley Rd.	SR 1557	SR 1553	1.15	Seal - Double and Fog Seal	$51,175
2029	7	079-Rockingham	Preservation	Eastern St.	SR 1737	SR 1740	0.22	Seal - Double and Fog Seal	$9,790
2029	7	079-Rockingham	Preservation	Garrett Road Ext.	SR 1501	END MAINT	0.05	Seal - Double and Fog Seal	$2,225
2029	7	079-Rockingham	Preservation	Ginny Rd.	SR 1535	DEAD END	0.50	Seal - Double and Fog Seal	$22,250
2029	7	079-Rockingham	Preservation	Goose Pond Rd.	SR 1759	NC 700	1.53	Seal - Double and Fog Seal	$67,863
2029	7	079-Rockingham	Preservation	Gravel Hill Rd.	SR 1761	VSL	3.69	Seal - Double and Fog Seal	$164,205
2029	7	079-Rockingham	Preservation	Happy Home School Rd.	NC 700	DEAD END	1.31	Seal - Double and Fog Seal	$58,430
2029	7	079-Rockingham	Preservation	Henderson Rd.	SR 1716	END MAINT	0.17	Seal - Double and Fog Seal	$7,565
2029	7	079-Rockingham	Preservation	Highland Dr.	SR 1716	END MAINT	0.20	Seal - Double and Fog Seal	$8,900
2029	7	079-Rockingham	Preservation	Holland Rd.	SR 1543	DEAD END	0.42	Seal - Double and Fog Seal	$18,690
2029	7	079-Rockingham	Preservation	Hundley Dr.	NC 770	DEAD END	0.15	Seal - Double and Fog Seal	$6,675
2029	7	079-Rockingham	Preservation	Jumper Rd	NC 700	DEAD END	0.09	Seal - Double and Fog Seal	$4,028
2029	7	079-Rockingham	Preservation	Jumper Rd.	NC 700	DEAD END	0.09	Seal - Double and Fog Seal	$4,051
2029	7	079-Rockingham	Preservation	Lakewood Rd.	BEG PVMT	SR 1535	0.30	Seal - Double and Fog Seal	$13,350
2029	7	079-Rockingham	Preservation	Lattimore Rd.	SR 1535	DEAD END	0.08	Seal - Double and Fog Seal	$3,560
2029	7	079-Rockingham	Preservation	Loop Loop	NC 700	NC 700	0.55	Seal - Double and Fog Seal	$24,386
2029	7	079-Rockingham	Preservation	McDaniel Rd.	SR 1535	DEAD END	0.60	Seal - Double and Fog Seal	$26,700
2029	7	079-Rockingham	Preservation	Old NC 87	NC 87	VSL	0.33	Seal - Double and Fog Seal	$14,685
2029	7	079-Rockingham	Preservation	Perkinson Rd.	NC 700	SR 1761	3.19	Seal - Double and Fog Seal	$141,955
2029	7	079-Rockingham	Preservation	Phillip St.	NC 770	END MAINT	0.20	Seal - Double and Fog Seal	$8,677
2029	7	079-Rockingham	Preservation	Piedmont St.	SR 1716	DEAD END	0.12	Seal - Double and Fog Seal	$5,340
2029	7	079-Rockingham	Preservation	Plantation Rd.	SR 1535	DEAD END	0.30	Seal - Double and Fog Seal	$13,350
2029	7	079-Rockingham	Preservation	Pryor Rd.	NC 700	DEAD END	0.45	Seal - Double and Fog Seal	$20,025
2029	7	079-Rockingham	Preservation	Redwood Rd.	SR 1702	DEAD END	0.15	Seal - Double and Fog Seal	$6,675
2029	7	079-Rockingham	Preservation	Rhodes Rd.	SR 1555	SR 1501	1.54	Seal - Double and Fog Seal	$68,530
2029	7	079-Rockingham	Preservation	Rose St.	SR 1738	END MAINT	0.21	Seal - Double and Fog Seal	$9,345
2029	7	079-Rockingham	Preservation	Schoolfield Rd.	NC 700	END MAINT	1.50	Seal - Double and Fog Seal	$66,840
2029	7	079-Rockingham	Preservation	Steeple Rd.	SR 1555	DEAD END	0.06	Seal - Double and Fog Seal	$2,670
2029	7	079-Rockingham	Preservation	Wiley Rd.	SR 1796	END MAINT	0.18	Seal - Double and Fog Seal	$8,010
2029	7	079-Rockingham	Preservation	Williamson Creek Rd.	NC 700	SR 1759	1.46	Seal - Double and Fog Seal	$64,970
2029	8	019-Chatham	Resurfacing	NC 902	NC 22	US 41	11.50	Mill 1.5" and 2.0" S9.5B	$2,300,000
2029	8	019-Chatham	Resurfacing	SR 1006	NC 902	MOORE CO	4.33	#67 Mat Seal and 1.5" S9.5B	$880,000
2029	8	019-Chatham	Resurfacing	SR 1006	SR 1119	NC 902	10.00	1.5" S9.5B	$1,800,000
2029	8	019-Chatham	Resurfacing	SR 1176	SR 2113	SR 1005	4.00	#67 Mat Seal and 1.5" S9.5B	$860,000
2029	8	019-Chatham	Resurfacing	SR 1176	NC 902	SR 2333	2.75	#67 Mat Seal and 1.5" S9.5B	$591,000
2029	8	019-Chatham	Resurfacing	SR 1176	SR 1005	NC 902	3.00	#67 Mat Seal and 1.5" S9.5B	$645,000
2029	8	019-Chatham	Resurfacing	SR 1506	NC 902	END PVMT	1.79	1.25" S9.5B	$303,000
2029	8	019-Chatham	Resurfacing	SR 1953	SR 2151	BRIDGE	1.28	1.25" S9.5B	$200,000
2029	8	019-Chatham	Resurfacing	SR 2118	SR 1176	US 421	0.92	1.25" S9.5B	$120,000
2029	8	019-Chatham	Resurfacing	SR 2152	SR 2151	SR 2217	0.59	1.25" S9.5B	$107,000
2029	8	019-Chatham	Resurfacing	SR 2165	US 64	SR 1506	3.19	1.25" S9.5B	$575,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	8	019-Chatham	Resurfacing	SR 2176	NC 902	SR 1010	3.27	1.25" S9.5B	$590,000
2029	8	019-Chatham	Resurfacing	SR 2178	NC 902	SR 1010	3.44	1.25" S9.5B	$620,000
2029	8	019-Chatham	Resurfacing	SR 2188	SR 2142	NC 902	2.31	1.25" S9.5B	$416,000
2029	8	019-Chatham	Resurfacing	US 1 SB	WAKE CO	LEE CO	6.63	Mill 2.0" and 2.0" S9.5D	$2,150,055
2029	8	019-Chatham	Preservation	SR 1100	SR 1005	SR 1129	2.31	Seal - Double	$120,000
2029	8	019-Chatham	Preservation	SR 1100	SR 1145	SR 1005	1.89	Seal - Double	$98,000
2029	8	019-Chatham	Preservation	SR 1100	SR 1129	SR 1125	1.47	Seal - Double	$76,000
2029	8	019-Chatham	Preservation	SR 1100	SR 1006	SR 1145	3.23	Seal - Double	$168,000
2029	8	019-Chatham	Preservation	SR 1139	NC 902	SR 1005	3.04	Seal - Double	$158,000
2029	8	019-Chatham	Preservation	SR 1142	SR 1176	SR 1139	0.84	Seal - Double	$44,000
2029	8	019-Chatham	Preservation	SR 2303	NC 42	MOORE CO	0.96	Seal - Double	$50,000
2029	8	019-Chatham	Preservation	SR 2303	SR 1009	NC 42	2.24	Seal - Double	$90,000
2029	8	019-Chatham	Preservation	SR 2305	SR 2303	SR 2306	3.52	Seal - Double	$183,000
2029	8	019-Chatham	Preservation	SR 2314	SR 2303	SR 1006	1.21	Seal - Double	$63,000
2029	8	047-Hoke	Resurfacing	NC211	NC20	PVT JT Project No. R5709	1.42	Mill 1.5" and 1.5" S9.5B	$264,960
2029	8	047-Hoke	Resurfacing	NC211	SR1149	US401 BUS	0.76	Mill 1.5" and 1.5" S9.5B	$214,160
2029	8	047-Hoke	Resurfacing	SR1105	SR1432	SR1003	2.06	1.5" S9.5B and Widen	$665,700
2029	8	047-Hoke	Resurfacing	SR1214	NC211	SR1211	3.10	1.5" S9.5B	$642,500
2029	8	047-Hoke	Resurfacing	SR1251	PVT JT Project No. R5709	US401	0.85	1.5" S9.5B	$180,960
2029	8	047-Hoke	Resurfacing	SR1406	SR1408	SR1754	1.03	1.5" S9.5B	$206,625
2029	8	047-Hoke	Resurfacing	US401 BUS	NC211	NC20	0.07	Mill 1.5" and 1.5" S9.5B	$53,960
2029	8	047-Hoke	Preservation	SR1100	SR1104	ROBESON CO	2.00	Seal - Double	$84,084
2029	8	047-Hoke	Preservation	SR1102	SR1104	SR1100	1.08	Seal - Double	$45,318
2029	8	047-Hoke	Preservation	SR1108	ROBESON CO	SR1113	2.78	Seal - Double	$116,718
2029	8	047-Hoke	Preservation	SR1443	ROBESON CO	NC20	2.74	Seal - Double	$132,000
2029	8	047-Hoke	Preservation	SR1445	ROBESON CO	SR1436	0.31	Seal - Double	$12,978
2029	8	047-Hoke	Preservation	SR1446	SR1436	SR1001	0.75	Seal - Double	$38,500
2029	8	047-Hoke	Preservation	SR1448	SR1105	SR1436	2.49	Seal - Double	$104,580
2029	8	053-Lee	Resurfacing	SR 1139	NC 87	DEAD END	0.25	Crack Seal and 1.25" S9.5A	$22,000
2029	8	053-Lee	Resurfacing	SR 1146	SR 1001	SR 1133	1.61	1.5" S9.5B	$210,000
2029	8	053-Lee	Resurfacing	SR 1146	BRIDGE	SR 1144	4.14	1.5" S9.5B	$705,565
2029	8	053-Lee	Resurfacing	SR 1157	SR 1293	US 1	1.86	1.5" S9.5B	$365,000
2029	8	053-Lee	Resurfacing	SR 1162	SR 1165	SR 1144	0.73	Full Depth Patching and 1.5" S9.5B	$93,000
2029	8	053-Lee	Resurfacing	SR 1178	SR 1144	SR 1144	0.16	Crack Seal and 1.5" S9.5B	$15,000
2029	8	053-Lee	Resurfacing	SR 1307	SR 1305	END MAINT.	0.61	1.5" S9.5B	$78,800
2029	8	053-Lee	Resurfacing	SR 1328	US 421	SR 1100	1.39	1.5" S9.5B	$241,000
2029	8	053-Lee	Resurfacing	SR 1400	PVMNT CHG	SR 1401	1.00	1.5" S9.5B	$157,500
2029	8	053-Lee	Resurfacing	SR 1405	PVMT CHG	SR 1406	0.65	1.5" S9.5B	$130,000
2029	8	053-Lee	Resurfacing	SR 1406	US 1 BUS	END MAINT	0.85	1.5" S9.5B	$112,000
2029	8	053-Lee	Resurfacing	SR 1423	SR 1466	DEAD END	0.58	Full Depth Patching and 1.5" S9.5B	$90,000
2029	8	053-Lee	Resurfacing	SR 1423	SR 1466	DEAD END	0.58	Full Depth Patching and 1.5" S9.5B	$120,000
2029	8	053-Lee	Resurfacing	SR 1466	US 1	CHATHAM CO	0.44	1.5" S9.5B	$82,000
2029	8	053-Lee	Resurfacing	SR 1500	BRIDGE	SR 1425	1.71	Crack Seal and 1.5" S9.5B	$365,000
2029	8	053-Lee	Resurfacing	SR 1510	BRIDGE	SR 1509	0.54	Full Depth Patching and 1.5" S9.5B	$87,500
2029	8	053-Lee	Resurfacing	SR 1521	Width Chg @ End C&G	Pvmt Chg @ CJ East US 421	1.10	1.5" S9.5B	$167,500
2029	8	053-Lee	Resurfacing	SR 1540	SR 1538	DEAD END	1.10	1.5" S9.5B	$162,700
2029	8	053-Lee	Resurfacing	SR 1547	SR 1538	SR 1546	1.28	1.5" S9.5B	$142,000
2029	8	053-Lee	Resurfacing	SR 1558	SR 1561	SR 1519	1.38	Crack Seal and 1.5" S9.5B	$260,000
2029	8	053-Lee	Resurfacing	US 1 N	SR 1415	SR 1423	5.67	Mill 1.5" and 1.5" S9.5B	$1,080,500
2029	8	053-Lee	Resurfacing	US 1 NB	C. J NORTH OF US 421 BUS	C. J NORTH OF US501N	5.48	1.5" S9.5C	$1,013,800
2029	8	053-Lee	Preservation	SR 1141	BGN PVMT	SR 1140	0.54	Crack Seal and Double Seal	$15,000
2029	8	053-Lee	Preservation	SR 1161	SR 1156	SR 1215 +.211	0.42	Crack Seal and Double Seal	$18,000
2029	8	053-Lee	Preservation	SR 1173	US 1	SR 1179	0.23	Crack Seal	$1,500
2029	8	053-Lee	Preservation	SR 1221	SR 1122	DEAD END	0.34	Crack Seal and Double Seal	$13,000
2029	8	053-Lee	Preservation	SR 1242	SR 1244	SR 1243	0.17	Seal - Double	$6,500
2029	8	053-Lee	Preservation	SR 1304	SR 1303	DEAD END	0.70	Crack Seal and Double Seal	$20,000
2029	8	053-Lee	Preservation	SR 1309	SR 1305	SR 1313	1.46	Seal - Double	$30,000
2029	8	053-Lee	Preservation	SR 1319	SR 1318	SR 1320	0.44	Seal - Double	$16,750
2029	8	053-Lee	Preservation	SR 1321	NC 42	NC 42	0.66	Seal - Double	$25,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	8	053-Lee	Preservation	SR 1384	US 421	CUL DE SAC	0.98	Seal - Double	$38,000
2029	8	053-Lee	Preservation	SR 1386	SR 1303	DEAD END	0.52	Seal - Double	$19,875
2029	8	053-Lee	Preservation	SR 1386	SR 1303	DEAD END	0.52	Seal - Double	$20,000
2029	8	053-Lee	Preservation	SR 1418	SR 1415	SR 1419	0.56	Seal - Double	$22,000
2029	8	053-Lee	Preservation	SR 1530	SR 1531	US 421	1.42	Seal - Double	$45,000
2029	8	053-Lee	Preservation	SR 1538	Moore Union Church	Sidney Ln (PVT)	5.56	Seal - Double	$167,800
2029	8	053-Lee	Preservation	SR 1591	SR 1590	SR 1592	0.14	Seal - Double	$5,475
2029	8	053-Lee	Preservation	SR 1596	NC 42	CUL DE SAC	0.57	Seal - Double	$20,000
2029	8	062-Montgomery	Resurfacing	NC 73	Richmond County	Moore County	1.52	1.5" S9.5B	$396,000
2029	8	062-Montgomery	Resurfacing	NC 731	SR 1625	US 220 ALT	4.04	1.5" S9.5B	$900,300
2029	8	062-Montgomery	Resurfacing	NC 731	SR 1541	SR 1563	3.11	Mill 1.5" and 1.5" S9.5B	$875,000
2029	8	062-Montgomery	Resurfacing	SR 1005	SR 1516	SR 1564	2.50	1.5" S9.5B	$455,088
2029	8	062-Montgomery	Resurfacing	SR 1524	SR 1003	SR 1626	2.00	1.5" S9.5B	$325,088
2029	8	062-Montgomery	Resurfacing	SR 1603	SR 1005	END OF PVT	0.24	1.5" S9.5B	$45,000
2029	8	062-Montgomery	Preservation	SR 1354	SR 1349	US 220A	3.52	Crack Seal	$47,000
2029	8	062-Montgomery	Preservation	SR 1523	SR 1522	SR 1003	0.83	Seal - Double	$33,245
2029	8	062-Montgomery	Preservation	SR 1530	Richmond County Line	SR 1531	0.60	Seal - Double	$24,000
2029	8	062-Montgomery	Preservation	SR 1531	Richmond County Line	Moore County Line	1.36	Seal - Double	$60,000
2029	8	062-Montgomery	Preservation	SR 1534	Richmond County Line	SR 1533	0.70	Seal - Double	$31,000
2029	8	062-Montgomery	Preservation	SR 1535	Richmond Co	SR 1536	1.64	Seal - Double	$72,000
2029	8	062-Montgomery	Preservation	SR 1536	SR 1535	NC 731	1.68	Seal - Double	$75,000
2029	8	062-Montgomery	Preservation	SR 1536	SR 1535	NC 731	1.68	Seal - Double	$74,000
2029	8	062-Montgomery	Preservation	SR 1537	SR 1536	End of Maint.	0.90	Seal - Double	$40,000
2029	8	062-Montgomery	Preservation	SR 1538	SR 1524	NS 99142	1.09	Seal - Double	$48,000
2029	8	063-Moore	Resurfacing	NC 22	SR 1638	CHATHAM CO LINE	4.63	Mill 1.5" and 1.5" S9.5B	$868,000
2029	8	063-Moore	Resurfacing	SR 1125	SR 1122	NC 73	0.22	1.5" S9.5B	$34,750
2029	8	063-Moore	Resurfacing	SR 1133	NC 211	SR 1302	0.12	1.5" S9.5A	$21,175
2029	8	063-Moore	Resurfacing	SR 1134	NC 211	SR 1233	0.30	1.5" S9.5B	$48,000
2029	8	063-Moore	Resurfacing	SR 1143	SR 1145	SR 1144	1.97	1.5" S9.5B	$292,000
2029	8	063-Moore	Resurfacing	SR 1158	SR 1150	DEAD END	0.31	1.0" S9.5A	$26,750
2029	8	063-Moore	Resurfacing	SR 1169	SR 1122	PVMT CHNG	0.08	1.25" SF9.5A	$11,000
2029	8	063-Moore	Resurfacing	SR 1210	NC 73	MP 5.10	5.10	1.5" S9.5B	$782,146
2029	8	063-Moore	Resurfacing	SR 1214	SR 1216	END MAINT.	0.10	1.5" S9.5B	$12,000
2029	8	063-Moore	Resurfacing	SR 1223	US 15	DEAD END	0.25	1.5" S9.5B	$45,000
2029	8	063-Moore	Resurfacing	SR 1240	SR 1248	SR 1229	0.62	1.5" S9.5B	$133,000
2029	8	063-Moore	Resurfacing	SR 1251	SR 1250	US 15	0.63	1.5" S9.5B	$92,000
2029	8	063-Moore	Resurfacing	SR 1270	SR 1271	NC 705	1.18	1.5" S9.5B	$190,000
2029	8	063-Moore	Resurfacing	SR 1281	SR 1002	CABIN CRK	1.19	1.5" S9.5B	$175,000
2029	8	063-Moore	Resurfacing	SR 1490	SR 1477	NC 24	1.81	1.5" S9.5B	$220,500
2029	8	063-Moore	Resurfacing	SR 1492	SR 1491	DEAD END	0.60	1.0" S9.5A	$27,000
2029	8	063-Moore	Resurfacing	SR 1621	SR 1006	BRIDGE	1.60	1.5" S9.5B	$328,000
2029	8	063-Moore	Resurfacing	SR 1658	SR 1659	BRIDGE	1.30	1.5" S9.5B	$222,500
2029	8	063-Moore	Resurfacing	SR 1833	SR 1802	SR 1805	2.77	1.5" S9.5B	$396,000
2029	8	063-Moore	Resurfacing	SR 1833	SR 1802	SR 1805	2.77	1.5" S9.5B	$396,000
2029	8	063-Moore	Resurfacing	SR 1843	MP 7.8	NC 2	1.38	1.5" S9.5C	$190,000
2029	8	063-Moore	Resurfacing	SR 1848	NC 22	NC 2	0.96	1.5" S9.5B	$137,000
2029	8	063-Moore	Resurfacing	SR 1864	SR 2175	DEAD END	1.85	1.5" S9.5B	$265,000
2029	8	063-Moore	Resurfacing	SR 2105	SR 2080	SR 2036	0.54	1.5" S9.5C	$75,000
2029	8	063-Moore	Resurfacing	SR 2126	SR 2110	SR 2110	0.38	1.0" S9.5A	$20,000
2029	8	063-Moore	Resurfacing	US 1	BRIDGE #56	SR 2124	1.09	Mill 1.5" and 1.5" S9.5B	$236,000
2029	8	063-Moore	Resurfacing	US 1	SR 2124	SR 2026	0.59	1.5" S9.5B	$84,370
2029	8	063-Moore	Resurfacing	US 1 BUS	SR 1826	SR 1821 + .37	3.80	Mill 1.5" and 1.5" S9.5B	$694,000
2029	8	063-Moore	Resurfacing	US 15	NC 24	SR 1656	1.50	Mill 1.5" and 1.5" S9.5B	$382,000
2029	8	063-Moore	Resurfacing	US 15	SR 1656	LEE CO	3.87	Mill 1.5" and 1.5" S9.5B	$930,035
2029	8	063-Moore	Preservation	SR 1101	SR 1100	END MAINT.	0.58	Seal - Double	$22,750
2029	8	063-Moore	Preservation	SR 1105	US 15	SR 1104	2.12	Seal - Double	$101,700
2029	8	063-Moore	Preservation	SR 1129	SR 1137	SR 1136	1.88	Seal - Double	$79,000
2029	8	063-Moore	Preservation	SR 1137	MP 2.79	SR 1126	4.23	Seal - Double	$219,856
2029	8	063-Moore	Preservation	SR 1137	SR 1129	MP 2.79	2.79	Seal - Double	$145,080

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	8	063-Moore	Preservation	SR 1140	SR 1126	SR 1141	1.23	Seal - Double	$46,000
2029	8	063-Moore	Preservation	SR 1145	MONTGOMERY CO	SR 1143	1.40	Seal - Double	$52,000
2029	8	063-Moore	Preservation	SR 1148	SR 1146	SR 1145	0.93	Seal - Double	$34,000
2029	8	063-Moore	Preservation	SR 1209	SR 1217	NC 73	1.26	Seal - Double	$44,500
2029	8	063-Moore	Preservation	SR 1216	SR 1209	SR 1210	1.13	Seal - Double	$52,000
2029	8	063-Moore	Preservation	SR 1222	NC 73	DEAD END	0.89	Seal - Double	$32,650
2029	8	063-Moore	Preservation	SR 1226	SR 1224	PVMT CHG	0.67	Seal - Double	$27,700
2029	8	063-Moore	Preservation	SR 1245	SR 1246	SR 1261	2.09	Seal - Double	$56,500
2029	8	063-Moore	Preservation	SR 1252	SR 1254	US 15	1.41	Seal - Double	$45,500
2029	8	063-Moore	Preservation	SR 1255	SR 1256	SR 1248	1.06	Seal - Double	$37,520
2029	8	063-Moore	Preservation	SR 1261	BRIDGE	NC 24	1.36	Seal - Double	$44,750
2029	8	063-Moore	Preservation	SR 1261	SR 1243	SR 1245	0.95	Seal - Double	$37,500
2029	8	063-Moore	Preservation	SR 1261	SR 1245	BRIDGE	0.82	Seal - Double	$32,000
2029	8	063-Moore	Preservation	SR 1280	NC 211	MONTGOMERY CO	1.08	Seal - Double	$44,750
2029	8	063-Moore	Preservation	SR 1285	US 15	US 15	1.25	Seal - Double	$52,500
2029	8	063-Moore	Preservation	SR 1453	SR 1454	NC 705	0.80	Seal - Double	$33,000
2029	8	063-Moore	Preservation	SR 1462	SR 1461	SR 1462	1.78	Seal - Double	$74,101
2029	8	063-Moore	Preservation	SR 1651	SR 1660	MP 5	2.63	Seal - Double	$82,300
2029	8	076-Randolph	Resurfacing	NC 705	Moore County Line	SR 1002 Fork Creek Mill Rd.	2.45	Full Depth Patching and 1.5" S9.5C	$465,000
2029	8	076-Randolph	Resurfacing	NC 705	SR 1002 Fork Creek Mill Rd.	US 220 ALT.	1.32	Full Depth Patching and 1.5" S9.5C	$251,000
2029	8	076-Randolph	Resurfacing	SR 1003	Moore County Line	US 64	16.72	Full Depth Patching and 1.5" S9.5B	$3,350,000
2029	8	076-Randolph	Resurfacing	SR 1004	NC 62	Bridge over I-73	18.60	Full Depth Patching and 1.5" S9.5B	$3,450,000
2029	8	076-Randolph	Resurfacing	SR 1143	SR 1107 Lassiter Mill Rd.	SR 1181 New Hope Rd.	3.98	Full Depth Patching and 1.5" S9.5B	$715,000
2029	8	076-Randolph	Resurfacing	SR 1841	SR 1840	CUL DE SAC	0.11	1.5" S9.5B	$10,000
2029	8	076-Randolph	Resurfacing	SR 1898	SR 1897	DEAD END	0.05	1.5" S9.5B	$4,000
2029	8	076-Randolph	Resurfacing	SR 1942	SR 1944	DEAD END	0.40	1.5" S9.5B	$35,000
2029	8	076-Randolph	Resurfacing	SR 1944	SR 1941	SR 1931 + .138 MILES	1.15	Mill 1.25" and 1.25" S9.5B	$275,000
2029	8	076-Randolph	Resurfacing	SR 1962	SR 1939	END MAINTENANCE	0.22	1.5" S9.5B	$19,000
2029	8	076-Randolph	Resurfacing	SR 2007	SR 2008	DEAD END	0.18	1.5" S9.5B	$14,000
2029	8	076-Randolph	Resurfacing	SR 2113	SR 2114	SR 2359 + .61 MILES	1.41	Full Depth Patching and 1.25" S9.5B	$250,000
2029	8	076-Randolph	Resurfacing	SR 2115	SR 2116	US 220 BUS	1.87	1.5" S9.5B	$325,000
2029	8	076-Randolph	Resurfacing	SR 2124	US 220 BUS	END MAINTENANCE	0.20	1.5" S9.5B	$14,000
2029	8	076-Randolph	Resurfacing	SR 2142	SR 2261	NC 22	1.84	1.5" S9.5B	$163,000
2029	8	076-Randolph	Resurfacing	SR 2142	SR 2261	NC 22	1.84	1.5" S9.5B	$275,000
2029	8	076-Randolph	Resurfacing	SR 2145	SR 2261	DEAD END	0.53	1.5" S9.5B	$47,000
2029	8	076-Randolph	Resurfacing	SR 2303	SR 2302	SR 2305	0.22	1.5" S9.5B	$17,000
2029	8	076-Randolph	Resurfacing	SR 2305	SR 2303	SR 2304	0.09	1.5" S9.5B	$7,000
2029	8	076-Randolph	Resurfacing	SR 2310	US 220 BUS	DEAD END	0.22	1.5" S9.5B	$18,000
2029	8	076-Randolph	Resurfacing	SR 2315	SR 2109	DEAD END	0.19	1.5" S9.5B	$15,000
2029	8	076-Randolph	Resurfacing	SR 2360	SR 2360 TAYLOR WOODS LN.	SR 2103 WHITT HUNT RD.	0.57	Full Depth Patching and 1.5" S9.5B	$100,000
2029	8	076-Randolph	Resurfacing	SR 2377	SR 2217	CUL DE SAC	0.31	Full Depth Patching and 1.5" S9.5B	$27,000
2029	8	076-Randolph	Resurfacing	SR 2380	SR 2379	DEAD END	0.31	1.5" S9.5B	$27,000
2029	8	076-Randolph	Resurfacing	SR 2438	NC 49	SR 2434	1.66	1.5" S9.5B	$240,000
2029	8	076-Randolph	Resurfacing	SR 2447	NC 22	NC 22	0.08	1.5" S9.5B	$9,000
2029	8	076-Randolph	Resurfacing	SR 2453	SR 2442	SR 2448	1.67	1.5" S9.5B	$245,000
2029	8	076-Randolph	Resurfacing	SR 2524	SR 2442	SR 2525	0.23	1.5" S9.5B	$30,000
2029	8	076-Randolph	Resurfacing	SR 2527	SR 2526	SR 2528	0.18	1.5" S9.5B	$25,000
2029	8	076-Randolph	Resurfacing	SR 2536	SR 2461	SR 2462	0.17	1.5" S9.5B	$14,000
2029	8	076-Randolph	Resurfacing	SR 2621	NC 22	SR 2626	1.75	1.5" S9.5B	$214,000
2029	8	076-Randolph	Resurfacing	SR 2686	DEAD END	DEAD END	0.33	1.5" S9.5B	$26,000
2029	8	076-Randolph	Resurfacing	SR 2687	SR 2689	SR 2686	0.15	1.5" S9.5B	$12,000
2029	8	076-Randolph	Resurfacing	SR 2688	SR 2689	SR 2686	0.15	1.5" S9.5B	$12,000
2029	8	076-Randolph	Resurfacing	SR 2689	DEAD END	DEAD END	0.29	1.5" S9.5B	$23,000
2029	8	076-Randolph	Resurfacing	SR 2710	SR 1003	SR 2709	0.35	1.5" S9.5B	$28,000
2029	8	076-Randolph	Resurfacing	SR 2711	SR 2610	SR 2695	0.29	1.5" S9.5B	$23,000
2029	8	076-Randolph	Resurfacing	SR 2719	SR 2696	SR 2697	0.09	1.5" S9.5B	$7,000
2029	8	076-Randolph	Resurfacing	SR 2725	SR 2713	SR 2680	0.08	1.5" S9.5B	$17,000
2029	8	076-Randolph	Resurfacing	SR 2835	PVMT CHG	NC 159	1.54	Full Depth Patching and 1.25" S9.5B	$285,000
2029	8	076-Randolph	Resurfacing	SR 2845	NC 42	SR 2909	1.82	1.5" S9.5B	$225,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	8	076-Randolph	Resurfacing	SR 2845	SR 2909	SR 2849	1.29	1.5" S9.5B	$170,000
2029	8	076-Randolph	Resurfacing	SR 2859	NC 705	MOORE COUNTY	1.44	Mill 1.25" and 1.25" S9.5B	$282,000
2029	8	076-Randolph	Resurfacing	SR 2884	SR 2885	SR 2885 + 1.041 MILES	1.04	Seal - Single and 1.5" S9.5B	$195,000
2029	8	076-Randolph	Resurfacing	SR 2884	MP 1.05	SR 2885	1.05	Seal - Single and 1.5" S9.5B	$115,000
2029	8	076-Randolph	Resurfacing	SR 3252	WIDTH CHANGE	SR 1556	0.71	1.5" S9.5B	$94,000
2029	8	076-Randolph	Resurfacing	US 220 BUS	E. Beasley St.	I-73 Bridge	11.76	Full Depth Patching and 1.5" S9.5C	$2,300,000
2029	8	076-Randolph	Resurfacing	US 29 Northbound	Davidson County Line	Guilford County Line	1.63	Full Depth Patching and 1.5" S9.5C	$340,000
2029	8	076-Randolph	Resurfacing	US 29 Southbound	Guilford County Line	Davidson County Line	1.61	Full Depth Patching and 1.5" S9.5C	$310,000
2029	8	076-Randolph	Resurfacing	Wall Bros Rd.	SR 1944 Branson Davis Rd.	Dirt Section	1.04	Full Depth Patching and 1.5" S9.5B	$192,000
2029	8	076-Randolph	Resurfacing	Wall Bros. Rd.	End Dirt Section	SR 1009 US Hwy 311	0.24	Full Depth Patching and 1.5" S9.5B	$44,000
2029	8	076-Randolph	Preservation	Center Cross Church Rd	NC-134	SR-1188 Old Troy Rd	1.76	Full Depth Patching and Double Seal	$115,000
2029	8	076-Randolph	Preservation	SR 1143	SR 1142 HOPEWELL FRIENDS RD.	SR 1181 NEW HOPE RD.	13.47	Full Depth Patching and Double Seal	$860,000
2029	8	076-Randolph	Preservation	SR 1145	SR 1202	SR 1144	0.16	Seal - Triple	$4,500
2029	8	076-Randolph	Preservation	SR 1400 HUGHES GROVE RD.	DAVIDSON COUNTY	SR 1401 KENNEDY FARM RD.	1.12	Seal - Double and Fog Seal	$35,000
2029	8	076-Randolph	Preservation	SR 1400 OLD POST OFFICE RD.	SR 1401 KENNEDY FARM RD.N	SR 1404 FULLER MILL RD N	0.94	Seal - Double and Fog Seal	$30,000
2029	8	076-Randolph	Preservation	SR 1402 LITTLE UWHARRIE RD	DAVIDSON COUNTY	SR 1401 KENNEDY FARM RD N.	0.94	Seal - Double and Fog Seal	$29,740
2029	8	076-Randolph	Preservation	SR 1406 COVERED BRIDGE RD.	SR 1405 TABERNACLE CHURCH RD.	SR 1408 HOOVER HILL RD.	2.32	Seal - Double and Fog Seal	$75,000
2029	8	076-Randolph	Preservation	SR 1407 HARRIS RD.	SR 1406 COVERED BRIDGE RD.	END OF MAINTENANCE	0.19	Seal - Double and Fog Seal	$6,000
2029	8	076-Randolph	Preservation	SR1115	SR-1109 Pisgah Rd	SR 134	0.90	Full Depth Patching and Double Seal	$57,000
2029	8	076-Randolph	Preservation	SR-1179	SR-1181 New Hope Rd	SR-1143 High Pine Church Rd	2.97	Full Depth Patching and Double Seal	$190,000
2029	8	076-Randolph	Preservation	SR-1183	DAVIDSON COUNTY LINE	SR-1181 New Hope Rd	2.91	Full Depth Patching and Double Seal	$188,000
2029	8	076-Randolph	Preservation	SR-1262	SR-1103 Volunteer Rescue Rd	SR-1183 Gravel Hill Rd	1.45	Full Depth Patching and Double Seal	$95,000
2029	8	076-Randolph	Preservation	SR-2409	SR-2504 Macedonia Loop Rd	SR-2407 Starmount Rd	2.09	Full Depth Patching and Double Seal	$135,000
2029	8	077-Richmond	Resurfacing	NC 38	SC line	US 74 bus	5.50	1.5" S9.5B	$1,150,000
2029	8	077-Richmond	Resurfacing	NC 73	US 220 bus	Mont Co	3.61	1.5" S9.5B	$620,000
2029	8	077-Richmond	Resurfacing	SR 1241	SR 1966	SR 1108	1.70	1.5" S9.5B	$238,000
2029	8	077-Richmond	Resurfacing	SR 1423	SR 1442	SR 1424	1.80	1.5" S9.5B	$238,000
2029	8	077-Richmond	Resurfacing	SR 1971	US 1	SR 1108	5.52	1.5" S9.5B	$993,000
2029	8	077-Richmond	Resurfacing	SR 1994	SR 1900	SR 1104	2.57	1.5" S9.5B	$400,000
2029	8	077-Richmond	Resurfacing	US 1	Begin divide	Pavt jt	0.30	Mill 1.5" and 1.5" S9.5B	$80,000
2029	8	077-Richmond	Resurfacing	US 1	Pavt jt	Begin divide	0.80	1.5" S9.5B	$145,000
2029	8	077-Richmond	Resurfacing	US 1	Begin island	End island	0.12	Mill 1.5" and 1.5" S9.5B	$30,000
2029	8	077-Richmond	Resurfacing	US 220 bus	NC 73 W	Mont Co	7.04	1.5" S9.5B	$1,200,000
2029	8	077-Richmond	Preservation	SR 1106	US 1	SR 1227	0.66	Seal - Double and Fog Seal	$22,000
2029	8	077-Richmond	Preservation	SR 1107	SR 1103	SR 1112	0.60	Seal - Double and Fog Seal	$20,000
2029	8	077-Richmond	Preservation	SR 1108	SR 1109	SR 1103	0.22	Seal - Double and Fog Seal	$8,000
2029	8	077-Richmond	Preservation	SR 1111	SR 1110	SR 1113	0.21	Seal - Double and Fog Seal	$6,000
2029	8	077-Richmond	Preservation	SR 1112	SR 1110	SR 1109	0.68	Seal - Double and Fog Seal	$19,000
2029	8	077-Richmond	Preservation	SR 1113	SR 1111	SR 1109	0.29	Seal - Double and Fog Seal	$11,000
2029	8	077-Richmond	Preservation	SR 1114	SR 1113	Dead end	0.21	Seal - Double and Fog Seal	$5,500
2029	8	077-Richmond	Preservation	SR 1115	SR 1110	SR 1112	0.15	Seal - Double and Fog Seal	$5,000
2029	8	077-Richmond	Preservation	SR 1116	SR 1109	SR 1110	0.08	Seal - Double and Fog Seal	$2,000
2029	8	077-Richmond	Preservation	SR 1163	SR 1162	SR 1148	1.30	Seal - Double	$40,000
2029	8	077-Richmond	Preservation	SR 1171	SR 1109	SR 1113	0.15	Seal - Double and Fog Seal	$4,000
2029	8	077-Richmond	Preservation	SR 1172	SR 1110	SR 1113	0.23	Seal - Double and Fog Seal	$6,000
2029	8	077-Richmond	Preservation	SR 1173	SR 1110	SR 1109	0.08	Seal - Double and Fog Seal	$2,000
2029	8	077-Richmond	Preservation	SR 1174	SR 1109	SR 1112	0.08	Seal - Double and Fog Seal	$2,000
2029	8	077-Richmond	Preservation	SR 1175	SR 1109	SR 1111	0.20	Seal - Double and Fog Seal	$5,500
2029	8	077-Richmond	Preservation	SR 1177	SR 1113	Dead End	0.06	Seal - Double and Fog Seal	$2,000
2029	8	077-Richmond	Preservation	SR 1178	SR 1103	SR 1179	0.29	Seal - Double and Fog Seal	$10,000
2029	8	077-Richmond	Preservation	SR 1179	SR 1108	SR 1183	0.27	Seal - Double and Fog Seal	$9,000
2029	8	077-Richmond	Preservation	SR 1183	SR 1103	SR 1179	0.30	Seal - Double and Fog Seal	$10,000
2029	8	077-Richmond	Preservation	SR 1184	US 74 bus	US 74 bus	0.60	Seal - Double	$18,000
2029	8	077-Richmond	Preservation	SR 1190	SR 1200	Dead end	0.36	Seal - Double and Fog Seal	$23,000
2029	8	077-Richmond	Preservation	SR 1191	SR 1189	Dead End	0.30	Seal - Double and Fog Seal	$15,000
2029	8	077-Richmond	Preservation	SR 1193	SR 1108	SR 1195	0.17	Seal - Double and Fog Seal	$6,000
2029	8	077-Richmond	Preservation	SR 1194	SR 1108	SR 1195	0.17	Seal - Double and Fog Seal	$6,000
2029	8	077-Richmond	Preservation	SR 1195	SR 1193	SR1194	0.13	Seal - Double and Fog Seal	$4,000
2029	8	077-Richmond	Preservation	SR 1196	SR 1193	SR 1194	0.13	Seal - Double and Fog Seal	$5,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	8	077-Richmond	Preservation	SR 1200	SR 1103	X-Cross	0.91	Seal - Double and Fog Seal	$44,000
2029	8	077-Richmond	Preservation	SR 1208	SR 1109	SR 1209	0.07	Seal - Double and Fog Seal	$2,500
2029	8	077-Richmond	Preservation	SR 1209	Dead End	End Pavt	0.30	Seal - Double and Fog Seal	$9,000
2029	8	077-Richmond	Preservation	SR 1216	CDS	Dead End	0.55	Seal - Double and Fog Seal	$35,000
2029	8	077-Richmond	Preservation	SR 1221	SR 1103	CDS	0.15	Seal - Double and Fog Seal	$5,000
2029	8	077-Richmond	Preservation	SR 1222	SR 1103	CDS	0.19	Seal - Double and Fog Seal	$6,500
2029	8	077-Richmond	Preservation	SR 1223	SR 1103	CDS	0.16	Seal - Double and Fog Seal	$5,500
2029	8	077-Richmond	Preservation	SR 1224	SR 1200	CDS	0.09	Seal - Double and Fog Seal	$4,200
2029	8	077-Richmond	Preservation	SR 1226	SR 1225	CDS	0.01	Seal - Double and Fog Seal	$500
2029	8	077-Richmond	Preservation	SR 1227	SR 1106	CDS	0.28	Seal - Double and Fog Seal	$9,000
2029	8	077-Richmond	Preservation	SR 1228	SR 1225	CDS	0.05	Seal - Double and Fog Seal	$1,800
2029	8	077-Richmond	Preservation	SR 1234	SR 1103	CDS	0.11	Seal - Double and Fog Seal	$4,000
2029	8	077-Richmond	Preservation	SR 1465	SR 1003	SR 1466	3.46	Seal - Double	$145,000
2029	8	077-Richmond	Preservation	SR 1900	NC 177	SR 1966	4.80	Seal - Double	$202,000
2029	8	077-Richmond	Preservation	SR 2012	SR 1108	Dead End	0.16	Seal - Double and Fog Seal	$5,500
2029	8	077-Richmond	Preservation	SR 2027	SR 2031	CDS	0.36	Seal - Double	$15,000
2029	8	077-Richmond	Preservation	SR1225	SR 1103	SR 1108	0.28	Seal - Double and Fog Seal	$9,000
2029	8	083-Scotland	Resurfacing	SR1407	SR1434	SR1435	2.52	1.5" S9.5B	$371,900
2029	8	083-Scotland	Resurfacing	SR1471	US15 BUS	SR1433	0.52	Mill 1.5" and 1.5" S9.5B	$109,740
2029	8	083-Scotland	Resurfacing	SR1642	US501 BUS	SR1643	1.09	Mill 1.5" and 1.5" S9.5B	$275,000
2029	8	083-Scotland	Resurfacing	US74	SR1601	Shoeheel Creek	0.80	Mill 1.5" and 1.5" S9.5C	$184,600
2029	8	083-Scotland	Resurfacing	US74	Shoeheel Creek	SR1601	0.86	Mill 1.5" and 1.5" S9.5C	$183,600
2029	8	083-Scotland	Preservation	SR1104	SR1100	SR1108	1.68	Crack Seal	$16,820
2029	8	083-Scotland	Preservation	SR1105	NC144	SR1300	2.09	Seal - Double	$96,738
2029	8	083-Scotland	Preservation	SR1105	US74 BUS	SR1117	2.29	Seal - Double	$96,138
2029	8	083-Scotland	Preservation	SR1120	SR1108	SR1128	1.28	Crack Seal	$12,800
2029	8	083-Scotland	Preservation	SR1157	SR1126	NC381	1.45	Crack Seal	$14,480
2029	8	083-Scotland	Preservation	SR1158	SR1162	SR1152	1.92	Crack Seal	$19,150
2029	8	083-Scotland	Preservation	SR1159	SC LINE	SR1158	1.08	Crack Seal	$10,810
2029	8	083-Scotland	Preservation	SR1160	SR1159	SC LINE	0.36	Crack Seal	$3,600
2029	8	083-Scotland	Preservation	SR1161	SR1158	DEAD END	0.76	Seal - Double	$31,836
2029	8	083-Scotland	Preservation	SR1162	SC LINE	NC381	1.66	Crack Seal	$16,590
2029	8	083-Scotland	Preservation	SR1163	RICHMOND CO	SR1162	0.51	Crack Seal	$5,130
2029	8	083-Scotland	Preservation	SR1254	SR1100	DEAD END	0.10	Seal - Double and Fog Seal	$4,850
2029	8	083-Scotland	Preservation	SR1255	SR1254	DEAD END	0.08	Seal - Double and Fog Seal	$3,900
2029	8	083-Scotland	Preservation	SR1256	SR1100	DEAD END	0.28	Seal - Double and Fog Seal	$14,150
2029	8	083-Scotland	Preservation	SR1257	SR1256	SR1261	0.09	Seal - Double and Fog Seal	$4,350
2029	8	083-Scotland	Preservation	SR1258	SR1256	SR1104	0.17	Seal - Double and Fog Seal	$8,300
2029	8	083-Scotland	Preservation	SR1259	SR1100	DEAD END	0.20	Seal - Double and Fog Seal	$10,150
2029	8	083-Scotland	Preservation	SR1263	SR1104	SR1282	0.51	Seal - Double and Fog Seal	$25,250
2029	8	083-Scotland	Preservation	SR1269	SR1108	SR1263	0.50	Seal - Double and Fog Seal	$25,100
2029	8	083-Scotland	Preservation	SR1270	SR1269	SR1263	0.29	Seal - Double and Fog Seal	$14,450
2029	8	083-Scotland	Preservation	SR1278	SR1269	DEAD END	0.20	Seal - Double and Fog Seal	$9,950
2029	8	083-Scotland	Preservation	SR1282	SR1104	SR1269	0.40	Seal - Double and Fog Seal	$20,200
2029	8	083-Scotland	Preservation	SR1305	NC144	US74	1.23	Seal - Double	$51,744
2029	8	083-Scotland	Preservation	SR1326	NC144	US15	1.59	Crack Seal	$15,870
2029	8	083-Scotland	Preservation	SR1331	BEG PAVT	SR1324	3.56	Seal - Double	$149,100
2029	9	029-Davidson	Resurfacing	NC 109	SR 1001	SR 2205	6.82	Mill 1.5" and 1.5" S9.5C	$2,700,720
2029	9	029-Davidson	Resurfacing	SR 1104	SR 1266	NC 47	2.73	#67 Mat Seal and 1.5" S9.5B	$800,800
2029	9	029-Davidson	Resurfacing	SR 1260	SR 1104	NC 8	0.65	#67 Mat Seal and 1.5" S9.5B	$190,667
2029	9	029-Davidson	Resurfacing	SR 1813	SR 1802	SR 1844	7.30	1.5" S9.5C	$1,541,760
2029	9	029-Davidson	Resurfacing	SR 1821	SR 1835	SR 1813	1.11	1.5" S9.5B	$196,064
2029	9	029-Davidson	Resurfacing	SR 1822	SR 1821	SR 3010	2.08	1.5" S9.5B	$463,701
2029	9	029-Davidson	Resurfacing	SR 1835	SR 1836	SR 1821	1.12	1.5" S9.5B	$226,723
2029	9	029-Davidson	Resurfacing	SR 2017	SR 2014	SR 2020	2.03	#67 Mat Seal and 1.5" S9.5B	$595,467
2029	9	029-Davidson	Resurfacing	SR 2062	SR 2091	SR 2055	1.89	1.5" S9.5B	$421,344
2029	9	029-Davidson	Resurfacing	SR 2091	RANDOLPH CO LINE	SR 2066	0.92	1.5" S9.5B	$269,867
2029	9	029-Davidson	Resurfacing	SR 2097	SR 2104	NC 109	1.97	Mill 1.5" and 1.5" S9.5B	$508,523
2029	9	029-Davidson	Resurfacing	SR 2183	END 4 LANE	NC 109	4.92	1.5" S9.5C	$1,108,378

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	9	029-Davidson	Resurfacing	SR 2205	NC 109	RANDOLPH CO	2.56	1.5" S9.5C	$540,883
2029	9	029-Davidson	Resurfacing	SR 2858	SR 2123	END	0.58	1.5" S9.5B	$129,970
2029	9	029-Davidson	Preservation	SR 1176	SR 1172	SR 1178	1.33	Seal - Double and Fog Seal	$99,874
2029	9	029-Davidson	Preservation	SR 1176	SR 1183	NC150	1.29	Seal - Double and Fog Seal	$108,979
2029	9	029-Davidson	Preservation	SR 1176	SR 1178	SR 1183	2.42	Seal - Double and Fog Seal	$204,442
2029	9	029-Davidson	Preservation	SR 1183	NC 150	SR 1176	1.10	Seal - Double and Fog Seal	$92,928
2029	9	029-Davidson	Preservation	SR 1190	SR 1196	EOM	1.03	Seal - Double and Fog Seal	$78,250
2029	9	029-Davidson	Preservation	SR 1191	NC 150	EOM	0.42	Seal - Double and Fog Seal	$32,032
2029	9	029-Davidson	Preservation	SR 1196	NC 150	SR 1192	0.58	Seal - Double and Fog Seal	$39,743
2029	9	029-Davidson	Preservation	SR 1197	SR 1196	SR 1192	0.17	Seal - Double and Fog Seal	$13,194
2029	9	029-Davidson	Preservation	SR 1198	SR 1192	NC 150	0.18	Seal - Double and Fog Seal	$13,499
2029	9	029-Davidson	Preservation	SR 1200	SR 1192	SR 1192	0.82	Seal - Double and Fog Seal	$62,157
2029	9	029-Davidson	Preservation	SR 1201	SR 1192	SR 1205	0.28	Seal - Double and Fog Seal	$21,660
2029	9	029-Davidson	Preservation	SR 1204	SR 1231	EOM	0.28	Seal - Double and Fog Seal	$19,425
2029	9	029-Davidson	Preservation	SR 1231	NC 150	US 64	2.55	Seal - Double and Fog Seal	$174,963
2029	9	029-Davidson	Preservation	SR 1231	US 64	CUL DE SAC	0.80	Seal - Double and Fog Seal	$67,584
2029	9	029-Davidson	Preservation	SR 1336	SR 1196	EOM	0.17	Seal - Double and Fog Seal	$12,584
2029	9	029-Davidson	Preservation	SR 1337	SR 1192	EOM	0.15	Seal - Double and Fog Seal	$11,440
2029	9	029-Davidson	Preservation	SR 1338	SR 1220	SR 1201	0.23	Seal - Double and Fog Seal	$17,465
2029	9	029-Davidson	Preservation	SR 1347	SR 1192	EOM	0.25	Seal - Double and Fog Seal	$19,067
2029	9	029-Davidson	Preservation	SR 1357	SR 1231	EOM	0.09	Seal - Double and Fog Seal	$5,834
2029	9	029-Davidson	Preservation	SR 1358	SR 1231	EOM	0.09	Seal - Double and Fog Seal	$6,452
2029	9	029-Davidson	Preservation	SR 1380	SR 1231	EOM	0.28	Seal - Double and Fog Seal	$19,425
2029	9	029-Davidson	Preservation	SR 1381	SR 1380	SR 1382	0.09	Seal - Double and Fog Seal	$5,972
2029	9	029-Davidson	Preservation	SR 1382	SR 1231	SR 1380	0.18	Seal - Double and Fog Seal	$12,149
2029	9	029-Davidson	Preservation	SR 2212	NC 8	SR 1243	2.65	Crack Seal	$17,101
2029	9	029-Davidson	Preservation	SR 3168	SR 1176	EOM	0.21	Seal - Double and Fog Seal	$17,741
2029	9	029-Davidson	Preservation	SR 3346	PVMT JOINT	CONC PVMT	3.80	Crack Seal	$24,523
2029	9	030-Davie	Resurfacing	NC 801	SR 1653	US 158	4.48	Mill 1.5" and 1.5" S9.5C	$1,578,368
2029	9	030-Davie	Resurfacing	SR 1306	US 64	SR 1317	4.14	Mill 1.5" and 1.5" S9.5B	$1,456,224
2029	9	030-Davie	Resurfacing	US 601	SR 1415	YADKIN CO	3.34	Mill 1.5" and 1.5" S9.5C	$1,174,976
2029	9	030-Davie	Resurfacing	US 601	SR 1408	SR 1415	4.43	Mill 1.5" and 1.5" S9.5C	$1,560,768
2029	9	030-Davie	Preservation	SR 1150	US 601	SR 1143	4.61	Seal - Double and Fog Seal	$432,725
2029	9	030-Davie	Preservation	SR 1313	SR 1320	US 64	3.06	Seal - Double and Fog Seal	$286,763
2029	9	030-Davie	Preservation	SR 1357	US 64	SR 1306	1.48	Seal - Double and Fog Seal	$139,204
2029	9	030-Davie	Preservation	SR 1410	YADKIN CO	US 158	6.70	Crack Seal	$38,914
2029	9	034-Forsyth	Resurfacing	SR 1171	US 421	SR 1166	1.34	1.5" S9.5B	$358,477
2029	9	034-Forsyth	Resurfacing	SR 1920	SR 4000	NC 8	2.87	1.5" S9.5B	$767,782
2029	9	034-Forsyth	Resurfacing	SR 2017	NC 150	GUILFORD CO	2.71	Mill 1.5" and 1.5" S9.5B	$774,400
2029	9	034-Forsyth	Resurfacing	SR 2211	Stokes Co Line	SR 2207	2.08	Mill 1.5" and 1.5" S9.5B	$2,143,680
2029	9	034-Forsyth	Resurfacing	SR 2632	SR 2643	SR 2667	3.28	Mill 1.5" and 1.5" S9.5C	$1,301,813
2029	9	034-Forsyth	Resurfacing	SR 2991	US 158	SR 2902	3.77	Mill 1.5" and 1.5" S9.5B	$1,327,040
2029	9	034-Forsyth	Resurfacing	SR 4000	US 52	SR 1920	0.86	Mill 1.5" and 1.5" S9.5C	$1,129,920
2029	9	034-Forsyth	Resurfacing	SR 4000	SR 1528	US 52	2.04	Mill 1.5" and 1.5" S9.5C	$1,119,360
2029	9	034-Forsyth	Resurfacing	SR 4000	US 52	SR 1528	2.05	Mill 1.5" and 1.5" S9.5C	$1,124,640
2029	9	034-Forsyth	Resurfacing	SR 4315	NC 66	NC 150	1.22	Mill 1.5" and 1.5" S9.5C	$644,160
2029	9	034-Forsyth	Preservation	NC 67	SR 1001	ROBINHOOD RD	1.44	Crack Seal	$20,275
2029	9	034-Forsyth	Preservation	SR 1178	SR 1001	EOM	0.10	Seal - Double and Fog Seal	$9,912
2029	9	034-Forsyth	Preservation	SR 1307	SR 1305	SR 1308	2.37	Crack Seal	$13,342
2029	9	034-Forsyth	Preservation	SR 1436	SR 1393	EOM	0.25	Seal - Double and Fog Seal	$19,219
2029	9	034-Forsyth	Preservation	SR 1437	SR 1525	SR 1348	1.51	Seal - Double and Fog Seal	$126,595
2029	9	034-Forsyth	Preservation	SR 1449	SR 1525	SR 1447	0.78	Seal - Triple and Fog Seal	$73,404
2029	9	034-Forsyth	Preservation	SR 1500	SR 1449	EOM	0.30	Seal - Double and Fog Seal	$28,254
2029	9	034-Forsyth	Preservation	SR 1522	SR 1435	SR 1434	0.30	Seal - Double and Fog Seal	$22,727
2029	9	034-Forsyth	Preservation	SR 1546	SR 1449	EOM	0.29	Seal - Double and Fog Seal	$27,034
2029	9	034-Forsyth	Preservation	SR 1547	SR 1546	EOM	0.07	Seal - Double and Fog Seal	$6,665
2029	9	034-Forsyth	Preservation	SR 1548	SR 1546	EOM	0.09	Seal - Double and Fog Seal	$8,448
2029	9	034-Forsyth	Preservation	SR 1565	SR 1393	EOM	0.32	Seal - Double and Fog Seal	$24,710
2029	9	034-Forsyth	Preservation	SR 1862	SR 1863	EOM	0.49	Seal - Double and Fog Seal	$45,995

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	9	034-Forsyth	Preservation	SR 1863	SR 1434	SR 1862	0.10	Seal - Double and Fog Seal	$9,199
2029	9	034-Forsyth	Preservation	SR 1864	SR 1862	EOM	0.05	Seal - Double and Fog Seal	$4,975
2029	9	034-Forsyth	Preservation	SR 1865	SR 1862	EOM	0.55	Seal - Double and Fog Seal	$51,345
2029	9	034-Forsyth	Preservation	SR 3224	SR 1449	EOM	0.22	Seal - Double and Fog Seal	$20,275
2029	9	034-Forsyth	Preservation	SR 3250	SR 1433	SR 3325	0.40	Seal - Double and Fog Seal	$37,359
2029	9	034-Forsyth	Preservation	SR 3251	SR 3250	EOM	0.06	Seal - Double and Fog Seal	$4,900
2029	9	034-Forsyth	Preservation	SR 3266	SR 1434	EOM	0.24	Seal - Double and Fog Seal	$18,151
2029	9	034-Forsyth	Preservation	SR 3295	SR 1525	EOM	0.64	Seal - Double and Fog Seal	$59,981
2029	9	034-Forsyth	Preservation	SR 3296	SR 3295	EOM	0.09	Seal - Double and Fog Seal	$8,730
2029	9	034-Forsyth	Preservation	SR 3297	SR 3295	EOM	0.13	Seal - Double and Fog Seal	$11,733
2029	9	034-Forsyth	Preservation	SR 3298	SR 3295	EOM	0.10	Seal - Double and Fog Seal	$9,668
2029	9	034-Forsyth	Preservation	SR 3313	SR 1449	EOM	0.22	Seal - Double and Fog Seal	$20,275
2029	9	034-Forsyth	Preservation	SR 3314	SR 3313	SR 3315	0.09	Seal - Double and Fog Seal	$8,166
2029	9	034-Forsyth	Preservation	SR 3315	SR 3314	SR 3316	0.14	Seal - Double and Fog Seal	$12,672
2029	9	034-Forsyth	Preservation	SR 3316	SR 3315	EOM	0.07	Seal - Double and Fog Seal	$6,477
2029	9	034-Forsyth	Preservation	SR 3325	SR 3326	EOM	0.34	Seal - Double and Fog Seal	$28,977
2029	9	034-Forsyth	Preservation	SR 3326	SR 3328	EOM	0.39	Seal - Double and Fog Seal	$32,609
2029	9	034-Forsyth	Preservation	SR 3327	SR 3326	EOM	0.09	Seal - Double and Fog Seal	$8,730
2029	9	034-Forsyth	Preservation	SR 3328	SR 1433	EOM	0.22	Seal - Double and Fog Seal	$20,463
2029	9	034-Forsyth	Preservation	SR 3329	SR 3328	EOM	0.16	Seal - Double and Fog Seal	$15,206
2029	9	034-Forsyth	Preservation	SR 3344	SR 1434	EOM	0.34	Seal - Double and Fog Seal	$25,778
2029	9	034-Forsyth	Preservation	SR 3356	SR 1433	EOM	0.17	Seal - Double and Fog Seal	$15,488
2029	9	034-Forsyth	Preservation	SR 3363	SR 3295	EOM	0.23	Seal - Double and Fog Seal	$21,496
2029	9	034-Forsyth	Preservation	SR 3367	SR 3363	EOM	0.14	Seal - Double and Fog Seal	$12,860
2029	9	034-Forsyth	Preservation	SR 3368	SR 3367	SR 3369	0.10	Seal - Double and Fog Seal	$9,190
2029	9	034-Forsyth	Preservation	SR 3369	SR 3368	EOM	0.08	Seal - Double and Fog Seal	$7,322
2029	9	034-Forsyth	Preservation	SR 3370	SR 1433	EOM	0.20	Seal - Double and Fog Seal	$15,253
2029	9	034-Forsyth	Preservation	SR 3378	SR 1434	EOM	0.15	Seal - Double and Fog Seal	$10,296
2029	9	034-Forsyth	Preservation	SR 4100	SR 1525	EOM	0.15	Seal - Double and Fog Seal	$12,500
2029	9	034-Forsyth	Preservation	SR 4101	SR 4100	EOM	0.05	Seal - Double and Fog Seal	$4,530
2029	9	034-Forsyth	Preservation	SR 4102	SR 4100	EOM	0.08	Seal - Double and Fog Seal	$6,879
2029	9	034-Forsyth	Preservation	SR 4104	SR 1434	EOM	0.18	Seal - Double and Fog Seal	$14,933
2029	9	034-Forsyth	Preservation	SR 4105	SR 4104	EOM	0.33	Seal - Double and Fog Seal	$27,936
2029	9	034-Forsyth	Preservation	SR 4107	SR 1865	EOM	0.14	Seal - Double and Fog Seal	$13,141
2029	9	034-Forsyth	Preservation	SR 4108	SR 1308	EOM	0.39	Seal - Double and Fog Seal	$29,820
2029	9	034-Forsyth	Preservation	SR 4109	SR 4108	EOM	0.12	Seal - Double and Fog Seal	$9,381
2029	9	034-Forsyth	Preservation	SR 4110	SR 4109	EOM	0.16	Seal - Double and Fog Seal	$11,821
2029	9	034-Forsyth	Preservation	SR 4111	SR 4108	EOM	0.05	Seal - Double and Fog Seal	$3,890
2029	9	034-Forsyth	Preservation	SR 4125	SR 1865	EOM	0.32	Seal - Double and Fog Seal	$29,756
2029	9	034-Forsyth	Preservation	SR 4126	SR 4127	SR 1433	0.10	Seal - Double and Fog Seal	$9,762
2029	9	034-Forsyth	Preservation	SR 4127	SR 3325	EOM	0.33	Seal - Double and Fog Seal	$30,694
2029	9	034-Forsyth	Preservation	SR 4128	SR 4127	EOM	0.14	Seal - Double and Fog Seal	$13,517
2029	9	034-Forsyth	Preservation	SR 4130	SR 4105	EOM	0.07	Seal - Double and Fog Seal	$6,208
2029	9	080-Rowan	Resurfacing	NC 152	SR 2333	US 52	0.45	Mill 1.5" and 1.5" S9.5B	$151,800
2029	9	080-Rowan	Resurfacing	NC 801	US 70	DAVIE CO	5.39	1.5" S9.5C	$1,011,883
2029	9	080-Rowan	Resurfacing	NC 801	US 70	DAVIE CO	0.99	1.5" S9.5C	$186,419
2029	9	080-Rowan	Resurfacing	SR 1500	SR 1503	US 29	1.81	1.5" S9.5C	$339,797
2029	9	080-Rowan	Resurfacing	SR 1526	NC 150	US 29	1.77	1.5" S9.5B	$399,051
2029	9	080-Rowan	Resurfacing	SR 1625	SR 1516	EOM	0.62	1.5" S9.5B	$152,041
2029	9	080-Rowan	Resurfacing	SR 1673	NC 152	EOM of SR 1673	0.52	Mill 1.5" and 1.5" S9.5B	$211,200
2029	9	080-Rowan	Resurfacing	SR 2333	NC 152	SR 2336	1.21	1.5" S9.5B	$241,972
2029	9	080-Rowan	Resurfacing	SR 2490	SR 1006	EOM	0.10	1.5" S9.5B	$27,768
2029	9	080-Rowan	Resurfacing	SR 2578	US 601	SR 2528	0.80	Mill 1.5" and 1.5" S9.5B	$281,600
2029	9	080-Rowan	Resurfacing	SR 2739	NC 153	NC152	3.10	Mill 1.5" and 1.5" S9.5B	$1,091,200
2029	9	080-Rowan	Resurfacing	SSR 2370	SR 1004	US 52	4.44	Mill 1.5" and 1.5" S9.5B	$1,302,400
2029	9	080-Rowan	Resurfacing	US 29	SR 1221	CABARRUS CO	2.79	Mill 1.5" and 1.5" S9.5C	$1,145,760
2029	9	080-Rowan	Resurfacing	US 29	SR 1221	Cabarrus Co Line	2.69	Mill 1.5" and 1.5" S9.5C	$2,367,200
2029	9	080-Rowan	Preservation	NC 150	BRG # 63	SR 1509	3.83	Crack Seal	$7,415
2029	9	080-Rowan	Preservation	SR 1383	SR 1124	SR 1391	0.43	Seal - Double and Fog Seal	$36,678

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	9	080-Rowan	Preservation	SR 1384	SR 1382	SR 1388	0.19	Seal - Double and Fog Seal	$17,841
2029	9	080-Rowan	Preservation	SR 1385	SR 1386	SR 1384	0.06	Seal - Double and Fog Seal	$6,010
2029	9	080-Rowan	Preservation	SR 1387	SR 1382	SR 1392	0.35	Seal - Double and Fog Seal	$26,067
2029	9	080-Rowan	Preservation	SR 1388	SR 1124	SR 1387	0.23	Seal - Double and Fog Seal	$17,428
2029	9	080-Rowan	Preservation	SR 1389	SR 1382	SR 1383	0.20	Seal - Double and Fog Seal	$18,876
2029	9	080-Rowan	Preservation	SR 1390	SR 1382	SR 1383	0.21	Seal - Double and Fog Seal	$17,663
2029	9	080-Rowan	Preservation	SR 1396	SR 1395	SR 1104	0.27	Seal - Double and Fog Seal	$22,480
2029	9	080-Rowan	Preservation	SR 1400	SR 1360	SR 1351	0.19	Seal - Double and Fog Seal	$16,395
2029	9	080-Rowan	Preservation	SR 1401	SR 1360	SR 1400	0.27	Seal - Double and Fog Seal	$25,260
2029	9	080-Rowan	Preservation	SR 1402	SR 1360	SR 2731	0.14	Seal - Double and Fog Seal	$11,916
2029	9	080-Rowan	Preservation	SR 1403	SR 1351	SR 1351	0.11	Seal - Double and Fog Seal	$19,719
2029	9	080-Rowan	Preservation	SR 1404	SR 2731	SR 1351	0.32	Seal - Double and Fog Seal	$26,621
2029	9	080-Rowan	Preservation	SR 1405	SR 2731	SR 1404	0.17	Seal - Double and Fog Seal	$14,029
2029	9	080-Rowan	Preservation	SR 1426	SR 1427	EOM	0.06	Seal - Double and Fog Seal	$5,634
2029	9	080-Rowan	Preservation	SR 1427	SR 1414	EOM	0.14	Seal - Double and Fog Seal	$13,428
2029	9	080-Rowan	Preservation	SR 1446	SR 1350	SR 1483	0.34	Seal - Double and Fog Seal	$31,833
2029	9	080-Rowan	Preservation	SR 1447	EOM	EOM	0.14	Seal - Double and Fog Seal	$12,170
2029	9	080-Rowan	Preservation	SR 1448	SR 1447	EOM	0.05	Seal - Double and Fog Seal	$4,507
2029	9	080-Rowan	Preservation	SR 1452	SR 1383	EOM	0.14	Seal - Double and Fog Seal	$11,578
2029	9	080-Rowan	Preservation	SR 1462	SR 1446	EOM	0.26	Seal - Double and Fog Seal	$23,945
2029	9	080-Rowan	Preservation	SR 1474	SR 1362	EOM	0.16	Seal - Double and Fog Seal	$14,649
2029	9	080-Rowan	Preservation	SR 1483	EOM	EOM	0.07	Seal - Double and Fog Seal	$6,855
2029	9	080-Rowan	Preservation	SR 1489	SR 1197	EOM	0.16	Seal - Double and Fog Seal	$14,930
2029	9	080-Rowan	Preservation	SR 1490	SR 1489	SR 2755	0.22	Seal - Double and Fog Seal	$21,034
2029	9	080-Rowan	Preservation	SR 1931	US 29	US 29	0.23	Seal - Double and Fog Seal	$17,578
2029	9	080-Rowan	Preservation	SR 1932	US 29	SR 1936	0.32	Seal - Double and Fog Seal	$27,044
2029	9	080-Rowan	Preservation	SR 1933	US 29	SR 1934	0.10	Seal - Double and Fog Seal	$8,451
2029	9	080-Rowan	Preservation	SR 1934	SR 1935	EOM	0.10	Seal - Double and Fog Seal	$8,113
2029	9	080-Rowan	Preservation	SR 1935	SR 1936	SR 1933	0.07	Seal - Double and Fog Seal	$5,183
2029	9	080-Rowan	Preservation	SR 1936	SR 1937	EOM	0.20	Seal - Double and Fog Seal	$29,598
2029	9	080-Rowan	Preservation	SR 1937	US 29	EOM	0.16	Seal - Double and Fog Seal	$18,367
2029	9	080-Rowan	Preservation	SR 2157	SR 1002	SR 2158	0.84	Seal - Double and Fog Seal	$63,253
2029	9	080-Rowan	Preservation	SR 2158	EOM	EOM	1.08	Seal - Double and Fog Seal	$80,981
2029	9	080-Rowan	Preservation	SR 2159	SR 2158	EOM	0.82	Seal - Double and Fog Seal	$69,638
2029	9	080-Rowan	Preservation	SR 2276	SR 1104	EOM	0.51	Seal - Double and Fog Seal	$48,172
2029	9	080-Rowan	Preservation	SR 2705	SR 1104	SR 1104	0.29	Seal - Double and Fog Seal	$27,232
2029	9	080-Rowan	Preservation	SR 2714	SR 1350	SR 1350	0.32	Seal - Double and Fog Seal	$29,673
2029	9	080-Rowan	Preservation	SR 2730	SR 1402	SR 2731	0.13	Seal - Double and Fog Seal	$11,325
2029	9	080-Rowan	Preservation	SR 2731	SR 1351	SR 2730	0.17	Seal - Double and Fog Seal	$16,245
2029	9	080-Rowan	Preservation	SR 2755	SR 1197	EOM	0.15	Seal - Double and Fog Seal	$13,710
2029	9	080-Rowan	Preservation	SR 2766	SR 2765	EOM	0.11	Seal - Double and Fog Seal	$10,048
2029	9	080-Rowan	Preservation	SR 2777	Archer Rd	EOM	0.81	Seal - Double and Fog Seal	$76,436
2029	9	080-Rowan	Preservation	SR 2778	SR 2777	EOM	0.07	Seal - Double and Fog Seal	$5,493
2029	9	080-Rowan	Preservation	SR 2780	SR 2777	EOM	0.07	Seal - Double and Fog Seal	$5,916
2029	9	080-Rowan	Preservation	US 29	S Spencer CL	SR 2120	2.05	Crack Seal	$9,020
2029	9	080-Rowan	Preservation	US 70	BRG# 71	SR 1847	4.04	Crack Seal	$10,666
2029	9	080-Rowan	Preservation	US 70	SR 1847	BRG# 416	4.07	Crack Seal	$10,745
2029	9	085-Stokes	Resurfacing	NC 89	NC 8	NC 66	13.82	1.5" S9.5B	$3,234,986
2029	9	085-Stokes	Resurfacing	SR 1711	NC 89	SR 1707	1.61	1.5" S9.5B	$358,031
2029	9	085-Stokes	Resurfacing	SR 1921	NC 65	SR 1299	2.06	1.5" S9.5B	$551,091
2029	9	085-Stokes	Resurfacing	US 311	FORSTYH COUNTY	SR 2065	4.96	Mill 1.5" and 1.5" S9.5B	$1,964,160
2029	9	085-Stokes	Preservation	NC 66	NC 268	NC 89	6.32	Seal - Double and Fog Seal	$563,219
2029	9	085-Stokes	Preservation	NC 8	SR 1945	NC 89	4.60	Crack Seal	$33,763
2029	9	085-Stokes	Preservation	NC 8	SR 1961	SR 1945	1.86	Crack Seal	$12,549
2029	9	085-Stokes	Preservation	SR 1237	SR 1144	EOM	0.31	Seal - Double and Fog Seal	$26,020
2029	9	085-Stokes	Preservation	SR 1347	NC 268	EOM	0.26	Seal - Double and Fog Seal	$21,711
2029	9	085-Stokes	Preservation	SR 1989	NC 8	EOM	0.70	Seal - Double and Fog Seal	$65,331
2029	9	085-Stokes	Preservation	SR 1990	SR 2019	NC 8	2.00	Seal - Double and Fog Seal	$187,546
2029	9	085-Stokes	Preservation	SR 2043	NC 8	SR 2045	0.40	Seal - Double and Fog Seal	$37,171

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	9	085-Stokes	Preservation	SR 2044	SR 2043	EOM	0.09	Seal - Double and Fog Seal	$7,979
2029	10	004-Anson	Resurfacing	NC 109 S	NC 742	US 74	0.75	Mill 2.0" and 2.0" S9.5C	$300,000
2029	10	004-Anson	Resurfacing	NC 742 N	SR 1422 Boggan Cut	SR 1610 Cedar Grove Church Rd	7.30	Full Depth Patching and 1.5" S9.5C	$2,299,500
2029	10	004-Anson	Resurfacing	SR 1207 Avery Road	US 74	US 74	1.40	1.5" S9.5C and Widen	$354,200
2029	10	004-Anson	Resurfacing	SR 1600 Rocky Mount Church Road	Union County Line	SR 1601 Ashley Allen Circle	0.55	1.5" S9.5C and Widen	$139,150
2029	10	004-Anson	Resurfacing	SR 1627 Pinkston River Rd	SR 1650	SR 1645	3.63	Full Depth Patching and 1.5" S9.5C	$1,143,450
2029	10	004-Anson	Resurfacing	SR 1645 Airport	US 52	SR 1646 Morgan Sellers Rd	2.10	Full Depth Patching and 1.25" S9.5C	$661,500
2029	10	004-Anson	Preservation	SR 1003 E Broad Strett	SR 1003 McLendon Rd	US 52	0.24	Seal - Double	$9,120
2029	10	004-Anson	Preservation	SR 1003 McLendon Rd	NC 145	Zoar Rd	3.52	Seal - Double	$133,550
2029	10	004-Anson	Preservation	SR 1100 Adams Rd	SR 1102 McCoy Road	SR 1003 Cason Oldfield Rd	1.03	Seal - Double	$39,140
2029	10	004-Anson	Preservation	SR 1102 McCoy	South Carolina State Line	SR 1100 Adams Rd	0.32	Seal - Double	$12,160
2029	10	004-Anson	Preservation	SR 1804 Hinson Rd	NC 145	SR 1801 Haileys Ferry Rd	1.03	Seal - Double	$39,140
2029	10	004-Anson	Preservation	SR 1805 Atkinson Rd	SR 1806 Wall Rd	SR 1806 Wall Rd	1.47	Seal - Double	$55,860
2029	10	004-Anson	Preservation	SR 1806 Wall Rd	SR 1801 Haileys Ferry Rd	NC 145 S	3.49	Seal - Double	$132,620
2029	10	004-Anson	Preservation	SR 1812 Diggs Rd	NC 145	US 52	4.02	Seal - Double	$152,760
2029	10	004-Anson	Preservation	SR 1829 Sneedsboro Rd	US 52 S	US 52 S	6.70	Seal - Double	$254,600
2029	10	004-Anson	Preservation	SR 1830 Nivens Rd	SR 1829 Sneedsboro Rd	US 52	0.98	Seal - Double	$37,240
2029	10	004-Anson	Preservation	SR 1831 Ratliff Gin Rd	US 52 S	SR 1832 Peru Rd	0.66	Seal - Double	$25,080
2029	10	004-Anson	Preservation	SR 1833 Cason-Mclaurin	SR 1832 Peru Rd	NC 145	1.48	Seal - Double	$56,240
2029	10	004-Anson	Preservation	SR 1834 Previtte Rd	NC 145	NC 145	1.71	Seal - Double	$64,980
2029	10	004-Anson	Preservation	SR 1835 Johnson Melton Rd	SR 1832 Peru Rd	NC 145 S	1.58	Seal - Double	$60,040
2029	10	004-Anson	Preservation	SR 1837 Zoar Rd	South Carolina State Line	SR 1003 McLendon Rd	1.11	Seal - Double	$42,180
2029	10	004-Anson	Preservation	SR 1840 Thomas Rd	US 52 S	SR 1821 Country Club Rd	0.09	Seal - Double	$3,420
2029	10	004-Anson	Preservation	SR 1866 Galilee Rd	SR 1003 McLendon Rd	End of Maintenance	0.25	Seal - Double	$9,500
2029	10	013-Cabarrus	Resurfacing	NC 73	Mecklenburg County Line	SR 1602 +.817 miles	1.80	Full Depth Patching and 2.0" S9.5C	$900,000
2029	10	013-Cabarrus	Resurfacing	SR 1155 Webb Rd	SR 1157 Wilshire Dr	SR 1482 Zion Ch Rd	0.41	Mill 1.5" and 1.5" S9.5B	$108,211
2029	10	013-Cabarrus	Resurfacing	SR 1157 Old Charlotte Rd	NC 49	SR 1335 Old Charlotte Rd	1.13	1.5" S9.5C	$384,200
2029	10	013-Cabarrus	Resurfacing	SR 1238 Hackney Ct	SR 1223 Appaloosa Ln	dead end	0.05	1.5" S9.5B	$17,000
2029	10	013-Cabarrus	Resurfacing	SR 1270 Sparrow Ln	SR 1269 Falcon Dr	SR 2366 Kiwi Ct	0.10	1.25" S4.75A	$34,000
2029	10	013-Cabarrus	Resurfacing	SR 1304 Roberta Rd	bridge	bridge	1.14	Mill 1.5" and 1.5" S9.5C	$220,000
2029	10	013-Cabarrus	Resurfacing	SR 1448 Cox Mill Rd	Heritage	SR 1394 Poplar Tent Rd	1.78	Full Depth Patching and 1.5" S9.5C	$943,003
2029	10	013-Cabarrus	Resurfacing	SR 1624 Boy Scout Camp	SR 1625	dead end	0.22	1.25" S4.75A	$40,000
2029	10	013-Cabarrus	Resurfacing	SR 1624 Boy Scout Camp Rd	SR 1625	Dead End	0.22	Full Depth Patching and 2.0" S9.5C	$110,000
2029	10	013-Cabarrus	Resurfacing	SR 1745 Oakwood Ave	Begin 18' pavement	SR 1643	0.61	Mill 3.0" and 3.0" S9.5C	$450,000
2029	10	013-Cabarrus	Resurfacing	SR 1841 Avalon Dr	SR 1841 Bahama Dr	SR 1841 Bahama Dr	0.39	1.25" S4.75A	$180,000
2029	10	013-Cabarrus	Resurfacing	SR 1864 Hills Dell Dr	SR 1442 Odell School Rd	dead end	0.28	1.25" S4.75A	$95,200
2029	10	013-Cabarrus	Resurfacing	SR 1871 Canterbury Rd	SR 1870 Surrey Dr	dead end	0.13	1.25" S4.75A	$41,400
2029	10	013-Cabarrus	Resurfacing	SR 1933 Hunter's Trace Dr	SR 1602 Jim Johnson Rd	dead end	0.36	1.25" S4.75A	$122,400
2029	10	013-Cabarrus	Resurfacing	SR 1951 Sunshine Ln	SR 1948 Gail Ln	eom	0.20	1.25" S4.75A	$68,000
2029	10	013-Cabarrus	Resurfacing	SR 2114 Centergrove Rd	Penninger Rd	MP 3.46	3.47	Mill 1.5" and 2.0" S9.5C	$600,000
2029	10	013-Cabarrus	Resurfacing	SR 2119 Camp Julia Rd	SR 2114 Centergrove Rd	SR 1002 Concord Salisbury Rd	1.16	Full Depth Patching and 1.5" S9.5B	$174,000
2029	10	013-Cabarrus	Resurfacing	SR 2287 Church St	US 29 South	US 29 +.075 miles	0.14	Mill 1.5" and 1.5" S9.5B	$51,100
2029	10	013-Cabarrus	Resurfacing	SR 2378 Valley Trail	SR 2375 Broxton Dr	dead end	0.06	1.25" SF9.5A	$17,250
2029	10	013-Cabarrus	Resurfacing	SR 2382 Brigadoon Ct	SR 1154 Piney Church Rd	Cul-de-sac	0.13	Mill 1.25" and 1.25" S9.5B	$78,500
2029	10	013-Cabarrus	Resurfacing	SR 2383 Castle Rock Ct	SR 1154 Piney Church Rd	Cul-de-sac	0.11	Mill 1.25" and 1.25" S9.5B	$66,500
2029	10	013-Cabarrus	Resurfacing	SR 2398 Stafford Farm Rd	Sr 1132 Flowes Store RD	cul-de-sac	0.24	1.25" S4.75A	$50,000
2029	10	013-Cabarrus	Resurfacing	SR 2416 Mt Olive Rd	SR 2414 St John's Ch Rd	SR 1006 Mt Pleasant Rd	2.15	1.25" S9.5B	$440,000
2029	10	013-Cabarrus	Resurfacing	SR 2485 Lynwood Dr	SR 2635 Old Airport Rd	SR 2635 Old Airport Rd	0.51	Full Depth Patching and 1.5" S9.5B	$110,000
2029	10	013-Cabarrus	Resurfacing	SR 2703 Ross Lee Dr	SR 2411 Cold Springs Rd	Dead End	0.09	Mill 1.5" and 1.5" S9.5B	$33,000
2029	10	013-Cabarrus	Resurfacing	SR 2706 Navion Pl	Cul-de-sac	Cul-de-sac	0.30	Mill 1.5" and 1.5" S9.5B	$109,500
2029	10	013-Cabarrus	Resurfacing	SR 2718 Corina Dr	SR 1006 Mt Pleasant Rd	cul-de-sac	0.17	1.25" S4.75A	$55,200
2029	10	013-Cabarrus	Resurfacing	SR 2820 Bayberry Trail	Scalybark	Scalybark	0.53	1.25" SF9.5A	$182,850
2029	10	013-Cabarrus	Resurfacing	SR 2821 Chinaberry Lane	Scalybark	Bayberry Trail	0.29	1.25" SF9.5A	$100,050
2029	10	013-Cabarrus	Resurfacing	SR 2904 North Chase Dr	SR 1394 Poplar Tent Rd	dead end	0.45	1.25" S4.75A	$151,800
2029	10	013-Cabarrus	Resurfacing	SR 2910 Scottland Dr	SR 1154 Piney Church Rd	SR 2376 Daffodil Ln	0.17	Mill 1.25" and 1.25" S9.5B	$83,823
2029	10	013-Cabarrus	Resurfacing	SR 2912 Poplar Woods Dr	SR 1394 Poplar Tent Rd	dead end	0.51	Mill 1.25" and 1.25" S9.5A	$242,780
2029	10	013-Cabarrus	Resurfacing	SR 2912 Poplar Woods Dr	begin div	end div	0.08	Mill 1.25" and 1.25" S9.5A	$36,672
2029	10	013-Cabarrus	Resurfacing	SR 2919 Astonshire Ln	SR 2898 Hawick Commons	End Maintenance	0.13	Mill 1.5" and 1.5" S9.5B	$47,450
2029	10	013-Cabarrus	Resurfacing	SR 3015 Tyne Castle Ct	SR 3013 Loch Lomond Cir	Cul-de-sac	0.07	Mill 1.25" and 1.25" S9.5B	$45,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	10	013-Cabarrus	Resurfacing	SR 3034 Baystone Pl	SR 1135 Morrison Rd	dead end	0.36	Full Depth Patching and 1.5" S9.5B	$90,091
2029	10	013-Cabarrus	Resurfacing	SR 3037 Weatherstone Pl	SR 3036 McCamie Hill Pl	dead end	0.05	Full Depth Patching and 1.5" S9.5B	$17,000
2029	10	013-Cabarrus	Resurfacing	SR 3038 Rolling Hills Ct	SR 3036 McCamie Hill Pl	dead end	0.20	Full Depth Patching and 1.5" S9.5B	$69,000
2029	10	013-Cabarrus	Resurfacing	SR 3039 Weaston Point Pl	SR 3038 Rolling Hills Ct	dead end	0.05	Full Depth Patching and 1.5" S9.5B	$14,000
2029	10	013-Cabarrus	Resurfacing	SR 3040 St Andews Pl	SR 1154 Piney Church Rd	Cul-de-sac	0.13	Mill 1.25" and 1.25" S9.5B	$78,500
2029	10	013-Cabarrus	Resurfacing	SR 3043 Hildreth Ct	Cul-de-sac	Cul-de-sac	0.26	Mill 1.25" and 1.25" S9.5B	$157,000
2029	10	013-Cabarrus	Resurfacing	SR 3044 Meredith Ct	SR 1154 Piney Church Rd	Cul-de-sac	0.11	Mill 1.25" and 1.25" S9.5B	$66,500
2029	10	013-Cabarrus	Resurfacing	SR 3045 Adamshire Ave	SR 3013 Loch Lomond Cir	SR 1154 Piney Ch Rd	0.23	Mill 1.25" and 1.25" S9.5B	$140,000
2029	10	013-Cabarrus	Resurfacing	SR 3046 Gerry Ct	SR 3045 Adamshre Ave	Cul-de-sac	0.20	Mill 1.25" and 1.25" S9.5B	$121,000
2029	10	013-Cabarrus	Resurfacing	US 29 NB	Meck Co Line	Driveway past median opening	1.80	Mill 3.0" and 3.0" S9.5C	$1,412,220
2029	10	013-Cabarrus	Resurfacing	US 29 SB	Pvmt Jt after bridge	Meck Co Line	1.21	Mill 3.0" and 3.0" S9.5C	$949,326
2029	10	013-Cabarrus	Resurfacing	US 52	Rowan County Line	Stanly County Line	1.01	Full Depth Patching and 2.0" S9.5C	$303,000
2029	10	013-Cabarrus	Preservation	SR 1116 Drake Rd	US 601	SR 1113 Hopewell Ch. Rd.	1.17	Seal - Double and Fog Seal	$77,796
2029	10	013-Cabarrus	Preservation	SR 1118 Ben Black Rd	SR 1117	Mecklenburg Co. line	1.15	Seal - Double and Fog Seal	$77,796
2029	10	013-Cabarrus	Preservation	SR 1121 Midland	SR 1123 Bethel Church Rd	SR 1120 Bethel School Rd	0.99	Seal - Double and Fog Seal	$60,000
2029	10	013-Cabarrus	Preservation	SR 1128 Pope Rd	SR 1127	dead end	0.46	Seal - Double and Fog Seal	$32,415
2029	10	013-Cabarrus	Preservation	SR 1133	NC 24-27	SR 1132	1.66	Seal - Double and Fog Seal	$153,000
2029	10	013-Cabarrus	Preservation	SR 1133 Alvin Hugh Rd	SR 1132	NC 24/27	1.66	Seal - Double and Fog Seal	$110,211
2029	10	013-Cabarrus	Preservation	SR 1193 Cimarron Cr/Brandywine ln	SR 1128 Pope Rd	SR 1121 Midland Rd	1.04	Seal - Double and Fog Seal	$60,830
2029	10	013-Cabarrus	Preservation	SR 1295 Watson Dr	SR 1294 Clara Cir	SR 1294 Clara Cir	0.15	Seal - Double and Fog Seal	$9,750
2029	10	013-Cabarrus	Preservation	SR 1444 Untz Rd	SR 1442	Dead End	1.44	Seal - Triple and Fog Seal	$92,102
2029	10	013-Cabarrus	Preservation	SR 1574 Melissa Dr	SR 1304 Roberta Rd	dead end	0.22	Seal - Double and Fog Seal	$14,260
2029	10	013-Cabarrus	Preservation	SR 1607 Sudbury Rd	SR 1608 Davidson Rd	NC 3	0.84	Seal - Double and Fog Seal	$58,347
2029	10	013-Cabarrus	Preservation	SR 1629 Woodside St	SR 1628 Charlie Walker Rd	dead end	0.43	Seal - Double and Fog Seal	$32,415
2029	10	013-Cabarrus	Preservation	SR 1630 Power Line Rd	SR 1628 Charlie Walker Rd	SR 1629	0.15	Seal - Double and Fog Seal	$9,750
2029	10	013-Cabarrus	Preservation	SR 1821 Circlewood Rd	SR 1626 Paigemont	SR 1626 Paigemont	0.32	Seal - Double and Fog Seal	$19,449
2029	10	013-Cabarrus	Preservation	SR 1836 Kentwood	SR 1626 Paigemont	dead end	0.30	Seal - Double and Fog Seal	$19,500
2029	10	013-Cabarrus	Preservation	SR 1843 Dellinger Dr	SR 1600 Shiloh Church Rd	dead end	0.20	Seal - Double and Fog Seal	$13,000
2029	10	013-Cabarrus	Preservation	SR 1925 Randolph Rd	NC 3	dead end	0.29	Seal - Double and Fog Seal	$18,850
2029	10	013-Cabarrus	Preservation	SR 1954 Granite Hill Dr	SR 1608 Davidson Dr	SR 1955 Hidden Forest Ln	0.37	Seal - Double and Fog Seal	$25,932
2029	10	013-Cabarrus	Preservation	SR 2235 Copeland Rd	SR 2113 Penninger Rd	SR 2113 Penninger Rd	0.59	Seal - Double and Fog Seal	$38,350
2029	10	013-Cabarrus	Preservation	SR 2309 Ashley Dr	SR 1292 Bostwood Ln	SR 1292 Bostwood Ln	0.30	Seal - Double and Fog Seal	$20,000
2029	10	013-Cabarrus	Preservation	SR 2310 Vanderhorst Dr	SR 2309 Ashley Dr	SR 1292 Bostwood Ln	0.28	Seal - Double and Fog Seal	$18,200
2029	10	013-Cabarrus	Preservation	SR 2416 Sansberry Rd	SR 2446 Mt Olive Rd	SR 2444 St Stephens Ch Rd	1.25	Seal - Double and Fog Seal	$81,250
2029	10	013-Cabarrus	Preservation	SR 2457 Glenmore Rd	Stanley Co. Line	Rowan Co. Line	1.28	Seal - Double and Fog Seal	$84,279
2029	10	060-Mecklenburg	Resurfacing	NC 16 Providence Rd	NC 51 Pineville Matthews Rd	Old Providence Road	2.56	Mill 1.5" and 1.5" S9.5D	$700,000
2029	10	060-Mecklenburg	Resurfacing	NC 16 Providence Rd	Old Providence Road	NC 51 Pineville Matthews Rd	2.56	Mill 1.5" and 1.5" S9.5D	$950,000
2029	10	060-Mecklenburg	Resurfacing	NC 160	Begin divide west of International Airport Dr	End divide	1.05	Mill 1.5" and 1.5" S9.5D	$270,000
2029	10	060-Mecklenburg	Resurfacing	NC 160 West Blvd	Median split west of International Airport Dr	SR 5901 Billy Graham Parkway	1.08	Mill 1.5" and 1.5" S9.5D	$350,000
2029	10	060-Mecklenburg	Resurfacing	NC 24 East WT Harris Blvd EBL	NC 115 Old Statesville Rd	SR 2480 West Sugar Creek Rd	1.52	Mill 1.5" and 1.5" S9.5D	$1,000,000
2029	10	060-Mecklenburg	Resurfacing	NC 24 East WT Harris Blvd WBL	SR 2480 West Sugar Creek Rd	NC 115 Old Statesville Rd	1.52	Mill 1.5" and 1.5" S9.5D	$1,150,000
2029	10	060-Mecklenburg	Resurfacing	NC 27 / Independence Blvd Ramp	E 7th St / Monroe Rd	Ramp tie in	0.01	Mill 3.0" and 3.0" S9.5C	$2,000
2029	10	060-Mecklenburg	Resurfacing	NC 27 Freedom Dr EBL	0.10 mi before Wesley Village Rd	Bryant St	0.39	Mill 1.5" and 1.5" S9.5D	$130,000
2029	10	060-Mecklenburg	Resurfacing	NC 27 Freedom Dr WBL	Bryant St	0.10 mi past Wesley Village Rd	0.40	Mill 1.5" and 1.5" S9.5D	$130,000
2029	10	060-Mecklenburg	Resurfacing	NC 49	I-77 +.832 miles	NC 49 S	0.60	Mill 1.5" and 1.5" S9.5D	$260,000
2029	10	060-Mecklenburg	Resurfacing	NC 49 South Tryon St NBL	NC 160 Steele Creek Rd	SR 1347 Nevada Blvd	2.89	Mill 1.5" and 1.5" S9.5D	$600,000
2029	10	060-Mecklenburg	Resurfacing	NC 49 South Tryon ST SBL	SR 1347 Nevada Blvd	NC 160 Steele Creek Rd	2.89	Mill 1.5" and 1.5" S9.5D	$600,000
2029	10	060-Mecklenburg	Resurfacing	NC 51 Rock Hill Pineville Rd	NC 51 S	Miller Rd	0.12	Mill 1.5" and 1.5" S9.5D	$30,000
2029	10	060-Mecklenburg	Resurfacing	SR 1106 Hamilton Rd	NC 160 Steele Creek	State Line	1.16	Mill 1.5" and 2.0" S9.5C	$400,000
2029	10	060-Mecklenburg	Resurfacing	SR 1116 Shopton Rd West	Kirkwood Commons Dr	SR 1114 Woody Point Rd	3.32	Full Depth Patching and 1.5" S9.5C	$710,000
2029	10	060-Mecklenburg	Resurfacing	SR 1129 Downs Road	NC 51 Rock Hill Pineville Road	EOM past Ammon Lane	1.26	Full Depth Patching and 1.5" S9.5C	$300,000
2029	10	060-Mecklenburg	Resurfacing	SR 1143 West Arrowood Rd EBL	SR 1142 Sandy Porter Rd	EOM	0.15	Full Depth Patching and 1.5" S9.5C	$30,000
2029	10	060-Mecklenburg	Resurfacing	SR 1143 West Arrowood Rd EBL	SR 1142 Sandy Porter Rd	I-485 Bridge	0.34	Full Depth Patching and 1.5" S9.5C	$100,000
2029	10	060-Mecklenburg	Resurfacing	SR 1143 West Arrowood Rd WBL	I-485 Bridge	SR 1142 Sandy Porter Rd	0.34	Full Depth Patching and 1.5" S9.5C	$100,000
2029	10	060-Mecklenburg	Resurfacing	SR 1143 West Arrowood Rd WBL	SR 1142 Sandy Porter Rd	EOM	0.15	Full Depth Patching and 1.5" S9.5C	$30,000
2029	10	060-Mecklenburg	Resurfacing	SR 1149 Horton Rd	Garrison Rd	eom	0.31	Full Depth Patching and 1.25" S9.5B	$55,000
2029	10	060-Mecklenburg	Resurfacing	SR 1291 East Woodlawn Rd	SR 3998 South Blvd	NC 49 S Tryon S	0.80	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$335,000
2029	10	060-Mecklenburg	Resurfacing	SR 1291 East Woodlawn Rd	Begin Divide at Sterling Dr	End Divide at South Blvd	0.16	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$37,000
2029	10	060-Mecklenburg	Resurfacing	SR 1291 W. Woodlawn Rd	NC 49 S Tryon St	end divide at Wallingford st	0.28	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$70,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	10	060-Mecklenburg	Resurfacing	SR 1335 Wildlife Rd	pvmnt change	pvmnt change	0.26	Full Depth Patching and 1.25" S9.5B	$40,000
2029	10	060-Mecklenburg	Resurfacing	SR 1392 Harbor View Rd	Kalabash Rd	eom	0.30	Full Depth Patching and 1.25" S9.5B	$55,000
2029	10	060-Mecklenburg	Resurfacing	SR 1435 Sharlyn Dr	Walker Ferry Rd	dead end	0.28	Full Depth Patching and 1.25" S9.5B	$55,000
2029	10	060-Mecklenburg	Resurfacing	SR 1436 Parkwood Dr	Sharlyn Dr	dead end	0.12	Full Depth Patching and 1.25" S9.5B	$25,000
2029	10	060-Mecklenburg	Resurfacing	SR 1437 Margaret Lane	Parkwood Dr	dead end	0.06	Full Depth Patching and 1.25" S9.5B	$15,000
2029	10	060-Mecklenburg	Resurfacing	SR 1446 Marshall Acres Drive	Old Dowd Rd	Barry Oak Circle	0.12	Full Depth Patching and 1.25" S9.5B	$25,000
2029	10	060-Mecklenburg	Resurfacing	SR 1447 Barry Oak Circle	Marshall Acres Dr	eom	0.16	Full Depth Patching and 1.25" S9.5B	$30,000
2029	10	060-Mecklenburg	Resurfacing	SR 1501 Traymore Lane/ Withers Cove	Wildlife Rd / Withers Cove	dead end	0.21	Full Depth Patching and 1.25" S9.5B	$40,000
2029	10	060-Mecklenburg	Resurfacing	SR 1509 Four Horse Rd	SR 1116 Shopton Rd W	Waymart Ln	0.63	Mill 1.5" and 2.0" S9.5C	$269,000
2029	10	060-Mecklenburg	Resurfacing	SR 1510 Here At Last Lane	Youngblood Rd North	eom	0.48	Full Depth Patching and 1.25" S9.5B	$90,000
2029	10	060-Mecklenburg	Resurfacing	SR 1531 Tulloch Rd	Walnut Hill Dr	eom	0.49	Full Depth Patching and 1.25" S9.5B	$90,000
2029	10	060-Mecklenburg	Resurfacing	SR 1567 Split Pine Ct	Broad Oak Dr	cul-de-sac	0.03	Mill 1.25" and 1.25" S9.5B	$5,000
2029	10	060-Mecklenburg	Resurfacing	SR 1813 Thomasboro Dr	Glenwood Dr	Bradford Dr	0.58	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5C	$625,000
2029	10	060-Mecklenburg	Resurfacing	SR 2075 Weston Woods Lane	SR 2037 Kelly Road	SR 2078 Aldwych Way	0.18	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$40,000
2029	10	060-Mecklenburg	Resurfacing	SR 2076 Bamburgh Ct	EOM	EOM	0.14	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$30,000
2029	10	060-Mecklenburg	Resurfacing	SR 2077 Deshler Morris Lane	SR 2076 Weston Woods	SR 2078 Aldwych Way	0.11	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$25,000
2029	10	060-Mecklenburg	Resurfacing	SR 2078 Aldwych Way	EOM	EOM	0.16	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$35,000
2029	10	060-Mecklenburg	Resurfacing	SR 2112 Lakeview Rd	Reames Rd	Beatties Ford Rd	0.98	Full Depth Patching and 1.5" S9.5B	$160,000
2029	10	060-Mecklenburg	Resurfacing	SR 2136 Gilead Rd	I-77 bridge	SR 2138 McCoy Rd	0.71	Full Depth Patching and 1.5" S9.5C	$320,000
2029	10	060-Mecklenburg	Resurfacing	SR 2147 Westmoreland Rd	SR 5544 W Catawba Ave	EOM	1.27	Full Depth Patching and 1.5" S9.5C	$300,000
2029	10	060-Mecklenburg	Resurfacing	SR 2151 Jetton Rd	Peninsula Point Dr	EOM	1.89	Full Depth Patching and 1.5" S9.5C	$350,000
2029	10	060-Mecklenburg	Resurfacing	SR 2179 Carrier Dr/Sage Ave/Rosa Parks P	Beatties Ford Rd	Kentucky Ave	1.51	Full Depth Patching and 1.5" S9.5B	$320,000
2029	10	060-Mecklenburg	Resurfacing	SR 2279 Kennewick Rd	SR 2004 Mt Holly Huntersville Rd	EOM	0.42	Full Depth Patching and 1.25" S9.5B	$75,000
2029	10	060-Mecklenburg	Resurfacing	SR 2321 Marengo Cr	SR 2279 Kennewick Rd	SR 2279 Kennewick Rd	0.49	Mill 1.5" and 2.0" S9.5B	$120,000
2029	10	060-Mecklenburg	Resurfacing	SR 2344 J. T. Williams Junior High Dr	Tipton Dr	eom	0.18	Full Depth Patching and 1.25" S9.5B	$40,000
2029	10	060-Mecklenburg	Resurfacing	SR 2802 Rocky River Rd	Cabarrus County line	Back Creek Church Rd	1.76	Full Depth Patching and 1.5" S9.5C	$325,000
2029	10	060-Mecklenburg	Resurfacing	SR 3106 Brief Rd	NC 218	MP .655	0.67	Full Depth Patching and 1.5" S9.5B	$115,000
2029	10	060-Mecklenburg	Resurfacing	SR 3110 Arlington Church Rd	SR 3110 Arlington Church Rd	EOM	0.36	Full Depth Patching and 1.5" S9.5B	$75,000
2029	10	060-Mecklenburg	Resurfacing	SR 3135 Lebanon Rd	Begin Divide	SR 3128 Lawyers Rd	0.05	Full Depth Patching and 1.5" S9.5C	$10,000
2029	10	060-Mecklenburg	Resurfacing	SR 3135 Lebanon Rd	SR 3128 Lawyers Rd	SR 3156 Margaret Wallace Rd	0.45	Full Depth Patching and 1.5" S9.5C	$100,000
2029	10	060-Mecklenburg	Resurfacing	SR 3156 Margaret Wallace Rd	SR 3135 Lebanon Rd	SR 3143 Idlewild Rd	1.02	Full Depth Patching and 1.5" S9.5C	$210,000
2029	10	060-Mecklenburg	Resurfacing	SR 3624 Rea Rd	NC 51 Pineville-Matthews Rd	Piper Glenn Dr	1.57	Mill 2.0" and 2.0" S9.5C	$550,000
2029	10	060-Mecklenburg	Resurfacing	SR 3624 Rea Road	Piper Glenn Drive	NC 51 Pineville Matthews Road	1.57	Mill 2.0" and 2.0" S9.5C	$720,000
2029	10	060-Mecklenburg	Resurfacing	SR 3687 Park Rd	NC 51 Pineville Matthews	Johnston Rd	0.87	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$524,000
2029	10	060-Mecklenburg	Resurfacing	SR 4240 Morris Pond Dr	Begin Divide	SR 3128 Lawyers Rd	0.06	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$10,000
2029	10	060-Mecklenburg	Resurfacing	SR 4240 Morris Pond Dr	SR 3128 Lawyers Rd	SR 4244 Milton Morris Dr	0.31	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$80,000
2029	10	060-Mecklenburg	Resurfacing	SR 4241 Rena Mae Ln	SR 4240 Morris Pond Dr	SR 4244 Milton Morris Dr	0.37	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$75,000
2029	10	060-Mecklenburg	Resurfacing	SR 4242 Brass Bell Ct	Rena Mae Ln	cul-de-sac	0.04	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$10,000
2029	10	060-Mecklenburg	Resurfacing	SR 4243 Blue Willow Ln	Rena Mae Ln	cul-de-sac	0.06	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$10,000
2029	10	060-Mecklenburg	Resurfacing	SR 4245 English Ivy Ln	SR 4244 Milton Morris Dr	EOM	0.07	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$15,000
2029	10	060-Mecklenburg	Resurfacing	SR 4259 Moss Cove Court	SR 4246 Spring Morning Lane	EOM	0.13	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$25,000
2029	10	060-Mecklenburg	Resurfacing	SR 4260 Ginger Spice Ln	SR 4244 Milton Morris Dr	EOM	0.20	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$45,000
2029	10	060-Mecklenburg	Resurfacing	SR 4261 Sweet Sage Ln	SR 4260 Ginger Spice Ln	EOM	0.06	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$15,000
2029	10	060-Mecklenburg	Resurfacing	SR 4262 Barn Stone Dr	SR 4244 Milton Morris Dr	EOM	0.31	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$65,000
2029	10	060-Mecklenburg	Resurfacing	SR 4263 Pinstripe Ln	SR 4262 Barn Stone Dr	EOM	0.04	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$10,000
2029	10	060-Mecklenburg	Resurfacing	SR 4264 Hunter Green Ln	SR 4241 Rena Mae Ln	EOM	0.08	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$20,000
2029	10	060-Mecklenburg	Resurfacing	SR 4265 Brown Oak Ct	SR 4241 Rena Mae Ln	EOM	0.02	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$5,000
2029	10	060-Mecklenburg	Resurfacing	SR 4277 Verda's Path	SR 3102 Cabarrus Rd	EOM	0.18	Full Depth Patching and 1.5" S9.5B	$40,000
2029	10	060-Mecklenburg	Resurfacing	SR 4279 Red Setter Lane	SR 4278 Swedish Ivy Lane	EOM	0.17	Mill 1.5" and 2.0" S9.5B	$35,000
2029	10	060-Mecklenburg	Resurfacing	SR 4282 David Lee Ln	SR 4278 Swedish Ivy Ln	EOM	0.30	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$60,000
2029	10	060-Mecklenburg	Resurfacing	SR 4283 Houndstooth Dr	SR 4278 Swedish Ivy Ln	EOM	0.12	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$25,000
2029	10	060-Mecklenburg	Resurfacing	SR 4299 Little Fox Lane	SR 4282 Davis Lee Lane	EOM	0.02	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$5,000
2029	10	060-Mecklenburg	Resurfacing	SR 5212 Erica Ct	SR 4282 Davis Lee Ln	EOM	0.03	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$6,000
2029	10	060-Mecklenburg	Resurfacing	SR 5213 Liska Ct	SR 4282 Davis Lee Ln	EOM	0.03	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$6,000
2029	10	060-Mecklenburg	Resurfacing	SR 5225 Morgan Glenn Drive	SR 3110 Arlington Church Rd	EOM	0.36	Full Depth Patching and 1.5" S9.5B	$90,000
2029	10	060-Mecklenburg	Resurfacing	SR 5226 Coral Ridge Drive	SR 5225 Morgan Glenn Dr	EOM	0.15	Full Depth Patching and 1.5" S9.5B	$40,000
2029	10	060-Mecklenburg	Resurfacing	SR 5227 White Cliffs Drive	SR 5225 Morgan Glenn Dr	EOM	0.07	Full Depth Patching and 1.5" S9.5B	$15,000
2029	10	060-Mecklenburg	Resurfacing	SR 5245 Conell Rd	NC 51	eom	0.06	Full Depth Patching and 1.25" S9.5B	$10,000
2029	10	060-Mecklenburg	Resurfacing	SR 5427 S Mint St	US 29 Graham St	W 3rd St	0.21	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$140,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	10	060-Mecklenburg	Resurfacing	SR 5428 W Martin Luther King Jr Blvd	US 29 Graham St	SR 5427 S Mint St	0.10	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$55,000
2029	10	060-Mecklenburg	Resurfacing	SR 5589 Oakdale Woods Dr	SR 2025 Oakdale Rd	EOM	0.05	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$12,000
2029	10	060-Mecklenburg	Resurfacing	SR 5590 Oakdale Creek Ln	BOM	EOM	0.18	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$40,000
2029	10	060-Mecklenburg	Resurfacing	SR 5591 Oakdale Commons Ct	SR 5590 Oakdale Creek Ln	EOM	0.06	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$13,000
2029	10	060-Mecklenburg	Resurfacing	SR 5702 Wilson Dr	Davis Dr	cul de sac	0.73	Full Depth Patching and 1.25" S9.5B	$130,000
2029	10	060-Mecklenburg	Resurfacing	SR 5723 Silveroak Ln	SR 5724 Strathmoor Dr	EOM	0.20	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$50,000
2029	10	060-Mecklenburg	Resurfacing	SR 5724 Strathmoor Dr	Providence Rd West	EOM	0.21	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$51,000
2029	10	060-Mecklenburg	Resurfacing	SR 5725 Olde Mill Stream Ct	SR 5724 Strathmoor Dr	EOM	0.07	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$16,000
2029	10	060-Mecklenburg	Resurfacing	SR 5726 Glenfinnan Dr	Providence Road West	EOM	0.17	Mill 1.25" and 1.25" S9.5B	$40,000
2029	10	060-Mecklenburg	Resurfacing	SR 5727 Stirling Trace Court	EOM	EOM	0.13	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$30,000
2029	10	060-Mecklenburg	Resurfacing	SR 5738 Cardinal Woods Dr	SR 4982 Lancaster Hwy	EOM	0.24	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$46,000
2029	10	060-Mecklenburg	Resurfacing	SR 5739 Bluffton Ct	SR 5738 Cardinal Woods	EOM	0.09	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$15,000
2029	10	060-Mecklenburg	Resurfacing	SR 5740 Edgetree Dr	SR 5738 Cardinal Woods	EOM	0.30	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$60,000
2029	10	060-Mecklenburg	Resurfacing	SR 5741 Autumn Winds Ln	SR 5740 Edgetree Dr	EOM	0.10	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$20,000
2029	10	060-Mecklenburg	Resurfacing	SR 5742 Honeytree Ln	SR 5741 Autumn Winds Ln	EOM	0.16	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$31,000
2029	10	060-Mecklenburg	Resurfacing	SR 5743 Pinegate Ct	SR 5742 Honeytree lane	EOM	0.05	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$10,000
2029	10	060-Mecklenburg	Resurfacing	SR 5744 Bannock Dr	SR 5726 Glenfinnan Dr	EOM	0.18	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$35,000
2029	10	060-Mecklenburg	Resurfacing	SR 5745 Balenie Trace Lane	SR 5744 Bannock Dr	EOM	0.05	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$10,000
2029	10	060-Mecklenburg	Resurfacing	SR 5746 Hawick Manor Lane	SR 5744 Banock Dr	SR 5768 Hawick Manor Lane	0.18	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$35,000
2029	10	060-Mecklenburg	Resurfacing	SR 5747 Tantalion Court	SR 5746 Hawick Manor lane	EOM	0.17	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$33,000
2029	10	060-Mecklenburg	Resurfacing	SR 5753 Winghurst Dr	SR 4982 Lancaster Hwy	EOM	0.28	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$50,000
2029	10	060-Mecklenburg	Resurfacing	SR 5754 Pomerol Ln	SR 5753 Winghurst Dr	EOM	0.27	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$48,000
2029	10	060-Mecklenburg	Resurfacing	SR 5755 Latour Ct	SR 5753 Winghurst Dr	EOM	0.02	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$5,000
2029	10	060-Mecklenburg	Resurfacing	SR 5756 Cognac Ct	Winghurst Dr	cul de sac	0.03	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$6,000
2029	10	060-Mecklenburg	Resurfacing	SR 5757 Emilion Pl	SR 5754 Pomerol Ln	EOM	0.11	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$20,000
2029	10	060-Mecklenburg	Resurfacing	SR 5758 Bergerac Ct	SR 5757 St Emilion Pl	cul-de-sac	0.03	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$4,000
2029	10	060-Mecklenburg	Resurfacing	SR 5759 Harmon Ln	SR 5740 Edgetree Dr	EOM	0.20	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$40,000
2029	10	060-Mecklenburg	Resurfacing	SR 5760 Alex Mill Dr	Harmon Ln	cul de sac	0.16	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$30,000
2029	10	060-Mecklenburg	Resurfacing	SR 5761 Jacobs Ridge Ct	SR 5760 Alex Mill Dr	EOM	0.05	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$10,000
2029	10	060-Mecklenburg	Resurfacing	SR 5762 Rudolph Place	SR 4982 Lancaster Hwy	SR 5759 Harmon Ln	0.06	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$12,000
2029	10	060-Mecklenburg	Resurfacing	SR 5763 Treybrooke Ln	SR 5742 Honeytree Lane	SR 5740 Edgetree Dr	0.06	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$12,000
2029	10	060-Mecklenburg	Resurfacing	SR 5765 Southcrest Ln	SR 4982 Lancaster Hwy	EOM	0.39	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$75,000
2029	10	060-Mecklenburg	Resurfacing	SR 5766 Aden Creek Way	SR 5765 Southcrest Lane	SR 5769 Eastgrove Dr	0.16	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$32,000
2029	10	060-Mecklenburg	Resurfacing	SR 5767 Ridge Stone Court	SR 5768 Hawick Manor Lane	SR 5770 Stone Forest Drive	0.12	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$23,000
2029	10	060-Mecklenburg	Resurfacing	SR 5768 Hawick Manor Lane	SR 5746 Hawick Manor Lane	EOM	0.16	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$32,000
2029	10	060-Mecklenburg	Resurfacing	SR 5769 Eastgrove Dr	SR 5770 Stone Forest Dr	EOM	0.11	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$21,422
2029	10	060-Mecklenburg	Resurfacing	SR 5770 Stone Forest Dr	EOM	EOM	0.18	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$35,000
2029	10	060-Mecklenburg	Resurfacing	SR 5771 Windfall Place	SR 5772 Bridle Trace Lane	EOM	0.04	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$10,000
2029	10	060-Mecklenburg	Resurfacing	SR 5772 Bridel Trace Lane	SR 5766 Aden Creek Way	EOM	0.58	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$110,000
2029	10	060-Mecklenburg	Resurfacing	US 29/NC 49 N Graham St/Dalton Ave	NC 27 W Morehead St	I-277	1.27	Mill 1.5" and 1.5" S9.5D	$850,000
2029	10	060-Mecklenburg	Preservation	SR 1106 Hamilton Rd	NC 160 Steele Creek	State Line	1.16	Rejuvenator	$18,300
2029	10	060-Mecklenburg	Preservation	SR 1609 Rhyne Rd	NC 27 Mt Holly Rd	SR 1601 Moores Chapel Rd	1.33	Rejuvenator	$26,000
2029	10	060-Mecklenburg	Preservation	SR 1676 Old Moores Chapel	SR 6102 Rhyne Station Rd	EOM	0.11	Rejuvenator	$1,500
2029	10	060-Mecklenburg	Preservation	SR 1681 N McDowell St	NC 16 S / East 4th St	East 7th St / Monroe Rd	0.33	Rejuvenator	$11,500
2029	10	060-Mecklenburg	Preservation	SR 2025 Miranda Rd	SR 2108 Sunset Rd	SR 2074 Beatties Ford Rd	1.89	Rejuvenator	$38,000
2029	10	060-Mecklenburg	Preservation	SR 2074 Neck Rd	SR 2165 Johnson Davis Rd	eom	1.72	Rejuvenator	$18,570
2029	10	060-Mecklenburg	Preservation	SR 2136 Gilead Rd	I-77 bridge	SR 2138 McCoy Rd	0.71	Rejuvenator	$13,410
2029	10	060-Mecklenburg	Preservation	SR 2137 Ervin Cook Rd	SR 2136 Gilead Rd	EOM	0.75	Rejuvenator	$8,100
2029	10	060-Mecklenburg	Preservation	SR 2234 Stonegate Dr	SR 2037 Kelly Rd	EOM	0.26	Rejuvenator	$3,500
2029	10	060-Mecklenburg	Preservation	SR 2417 Grey Rd	Iredell County line	Charden Rd	1.02	Rejuvenator	$20,000
2029	10	060-Mecklenburg	Preservation	SR 2417 Grey Rd	Charden Rd	Davidson-Concord Rd	1.51	Rejuvenator	$21,300
2029	10	060-Mecklenburg	Preservation	SR 2445 Trails End Lane	Asbury Chapel Rd	eom	0.53	Rejuvenator	$6,390
2029	10	060-Mecklenburg	Preservation	SR 2467 Mallard Creek	Beg Divide Grace Lane	End Divide Odell School	1.01	Rejuvenator	$17,100
2029	10	060-Mecklenburg	Preservation	SR 2472 W Mallard Creek Ch Rd	Pavement Divide	I-85	0.16	Rejuvenator	$2,300
2029	10	060-Mecklenburg	Preservation	SR 2472 W Mallard Creek Ch Rd	SR 2467 Mallard Creek	Pavement Divide	1.08	Rejuvenator	$15,300
2029	10	060-Mecklenburg	Preservation	SR 2475 Benfield Rd	SR 2479 Dearmon Dr	EOM	0.18	Rejuvenator	$2,800
2029	10	060-Mecklenburg	Preservation	SR 2848 Orr Rd	SR 2853 Newell Hickory Grove Rd	EOM	0.28	Rejuvenator	$3,780
2029	10	060-Mecklenburg	Preservation	SR 2853 Newell Hickory Grove Rd	Newell Acres Dr	EOM	0.78	Rejuvenator	$12,630
2029	10	060-Mecklenburg	Preservation	SR 3047 Morningstar Place Dr	NC 29 N Tryon St	EOM	0.44	Rejuvenator	$7,200

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	10	060-Mecklenburg	Preservation	SR 4221 Spicewood Dr	SR 3128 Lawyers Rd	SR 4222 Redbud Dr	0.69	Rejuvenator	$7,500
2029	10	060-Mecklenburg	Preservation	SR 4222 Redbud Dr	SR 42221 Spicewood Dr	EOM	0.09	Rejuvenator	$1,508
2029	10	060-Mecklenburg	Preservation	SR 4862 Alumni Way	NC 24 E WT Harris Blvd	Cameron Blvd	0.51	Rejuvenator	$8,300
2029	10	060-Mecklenburg	Preservation	SR 4906 Woodside Falls	SR 4982 Lancaster Hwy	EOM	0.78	Rejuvenator	$18,000
2029	10	060-Mecklenburg	Preservation	SR 4907 Blue Granite road	SR 4906 Woodside Falls	EOM	0.10	Rejuvenator	$1,700
2029	10	060-Mecklenburg	Preservation	SR 4908 Slate Rd	SR 4906 Woodside Falls	EOM	0.03	Rejuvenator	$1,250
2029	10	060-Mecklenburg	Preservation	SR 4909 Emerald Ct	SR 4910 Sapphire Ln	EOM	0.11	Rejuvenator	$2,000
2029	10	060-Mecklenburg	Preservation	SR 4910 Sapphire Ln	SR 4906 Woodside Falls	EOM	0.27	Rejuvenator	$5,100
2029	10	060-Mecklenburg	Preservation	SR 4970 Diamond Dr	SR 4910 Sapphire Ln	EOM	0.34	Rejuvenator	$4,800
2029	10	060-Mecklenburg	Preservation	SR 4971 Peridot Ct	SR 4970 Diamond Dr	EOM	0.05	Rejuvenator	$1,500
2029	10	060-Mecklenburg	Preservation	SR 4972 Limestone Ln	SR 4906 Woodside Falls	EOM	0.13	Rejuvenator	$2,100
2029	10	060-Mecklenburg	Preservation	SR 5223 Wilgrove-Mint Hill Rd	NC 24	Wilson Grove Rd	0.22	Rejuvenator	$3,560
2029	10	060-Mecklenburg	Preservation	SR 5435 Old Nations Ford Rd	E Westinghouse Blvd	EOM	0.17	Rejuvenator	$2,300
2029	10	060-Mecklenburg	Preservation	SR 6000 Sweetfield Dr	SR 2459 Eastfield Rd	EOM	0.48	Rejuvenator	$7,800
2029	10	060-Mecklenburg	Preservation	SR 6001 McCahan Ln	EOM	Cul de sac	0.05	Rejuvenator	$600
2029	10	060-Mecklenburg	Preservation	SR 6002 Ryddell Ct	SR 6000 Sweetfield Dr	Cul de sac	0.04	Rejuvenator	$350
2029	10	060-Mecklenburg	Preservation	SR 6003 McGinnis Ln	SR 6000 Sweetfield Dr	Cul de sac	0.13	Rejuvenator	$1,500
2029	10	060-Mecklenburg	Preservation	SR 6004 Glassonby Ct	SR 6000 Sweetfield Dr	Cul de sac	0.04	Rejuvenator	$540
2029	10	060-Mecklenburg	Preservation	SR 6005 McGinnis Woods Dr	SR 6000 Sweetfield Dr	Cul de sac	0.04	Rejuvenator	$540
2029	10	060-Mecklenburg	Preservation	US 74 Wilkinson Blvd	Barry Dr	Alleghany St	2.11	Microsurface	$404,501
2029	10	060-Mecklenburg	Preservation	US 74 Wilkinson Blvd	Alleghany St	Barry Dr	2.11	Microsurface	$404,501
2029	10	084-Stanly	Resurfacing	NC 24/27	Cabarrus Co Line	Begin Divide past Barbee rd	4.21	Mill 1.5" and 1.5" S9.5B	$2,013,000
2029	10	084-Stanly	Resurfacing	NC 73	Cabarrus Co Line	SR 1134 Millingport Rd	4.06	1.5" S9.5C	$1,350,000
2029	10	084-Stanly	Resurfacing	SR 1214 Austin Rd	SR 1400 Old Salisbury Rd	SR 1436 Henderson Rd	1.75	1.5" S9.5B	$537,000
2029	10	084-Stanly	Resurfacing	SR 1837 Old Business 52/ S Second St	US 52	Bus 52/ S Second St	2.60	1.5" S9.5B	$718,515
2029	10	084-Stanly	Resurfacing	SR1436 Austin Rd	US 52 North	SR 1214 Austin Rd	0.07	1.5" S9.5B	$17,500
2029	10	084-Stanly	Resurfacing	US Business 52	NC 24/27 Bypass	SR 1494 East Main St	0.79	Mill 1.5" and 1.5" S9.5B	$267,250
2029	10	084-Stanly	Preservation	SR 1247 McSwain	SR 1214 Austin Rd	SR 1249 Canton Rd	1.79	Seal - Double	$45,000
2029	10	084-Stanly	Preservation	SR 1259 Hickory	SR 1259 Morton	SR 1259 Scally Bark	0.05	Seal - Double	$5,000
2029	10	084-Stanly	Preservation	SR 1259 Morton	SR 1259 Tom Thumb	SR 1259 Hickory Tree	0.04	Seal - Double	$5,000
2029	10	084-Stanly	Preservation	SR 1259 Scally Bark Rd	SR 1259 Hickory Tree	dead end	0.03	Seal - Double	$5,000
2029	10	084-Stanly	Preservation	SR 1259 Tom Thumb	NC 24/27	SR 1259 Morton	0.06	Seal - Double	$1,000
2029	10	084-Stanly	Preservation	SR 1260 Canton Heights	SR 1249 Canton Rd	dead end	0.15	Seal - Double	$8,000
2029	10	084-Stanly	Preservation	SR 1263 Little Bear	SR 1240 Fink Rd	dead end	0.31	Seal - Double	$10,000
2029	10	084-Stanly	Preservation	SR 1266 Bobcat	SR 1266 City Lake	eom	0.60	Seal - Double	$18,000
2029	10	084-Stanly	Preservation	SR 1276 Community	SR 1276 Treece Rd	SR 1242 Hatley Farm Rd	0.40	Seal - Double	$15,000
2029	10	084-Stanly	Preservation	SR 1276 Treece Rd	SR 1240 Fink Rd	SR 1260 Community	0.60	Seal - Double	$15,000
2029	10	084-Stanly	Preservation	SR 1290 Community	SR 1240 Fink Rd	SR 1276 Treece Rd	0.54	Seal - Double	$13,000
2029	10	084-Stanly	Preservation	SR 1511 Yadkin Brick Rd	NC 740 Hwy	SR 1521 Old Whitney Rd	1.16	Seal - Double	$39,000
2029	10	084-Stanly	Preservation	SR 1521 Old Whitney Rd	NC 740 Hwy	EOM	2.81	Seal - Double	$98,350
2029	10	084-Stanly	Preservation	SR 1526 Adam Rd	SR 1569 Barnhardt Rd	SR 1571 Moss Lane	0.33	Seal - Double	$11,000
2029	10	084-Stanly	Preservation	SR 1545 Barnhardt Road	NC 740 Hwy	SR 1524 Airport Rd	2.65	Seal - Double	$92,750
2029	10	084-Stanly	Preservation	SR 1550 Tick Tack Hill Rd	NC 740 Hwy	EOM	0.32	Seal - Double	$11,200
2029	10	084-Stanly	Preservation	SR 1566 Palmerville Rd	NC 740 Hwy	EOM	1.43	Seal - Double	$50,050
2029	10	084-Stanly	Preservation	SR 1568 Gadson Rd	NC 740 Hwy	EOM	0.28	Seal - Double	$12,000
2029	10	084-Stanly	Preservation	SR 1571 Moss Lane	NC 740 Hwy	SR 1511 Yadkin Brick Rd	1.71	Seal - Double	$55,470
2029	10	084-Stanly	Preservation	SR 1583 Isen Lane	SR 1571 Moss Lane	EOM	0.21	Seal - Double	$7,800
2029	10	084-Stanly	Preservation	SR 1584 Martin Rd	NC 740 Hwy	EOM	0.40	Seal - Double	$14,500
2029	10	084-Stanly	Preservation	SR 1594 Shady Rest Rd	NC 740 Hwy	EOM	0.94	Seal - Double	$35,000
2029	10	084-Stanly	Preservation	SR 1600 Wright Rd	NC 740 Hwy	SR 1550 Tick Tack Hill	0.22	Seal - Double	$10,000
2029	10	084-Stanly	Preservation	SR 1607 Catfish Rd	SR 1510 Harper Hearne	EOM	0.36	Seal - Double	$12,000
2029	10	084-Stanly	Preservation	SR 1608 Kings Rd	NC 740 Hwy	EOM	0.22	Seal - Double	$12,000
2029	10	084-Stanly	Preservation	SR 1613 Canal Rd	SR 1647 Snider Rd	EOM	0.77	Seal - Double	$26,950
2029	10	084-Stanly	Preservation	SR 1618 Hudson Rd	SR 1571 Moss Lane	EOM	0.08	Seal - Double	$5,000
2029	10	084-Stanly	Preservation	SR 1647 Snider rd	SR 1613 Canal Rd	EOM	0.46	Seal - Double	$16,500
2029	10	084-Stanly	Preservation	SR 1723 Byrd Rd	SR 1725 Guard Rd	SR 1720 Valley Drive	1.38	Seal - Double	$48,300
2029	10	084-Stanly	Preservation	SR 1724 Miller Town Rd	SR 1720 Valley Drive	EOM	0.34	Seal - Double	$11,900
2029	10	084-Stanly	Preservation	SR 1725 Guard Rd	NC 740 Hwy	SR 1798 Morrow Mountain Rd	1.08	Seal - Double	$35,640
2029	10	084-Stanly	Preservation	SR 1726 Tom Rd	SR 1798 Morrow Mountain Rd	SR 1730 Vickers Store Rd	1.17	Seal - Double	$40,950

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	10	084-Stanly	Preservation	SR 1729 Stony Hill Rd	SR 1720 Valley Drive	End of Asphalt	0.35	Seal - Double	$11,550
2029	10	084-Stanly	Preservation	SR 1730 Clodfelter	SR 1720 Valley Drive	EOM	2.89	Seal - Double	$95,370
2029	10	084-Stanly	Preservation	SR 1730 Vickers Store Rd	NC 742	SR 1720 Valley Drive	2.12	Seal - Double	$74,200
2029	10	084-Stanly	Preservation	SR 1731 Sweet Home Ch Rd	SR 1730 Vickers Store Rd	NC 24-27 Hwy	1.19	Seal - Double	$41,650
2029	10	084-Stanly	Preservation	SR 1736 Dunlap Rd	NC 27-27 Hwy	EOM	0.84	Seal - Double	$29,400
2029	10	084-Stanly	Preservation	SR 1805 Keystone Drive	SR 1720 Valley Drive	EOM	0.49	Seal - Double	$17,150
2029	10	084-Stanly	Preservation	SR 1818 Stony Mountain Rd	NC 24-27 Hwy	SR 1818 Stony Montain End of loop	1.77	Seal - Double	$61,950
2029	10	084-Stanly	Preservation	SR 1827 Scenic Drive	SR 1720 Valley Drive	SR 1805 Keystone Drive	0.26	Seal - Double	$10,000
2029	10	090-Union	Resurfacing	NC 200 N	SR 1681 Old Camden	SR 1643 Watson Ch Rd	3.43	1.5" S9.5B	$1,000,000
2029	10	090-Union	Resurfacing	NC 205	NC 218	Stanly County line	3.18	1.5" S9.5B	$980,000
2029	10	090-Union	Resurfacing	NC 218	SR 1260 Crowell Dairy	US 601	2.17	#67 Mat Seal and 2.0" S9.5B	$800,000
2029	10	090-Union	Resurfacing	NC 218	SR 1601 Unionville-Brief Rd	SR 1001 Sikes Mill Rd	1.78	#67 Mat Seal and 2.0" S9.5C	$750,000
2029	10	090-Union	Resurfacing	NC 218	RAB	SR 1260 Crowell Dairy	0.86	#67 Mat Seal and 2.0" S9.5B	$350,000
2029	10	090-Union	Resurfacing	NC 218	Mecklenburg County line	RAB	1.30	#67 Mat Seal and 2.0" S9.5B	$550,000
2029	10	090-Union	Resurfacing	NC 522	SR 1132 Frank Brome Rd	SR 1134 Lathan Rd	1.32	1.5" S9.5B	$270,000
2029	10	090-Union	Resurfacing	NC 522	SR 1134 Lathan Rd	NC 200 S	1.35	1.5" S9.5B	$270,000
2029	10	090-Union	Resurfacing	SR 1008 Waxhaw-Indian Trail Rd	SR 1328 Shannon Rd	SR 1515 Newtown Rd	0.90	1.5" S9.5B	$240,000
2029	10	090-Union	Resurfacing	SR 1329 Billy Howie Rd	SR 1315 Newtown Rd	SR 1327 Pleasant Grove Rd	2.19	1.5" S9.5B	$700,000
2029	10	090-Union	Resurfacing	SR 1362 Chestnut Ln	SR 1357 Potters Rd	SR 1344 Weddington-Matthews	1.65	1.5" S9.5C	$550,000
2029	10	090-Union	Resurfacing	SR 1367 Unionville-Indian Trail	SR 1518 Faith Ch	SR 1515 Sardis Ch Rd	0.73	1.5" S9.5B	$200,000
2029	10	090-Union	Resurfacing	SR 1518 Faith Ch Rd	SR 1520 Indian Trail/Fariview	SR 3034 Hemby Commons	0.10	Mill 1.5" and 1.5" S9.5C	$40,000
2029	10	090-Union	Resurfacing	SR 1615 Unionville Rd	SR 1606 Sikes Mill	SR 1001 Sikes Mill Rd	2.88	1.5" S9.5B and Widen	$900,000
2029	10	090-Union	Resurfacing	SR 1640 Rushing Benton Rd	SR 1515 Unionville Rd	SR 1611 Clontz Long	1.26	1.5" S9.5C	$400,000
2029	10	090-Union	Resurfacing	SR 1710 Pleasant Hill Ch	NC 218	SR 1706 Fish Rd	2.33	1.5" S9.5C	$790,000
2029	10	090-Union	Resurfacing	SR 1710 Pleasant Hill Ch	SR 1706 Fish Rd	SR 1708 Old Kennedy Ford	0.74	1.5" S9.5C	$100,000
2029	10	090-Union	Resurfacing	SR 1740 Old 74	US 74	SR 1937 Old Pageland Marshville Rd	3.63	#67 Mat Seal and 2.0" S9.5C	$1,000,000
2029	10	090-Union	Resurfacing	SR 2133 E Sandy Ridge Rd	NC 207	SR 2115 Stack Rd	3.41	1.5" S9.5B	$920,000
2029	10	090-Union	Resurfacing	SR 2717 Polk Mnt Dr	SR 1627 New Salem Rd	SR 2717 Polk Mnt Dr	1.49	#78 Mat Seal and 1.0" S9.5A	$300,000
2029	10	090-Union	Resurfacing	SR 3015 Trillium Dr	SR 3034 Hemby Commons Parkway	cul de sac	0.08	Mill 1.5" and 1.5" S9.5C	$32,000
2029	10	090-Union	Resurfacing	SR 3033 Galena Chase	cul de sac	cul de sac	0.32	Mill 1.5" and 1.5" S9.5C	$125,000
2029	10	090-Union	Resurfacing	SR 3034 Hemby Commons Parkway	cul de sac	SR 1520 Indian Trail/Fairview	0.45	Mill 1.5" and 1.5" S9.5C	$175,000
2029	10	090-Union	Resurfacing	SR 3036 Thicketty Parkway	SR 1520 Indian Trail/Fairview	SR 3038 Enderbury	0.44	Mill 1.5" and 1.5" S9.5C	$175,000
2029	10	090-Union	Resurfacing	SR 3037 Biker Ct	cul de sac	cul de sac	0.19	Mill 1.5" and 1.5" S9.5C	$80,000
2029	10	090-Union	Resurfacing	SR 3038 Enderbury Ct	SR 3036Thicketty Parkway	cul de sac	0.80	Mill 1.5" and 1.5" S9.5C	$320,000
2029	10	090-Union	Resurfacing	SR 3039 Makin Dr	SR 3036Thicketty Parkway	SR 3038 Enderbury	0.38	Mill 1.5" and 1.5" S9.5C	$140,000
2029	10	090-Union	Resurfacing	SR 3040 Banaba Ct	SR 3039 Makin Dr	cul de sac	0.06	Mill 1.5" and 1.5" S9.5C	$22,000
2029	10	090-Union	Resurfacing	SR 3041 Chrisopal Ct	SR 3036Thicketty Parkway	cul de sac	0.11	Mill 1.5" and 1.5" S9.5C	$43,000
2029	10	090-Union	Resurfacing	SR 3042 Ponape Ct	SR 3036Thicketty Parkway	cul de sac	0.05	Mill 1.5" and 1.5" S9.5C	$20,000
2029	10	090-Union	Resurfacing	SR 3043 Mortlock Ct	SR 3038 Enderbury	cul de sac	0.04	Mill 1.5" and 1.5" S9.5C	$20,000
2029	10	090-Union	Resurfacing	SR 3045 Quota Dr	cul de sac	cul de sac	0.14	Mill 1.5" and 1.5" S9.5C	$55,000
2029	10	090-Union	Rehabilitation	SR 1920 Zion Ch	SR 1919 Canal Rd	SR 1915 Smith Town Rd	1.27	FDR and 1.0" S9.5A	$570,000
2029	10	090-Union	Rehabilitation	SR 1963 Presson Rd	US 74	US 74	0.74	FDR and 1.5" S9.5B	$340,000
2029	10	090-Union	Preservation	SR 1724 Nance Tarlton Rd	SR1724 Nance Tarlton rd	SR 1725 Deep Springs Rd	1.99	Seal - Double	$93,530
2029	10	090-Union	Preservation	SR 1900 Marshville water plant Rd	US 74	EOM	1.43	Seal - Double	$67,210
2029	10	090-Union	Preservation	SR 2549 Steeplechase Cir	SR 2548 High Gate	SR 2548 High Gate	0.64	Seal - Double and Fog Seal	$45,500
2029	11	003-Alleghany	Resurfacing	SR 1153	NC 113	SR 1154	0.72	Leveling and 1.5" S9.5B	$228,100
2029	11	003-Alleghany	Resurfacing	SR 1154	SR 1161	SR 1153	1.23	Leveling and 1.5" S9.5B	$432,960
2029	11	003-Alleghany	Resurfacing	SR 1161	US 221	SR 1154	2.23	Leveling and 1.5" S9.5B	$784,960
2029	11	003-Alleghany	Resurfacing	SR 1170	BEG PVMT	US 221	0.69	1.5" S9.5B	$218,600
2029	11	003-Alleghany	Preservation	SR 1160	NC 113	EOM	0.75	Seal - Triple and Fog Seal	$63,360
2029	11	003-Alleghany	Preservation	SR 1463	US 21	SR 1472	3.10	Seal - Triple and Fog Seal	$272,420
2029	11	003-Alleghany	Preservation	SR 1463	SR 1472	BR PKWY	2.72	Seal - Triple and Fog Seal	$229,620
2029	11	003-Alleghany	Preservation	SR 1463	BR PKWY	SR 1464	0.12	Seal - Triple and Fog Seal	$8,790
2029	11	005-Ashe	Resurfacing	NC 16	SR 1158	NC 88	2.38	1.5" S9.5C	$963,424
2029	11	005-Ashe	Resurfacing	NC 88	NC 194	US 221 Bus	0.75	1.5" S9.5C	$314,688
2029	11	005-Ashe	Resurfacing	NC 88	NC 194	US 221 Bus	0.47	1.5" S9.5C	$197,261
2029	11	005-Ashe	Resurfacing	SR 1100	NC 194	Begin 20' PVMT	2.59	1.5" S9.5B	$820,512
2029	11	005-Ashe	Resurfacing	SR 1181	NC 163	END PVMT	1.75	1.5" S9.5B	$554,400
2029	11	005-Ashe	Preservation	SR 1106	SR 1105	SR 1111	3.29	FDR and 2.0" S9.5B	$810,656

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	11	005-Ashe	Preservation	SR 1180	MP 1.05	SR 1179	0.92	Seal - Triple and Fog Seal	$77,722
2029	11	006-Avery	Resurfacing	NC 105	US 221	MP 3.5	3.50	Full Depth Patching and 1.5" S9.5C	$1,848,000
2029	11	006-Avery	Resurfacing	SR 1321	NC 194	EOM	2.20	1.5" S9.5B	$696,960
2029	11	006-Avery	Preservation	SR 1347	NC 181	SR 1346	2.51	Seal - Triple and Fog Seal	$212,040
2029	11	014-Caldwell	Resurfacing	NC 268	US 321 NB	Bridge # 007 over Yadkin River	0.93	Pavement Interlayer and 1.5" S9.5C	$343,728
2029	11	014-Caldwell	Resurfacing	NC 90	Milepost 10.05	SR 1356	3.79	1.5" S9.5B	$1,200,670
2029	11	014-Caldwell	Resurfacing	SR 1134	SR 1153	SR 1141	1.45	Full Depth Patching and 1.5" S9.5C	$510,400
2029	11	014-Caldwell	Resurfacing	SR 1145	VIRGINIA ST (NS)	BRIDGE # 0357	0.34	Mill 1.5" and 1.5" S9.5C	$179,520
2029	11	014-Caldwell	Resurfacing	SR 1149	SR 1153	SR 1150	0.58	Mill 1.5" and 1.5" S9.5B	$183,744
2029	11	014-Caldwell	Resurfacing	SR 1150	SR 1933	SCL Lenoir	0.30	Mill 1.5" and 1.5" S9.5B	$84,480
2029	11	014-Caldwell	Resurfacing	SR 1150	SR 1149	SR 1933	1.28	Mill 1.5" and 1.5" S9.5B	$405,504
2029	11	014-Caldwell	Resurfacing	SR 1180	US 321	SR 1178	0.90	1.5" S9.5B	$380,160
2029	11	014-Caldwell	Resurfacing	SR 1180	BEGIN MEDIAN	US 321	0.35	1.5" S9.5B	$147,840
2029	11	014-Caldwell	Resurfacing	US 321	Begin Median Island South Of US 321	End 5 lane Section at NC 90	2.38	Mill 1.5" and 1.5" S9.5C	$2,586,144
2029	11	014-Caldwell	Preservation	SR 1396	NC 90	EOM	0.20	Seal - Triple and Fog Seal	$16,896
2029	11	014-Caldwell	Preservation	SR 1503	SR 1504	EOP	2.33	Seal - Triple and Fog Seal	$219,085
2029	11	014-Caldwell	Preservation	SR 1513	SR 1604	US 321	0.78	Seal - Triple and Fog Seal	$58,573
2029	11	014-Caldwell	Preservation	SR 1513	PVMT WIDTH CHANGE	SR 1604	0.80	Seal - Triple and Fog Seal	$67,584
2029	11	014-Caldwell	Preservation	SR 1513	SR 1518	PVMT WIDTH CHANGE	3.35	Seal - Triple and Fog Seal	$296,173
2029	11	014-Caldwell	Preservation	SR 1513	NC 268	SR 1518	1.57	Seal - Triple and Fog Seal	$132,634
2029	11	014-Caldwell	Preservation	SR 1514	NC 268	SR 1513	0.90	Seal - Triple and Fog Seal	$84,480
2029	11	014-Caldwell	Preservation	SR 1701	NC 18	EOP	0.46	Seal - Triple and Fog Seal	$43,179
2029	11	014-Caldwell	Preservation	SR 1749	SR 1718	SR 1751	0.48	Seal - Triple and Fog Seal	$45,056
2029	11	086-Surry	Resurfacing	SR 1003	SR 2000	SR 2258	1.10	1.5" S9.5B	$385,440
2029	11	086-Surry	Resurfacing	SR 1356	SR 1350	SR 2258	3.45	1.5" S9.5B	$1,275,120
2029	11	086-Surry	Resurfacing	SR 1815	Bridge # 0181 over US 52	SR 1951	0.36	1.5" S9.5B	$139,392
2029	11	086-Surry	Resurfacing	SR 2019	SR 2034	SR 2038	1.43	1.5" S9.5B	$503,360
2029	11	086-Surry	Resurfacing	SR 2019	SR 1003	SR 2034	1.82	1.5" S9.5B	$640,640
2029	11	086-Surry	Resurfacing	SR 2037	SR 1003	NC 268	1.82	1.5" S9.5B	$576,576
2029	11	086-Surry	Resurfacing	SR 2258	SR 2218	SR 1359	3.41	1.5" S9.5B	$1,080,288
2029	11	086-Surry	Resurfacing	US 52 BUS	US 52	ARARAT RIVER BRIDGE	2.06	1.5" S9.5C	$870,144
2029	11	086-Surry	Preservation	SR 1105	SR 1104	SR 1110	1.97	Seal - Triple and Fog Seal	$166,426
2029	11	086-Surry	Preservation	SR 1107	SR 1110	SR 1109	1.34	Seal - Triple and Fog Seal	$113,203
2029	11	086-Surry	Preservation	SR 1109	US 601	SR 1105	2.09	Seal - Triple and Fog Seal	$176,563
2029	11	086-Surry	Preservation	SR 1111	NC 268	SR 1177	1.80	Seal - Triple and Fog Seal	$168,960
2029	11	086-Surry	Preservation	SR 1127	SR 1001	SR 1126	1.26	Seal - Triple and Fog Seal	$118,272
2029	11	086-Surry	Preservation	SR 1136	US 21	NC 268	2.54	Seal - Triple and Fog Seal	$238,421
2029	11	086-Surry	Preservation	SR 1161	US 21	END PVMT	2.16	Seal - Triple and Fog Seal	$182,477
2029	11	086-Surry	Preservation	SR 1468	SR 1470	CUL-DE-SAC	0.11	Seal - Triple and Fog Seal	$10,325
2029	11	086-Surry	Preservation	SR 1486	SR 1485	END Maintenance	0.13	Seal - Triple and Fog Seal	$12,203
2029	11	086-Surry	Preservation	SR 2140	SR 2012	SR 2012	0.45	Seal - Triple and Fog Seal	$42,240
2029	11	086-Surry	Preservation	SR 2141	SR 2140	CUL-DE-SAC	0.12	Seal - Triple and Fog Seal	$11,264
2029	11	086-Surry	Preservation	SR 2204	SR 1100	SR 1003	1.63	Seal - Triple and Fog Seal	$137,702
2029	11	086-Surry	Preservation	SR 2217	SR 2218	SR 2215	0.56	Seal - Triple and Fog Seal	$47,309
2029	11	086-Surry	Preservation	SR 2223	US 601	CUL-DE-SAC	0.90	Seal - Triple and Fog Seal	$84,480
2029	11	086-Surry	Preservation	SR 2249	SR 2221	END MAINTENANCE	0.47	Seal - Triple and Fog Seal	$35,294
2029	11	086-Surry	Preservation	SR 2439	SR 2434	CUL-DE-SAC	0.16	Seal - Triple and Fog Seal	$15,019
2029	11	086-Surry	Preservation	SR 2440	SR 2450	CUL-DE-SAC	0.44	Seal - Triple and Fog Seal	$41,301
2029	11	086-Surry	Preservation	SR 2444	SR 2440	CUL-DE-SAC	0.17	Seal - Triple and Fog Seal	$15,863
2029	11	086-Surry	Preservation	SR 2450	SR 2440	CUL-DE-SAC	0.48	Seal - Triple and Fog Seal	$44,587
2029	11	095-Watauga	Resurfacing	NC 105	End 3Lane Section	SR 1594	0.72	1.5" S9.5C	$329,470
2029	11	095-Watauga	Resurfacing	NC 105	AVERY CO	End of 3Lane Section	1.04	Mill 1.5" and 1.5" S9.5B	$841,980
2029	11	095-Watauga	Resurfacing	NC 105	Begin 3Lane Section	SR 1107	1.42	1.5" S9.5C	$899,710
2029	11	095-Watauga	Resurfacing	NC 105	Northern intersection of SR 1568	SR 1109	1.62	1.5" S9.5C	$741,310
2029	11	095-Watauga	Resurfacing	SR 1539	SR 1533 FLAT TOP	US 321S	1.35	1.5" S9.5C	$427,990
2029	11	095-Watauga	Resurfacing	SR 1581	SR 1539 EDMISTEN RD	EOM	0.86	1.5" S9.5B	$272,450
2029	11	095-Watauga	Preservation	SR 1102	Almost Heaven (NS)	SR 1390	2.16	Seal - Triple and Fog Seal	$182,646
2029	11	095-Watauga	Preservation	SR 1109	SR 1110	NC 105	2.64	Seal - Triple and Fog Seal	$247,526
2029	11	095-Watauga	Preservation	SR 1122	BEGIN PVMT	SR 1121	2.96	Seal - Triple and Fog Seal	$231,696

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	11	097-Wilkes	Resurfacing	NC 18	SR 1531/End 5-Lane Section	SR 1720/End 3-Lane Section	3.19	Mill 1.5" and 1.5" S9.5C	$2,245,760
2029	11	097-Wilkes	Resurfacing	NC 18	NC 18/NC 268 Split	SR 1531/End 5-Lane Section	1.92	Mill 1.5" and 1.5" S9.5B	$2,027,520
2029	11	097-Wilkes	Resurfacing	SR 1304	SR 1343	NC 16	2.32	1.5" S9.5B	$734,970
2029	11	097-Wilkes	Resurfacing	SR 1368	NC 16	SR 1317	1.46	1.5" S9.5B	$462,530
2029	11	097-Wilkes	Resurfacing	SR 1372	SR 1304	SR 1517	0.98	1.5" S9.5B	$379,456
2029	11	097-Wilkes	Resurfacing	SR 1455	SR 1304	SR 1317	0.83	1.5" S9.5C	$262,950
2029	11	097-Wilkes	Preservation	SR 1114	NC 18	Alexander Co Line	3.36	Seal - Triple and Fog Seal	$265,573
2029	11	097-Wilkes	Preservation	SR 1120	SR 1119	SR 1119	0.96	Seal - Triple and Fog Seal	$81,101
2029	11	097-Wilkes	Preservation	SR 1147	US 421	EOM	1.66	Seal - Triple and Fog Seal	$140,237
2029	11	097-Wilkes	Preservation	SR 1151	SR 1148	SR 1152	0.79	Seal - Triple and Fog Seal	$74,155
2029	11	097-Wilkes	Preservation	SR 1152	US 421	SR 1151	0.89	Seal - Triple and Fog Seal	$83,541
2029	11	097-Wilkes	Preservation	SR 1157	SR 1155	SR 1155	1.58	Seal - Triple and Fog Seal	$148,309
2029	11	097-Wilkes	Preservation	SR 1441	SR 1435	EOM	0.16	Seal - Triple and Fog Seal	$13,517
2029	11	097-Wilkes	Preservation	SR 1446	SR 1326	DE	0.07	Seal - Triple and Fog Seal	$5,257
2029	11	097-Wilkes	Preservation	SR 1629	SR 1520	EOM	0.18	Seal - Triple and Fog Seal	$13,517
2029	11	097-Wilkes	Preservation	SR 1760	SR 1714	EOM	0.40	Seal - Triple and Fog Seal	$30,037
2029	11	097-Wilkes	Preservation	SR 1797	SR 1712	EOM	0.26	Seal - Triple and Fog Seal	$19,524
2029	11	097-Wilkes	Preservation	SR 1800	SR 1760	EOM	0.30	Seal - Triple and Fog Seal	$22,528
2029	11	097-Wilkes	Preservation	SR 1948	SR 1946	SR 1945	1.48	Seal - Triple and Fog Seal	$125,030
2029	11	097-Wilkes	Preservation	SR 1964	SR 1965	EOM	0.20	Seal - Triple and Fog Seal	$15,019
2029	11	097-Wilkes	Preservation	SR 1969	SR 1966	EOM	0.70	Seal - Triple and Fog Seal	$59,136
2029	11	097-Wilkes	Preservation	SR 1974	SR 1973	DE	0.20	Seal - Triple and Fog Seal	$16,896
2029	11	097-Wilkes	Preservation	SR 1979	NC 268	DE	0.19	Seal - Triple and Fog Seal	$14,268
2029	11	097-Wilkes	Preservation	SR 1988	SR 1957	DE	0.60	Seal - Triple and Fog Seal	$56,320
2029	11	097-Wilkes	Preservation	SR 2016	SR 1924	DE	0.20	Seal - Triple and Fog Seal	$15,019
2029	11	097-Wilkes	Preservation	SR 2134	SR 2083	DE	0.07	Seal - Triple and Fog Seal	$5,257
2029	11	097-Wilkes	Preservation	SR 2136	SR 1957	SR 2137	0.05	Seal - Triple and Fog Seal	$4,224
2029	11	097-Wilkes	Preservation	SR 2137	SR 2136	EOM	0.17	Seal - Triple and Fog Seal	$14,362
2029	11	097-Wilkes	Preservation	SR 2154	SR 1002	EOM	0.17	Seal - Triple and Fog Seal	$14,362
2029	11	097-Wilkes	Preservation	SR 2323	SR 2576	SR 2318	1.39	Seal - Triple and Fog Seal	$117,427
2029	11	097-Wilkes	Preservation	SR 2325	Begin Pvmt	SR 2576	0.75	Seal - Triple and Fog Seal	$63,360
2029	11	097-Wilkes	Preservation	SR 2325	BEG 18' PVMT	SR 2344	2.07	Seal - Triple and Fog Seal	$174,874
2029	11	099-Yadkin	Resurfacing	NC 67	End 3-Lane Section	Begin Curb & Gutter	4.31	1.5" S9.5C	$1,972,260
2029	11	099-Yadkin	Resurfacing	NC 67	Western Project Limits at RoundABout	End 3-Lane Section	1.03	Mill 1.5" and 1.5" S9.5C	$688,860
2029	11	099-Yadkin	Resurfacing	NC 67	Begin Curb & Gutter	Howard Ave	0.44	Mill 1.5" and 1.5" S9.5C	$278,790
2029	11	099-Yadkin	Resurfacing	SR 1363	SR 1366	NC 67	1.85	Leveling and 1.5" S9.5B	$586,080
2029	11	099-Yadkin	Resurfacing	SR 1634	SR 1146	SR 1605	0.75	1.5" S9.5B	$316,800
2029	11	099-Yadkin	Preservation	SR 1107	Wilkes Co Line	SR 1100	1.20	Seal - Triple and Fog Seal	$112,640
2029	11	099-Yadkin	Preservation	SR 1371	SR 1370	SR 1368	1.07	Seal - Triple and Fog Seal	$100,437
2029	11	099-Yadkin	Preservation	SR 1372	US 601	SR 1370	1.51	Seal - Triple and Fog Seal	$141,739
2029	11	099-Yadkin	Preservation	SR 1576	SR 1573	SR 1573	2.34	Seal - Triple and Fog Seal	$219,648
2029	11	099-Yadkin	Preservation	SR 1587	SR 1583	DE	0.80	Seal - Triple and Fog Seal	$60,075
2029	11	099-Yadkin	Preservation	SR 1661	SR 1763	CulDeSac	0.21	Seal - Triple and Fog Seal	$17,741
2029	11	099-Yadkin	Preservation	SR 1703	SR 1605	DE	0.23	Seal - Triple and Fog Seal	$16,971
2029	11	099-Yadkin	Preservation	SR 1763	SR 1605	EOM	0.29	Seal - Triple and Fog Seal	$27,221
2029	11	099-Yadkin	Preservation	SR 1764	SR 1763	EOM	0.09	Seal - Triple and Fog Seal	$7,603
2029	11	099-Yadkin	Preservation	SR 1767	SR 1710	CDS	0.57	Seal - Triple and Fog Seal	$48,154
2029	12	002-Alexander	Resurfacing	SR 1142	SR 1141	SR 1141	0.99	1.5" S9.5B	$153,140
2029	12	002-Alexander	Resurfacing	SR 1156	SR 1144	NC 127	1.72	1.5" S9.5B	$266,290
2029	12	002-Alexander	Resurfacing	SR 1208	NC 127	NC 127	1.23	1.5" S9.5B	$190,340
2029	12	002-Alexander	Resurfacing	SR 1327	SR 1307	SR 1313	1.30	1.5" S9.5B	$202,120
2029	12	002-Alexander	Resurfacing	SR 1422	NC 90	SR 1419	1.87	1.5" S9.5B	$290,470
2029	12	002-Alexander	Resurfacing	SR 1605	Iredell County Line	SR 1610	5.98	1.5" S9.5C	$926,435
2029	12	002-Alexander	Resurfacing	SR 1610	NC 90	SR 1605	3.47	1.5" S9.5C	$581,046
2029	12	002-Alexander	Resurfacing	US 64	SR 1349 Bumgarner Ln	SR 1005 Old Mtn Rd	7.60	Mill 2.0" and 2.0" S9.5C	$2,464,619
2029	12	002-Alexander	Preservation	SR 1152	NC 127	SR 1150	4.05	Seal - Double and Fog Seal	$145,691
2029	12	002-Alexander	Preservation	SR 1153	NC 127	SR 1152	1.76	Seal - Double and Fog Seal	$63,324
2029	12	002-Alexander	Preservation	SR 1155	SR 1153	SR 1150	0.66	Seal - Double and Fog Seal	$23,652
2029	12	002-Alexander	Preservation	SR 1162	NC 127	End Maintenance	0.60	.75" S4.75A	$84,140

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	12	002-Alexander	Preservation	SR 1163	NC 127	End Maintenance	0.48	.75" S4.75A	$66,920
2029	12	002-Alexander	Preservation	SR 1199	SR 1144	End Maintenance	0.11	.75" S4.75A	$14,980
2029	12	002-Alexander	Preservation	SR 1203	SR 1144	SR 1144	0.34	.75" S4.75A	$47,880
2029	12	002-Alexander	Preservation	SR 1213	SR 1138	Dead End	0.56	.75" S4.75A	$78,680
2029	12	002-Alexander	Preservation	SR 1214	SR 1144	Dead End	0.13	.75" S4.75A	$18,200
2029	12	002-Alexander	Preservation	SR 1215	SR 1214	End Maintenance	0.23	.75" S4.75A	$32,200
2029	12	002-Alexander	Preservation	SR 1216	SR 1215	SR 1156	0.13	.75" S4.75A	$18,200
2029	12	002-Alexander	Preservation	SR 1217	SR 1215	SR 1156	0.15	.75" S4.75A	$21,000
2029	12	002-Alexander	Preservation	SR 1218	SR 1215	SR 1156	0.16	.75" S4.75A	$22,400
2029	12	002-Alexander	Preservation	SR 1262	SR 1199	End Maintenance	0.06	.75" S4.75A	$8,400
2029	12	002-Alexander	Preservation	SR 1264	SR 1150	End Maintenance	0.50	Seal - Double and Fog Seal	$18,036
2029	12	002-Alexander	Preservation	SR 1325	NC 16	SR 1356	0.26	.75" S4.75A	$36,400
2029	12	002-Alexander	Preservation	SR 1333	Pavement Change	SR 1311	0.62	Seal - Double and Fog Seal	$22,320
2029	12	002-Alexander	Preservation	SR 1353	SR 1365	End Maintenance	0.53	Seal - Double and Fog Seal	$19,080
2029	12	002-Alexander	Preservation	SR 1356	SR 1356	Dead End	0.18	.75" S4.75A	$25,760
2029	12	002-Alexander	Preservation	SR 1365	NC 16	NC 16	0.53	Seal - Double and Fog Seal	$19,080
2029	12	002-Alexander	Preservation	SR 1415	SR 1409	SR 1412	1.67	Seal - Double and Fog Seal	$60,012
2029	12	002-Alexander	Preservation	SR 1421	NC 90	End Maintenance	0.28	.75" S4.75A	$39,200
2029	12	002-Alexander	Preservation	SR 1624	SR 1605	End Maintenance	0.75	Seal - Double and Fog Seal	$27,144
2029	12	002-Alexander	Preservation	SR 1648	NC 90	SR 1612	0.18	Seal - Double and Fog Seal	$6,984
2029	12	002-Alexander	Preservation	SR 1665	SR 1682	End Maintenance	0.97	Seal - Double and Fog Seal	$34,740
2029	12	018-Catawba	Resurfacing	RMP 3571	321	70	0.34	Mill 1.5" and 1.5" S9.5C	$66,300
2029	12	018-Catawba	Resurfacing	RMP 3577	321	127	0.38	Mill 1.5" and 1.5" S9.5C	$74,100
2029	12	018-Catawba	Resurfacing	RMP 3578	127	321	0.24	Mill 1.5" and 1.5" S9.5C	$46,800
2029	12	018-Catawba	Resurfacing	RMP 3579	127	321	0.06	Mill 1.5" and 1.5" S9.5C	$11,700
2029	12	018-Catawba	Resurfacing	RMP 3582	321	SR 1144	0.29	Mill 1.5" and 1.5" S9.5C	$56,550
2029	12	018-Catawba	Resurfacing	RMP 3583	SR 1144	321	0.30	Mill 1.5" and 1.5" S9.5C	$58,500
2029	12	018-Catawba	Resurfacing	RMP 3586	321	NC 10	0.22	Mill 1.5" and 1.5" S9.5C	$42,900
2029	12	018-Catawba	Resurfacing	RMP 3587	NC 10	321	0.25	Mill 1.5" and 1.5" S9.5C	$48,750
2029	12	018-Catawba	Resurfacing	RMP 3592	321	SR 1005	0.31	Mill 1.5" and 1.5" S9.5C	$74,100
2029	12	018-Catawba	Resurfacing	RMP 3593	SR 1005	321	0.18	Mill 1.5" and 1.5" S9.5C	$35,100
2029	12	018-Catawba	Resurfacing	RMP 7154	I40	321	1.08	Mill 1.5" and 1.5" S9.5C	$210,600
2029	12	018-Catawba	Resurfacing	SR 1124	Pavement Joint	I 40	2.41	Full Depth Patching and 1.5" S9.5C	$469,950
2029	12	018-Catawba	Resurfacing	SR 1124	I 40	US 70	1.02	Full Depth Patching and 1.5" S9.5C	$198,900
2029	12	018-Catawba	Resurfacing	SR 1170	SR 1146	SR 1171	0.81	Full Depth Patching and 1.5" S9.5C	$157,950
2029	12	018-Catawba	Resurfacing	SR 1173	PVMT JOINT	SR 1171	0.61	Full Depth Patching and 1.5" S9.5B	$118,560
2029	12	018-Catawba	Resurfacing	SR 1254	SR 1005	SR 2941	0.31	Patching and 1.0" S9.5A	$60,450
2029	12	018-Catawba	Resurfacing	SR 1305	SR 1306	SR 1307	0.48	1.5" S9.5C	$93,600
2029	12	018-Catawba	Resurfacing	SR 1306	Burke Co	9th St NW	1.98	Mill 1.5" and 1.5" S9.5C	$386,100
2029	12	018-Catawba	Resurfacing	SR 1307	SR 1306	SR 1312	0.97	Patching and 1.5" S9.5A	$189,930
2029	12	018-Catawba	Resurfacing	SR 1310	SR 1339	SR 1307	0.22	Patching and 1.0" S9.5A	$42,900
2029	12	018-Catawba	Resurfacing	SR 1311	SR 1307	SR 1347	0.21	Full Depth Patching and 1.25" S9.5A	$40,560
2029	12	018-Catawba	Resurfacing	SR 1312	SR 1307	END MAINT	0.09	Full Depth Patching and 1.5" S9.5B	$16,575
2029	12	018-Catawba	Resurfacing	SR 1317	NC 127	MP 0.72	0.72	Full Depth Patching and 1.5" S9.5B	$140,400
2029	12	018-Catawba	Resurfacing	SR 1318	SR 1352	NC 127	0.49	Full Depth Patching and 1.5" S9.5B	$95,355
2029	12	018-Catawba	Resurfacing	SR 1339	SR 1311	SR 1310	0.18	Patching and 1.0" S9.5A	$35,100
2029	12	018-Catawba	Resurfacing	SR 1347	SR 1311	END MAINT	0.09	Full Depth Patching and 1.25" S9.5A	$18,330
2029	12	018-Catawba	Resurfacing	SR 1350	SR 1310	END MAINT	0.08	Patching and 1.0" S9.5A	$14,625
2029	12	018-Catawba	Resurfacing	SR 1372	19TH AVE NW	DE	0.14	Full Depth Patching and 1.5" S9.5B	$26,325
2029	12	018-Catawba	Resurfacing	SR 1471	SR 1005	END MAINT	0.32	Full Depth Patching and 1.5" S9.5C	$61,425
2029	12	018-Catawba	Resurfacing	SR 1471	END C & G	DEAD END	0.19	Mill 1.5" and 1.5" S9.5C	$36,075
2029	12	018-Catawba	Resurfacing	SR 1472	SR 1468	DEAD END	0.70	Full Depth Patching and 1.5" S9.5C	$136,500
2029	12	018-Catawba	Resurfacing	SR 1472	SR 1460	END MAINT	0.70	Patching and 1.0" S9.5A	$136,500
2029	12	018-Catawba	Resurfacing	SR 1486	SR 1517	SR 1453	0.34	1.5" S9.5B	$66,690
2029	12	018-Catawba	Resurfacing	SR 1502	SR 1400	SR 1690	0.46	Full Depth Patching and 1.5" S9.5B	$89,700
2029	12	018-Catawba	Resurfacing	SR 1514	SR 1453	END MAINT	0.18	1.25" SF9.5A	$35,685
2029	12	018-Catawba	Resurfacing	SR 1560	SR 1505	SR 1484	0.27	Full Depth Patching and 1.25" S9.5A	$52,065
2029	12	018-Catawba	Resurfacing	SR 1600	SR 1486	END MAINT	0.69	1.25" SF9.5A	$134,355
2029	12	018-Catawba	Resurfacing	SR 1633	SR 1453	PVMT CHANGE	0.39	Full Depth Patching and 1.5" S9.5B	$76,830

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	12	018-Catawba	Resurfacing	SR 1635	SR 1504	END MAINT	0.07	Full Depth Patching and 1.25" S9.5A	$13,260
2029	12	018-Catawba	Resurfacing	SR 1644	SR 1486	SR 2243	0.37	1.25" SF9.5A	$72,930
2029	12	018-Catawba	Resurfacing	SR 1656	SR 1517	END MAINT	0.37	1.25" SF9.5A	$72,735
2029	12	018-Catawba	Resurfacing	SR 1660	SR 1560	CUL DE SAC	0.18	Full Depth Patching and 1.25" S9.5A	$35,880
2029	12	018-Catawba	Resurfacing	SR 1674	SR 1401	END MAINT	0.30	Full Depth Patching and 1.25" S9.5A	$59,280
2029	12	018-Catawba	Resurfacing	SR 1678	NC 127	END MAINT	0.11	Full Depth Patching and 1.25" S9.5A	$21,450
2029	12	018-Catawba	Resurfacing	SR 1691	SR 1690	END MAINT	0.10	Full Depth Patching and 1.25" S9.5A	$19,695
2029	12	018-Catawba	Resurfacing	SR 2002	SR 2003	DEAD END	0.37	Full Depth Patching and 1.25" S9.5B	$71,175
2029	12	018-Catawba	Resurfacing	SR 2013	SR 2012	NC 10	2.89	Full Depth Patching and 1.5" S9.5C	$562,770
2029	12	018-Catawba	Resurfacing	SR 2014	321 Buss	SR 2013	1.55	Full Depth Patching and 1.5" S9.5C	$302,250
2029	12	018-Catawba	Resurfacing	SR 2034	SR 1008	Dead End	0.19	Full Depth Patching and 1.5" S9.5C	$36,855
2029	12	018-Catawba	Resurfacing	SR 2036	Lincoln County	SR 2029	1.20	Full Depth Patching and 1.5" S9.5C	$234,000
2029	12	018-Catawba	Resurfacing	SR 2225	SR 1438	END MAINT	0.16	Full Depth Patching and 1.25" S9.5A	$31,785
2029	12	018-Catawba	Resurfacing	SR 2229	SR 1618	END MAINT	0.09	.75" S4.75A	$16,575
2029	12	018-Catawba	Resurfacing	SR 2234	SR 1512	SR 2235	0.15	1.25" SF9.5A	$28,860
2029	12	018-Catawba	Resurfacing	SR 2238	SR 2234	SR 2239	0.12	1.25" SF9.5A	$23,400
2029	12	018-Catawba	Resurfacing	SR 2241	SR 1453	END MAINT	0.19	1.25" SF9.5A	$36,660
2029	12	018-Catawba	Resurfacing	SR 2321	NC 16	SR 2357	0.10	Patching and 1.0" S9.5A	$19,305
2029	12	018-Catawba	Resurfacing	SR 2324	SR 2323	DEAD END	0.13	Patching and 1.0" S9.5A	$24,570
2029	12	018-Catawba	Resurfacing	SR 2325	SR 2323	DEAD END	0.13	Patching and 1.0" S9.5A	$25,350
2029	12	018-Catawba	Resurfacing	SR 2329	SR 1511	END MAINT	0.15	Full Depth Patching and 1.25" S9.5A	$28,275
2029	12	018-Catawba	Resurfacing	SR 2347	SR 1441	DEAD END	0.19	Full Depth Patching and 1.5" S9.5C	$36,465
2029	12	018-Catawba	Resurfacing	SR 2390	SR 1007	SR 2347	0.14	Full Depth Patching and 1.5" S9.5C	$27,300
2029	12	018-Catawba	Resurfacing	SR 2903	BURKE CO	END MAINT	0.44	Patching and 1.0" S9.5A	$85,800
2029	12	018-Catawba	Resurfacing	SR 2904	SR 2903	END MAINT	0.15	Patching and 1.0" S9.5A	$29,250
2029	12	018-Catawba	Resurfacing	SR 2915	SR 2014	SR 1209	0.17	Full Depth Patching and 1.5" S9.5C	$32,175
2029	12	018-Catawba	Resurfacing	SR 2932	SR 1146	SR 1005	1.28	Mill 1.5" and 1.5" S9.5C	$249,600
2029	12	018-Catawba	Resurfacing	SR 2938	SR 1008	End Maint	0.15	Full Depth Patching and 1.5" S9.5C	$29,250
2029	12	018-Catawba	Resurfacing	SR 2941	SR 1254	Dead End	0.20	Patching and 1.0" S9.5A	$39,000
2029	12	018-Catawba	Resurfacing	SR 3027	SR 1512	CUL DE SAC	0.20	1.25" SF9.5A	$38,805
2029	12	018-Catawba	Resurfacing	SR 3028	SR 1512	CUL DE SAC	0.03	1.25" SF9.5A	$6,630
2029	12	018-Catawba	Resurfacing	US 321	US 70	Lincoln Co	13.79	Mill 1.5" and 1.5" S9.5C	$2,688,075
2029	12	018-Catawba	Preservation	SR 1134	SR 1131	Dead End	0.75	Microsurface	$40,312
2029	12	018-Catawba	Preservation	SR 1858	SR 1855	SR 1810	5.48	Microsurface	$294,550
2029	12	018-Catawba	Preservation	SR 1859	SR 1858	SR 1860	1.08	Microsurface	$58,050
2029	12	018-Catawba	Preservation	SR 1860	SR 1003	SR 1855	1.92	Microsurface	$103,200
2029	12	018-Catawba	Preservation	SR 1866	SR 1874	SR 1003	1.27	Microsurface	$68,262
2029	12	018-Catawba	Preservation	SR 1867	SR 1874	SR 1855	1.49	Microsurface	$80,087
2029	12	018-Catawba	Preservation	SR 2004	SR 2003	Lincoln Co	1.35	Microsurface	$72,562
2029	12	018-Catawba	Preservation	SR 2005	SR 2004	End Maint	0.91	Microsurface	$48,912
2029	12	018-Catawba	Preservation	SR 2010	US 321 Bus	SR 2007	1.13	Microsurface	$60,737
2029	12	018-Catawba	Preservation	SR 2021	SR 1008	SR 1005	2.77	Microsurface	$148,887
2029	12	018-Catawba	Preservation	SR 2022	SR 2021	Lincoln Co	1.63	Microsurface	$87,612
2029	12	018-Catawba	Preservation	SR 2084	SR 2024	Dead End	0.61	Microsurface	$32,787
2029	12	023-Cleveland	Resurfacing	40001123	NC 150	SR 1151	2.42	1.5" S9.5B	$387,626
2029	12	023-Cleveland	Resurfacing	40001159	NC 150	SR 1161	2.82	1.5" S9.5B	$428,145
2029	12	023-Cleveland	Resurfacing	40001162	US 74	SR 1161	0.11	1.5" S9.5B	$11,143
2029	12	023-Cleveland	Resurfacing	40001547	NC 10	Burke co line	3.45	1.5" S9.5B	$559,487
2029	12	023-Cleveland	Resurfacing	40001612	NC 18	SR 1643	1.42	1.5" S9.5B	$352,841
2029	12	023-Cleveland	Resurfacing	40001664	NC 182	SR 1665	1.24	1.5" S9.5B	$334,608
2029	12	023-Cleveland	Resurfacing	40001802	SR 1005	NC 182	1.03	1.5" S9.5B	$313,335
2029	12	023-Cleveland	Resurfacing	40002041	SR 2319	EOP	0.64	1.5" S9.5B	$64,830
2029	12	023-Cleveland	Resurfacing	40002042	SR 2041	DE	0.68	1.5" S9.5B	$69,894
2029	12	023-Cleveland	Resurfacing	40002212	SR 2226	NC 226	1.86	1.5" S9.5B	$330,900
2029	12	023-Cleveland	Resurfacing	40002226	SR 2308	NC 198	2.58	1.5" S9.5B	$403,834
2029	12	023-Cleveland	Resurfacing	40002247	SR 2246	SR 2245	0.88	1.5" S9.5B	$231,629
2029	12	023-Cleveland	Resurfacing	NC 226	SR 1510+.060	Rutherford Co	5.39	1.5" S9.5B	$1,776,611
2029	12	023-Cleveland	Resurfacing	SR 1538	SR 1536	SR 1543	2.66	1.5" S9.5B	$513,304
2029	12	023-Cleveland	Resurfacing	SR 1543	NC 10	SR 1538	2.19	1.5" S9.5B	$459,536

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	12	023-Cleveland	Resurfacing	SR 1658	NC 182	SR 1657	0.94	1.0" S9.5B	$221,488
2029	12	023-Cleveland	Resurfacing	SR 1658	NC 182	SR 1657	0.94	1.0" S9.5B	$288,000
2029	12	023-Cleveland	Resurfacing	SR 2675	SR 2008	DEAD END	0.69	1.5" S9.5B	$79,279
2029	12	023-Cleveland	Resurfacing	US 29	BS00092	US 29 South	0.59	1.5" S9.5C	$222,994
2029	12	023-Cleveland	Resurfacing	US 29	I -85 South	SR 2238	2.00	1.5" S9.5C	$724,402
2029	12	023-Cleveland	Resurfacing	US 29	US 29 South	SR 2276	2.01	1.5" S9.5C	$726,116
2029	12	023-Cleveland	Preservation	40001363	NC 182	NC 226	1.40	Seal - Double	$60,397
2029	12	023-Cleveland	Preservation	S.R. 1654	Lincoln Co	NC 18	2.65	Seal - Double	$123,500
2029	12	023-Cleveland	Preservation	S.R. 1657	NC 182	SR 1654	1.41	Seal - Double	$80,500
2029	12	023-Cleveland	Preservation	S.R. 2289	NC 161	NC 161	2.32	.75" S4.75A	$187,833
2029	12	023-Cleveland	Preservation	SR 1325	SR 1351	1323	4.66	Seal - Double	$176,600
2029	12	023-Cleveland	Preservation	SR 1605	1607	NC 18	0.38	Seal - Double	$19,000
2029	12	023-Cleveland	Preservation	SR 2276	US 29	SR 2238	1.18	.75" S4.75A	$101,833
2029	12	023-Cleveland	Preservation	SR 2277	SR 2276	DE	0.19	.75" S4.75A	$27,583
2029	12	023-Cleveland	Preservation	SR 2287	SR 2286	DE	0.92	.75" S4.75A	$82,333
2029	12	023-Cleveland	Preservation	SR 2354	NC 161	DE	0.40	.75" S4.75A	$56,149
2029	12	023-Cleveland	Preservation	SR 2443	SR 2289	EOM	0.89	.75" S4.75A	$80,083
2029	12	036-Gaston	Resurfacing	NC 274	FIRST ST	bridge	4.70	1.5" S9.5B	$850,000
2029	12	036-Gaston	Resurfacing	SR 1106	SR 1126	SR 1103	1.28	1.5" S9.5B	$227,500
2029	12	036-Gaston	Resurfacing	SR 1255	1136	US 321	1.50	1.5" S9.5B	$300,000
2029	12	036-Gaston	Resurfacing	SR 1255	SR 1136	US 321	1.52	1.5" S9.5B	$300,000
2029	12	036-Gaston	Resurfacing	SR 1304	NC 161	SR1302	0.52	1.5" S9.5A	$91,000
2029	12	036-Gaston	Resurfacing	SR 1339	US 321	US 29/74	1.24	1.5" S9.5B	$225,120
2029	12	036-Gaston	Resurfacing	SR 1623	SR 1622	SR 1620	0.45	1.5" S9.5C	$66,785
2029	12	036-Gaston	Resurfacing	SR 1628	SR 1622	NC 150	0.61	1.5" S9.5C	$82,900
2029	12	036-Gaston	Resurfacing	SR 1638	SR 1644	SR 1642	0.77	1.5" S9.5B	$134,575
2029	12	036-Gaston	Resurfacing	SR 1820	NC 27	SR 1902	2.60	1.5" S9.5C and Widen	$455,000
2029	12	036-Gaston	Resurfacing	SR 1820	SR 1902	SR 1905	3.87	1.5" S9.5B	$691,000
2029	12	036-Gaston	Resurfacing	SR 1925	NC 27	END MAINT	0.10	1.5" S9.5B	$12,000
2029	12	036-Gaston	Resurfacing	SR 1939	SR 273	SR 1974 + .121MILES	0.76	1.5" S9.5B	$133,000
2029	12	036-Gaston	Resurfacing	SR 2265	NC 279	D END	0.90	1.5" S9.5B	$116,100
2029	12	036-Gaston	Resurfacing	SR 2278	BRIDGE	NC 279	1.73	1.5" S9.5B	$300,000
2029	12	036-Gaston	Resurfacing	SR 2278	NC 7	BRIDGE	1.90	1.5" S9.5B	$275,000
2029	12	036-Gaston	Resurfacing	SR 2644	SR 2427	SR 2426	0.54	1.5" S9.5B	$75,000
2029	12	036-Gaston	Resurfacing	SR 2742	SR 2430	SR 2430	0.10	1.5" S9.5B	$7,500
2029	12	036-Gaston	Resurfacing	SR 3604	SR 2416	CDS	0.16	1.5" S9.5B	$12,300
2029	12	036-Gaston	Resurfacing	SR1638	SR1642	C.LIMITS	0.99	1.5" S9.5B	$135,500
2029	12	036-Gaston	Resurfacing	SR2339	SR2329	US 29/74	0.96	1.5" S9.5B	$130,000
2029	12	036-Gaston	Resurfacing	SR2798	NC273	CHNG. PVT	0.68	1.5" S9.5B	$94,805
2029	12	036-Gaston	Resurfacing	SR3018	SR2523	D.END	0.50	1.5" S9.5B	$120,750
2029	12	036-Gaston	Resurfacing	US 321	LIN CO	CITY LIMITS	8.10	1.5" S9.5B	$1,200,000
2029	12	036-Gaston	Resurfacing	US 321	SR 1136	SC LINE	3.71	1.5" S9.5C	$1,100,000
2029	12	036-Gaston	Resurfacing	US 321	CITY LIMITS	LIN CO	8.39	1.5" S9.5B	$1,300,000
2029	12	036-Gaston	Preservation	SR 2889	SR2435	D. END	0.13	1.0" S9.5B	$10,000
2029	12	036-Gaston	Preservation	SR 1100	SR 1102	S.C.	1.10	Microsurface	$74,500
2029	12	036-Gaston	Preservation	SR 1101`	SR 1103	S.C.	0.25	Microsurface	$15,500
2029	12	036-Gaston	Preservation	SR 1112	SR 1126	SR 1130	2.25	Microsurface	$123,750
2029	12	036-Gaston	Preservation	SR 1219	SR 3126	SR 1113	0.14	1.0" S9.5B	$16,100
2029	12	036-Gaston	Preservation	SR 1241	SR 1125	D END	0.64	Microsurface	$39,200
2029	12	036-Gaston	Preservation	SR 1447	SR 1446	SR 1443	1.01	Microsurface	$44,520
2029	12	036-Gaston	Preservation	SR 1450	SR1443	DE	0.80	Microsurface	$36,100
2029	12	036-Gaston	Preservation	SR 1454	SR 1453	SR 1448	0.45	Microsurface	$22,500
2029	12	036-Gaston	Preservation	SR 1459	NC274	D.END	0.48	Microsurface	$27,000
2029	12	036-Gaston	Preservation	SR 1475	SR 1446	CDS	0.40	1.0" S9.5B	$41,000
2029	12	036-Gaston	Preservation	SR 1476	SR 1446	CDS	0.20	1.0" S9.5B	$22,300
2029	12	036-Gaston	Preservation	SR 1536	SR 1401	CDS	0.28	1.0" S9.5B	$28,200
2029	12	036-Gaston	Preservation	SR 1537	SR 1536	CDS	0.33	1.0" S9.5B	$32,000
2029	12	036-Gaston	Preservation	SR 1539	SR 1446	D END	0.32	1.0" S9.5B	$34,100
2029	12	036-Gaston	Preservation	SR 1542	SR 1541	CDS	0.18	1.0" S9.5B	$18,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	12	036-Gaston	Preservation	SR 1765	SR 1605	CDS	0.27	1.0" S9.5B	$20,300
2029	12	036-Gaston	Preservation	SR 1822	SR 1820	SR 1001	2.12	Microsurface	$124,100
2029	12	036-Gaston	Preservation	SR 1861	SR 1827	SR 1831	0.30	Microsurface	$13,000
2029	12	036-Gaston	Preservation	SR 1884	SR 1805	SR 1805	0.42	1.0" S9.5B	$25,450
2029	12	036-Gaston	Preservation	SR 2262	SR 2259	SR 2356	1.04	1.5" S9.5B	$148,200
2029	12	036-Gaston	Preservation	SR 2641	SR 2423	D END	0.85	Microsurface	$38,200
2029	12	036-Gaston	Preservation	SR 2644	SR 2427	SR 2426	0.54	Microsurface	$20,500
2029	12	036-Gaston	Preservation	SR 2664	SR 2439	SR 2710	0.36	1.0" S9.5B	$26,850
2029	12	036-Gaston	Preservation	SR 2710	SR 2664	D END	0.35	1.0" S9.5B	$26,000
2029	12	036-Gaston	Preservation	SR 2711	SR 2715+.167	D END	0.44	1.0" S9.5B	$33,000
2029	12	036-Gaston	Preservation	SR 2849	NC 279+0.24 MILES	D. END	1.36	Microsurface	$56,000
2029	12	036-Gaston	Preservation	SR 2880	SR 2715	D END	0.16	1.0" S9.5B	$12,100
2029	12	036-Gaston	Preservation	SR 2881	NC 274	D END	0.25	1.0" S9.5B	$21,000
2029	12	036-Gaston	Preservation	SR 2903	BURTON HILLS	D END	0.16	1.0" S9.5B	$12,200
2029	12	036-Gaston	Preservation	SR 2910	NC 7	SR 2909	0.08	Microsurface	$3,200
2029	12	036-Gaston	Preservation	SR1118	US74B	SR1188	0.72	Microsurface	$37,200
2029	12	036-Gaston	Preservation	SR1306	SR1309	DE	0.50	Microsurface	$27,000
2029	12	036-Gaston	Preservation	SR1412	NC216	NC274	1.85	Microsurface	$86,200
2029	12	036-Gaston	Preservation	SR1413	NC216	SR1412	1.12	Microsurface	$57,500
2029	12	036-Gaston	Preservation	SR1415	NC274	CLEV CO	1.31	Microsurface	$72,200
2029	12	036-Gaston	Preservation	SR1481	SR 1459	D END	0.26	Microsurface	$14,000
2029	12	036-Gaston	Preservation	SR1541	SR1448	CDS	0.37	1.0" S9.5B	$37,000
2029	12	036-Gaston	Preservation	SR1543	SR1541	CDS	0.08	1.0" S9.5B	$7,500
2029	12	049-Iredell	Resurfacing	SR 1004	Catawba County	SR 1005	4.17	1.5" S9.5C	$850,000
2029	12	049-Iredell	Resurfacing	SR 1153	NC 152	SR 1150	2.23	1.5" S9.5C	$501,750
2029	12	049-Iredell	Resurfacing	SR 1333	US 70	SR 1004	5.03	1.5" S9.5C	$1,131,750
2029	12	049-Iredell	Resurfacing	SR 1367	SR 1368	DE	0.69	1.0" S9.5B	$155,250
2029	12	049-Iredell	Resurfacing	SR 1368	SR 1005	SR 1333	2.29	1.5" S9.5C	$515,250
2029	12	049-Iredell	Resurfacing	SR 1369	Maint Limit	SR 1005	4.18	1.5" S9.5C	$938,250
2029	12	049-Iredell	Resurfacing	SR 1640	NC 115	SR 1420	1.71	1.5" S9.5C	$384,750
2029	12	049-Iredell	Resurfacing	SR 1845	NC 901	US 21	5.78	1.5" S9.5C	$1,300,500
2029	12	049-Iredell	Resurfacing	SR 1981	SR 1845	End Maint.	0.62	1.5" S9.5C	$139,500
2029	12	049-Iredell	Resurfacing	SR 2145	SR 2158	SR2143	2.06	1.5" S9.5C	$463,500
2029	12	049-Iredell	Resurfacing	SR 2150	SR 2145	End Maint	0.65	1.5" S9.5C	$146,250
2029	12	049-Iredell	Resurfacing	SR 2308	SR 2309	SR 2638	4.18	1.5" S9.5C	$773,300
2029	12	049-Iredell	Resurfacing	SR 2309	SR 2308	SR 2305	2.39	1.5" S9.5C	$442,150
2029	12	049-Iredell	Resurfacing	SR 2315	US 64	Dead End	0.76	1.5" S9.5C	$171,000
2029	12	049-Iredell	Resurfacing	SR 2379	SR 1001	SR 2383	3.16	1.5" S9.5C	$711,000
2029	12	049-Iredell	Resurfacing	SR 2994	SR 2905	End Maint.	0.32	1.0" S9.5B	$72,000
2029	12	049-Iredell	Resurfacing	SR1331	SR 1402	End Maint.	0.95	1.0" S9.5B	$213,750
2029	12	049-Iredell	Resurfacing	SR1747	SR 1005	End Maint.	0.59	1.0" S9.5B	$132,750
2029	12	049-Iredell	Resurfacing	SR2905	SR 1138	End Maint.	0.54	1.0" S9.5B	$121,500
2029	12	049-Iredell	Resurfacing	US 70	Divided	Rowan CL	4.02	1.5" S9.5C	$904,500
2029	12	049-Iredell	Preservation	SR 1572	SR 1903	NC 115	2.42	Seal - Double	$108,900
2029	12	049-Iredell	Preservation	SR 1573	SR 1572	SR 1561	0.76	Seal - Double	$34,650
2029	12	049-Iredell	Preservation	SR 1575	SR 1571	SR 1561	1.84	Seal - Double	$83,250
2029	12	049-Iredell	Preservation	SR 1839	US 21	DE	1.28	Seal - Double and Fog Seal	$57,600
2029	12	049-Iredell	Preservation	SR 1846	SR 1845	NC 901	1.42	Seal - Double	$63,900
2029	12	049-Iredell	Preservation	SR 1882	SR 1896	SR 1937	1.03	Seal - Double	$46,350
2029	12	049-Iredell	Preservation	SR 1896	SR 1892	NC 115	6.65	Seal - Double	$299,250
2029	12	049-Iredell	Preservation	SR 1937	SR 1892	SR 1896	1.72	Seal - Double	$77,400
2029	12	049-Iredell	Preservation	SR 1982	SR 1849	SR 1845	1.62	Seal - Double	$72,900
2029	12	049-Iredell	Preservation	SR 2115	US 21	SR 2105	3.48	Seal - Double and Fog Seal	$156,600
2029	12	049-Iredell	Preservation	SR 2117	SR 2115	SR 2120	1.80	Seal - Double and Fog Seal	$81,000
2029	12	049-Iredell	Preservation	SR 2125	US 21	SR 2126	3.68	Seal - Double and Fog Seal	$165,000
2029	12	055-Lincoln	Resurfacing	RMP 5206	27	321	0.20	Mill 1.5" and 1.5" S9.5C	$39,000
2029	12	055-Lincoln	Resurfacing	RMP 5207	321	27	0.26	Mill 1.5" and 1.5" S9.5C	$50,700
2029	12	055-Lincoln	Resurfacing	SR 1274	Catawba Co	SR 1279	0.40	Full Depth Patching and 1.5" S9.5C	$54,600
2029	12	055-Lincoln	Resurfacing	SR 1276	SR 1274	SR 1276	1.08	Full Depth Patching and 1.5" S9.5C	$214,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	12	055-Lincoln	Resurfacing	SR 1279	321 Bus	SR 1279	2.18	Full Depth Patching and 1.5" S9.5C	$425,100
2029	12	055-Lincoln	Resurfacing	SR 1339	US 321 Bus	SR 1003	1.61	Full Depth Patching and 1.5" S9.5C	$313,950
2029	12	055-Lincoln	Resurfacing	SR 1355	NC 73	SR 1354	3.56	Full Depth Patching and 1.5" S9.5C	$693,420
2029	12	055-Lincoln	Resurfacing	SR 1371	SR 1349	CATAWBA CO	1.15	Full Depth Patching and 1.5" S9.5B	$223,665
2029	12	055-Lincoln	Resurfacing	SR 1377	SR 1376	CUL DE SAC	1.22	Full Depth Patching and 1.5" S9.5B	$237,900
2029	12	055-Lincoln	Resurfacing	SR 1642	SR 1619	SR 1755	0.33	1.0" S9.5B	$63,375
2029	12	055-Lincoln	Resurfacing	SR 1656	SR 1456	SR 1456	0.46	1.0" S9.5B	$89,700
2029	12	055-Lincoln	Resurfacing	SR 1754	SR 1389	SR 1642	0.83	1.0" S9.5B	$160,875
2029	12	055-Lincoln	Resurfacing	SR 1755	SR 1754	SR 1642	0.09	1.0" S9.5B	$17,550
2029	12	055-Lincoln	Resurfacing	SR 1938	SR 1377	Cul-de-sac	0.16	Mill 1.5" and 1.5" S9.5C	$31,200
2029	12	055-Lincoln	Resurfacing	SR 1957	NC 16 BRIDGE	E O M	0.36	Patching and 1.0" S9.5A	$69,615
2029	12	055-Lincoln	Resurfacing	SR 1958	SR 1957	END MAINT	0.34	Patching and 1.0" S9.5A	$66,105
2029	12	055-Lincoln	Resurfacing	SR 2016	SR 2015	CUL-DE-SAC	0.18	Mill 1.5" and 1.5" S9.5C	$35,100
2029	12	055-Lincoln	Resurfacing	SR 2068	SR 2016	Cul-de-sac	0.19	Mill 1.5" and 1.5" S9.5C	$36,855
2029	12	055-Lincoln	Resurfacing	SR 2185	SR 1387	Cul-de-sac	0.25	Full Depth Patching and 1.5" S9.5C	$48,750
2029	12	055-Lincoln	Resurfacing	SR 2193	SR 2192	Dead End	0.22	Full Depth Patching and 1.5" S9.5C	$42,900
2029	12	055-Lincoln	Resurfacing	US 321	Gaston Co	NC 27	11.07	Mill 1.5" and 1.5" S9.5C	$2,158,650
2029	12	055-Lincoln	Preservation	SR 1100	NC 18	Burke Co	1.41	Seal - Double and Fog Seal	$57,787
2029	12	055-Lincoln	Preservation	SR 1101	Catawba Co	SR 1100	0.30	Microsurface	$16,125
2029	12	055-Lincoln	Preservation	SR 1102	SR 1100	Cleveland Co	0.11	Microsurface	$5,912
2029	12	055-Lincoln	Preservation	SR 1105	NC 10	Catawba Co	0.63	Seal - Double and Fog Seal	$33,862
2029	12	055-Lincoln	Preservation	SR 1135	274	SR 1139	1.57	Microsurface	$84,387
2029	12	055-Lincoln	Preservation	SR 1150	182	SR 1140	2.09	Microsurface	$112,337
2029	12	055-Lincoln	Preservation	SR 1158	NC 182	GASTON CO	1.35	Microsurface	$72,293
2029	12	055-Lincoln	Preservation	SR 1162	SR 1140	DEAD END	1.10	Microsurface	$59,125
2029	12	055-Lincoln	Preservation	SR 1445	SR 1003	DEAD END	0.72	.75" S4.75A	$80,080
2029	12	055-Lincoln	Preservation	SR 1464	SR 1005	Dead End	0.23	.75" S4.75A	$25,760
2029	12	055-Lincoln	Preservation	SR 1508	SR 1003	SR 1673	0.34	.75" S4.75A	$38,528
2029	12	055-Lincoln	Preservation	SR 1562	US 321 Bus	Gaston Co	0.54	Seal - Double and Fog Seal	$22,000
2029	12	055-Lincoln	Preservation	SR 1673	SR 1003	SR 1673	0.52	.75" S4.75A	$58,576
2029	12	055-Lincoln	Preservation	SR 1690	SR 1114	Dead End	0.70	Microsurface	$37,625
2029	12	055-Lincoln	Preservation	SR 1790	SR 1366	SR 1791	0.38	.75" S4.75A	$42,224
2029	12	055-Lincoln	Preservation	SR 1791	SR 1790	End Maint	0.30	.75" S4.75A	$33,488
2029	12	055-Lincoln	Preservation	SR 1940	SR 1127	SR 1147	1.65	Seal - Double and Fog Seal	$184,800
2029	13	011-Buncombe	Resurfacing	SR 1003 (PAINT FORK ROAD)	SR 2117 (HARWOOD ROAD)	BRIDGE	0.79	Full Depth Patching and 1.5" S9.5C	$764,000
2029	13	011-Buncombe	Resurfacing	SR 1003 (REEMS CREEK ROAD)	SR 2109 (OX CREEK ROAD)	SR 2115 (BLACKBERRY INN ROAD)	2.39	Full Depth Patching and 1.5" S9.5C	$490,200
2029	13	011-Buncombe	Resurfacing	SR 1679 (LOOKOUT ROAD)	BEGIN DOT MAINTENANCE	CITY LIMIT	0.29	Full Depth Patching and 1.0" S4.75A	$50,000
2029	13	011-Buncombe	Resurfacing	SR 1683 (CAMPUS DRIVE)	SR 1781 BROADWAY STREET	P .46 (END OF STATE MAINTENANC	0.45	Mill 1.5" and 1.5" S9.5C	$99,000
2029	13	011-Buncombe	Resurfacing	SR 1711 (OLD WEAVERVILLE ROAD)	BEGIN MAINTENANCE	END OF MAINTENANCE	0.58	Full Depth Patching and 1.5" S9.5C	$101,500
2029	13	011-Buncombe	Resurfacing	SR 1781 (BROADWAY STREET)	BEG DIVIDED HIGHWAY	SR 1683 (CAMPUS DRIVE)+ .1 MILE	0.63	Full Depth Patching and 1.5" S9.5B	$129,000
2029	13	011-Buncombe	Resurfacing	SR 2042 (CHUNNS COVE ROAD)	SR 2208 (CHUNNS COVE ROAD)	END OF MAINTENANCE	0.75	Full Depth Patching and 1.5" S9.5C	$161,000
2029	13	011-Buncombe	Resurfacing	SR 2053 (BEAVERDAM ROAD)	SR 2230 (ELK MOUNTAIN SENIC HIGHWAY)	ELK MOUNTAIN SENIC HIGHWAY)+	0.44	Full Depth Patching and 1.5" S9.5C	$93,000
2029	13	011-Buncombe	Resurfacing	SR 2053 (BEAVERDAM ROAD)	ELK MOUNTAIN SENIC HIGHWAY	SR 2070 (LYNN COVE ROAD)	1.96	Full Depth Patching and 1.5" S9.5C	$385,995
2029	13	011-Buncombe	Resurfacing	SR 2053 (WEBB COVE ROAD)	SR 2070 (LYNN COVE ROAD)	END OF PAVEMENT	0.91	Full Depth Patching and 1.5" S9.5C	$168,270
2029	13	011-Buncombe	Resurfacing	SR 2070 (LYNN COVE ROAD)	SR 2053 (WEBB COVE ROAD)	END OF MAINTENANCE	1.10	Full Depth Patching and 1.5" S9.5C	$185,000
2029	13	011-Buncombe	Resurfacing	SR 2095 (BOYDS CHAPEL ROAD)	SR 2094 (STONY KNOB ROAD)	END OF MAINTENANCE	0.29	Full Depth Patching and 1.5" S9.5C	$55,000
2029	13	011-Buncombe	Resurfacing	SR 2097 (INDIAN LANE)	SR 2094 (STONY KNOB ROAD)	END OF MAINTENANCE	0.41	Full Depth Patching and 1.0" S4.75A	$61,500
2029	13	011-Buncombe	Resurfacing	SR 2123 (HAMBURG MOUNTAIN ROAD)	SR 1003 (REEMS CREEK ROAD)	SR 2124 (DOGWOOD DRIVE)	1.44	Full Depth Patching and 1.5" S9.5C	$269,979
2029	13	011-Buncombe	Resurfacing	SR 2124 (DOGWOOD DRIVE)	SR 1003 (REEMS CREEK ROAD)	2123 (HAMBURG MOUNTAIN ROA	0.89	Full Depth Patching and 1.5" S9.5C	$179,995
2029	13	011-Buncombe	Resurfacing	SR 2127 (SOUTH MAIN STREET)	US 19	SR 1003 (REEMS CREEK ROAD)	0.74	Full Depth Patching and 1.5" S9.5C	$148,000
2029	13	011-Buncombe	Resurfacing	SR 2130 (DULA SPRINGS ROAD)	US 19 BUSINESS	SR 2131 (BRITTEN COVE ROAD)	1.95	Full Depth Patching and 1.25" S9.5B	$399,989
2029	13	011-Buncombe	Resurfacing	SR 2171 (POVERTY BRANCH ROAD)	BEGIN MAINTENANCE	NC 197	2.96	Full Depth Patching and 1.5" S9.5C	$600,000
2029	13	011-Buncombe	Resurfacing	SR 2173 (DILLINGHAM ROAD)	BRIDGE	SR 2175 (HAW BRANCH ROAD)	0.83	Full Depth Patching and 1.25" S9.5B	$123,900
2029	13	011-Buncombe	Resurfacing	SR 2173 (DILLINGHAM ROAD)	NC 197	L (BANARDSVILLE HIGHWAY)+ 1.32	1.34	Full Depth Patching and 1.25" S9.5B	$232,750
2029	13	011-Buncombe	Resurfacing	SR 2173 (DILLINGHAM ROAD)	SR 2175 (HAW BRANCH ROAD)	SR 2178 (STONY FORK ROAD)	1.44	Full Depth Patching and 1.5" S9.5C	$775,000
2029	13	011-Buncombe	Resurfacing	SR 2182 (MORGAN ROAD)	SR 2158 (MORGAN BRANCG ROAD)	NC 197	0.23	Full Depth Patching and 1.5" S9.5C	$45,650
2029	13	011-Buncombe	Resurfacing	SR 2215 (BROWN ROAD)	SR 2148 (STOCKTON BRANCH ROAD)	NC 197	0.20	Full Depth Patching and 1.5" S9.5C	$36,000
2029	13	011-Buncombe	Resurfacing	230 (BEAVERDAM ROAD/ WEBB COVE RO	PAVEMENT JOINT	END OF PAVEMENT	2.27	Full Depth Patching and 1.25" S9.5B	$397,250
2029	13	011-Buncombe	Resurfacing	SR 2247 (SHANNA DRIVE)	SR 1003 (REEMS CREEK ROAD)	END OF MAINTENANCE	0.18	Full Depth Patching and 1.0" S4.75A	$27,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	13	011-Buncombe	Resurfacing	SR 2256 (CLAIRCASTLE DRIVE)	SR 2255 (APPLECROSS ROAD)	DEAD END	0.09	Full Depth Patching and 1.0" S4.75A	$13,500
2029	13	011-Buncombe	Resurfacing	SR 2257 (BROOKWOOD ROAD)	SR 2276 (ROBINHOOD ROAD)	END OF STATE MAINTENANCE	0.37	Full Depth Patching and 1.0" S4.75A	$59,200
2029	13	011-Buncombe	Resurfacing	SR 2268 (LOWRY LANE)	SR 2255 (APPLECROSS ROAD)	CUL DE SAC	0.10	Full Depth Patching and 1.0" S4.75A	$15,000
2029	13	011-Buncombe	Resurfacing	SR 2274 (MARLWOOD COURT)	SR 2232 (KNOLL RIDGE DRIVE)	CUL DE SAC	0.31	Full Depth Patching and 1.0" S4.75A	$85,013
2029	13	011-Buncombe	Resurfacing	SR 2290 (STRAWBERRY LANE)	SR 2094 (STONEY KNOB ROAD)	DEAD END	0.15	Full Depth Patching and 1.0" S4.75A	$22,350
2029	13	011-Buncombe	Preservation	SR 1431 (VIEW STREET)	SR 1357 (GORMAN BRIDGE ROAD)	END OF MAINTENANCE	0.41	Full Depth Patching and Double Seal and Fog Seal	$20,500
2029	13	011-Buncombe	Preservation	SR 3430 (FRISBEE ROAD)	NC 112 (SARDIS ROAD)	END OF MAINTENANCE	0.25	Full Depth Patching and Double Seal and Fog Seal	$18,778
2029	13	011-Buncombe	Preservation	SR 3432 (POND ROAD CIRCLE)	SR 3431 (POND ROAD)	END OF MAINTENANCE	0.10	Full Depth Patching and Double Seal and Fog Seal	$7,990
2029	13	011-Buncombe	Preservation	SR 3433 (THOMPSON ROAD/FAMILY LANE	SR 1790 (POWELL STREET)	DEAD END	0.29	Full Depth Patching and Double Seal and Fog Seal	$19,000
2029	13	011-Buncombe	Preservation	SR 3477 (MORRIS ROAD)	NC 191	END OF MAINTENANCE	0.37	Full Depth Patching and Double Seal and Fog Seal	$29,000
2029	13	011-Buncombe	Preservation	3478 (CASE ROAD/CHARLIE AUTHUR LAN	SR 3477 (MORRIS ROAD)	END OF MAINTENANCE	0.28	Full Depth Patching and Double Seal and Fog Seal	$24,000
2029	13	011-Buncombe	Preservation	4 (BENT CREEEK RANCH/WESLEY BRANCH	NC 191	END OF MAINTENANCE	2.40	Microsurface	$170,050
2029	13	011-Buncombe	Preservation	SR 3486 (GLEN BRIDGE ROAD SOUTH EAST	SR 3495 (GLEN BRIDGE ROAD)	NC 191	1.85	Microsurface	$150,750
2029	13	011-Buncombe	Preservation	SR 3487 (MCDONALD ROAD)	SR 3486 (AVERY CREEK ROAD)	CUL DE SAC	0.29	Full Depth Patching and Double Seal and Fog Seal	$22,590
2029	13	011-Buncombe	Preservation	SR 3490 (SLEEPY GAP ROAD)	SR 3486 (AVERYS CREEK ROAD)	END OF MAINTENANCE	0.79	Full Depth Patching and Double Seal and Fog Seal	$66,890
2029	13	011-Buncombe	Preservation	SR 3492 (PENNSYLVANIA ROAD)	SR 3486 (AVERYS CREEK ROAD)	COUNTY LINE	1.55	Microsurface	$105,077
2029	13	011-Buncombe	Preservation	SR 3494 (BISHOP ROAD)	NC 191	NC 191 + .32 MILES	0.34	Full Depth Patching and Double Seal and Fog Seal	$30,090
2029	13	011-Buncombe	Preservation	SR 3495 (GLEN BRIDGE ROAD)	I 26 OVERPASS PAVEMENT JOINT	US 25	1.87	Microsurface	$145,550
2029	13	011-Buncombe	Preservation	SR 3497 (SUMNER DRIVE)	SR 3495 (GLEN BRIDGE ROAD)	495 (GLEN BRIDGE ROAD) + .108 M	0.11	Full Depth Patching and Double Seal and Fog Seal	$9,500
2029	13	011-Buncombe	Preservation	SR 3498 (LEDBETTER ROAD)	NC 146	NC 191	2.23	Microsurface	$146,850
2029	13	011-Buncombe	Preservation	SR 3522 (OLD SHOALS ROAD)	SR 3521 (BEALE ROAD)	NC 280	0.99	Microsurface	$84,090
2029	13	011-Buncombe	Preservation	SR 3555 (BROWN ROAD)	NC 112	END OF MAINTENANCE	0.26	Full Depth Patching and Double Seal and Fog Seal	$17,940
2029	13	011-Buncombe	Preservation	SR 3564 (HOYT ROAD)	SR 3498 (LEDBETTER ROAD)	CUL DE SAC	0.41	Full Depth Patching and Double Seal and Fog Seal	$32,899
2029	13	011-Buncombe	Preservation	SR 3573 (SOUTHWICKE DRIVE)	NC 191	END OF MAINTENANCE	0.42	Full Depth Patching and 1.0" S4.75A	$68,733
2029	13	011-Buncombe	Preservation	SR 3574 (SOUTHWICKE COURT)	SR 3573 (SOUTHWICKE DRIVE)	CUL DE SAC	0.10	Full Depth Patching and 1.0" S4.75A	$18,079
2029	13	011-Buncombe	Preservation	SR 3575 (SOUTHWICKE PLACE)	SR 3573 (SOUTHWICKE DRIVE)	CUL DE SAC	0.14	Full Depth Patching and 1.0" S4.75A	$32,275
2029	13	011-Buncombe	Preservation	SR 3576 (MCILWAIN ROAD)	NC 191	END OF MAINTENANCE	0.13	Full Depth Patching and Double Seal and Fog Seal	$10,400
2029	13	011-Buncombe	Preservation	SR 3596 (GLENVIEW ROAD)	SR 3495 (GLENN BRIDGE ROAD)	END OF MAINTENANCE	0.29	Full Depth Patching and 1.0" S4.75A	$35,000
2029	13	011-Buncombe	Preservation	SR 3597 (GLENVIEW PLACE)	SR 3596 (GLENVIEW ROAD)	CUTSHAW DRIVE (PRIVATE)	0.13	Full Depth Patching and 1.0" S4.75A	$26,777
2029	13	011-Buncombe	Preservation	SR 3612 (MOUNTAIN VIEW DRIVE)	SR 3496 (PINNER ROAD)	END OF MAINTENANCE	0.30	Full Depth Patching and Double Seal and Fog Seal	$25,000
2029	13	011-Buncombe	Preservation	SR 3619 (COFFEY CIRCLE)	SR 3474 (STRADLEY MOUNTAIN ROAD)	END OF MAINTENANCE	0.36	Full Depth Patching and Double Seal and Fog Seal	$31,550
2029	13	011-Buncombe	Preservation	SR 3630 (TURKEY TOE LANE)	SR 3631 (PINE RIDGE TRAIL)	SR 3631 (PINE RIDGE TRAIL)	0.18	Full Depth Patching and 1.0" S4.75A	$32,400
2029	13	011-Buncombe	Preservation	SR 3631 (PINE RIDGE TRAIL)	SR 3629 (AVERYS CREEK LANE)	END OF MAINTENANCE	0.51	Full Depth Patching and 1.0" S4.75A	$135,550
2029	13	011-Buncombe	Preservation	SR 3632 (BRAMBLE COURT)	SR 3631 (PINE RIDGE TRAIL)	CUL DE SAC	0.06	Full Depth Patching and 1.0" S4.75A	$10,500
2029	13	011-Buncombe	Preservation	SR 3635 (LINDA VISTA DRIVE)	NC 112	END OF MAINTENANCE	0.14	Full Depth Patching and Double Seal and Fog Seal	$11,120
2029	13	011-Buncombe	Preservation	SR 3637 (ERIKA LANE)	SR 3498 (LEDBETTER ROAD)	CUL DE SAC	0.12	Full Depth Patching and 1.0" S4.75A	$15,000
2029	13	011-Buncombe	Preservation	SR 3638 (HIDDEN ACRES DRIVE)	SR3479 (POLE CREASMAN)	END OF MAINTENANCE	0.21	Microsurface	$14,000
2029	13	012-Burke	Resurfacing	SR 1423 (PIDEMONT ROAD)	US 18/64	105 (BROWN MOUNTAIN BEACH R(	6.42	Full Depth Patching and 1.5" S9.5C	$1,595,600
2029	13	012-Burke	Resurfacing	SR 1430 (HARTLAND ROAD)	CALDWELL COUNTY LINE	SR 1426 (PAX HILL ROAD)	3.28	Full Depth Patching and 1.5" S9.5C	$595,400
2029	13	012-Burke	Resurfacing	SR 1493 (OLD SCHOOL TRAIL)	SR 1423 (PIEDMONT ROAD)	CUL DE SAC	0.33	Full Depth Patching and 1.0" S4.75A	$67,899
2029	13	012-Burke	Resurfacing	SR 1503 (RADER CIRCLE)	US 18/64	END OF MAINTENANCE	0.30	Full Depth Patching and 1.5" S9.5C	$65,775
2029	13	012-Burke	Resurfacing	SR 1505 (DUCKWORTH STREET)	SR 1504 (DUCKWORTH DRIVE)	END OF MAINTENANCE	0.37	Full Depth Patching and 1.25" S9.5B	$76,000
2029	13	012-Burke	Resurfacing	SR 1512 (AMHERST ROAD)	SR 1501 (HUFFMAN BRIDGE ROAD)	SR 1531 (NORTH DREXEL ROAD)	1.01	Full Depth Patching and 1.5" S9.5C	$587,000
2029	13	012-Burke	Resurfacing	SR 1512 (AMHERST ROAD)	SR 1443 (KIRKSEY DRIVE)	SR 1501 (HUFFMAN BRIDGE ROAD)	2.25	Full Depth Patching and 1.5" S9.5C	$555,997
2029	13	012-Burke	Resurfacing	SR 1513 (OLD AMHERST ROAD)	SR 1515 (BURKE SMOKEY CREEK ROAD)	SR 1514	1.51	Full Depth Patching and 1.5" S9.5C	$325,990
2029	13	012-Burke	Resurfacing	SR 1514 (DOGWOOD VISTA)	PAVEMENT JOINT	COUNTY LINE	1.46	Full Depth Patching and 1.5" S9.5C	$294,500
2029	13	012-Burke	Resurfacing	SR 1522 (ZION ROAD)	SR 1512 (AMHERST ROAD)	SR 1525 (SETTLEMYRE ROAD)	0.33	Full Depth Patching and 1.5" S9.5C	$77,000
2029	13	012-Burke	Resurfacing	SR 1523 (BRANDON ROAD)	SR 1525 (MOUNTAIN VIEW DRIVE)	US 70	0.92	Full Depth Patching and 1.5" S9.5C	$193,000
2029	13	012-Burke	Resurfacing	5 (SETTLEMYRE ROAD/MOUNTAIN VIEW I	SR 1522 (ZION ROAD)	US 70	1.74	Full Depth Patching and 1.25" S9.5B	$313,200
2029	13	012-Burke	Resurfacing	SR 1526 (PARK AVENUE/SETTLEMYRE)	SR 1527 (MOUNTAIN VIEW STREET)	SR 1525 (MOUNTAIN VIEW DRIVE)	0.41	Full Depth Patching and 1.25" S9.5B	$76,000
2029	13	012-Burke	Resurfacing	SR 1538 (CHURCH STREET NORTH WEST)	MP 2.53 (PAVEMENT JOINT)	US 70	0.97	Full Depth Patching and 1.5" S9.5C	$299,795
2029	13	012-Burke	Resurfacing	7 (EASTWOOD STREET/AVENUE/ROYCE ST	SR 1512 (AMHERST ROAD)	SR 1512 (AMHERST ROAD)	0.36	FDR and 1.5" S9.5C	$425,877
2029	13	012-Burke	Resurfacing	SR 1582 (ROYCE STREET)	SR 1577 (EASTWOOD AVENUE)	END OF MAINTENANCE	0.18	Full Depth Patching and 1.5" S9.5C	$32,400
2029	13	012-Burke	Resurfacing	584 (MORGANTON LENIOIR AIRPORT AVEI	SR 1501 (ANTIOCH ROAD)	END OF MAINTENANCE	0.37	Full Depth Patching and 1.5" S9.5C	$101,999
2029	13	012-Burke	Resurfacing	1587 (EASTWOOD STREET/EASTWAY AVEN	SR 1577 (EASTWOOD STREET)	SR 1582 (ROYCE STREET)	0.28	Full Depth Patching and 1.5" S9.5C	$59,999
2029	13	012-Burke	Resurfacing	SR 1588 (EASTWAY STREET)	SR 1587 (EASTWAY AVENUE)	END OF MAINTENANCE	0.09	Full Depth Patching and 1.5" S9.5C	$18,877
2029	13	012-Burke	Resurfacing	SR 1704 (BETHEL ROAD)	I 40 RAMP	NC 18	1.00	Full Depth Patching and 1.5" S9.5C	$233,000
2029	13	012-Burke	Resurfacing	SR 1716 (BURKE MEMORIAL PARK ROAD)	US 70 EAST	SR 1713 (SUMMERS ROAD)	0.65	Full Depth Patching and 1.5" S9.5C	$156,100
2029	13	012-Burke	Resurfacing	SR 1852 (WINDY HILL DRIVE)	PAVEMENT CHANGE	END OF PAVEMENT	0.07	Full Depth Patching and 1.5" S9.5C	$15,499

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	13	012-Burke	Resurfacing	SR 1898 (PLEASANT VIEW LOOP)	SR 1713 (SUMMERS ROAD)	SR 1898 (PLEASANT VIEW LOOP)	0.94	Full Depth Patching and 1.25" S9.5B	$190,000
2029	13	012-Burke	Resurfacing	SR 1943 (ROPER DRIVE)	SR 1940 (PETE BRITTAIN ROAD)	END OF MAINTENANCE	0.30	Full Depth Patching and 1.0" S4.75A	$62,259
2029	13	012-Burke	Resurfacing	SR 2209 (MARSH TRAIL)	SR 1501 (ANTIOCH ROAD)	END OF MAINTENANCE	0.94	Full Depth Patching and 1.5" S9.5C	$175,000
2029	13	012-Burke	Resurfacing	SR 2216 (GREEN HAVEN DRIVE)	SR 1501 (ANTIOCH ROAD)	END OF MAINTENANCE	0.75	Full Depth Patching and 1.5" S9.5C	$159,999
2029	13	012-Burke	Resurfacing	SR 2223 (GREEN HAVEN CIRCLE)	SR 2223 (GREEN HAVEN DRIVE)	SR 2223 (GREEN HAVEN CIRCLE)	0.28	Full Depth Patching and 1.5" S9.5C	$57,779
2029	13	012-Burke	Preservation	1110 (OLD SALEM,GARRISON, CRESTWOO	US 64	END OF MAINTENANCE	0.71	Full Depth Patching and Double Seal and Fog Seal	$56,800
2029	13	012-Burke	Preservation	SR 1112 (CRAWLEY ROAD)	SR 1102 (HOPEWELL ROAD)	US 64	0.65	Full Depth Patching and Double Seal and Fog Seal	$59,990
2029	13	012-Burke	Preservation	SR 1114 (FRED WILLIAMS)	SR 1113 (BYRD ROAD)	END OF MAINTENANCE	0.39	Full Depth Patching and Double Seal and Fog Seal	$31,200
2029	13	012-Burke	Preservation	SR 1121 (FISHER DAVIS ROAD)	US 64	CONLEY ROAD	0.40	Full Depth Patching and Double Seal and Fog Seal	$34,000
2029	13	012-Burke	Preservation	SR 1122 (SILVER CREEK CHURCH ROAD)	US 64	END OF MAINTENANCE	0.80	Full Depth Patching and Double Seal and Fog Seal	$68,000
2029	13	012-Burke	Preservation	SR 1123 (GOLDMINE ROAD)	US 64	SR 1129 (DYSARTSVILLE ROAD)	2.73	Full Depth Patching and Double Seal and Fog Seal	$230,000
2029	13	012-Burke	Preservation	SR 1124 (MOUNT OLIVE CHURCH ROAD)	SR 1134 (MORNING STAR CHURCH ROAD)	1142 (JAMESTOWN ROAD)	0.91	Full Depth Patching and Double Seal and Fog Seal	$70,355
2029	13	012-Burke	Preservation	SR 1133 (PATTON ROAD)	SR 1124 (MOUNT OLIVE CHURCH ROAD)	SR 1129 (DYSARTSVILLE ROAD)	1.87	Full Depth Patching and Double Seal and Fog Seal	$165,000
2029	13	012-Burke	Preservation	SR 1134 (MORNING STAR CHURCH ROAD)	SR 1124 (MOUNT OLIVE CHURCH ROAD)	SR 1129 (DYSARTSVILLE ROAD)	2.12	Full Depth Patching and Double Seal and Fog Seal	$149,775
2029	13	012-Burke	Preservation	SR 1158 (BILL EPLEY AVENUE)	SR 1124 (MOUNT OLIVE CHURCH ROAD)	END OF MAINTENANCE	0.48	Full Depth Patching and Double Seal and Fog Seal	$39,400
2029	13	012-Burke	Preservation	SR 1159 (TOPAZ AVENUE)	SR 1102 (HOPEWELL ROAD)	END OF MAINTENANCE	0.08	Full Depth Patching and Double Seal and Fog Seal	$6,790
2029	13	012-Burke	Preservation	SR 1160 (FLINT AVENUE)	SR 1102 (HOPEWELL ROAD)	END OF MAINTENANCE	0.38	Full Depth Patching and Double Seal and Fog Seal	$30,000
2029	13	012-Burke	Preservation	SR 1166 (SECREST STREET)	SR 1112 (PROPST ROAD)	END OF MAINTENANCE	0.29	Full Depth Patching and Double Seal and Fog Seal	$23,200
2029	13	012-Burke	Preservation	SR 1169 (CRAWLEY HIGGING AVENUE)	SR 1149 (CONLEY ROAD)	END OF MAINTENANCE	0.81	Full Depth Patching and Double Seal and Fog Seal	$75,000
2029	13	012-Burke	Preservation	SR 1170 (SUTTLE STREET)	US 64	END OF MAINTENANCE	0.08	Full Depth Patching and Double Seal and Fog Seal	$6,900
2029	13	012-Burke	Preservation	SR 1180 (REESE STORE AVENUE)	SR 1149 (CONLEY ROAD)	END OF MAINTENANCE	0.22	Full Depth Patching and Double Seal and Fog Seal	$19,200
2029	13	012-Burke	Preservation	SR 1181 (ROYAL STREET)	US 64	END OF MAINTENANCE	0.07	Full Depth Patching and Double Seal and Fog Seal	$4,950
2029	13	012-Burke	Preservation	SR 1182 (STROUPE STREET)	SR 1112 (PROPST ROAD)	END OF MAINTENANCE	0.21	Full Depth Patching and Double Seal and Fog Seal	$16,800
2029	13	012-Burke	Preservation	85 (BRENTWOOD ROAD/GRANDVIEW AVE	SR 1149 (CONLEY ROAD)	END OF MAINTENANCE	0.44	Full Depth Patching and 1.0" S4.75A	$79,790
2029	13	012-Burke	Preservation	SR 1186 (BRENTWOOD ROAD)	SR 1142 (JAMESTOWN ROAD)	SR 1185 (GRANDVIEW AVENUE)	0.61	Full Depth Patching and 1.0" S4.75A	$111,223
2029	13	012-Burke	Preservation	SR 1187 (FAIRVIEW AVENUE)	US 64	END OF MAINTENANCE	0.20	Full Depth Patching and Double Seal and Fog Seal	$16,900
2029	13	012-Burke	Preservation	SR 1189 (JAKE WILSON CIRCLE)	SR 1113 (BYRD ROAD)	SR 1113 (BYRD ROAD)	0.18	Full Depth Patching and Double Seal and Fog Seal	$15,459
2029	13	012-Burke	Preservation	SR 1195 (ANDY WILLIAMS STREET)	SR 1134 (MORNING STAR CHURCH ROAD)	DEAD END	0.34	Full Depth Patching and Double Seal and Fog Seal	$29,600
2029	13	012-Burke	Preservation	SR 1196 (BERKLEY STREET)	SR 1116 (JETER CARSWELL ROAD)	END OF MAINTENANCE	0.33	Full Depth Patching and Double Seal and Fog Seal	$28,450
2029	13	012-Burke	Preservation	SR 1941 (WILLIAMS ROAD)	I-40 (RAMP 2857)	END OF MAINTENANCE	0.56	Full Depth Patching and Double Seal and Fog Seal	$46,500
2029	13	012-Burke	Preservation	SR 1942 (WALKER ROAD)	US 64	SR 1941 (WILLIAMS ROAD)	0.81	Full Depth Patching and Double Seal and Fog Seal	$68,500
2029	13	012-Burke	Preservation	SR 1946 (WHISNANT STREET)	SR 1949 (SALEM ROAD)	END OF MAINTENANCE	0.09	Full Depth Patching and Double Seal and Fog Seal	$6,500
2029	13	012-Burke	Preservation	SR 1948 (PERPONS STREET)	SR 1949 (SALEM ROAD)	END OF MAINTENANCE	0.16	Full Depth Patching and Double Seal and Fog Seal	$100
2029	13	012-Burke	Preservation	SR 1962 (ROSE CARSWELL)	US 64	SR 1956 (JENKINS ROAD)	0.71	Full Depth Patching and Double Seal and Fog Seal	$66,975
2029	13	012-Burke	Preservation	SR 1963 (CLARK LOOP)	SR 1956 (JENKINS ROAD)	SR 1956 (JENKINS ROAD)	0.92	Full Depth Patching and Double Seal and Fog Seal	$78,099
2029	13	012-Burke	Preservation	SR 1966 (MILL RACE ROAD)	SR 1956 (JENKINS ROAD)	US 64	0.67	Full Depth Patching and Double Seal and Fog Seal	$49,490
2029	13	012-Burke	Preservation	SR 1969 (ROPER HOLLOW ROAD)	US 64	END OF MAINTENANCE	1.39	Full Depth Patching and Double Seal and Fog Seal	$118,000
2029	13	012-Burke	Preservation	SR 1988 (LYLE STREET)	SR 1949 (SALEM ROAD)	SR 1987 (PHILLIPS STREET)	0.07	Full Depth Patching and Double Seal and Fog Seal	$5,795
2029	13	012-Burke	Preservation	SR 1994 (PHOENIX DRIVE)	SR 1949 (SALEM ROAD)	SR 2004 (SOUTH PHOENIX AVENUE	0.08	Full Depth Patching and Double Seal and Fog Seal	$7,002
2029	13	012-Burke	Preservation	SR 1998 (NOWLINGS CHAPEL STREET)	US 64	END OF MAINTENANCE	0.41	Full Depth Patching and Double Seal and Fog Seal	$35,000
2029	13	012-Burke	Preservation	SR 2004 (SOUTH PHOENIX AVENUE)	SR 1994 (PHOENIX DRIVE)	END OF MAINTENANCE)	0.09	Full Depth Patching and Double Seal and Fog Seal	$5,980
2029	13	012-Burke	Preservation	SR 2030 (GERALD ROAD)	US 64	SR 1949 (SALEM ROAD)	0.15	Full Depth Patching and Double Seal and Fog Seal	$12,590
2029	13	012-Burke	Preservation	SR 2100 (BEDFORD AVENUE)	SR 1149 (CONLEY ROAD)	END OF MAINTENANCE	0.05	Full Depth Patching and 1.0" S4.75A	$11,567
2029	13	012-Burke	Preservation	SR 2114 (GOODES CREEK CHURCH ROAD)	SR 1102 (HOPEWELL ROAD)	END OF MAINTENANCE	0.76	Full Depth Patching and Double Seal and Fog Seal	$68,022
2029	13	057-Madison	Resurfacing	SR 1355 (BAILEY STREET)	SR 1609 (NORTH MAIN STREET)	MP.42 (SCHOOL)	1.54	Full Depth Patching and 1.5" S9.5C	$366,550
2029	13	057-Madison	Resurfacing	SR 1356 (FOREST STREET)	SR 1357 (BANJO BRANCH ROAD)	END OF MAINTENANCE	0.26	Full Depth Patching and 1.5" S9.5C	$1,201,250
2029	13	057-Madison	Resurfacing	SR 1359 (PHILLIPS VALLEY ROAD)	SR 1428 (STONE COTTAGE ROAD)	SR 1428 (STONE COTTAGE ROAD)	0.70	Full Depth Patching and 1.25" S9.5B	$150,990
2029	13	057-Madison	Preservation	SR 1428 (STONE COTTAGE ROAD)	NC 213	NC 213	0.64	Full Depth Patching and Double Seal and Fog Seal	$24,450
2029	13	057-Madison	Preservation	SR 1555 (MOUNT OLIVE DRIVE)	SR 1557 (LONG RIDGE ROAD)	END OF MAINTENANCE	0.38	Full Depth Patching and Double Seal and Fog Seal	$29,000
2029	13	057-Madison	Preservation	SR 1556 (FORKS OF IVY ROAD)	SR 1557 (LONG RIDGE ROAD)	END OF PAVEMENT	0.82	Full Depth Patching and Double Seal and Fog Seal	$58,875
2029	13	059-McDowell	Resurfacing	1805 (HUNTER DRIVE)	SR 1713 (MARION STREET)	SR 1806 (HUNTER DRIVE)	0.29	Full Depth Patching and 1.25" S9.5B	$62,399
2029	13	059-McDowell	Resurfacing	SR 1103 (BAT CAVE ROAD)	BUNCOMBE COUNTY LINE	I 40 WEST	6.75	Full Depth Patching and 1.25" S9.5C	$4,099,000
2029	13	059-McDowell	Resurfacing	1153 (GLENWOOD BAPTIST CHURCH ROA	SR 1786 (OLD US 221 SOUTH)	US 221	0.21	Full Depth Patching and 1.5" S9.5C	$42,700
2029	13	059-McDowell	Resurfacing	SR 1197 (ROBY CONLEY ROAD)	SR 1214 (OLD GREENLEE ROAD)	US 70	1.73	Full Depth Patching and 1.5" S9.5C	$474,000
2029	13	059-McDowell	Resurfacing	SR 1214 OLD # 10 (GREENLEE ROAD)	BEGIN PAVEMENT	US 70	1.24	Full Depth Patching and 1.5" S9.5C	$269,995
2029	13	059-McDowell	Resurfacing	28 (221 BYPASS ON / OFF RAMPS TATE ST	SR 1195 (TATE STREET)	SR 1195 (TATE STREET)	0.48	Full Depth Patching and 1.5" S9.5C	$159,995
2029	13	059-McDowell	Resurfacing	SR 1419 (AB ELLIOTT ROAD)	US 70	END OF MAINTENANCE	0.51	Full Depth Patching and 1.5" S9.5C	$99,829
2029	13	059-McDowell	Resurfacing	SR 1464 US 221 NORTH BUISNESS EXT	SR 1501 (HANKINS ROAD)	END OF MAINTENANCE	0.25	Full Depth Patching and 1.5" S9.5C	$56,575
2029	13	059-McDowell	Resurfacing	SR 1547 (LONESOME PINE DRIVE)	NC 126	END OF MAINTENANCE	0.26	Full Depth Patching and 1.5" S9.5C	$49,995

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	13	059-McDowell	Resurfacing	SR 1741 (FAIRVIEW ROAD)	NC 226 SOUTH	SR 1736 (TONEY ROAD)	1.32	Full Depth Patching and 1.5" S9.5C	$289,999
2029	13	059-McDowell	Resurfacing	SR 1767 (BIGGERSTAFF LOOP)	PAVEMENT CHANGE	SR 1758 (DRUCILLA CHURCH ROAD	1.17	Full Depth Patching and 1.25" S9.5B	$278,959
2029	13	059-McDowell	Resurfacing	SR 1786 (OLD US 221 SOUTH)	US 221	US 221	3.92	Full Depth Patching and 1.5" S9.5C	$706,500
2029	13	059-McDowell	Resurfacing	SR 1839 (ALMA MORGAN DRIVE)	SR 1786 (OLD US 221 SOUTH)	CUL DE SAC	0.28	Mill 1.5" and 1.5" S9.5C	$51,120
2029	13	059-McDowell	Preservation	SR 1111 (MOFFITT HILL CHURCH ROAD)	SR 1103 (BAT CAVE ROAD)	END OF MAINTENANCE	0.94	Full Depth Patching and Double Seal and Fog Seal	$69,950
2029	13	059-McDowell	Preservation	SR 1219 (BUNKER DRIVE)	SR 1220 (TOM CAMP ROAD)	END OF PAVEMENT	0.41	Full Depth Patching and 1.0" S4.75A	$75,332
2029	13	059-McDowell	Preservation	SR 1226 (OLD RIVER ROAD)	US 70	END OF MAINTENANCE	0.27	Full Depth Patching and Double Seal and Fog Seal	$16,000
2029	13	059-McDowell	Preservation	SR 1237 (WILDLIFE LAKE ROAD)	SR 1135 (OLD FORT/ SUGAR HILL ROAD)	SR 1238 (GOLF COURSE ROAD)	1.17	Full Depth Patching and Double Seal and Fog Seal	$85,550
2029	13	059-McDowell	Preservation	SR 1238 (GOLF COURSE ROAD)	SR 1135 (OLD FORT/ SUGAR HILL ROAD)	END OF MAINTENANCE	1.23	Full Depth Patching and Double Seal and Fog Seal	$105,575
2029	13	059-McDowell	Preservation	SR 1254 (MORRIS HOLLOW ROAD)	SR 1274 (CATAWBA RIVER ROAD)	END OF MAINTENANCE	0.32	Full Depth Patching and Double Seal and Fog Seal	$17,500
2029	13	059-McDowell	Preservation	SR 1263 (WALL POOL ROAD)	SR 1161 (LYTLE MOUNTAIN ROAD)	END OF MAINTENANCE	0.16	Full Depth Patching and Double Seal and Fog Seal	$14,000
2029	13	059-McDowell	Preservation	SR 1304 (WEST CASCADE DRIVE)	SR 1303 (CASCADE DRIVE)	END OF MAINTENANCE	0.19	Full Depth Patching and 1.0" S4.75A	$19,000
2029	13	059-McDowell	Preservation	SR 1415 (JOHNSON HOLLOW ROAD WEST	US 70	1454 (MOUNT OLIVE CHURCH ROA	0.46	Full Depth Patching and 1.0" S4.75A	$75,000
2029	13	059-McDowell	Preservation	SR 1454 (MOUNT OLIVE CHURCH ROAD)	SR 1415 (JOHNSON HOLLOW ROAD WEST)	END OF MAINTENANCE	0.06	Full Depth Patching and Double Seal and Fog Seal	$3,000
2029	13	059-McDowell	Preservation	SR 1462 (EAST AND WEST CARSON STREET	BEGIN MAINTENANCE	END OF MAINTENANCE	0.21	Full Depth Patching and Double Seal and Fog Seal	$20,000
2029	13	059-McDowell	Preservation	SR 1513 (JUSTICE ROAD)	SR 1500 (AIRPORT ROAD)	END OF MAINTENANCE	0.26	Full Depth Patching and 1.0" S4.75A	$26,000
2029	13	059-McDowell	Preservation	SR 1788 (RED HILL DRIVE)	SR 1785 (MUD CUT LOOP)	END OF PAVEMENT	0.26	Full Depth Patching and Double Seal and Fog Seal	$14,000
2029	13	059-McDowell	Preservation	SR 1813 (EAST HUNT DRIVE/COVE ROAD)	US 70	END OF MAINTENANCE	0.15	Full Depth Patching and 1.0" S4.75A	$29,405
2029	13	059-McDowell	Preservation	SR 1817 (PINE AVENUE)	SR 1810 (BRADLEY STREET)	END OF MAINTENANCE	0.11	Full Depth Patching and 1.0" S4.75A	$12,000
2029	13	059-McDowell	Preservation	SR 1831 (RTHMOS ROAD)	SR 1760 (HARMONY GROVE ROAD)	END OF MAINTENANCE	0.08	Full Depth Patching and Double Seal and Fog Seal	$5,675
2029	13	061-Mitchell	Resurfacing	SR 1121 (ALTAPASS HIGHWAY)	MILE POST 1.762	1128 (HUMPBACK MOUNTAIN ROA	1.72	Full Depth Patching and 1.5" S9.5C	$355,777
2029	13	061-Mitchell	Resurfacing	SR 1150 (HAWKINS BRANCH ROAD)	SR 1403 (ROAN ROAD)	END OF MAINTENANCE	0.50	Full Depth Patching and Double Seal and Fog Seal	$1,201,250
2029	13	061-Mitchell	Resurfacing	SR 1170 (SNOW CREEK ROAD)	NC 80	SR 1170 (SLAGLE ROAD)	1.87	Full Depth Patching and 1.5" S9.5C	$2,330,000
2029	13	061-Mitchell	Resurfacing	SR 1171 (SNOW CREEK ROAD)	SR 1164 (CONLEY RIDGE ROAD)	SR 1172 (PATRICK PHILLIPS ROAD)	0.33	Full Depth Patching and 1.5" S9.5C	$209,000
2029	13	061-Mitchell	Resurfacing	SR 1172 (SNOW CREEK ROAD)	SR 1170 (SLAGLE ROAD)	SR 1172 (PATRICK PHILLIPS ROAD)	0.41	Full Depth Patching and 1.5" S9.5C	$89,995
2029	13	061-Mitchell	Resurfacing	SR 1197 (BEAR CREEK ROAD)	SR 1195 (HAMBURG ROAD)	MP 1.37	0.95	Full Depth Patching and 1.5" S9.5C	$189,999
2029	13	061-Mitchell	Preservation	SR 1105 (EMERALD MINE ROAD)	SR 1104 (CHESTNUT GROVE ROAD)	END OF MAIINTENANCE	0.70	Full Depth Patching and Double Seal and Fog Seal	$61,500
2029	13	061-Mitchell	Preservation	SR 1135 (JAKES BRANCH ROAD)	US 19E	END OF MAINTENANCE	0.41	Full Depth Patching and Double Seal and Fog Seal	$35,559
2029	13	061-Mitchell	Preservation	SR 1146 (SULLINS BRANCH ROAD)	MILE POST .37	END OF MAINTENANCE	0.43	Full Depth Patching and Double Seal and Fog Seal	$42,000
2029	13	061-Mitchell	Preservation	SR 1157 (HOOT OWL ROAD)	SR 1156 (BRUSHEY CREEK ROAD)	END OF MAINTENANCE	0.77	Full Depth Patching and Double Seal and Fog Seal	$67,000
2029	13	061-Mitchell	Preservation	SR 1164 (CONLEY RIDGE ROAD)	BEGIN PAVEMENT	SR 1171 (SNOW CREEK ROAD)	0.38	Full Depth Patching and Double Seal and Fog Seal	$33,000
2029	13	061-Mitchell	Preservation	SR 1164 (SNOW CREEK ROAD)	SR 1171 (SNOW CREEK ROAD)	SR 1250 (ORCHARD ROAD)	1.75	Full Depth Patching and Double Seal and Fog Seal	$149,550
2029	13	061-Mitchell	Preservation	SR 1167 (WING ROAD)	SR 1250 (ORCHARD ROAD)	SR 1164 (SNOW CREEK ROAD)	1.31	Full Depth Patching and Double Seal and Fog Seal	$95,550
2029	13	061-Mitchell	Preservation	SR 1170 (SLAGLE ROAD)	BEGIN PAVEMENT	SR 1168 (MURDOCK ROAD)	0.37	Full Depth Patching and Double Seal and Fog Seal	$31,977
2029	13	061-Mitchell	Preservation	SR 1206 (STAGGER WEED ROAD)	SR 1211 (CANE CREEK ROAD)	END OF MAINTENANCE	1.59	Full Depth Patching and Double Seal and Fog Seal	$135,450
2029	13	061-Mitchell	Preservation	SR 1270 (RIVER ROAD)	SR 1162 (PENLAND ROAD)	END OF MAINTENANCE	0.08	Full Depth Patching and 1.5" S9.5C	$9,000
2029	13	061-Mitchell	Preservation	SR1146 (SULLINS BRANCH ROAD)	SR 1403 (ROAN ROAD)	MILE POST .37	0.37	Full Depth Patching and Double Seal and Fog Seal	$37,900
2029	13	081-Rutherford	Resurfacing	SR 2041 (DRAKE CIRCLE)	NC 120	R 1921 (RACE PATH CHURCH ROAD	0.25	Full Depth Patching and 1.5" S9.5C	$49,000
2029	13	081-Rutherford	Resurfacing	SR 1112 (W.V. THOMPSON ROAD)	SR 1111 (JACK MCKINNEY ROAD)	1101 (COUNTY LINE ROAD)	4.38	Full Depth Patching and 1.5" S9.5C	$2,099,000
2029	13	081-Rutherford	Resurfacing	SR 1118 (HOPPER ROAD)	SR 1106 (BIG ISLAND ROAD)	END OF MAINTENANCE	2.43	Full Depth Patching and 1.5" S9.5C	$443,000
2029	13	081-Rutherford	Resurfacing	SR 1136 (NEW BETHEL CHURCH ROAD)	221	PAVEMENT JOINT	0.11	Full Depth Patching and 1.5" S9.5C	$29,995
2029	13	081-Rutherford	Resurfacing	SR 1806 (ODESSA PARK ROAD)	SR 1919 (WEBB CHURCH ROAD)	END OF MAINTENANCE	0.22	Full Depth Patching and 1.5" S9.5C	$44,000
2029	13	081-Rutherford	Resurfacing	SR 1910 (BAXTER CEMETERY ROAD)	SR 1901 (OLD CAROLEEN ROAD)	SR 1911 (LOW BRIDGE ROAD)	0.71	Full Depth Patching and 1.5" S9.5C	$149,455
2029	13	081-Rutherford	Resurfacing	SR 1914 (PUZZLE CREEK ROAD)	SR 1913 (OAK GROVE CHURCH ROAD)	US 74 BUSINESS	0.93	Full Depth Patching and 1.5" S9.5C	$201,000
2029	13	081-Rutherford	Resurfacing	SR 1937 (BROOKLYN ROAD)	SR 1989 (2ND STREET)	SR 1937 (BROOKLYN ROAD)	0.48	Full Depth Patching and 1.5" S9.5C	$82,999
2029	13	081-Rutherford	Resurfacing	SR 1981 (BOSS MOORE ROAD)	SR 1920 (ELLENBORO HENRIETTA ROAD)	US 221 ALTERNATE	1.22	Full Depth Patching and 1.5" S9.5C	$224,799
2029	13	081-Rutherford	Resurfacing	SR 1989 (1ST STREET)	SR 2003 (3RD STREET)	US 221 ALTERNATE	0.17	Full Depth Patching and 1.5" S9.5C	$33,989
2029	13	081-Rutherford	Resurfacing	SR 1989 (BROOKLYN ROAD)	SR 1901 (OLD CAROLEEN ROAD)	END OF PAVEMENT	0.09	Full Depth Patching and 1.5" S9.5C	$18,990
2029	13	081-Rutherford	Resurfacing	SR 1993 (OLD US 221A HIGHWAY)	US 221 ALTERNATE	SR 1002 (DUKE POWER ROAD)	2.90	Full Depth Patching and 1.25" S9.5B	$589,990
2029	13	081-Rutherford	Resurfacing	SR 1997 (BURGESS ROAD)	BEGIN PAVEMENT	END OF MAINTENANCE	0.17	Full Depth Patching and 1.5" S9.5C	$32,500
2029	13	081-Rutherford	Resurfacing	SR 2007 (MORGAN STREET)	US 221 ALTERNATE	DEAD END	0.38	Full Depth Patching and 1.5" S9.5C	$79,990
2029	13	081-Rutherford	Resurfacing	SR 2015 (LEON ROAD)	SR 1920 (ELLENBORO HENRIETTA ROAD)	END OF MAINTENANCE	0.31	Full Depth Patching and 1.5" S9.5C	$65,500
2029	13	081-Rutherford	Resurfacing	SR 2032 (RALEIGH LEDBETTER ROAD)	SR 1920 (ELLENBORO HENRIETTA ROAD)	END OF MAINTENANCE	0.37	Full Depth Patching and 1.5" S9.5C	$79,900
2029	13	081-Rutherford	Resurfacing	SR 2033 (HILLBROOK DRIVE)	SR 1914 (PUZZLE CREEK ROAD)	END OF MAINTENANCE	0.40	Full Depth Patching and 1.5" S9.5C	$169,000
2029	13	081-Rutherford	Resurfacing	SR 2034 (EAST DALTON ROAD)	SR 1935 (WALKERS STORE ROAD)	END OF MAINTENANCE	0.47	Full Depth Patching and 1.5" S9.5C	$35,000
2029	13	081-Rutherford	Resurfacing	SR 2101 (BALLENGER ROAD)	SR 1993 (OLD US 221 ALTERNATE HIGHWAY)	US 221 ALTERNATE	0.31	Full Depth Patching and 1.5" S9.5C	$75,090
2029	13	081-Rutherford	Resurfacing	SR 2102 (HINES ROAD)	SR 2103 (CAMP FERRY ROAD)	US 221 SOUTH	2.15	Full Depth Patching and 1.5" S9.5C	$439,599
2029	13	081-Rutherford	Resurfacing	SR 2120 (HAMES RIDGE ROAD)	SR 2119 (HOG PEN BRANCH ROAD)	2110 (OLD CALVARY CHURCH ROA	1.56	Full Depth Patching and 1.5" S9.5C	$169,000
2029	13	081-Rutherford	Resurfacing	SR 2125 (HARRIS HENRIETTA ROAD)	SR 2117 (FERRY ROAD)	SR 2210 (CHASE HIGH ROAD)	1.32	Full Depth Patching and 1.25" S9.5B	$362,999

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	13	081-Rutherford	Resurfacing	SR 2130 (WISEMAN STREET)	US 221 ALTERNATE	END OF MAINTENANCE	0.35	Full Depth Patching and 1.5" S9.5C	$58,300
2029	13	081-Rutherford	Resurfacing	SR 2138 (AVONDALE LANDFILL ROAD)	US 221 ALTERNATE	SR 2142 (BYERS ROAD)	1.35	Full Depth Patching and 1.25" S9.5B	$256,000
2029	13	081-Rutherford	Resurfacing	SR 2152 (MORNINGSTAR LAKE ROAD)	US 221	SR 2159 (DOGGETT ROAD)	2.46	Full Depth Patching and 1.5" S9.5C	$499,599
2029	13	081-Rutherford	Resurfacing	SR 2267 (MICHAEL DRIVE)	SR 2159 (DOGGETT ROAD)	CUL DE SAC	0.35	Crack Seal and 1.5" S9.5C	$72,561
2029	13	081-Rutherford	Preservation	SR 1102 (LAMBS GRILL ROAD)	SOUTH CAROLINA STATE LINE	SR 1101 (COUNTY LINE ROAD)	1.61	Full Depth Patching and Double Seal and Fog Seal	$154,555
2029	13	081-Rutherford	Preservation	SR 1117 (HARRILL ROAD)	US 221	END OF MAINTENANCE	0.41	Full Depth Patching and Double Seal and Fog Seal	$35,599
2029	13	081-Rutherford	Preservation	SR 1134 (HOLLY SPRINGS CHURCH ROAD)	SR 1221 (HARRIS HOLLY SPRINGS ROAD)	END OF MAINTENANCE	0.29	Full Depth Patching and Double Seal and Fog Seal	$21,750
2029	13	081-Rutherford	Preservation	SR 1136 (NEW BETHEL CHURCH ROAD)	SR 1111 (JACK MCKINNEY ROAD)	MILE POST .19	0.19	Full Depth Patching and Double Seal and Fog Seal	$17,900
2029	13	081-Rutherford	Preservation	SR 1139 (TOMS LAKE ROAD)	SR 1106 (BIG ISLAND ROAD)	US 221	1.72	Full Depth Patching and Double Seal and Fog Seal	$146,550
2029	13	081-Rutherford	Preservation	SR 1930 (GILLESPIE ROAD)	NC 120	SR 1931 (OLD MOORESBORO ROAD	0.57	Seal - Double and Fog Seal	$25,000
2029	13	081-Rutherford	Preservation	SR 1935 (WALKER STORE ROAD)	END OF MAINTENANCE	SR 1944 (MILLS AVENUE)	1.98	Seal - Double and Fog Seal	$57,955
2029	13	081-Rutherford	Preservation	SR 1991 (HIGH SHOALS CHURCH ROAD)	NC 120	SR 1931 (OLD MOORESBORO ROAD	1.30	Seal - Double and Fog Seal	$48,750
2029	13	081-Rutherford	Preservation	SR 2112 (GOODES CREEK CHURCH ROAD)	SR 2114 (HAMRICK ROAD)	SR 2109 (ISLANDS FORD ROAD)	1.34	Full Depth Patching and Double Seal and Fog Seal	$100,770
2029	13	081-Rutherford	Preservation	SR 2145 (WOMACK LAKE ROAD)	SR 2129 (OLD HENRIETTA ROAD)	SR 2143 (KELLY ROAD)	0.86	Full Depth Patching and Double Seal and Fog Seal	$74,899
2029	13	081-Rutherford	Preservation	SR 2149 (DOGGETT GROVE ROAD)	SR 2215 (HENSON ROAD)	SR 2159 (DOGGETT ROAD)	1.80	Full Depth Patching and Double Seal and Fog Seal	$159,770
2029	13	081-Rutherford	Preservation	SR 2171 (BURCH HUTCHINS ROAD)	SR 2169 (OAKLAND ROAD)	PAVEMENT CHANGE	0.96	Full Depth Patching and Double Seal and Fog Seal	$93,000
2029	13	081-Rutherford	Preservation	SR 2254 (HAWTHORNE LANE)	SR 2159 (PINEY RIDGE ROAD)	END OF MAINTENANCE	0.37	Full Depth Patching and Double Seal and Fog Seal	$33,675
2029	13	100-Yancey	Resurfacing	1126 (HORTONS CREEK/PRICES CREEK ROA	MADISON COUNTY LINE	SR 1136 (BANKS CREEK ROAD)	4.08	Full Depth Patching and 1.5" S9.5C	$734,000
2029	13	100-Yancey	Resurfacing	SR 1117 (BANKS CREEK ROAD)	SR 1136 (PHIPPS CREEK ROAD)	SR 1118 (BURLESON GAP ROAD)	0.81	Full Depth Patching and 1.5" S9.5C	$155,000
2029	13	100-Yancey	Resurfacing	SR 1118 (BURLESON GAP ROAD)	SR 1121 (PRICES CREEK ROAD)	SR 1117 (BANKS CREEK ROAD)	0.99	Full Depth Patching and 1.5" S9.5C	$198,000
2029	13	100-Yancey	Resurfacing	SR 1121 (PRICES CREEK ROAD)	SR 1120 (BLANKENSHIP CREEK ROAD)	END OF PAVEMENT	1.64	Full Depth Patching and 1.5" S9.5C	$295,200
2029	13	100-Yancey	Preservation	SR 1114 (DAM ROAD)	SR 1115 (BAKERS CREEK ROAD)	END OF PAVEMENT	1.11	Full Depth Patching and Double Seal and Fog Seal	$83,250
2029	13	100-Yancey	Preservation	SR 1118 (BANKS CREEK ROAD)	SR 1118 (BURLESON GAP ROAD)	END OF PAVEMENT	0.76	Full Depth Patching and Double Seal and Fog Seal	$57,000
2029	13	100-Yancey	Preservation	SR 1124 (INDIAN CREEK ROAD)	SR 1126 (HORTONS CREEK ROAD)	END OF PAVEMENT	3.14	Full Depth Patching and Double Seal and Fog Seal	$275,775
2029	13	100-Yancey	Preservation	SR 1137 (CANE RIVER CHURCH ROAD)	US 19 E	END OF PAVEMENT	0.40	Full Depth Patching and Double Seal and Fog Seal	$29,625
2029	13	100-Yancey	Preservation	SR1120 (BLANKENSHIP CREEK ROAD)	SR 1121 (PRICES CREEK ROAD)	END OF PAVEMENT	0.94	Full Depth Patching and Double Seal and Fog Seal	$70,500
2029	14	020-Cherokee	Resurfacing	SR 1112	SR 1110	GA Line	1.94	1.25" SF9.5A	$534,050
2029	14	020-Cherokee	Resurfacing	SR 1326	SR 1365	SR 1354	4.27	1.25" SF9.5A	$1,173,975
2029	14	020-Cherokee	Resurfacing	US 64/74 E	Tennessee State Line	.33 miles west of SR 1131	6.96	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5C	$3,850,000
2029	14	020-Cherokee	Resurfacing	US 64/74 W	.33 miles west of SR 1131	Tennessee State Line	6.91	Mill 2.5" and 2.5" I19.0C and 1.5" S9.5C	$3,850,000
2029	14	020-Cherokee	Preservation	SR 1120	SR 1116	SR 1121	2.41	Seal - Double and Fog Seal	$168,490
2029	14	020-Cherokee	Preservation	SR 1148	SR 1145	SR 1150	1.39	Seal - Double and Fog Seal	$96,950
2029	14	020-Cherokee	Preservation	SR 1150	Pvmt Chng	NC 294	2.65	Seal - Double and Fog Seal	$185,570
2029	14	020-Cherokee	Preservation	SR 1152	NC 294	DEAD END	1.17	Seal - Double and Fog Seal	$81,830
2029	14	022-Clay	Resurfacing	SR 1169	Old Hwy 64	EOP	2.90	1.5" S9.5B	$797,500
2029	14	022-Clay	Resurfacing	US 64	SR 1343 + 0.37	Bridge #6	1.45	Full Depth Patching and 1.5" S9.5B	$2,000,000
2029	14	022-Clay	Preservation	SR 1120	Us 69	OLD US 64	0.94	Seal - Double and Fog Seal	$65,800
2029	14	022-Clay	Preservation	SR 1156	SR 1155	End of Maint.	0.30	Seal - Double and Fog Seal	$21,000
2029	14	022-Clay	Preservation	SR 1314	SR 1307	SR 1325	2.32	Seal - Double and Fog Seal	$162,400
2029	14	022-Clay	Preservation	SR 1357	SR 1356	END MAINT	0.09	Seal - Double and Fog Seal	$6,300
2029	14	022-Clay	Preservation	SR 1377	US 64 BUS	END MAINT	0.44	Seal - Double and Fog Seal	$30,800
2029	14	038-Graham	Resurfacing	SR 1252	East Buffalo Circle	EOM	1.44	Full Depth Patching and 1.25" S9.5B	$375,000
2029	14	038-Graham	Preservation	SR 1240	NC 28	EOP	1.10	Seal - Double and Fog Seal	$76,790
2029	14	038-Graham	Preservation	SR 1242	BEG 16'PVT	PVMT CHG	0.83	Seal - Double and Fog Seal	$58,100
2029	14	038-Graham	Preservation	SR 1242	SR 1251	NC 28	0.96	Seal - Double and Fog Seal	$67,270
2029	14	038-Graham	Preservation	SR 1242	PVMT CHG	PVMT CHG	2.17	Seal - Double and Fog Seal	$151,900
2029	14	038-Graham	Preservation	SR 1242	PVMT CHG	SR 1251	1.07	Seal - Double and Fog Seal	$75,040
2029	14	044-Haywood	Resurfacing	SR 1338	NC 209	SR 1395	10.40	Full Depth Patching and 1.25" S9.5B	$2,858,900
2029	14	044-Haywood	Resurfacing	US 19/23 N	US 74	End Dvd Hwy (Smathers St in Clyde	0.52	Mill 1.5" and 1.5" S9.5B	$250,000
2029	14	044-Haywood	Resurfacing	US 19/23/74 E	Bridge 0121 @ Exit 104 (NC 209)	Exit 106 Clyde Exit	1.75	Mill 1.5" and 1.5" S9.5C	$1,000,000
2029	14	044-Haywood	Resurfacing	US 19/23/74 W	Bridge 0126 @ I-40	Bridge 0073 (Clyde Exit)	0.96	Mill 1.5" and 1.5" S9.5C	$800,000
2029	14	044-Haywood	Resurfacing	US 19/23/74 W	Merge of US 19	Bridge 0122 @ Lowes	1.34	Mill 1.5" and 1.5" S9.5C	$850,000
2029	14	044-Haywood	Resurfacing	US 74 E	Exit 106	Bridge 0126 @ I-40	1.14	Mill 1.5" and 1.5" S9.5C	$1,000,000
2029	14	044-Haywood	Resurfacing	US 74 W	Bridge 0073 (Clyde Exit)	Merge of US 19	0.54	Mill 1.5" and 1.5" S9.5C	$450,000
2029	14	044-Haywood	Preservation	SR 1120	NC 215	DEAD END	0.82	Seal - Double and Fog Seal	$57,260
2029	14	044-Haywood	Preservation	SR 1134	US 276	EOM	1.11	Seal - Double and Fog Seal	$77,630
2029	14	044-Haywood	Preservation	SR 1301	SR 1300	DEAD END	0.41	Seal - Double and Fog Seal	$28,560
2029	14	044-Haywood	Preservation	SR 1306	Bridge # 219	Dead End	0.90	Seal - Double and Fog Seal	$62,930
2029	14	044-Haywood	Preservation	SR 1320	SR 1322	SR 1318	1.82	Seal - Double and Fog Seal	$127,260

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	14	044-Haywood	Preservation	SR 1322	US 276	EOP	1.00	Seal - Double and Fog Seal	$70,000
2029	14	044-Haywood	Preservation	SR 1510	SR 1509	DEAD END	0.30	Seal - Double and Fog Seal	$20,860
2029	14	044-Haywood	Preservation	SR 1511	SR 1503	DEAD END	0.48	Seal - Double and Fog Seal	$33,670
2029	14	044-Haywood	Preservation	SR 1571	SR 1569	EOM	0.36	Seal - Double and Fog Seal	$25,200
2029	14	044-Haywood	Preservation	SR 1603	SR 1004	DEAD END	0.46	Seal - Double and Fog Seal	$32,060
2029	14	044-Haywood	Preservation	SR 1626	SR 1585	SR 1556	0.59	Seal - Double and Fog Seal	$41,300
2029	14	044-Haywood	Preservation	SR 1627	SR 1513	DEAD END	0.21	Seal - Double and Fog Seal	$14,700
2029	14	044-Haywood	Preservation	SR 1809	SR 1812	SR 1810	0.78	Seal - Double and Fog Seal	$54,740
2029	14	044-Haywood	Preservation	SR 1853	SR 1854	Dead End	0.58	Seal - Double and Fog Seal	$40,250
2029	14	045-Henderson	Resurfacing	SR 1125	SR-1123	SR-1125	1.51	Full Depth Patching and 1.5" S9.5B	$411,875
2029	14	045-Henderson	Resurfacing	SR 1126	SR-1127	SR-1125	0.46	Full Depth Patching and 1.5" S9.5B	$127,600
2029	14	045-Henderson	Resurfacing	SR 1261	SR-1127	SR-1261	1.75	Full Depth Patching and 1.5" S9.5B	$481,250
2029	14	045-Henderson	Resurfacing	SR 1331	NC-191	SR-1314	2.04	Full Depth Patching and 1.5" S9.5B	$561,000
2029	14	045-Henderson	Resurfacing	SR 1351	SR-1354	NC 191 (Old Haywood Rd)	1.36	Full Depth Patching and 1.5" S9.5B	$373,450
2029	14	045-Henderson	Resurfacing	SR 1354	SR-1352	SR-1351	0.15	Full Depth Patching and 1.5" S9.5B	$41,250
2029	14	045-Henderson	Resurfacing	SR 1359	SR-1358	Buncombe County Line	0.92	Full Depth Patching and 1.5" S9.5B	$254,100
2029	14	045-Henderson	Resurfacing	SR 1383	SR-1381	US 25	1.96	Full Depth Patching and 1.5" S9.5B	$538,175
2029	14	045-Henderson	Resurfacing	SR 1557	SR-1528	MP 0.80	0.80	Full Depth Patching and 1.5" S9.5B	$220,000
2029	14	045-Henderson	Resurfacing	SR 1574	US 64	MP 1.4	1.40	Full Depth Patching and 1.5" S9.5B	$385,000
2029	14	045-Henderson	Resurfacing	SR 1645	SR-1528	Cul-de-sac	0.64	Full Depth Patching and 1.5" S9.5B	$176,000
2029	14	045-Henderson	Resurfacing	SR 2139	SR-1261	Cul-de-sac	0.06	Full Depth Patching and 1.5" S9.5B	$16,500
2029	14	045-Henderson	Preservation	SR 1132	SR 1127	DEAD END	0.41	Seal - Double and Fog Seal	$28,560
2029	14	045-Henderson	Preservation	SR 1138	SR-1171	SR-1440	0.40	Seal - Double and Fog Seal	$28,070
2029	14	045-Henderson	Preservation	SR 1211	US 64	Dead End	1.62	Seal - Double and Fog Seal	$113,400
2029	14	045-Henderson	Preservation	SR 1212	US 64	SR-1213	0.34	Seal - Double and Fog Seal	$23,520
2029	14	045-Henderson	Preservation	SR 1241	SR 1132	DEAD END	0.22	Seal - Double and Fog Seal	$15,330
2029	14	045-Henderson	Preservation	SR 1246	US 64	SR-1248	0.12	Seal - Double and Fog Seal	$8,400
2029	14	045-Henderson	Preservation	SR 1248	Dead End	SR-1246	0.09	Seal - Double and Fog Seal	$6,300
2029	14	045-Henderson	Preservation	SR 1360	US 25	DEAD END	0.30	Seal - Double and Fog Seal	$21,000
2029	14	045-Henderson	Preservation	SR 1553	SR 1553	SR 1571	1.84	Seal - Double and Fog Seal	$128,800
2029	14	045-Henderson	Preservation	SR 1571	SR 1569	SR 1553	0.51	Seal - Double and Fog Seal	$35,700
2029	14	045-Henderson	Preservation	SR 1594	SR-1693	SR-1569	2.38	Seal - Mat and Triple Seal	$166,600
2029	14	045-Henderson	Preservation	SR 1735	SR-1783	SR- 1734	0.96	Seal - Double and Fog Seal	$67,200
2029	14	045-Henderson	Preservation	SR 1798	SR-1783	SR-1799	0.47	Seal - Double and Fog Seal	$32,900
2029	14	045-Henderson	Preservation	SR 1799	SR-1783	MP 3.33	3.33	Seal - Double and Fog Seal	$233,100
2029	14	045-Henderson	Preservation	SR 1809	SR-1812	US 176	0.34	Seal - Double and Fog Seal	$24,010
2029	14	045-Henderson	Preservation	SR 1811	US 176	PVMT CHNG	0.69	Seal - Double and Fog Seal	$48,580
2029	14	045-Henderson	Preservation	SR 1828	US 176	US 176	0.29	Seal - Double and Fog Seal	$20,510
2029	14	045-Henderson	Preservation	SR 1975	SR-1557	CUL-DE-SAC	0.22	Seal - Double and Fog Seal	$15,400
2029	14	045-Henderson	Preservation	SR 1976	SR-1965	CUL-DE-SAC	0.06	Seal - Double and Fog Seal	$4,200
2029	14	045-Henderson	Preservation	SR 1977	SR-1627	SR-2304	0.54	Seal - Double and Fog Seal	$37,660
2029	14	045-Henderson	Preservation	SR 2025	US 25	MP 0.509	0.51	Seal - Double and Fog Seal	$35,630
2029	14	045-Henderson	Preservation	SR 2238	SR 1354	DEAD END	0.11	Seal - Double and Fog Seal	$7,700
2029	14	050-Jackson	Resurfacing	SR 1169	SR 1002	SR 1325	0.34	Patching and 1.25" S9.5A	$93,500
2029	14	050-Jackson	Resurfacing	SR 1405	US 74	US 441	2.06	Patching and 1.25" S9.5A	$565,250
2029	14	050-Jackson	Resurfacing	SR 1427	SR 1406	US 19	2.43	Patching and 1.25" S9.5A	$688,250
2029	14	050-Jackson	Resurfacing	SR 1724	NC 107	EOP	1.56	Patching and 1.25" S9.5A	$429,000
2029	14	050-Jackson	Resurfacing	SR 1734	SR 1002	EOM	0.22	Patching and 1.25" S9.5A	$60,500
2029	14	050-Jackson	Resurfacing	US 23 Bus	Pvmt Chnge 0.28 Mi. N. of SR 1432 (Skyland Dr)	US 23/74	1.16	Mill 1.5" and 1.5" S9.5C	$319,000
2029	14	050-Jackson	Resurfacing	US 23/441N	Pvmt Change (.33 miles N of SR 1310)	vmt Change (.39 miles N of SR 130(	2.07	Mill 1.5" and 1.5" S9.5C	$1,000,000
2029	14	050-Jackson	Resurfacing	US 23/441N	SR 1300	vmt Change (.39 miles N of SR 130(	0.41	Mill 1.5" and 1.5" S9.5C	$250,000
2029	14	050-Jackson	Resurfacing	US 23/441N	Pvmt Change (.39 miles N of SR 1300)	vmt Change (.33 miles N of SR 131(	2.08	Mill 1.5" and 1.5" S9.5C	$1,000,000
2029	14	050-Jackson	Resurfacing	US 23/441N	Pvmt Change (.39 miles N of SR 1300)	SR 1300	0.40	Mill 1.5" and 1.5" S9.5C	$250,000
2029	14	050-Jackson	Preservation	SR 1756	SR 1757	NC 215	7.69	Seal - Double and Fog Seal	$346,080
2029	14	050-Jackson	Preservation	SR 1756	NC 281	SR 1757	3.13	Seal - Double and Fog Seal	$219,100
2029	14	056-Macon	Resurfacing	SR 1146	US 64	SR 1148	1.71	Full Depth Patching and 1.25" S9.5B	$470,250
2029	14	056-Macon	Resurfacing	SR 1335	NC 28	US 23	3.26	Full Depth Patching and 1.25" S9.5B	$896,500
2029	14	056-Macon	Resurfacing	SR 1412	SR 1415	SR 1414	0.87	1.25" S9.5B	$239,250
2029	14	056-Macon	Resurfacing	SR 1667	SR 1653	SR 1668	0.54	1.5" S9.5B	$148,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2029	14	056-Macon	Resurfacing	US 441B	Panther Drive (High School)	SR 1442	0.31	Full Depth Patching and 1.5" S9.5B	$150,000
2029	14	056-Macon	Resurfacing	US 441B	.05N of SR 1324	.05N of SR 1510	0.60	Full Depth Patching and 1.5" S9.5B	$250,000
2029	14	056-Macon	Preservation	SR 1303	SR 1302	SR 1448	2.13	Seal - Double and Fog Seal	$149,100
2029	14	056-Macon	Preservation	SR 1311	SR 1442	END MAINT	0.43	Seal - Double and Fog Seal	$30,100
2029	14	056-Macon	Preservation	SR 1315	SR 1314	END MAINT	0.66	Seal - Double and Fog Seal	$46,200
2029	14	056-Macon	Preservation	SR 1320	SR 1319	END MAINT	0.27	Seal - Double and Fog Seal	$18,900
2029	14	056-Macon	Preservation	SR 1332	SR 1331	EOP	0.23	Seal - Double	$15,960
2029	14	056-Macon	Preservation	SR 1422	SR 1337	END MAINT	0.32	Seal - Double and Fog Seal	$22,540
2029	14	056-Macon	Preservation	SR 1432	SR 1337	SR 1432	1.54	Seal - Double and Fog Seal	$107,520
2029	14	056-Macon	Preservation	SR 1512	SR 1574	SR 1571	0.53	Seal - Double and Fog Seal	$37,100
2029	14	056-Macon	Preservation	SR 1515	SR 1573	END MAINT	0.38	Seal - Double and Fog Seal	$26,600
2029	14	056-Macon	Preservation	SR 1560	US 64	DEAD END	0.42	Seal - Double and Fog Seal	$29,400
2029	14	056-Macon	Preservation	SR 1570	US 23	END PVMT	0.40	Seal - Double and Fog Seal	$28,000
2029	14	056-Macon	Preservation	SR 1649	US 441	SR 1652	0.97	Seal - Double and Fog Seal	$67,900
2029	14	056-Macon	Preservation	SR 1702	US 23	SR 1700 + 0.14 miles	0.17	Seal - Double and Fog Seal	$11,900
2029	14	056-Macon	Preservation	SR 1728	SR 1653	SR 1653	1.07	Seal - Double and Fog Seal	$74,900
2029	14	075-Polk	Resurfacing	SR 1332	SR 1330	SR 13333	1.60	1.25" S9.5B	$480,000
2029	14	075-Polk	Resurfacing	SR 1346	SR 1348	DEAD END	1.65	1.25" S9.5B	$495,600
2029	14	075-Polk	Resurfacing	SR 1361	SR 1343	MP 0.62	0.62	1.25" S9.5B	$186,000
2029	14	075-Polk	Resurfacing	SR 1520	SR 1522	SR 1524	1.44	1.25" S9.5B	$433,200
2029	14	075-Polk	Resurfacing	SR 1527	SR 1525	MP 0.54	0.54	1.25" S9.5B	$162,000
2029	14	075-Polk	Preservation	SR 1165	NC 9	Polk CL	1.85	Seal - Double and Fog Seal	$129,500
2029	14	075-Polk	Preservation	SR 1168	NC 9	EOP	0.78	Seal - Double and Fog Seal	$54,320
2029	14	075-Polk	Preservation	SR 1201	NC 9	EOP	3.56	Seal - Double and Fog Seal	$249,270
2029	14	087-Swain	Resurfacing	SR 1355	US 19	SR 1356	1.48	Patching and Leveling and 1.5" S9.5A	$407,000
2029	14	087-Swain	Resurfacing	SR 1362	SR 1355	EOM	0.60	Patching and 1.25" S9.5A	$165,000
2029	14	087-Swain	Preservation	SR 1177	SR 1178	EOM	3.87	Seal - Double and Fog Seal	$270,900
2029	14	087-Swain	Preservation	SR 1197	SR 1177	EOM	0.32	Seal - Double and Fog Seal	$22,400
2029	14	087-Swain	Preservation	SR 1370	US 19	EOM	0.39	Seal - Double and Fog Seal	$27,300
2029	14	087-Swain	Preservation	SR 1371	SR 1351	EOM	0.39	Seal - Double and Fog Seal	$27,300
2029	14	088-Transylvania	Resurfacing	SR 1105	SR 1107	MP .6	0.60	1.25" S9.5B	$165,000
2029	14	088-Transylvania	Resurfacing	SR 1112	US 276	SR 1110	0.57	Full Depth Patching and 1.5" S9.5B	$156,475
2029	14	088-Transylvania	Resurfacing	SR 1324	NC 215	SR 1325	1.47	1.25" S9.5B	$403,150
2029	14	088-Transylvania	Resurfacing	SR 1327	SR 1328	BRIDGE	1.27	1.75" S9.5B	$348,700
2029	14	088-Transylvania	Resurfacing	SR 1398	SR 1400	EOM	0.29	1.25" S9.5B	$79,750
2029	14	088-Transylvania	Resurfacing	SR 1510	US 64	SR 1504	0.23	Full Depth Patching and 1.5" S9.5B	$63,250
2029	14	088-Transylvania	Resurfacing	SR 1546	SR 1504	SR 1544	0.98	Full Depth Patching and 1.5" S9.5B	$269,500
2029	14	088-Transylvania	Resurfacing	US 64	US 178	Divided Hwy	4.37	Full Depth Patching and 1.5" S9.5B	$1,400,000
2029	14	088-Transylvania	Preservation	SR 1114	SR 1116	US 64	1.09	Seal - Double and Fog Seal	$76,300
2029	14	088-Transylvania	Preservation	SR 1123	SR 1208	SR 1114	0.91	Seal - Double and Fog Seal	$63,700
2029	14	088-Transylvania	Preservation	SR 1124	SR 1114	EMO	0.50	Seal - Double and Fog Seal	$35,000
2029	14	088-Transylvania	Preservation	SR 1125	SR 1161	EOM	1.05	Seal - Double and Fog Seal	$73,500
2029	14	088-Transylvania	Preservation	SR 1161	US 64	SR 1110	0.44	Seal - Double and Fog Seal	$30,800
2029	14	088-Transylvania	Preservation	SR 1179	SR 1110	EOM	0.05	Seal - Double and Fog Seal	$3,430
2029	14	088-Transylvania	Preservation	SR 1337	US 64	EOM	0.75	Seal - Double and Fog Seal	$52,290
2029	14	088-Transylvania	Preservation	SR 1338	US 64	SR 1401	0.81	Seal - Double and Fog Seal	$56,700
2029	14	088-Transylvania	Preservation	SR 1354	SR 1353	EOM	0.11	Seal - Double and Fog Seal	$7,700
2029	14	088-Transylvania	Preservation	SR 1523	SR 1528	EOM	0.72	Seal - Double and Fog Seal	$50,400
2029	14	088-Transylvania	Preservation	SR 1592	US 64	EOM	0.21	Seal - Double and Fog Seal	$14,700
2030	1	008-Bertie	Resurfacing	NC 11	End C&G	Hetford County Line	0.29	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$82,000
2030	1	008-Bertie	Resurfacing	NC 11 (East Main St.)	NC 305	End C&G	0.72	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$254,000
2030	1	008-Bertie	Resurfacing	SR 1001 (Wakelon Rd.)	US 17	Pavement Joint	0.90	Full Depth Patching and 1.5" S9.5B	$216,000
2030	1	008-Bertie	Resurfacing	SR 1001 (Wakelon Rd.)	SR 1366 (Bakertown Rd.)	SR 1301 (Bull Hill Rd.)	1.71	Full Depth Patching and 1.5" S9.5B	$342,000
2030	1	008-Bertie	Resurfacing	SR 1108 (Indian Woods Rd.)	SR 1124 (Green Pond Rd.)	SR 1122 (Broad Neck Rd.)	2.65	Full Depth Patching and 1.5" S9.5B	$556,000
2030	1	008-Bertie	Resurfacing	SR 1131 (Flag Run Rd.)	Begin Pavement	SR 1132 (Oak Dr.)	0.65	Full Depth Patching and 1.5" S9.5B	$130,000
2030	1	008-Bertie	Resurfacing	SR 1133 (Burch Rd.)	NC 308	End of Pavement	0.80	Full Depth Patching and 1.5" S9.5B	$160,000
2030	1	008-Bertie	Resurfacing	SR 1145 (Cashie St.)	NC 308	NC 11	0.48	Full Depth Patching and 1.5" S9.5B	$95,000
2030	1	008-Bertie	Resurfacing	SR 1145 (Main St.)	Begin C&G	NC 308	0.13	Full Depth Patching and 1.5" S9.5B	$25,000
2030	1	008-Bertie	Resurfacing	SR 1145 (Main St.)	NC 11	Begin C&G	1.06	Full Depth Patching and 1.5" S9.5B	$212,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	1	008-Bertie	Resurfacing	SR 1300 (Green Cross Rd.)	SR 1390	Pavement Joint	0.88	Full Depth Patching and 1.5" S9.5B	$211,000
2030	1	008-Bertie	Resurfacing	SR 1360 (Ashland Church Rd.)	NC 45	SR 1358	0.99	Full Depth Patching and 1.5" S9.5B	$198,000
2030	1	008-Bertie	Resurfacing	SR 1503 (Davis Rd.)	Dead End	US 17	0.90	Full Depth Patching and 1.5" S9.5B	$181,000
2030	1	008-Bertie	Resurfacing	SR 1535 (Laytonl Rd.)	NC 45	End of Pavement	0.24	Full Depth Patching and 1.5" S9.5B	$48,000
2030	1	008-Bertie	Resurfacing	SR 1540 (Old Merry Hill Rd.)	NC 45	SR 1502(Avoca Rd.)	2.12	Full Depth Patching and 1.5" S9.5B	$423,000
2030	1	008-Bertie	Resurfacing	SR 1547 (Bachelor Bay Dr.)	NC 45	End of Maintenance	1.50	Full Depth Patching and 1.5" S9.5B	$300,000
2030	1	008-Bertie	Preservation	SR 1344 Perrytown Rd.)	SR 1345 (Cale Rd.)	SR 1001 (Wakelon Rd.)	3.35	Seal - Double	$176,000
2030	1	008-Bertie	Preservation	SR 1345 (Cale Rd.)	SR 1344 (Perrytown Rd.)	Dead End	0.71	Seal - Double	$35,000
2030	1	008-Bertie	Preservation	SR 1348 (Brown's School Rd.)	SR 1344 (Perrytown Rd.)	SR 1301 (Bull Hill Rd.)	3.52	Seal - Double	$176,000
2030	1	008-Bertie	Preservation	SR 1364 (Ledrew Perry Rd.)	US 17	NC 45	3.44	Seal - Double	$172,000
2030	1	008-Bertie	Preservation	SR 1365 (Capehart Church Rd.)	SR 1301 (Bull Hill Rd.)	SR 1364 (Ledrew Perry Rd.)	3.24	Seal - Double	$162,000
2030	1	015-Camden	Resurfacing	NC 343	US 158	US 17 Bus.	12.26	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$3,741,000
2030	1	015-Camden	Resurfacing	SR 1104 (Wharf Rd)	NC 343	Dead End	1.54	Full Depth Patching and 1.5" S9.5B	$292,000
2030	1	015-Camden	Resurfacing	SR 1115 (Garrington Island Rd.)	SR 1107 (Sandy Hook Rd.)	Dead EndDead End	1.11	Full Depth Patching and 1.5" S9.5B	$178,000
2030	1	015-Camden	Resurfacing	SR 1131 (Whitehall Rd)	SR 1132 (Country Club Rd)	SR 1152 (Magnolia Dr)	0.24	Full Depth Patching and 1.5" S9.5B	$48,000
2030	1	015-Camden	Resurfacing	SR 1150 (Pinewood Dr)	SR 1131 (Whitehall Rd)	SR 1170 (Wisteria Dr)	0.12	Full Depth Patching and 1.5" S9.5B	$22,000
2030	1	015-Camden	Resurfacing	SR 1151 (Dogwood)	SR 1131 (Whitehall Rd)	SR 1170 (Wisteria Dr)	0.25	Full Depth Patching and 1.5" S9.5B	$50,000
2030	1	015-Camden	Resurfacing	SR 1152 (Magnolia Dr)	SR 1131 (Whitehall Rd)	SR 1167 (Azalea Rd)	0.17	Full Depth Patching and 1.5" S9.5B	$34,000
2030	1	015-Camden	Resurfacing	SR 1153 (Windy Height Dr)	SR 1152 (Magnolia Dr)	Dead EndDead End	0.20	Full Depth Patching and 1.5" S9.5B	$36,000
2030	1	015-Camden	Resurfacing	SR 1166 (Japonica/Valley Rd)	SR 1131 (Whitehall Rd)	Sr 1173 (River Rd)	0.56	Full Depth Patching and 1.5" S9.5B	$112,000
2030	1	015-Camden	Resurfacing	SR 1168 (Canal St)	SR 1166 (Japonica/Valley Rd)	Dead EndDead End	0.09	Full Depth Patching and 1.5" S9.5B	$18,000
2030	1	015-Camden	Resurfacing	SR 1169 (Holly Dr)	SR 1131 (Whitehall Rd)	SR 1170 (Wisteria Dr)	0.26	Full Depth Patching and 1.5" S9.5B	$52,000
2030	1	015-Camden	Resurfacing	Sr 1173 (River Rd)	SR 1166 (Japonica/Valley Rd)	Dead EndDead End	0.08	Full Depth Patching and 1.5" S9.5B	$16,000
2030	1	015-Camden	Resurfacing	SR 1205 (Shipyard Rd)	NC 343	Dead EndDead End	1.01	Full Depth Patching and 1.5" S9.5B	$182,000
2030	1	015-Camden	Resurfacing	US 17 NBL	SR 1231 (McPherson Rd.)	Virginia State Line	3.18	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,044,000
2030	1	015-Camden	Resurfacing	US 17 NBL	Bridge #44	SR 1231 (McPherson Rd.)	3.60	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,185,000
2030	1	015-Camden	Resurfacing	US 17 NBL	Bridge #88 @ Pasquotank County Line	Bridge #44	2.36	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$775,000
2030	1	015-Camden	Resurfacing	US 17 SBL	SR 1231 (McPherson Rd.)	Bridge #43	3.59	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,180,000
2030	1	015-Camden	Resurfacing	US 17 SBL	Bridge #89 @ Pasquotank County Line	Bridge #43	2.38	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$781,000
2030	1	015-Camden	Resurfacing	US 17 SBL	Virginia State Line	SR 1231 (McPherson Rd.)	3.18	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,045,000
2030	1	015-Camden	Preservation	SR 1165 (Jordan Ln.)	NC 343	Dead End	0.37	1.25" S9.5B	$45,000
2030	1	015-Camden	Preservation	SR 1179 Tulip Tree Dr	NC 343	Dead End	0.39	Microsurface	$23,000
2030	1	015-Camden	Preservation	SR 1180 N Cherry Blossom	SR 1179 Tulip Tree Dr	Dead End	0.13	Microsurface	$8,000
2030	1	015-Camden	Preservation	SR 1181 S Cherry Blossom	SR 1179 Tulip Tree Dr	Dead End	0.14	Microsurface	$9,000
2030	1	015-Camden	Preservation	SR 1182 Applewood Ct	SR 1181 S Cherry Blossom	Dead End	0.07	Microsurface	$5,000
2030	1	021-Chowan	Resurfacing	NC 37	Perquimans County Line	NC 32	4.26	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,253,000
2030	1	021-Chowan	Resurfacing	SR 1100 (Drummonds Point Rd)	SR 1102 (Yeopim Rd.)	SR 1108 (Indian Trail Rd)	3.33	Full Depth Patching and 1.5" S9.5B	$665,000
2030	1	021-Chowan	Resurfacing	SR 1101 (Burnt Mill rd)	Perquimans County Line	SR 1102 (Yeopim Rd.)	0.96	Full Depth Patching and 1.5" S9.5B	$192,000
2030	1	021-Chowan	Resurfacing	SR 1101 (Thick Neck Rd.)	SR 1102 (Yeopim Rd.)	NC 37	0.64	Full Depth Patching and 1.5" S9.5B	$128,000
2030	1	021-Chowan	Resurfacing	SR 1116 (Alexander/Oak Grove Rd.)	SR 1102 (Yeopim Rd.)	End of Pavement	1.08	Full Depth Patching and 1.5" S9.5B	$216,000
2030	1	021-Chowan	Resurfacing	SR 1204 (Emperor Landing Rd)	SR 1203 (Emperor Landing Rd.)	SR 1204 (W Queen St.)	0.38	Full Depth Patching and 1.5" S9.5B	$76,000
2030	1	021-Chowan	Resurfacing	SR 1239 (Emperor Landing Rd)	SR 1202 (Hickory Fork Rd)	SR 1204 (W Queen St.)	0.31	Full Depth Patching and 1.5" S9.5B	$62,000
2030	1	021-Chowan	Preservation	SR 1158 (Snow Hill Rd.)	Dead End	SR 1108 (Indian Trail Rd.)	0.32	1.0" S9.5B	$39,000
2030	1	021-Chowan	Preservation	SR 1217 (Rockyhock Landing Rd)	SR 1222 (Rockyhock Rd)	End of Pavement	1.55	1.0" S9.5B	$189,000
2030	1	027-Currituck	Resurfacing	SR 1100 (S. Albetuck Rd)	US 158	Dead End	0.35	Full Depth Patching and 1.5" S9.5B	$63,000
2030	1	027-Currituck	Resurfacing	SR 1101 (Griggs Acres Rd)	US 158	SR 1163 (Griggs Acres Rd)	0.53	Full Depth Patching and 1.5" S9.5B	$96,000
2030	1	027-Currituck	Resurfacing	SR 1102 (Pinegrove Rd)	US 158	Dead End	0.19	Full Depth Patching and 1.5" S9.5B	$31,000
2030	1	027-Currituck	Resurfacing	SR 1107 (Church Rd)	US 158	Dead End	0.74	Full Depth Patching and 1.5" S9.5B	$133,000
2030	1	027-Currituck	Resurfacing	SR 1111 (S. Spot Rd.)	US 158	Dead End	1.30	1.5" S9.5B	$260,000
2030	1	027-Currituck	Resurfacing	SR 1113 (N. Spot Rd.)	US 158	SR 1111 (S. Spot Rd.)	1.60	1.5" S9.5B	$320,000
2030	1	027-Currituck	Resurfacing	SR 1115 (Snows Ln)	US 158	End of Pavement	0.25	Full Depth Patching and 1.5" S9.5B	$45,000
2030	1	027-Currituck	Resurfacing	SR 1127 (Garrenton Rd.)	SR 1125 (Grandy Rd.)	US 158	0.76	1.5" S9.5B	$152,000
2030	1	027-Currituck	Resurfacing	SR 1163 (Griggs Acres Dr)	Culdesac	Culdesac	0.65	Full Depth Patching and 1.5" S9.5B	$117,000
2030	1	027-Currituck	Resurfacing	SR 1429 (Reggie Owens Dr.)	SR 1103 (Harbinger Ridge Rd)	SR 1431 (Waterside Dr)	0.55	Full Depth Patching and 1.5" S9.5B	$110,000
2030	1	027-Currituck	Resurfacing	SR 1435 (Arnold Dr)	US 158	Dead End	0.25	Full Depth Patching and 1.5" S9.5B	$45,000
2030	1	027-Currituck	Resurfacing	SR 1459 (James Griggs Rd)	US 158	Dead End	0.25	Full Depth Patching and 1.5" S9.5B	$55,000
2030	1	027-Currituck	Resurfacing	SR 1468 (Pan Ridge Ct)	US 158	Dead End	0.13	Full Depth Patching and 1.5" S9.5B	$29,000
2030	1	027-Currituck	Preservation	SR 1326 Evergreen Dr	SR 1216 Puddin Ridge Rd	SR 1328 Oakdale Dr	0.14	1.25" S9.5B	$16,000
2030	1	027-Currituck	Preservation	SR 1327 Woodland Ct	SR 1328 Oakdale Dr	End	0.17	1.25" S9.5B	$19,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	1	027-Currituck	Preservation	SR 1328 Oakdale Dr	SR 1329 Beechwood Dr	End	0.16	1.25" S9.5B	$18,000
2030	1	027-Currituck	Preservation	SR 1329 Beechwood Dr	SR 1216 Puddin Ridge Rd	SR 1328 Oakdale Dr	0.12	1.25" S9.5B	$14,000
2030	1	027-Currituck	Preservation	SR 1330 Laurel CT	SR 1328 Oakdale Dr	Dead End	0.13	1.25" S9.5B	$15,000
2030	1	027-Currituck	Preservation	SR 1340 South Landing DR	SR 1228 Camellia DR	SR 1111 (S. Spot Rd.)	0.20	1.25" S9.5B	$25,000
2030	1	027-Currituck	Preservation	SR 1351 Streamdale Ct	SR 1216 Puddin Ridge Rd	End	0.20	1.25" S9.5B	$22,000
2030	1	027-Currituck	Preservation	SR 1352 Covey Lane	SR 1353 Quail Rd DR	SR 1351 Streamdale Ct	0.16	1.25" S9.5B	$18,000
2030	1	027-Currituck	Preservation	SR 1353 Quail Rd DR	SR 1216 Puddin Ridge Rd	End	0.71	1.25" S9.5B	$78,000
2030	1	027-Currituck	Preservation	SR 1355 Birchview Ct	SR 1353 Quail Rd DR	End	0.18	1.25" S9.5B	$20,000
2030	1	027-Currituck	Preservation	SR 1363 Jae Ct	SR 1216 Puddin Ridge Rd	US 158	0.27	1.25" S9.5B	$33,000
2030	1	027-Currituck	Preservation	SR 1376 E White Pine Dr	SR 1353 Quail Rd DR	End	0.23	1.25" S9.5B	$26,000
2030	1	027-Currituck	Preservation	SR 1377 Alder Lane	SR 1353 Quail Rd DR	SR 1378 Brookdale Ct	0.18	1.25" S9.5B	$20,000
2030	1	027-Currituck	Preservation	SR 1378 Brookdale Ct	End	End	0.23	1.25" S9.5B	$26,000
2030	1	027-Currituck	Preservation	SR 1547 Northwest River Dr	SR 1230 Mack Jones Rd	End	0.31	1.25" S9.5B	$38,000
2030	1	028-Dare	Resurfacing	NC 12	End of Jug Handle Bridge	SR 1470	0.31	1.5" S9.5C	$74,000
2030	1	028-Dare	Resurfacing	SR 1226-McMullen St.	SR 1224-Harbor Rd.	SR 1224-Harbor Rd.	0.46	Full Depth Patching and 1.5" S9.5B	$92,000
2030	1	028-Dare	Resurfacing	SR 1226-Reef Dr.	CDS	SR 1224-Harbor Rd.	0.20	Full Depth Patching and 1.5" S9.5B	$40,000
2030	1	028-Dare	Resurfacing	SR 1282-Hatteras Lane	NC 12	Jollie Rd	0.10	Full Depth Patching and 1.5" S9.5B	$22,000
2030	1	028-Dare	Resurfacing	SR 1419-Greenwood Place	NC 12	CDS	0.32	Full Depth Patching and 1.5" S9.5B	$64,000
2030	1	028-Dare	Resurfacing	SR 1420-Kinnakeet Dr.	NC 12	SR 1419-Greenwood Place	0.05	Full Depth Patching and 1.5" S9.5B	$10,000
2030	1	028-Dare	Resurfacing	SR 1421-Ocean View Dr.	SR 1521-Tern St.	CDS	0.77	Full Depth Patching and 1.5" S9.5B	$155,000
2030	1	028-Dare	Resurfacing	SR 1422-Pampas ST.	NC 12	SR 1421-Ocean View Dr.	0.06	Full Depth Patching and 1.5" S9.5B	$12,000
2030	1	028-Dare	Resurfacing	SR 1423-Myrtle St.	NC 12	SR 1421-Ocean View Dr.	0.06	Full Depth Patching and 1.5" S9.5B	$12,000
2030	1	028-Dare	Resurfacing	SR 1424-Seaside St.	NC 12	SR 1421-Ocean View Dr.	0.06	Full Depth Patching and 1.5" S9.5B	$13,000
2030	1	028-Dare	Resurfacing	SR 1485-Kinnakeet Dr.	NC 12	SR 1486-Pheasant Circle	0.04	Full Depth Patching and 1.5" S9.5B	$8,000
2030	1	028-Dare	Resurfacing	SR 1486-Pheasant Circle	SR 1485-Kinnakeet Dr.	CDS	0.16	Full Depth Patching and 1.5" S9.5B	$32,000
2030	1	028-Dare	Resurfacing	SR 1488-Cedar Circle	SR 1485-Kinnakeet Dr.	CDS	0.16	Full Depth Patching and 1.5" S9.5B	$32,000
2030	1	028-Dare	Resurfacing	SR 1494-Moore Way	NC 12	CDS	0.09	Full Depth Patching and 1.5" S9.5B	$18,000
2030	1	028-Dare	Resurfacing	SR 1500-Nova Dr.	NC 12	Dead End	0.09	Full Depth Patching and 1.5" S9.5B	$20,000
2030	1	028-Dare	Resurfacing	SR 1501-Kinnakeet Dr. North	NC 12	CDS	0.09	Full Depth Patching and 1.5" S9.5B	$18,000
2030	1	028-Dare	Resurfacing	SR 1524-Tern St.	NC 12	SR 1421-Ocean View Dr.	0.05	Full Depth Patching and 1.5" S9.5B	$10,000
2030	1	028-Dare	Preservation	SR 1261-Angelfish Rd.	NC 12	Dead End	0.10	1.0" S9.5B	$13,000
2030	1	028-Dare	Preservation	SR 1263-Sailfish Lane	NC 12	CDS	0.10	1.0" S9.5B	$13,000
2030	1	028-Dare	Preservation	SR 1264-Sandfiddler Lane	NC 12	CDS	0.08	1.0" S9.5B	$10,000
2030	1	028-Dare	Preservation	SR 1269-Water Assoc. Rd.	NC 12	End Maint	0.30	1.0" S9.5B	$37,000
2030	1	028-Dare	Preservation	SR 1279-Bonito Rd.	NC 12	Dead End	0.15	1.0" S9.5B	$19,000
2030	1	028-Dare	Preservation	SR 1280-Ocean Lane	NC 12	Jollie Rd	0.11	1.0" S9.5B	$14,000
2030	1	028-Dare	Preservation	SR 1284-Seashore Blvd.	SR 1278-S. Albacore Lane	NC 12	0.16	1.0" S9.5B	$20,000
2030	1	028-Dare	Preservation	SR 1427-Laughing Gull Lane	CDS	NC 12	0.24	1.0" S9.5B	$30,000
2030	1	028-Dare	Preservation	SR 1431-Colony Dr.	End Maint	NC 12	0.94	1.0" S9.5B	$115,000
2030	1	037-Gates	Resurfacing	SR 1303 (Parker Rd)	SR 1300 (Medical Center Rd.)	NC 37	2.39	Full Depth Patching and 1.5" S9.5B	$501,000
2030	1	037-Gates	Resurfacing	SR 1318 (Middle Swamp Rd)	SR 1319 (Clay Hill Rd.)	SR 1305 (Union Branch Rd.)	4.59	Full Depth Patching and 1.5" S9.5B	$962,000
2030	1	037-Gates	Resurfacing	SR 1330 (Adam Swamp Rd)	NC 32	Virginia State Line	1.47	Full Depth Patching and 1.5" S9.5B	$294,000
2030	1	037-Gates	Resurfacing	SR 1333 (Desert Rd)	SR 1332 (Daniels Rd.)	Virginia State Line	1.03	Full Depth Patching and 1.5" S9.5B	$206,000
2030	1	037-Gates	Resurfacing	US 13 North	Hertford County Line	End Median Divided Hwy	6.08	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,426,000
2030	1	037-Gates	Resurfacing	US 13 South	Begin Median Divided Hwy	Hertford County Line	6.07	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,430,000
2030	1	037-Gates	Preservation	SR 1332 (Daniels Rd.)	SR 1333 (Desert Rd.)	NC 32	3.27	1.0" S9.5B	$398,000
2030	1	046-Hertford	Resurfacing	NC 11 (Millenium)	Bertie County Line	NC 42	1.55	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$546,000
2030	1	046-Hertford	Resurfacing	SR 1141 (Menola St. John Rd.)	NC 461	SR 1141 (Henry Brown Rd.)	3.67	Full Depth Patching and 1.5" S9.5B	$769,000
2030	1	046-Hertford	Resurfacing	SR 1218 (Industrial Park Rd.)	US 158	End of Pavement	0.50	Full Depth Patching and 1.5" S9.5B	$90,000
2030	1	046-Hertford	Resurfacing	SR 1413 (Willoughby Rd.)	SR 1409 (Ahoskie Cofield Rd.)	SR 1403 (Ahoskie Cofield Rd.)	1.63	Full Depth Patching and 1.5" S9.5B	$326,000
2030	1	046-Hertford	Resurfacing	SR 1425 (N. Main St.)	NC 45	SR 1448 (E. Brickell St.)	0.34	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$240,000
2030	1	046-Hertford	Resurfacing	SR 1425 (W. Brickell St..)	SR 1448 (E. Brickell St.)	End of Pavement	0.34	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$200,000
2030	1	046-Hertford	Resurfacing	SR 1445 (Bazemore Rd.)	SR 1469 (River d.)	End of Pavement	2.00	Full Depth Patching and 1.5" S9.5B	$360,000
2030	1	046-Hertford	Resurfacing	SR 1446 (Pritchard Farmd Rd.)	SR 1427 (Thomas Bridge Rd.)	NC 45	1.59	Full Depth Patching and 1.5" S9.5B	$318,000
2030	1	046-Hertford	Preservation	SR 1152 (Jim Hardy Rd.)	End Pavement	NC 561	2.73	Seal - Double	$137,000
2030	1	046-Hertford	Preservation	SR 1154 (Bakers Store Rd.)	SR 1155 (Fennell Rd.)	SR 1152 (Jim Hardy Rd.)	1.47	Seal - Double	$74,000
2030	1	046-Hertford	Preservation	SR 1156 (Lee Harmond Rd.)	Dead End	SR 1155 (Fennell Rd.)	0.35	Microsurface	$18,000
2030	1	046-Hertford	Preservation	SR 1171 (Talton Rd.)	Dead End	SR 1169 (Talton Rd.)	0.37	Microsurface	$20,000
2030	1	046-Hertford	Preservation	SR 1344 (Eleytown Rd.)	Dead End	SR 1303 (Mapletown Rd.)	0.70	Microsurface	$40,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	1	048-Hyde	Resurfacing	SR 1100 (Hill St.)	Dead End	US 264	0.27	Full Depth Patching and 1.5" S9.5B	$54,000
2030	1	048-Hyde	Resurfacing	SR 1103 (Lazy Lane Rd.)	SR 1104 (Goshen Rd.)	US 264	1.20	Full Depth Patching and 1.5" S9.5B	$240,000
2030	1	048-Hyde	Resurfacing	SR 1124 (Quarter Rd.)	SR 1128 (Oyster Creek Rd.)	NC 94	2.37	Full Depth Patching and 1.5" S9.5B	$473,000
2030	1	048-Hyde	Resurfacing	SR 1315 (Swamp Rd.)	SR 1311 (N. Lake Rd.)	US 264	2.08	Full Depth Patching and 1.5" S9.5B	$416,000
2030	1	048-Hyde	Preservation	SR 1138 (Rose Bay Loop)	US 264	US 264	0.29	Microsurface	$18,000
2030	1	048-Hyde	Preservation	SR 1140 (Germantown Rd.)	Dead End	SR 1141 (Hodges Rd.)	0.43	Microsurface	$26,000
2030	1	048-Hyde	Preservation	SR 1160 (Collins Lane)	End Pavement	SR 1104 (Goshen Rd.)	0.46	Microsurface	$27,000
2030	1	048-Hyde	Preservation	SR 1308 (Canal St.)	Dead End	SR 1305 (Piney Woods Rd.)	0.76	Microsurface	$45,000
2030	1	058-Martin	Resurfacing	NC 111	Pitt County Line	NC 11	3.54	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$997,000
2030	1	058-Martin	Resurfacing	NC 903	Pitt County Line	Begin C&G (Robersonville)	4.03	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,183,000
2030	1	058-Martin	Resurfacing	SR 1404 (Airport Rd)	SR 1138 (Everetts Rd)	SR 1409 (Wild Cat Rd)	0.35	Full Depth Patching and 1.5" S9.5B	$77,000
2030	1	058-Martin	Resurfacing	SR 1441 (Landfill Rd)	SR 1420 (McCaskey Rd)	End of Pavement	0.33	Full Depth Patching and 1.5" S9.5B	$66,000
2030	1	058-Martin	Resurfacing	SR 1442 (Cargill Rd)	SR 1420 (McCaskey Rd)	End of Pavement	0.19	Full Depth Patching and 1.5" S9.5B	$42,000
2030	1	058-Martin	Resurfacing	SR 1545 (Seymour Price Rd)	SR 1538 (Manning Rd)	Dead End	0.70	Full Depth Patching and 1.5" S9.5B	$140,000
2030	1	058-Martin	Resurfacing	SR 1546 (Barber Cutoff Rd)	SR 1538 (Manning Rd)	SR 1547 (Barber Rd)	0.63	Full Depth Patching and 1.5" S9.5B	$126,000
2030	1	058-Martin	Resurfacing	SR 1552 (Jerden Thicket)	US Hwy 64	SR 1510 (Maurice Brown Rd)	1.07	Full Depth Patching and 1.5" S9.5B	$214,000
2030	1	058-Martin	Resurfacing	SR 1552 (Jerden Thicket)	SR 1510 (Maurice Brown Rd)	SR 1587 (Cooper Ln)	0.98	Full Depth Patching and 1.5" S9.5B	$196,000
2030	1	058-Martin	Resurfacing	SR 1555 (Free Union Rd)	SR 1556 (Creek Rd)	SR 1552 (Jerden Thicket)	1.29	Full Depth Patching and 1.5" S9.5B	$232,000
2030	1	058-Martin	Resurfacing	SR 1555 (Free Union Rd)	SR 1557 (Piney Woods Rd)	SR 1556 (Creek Rd)	1.12	Full Depth Patching and 1.5" S9.5B	$202,000
2030	1	058-Martin	Resurfacing	SR 1557 (Piney Woods Rd)	SR 1558 (Uniontown Rd)	SR 1559 (Corinth Church Rd)	1.37	Full Depth Patching and 1.5" S9.5B	$274,000
2030	1	058-Martin	Resurfacing	SR 1557 (Piney Woods Rd)	SR 1559 (Corinth Church Rd)	US 64 W	1.18	Full Depth Patching and 1.5" S9.5B	$236,000
2030	1	058-Martin	Resurfacing	SR 1557 (Swinson Rd)	SR 1563 (Grey Farm Rd)	SR 1592 (Old Hwy 64)	0.94	Full Depth Patching and 1.5" S9.5B	$188,000
2030	1	058-Martin	Resurfacing	SR 1557 (Uniontown Rd)	SR 1592 (Old Hwy 64)	SR 1558 (Uniontown Rd)	1.79	Full Depth Patching and 1.5" S9.5B	$358,000
2030	1	058-Martin	Resurfacing	SR 1560 (Davis Rd)	SR 1559 (Corinth Church Rd)	SR 1592 (Old Hwy 64)	0.50	Full Depth Patching and 1.5" S9.5B	$100,000
2030	1	058-Martin	Resurfacing	SR 1565 (Pulp Mill Rd)	US 64	PVMT Change	1.04	Full Depth Patching and 1.5" S9.5B	$208,000
2030	1	058-Martin	Preservation	SR 1103 (Lee Rd.)	SR 1100 (Sweet Home Rd.)	SR 1106 (Joe Mobley Rd.)	2.51	Seal - Double	$126,000
2030	1	058-Martin	Preservation	SR 1308 (Black Rd.)	SR 1305 (Vanderford Rd.)	SR 1306 (Grimes Rd.)	1.37	Seal - Double	$69,000
2030	1	058-Martin	Preservation	SR 1552 (Jerden Thicket Rd.)	Washington Co	US 64	5.86	Seal - Double	$293,000
2030	1	066-Northampton	Resurfacing	SR 1311 (Jackson Bypass Rd.)	SR 1313 (Hargraves Rd.)	SR 1301 (Cornwallis Rd.)	3.69	Full Depth Patching and 1.5" S9.5B	$737,000
2030	1	066-Northampton	Resurfacing	SR 1314 (Pleasant Grove Rd.)	NC 186	SR 1311 (Jackson Bypass Rd.)	3.55	Full Depth Patching and 1.5" S9.5B	$709,000
2030	1	066-Northampton	Resurfacing	SR 1333 (Mt. Carmel Rd.)	SR 1311 (Jackson Bypass Rd.)	SR 1329 (Devils Racetrack Rd.)	3.17	Full Depth Patching and 1.5" S9.5B	$633,000
2030	1	066-Northampton	Resurfacing	SR 1341 (Tower Rd.)	NC 186	SR 1333 (Severn Rd.)	2.04	Full Depth Patching and 1.5" S9.5B	$407,000
2030	1	066-Northampton	Resurfacing	SR 1520 (Pinners Church Rd.)	NC 305	US 258	2.62	Full Depth Patching and 1.5" S9.5B	$471,000
2030	1	066-Northampton	Preservation	SR 1290 (Seminole Trail)	SR 1287 (Tuscarora Trail)	CDS	0.07	1.25" S9.5B	$5,000
2030	1	066-Northampton	Preservation	SR 1360 (Horne Rd.)	SR 1351 (Vaughans Creek Rd.)	SR 1358 (Deloatch Mill Rd.)	4.98	Seal - Double	$261,000
2030	1	066-Northampton	Preservation	SR 1505 (NCHS Rd.)	SR 1504 (Creeksville Rd.)	US 158	3.82	Seal - Double	$201,000
2030	1	066-Northampton	Preservation	SR 1511 (Bridgers Rd.)	SR 1502 (Griffintown Rd.)	SR 1515 (Collier Rd.)	1.36	Seal - Double	$72,000
2030	1	070-Pasquotank	Resurfacing	SR 1101 (Peartree Rd)	NC344 (Sawmill Rd)	SR 1169 (Four Forks Rd)	3.65	Full Depth Patching and 1.5" S9.5B	$874,000
2030	1	070-Pasquotank	Resurfacing	SR 1103 (Esclip Rd)	NC344	SR 1118 (Leigh Farm Rd)	4.95	Full Depth Patching and 1.5" S9.5B	$938,000
2030	1	070-Pasquotank	Resurfacing	SR 1134 (Ludford Rd.)	End Pavement	SR 1169 (Pitts Chapel Rd.)	0.88	Full Depth Patching and 1.5" S9.5B	$176,000
2030	1	070-Pasquotank	Preservation	SR 1348 Ferry Rd	US 17	Dead End	0.67	Microsurface	$40,000
2030	1	070-Pasquotank	Preservation	SR 1350 Horseshoe Rd	US 17	US 17	2.66	1.25" S9.5B	$259,000
2030	1	070-Pasquotank	Preservation	SR 1518 Whipple Ave	SR 1348 Ferry Rd	Dead End	0.10	Microsurface	$6,000
2030	1	070-Pasquotank	Preservation	SR 1519 Cutter's Lane	SR 1518 Whipple Ave	Dead End	0.14	1.25" S9.5B	$18,000
2030	1	072-Perquimans	Resurfacing	SR 1214 (Bay Branch Rd.)	SR 1200 (Bethany Church Rd.)	SR 1214 (Bay Branch Rd.)	1.10	Full Depth Patching and 1.5" S9.5B	$220,000
2030	1	072-Perquimans	Resurfacing	SR 1216 (Fowler Fork Rd.)	SR 1215 (Bagley Swamp Rd.)	SR 1214 (Swamp Rd.)	1.38	Full Depth Patching and 1.5" S9.5B	$276,000
2030	1	072-Perquimans	Resurfacing	SR 1218 (2 Mile Desert Rd.)	SR 1214 (Swamp Rd)	NC 37	2.13	Full Depth Patching and 1.5" S9.5B	$424,000
2030	1	072-Perquimans	Resurfacing	SR 1341 (Burnt Mill Rd.)	SR 1340 (Snug Harbor Rd.)	Chowan County Line	2.50	Full Depth Patching and 1.5" S9.5B	$499,000
2030	1	072-Perquimans	Resurfacing	SR 1343 (Hopewell Rd)	US 17	SR 1341 (Burnt Mill Rd.)	1.92	Full Depth Patching and 1.5" S9.5B	$345,000
2030	1	072-Perquimans	Resurfacing	SR 1434 (ARPDC St.)	SR 1336 (S. Church St.)	End of Maintenance	0.16	Full Depth Patching and 1.5" S9.5B	$36,000
2030	1	072-Perquimans	Preservation	SR 1432 (Pinewood Trail)	SR 1449 (Tranquility Lane)	SR 1429 (Holiday Lane)	0.37	1.25" S9.5B	$45,000
2030	1	072-Perquimans	Preservation	SR 1446 (Driftwood Rd.)	SR 1447 (Soundward Lane)	Dead End	0.12	1.25" S9.5B	$15,000
2030	1	072-Perquimans	Preservation	SR 1447 (Soundward Lane)	SR 1432 (Pinewood Trail)	SR 1446 (Driftwood Rd.)	0.34	1.25" S9.5B	$42,000
2030	1	072-Perquimans	Preservation	SR 1448 (Shady Lane)	SR 1449 (Tranquility Lane)	SR 1451 (Venture Lane)	0.33	1.25" S9.5B	$41,000
2030	1	072-Perquimans	Preservation	SR 1451 (Venture Lane)	SR 1448 (Shady Lane)	SR 1452 (Wildwood Drive)	0.32	1.25" S9.5B	$39,000
2030	1	072-Perquimans	Preservation	SR 1452 (Wildwood Drive)	SR 1453 (W Island Trail)	SR 1449 (Tranquility Lane)	0.22	1.25" S9.5B	$27,000
2030	1	072-Perquimans	Preservation	SR 1455 (Sailway Court)	SR 1454 (Clipper Drive)	Dead End	0.05	1.25" S9.5B	$7,000
2030	1	072-Perquimans	Preservation	SR 1462 (Sunset Circle)	SR 1458 (Sunset Circle)	SR 1458 (Sunset Circle)	0.23	1.25" S9.5B	$28,000
2030	1	072-Perquimans	Preservation	SR 1472 (Yeopim Drive)	SR 1407 (Riverview Drive)	Dead End	0.12	1.25" S9.5B	$15,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	1	089-Tyrrell	Resurfacing	NC 94	SR 1116 (Woodley Station Rd.)	Washington County Line	1.29	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$467,000
2030	1	089-Tyrrell	Resurfacing	SR 1209 (Sound Side Rd.)	SR 1211 (Riverneck Rd.)	SR 1215 (New Road Ext)	2.91	Full Depth Patching and 1.5" S9.5B	$581,000
2030	1	089-Tyrrell	Resurfacing	SR 1301 (Mills Rd./Levels Rd.)	NC 94	End of Pavement	2.50	Full Depth Patching and 1.5" S9.5B	$499,000
2030	1	089-Tyrrell	Resurfacing	SR 1302 (Levels Rd.)	SR 1301 (Mills Rd.)	End of Pavement	0.50	Full Depth Patching and 1.5" S9.5B	$100,000
2030	1	089-Tyrrell	Preservation	SR 1100 (Kilkenny Loop Rd.)	NC 94	NC 94	0.37	1.0" S9.5B	$45,000
2030	1	089-Tyrrell	Preservation	SR 1101 (Hunter Rd.)	NC 94	CDS	0.90	1.0" S9.5B	$110,000
2030	1	089-Tyrrell	Preservation	SR 1306 (Scotia Rd.)	NC 94	Dead End	0.50	1.0" S9.5B	$61,000
2030	1	089-Tyrrell	Preservation	SR 1322 (Kilkenny Rd.)	NC 94	Dead End	0.64	1.0" S9.5B	$78,000
2030	1	094-Washington	Resurfacing	NC 308	NC 32	NC45	7.22	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,033,000
2030	1	094-Washington	Resurfacing	NC 94	Tyrrell County Line	SR 1304 (Scuppernong Rd.)	4.54	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,641,000
2030	1	094-Washington	Resurfacing	SR 1104 (Reno Rd.)	SR 1100 (Long Ridge Rd.)	SR 1174 (Reno Rd.)	0.71	Full Depth Patching and 1.5" S9.5B	$142,000
2030	1	094-Washington	Resurfacing	SR 1106 (Morrattock Rd.)	SR 1100 (Long Ridge Rd.)	NC 32	2.12	Full Depth Patching and 1.5" S9.5B	$423,000
2030	1	094-Washington	Resurfacing	SR 1174 (Reno Rd.)	Dead End	SR 1104 (Reno Rd.)	0.70	Full Depth Patching and 1.5" S9.5B	$126,000
2030	1	094-Washington	Resurfacing	SR 1215 (Country Ln.)	SR 1117 (Styons Rd.)	End of Pavement	0.06	Full Depth Patching and 1.5" S9.5B	$12,000
2030	1	094-Washington	Resurfacing	SR 1303 (Jones White Rd.)	SR 1304 (Scuppernong Rd.)	MP 6.22	1.99	Full Depth Patching and 1.5" S9.5B	$397,000
2030	1	094-Washington	Resurfacing	SR 1304 (Scuppernog Rd.)	SR 1303 (Jones White Rd.)	NC 94	1.66	Full Depth Patching and 1.5" S9.5B	$332,000
2030	1	094-Washington	Preservation	SR 1105 (McNair Rd.)	SR 1100 (Long Ridge Rd.)	End Of Maintenance	0.86	Seal - Double	$43,000
2030	1	094-Washington	Preservation	SR 1319 (Cypress Shore Rd.)	NC 32	Dead End	0.99	1.0" S9.5B	$121,000
2030	1	094-Washington	Preservation	SR01156 (Mountain Canal Rd.)	SR 1166 (Lake Shore Rd.)	SR 1155 (Cherry Rd.)	3.31	Seal - Double	$166,000
2030	2	007-Beaufort	Resurfacing	SR 1158	NC 33	PITT CO	2.81	1.5" S9.5B	$560,000
2030	2	007-Beaufort	Resurfacing	SR 1174	NC 33	DEAD END	0.21	1.25" S9.5B	$24,000
2030	2	007-Beaufort	Resurfacing	SR 1309	NC 32	DEAD END	0.55	1.5" S9.5B	$70,000
2030	2	007-Beaufort	Resurfacing	SR 1310	NC 32	SR 1309	0.42	1.5" S9.5B	$53,000
2030	2	007-Beaufort	Resurfacing	SR 1317	NC 32	DEAD END	0.45	1.5" S9.5B	$56,000
2030	2	007-Beaufort	Resurfacing	SR 1333	SR 1334	DEAD END	0.01	1.25" S9.5B	$840
2030	2	007-Beaufort	Resurfacing	SR 1333	SR 1334	DEAD END	0.46	1.25" S9.5B	$55,200
2030	2	007-Beaufort	Resurfacing	SR 1334	US 264	SR 1335	3.41	1.5" S9.5B	$700,000
2030	2	007-Beaufort	Resurfacing	SR 1335	SR 1334	DEAD END	0.67	1.5" S9.5B	$134,000
2030	2	007-Beaufort	Resurfacing	SR 1336	SR 1334	END MAINTENANCE	0.82	1.5" S9.5B	$105,000
2030	2	007-Beaufort	Resurfacing	SR 1337	SR 1334	DEAD END	1.10	1.25" S9.5B	$132,000
2030	2	007-Beaufort	Resurfacing	SR 1348	NC 32	DEAD END	1.13	1.5" S9.5B	$143,032
2030	2	007-Beaufort	Resurfacing	SR 1358	SR1334	END MAINTENANCE	0.46	1.25" S9.5B	$55,200
2030	2	007-Beaufort	Resurfacing	SR 1375	SR 1311	END MAINTENANCE	0.37	1.5" S9.5B	$47,000
2030	2	007-Beaufort	Resurfacing	SR 1410	US 264	SR 1001	2.36	Leveling and 1.5" S9.5B	$411,000
2030	2	007-Beaufort	Resurfacing	SR 1412	SR 1001	END MAINTENANCE	1.20	1.5" S9.5B	$180,000
2030	2	007-Beaufort	Resurfacing	SR 1439	US 17	END MAINTENANCE	0.34	1.5" S9.5B	$51,000
2030	2	007-Beaufort	Resurfacing	SR 1601	US 264	DEAD END	0.40	1.5" S9.5B	$50,000
2030	2	007-Beaufort	Resurfacing	SR 1610	US 264	END MAINTENANCE	0.56	1.5" S9.5B	$83,550
2030	2	007-Beaufort	Resurfacing	SR 1628	US 264	US 264	0.85	1.25" S9.5B	$93,500
2030	2	007-Beaufort	Resurfacing	SR 1718	NC 99	SR 1722	2.56	1.5" S9.5B	$320,000
2030	2	007-Beaufort	Resurfacing	SR 1759	SR 1718	DEAD END	0.30	1.5" S9.5B	$45,000
2030	2	007-Beaufort	Resurfacing	SR 1773	NC 92	END MAINTENANCE	0.30	1.25" S9.5B	$44,250
2030	2	007-Beaufort	Resurfacing	US 264	NC 32	SR 1714 + .674 MILES	15.19	Mill 1.5" and 1.5" S9.5C	$7,418,496
2030	2	007-Beaufort	Preservation	SR 1004	NC 306	Dead End	3.29	Seal - Double	$124,830
2030	2	007-Beaufort	Preservation	SR 1106	NC 33	SR 1100	2.11	Seal - Double	$80,332
2030	2	007-Beaufort	Preservation	SR 1619	SR 1612	SR 1609	4.16	Seal - Double	$158,080
2030	2	007-Beaufort	Preservation	SR 1939	SR 1938	SR 1925	0.97	Seal - Double	$36,822
2030	2	007-Beaufort	Preservation	SR 1966	Dead End	Dead End	0.13	Seal - Double	$4,940
2030	2	016-Carteret	Resurfacing	SR 1155	SR 1154	NC 101	3.73	2.0" S9.5C	$1,000,000
2030	2	016-Carteret	Resurfacing	SR 1376	US 70	END MAINTENANCE	0.37	1.5" S9.5B	$46,000
2030	2	016-Carteret	Resurfacing	SR 1377	US 70	END MAINTENANCE	0.30	1.5" S9.5B	$38,000
2030	2	016-Carteret	Resurfacing	SR 1378	SR 1387	END MAINTENANCE	0.81	1.5" S9.5A	$93,000
2030	2	016-Carteret	Resurfacing	SR 1380	US 70	SR 1378	0.22	1.5" S9.5A	$25,000
2030	2	016-Carteret	Resurfacing	SR 1381	SR 1417	SR 1378	0.23	1.5" S9.5A	$27,000
2030	2	016-Carteret	Resurfacing	SR 1382	SR 1417	DEAD END	0.05	1.5" S9.5B	$8,000
2030	2	016-Carteret	Resurfacing	SR 1383	SR 1384	SR 1381	0.22	1.5" S9.5B	$28,000
2030	2	016-Carteret	Resurfacing	SR 1387	SR 1378	NC 12	3.17	1.5" S9.5A	$365,000
2030	2	016-Carteret	Resurfacing	SR 1390	NC 12	END MAINTENANCE	0.09	1.5" S9.5B	$13,000
2030	2	016-Carteret	Resurfacing	SR 1442	SR 1378	END MAINTENANCE	0.58	1.25" S9.5B	$63,580

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	2	016-Carteret	Resurfacing	SR 1474	SR 1473	END MAINTENANCE	0.55	1.5" S9.5B	$69,000
2030	2	016-Carteret	Resurfacing	SR 1620	BEGIN MAINTENANCE	DEAD END	0.05	1.5" S9.5B	$8,000
2030	2	016-Carteret	Resurfacing	SR 1633	SR 1106	END MAINTENANCE	0.28	1.5" S9.5B	$36,000
2030	2	016-Carteret	Resurfacing	SR 1637	SR 1124	CUL-DE-SAC	0.28	1.5" S9.5B	$35,000
2030	2	016-Carteret	Resurfacing	SR 1638	SR 1637	CUL-DE-SAC	0.05	1.5" S9.5B	$8,000
2030	2	016-Carteret	Resurfacing	SR 1677	NC 24	SR 1678	0.23	1.25" S9.5B	$26,000
2030	2	016-Carteret	Resurfacing	SR 1684	SR 1154	DEAD END	0.24	1.5" S9.5B	$31,000
2030	2	016-Carteret	Resurfacing	SR 1689	SR 1101	END MAINTENANCE	0.57	1.5" S9.5B	$71,000
2030	2	016-Carteret	Resurfacing	SR 1690	SR 1691	CUL-DE-SAC	0.07	1.5" S9.5B	$9,000
2030	2	016-Carteret	Resurfacing	SR 1692	SR 1693	CUL-DE-SAC	0.05	1.5" S9.5B	$8,000
2030	2	016-Carteret	Resurfacing	SR 1693	SR 1691	SR 1149	0.28	1.5" S9.5B	$35,000
2030	2	016-Carteret	Resurfacing	SR 1694	SR 1149	SR 1615	0.11	1.5" S9.5B	$14,000
2030	2	016-Carteret	Resurfacing	SR 1699	SR 1614	SR 1700	0.27	1.5" S9.5B	$34,000
2030	2	016-Carteret	Resurfacing	SR 1700	SR 1615	SR 1614	0.31	1.5" S9.5B	$40,000
2030	2	016-Carteret	Resurfacing	SR 1705	SR 1161	END MAINTENANCE	0.13	1.5" S9.5B	$17,000
2030	2	016-Carteret	Resurfacing	SR 1742	SR 1140	END MAINTENANCE	0.25	1.5" S9.5B	$32,000
2030	2	016-Carteret	Resurfacing	SR 1743	SR 1745	CUL-DE-SAC	0.19	1.5" S9.5B	$24,000
2030	2	016-Carteret	Resurfacing	SR 1744	SR 1742	CUL-DE-SAC	0.04	1.5" S9.5B	$8,000
2030	2	016-Carteret	Resurfacing	SR 1745	SR 1140	END MAINTENANCE	0.31	1.5" S9.5B	$40,000
2030	2	016-Carteret	Resurfacing	SR 1782	SR 1125	SR 1783	0.10	1.5" S9.5B	$12,000
2030	2	016-Carteret	Resurfacing	SR 1783	SR 1782	CUL-DE-SAC	0.56	1.5" S9.5B	$70,000
2030	2	016-Carteret	Resurfacing	SR 1792	SR 1174	END MAINT	0.39	1.5" S9.5B	$57,750
2030	2	016-Carteret	Rehabilitation	SR 1373	US 70	END MAINTENANCE	1.29	2.5" I19.0B and 1.5" S9.5B	$350,000
2030	2	016-Carteret	Rehabilitation	SR 1385	SR 1373	SR 1373	1.44	2.5" I19.0B and 1.5" S9.5B	$400,000
2030	2	016-Carteret	Rehabilitation	SR 1389	NC 12	END MAINTENANCE	0.10	2.5" I19.0B and 1.5" S9.5B	$25,000
2030	2	016-Carteret	Rehabilitation	SR 1614	SR 1149	CUL-DE-SAC	0.37	2.5" I19.0B and 1.5" S9.5B	$110,000
2030	2	016-Carteret	Preservation	SR 1155	SR 1154	NC 101	3.73	FDR and Double Seal	$2,006,135
2030	2	025-Craven	Resurfacing	NC 118	PITT COUNTY	NC 43	10.62	Mill 1.5" and 1.5" S9.5C	$4,000,000
2030	2	025-Craven	Resurfacing	SR 1109	SR 1108	DEAD END	0.09	1.5" S9.5B	$18,000
2030	2	025-Craven	Resurfacing	SR 1700	SR 1704	Dead End	4.55	1.5" S9.5B and Widen	$1,362,000
2030	2	025-Craven	Resurfacing	SR 1707	SR 1700	End Maint	1.05	1.5" S9.5B	$210,000
2030	2	025-Craven	Resurfacing	SR 1708	SR 1700	END MAINTENANCE	0.56	1.5" S9.5B	$112,000
2030	2	025-Craven	Resurfacing	SR 1709	SR 1700	END MAINTENANCE	0.37	1.5" S9.5B	$74,000
2030	2	025-Craven	Resurfacing	SR 1710	SR 1700	Dead End	0.64	1.5" S9.5B	$126,000
2030	2	025-Craven	Resurfacing	SR 1822	SR 1821	SR 1827	0.07	1.5" S9.5B	$14,000
2030	2	025-Craven	Resurfacing	SR 1827	DEAD END	DEAD END	0.12	1.5" S9.5B	$24,000
2030	2	025-Craven	Resurfacing	SR 1831	SR 1700	DEAD END	0.62	1.5" S9.5B	$124,000
2030	2	025-Craven	Resurfacing	SR 1835	SR 1710	Dead End	0.12	1.5" S9.5B	$22,000
2030	2	025-Craven	Resurfacing	SR 1836	SR 1700	Dead End	0.28	1.5" S9.5B	$54,000
2030	2	025-Craven	Resurfacing	SR 1855	NC 101	END MAINTENANCE	0.09	1.5" S9.5B	$18,000
2030	2	025-Craven	Resurfacing	SR 1856	SR 1855	CUL-DE-SAC	0.06	1.5" S9.5B	$12,000
2030	2	025-Craven	Resurfacing	SR 1858	SR 1857	SR 1859	0.13	1.5" S9.5B	$25,800
2030	2	025-Craven	Resurfacing	SR 1859	SR 1858	END MAINTENANCE	0.29	1.5" S9.5B	$58,800
2030	2	025-Craven	Resurfacing	SR 1868	SR 1768	END MAINTENANCE	0.69	1.5" S9.5B	$138,800
2030	2	025-Craven	Resurfacing	SR 1871	CUL-DE-SAC	CUL-DE-SAC	0.14	1.5" S9.5B	$28,600
2030	2	025-Craven	Resurfacing	SR 1909	SR 1193	END MAINTENANCE	0.11	1.5" S9.5B	$22,000
2030	2	025-Craven	Resurfacing	SR 1930	SR 1114	DEAD END	0.11	1.5" S9.5B	$22,000
2030	2	025-Craven	Resurfacing	SR 1931	SR 1108	DEAD END	0.09	1.5" S9.5B	$18,000
2030	2	025-Craven	Rehabilitation	SR 1821	SR 1822	END MAINTENANCE	0.34	2.5" I19.0C and 1.5" S9.5B	$110,500
2030	2	025-Craven	Rehabilitation	SR 1830	SR 1700	END MAINTENANCE	0.50	2.5" I19.0C and 1.5" S9.5B	$162,500
2030	2	025-Craven	Rehabilitation	SR 1863	SR 1713	SR 1864	0.43	2.5" I19.0B and 1.5" S9.5B	$139,750
2030	2	025-Craven	Preservation	SR 1262	NC 55	SR 1270	8.63	Seal - Double	$327,902
2030	2	025-Craven	Preservation	SR 1271	SR 1262	NC 55	2.80	Seal - Double	$106,400
2030	2	025-Craven	Preservation	SR 1272	SR 1271	SR 1262	1.01	Seal - Double	$38,380
2030	2	025-Craven	Preservation	SR 1274	SR 1262	SR 1273	1.26	Seal - Double	$47,880
2030	2	025-Craven	Preservation	SR 1275	NC 55	SR 1262	2.90	Seal - Double	$110,162
2030	2	040-Greene	Resurfacing	SR 1177	SR 1124	CUL-DE-SAC	0.23	1.5" S9.5B	$34,050
2030	2	040-Greene	Resurfacing	SR 1178	SR 1177	CUL-DE-SAC	0.09	1.5" S9.5B	$13,350
2030	2	040-Greene	Resurfacing	SR 1233	NC 58	NC 58	1.22	1.5" S9.5B	$183,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	2	040-Greene	Resurfacing	SR 1235	SR 1236	SR 1225	2.54	1.5" S9.5B	$381,000
2030	2	040-Greene	Resurfacing	SR 1243	SR 1242	SR 1240	0.75	1.5" S9.5B	$111,900
2030	2	040-Greene	Resurfacing	SR 1251	SR 1210	END PAVEMENT	0.20	1.5" S9.5B	$30,150
2030	2	040-Greene	Resurfacing	SR 1259	US 264 ALT	CUL-DE-SAC	0.24	1.5" S9.5B	$36,000
2030	2	040-Greene	Resurfacing	SR 1260	SR 1259	END MAINTENANCE	0.05	1.5" S9.5B	$7,500
2030	2	040-Greene	Resurfacing	SR 1407	SR 1405	DEAD END	0.40	1.5" S9.5B	$60,000
2030	2	040-Greene	Resurfacing	SR 1441	SR 1413	DEAD END	0.50	1.5" S9.5B	$75,000
2030	2	040-Greene	Preservation	SR 1214	SR 1253	WAYNE COUNTY	0.71	Seal - Double	$26,866
2030	2	040-Greene	Preservation	SR 1317	SR 1301	SR 1324	4.34	Seal - Double	$164,958
2030	2	040-Greene	Preservation	SR 1320	US 258	SR 1301	2.07	Seal - Double	$78,774
2030	2	052-Jones	Resurfacing	NC 41	DUPLIN CO	SR 1003	11.61	Mill 1.5" and 1.5" S9.5C	$4,500,000
2030	2	052-Jones	Resurfacing	SR 1130	SR 1157	SR 1142	3.93	1.5" S9.5B	$786,400
2030	2	052-Jones	Resurfacing	SR 1162	SR 1131	DEAD END	0.52	1.5" S9.5B	$104,000
2030	2	052-Jones	Resurfacing	SR 1322	NC 41	SR 1002	2.09	1.5" S9.5B	$416,000
2030	2	054-Lenoir	Resurfacing	SR 1342	US 258	NC 58	2.26	1.5" S9.5B	$338,400
2030	2	054-Lenoir	Resurfacing	SR 1541	US 258	SR 1575	1.38	1.75" S9.5A	$207,000
2030	2	054-Lenoir	Resurfacing	SR 1634	SR 1544	DEAD END	0.22	1.5" S9.5B	$44,200
2030	2	054-Lenoir	Resurfacing	SR 1635	SR 1634	DEAD END	0.41	1.5" S9.5B	$61,500
2030	2	054-Lenoir	Resurfacing	SR 1636	SR 1001	DEAD END	0.77	1.5" S9.5B	$115,500
2030	2	054-Lenoir	Resurfacing	SR 1637	SR 1636	CUL-DE-SAC	0.43	1.5" S9.5B	$64,500
2030	2	054-Lenoir	Resurfacing	SR 1640	SR 1636	SR 1636	0.47	1.5" S9.5B	$70,500
2030	2	054-Lenoir	Resurfacing	SR 1641	SR 1636	SR 1640	0.14	1.5" S9.5B	$21,000
2030	2	054-Lenoir	Resurfacing	SR 1651	SR 1623	CUL-DE-SAC	0.16	1.5" S9.5B	$24,000
2030	2	054-Lenoir	Resurfacing	SR 1652	SR 1623	END MAINTENANCE	0.11	1.5" S9.5B	$16,500
2030	2	054-Lenoir	Resurfacing	SR 1653	CUL-DE-SAC	CUL-DE-SAC	0.27	1.5" S9.5B	$40,500
2030	2	054-Lenoir	Resurfacing	SR 1658	SR 2013	SR 1659	0.32	1.5" S9.5B	$48,000
2030	2	054-Lenoir	Resurfacing	SR 1659	SR 2013	DEAD END	0.22	1.5" S9.5B	$33,000
2030	2	054-Lenoir	Resurfacing	SR 1660	SR 1575	END PAVEMENT	0.23	1.5" S9.5B	$34,500
2030	2	054-Lenoir	Resurfacing	SR 1661	SR 1575	DEAD END	0.40	1.5" S9.5B	$60,000
2030	2	054-Lenoir	Resurfacing	SR 1662	SR 1543	CUL-DE-SAC	0.15	1.5" S9.5B	$22,500
2030	2	054-Lenoir	Resurfacing	SR 1663	SR 1662	CUL-DE-SAC	0.12	1.5" S9.5B	$18,000
2030	2	054-Lenoir	Resurfacing	SR 1664	SR 1543	SR 1663	0.07	1.5" S9.5B	$10,500
2030	2	054-Lenoir	Resurfacing	SR 1666	SR 1001	END MAINTENANCE	0.17	1.5" S9.5B	$25,500
2030	2	054-Lenoir	Resurfacing	SR 1667	SR 1001	SR 1666	0.14	1.5" S9.5B	$21,000
2030	2	054-Lenoir	Resurfacing	SR 1669	SR 1660	DEAD END	0.09	1.5" S9.5B	$13,500
2030	2	054-Lenoir	Resurfacing	SR 1674	SR 1579	SR 1675	0.15	1.5" S9.5B	$22,500
2030	2	054-Lenoir	Resurfacing	SR 1675	NC 58	DEAD END	0.13	1.5" S9.5B	$19,500
2030	2	054-Lenoir	Resurfacing	SR 1679	SR 1544	DEAD END	0.35	1.5" S9.5B	$53,100
2030	2	054-Lenoir	Resurfacing	SR 1680	SR 1679	CUL-DE-SAC	0.08	1.5" S9.5B	$15,000
2030	2	054-Lenoir	Resurfacing	SR 1681	SR 1679	Dead End	0.07	1.5" S9.5B	$15,000
2030	2	054-Lenoir	Resurfacing	SR 1682	SR 1001	CUL-DE-SAC	0.22	1.5" S9.5B	$32,550
2030	2	054-Lenoir	Resurfacing	SR 1696	SR 1661	DEAD END	0.16	1.5" S9.5B	$24,000
2030	2	054-Lenoir	Resurfacing	SR 1697	SR 1661	SR 1698	0.14	1.5" S9.5B	$21,000
2030	2	054-Lenoir	Resurfacing	SR 1699	SR 1661	SR 1698	0.15	1.5" S9.5B	$22,500
2030	2	054-Lenoir	Resurfacing	SR 1746	NC 58	SR 1747	0.87	Mill 1.75" and 1.75" S9.5B	$217,500
2030	2	054-Lenoir	Resurfacing	SR 1750	SR 1004	SR 1725	0.16	1.5" S9.5B	$24,000
2030	2	054-Lenoir	Resurfacing	SR 1751	NC 58	DEAD END	0.11	1.5" S9.5B	$16,500
2030	2	054-Lenoir	Resurfacing	SR 1752	SR 1751	DEAD END	0.09	1.5" S9.5B	$13,500
2030	2	054-Lenoir	Resurfacing	SR 1754	SR 1745	DEAD END	0.10	1.5" S9.5B	$15,000
2030	2	054-Lenoir	Resurfacing	SR 1755	SR 1727	DEAD END	0.34	1.5" S9.5B	$51,000
2030	2	054-Lenoir	Resurfacing	SR 1763	SR 1716	SR 1091	0.38	1.5" S9.5B	$57,000
2030	2	054-Lenoir	Resurfacing	SR 1764	SR 1727	DEAD END	0.24	1.5" S9.5B	$36,000
2030	2	054-Lenoir	Resurfacing	SR 1766	NC 58	END MAINTENANCE	0.13	1.5" S9.5B	$18,900
2030	2	054-Lenoir	Resurfacing	SR 1802	NC 11	SR 1801	1.81	1.5" S9.5B	$271,950
2030	2	054-Lenoir	Resurfacing	SR 1807	CRAVEN CO	SR 1804	4.62	1.75" S9.5A	$693,000
2030	2	054-Lenoir	Resurfacing	SR 1815	SR 1810	SR 1834	0.25	1.5" S9.5B	$37,500
2030	2	054-Lenoir	Resurfacing	SR 1824	NC 11	SR 1823	0.18	1.5" S9.5B	$27,000
2030	2	054-Lenoir	Resurfacing	SR 1834	SR 1810	CUL-DE-SAC	0.30	Mill 1.75" and 1.75" S9.5B	$75,000
2030	2	054-Lenoir	Resurfacing	SR 1841	SR 1804	SR 1804	0.34	1.5" S9.5B	$51,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	2	054-Lenoir	Resurfacing	SR 1842	SR 1801	SR 1802	0.55	1.5" S9.5B	$82,500
2030	2	054-Lenoir	Resurfacing	SR 1843	SR 1842	SR 1858	0.10	1.5" S9.5B	$15,000
2030	2	054-Lenoir	Resurfacing	SR 1857	SR 1802	CUL-DE-SAC	0.19	1.5" S9.5B	$28,500
2030	2	054-Lenoir	Resurfacing	SR 1858	SR 1843	DEAD END	0.08	1.5" S9.5B	$12,000
2030	2	054-Lenoir	Resurfacing	SR 1860	SR 1802	END MAINTENANCE	0.19	1.5" S9.5B	$28,500
2030	2	054-Lenoir	Resurfacing	SR 1861	SR 1860	END MAINTENANCE	0.16	1.5" S9.5B	$4,500
2030	2	054-Lenoir	Resurfacing	SR 1862	SR 1861	CUL-DE-SAC	0.04	1.5" S9.5B	$22,500
2030	2	054-Lenoir	Resurfacing	SR 1901	BEGIN CIRCLE	END CIRCLE	0.47	1.5" S9.5B	$70,500
2030	2	054-Lenoir	Resurfacing	SR 1935	US 258	SR 1908	0.17	1.5" S9.5B	$25,500
2030	2	054-Lenoir	Resurfacing	SR 2006	SR 1636	DEAD END	0.06	1.5" S9.5B	$9,000
2030	2	054-Lenoir	Resurfacing	SR 2009	SR 1546	DEAD END	0.14	1.5" S9.5B	$21,000
2030	2	054-Lenoir	Resurfacing	SR 2011	SR 1682	CUL-DE-SAC	0.06	1.5" S9.5B	$9,000
2030	2	054-Lenoir	Resurfacing	SR 2012	SR 1544	CUL-DE-SAC	0.12	1.5" S9.5B	$16,500
2030	2	054-Lenoir	Resurfacing	SR 2014	SR 1575	CUL-DE-SAC	0.22	1.5" S9.5B	$33,000
2030	2	054-Lenoir	Resurfacing	SR 2015	SR 1573	CUL-DE-SAC	0.25	1.5" S9.5B	$37,500
2030	2	054-Lenoir	Resurfacing	SR 2027	SR 2028	CUL-DE-SAC	0.10	1.5" S9.5B	$15,600
2030	2	054-Lenoir	Resurfacing	SR 2028	SR 1001	CUL-DE-SAC	0.41	1.5" S9.5B	$61,650
2030	2	054-Lenoir	Resurfacing	SR 2033	SR 1682	CUL-DE-SAC	0.05	1.5" S9.5B	$7,650
2030	2	054-Lenoir	Resurfacing	SR 2038	SR 1555	CUL-DE-SAC	0.13	1.5" S9.5B	$19,800
2030	2	054-Lenoir	Rehabilitation	SR 1814	SR 1810	CEDAR LANE	0.43	2.5" I19.0B and 1.5" S9.5B	$139,750
2030	2	054-Lenoir	Rehabilitation	SR 2000	SR 1575	DEAD END	0.09	2.5" I19.0B and 1.5" S9.5B	$29,250
2030	2	054-Lenoir	Preservation	SR 1110	DUPLIN COUNTY	NC 11	0.92	Seal - Double	$34,922
2030	2	054-Lenoir	Preservation	SR 1112	SR 1111	NC 11	0.66	Seal - Double	$24,890
2030	2	054-Lenoir	Preservation	SR 1121	NC 11	DUPLIN COUNTY	2.62	Seal - Double	$99,408
2030	2	054-Lenoir	Preservation	SR 1123	NC 11	SR 1111	1.28	Seal - Double	$48,564
2030	2	054-Lenoir	Preservation	SR 1145	SR 1143	DUPLIN COUNTY	0.47	Seal - Double	$17,860
2030	2	054-Lenoir	Preservation	SR 1146	SR 1147	DUPLIN COUNTY	0.24	Seal - Double	$9,120
2030	2	054-Lenoir	Preservation	SR 1147	SR 1143	DUPLIN COUNTY	0.50	Seal - Double	$19,000
2030	2	054-Lenoir	Preservation	SR 1153	SR 1300	SR 1154	1.89	Seal - Double	$71,820
2030	2	054-Lenoir	Preservation	SR 1154	NC 55	DUPLIN COUNTY	4.85	Seal - Double	$184,300
2030	2	054-Lenoir	Preservation	SR 1155	SR 1154	SR 1156	1.03	Seal - Double	$39,140
2030	2	054-Lenoir	Preservation	SR 1156	SR 1154	SR 1157	1.71	Seal - Double	$64,980
2030	2	054-Lenoir	Preservation	SR 1157	SR 1111	NC 55	4.87	Seal - Double	$185,060
2030	2	054-Lenoir	Preservation	SR 1167	SR 1143	DEAD END	0.91	Seal - Double	$34,580
2030	2	054-Lenoir	Preservation	SR 1344	NC 11	SR 1342	1.59	Seal - Double	$60,420
2030	2	054-Lenoir	Preservation	SR 1351	US 258	NC 11	1.17	Seal - Double	$44,574
2030	2	054-Lenoir	Preservation	SR 1515	SR 1531	SR 1603	4.38	Seal - Double	$166,288
2030	2	054-Lenoir	Preservation	SR 1516	SR 1514	SR 1515	0.57	Seal - Double	$21,584
2030	2	054-Lenoir	Preservation	SR 1529	SR 1530	SR 1001	0.73	Seal - Double	$27,740
2030	2	054-Lenoir	Preservation	SR 1531	SR 1530	DEAD END	1.07	Seal - Double	$40,456
2030	2	054-Lenoir	Preservation	SR 1533	SR 1001	GREENE COUNTY	0.08	Seal - Double	$3,040
2030	2	054-Lenoir	Preservation	SR 1705	SR 1704	GREENE COUNTY	0.76	Seal - Double	$28,804
2030	2	054-Lenoir	Preservation	SR 1802	NC 11	SR 1801	1.81	Seal - Double	$68,894
2030	2	054-Lenoir	Preservation	SR 1803	CRAVEN COUNTY	NC 55	4.07	Seal - Double	$154,660
2030	2	054-Lenoir	Preservation	SR 1804	US 70	SR 1805	10.58	Seal - Double	$402,202
2030	2	054-Lenoir	Preservation	SR 1805	SR 1804	NC 55	1.18	Seal - Double	$44,840
2030	2	069-Pamlico	Resurfacing	SR 1333	SR 1324	END MAINTENANCE	0.56	1.5" S9.5B	$111,400
2030	2	069-Pamlico	Resurfacing	SR 1374	SR 1324	END MAINTENANCE	0.63	1.5" S9.5B	$126,000
2030	2	069-Pamlico	Resurfacing	SR 1380	SR 1374	CUL-DE-SAC	0.65	1.5" S9.5B	$130,000
2030	2	069-Pamlico	Resurfacing	SR 1386	SR 1330	SR 1387	0.45	1.5" S9.5B	$90,600
2030	2	069-Pamlico	Resurfacing	SR 1387	SR 1386	CUL-DE-SAC	0.49	1.5" S9.5B	$98,800
2030	2	069-Pamlico	Preservation	SR 1332	SR 1324	END MAINT	1.22	Seal - Double	$46,398
2030	2	069-Pamlico	Preservation	SR 1334	NC 55	NC 55	1.85	Seal - Double	$70,376
2030	2	069-Pamlico	Preservation	SR 1335	NC 55	DEAD END	0.50	Seal - Double	$18,924
2030	2	074-Pitt	Resurfacing	NC 118	LENOIR COUNTY	CRAVEN COUNTY	7.32	Mill 1.5" and 1.5" S9.5C	$3,000,000
2030	2	074-Pitt	Resurfacing	NC 43	SR 1202 + .241 MILES	EDGECOMBE COUNTY	9.72	Mill 1.5" and 1.5" S9.5C	$3,500,000
2030	2	074-Pitt	Resurfacing	SR 1232	SR 1240	NC 222	4.25	1.5" S9.5B	$849,200
2030	2	074-Pitt	Resurfacing	SR 1236	SR 1232	SR 1231	1.25	1.5" S9.5B	$249,800
2030	2	074-Pitt	Resurfacing	SR 1241	SR 1200	SR 1232	3.28	1.5" S9.5B	$656,400

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	2	074-Pitt	Resurfacing	SR 1468	SR 1417	END MAINTENANCE	0.44	1.5" S9.5B	$88,000
2030	2	074-Pitt	Resurfacing	SR 1474	SR 1417	DEAD END	0.11	1.5" S9.5B	$22,000
2030	2	074-Pitt	Resurfacing	SR 1475	SR 1474	CUL-DE-SAC	0.07	1.5" S9.5B	$14,000
2030	2	074-Pitt	Resurfacing	SR 1515	US 13	SR 1514	1.62	1.5" S9.5B	$324,400
2030	2	074-Pitt	Resurfacing	SR 1518	SR 1514	SR 1517	1.70	1.5" S9.5B	$340,800
2030	2	074-Pitt	Resurfacing	SR 1572	US 13	SR 1514	1.13	1.5" S9.5B	$226,000
2030	2	074-Pitt	Resurfacing	SR 1740	SR 2241	SR 1725	1.26	1.5" S9.5B	$252,000
2030	2	074-Pitt	Resurfacing	SR 1772	SR 1777	SR 1755	2.14	1.5" S9.5B	$428,000
2030	2	074-Pitt	Resurfacing	SR 1925	SR 1725	NC 102	2.69	1.5" S9.5B	$538,000
2030	2	074-Pitt	Resurfacing	SR 1939	NC 118	END C&G	0.44	Mill 1.5" and 1.5" S9.5C	$236,028
2030	2	074-Pitt	Preservation	SR 1543	NC 30	NC 903	3.64	Seal - Double	$138,320
2030	2	074-Pitt	Preservation	SR 1715	SR 1700	SR 1725	1.98	Seal - Double	$75,126
2030	2	074-Pitt	Preservation	SR 1743	NC 43	DEAD END	2.06	Seal - Double	$78,166
2030	2	074-Pitt	Preservation	SR 1750	SR 1751	SR 1749	0.84	Seal - Double	$31,920
2030	2	074-Pitt	Preservation	SR 1752	NC 102	SR 1753	1.29	Seal - Double	$49,020
2030	3	010-Brunswick	Resurfacing	NC 211	US 17	Columbus County Line	14.87	1.5" S9.5C	$5,621,616
2030	3	010-Brunswick	Resurfacing	SR 1315	SR 1321	SR 1313	1.77	Full Depth Patching and 1.5" S9.5B and Widening	$662,720
2030	3	010-Brunswick	Resurfacing	SR 1322	SR 1321	SR 1300	1.47	Full Depth Patching and 1.5" S9.5B and Widening	$404,250
2030	3	010-Brunswick	Resurfacing	SR 1330	SR 1333	NC 130	1.21	Full Depth Patching and 1.5" S9.5B and Widening	$332,750
2030	3	010-Brunswick	Resurfacing	SR 1332	SR 1331	SR 1335	2.02	Full Depth Patching and 1.5" S9.5B and Widening	$554,125
2030	3	010-Brunswick	Resurfacing	SR 1336	SR 1335	SR 1333	4.07	Full Depth Patching and 1.5" S9.5B and Widening	$1,119,525
2030	3	010-Brunswick	Resurfacing	SR 1338	SR 1333	SR 1339	2.58	Full Depth Patching and 1.5" S9.5B and Widening	$710,325
2030	3	010-Brunswick	Resurfacing	SR 1342	SR 1345	SR 1340	7.13	Full Depth Patching and 1.5" S9.5B	$1,959,375
2030	3	010-Brunswick	Preservation	SR 1138	SR 1137	DEAD END	0.83	1.5" S9.5B	$91,300
2030	3	010-Brunswick	Preservation	SR 1187	SR 1145	SR 1188	0.22	1.5" S9.5B	$24,640
2030	3	010-Brunswick	Preservation	SR 1188	SR 1187	EOM	0.10	1.5" S9.5B	$11,000
2030	3	010-Brunswick	Preservation	SR 1192	SR 1150	SR 1935	0.34	1.5" S9.5B	$37,730
2030	3	010-Brunswick	Preservation	SR 1203	US 17	EOM	0.20	1.5" S9.5B	$21,780
2030	3	010-Brunswick	Preservation	SR 1207	NC 179	EOM	0.40	1.5" S9.5B	$44,440
2030	3	010-Brunswick	Preservation	SR 1211	SR 1115	DEAD END	0.10	1.5" S9.5B	$11,220
2030	3	010-Brunswick	Preservation	SR 1235	SR 1150	EOM	0.12	1.5" S9.5B	$13,640
2030	3	010-Brunswick	Preservation	SR 1245	SR 1115	DEAD END	0.91	1.5" S9.5B	$100,320
2030	3	010-Brunswick	Preservation	SR 1252	SR 1149	Sr 1253	0.21	1.5" S9.5B	$23,430
2030	3	010-Brunswick	Preservation	SR 1253	EOM	EOM	0.12	1.5" S9.5B	$13,200
2030	3	010-Brunswick	Preservation	SR 1270	US 17	DEAD END	0.58	1.5" S9.5B	$64,130
2030	3	010-Brunswick	Preservation	SR 1310	NC 904	DEAD END	0.23	1.25" S9.5B	$25,410
2030	3	010-Brunswick	Preservation	SR 1311	SR 1310	DEAD END	0.20	1.25" S9.5B	$21,890
2030	3	010-Brunswick	Preservation	SR 1346	SR 1345	EOM	0.58	1.5" S9.5B	$63,800
2030	3	010-Brunswick	Preservation	SR 1354	SR 1300	DEAD END	0.40	1.25" S9.5B	$44,110
2030	3	010-Brunswick	Preservation	SR 1361	SR 1343	EOM	0.31	1.5" S9.5B	$33,800
2030	3	010-Brunswick	Preservation	SR 1370	SR 1129	DEAD END	0.15	1.5" S9.5B	$16,500
2030	3	010-Brunswick	Preservation	SR 1371	SR 1370	DEAD END	0.09	1.5" S9.5B	$9,900
2030	3	010-Brunswick	Preservation	SR 1400	SR 1448	EOM	0.80	1.5" S9.5B	$87,780
2030	3	010-Brunswick	Preservation	SR 1829	SR 1837	EOM	0.06	1.5" S9.5B	$6,600
2030	3	010-Brunswick	Preservation	SR 1830	SR 1837	SR 1838	0.18	1.5" S9.5B	$19,800
2030	3	010-Brunswick	Preservation	SR 1831	SR 1837	SR 1838	0.18	1.5" S9.5B	$19,800
2030	3	010-Brunswick	Preservation	SR 1832	SR 1837	SR 1838	0.17	1.5" S9.5B	$18,700
2030	3	010-Brunswick	Preservation	SR 1833	SR 1132	SR 1838	0.20	1.5" S9.5B	$22,000
2030	3	010-Brunswick	Preservation	SR 1834	SR 1837	SR 1838	0.11	1.5" S9.5B	$12,100
2030	3	010-Brunswick	Preservation	SR 1835	SR 1837	SR 1338	0.09	1.5" S9.5B	$9,900
2030	3	010-Brunswick	Preservation	SR 1836	SR 1132	SR 1838	0.12	1.5" S9.5B	$13,200
2030	3	010-Brunswick	Preservation	SR 1837	SR 1829	EOM	0.70	1.5" S9.5B	$77,000
2030	3	010-Brunswick	Preservation	SR 1838	SR 1836	SR 1830	0.35	1.5" S9.5B	$38,500
2030	3	010-Brunswick	Preservation	SR 1840	SR 1115	DEAD END	0.28	1.5" S9.5B	$30,580
2030	3	010-Brunswick	Preservation	SR 1855	SR 1270	DEAD END	0.33	1.5" S9.5B	$36,300
2030	3	010-Brunswick	Preservation	SR 1879	SR 1145	EOM	0.19	1.5" S9.5B	$20,900
2030	3	010-Brunswick	Preservation	SR 1884	SR 1837	SR 1838	0.16	1.5" S9.5B	$17,600
2030	3	010-Brunswick	Preservation	SR 1897	SR 1145	EOM	0.07	1.5" S9.5B	$7,700
2030	3	010-Brunswick	Preservation	SR 1926	SR 1150	EOM	0.16	1.5" S9.5B	$17,710

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	3	010-Brunswick	Preservation	SR 1935	SR 1192	SR 1936	0.06	1.5" S9.5B	$6,600
2030	3	010-Brunswick	Preservation	SR 1936	SR 1935	SR 1935	0.27	1.5" S9.5B	$29,700
2030	3	031-Duplin	Resurfacing	SR 1133	SR 1146	SR 1137	1.31	#67 Mat Seal and 1.5" S9.5B	$301,000
2030	3	031-Duplin	Resurfacing	SR 1155	Pender County	SR 1156	1.24	1.5" S9.5B	$279,000
2030	3	031-Duplin	Resurfacing	SR 1348	US 117	NC 24 BUS	1.14	1.5" S9.5B	$154,700
2030	3	031-Duplin	Resurfacing	SR 1359	SR 1306	DEAD END	1.33	1.5" S9.5B	$266,000
2030	3	031-Duplin	Resurfacing	SR 1362	SR 1361	SR 1004	0.74	#67 Mat Seal and 1.5" S9.5A and Widen	$118,940
2030	3	031-Duplin	Resurfacing	SR 1396	US 117	SR 1305	1.25	#67 Mat Seal and 1.5" S9.5B	$282,000
2030	3	031-Duplin	Resurfacing	SR 1513	SR 1306	SR 1500	2.78	1.5" S9.5B	$556,000
2030	3	031-Duplin	Resurfacing	SR 1710	SR 1700	Lenoir Co Line	5.31	1.5" S9.5B	$1,039,554
2030	3	031-Duplin	Resurfacing	SR 1733	SR 1732	NC 241	1.50	1.5" S9.5B	$255,000
2030	3	031-Duplin	Resurfacing	SR 1807	SR 1801	SR 1715	1.66	1.5" S9.5B	$332,000
2030	3	031-Duplin	Resurfacing	SR 1996	NC 11	SR 1141	2.57	1.5" S9.5B	$514,000
2030	3	031-Duplin	Resurfacing	SR 2020	SR 1148	MP 019	0.19	#67 Mat Seal and 1.5" S9.5B	$45,000
2030	3	031-Duplin	Resurfacing	US 117 Conn N	Sampson County	US 117	4.00	1.5" S9.5C	$1,597,544
2030	3	031-Duplin	Resurfacing	US 117 Conn S	US 117	Sampson County	3.98	1.5" S9.5C	$1,589,039
2030	3	031-Duplin	Resurfacing	US 117 N	US 117 Connector	Wayne County	1.64	1.5" S9.5C	$664,200
2030	3	031-Duplin	Resurfacing	US 117 S	Wayne County	US 117 Connector	1.64	1.5" S9.5C	$664,200
2030	3	031-Duplin	Preservation	SR 1119	NC 903	SR 1117	0.51	Seal - Double and Fog Seal	$77,060
2030	3	031-Duplin	Preservation	SR 1322	SR 1302	Sampson County	0.75	Seal - Double and Fog Seal	$146,640
2030	3	031-Duplin	Preservation	SR 1358	SR 1304	SR 1305	1.19	Seal - Double and Fog Seal	$107,100
2030	3	031-Duplin	Preservation	SR 1519	SR 1501	SR 1111	1.94	Seal - Double and Fog Seal	$174,000
2030	3	031-Duplin	Preservation	SR 1530	Wayne County	SR 1501	1.92	Seal - Double and Fog Seal	$173,000
2030	3	031-Duplin	Preservation	SR 1729	NC 24	NC 24	2.30	Seal - Double and Fog Seal	$100,000
2030	3	031-Duplin	Preservation	SR 1902	US 117	US 117	1.39	Seal - Double and Fog Seal	$125,100
2030	3	031-Duplin	Preservation	SR 1935	SR 1148	SR 1162	1.44	Seal - Double and Fog Seal	$129,600
2030	3	065-New Hanover	Resurfacing	SR 1411	Dawson St.	Oleander Dr.	5.60	Full Depth Patching and 1.5" S9.5B	$1,540,000
2030	3	065-New Hanover	Resurfacing	SR 1492	US 421	Masonboro Loop Rd	4.11	Full Depth Patching and 1.5" S9.5B	$1,130,250
2030	3	065-New Hanover	Resurfacing	SR 1627	US 74 West	N. Front Street	0.36	Mill 1.5" and 1.5" S9.5C	$75,350
2030	3	065-New Hanover	Resurfacing	SR 1627	N. Front Street	US 74 E	0.43	Mill 1.5" and 1.5" S9.5C	$118,525
2030	3	065-New Hanover	Resurfacing	SR 1981	SR 1979	Cul-De-Sac	0.10	Mill 1.25" and 1.25" S9.5A	$27,500
2030	3	065-New Hanover	Resurfacing	SR 2195	Moland Dr.	N Kerr Ave	0.71	Full Depth Patching and 1.5" S9.5B	$195,250
2030	3	065-New Hanover	Resurfacing	SR 2911	SR 1979	SR 2910	0.15	Mill 1.25" and 1.25" S9.5B	$41,250
2030	3	065-New Hanover	Resurfacing	US 421 TRK	US 421	US 76	0.99	1.5" S9.5C	$320,760
2030	3	065-New Hanover	Resurfacing	US 74	Bridge 12 (H. Trask)	Bridge 24	1.01	1.5" S9.5C	$407,430
2030	3	065-New Hanover	Resurfacing	US 74	Isabel Holmes Bridge	PVMT joint at Kornegay Ave	2.49	1.5" S9.5C	$1,509,637
2030	3	065-New Hanover	Resurfacing	US 74 W	US 74 Begin Divided	Bridge 12 (H. Trask)	0.36	1.5" S9.5C	$146,205
2030	3	065-New Hanover	Resurfacing	US 74 W	PVMT joint at Kornegay Ave	Isabelle Holmes Bridge	2.41	1.5" S9.5C	$1,233,765
2030	3	065-New Hanover	Preservation	SR 1576	US 421	SR 1187	6.33	1.25" S9.5B	$1,000,000
2030	3	065-New Hanover	Preservation	SR 2656	SR 2195	DEAD END	0.09	1.0" S4.75A	$24,750
2030	3	067-Onslow	Resurfacing	Ernest King	SR 1107	Cul-De-Sac	0.97	Full Depth Patching and 1.25" S9.5B	$213,400
2030	3	067-Onslow	Resurfacing	Gregory Fork Rd	US 258	SR 1230	6.08	1.25" S9.5B	$1,337,600
2030	3	067-Onslow	Resurfacing	Hardy Graham Rd	Pender County Line	SR 1106	2.77	1.5" S9.5B	$609,400
2030	3	067-Onslow	Resurfacing	Harris Creek Rd	NC 53	SR 1105	3.77	1.25" S9.5B	$829,400
2030	3	067-Onslow	Resurfacing	Nelson Park Rd	SR 1107	Dead End	1.05	1.5" S9.5B	$231,000
2030	3	067-Onslow	Resurfacing	Northwest Bridge Rd	SR 1308	US 258	2.98	1.5" S9.5B	$655,600
2030	3	067-Onslow	Resurfacing	Old Northwest Bridge	US 258	EOM	0.85	1.5" S9.5B	$187,000
2030	3	067-Onslow	Resurfacing	Pony Farm Rd	SR 1215	NC 53	0.85	Mill 1.5" and 1.5" S9.5B	$186,120
2030	3	067-Onslow	Resurfacing	Potters Hill Rd	SR 1235	Duplin County Line	2.51	1.5" S9.5B	$552,200
2030	3	067-Onslow	Resurfacing	Richlands Loop Rd	SR 1301	US 258	2.84	1.5" S9.5B	$624,800
2030	3	067-Onslow	Resurfacing	Thomas Loop	SR 1352	US 258	1.00	1.5" S9.5B	$220,000
2030	3	067-Onslow	Resurfacing	Union Chapel Rd	NC 111	US 258	1.90	Patching and Leveling and 1.5" S9.5B	$418,000
2030	3	067-Onslow	Resurfacing	US 17 N	Moosehaven Rd	SR 1327 - 0.198mi	3.62	Mill 2.0" and 2.0" S9.5C	$1,368,360
2030	3	067-Onslow	Resurfacing	US 17 S	SR 1327 - 0.198mi	Moosehaven Rd	3.55	Mill 2.0" and 2.0" S9.5C	$1,341,900
2030	3	067-Onslow	Resurfacing	Verona Rd	SR 1119	SR 1153	1.05	1.25" S9.5B	$231,000
2030	3	067-Onslow	Resurfacing	Warren Taylor Rd	US 258	SR 1301	1.09	1.5" S9.5B	$239,800
2030	3	067-Onslow	Preservation	Cavanaughtown	1302	SR 1304	2.09	Seal - Cape	$161,975
2030	3	067-Onslow	Preservation	Chadwick Acres Rd	SR 1518	SR 1695	2.04	Microsurface	$122,400
2030	3	067-Onslow	Preservation	Cypress Creek Rd	NC 111	Duplin County Line	3.69	Crack Seal	$222,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	3	067-Onslow	Preservation	Falcon Crest	SR 1213	SR 2108	0.33	1.25" S9.5B	$61,380
2030	3	067-Onslow	Preservation	Franktown Rd	SR 1003	SR 1311	2.14	Seal - Cape	$165,850
2030	3	067-Onslow	Preservation	Galloway Jones	SR 1423	SR 1425	0.98	Crack Seal	$59,040
2030	3	067-Onslow	Preservation	Hardison Rd	SR 1534	SR 1538	1.70	Seal - Cape	$131,750
2030	3	067-Onslow	Preservation	Mill River Rd	SR 1105	EOM	0.52	1.25" S9.5B	$96,720
2030	3	071-Pender	Resurfacing	SR 1100	SR 1201	NC 53	3.50	Full Depth Patching and 1.5" S9.5B and Widening	$1,270,000
2030	3	071-Pender	Resurfacing	SR 1364	SR 1563	EOM	0.60	Full Depth Patching and 1.5" S9.5B	$135,000
2030	3	071-Pender	Resurfacing	SR 1561	US 17	EOM	2.65	Full Depth Patching and 1.5" S9.5B	$583,000
2030	3	071-Pender	Resurfacing	SR 1563	SR 1759	SR 1561	1.66	Full Depth Patching and 1.5" S9.5B	$400,000
2030	3	071-Pender	Resurfacing	SR 1565	US 17	SR 1563	3.35	Full Depth Patching and 1.5" S9.5B	$750,000
2030	3	071-Pender	Resurfacing	SR 1570	US 17	EOM	1.64	Full Depth Patching and 1.5" S9.5B	$370,000
2030	3	071-Pender	Resurfacing	US 421	End Divided Section	NC 11 - 0.28	12.30	1.5" S9.5C	$4,981,500
2030	3	071-Pender	Preservation	SR 1122	US 421	NC 53	1.15	Full Depth Patching and 1.5" S9.5B	$130,000
2030	3	071-Pender	Preservation	SR 1211	SR 1209	US 421	4.20	Full Depth Patching and 1.0" S4.75A	$470,000
2030	3	071-Pender	Preservation	SR 1212	SR 1211	US 421	1.30	Full Depth Patching and 1.0" S4.75A	$145,000
2030	3	071-Pender	Preservation	SR 1403	NC 53	SR 1120	2.40	Full Depth Patching and 1.5" S9.5B	$270,000
2030	3	082-Sampson	Resurfacing	NC 403 E	US 701 BUS	I-40	11.21	1.5" S9.5C	$4,541,670
2030	3	082-Sampson	Resurfacing	NC 403 W	I-40	End Divided Section	0.35	1.5" S9.5C	$143,370
2030	3	082-Sampson	Resurfacing	SR 1117	SR 1007	NC 41	1.88	1.5" S9.5B	$517,000
2030	3	082-Sampson	Resurfacing	SR 1311	SR 1006	US 421	7.68	1.5" S9.5B	$2,112,000
2030	3	082-Sampson	Resurfacing	SR 1919	Duplin County	NC 403	8.23	1.5" S9.5B	$2,263,250
2030	3	082-Sampson	Resurfacing	US 117 Conn N	I-40	Duplin County	1.31	1.5" S9.5C	$529,740
2030	3	082-Sampson	Resurfacing	US 117 Conn S	Duplin County	I-40	1.31	1.5" S9.5C	$528,930
2030	3	082-Sampson	Preservation	SR 1310	SR 1308	SR 1309	0.44	Seal - Double and Fog Seal	$17,600
2030	3	082-Sampson	Preservation	SR 1326	SR 1323	SR 1414	4.95	Seal - Double and Fog Seal	$198,000
2030	3	082-Sampson	Preservation	SR 1475	US 13	US 421	2.80	Seal - Double and Fog Seal	$112,000
2030	3	082-Sampson	Preservation	SR 1711	Wayne Co Line	SR 1722	6.92	Seal - Double and Fog Seal	$277,200
2030	3	082-Sampson	Preservation	SR 1742	SR 1751	SR 1731	9.99	Seal - Double and Fog Seal	$399,600
2030	4	033-Edgecombe	Resurfacing	NC 11	US 64 Bridge Joint	Martin County Line	1.92	1.5" S9.5B	$386,000
2030	4	033-Edgecombe	Resurfacing	NC 122	Asphalt Joint @ Speed C/L	Halifax County Line	2.87	1.5" S9.5B	$574,000
2030	4	033-Edgecombe	Resurfacing	SR 1152	SR 1006	SR 1157	2.28	1.5" S9.5B	$330,600
2030	4	033-Edgecombe	Resurfacing	SR 1153	SR 1154	SR 1002	0.24	1.25" S9.5B	$27,000
2030	4	033-Edgecombe	Resurfacing	SR 1154	SR 1152	SR 1002	0.82	1.5" S9.5B	$110,700
2030	4	033-Edgecombe	Resurfacing	SR 1155	SR 1156	Dead End	0.09	1.25" S9.5B	$10,125
2030	4	033-Edgecombe	Resurfacing	SR 1156	SR 1152	Dead End	0.35	1.25" S9.5B	$39,375
2030	4	033-Edgecombe	Resurfacing	SR 1157	Nash County Line	SR 1002	1.06	1.5" S9.5B	$164,280
2030	4	033-Edgecombe	Resurfacing	SR 1223	SR 1224	SR 1225	2.06	1.5" S9.5B	$298,100
2030	4	033-Edgecombe	Resurfacing	SR 1360	SR 1225	End of Maintenance	0.43	1.5" S9.5B	$70,785
2030	4	033-Edgecombe	Resurfacing	SR 1415	SR 1404	SR 1407	3.42	1.5" S9.5B	$461,700
2030	4	033-Edgecombe	Resurfacing	SR 1432	US 258	NC 97	1.34	1.5" S9.5B	$180,900
2030	4	033-Edgecombe	Resurfacing	SR 1433	NC 97	SR 1422	1.99	1.5" S9.5B	$268,650
2030	4	033-Edgecombe	Resurfacing	SR 1508	Halifax County Line	NC-122	4.19	1.5" S9.5B	$570,650
2030	4	033-Edgecombe	Resurfacing	US 258	US 64 Alt	Halifax County Line	11.99	Mill 1.5" and 1.5" S9.5B	$2,448,000
2030	4	033-Edgecombe	Preservation	NC 97	SR 1278	NC 33	12.00	Crack Seal	$75,000
2030	4	033-Edgecombe	Preservation	SR 1118	NC 42	NC 122	1.05	Microsurface	$60,250
2030	4	033-Edgecombe	Preservation	SR 1131	SR 1003	NC 43	2.14	Microsurface	$119,100
2030	4	033-Edgecombe	Preservation	SR 1218	SR 1337	SR 1208	2.13	Microsurface	$138,450
2030	4	033-Edgecombe	Preservation	SR 1507	NC 122	SR 1508	1.12	Microsurface	$67,800
2030	4	033-Edgecombe	Preservation	SR 1509	SR 1508	Martin County Line	1.33	Microsurface	$76,450
2030	4	033-Edgecombe	Preservation	SR 1587	NC 111	SR 1527	3.03	Microsurface	$176,950
2030	4	042-Halifax	Resurfacing	NC 122	Edgecombe County Line	NC 125	2.33	Mill 2.0" and 2.0" S9.5C	$575,700
2030	4	042-Halifax	Resurfacing	NC 903	US 258	Martin County Line	6.91	Mill 2.0" and 2.0" S9.5C	$1,565,000
2030	4	042-Halifax	Resurfacing	NC 97	Edgecombe County Line	NC Highway 122	2.44	Mill 2.0" and 2.0" S9.5C	$607,600
2030	4	042-Halifax	Resurfacing	NC Highway 4	NC Highway 561	SR 1310	4.17	Mill 2.0" and 2.0" S9.5C	$909,300
2030	4	042-Halifax	Resurfacing	SR 1003	NC 125	NC 561	4.50	1.5" S9.5B	$607,500
2030	4	042-Halifax	Resurfacing	SR 1102	SR 1100	US 258	4.13	1.5" S9.5B	$640,150
2030	4	042-Halifax	Resurfacing	SR 1122	SR 1003	SR 1117	1.12	1.5" S9.5B	$151,200
2030	4	042-Halifax	Resurfacing	SR 1222	SR 1002	NC-481	1.84	1.5" S9.5B	$248,400
2030	4	042-Halifax	Resurfacing	SR 1417	SR 1418	SR 1001	1.81	1.5" S9.5B	$262,450

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	4	042-Halifax	Resurfacing	SR 1602	SR 1001	NC 561	4.16	1.5" S9.5B	$561,600
2030	4	042-Halifax	Resurfacing	SR 1604	SR 1602	SR 1615	1.39	1.5" S9.5B	$200,100
2030	4	042-Halifax	Preservation	NC Highway 561	NC Highway 48	NC 48	7.16	Crack Seal	$48,625
2030	4	042-Halifax	Preservation	SR 1001	NC 561	I 95	2.53	Crack Seal	$15,813
2030	4	042-Halifax	Preservation	SR 1114	NC 481	NC 125	2.54	Crack Seal	$15,875
2030	4	042-Halifax	Preservation	SR 1135	NC 561	Dead End	1.70	Seal - Double and Fog Seal	$76,500
2030	4	042-Halifax	Preservation	SR 1200	NC 561	SR 1213	3.25	Seal - Double and Fog Seal	$146,250
2030	4	042-Halifax	Preservation	SR 1217	SR 1002	SR 1216	2.25	Microsurface	$146,250
2030	4	042-Halifax	Preservation	SR 1428	SR 1432	US 158	1.86	Seal - Double and Fog Seal	$83,700
2030	4	042-Halifax	Preservation	SR 1804	SR 1827	SR 1118	4.63	Microsurface	$300,950
2030	4	042-Halifax	Preservation	SR 1827	SR 1804	End of Pavement	1.01	Microsurface	$65,650
2030	4	042-Halifax	Preservation	US 301	Edgecombe County Line	NC 481	4.41	Crack Seal	$27,563
2030	4	051-Johnston	Resurfacing	NC 242	NC 55	NC 50	8.65	Mill 1.5" and 1.5" S9.5C	$1,738,125
2030	4	051-Johnston	Resurfacing	NC 242	US 301	I-40 Bridge	2.63	Mill 1.5" and 1.5" S9.5C	$533,875
2030	4	051-Johnston	Resurfacing	NC 27	Harnett County Line	NC 50	1.61	Mill 1.5" and 1.5" S9.5C	$342,125
2030	4	051-Johnston	Resurfacing	NC 42	Wake County Line	SR 3131 +0.7 mi	2.40	Mill 1.5" and 1.5" S9.5C	$510,000
2030	4	051-Johnston	Resurfacing	SR 1001	Wayne County Line	SR 2335	6.83	1.5" S9.5B	$922,050
2030	4	051-Johnston	Resurfacing	SR 1107	SR 1005	NC 242	1.21	1.5" S9.5B	$163,350
2030	4	051-Johnston	Resurfacing	SR 1168	NC 50	Harnett County Line	2.53	1.5" S9.5B	$341,550
2030	4	051-Johnston	Resurfacing	SR 1220	SR 1171	SR 1169	0.80	1.5" S9.5B	$108,000
2030	4	051-Johnston	Resurfacing	SR 1223	SR 1159	SR 1162	1.30	1.5" S9.5B	$175,500
2030	4	051-Johnston	Resurfacing	SR 1302	NC 27	SR 1303	0.54	1.5" S9.5B	$72,900
2030	4	051-Johnston	Resurfacing	SR 1316	Harnett County Line	NC 210	1.70	1.5" S9.5B	$229,500
2030	4	051-Johnston	Resurfacing	SR 1318	NC 210	Dead End	1.34	1.5" S9.5B	$180,630
2030	4	051-Johnston	Resurfacing	SR 1358	SR 1168	NC 242	0.82	1.5" S9.5B	$110,970
2030	4	051-Johnston	Resurfacing	SR 1378	SR 1360	SR 1359	0.45	1.5" S9.5B	$60,750
2030	4	051-Johnston	Resurfacing	SR 1380	NC 242	Dead End	0.70	1.5" S9.5B	$94,500
2030	4	051-Johnston	Resurfacing	SR 1507	SR 1330	NC 210	2.60	1.5" S9.5B	$351,000
2030	4	051-Johnston	Resurfacing	SR 1512	SR 1330	SR 1010	0.73	1.5" S9.5B	$98,550
2030	4	051-Johnston	Resurfacing	SR 1517	SR 1330	NC 50	3.72	1.5" S9.5B	$502,200
2030	4	051-Johnston	Resurfacing	SR 1519	SR 1382	Dead End	0.89	1.5" S9.5B	$130,500
2030	4	051-Johnston	Resurfacing	SR 1536	SR 1306	SR 1532	1.62	1.5" S9.5B	$218,700
2030	4	051-Johnston	Resurfacing	SR 1700	SR 1720	NC 231	4.23	1.5" S9.5B	$571,050
2030	4	051-Johnston	Resurfacing	SR 2127	SR 2110	SR 1938	2.60	1.5" S9.5B	$415,800
2030	4	051-Johnston	Resurfacing	SR 2142	SR 2141	US 301	0.92	1.5" S9.5B	$124,200
2030	4	051-Johnston	Resurfacing	SR 2144	US 301	SR 2143	1.22	1.5" S9.5B	$164,700
2030	4	051-Johnston	Resurfacing	SR 2152	SR 2149	SR 2157	1.31	1.5" S9.5B	$176,850
2030	4	051-Johnston	Resurfacing	SR 2155	NC 42	NC 42	0.69	1.5" S9.5B	$93,150
2030	4	051-Johnston	Resurfacing	SR 2306	SR 2305	SR 2307	0.83	1.5" S9.5B	$112,050
2030	4	051-Johnston	Resurfacing	SR 2309	Pavement Change	US 70 W	1.27	1.5" S9.5B	$184,150
2030	4	051-Johnston	Resurfacing	SR 2315	US 70	MM 0.946	0.95	1.5" S9.5B	$128,250
2030	4	051-Johnston	Resurfacing	SR 2318	US 70 Alt	SR 2141	1.51	1.5" S9.5B	$203,850
2030	4	051-Johnston	Resurfacing	SR 2319	US 70 Alt	SR 2141	0.77	1.5" S9.5B	$103,950
2030	4	051-Johnston	Resurfacing	SR 2337	SR 1001	SR 2335	0.77	1.5" S9.5B	$103,950
2030	4	051-Johnston	Resurfacing	SR 2353	SR 2385	SR 2357	1.70	1.5" S9.5B	$229,500
2030	4	051-Johnston	Resurfacing	SR 2356	SR 2354	SR 2342	2.29	1.5" S9.5B	$309,150
2030	4	051-Johnston	Resurfacing	SR 2369	SR 2342	SR 2320	1.46	1.5" S9.5B	$197,100
2030	4	051-Johnston	Resurfacing	SR 2372	US 70	SR 2535	0.72	Mill 1.5" and 1.5" S9.5B	$144,000
2030	4	051-Johnston	Resurfacing	SR 2500	US 301	SR 2548	0.21	1.5" S9.5B	$34,650
2030	4	051-Johnston	Resurfacing	SR 2508	US 70 B	SR 1007	2.27	1.5" S9.5B	$306,450
2030	4	051-Johnston	Resurfacing	SR 2509	US 70 Alt	SR 1007	1.63	1.5" S9.5B	$220,050
2030	4	051-Johnston	Resurfacing	SR 2529	SR 2530	SR 1007	2.15	1.5" S9.5B	$290,250
2030	4	051-Johnston	Resurfacing	SR 2533	SR 2535	SR 2531	0.98	1.5" S9.5B	$132,300
2030	4	051-Johnston	Resurfacing	SR 2543	SR 1007	SR 1007	4.85	1.5" S9.5B	$654,750
2030	4	051-Johnston	Resurfacing	SR 2548	SR 1007	SR 2500	1.14	1.5" S9.5B	$188,100
2030	4	051-Johnston	Resurfacing	SR 2816	SR 1913	Dead End	0.87	1.5" S9.5B	$117,045
2030	4	051-Johnston	Resurfacing	US 70	NC 42	SR 1923	8.56	Mill 1.5" and 1.5" S9.5C	$2,500,000
2030	4	051-Johnston	Resurfacing	US 70	NC 42	SR 1923	8.57	Mill 1.5" and 1.5" S9.5C	$2,500,000
2030	4	051-Johnston	Preservation	SR 1125	NC 96	SR 1124	1.27	1.25" S9.5B	$142,875

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	4	051-Johnston	Preservation	SR 1126	NC 96	SR 1124	1.39	1.25" S9.5B	$156,375
2030	4	051-Johnston	Preservation	SR 1129	NC 50	Sampson County Line	1.35	1.25" S9.5B	$151,875
2030	4	051-Johnston	Preservation	SR 1310	SR 1309	Harnett County Line	1.16	1.25" S9.5B	$130,500
2030	4	051-Johnston	Preservation	SR 1387	SR 1318	Cul-De-Sac	0.14	1.25" S9.5B	$15,750
2030	4	051-Johnston	Preservation	SR 1390	NC 210	Cul-De-Sac	0.50	1.25" S9.5B	$56,250
2030	4	051-Johnston	Preservation	SR 1391	Cul-De-Sac	SR 1335	0.42	1.25" S9.5B	$47,250
2030	4	051-Johnston	Preservation	SR 1392	SR 1391	Cul-De-Sac	0.16	1.25" S9.5B	$18,000
2030	4	051-Johnston	Preservation	SR 1398	SR 1390	Cul-De-Sac	0.16	1.25" S9.5B	$18,000
2030	4	051-Johnston	Preservation	SR 1842	SR 1521	Cul-De-Sac	0.54	1.25" S9.5B	$60,750
2030	4	051-Johnston	Preservation	SR 2056	SR 1842	Cul-De-Sac	0.16	1.25" S9.5B	$18,000
2030	4	051-Johnston	Preservation	SR 2057	SR 1842	Cul-De-Sac	0.07	1.25" S9.5B	$7,875
2030	4	051-Johnston	Preservation	SR 2225	SR 1544	SR 2226	0.42	1.25" S9.5B	$47,250
2030	4	051-Johnston	Preservation	SR 2226	Cul-De-Sac	Dead End	0.23	1.25" S9.5B	$25,875
2030	4	051-Johnston	Preservation	SR 2227	SR 2225	Cul-De-Sac	0.06	1.25" S9.5B	$6,750
2030	4	051-Johnston	Preservation	SR 2515	SR 2514	SR 1007	1.11	1.25" S9.5B	$124,875
2030	4	051-Johnston	Preservation	SR 2544	SR 1007	SR 2543	0.93	1.25" S9.5B	$104,625
2030	4	051-Johnston	Preservation	SR 2545	SR 1007	SR 2543	0.82	1.25" S9.5B	$92,250
2030	4	051-Johnston	Preservation	SR 2547	SR 2549	End of Pavement	0.59	1.25" S9.5B	$66,375
2030	4	051-Johnston	Preservation	SR 2549	SR 1007	SR 2547	1.10	1.25" S9.5B	$123,750
2030	4	051-Johnston	Preservation	SR 2558	SR 1007	SR 2559	0.09	1.25" S9.5B	$10,125
2030	4	051-Johnston	Preservation	SR 2559	SR 2507	Cul-De-Sac	0.29	1.25" S9.5B	$32,625
2030	4	051-Johnston	Preservation	SR 2702	SR 1310	Cul-De-Sac	0.16	1.25" S9.5B	$18,000
2030	4	051-Johnston	Preservation	SR 2711	SR 1318	Cul-De-Sac	0.23	1.25" S9.5B	$25,875
2030	4	051-Johnston	Preservation	SR 2712	NC 210	Cul-De-Sac	0.33	1.25" S9.5B	$37,125
2030	4	051-Johnston	Preservation	SR 2713	Sr 2712	Cul-De-Sac	0.18	1.25" S9.5B	$20,250
2030	4	051-Johnston	Preservation	SR 2714	SR 2712	Cul-De-Sac	0.10	1.25" S9.5B	$11,250
2030	4	051-Johnston	Preservation	SR 2715	Cul-De-Sac	Cul-De-Sac	0.19	1.25" S9.5B	$21,375
2030	4	051-Johnston	Preservation	SR 2720	SR 1317	Cul-De-Sac	0.49	1.25" S9.5B	$55,125
2030	4	051-Johnston	Preservation	SR 2721	SR 2720	Cul-De-Sac	0.36	1.25" S9.5B	$40,500
2030	4	051-Johnston	Preservation	SR 2742	SR 2715	Cul-De-Sac	0.05	1.25" S9.5B	$5,625
2030	4	051-Johnston	Preservation	SR 2753	SR 1318	Cul-De-Sac	0.22	1.25" S9.5B	$24,750
2030	4	051-Johnston	Preservation	SR 2754	SR 2753	SR 2755	0.10	1.25" S9.5B	$11,250
2030	4	051-Johnston	Preservation	SR 2755	Cul-De-Sac	Cul-De-Sac	0.12	1.25" S9.5B	$13,500
2030	4	051-Johnston	Preservation	SR 2765	Sr 2767	Cul-De-Sac	0.08	1.25" S9.5B	$9,000
2030	4	051-Johnston	Preservation	SR 2766	SR 2767	Cul-De-Sac	0.08	1.25" S9.5B	$9,000
2030	4	051-Johnston	Preservation	SR 2767	SR 1318	Cul-De-Sac	0.29	1.25" S9.5B	$32,625
2030	4	051-Johnston	Preservation	SR 2982	SR 1517	Cul-De-Sac	0.49	1.25" S9.5B	$55,125
2030	4	051-Johnston	Preservation	SR 2983	SR 2982	Cul-De-Sac	0.06	1.25" S9.5B	$6,750
2030	4	051-Johnston	Preservation	SR 2984	SR 2982	Cul-De-Sac	0.23	1.25" S9.5B	$25,875
2030	4	051-Johnston	Preservation	SR 2985	SR 2984	Cul-De-Sac	0.10	1.25" S9.5B	$11,250
2030	4	051-Johnston	Preservation	SR 2986	NC 210	Dead End	0.74	1.25" S9.5B	$83,250
2030	4	051-Johnston	Preservation	SR 2987	SR 2986	Cul-De-Sac	0.25	1.25" S9.5B	$28,125
2030	4	051-Johnston	Preservation	SR 2988	SR 2987	Cul-De-Sac	0.14	1.25" S9.5B	$15,750
2030	4	051-Johnston	Preservation	SR 2989	SR 2986	Cul-De-Sac	0.28	1.25" S9.5B	$31,500
2030	4	064-Nash	Resurfacing	NC 97	Franklin County Line	SR 1137	7.16	Mill 1.5" and 1.5" S9.5B	$3,436,800
2030	4	064-Nash	Resurfacing	SR 1105	Arlington Street	Tarboro St	0.33	Mill 1.5" and 1.5" S9.5B	$59,400
2030	4	064-Nash	Resurfacing	SR 1137	Franklin County Line	NC 231	2.17	1.25" S9.5B	$287,525
2030	4	064-Nash	Resurfacing	SR 1138	SR 1137	SR 1952	2.58	1.25" S9.5B	$290,250
2030	4	064-Nash	Resurfacing	SR 1414	SR 1004	SR 1004	3.14	1.25" S9.5B	$356,625
2030	4	064-Nash	Resurfacing	SR 1415	SR 1004	SR 1414	0.63	1.25" S9.5B	$70,875
2030	4	064-Nash	Resurfacing	SR 1416	SR 1414	SR 1417	0.81	1.25" S9.5B	$91,125
2030	4	064-Nash	Resurfacing	SR 1436	SR 1433	SR 1437	1.02	1.5" S9.5B	$147,900
2030	4	064-Nash	Resurfacing	SR 1437	SR 1435	SR 1003	1.90	1.25" S9.5B	$232,750
2030	4	064-Nash	Resurfacing	SR 1510	SR 1501	SR 1500	1.91	1.25" S9.5B	$214,875
2030	4	064-Nash	Resurfacing	SR 1510	SR 1500	NC 33	4.96	1.25" S9.5B	$607,600
2030	4	064-Nash	Resurfacing	SR 1510	SR 1516	NC 33	1.55	1.25" S9.5B	$205,375
2030	4	064-Nash	Resurfacing	SR 1520	SR 1510	SR 1519	1.59	1.25" S9.5B	$178,875
2030	4	064-Nash	Resurfacing	SR 1529	SR 1003	SR 1510	1.21	1.25" S9.5B	$136,125
2030	4	064-Nash	Resurfacing	SR 1530	NC 43	SR 1003	3.61	1.25" S9.5B	$406,125

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	4	064-Nash	Resurfacing	SR 1589	SR 1524	NC 43	1.85	1.25" S9.5B	$208,125
2030	4	064-Nash	Resurfacing	SR 1646	SR 1604	SR 1609	0.83	1.25" S9.5B	$101,675
2030	4	064-Nash	Resurfacing	SR 1714	Mile Marker 1.44	Mile Marker 2.76	1.32	Mill 1.5" and 1.5" S9.5B	$257,400
2030	4	064-Nash	Resurfacing	SR 1814	SR 1770	Mile Marker 0.26	0.26	1.5" S9.5B	$42,900
2030	4	064-Nash	Resurfacing	SR 1960	SR 1961	Wilson County Line	3.01	1.25" S9.5B	$338,625
2030	4	064-Nash	Resurfacing	SR 1962	SR 1961	SR 1945	1.09	1.25" S9.5B	$122,625
2030	4	064-Nash	Resurfacing	SR 1965	SR 1945	Wilson County Line	0.70	1.25" S9.5B	$78,750
2030	4	064-Nash	Resurfacing	SR 1970	Wilson County Line	Dead End	0.26	1.25" S9.5B	$29,250
2030	4	064-Nash	Resurfacing	SR 1993	Old Smithfield Road	Old Bailey Hwy	2.05	1.25" S9.5B	$230,625
2030	4	064-Nash	Resurfacing	SR 2214	SR 1544	Dead End	0.34	1.25" S9.5B	$33,750
2030	4	064-Nash	Preservation	SR 1321	NC-581	NC-58	7.52	1.0" S4.75A	$846,000
2030	4	064-Nash	Preservation	SR 1410	NC-58	Dead End	0.27	1.0" S4.75A	$30,375
2030	4	064-Nash	Preservation	SR 1445	SR 1425	Dead End	0.15	1.0" S4.75A	$16,875
2030	4	064-Nash	Preservation	SR 1585	SR 1507	Dead End	0.11	1.0" S4.75A	$12,375
2030	4	064-Nash	Preservation	SR 1953	NC 581	SR 1134	1.84	1.25" S9.5B	$207,000
2030	4	064-Nash	Preservation	SR 1986	SR 1945	NC-581	0.26	1.25" S9.5B	$29,250
2030	4	064-Nash	Preservation	SR 2328	SR 1507	Dead End	0.10	1.0" S4.75A	$11,250
2030	4	064-Nash	Preservation	SR 2337	SR 1532	Dead End	0.37	1.0" S4.75A	$41,625
2030	4	064-Nash	Preservation	SR 2338	SR 2337	Dead End	0.09	1.0" S4.75A	$10,125
2030	4	096-Wayne	Resurfacing	NC 111	NC 581	SR 1962	2.00	Mill 1.5" and 1.5" S9.5B	$960,000
2030	4	096-Wayne	Resurfacing	NC 111	Pavement Joint	US 70	0.37	Mill 1.5" and 1.5" S9.5B	$177,600
2030	4	096-Wayne	Resurfacing	NC 581	NC 111	US 117	6.06	Mill 1.5" and 1.5" S9.5C	$1,581,000
2030	4	096-Wayne	Resurfacing	NC 581	US 117	Old Cherry	1.52	Mill 1.5" and 1.5" S9.5B	$448,400
2030	4	096-Wayne	Resurfacing	NC 581	Stevens Mill / Cherry	SR 1007	2.00	1.5" S9.5B	$330,000
2030	4	096-Wayne	Resurfacing	SR 1007	Pavement Joint at Bridge	Randy Drive	1.90	1.5" S9.5B and Widen	$455,500
2030	4	096-Wayne	Resurfacing	SR 1007	NC 581	Pavement Joint at Bridge	1.90	1.5" S9.5B and Widen	$455,500
2030	4	096-Wayne	Resurfacing	SR 1304	SR 1300	US 117	0.37	Mill 1.5" and 1.5" S9.5B	$109,150
2030	4	096-Wayne	Resurfacing	SR 1362	SR 1003	Dead End	1.10	1.5" S9.5B	$148,500
2030	4	096-Wayne	Resurfacing	SR 1571	Lindsey Street	SR 1709	0.38	1.5" S9.5B	$65,550
2030	4	096-Wayne	Resurfacing	SR 1571	SR 1556	Lindsey Street	2.00	1.5" S9.5B	$370,000
2030	4	096-Wayne	Resurfacing	SR 2312	US 117	SR 2314	0.09	1.5" S9.5B and Widen	$20,550
2030	4	096-Wayne	Resurfacing	US 117 / US 13	Pavement Joint at Bridge # 0053	vement Joint at Goldsboro City Lim	1.13	Mill 2.0" and 2.0" S9.5C	$443,700
2030	4	096-Wayne	Resurfacing	US 117 Bypass	Pavement Joint at Goldsboro City Limits	Pavement Joint at Bridge # 0052	1.12	Mill 2.0" and 2.0" S9.5C	$313,200
2030	4	096-Wayne	Resurfacing	US 70 EB	N Berkley Blvd	Lizzell Road	3.85	Mill 1.5" and 1.5" S9.5D	$1,042,200
2030	4	096-Wayne	Resurfacing	US 70 WB	Pavement Joint	N Jordon Blvd	4.00	Mill 1.5" and 1.5" S9.5D	$1,080,000
2030	4	096-Wayne	Preservation	SR 1148	US 117	SR 1149	0.25	1.25" S9.5B	$28,125
2030	4	096-Wayne	Preservation	SR 1149	US 13	End of Maintenance	0.58	1.25" S9.5B	$65,250
2030	4	096-Wayne	Preservation	SR 1150	US 117	SR 1149	0.26	1.25" S9.5B	$29,250
2030	4	096-Wayne	Preservation	SR 1152	US 117	End of Maintenance	0.14	1.25" S9.5B	$15,750
2030	4	096-Wayne	Preservation	SR 1156	SR 1149	End of Maintenance	0.08	1.25" S9.5B	$9,000
2030	4	096-Wayne	Preservation	SR 1159	US 117	End of Maintenance	0.14	1.25" S9.5B	$15,750
2030	4	096-Wayne	Preservation	SR 1389	US 117	End of Maintenance	0.11	1.25" S9.5B	$12,375
2030	4	096-Wayne	Preservation	SR 1599	US 117	End of Maintenance	0.21	1.25" S9.5B	$23,625
2030	4	096-Wayne	Preservation	SR 1607	NC 111	SR 1545	0.34	1.25" S9.5B	$38,250
2030	4	096-Wayne	Preservation	SR 1647	NC 111	SR 1647	1.04	1.25" S9.5B	$117,000
2030	4	096-Wayne	Preservation	SR 1661	SR 1647	SR 1647	0.13	1.25" S9.5B	$14,625
2030	4	096-Wayne	Preservation	SR 1662	SR 1647	SR 1647	0.12	1.25" S9.5B	$13,500
2030	4	096-Wayne	Preservation	SR 2005	SR 2004	SR 2006	0.08	1.25" S9.5B	$9,000
2030	4	096-Wayne	Preservation	SR 2013	SR 1926	SR 2016	0.19	1.25" S9.5B	$21,375
2030	4	096-Wayne	Preservation	SR 2014	Begin Div	Cul-De-Sac	0.53	1.25" S9.5B	$59,625
2030	4	096-Wayne	Preservation	SR 2014	Begin Maintenance	Dead End	0.61	1.25" S9.5B	$68,625
2030	4	096-Wayne	Preservation	SR 2014	Begin Div	SR 2014	0.04	1.25" S9.5B	$3,375
2030	4	096-Wayne	Preservation	SR 2015	SR 2014	Cul-De-Sac	0.07	1.25" S9.5B	$7,875
2030	4	096-Wayne	Preservation	SR 2016	Cul-De-Sac	Cul-De-Sac	0.63	1.25" S9.5B	$70,875
2030	4	096-Wayne	Preservation	SR 2017	SR 2014	Cul-De-Sac	0.06	1.25" S9.5B	$6,750
2030	4	096-Wayne	Preservation	SR 2020	SR 2016	Cul-De-Sac	0.06	1.25" S9.5B	$6,750
2030	4	096-Wayne	Preservation	SR 2021	SR 2004	SR 2014	0.41	1.25" S9.5B	$46,125
2030	4	096-Wayne	Preservation	SR 2022	SR 2021	Cul-De-Sac	0.04	1.25" S9.5B	$4,500
2030	4	096-Wayne	Preservation	SR 2023	SR 2004	Cul-De-Sac	0.09	1.25" S9.5B	$10,125

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	4	096-Wayne	Preservation	SR 2043	SR 1926	SR 2044	0.27	1.25" S9.5B	$30,375
2030	4	096-Wayne	Preservation	SR 2044	SR 1930	End of Maintenance	0.16	1.25" S9.5B	$18,000
2030	4	096-Wayne	Preservation	SR 2057	SR 1927	End of Maintenance	0.43	1.25" S9.5B	$48,375
2030	4	096-Wayne	Preservation	SR 2058	SR 2057	SR 2057	0.25	1.25" S9.5B	$28,125
2030	4	096-Wayne	Preservation	SR 2059	SR 1927	End of Maintenance	0.31	1.25" S9.5B	$34,875
2030	4	096-Wayne	Preservation	SR 2060	SR 2059	Cul-De-Sac	0.15	1.25" S9.5B	$16,875
2030	4	096-Wayne	Preservation	SR 2061	SR 2059	Cul-De-Sac	0.05	1.25" S9.5B	$5,625
2030	4	096-Wayne	Preservation	SR 2310	NC 111	End of Maintenance	0.82	1.25" S9.5B	$92,250
2030	4	096-Wayne	Preservation	SR 2310	SR 2310	NC-111	0.12	1.25" S9.5B	$13,500
2030	4	096-Wayne	Preservation	SR 2311	SR 2310	End of Maintenance	0.32	1.25" S9.5B	$36,000
2030	4	096-Wayne	Preservation	SR 2316	SR 2310	SR 2311	0.38	1.25" S9.5B	$42,750
2030	4	096-Wayne	Preservation	SR 2317	SR 2316	SR 2316	0.33	1.25" S9.5B	$37,125
2030	4	096-Wayne	Preservation	SR 2328	SR 1545	End of Maintenance	0.38	1.25" S9.5B	$42,750
2030	4	096-Wayne	Preservation	SR 2329	SR 2328	End of Maintenance	0.44	1.25" S9.5B	$77,875
2030	4	096-Wayne	Preservation	SR 2330	SR 2328	Cul-De-Sac	0.04	1.25" S9.5B	$4,500
2030	4	096-Wayne	Preservation	SR 2332	SR 2310	End of Maintenance	0.06	1.25" S9.5B	$6,750
2030	4	096-Wayne	Preservation	SR 2333	SR 2317	Cul-De-Sac	0.05	1.25" S9.5B	$5,625
2030	4	096-Wayne	Preservation	SR 2334	SR 2317	Cul-De-Sac	0.04	1.25" S9.5B	$4,500
2030	4	096-Wayne	Preservation	SR 2335	SR 2316	Cul-De-Sac	0.04	1.25" S9.5B	$4,500
2030	4	096-Wayne	Preservation	SR 2336	SR 2311	End of Maintenance	0.03	1.25" S9.5B	$3,375
2030	4	096-Wayne	Preservation	SR 2339	SR 2329	End of Maintenance	0.19	1.25" S9.5B	$21,375
2030	4	096-Wayne	Preservation	SR 2340	SR 2329	End of Maintenance	0.04	1.25" S9.5B	$4,500
2030	4	096-Wayne	Preservation	SR 2342	SR 2310	End of Maintenance	0.13	1.25" S9.5B	$14,625
2030	4	098-Wilson	Resurfacing	NC 111	Good News Church Road	Edgecombe County Line	5.04	Mill 1.5" and 1.5" S9.5B	$843,600
2030	4	098-Wilson	Resurfacing	NC 111 / 222	NC 58	Good News Church Road	5.50	Mill 1.5" and 1.5" S9.5B	$1,009,350
2030	4	098-Wilson	Resurfacing	SR 1111	SR 1100	US 301	2.71	1.25" S9.5B	$304,875
2030	4	098-Wilson	Resurfacing	SR 1118	NC 581	SR 1103	3.38	1.25" S9.5B	$379,688
2030	4	098-Wilson	Resurfacing	SR 1136	NC 581	Joint at I-95 Bridge	5.88	1.25" S9.5B	$661,500
2030	4	098-Wilson	Resurfacing	SR 1136	SR 1131	NC 581	1.12	1.5" S9.5B and Widen	$258,000
2030	4	098-Wilson	Resurfacing	SR 1169	SR 1162	US 301	3.55	1.25" S9.5B	$399,375
2030	4	098-Wilson	Resurfacing	SR 1176	US 301	Dead End	0.24	Mill 1.5" and 1.5" S9.5B	$48,000
2030	4	098-Wilson	Resurfacing	SR 1179	NC 581	SR 1195	1.16	1.25" S9.5B	$130,500
2030	4	098-Wilson	Resurfacing	SR 1308	SR 1306	Nash County Line	0.81	1.5" S9.5B	$117,450
2030	4	098-Wilson	Resurfacing	SR 1422	SR 1419	Dead End	0.96	1.25" S9.5B	$108,000
2030	4	098-Wilson	Resurfacing	SR 1606	SR 1670	SR 1613	3.35	1.5" S9.5B	$452,250
2030	4	098-Wilson	Resurfacing	SR 1624	SR 1622	SR 1542	0.45	1.25" S9.5B	$50,625
2030	4	098-Wilson	Resurfacing	SR 1646	SR 1645	US 301	1.56	1.25" S9.5B	$175,500
2030	4	098-Wilson	Resurfacing	US 264 Alt	I-587	Green County Line	5.08	Mill 1.5" and 1.5" S9.5D	$996,000
2030	4	098-Wilson	Preservation	SR 1101	US 301	SR 1100	1.10	.75" S4.75A	$96,250
2030	4	098-Wilson	Preservation	SR 1105	Johnston County Line	SR 1195	0.63	1.0" S4.75A	$70,875
2030	4	098-Wilson	Preservation	SR 1113	US 301	Dead End	4.50	Crack Seal	$28,125
2030	4	098-Wilson	Preservation	SR 1131	Nash County Line	SR 1140	6.01	Crack Seal	$37,562
2030	4	098-Wilson	Preservation	SR 1136	Bridge Joint at I-95	Airport Blvd	1.75	Crack Seal	$10,937
2030	4	098-Wilson	Preservation	SR 1160	NC 42	SR 1136	1.74	1.0" S4.75A	$195,750
2030	4	098-Wilson	Preservation	SR 1309	US 264 Alt	Nash County Line	3.18	Crack Seal	$19,875
2030	4	098-Wilson	Preservation	SR 1384	SR 1328	Dead End	0.33	Crack Seal	$2,068
2030	4	098-Wilson	Preservation	SR 1505	SR 1506	SR 1514	1.36	1.0" S4.75A	$153,000
2030	4	098-Wilson	Preservation	SR 1533	SR 1526	US 264 Alt	1.23	1.0" S4.75A	$138,375
2030	4	098-Wilson	Preservation	SR 1626	SR 1602	NC 58	0.85	1.0" S4.75A	$95,625
2030	5	032-Durham	Resurfacing	Bakers Mill Rd	SR 1113	Cul-de-sac	0.40	Full Depth Patching and 1.25" S9.5B	$86,000
2030	5	032-Durham	Resurfacing	Bancroft Dr	SR 1384	SR 1398	0.08	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$23,000
2030	5	032-Durham	Resurfacing	Beaumont Dr	SR 1113	Dead End	0.29	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$79,000
2030	5	032-Durham	Resurfacing	Bristlewood Dr	SR 2085	SR 2039 (To Gravel Rd)	0.18	Full Depth Patching and 1.5" S9.5B	$40,000
2030	5	032-Durham	Resurfacing	Coley Rd.	SR 1902	NC 98	1.96	Full Depth Patching and 1.5" S9.5B	$427,000
2030	5	032-Durham	Resurfacing	Duke St	SR 1127	West Club Blvd	1.42	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$468,000
2030	5	032-Durham	Resurfacing	Fairbanks Circle	SR 1397	Cul-de-sac	0.04	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$10,000
2030	5	032-Durham	Resurfacing	Fayetteville Rd	NC 751	Woodcroft Pkwy	3.72	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,867,000
2030	5	032-Durham	Resurfacing	Gregson St	SR 1127	SR 1327	1.41	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$467,000
2030	5	032-Durham	Resurfacing	Montvale Dr	SR 1717 (in Orange County)	Dead End	0.22	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$68,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	5	032-Durham	Resurfacing	NC 54	NC 55	Pavement Joint	1.90	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,083,000
2030	5	032-Durham	Resurfacing	NC 55	Pavement Joint South of Latitude Dr	NC 147 Bridge	2.23	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,156,000
2030	5	032-Durham	Resurfacing	NC 751	NC 54	Littlewood Ln	2.14	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,359,000
2030	5	032-Durham	Resurfacing	NC 751	Roun-a-bout	SR 1307	3.78	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$1,485,000
2030	5	032-Durham	Resurfacing	Osborne Pl	SR 1384	Cul-de-sac	0.11	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$34,000
2030	5	032-Durham	Resurfacing	Randall Rd	SR 1283	1284	0.09	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$29,000
2030	5	032-Durham	Resurfacing	Safeway St	US 70 Bus	SR 1399	0.07	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$20,000
2030	5	032-Durham	Resurfacing	Sanders Ave.	US 70	ıavement joint at new developmen	0.11	Full Depth Patching and 1.5" S9.5B	$22,000
2030	5	032-Durham	Resurfacing	Tilley Farm Rd	SR 1471	SR 1607	1.43	1.0" S9.5B	$177,000
2030	5	032-Durham	Resurfacing	Yardley Terrace	SR 1283	SR 1285	0.26	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$85,000
2030	5	032-Durham	Preservation	Belden Dr	SR 1926	End Maintenance	0.15	1.0" S9.5B	$19,795
2030	5	032-Durham	Preservation	Dandy Dr	SR 1895	SR 1893	0.18	1.0" S9.5B	$20,000
2030	5	032-Durham	Preservation	Dude Ranch Rd	SR 1812	Dead End	0.50	1.0" S9.5B	$56,000
2030	5	032-Durham	Preservation	Marley Dr	SR 1926	US 70 / S Miami Blvd	0.43	1.0" S9.5B	$53,000
2030	5	032-Durham	Preservation	Moriah Rd	SR 1471	Person County Line	0.40	1.0" S9.5B	$50,000
2030	5	032-Durham	Preservation	Nob Hill Rd	SR 1896	SR 1897	0.74	1.0" S9.5B	$83,000
2030	5	032-Durham	Preservation	Old Red Mountain Rd	SR 1471	Dead End	0.17	1.0" S9.5B	$19,000
2030	5	032-Durham	Preservation	Paulwood Ct	SR 1800	Dead End	0.15	1.0" S9.5B	$17,000
2030	5	032-Durham	Preservation	Peyton Ave	US 70 / S Miami Blvd	SR 1957	0.20	1.0" S9.5B	$25,000
2030	5	032-Durham	Preservation	Pineview Cir	SR 1303	SR 1303	0.38	1.0" S9.5B	$47,000
2030	5	032-Durham	Preservation	Rodeo Dr	SR 1893	SR 1895	0.25	1.0" S9.5B	$28,000
2030	5	032-Durham	Preservation	Shaw Rd	SR 1800	Dead End	1.08	1.0" S9.5B	$121,000
2030	5	032-Durham	Preservation	Sweetbriar Rd	SR 2501	End Maintenance	0.33	1.0" S9.5B	$37,000
2030	5	032-Durham	Preservation	Tyonek Dr	SR 2003	SR 1957	0.06	1.0" S9.5B	$10,000
2030	5	032-Durham	Preservation	Tyonek Dr	SR 1926	SR 2077	0.32	1.0" S9.5B	$40,000
2030	5	035-Franklin	Resurfacing	Alston Pruitt Rd	SR 1600	SR 1600	0.38	Full Depth Patching and 1.25" S9.5B	$67,000
2030	5	035-Franklin	Resurfacing	Alton Acres Rd	SR 1600	Cul-de-sac	0.12	Full Depth Patching and 1.25" S9.5B	$23,000
2030	5	035-Franklin	Resurfacing	Best View	SR 1235	SR 1235	0.49	Full Depth Patching and 1.5" S9.5B	$112,000
2030	5	035-Franklin	Resurfacing	Cedar Creek Rd.	US 1 Alt	SR 1100	5.88	Full Depth Patching and 1.5" S9.5B	$1,411,000
2030	5	035-Franklin	Resurfacing	Chicken Farm Rd	SR 1207	SR 1208	0.14	Full Depth Patching and 1.5" S9.5B	$27,000
2030	5	035-Franklin	Resurfacing	East River	NC 56	SR 1601	2.71	Full Depth Patching and 1.5" S9.5B	$621,000
2030	5	035-Franklin	Resurfacing	Foster Rd	NC 561	NC 561	0.61	Full Depth Patching and 1.25" S9.5B	$107,000
2030	5	035-Franklin	Resurfacing	Fred Wilder Rd	NC 56	SR 1127	1.78	Full Depth Patching and 1.5" S9.5B	$388,000
2030	5	035-Franklin	Resurfacing	Long Mill Rd	SR 1138	SR 1202	3.16	Full Depth Patching and 1.5" S9.5B	$723,000
2030	5	035-Franklin	Resurfacing	Massenberg St	SR 1207	SR 1209	0.15	Full Depth Patching and 1.5" S9.5B	$29,000
2030	5	035-Franklin	Resurfacing	Perry Gupton Rd	NC 561	NC 561	0.34	Full Depth Patching and 1.25" S9.5B	$60,000
2030	5	035-Franklin	Preservation	Alert	WARREN CO	SR 1409	1.26	Full Depth Patching and Double Seal and Fog Seal	$131,000
2030	5	035-Franklin	Preservation	George Leonard	SR 1600	SR 1001	2.00	Full Depth Patching and 1.25" S9.5B	$146,000
2030	5	035-Franklin	Preservation	Strange	SR 1421SR 1421	NC-56	1.56	Full Depth Patching and 1.25" S9.5B	$319,000
2030	5	035-Franklin	Preservation	Wood Church	NC 561	NC 561	1.55	Full Depth Patching and 1.25" S9.5B	$304,000
2030	5	039-Granville	Resurfacing	Amis Chapel	NC 96	VIRGINIA	3.73	Full Depth Patching and 1.5" S9.5B	$812,000
2030	5	039-Granville	Resurfacing	Hallie Burnette	SR 1004	SR 1004	3.73	Full Depth Patching and 1.5" S9.5B	$813,000
2030	5	039-Granville	Resurfacing	J.G. Morton	US 15	SR 1445	3.84	Full Depth Patching and 1.5" S9.5B	$837,000
2030	5	039-Granville	Resurfacing	Lewis St	Montague Centre Rd	US 15	3.09	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$852,000
2030	5	039-Granville	Resurfacing	Lewis St	Montague Centre Rd	J' north of Belltown Rd, past concre	0.59	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$163,000
2030	5	039-Granville	Resurfacing	Sidney Cottrell	SR 1518	SR 1515	1.32	Full Depth Patching and 1.5" S9.5B	$288,000
2030	5	039-Granville	Resurfacing	US 15	NC 158	SR 1426 (Gela Rd)	5.47	Full Depth Patching and 1.5" S9.5B	$1,372,000
2030	5	039-Granville	Resurfacing	Walters Rd	NC 56	NC 56	4.09	Full Depth Patching and 1.5" S9.5B	$891,000
2030	5	039-Granville	Resurfacing	Webb Chapel	PERSON CO	SR 1325	2.80	Full Depth Patching and 1.5" S9.5B	$611,000
2030	5	039-Granville	Preservation	George Winston Rd	SR 1300	SR 1400	1.85	Microsurface	$150,000
2030	5	039-Granville	Preservation	Graham Hobgood	US 158	SR 1304	2.77	Microsurface	$224,000
2030	5	039-Granville	Preservation	Sunset Rd	NC 96	SR 1307	5.36	Full Depth Patching and 1.25" S9.5B	$1,109,000
2030	5	073-Person	Resurfacing	Edwin Robertson Road	SR 1326	SR 1333	2.91	Full Depth Patching and 1.5" S9.5C	$835,000
2030	5	073-Person	Resurfacing	Helena-Moriah Road	SR 1717	SR 1729	4.73	Full Depth Patching and 1.5" S9.5C	$1,149,000
2030	5	073-Person	Resurfacing	NC 49	US 501	Granville Co	12.63	Full Depth Patching and 1.5" S9.5B	$3,305,000
2030	5	073-Person	Resurfacing	Stoney Mountain Rd	SR 1715	SR 1723	2.10	Full Depth Patching and 1.5" S9.5B	$458,000
2030	5	073-Person	Resurfacing	Tom Oakley Rd	SR 1123	Pavement Change	1.41	Full Depth Patching and 1.5" S9.5B	$307,000
2030	5	073-Person	Preservation	Hall Rd	SR 1176	Cul-de-sac	0.56	Full Depth Patching and Double Seal and Fog Seal	$55,000
2030	5	073-Person	Preservation	Jones-Paylor Rd	SR 1512	DEAD END	1.38	Full Depth Patching and Double Seal and Fog Seal	$136,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	5	073-Person	Preservation	Lawson Adcock Rd	SR 1542	SR 1560	1.63	Full Depth Patching and Double Seal and Fog Seal	$161,000
2030	5	073-Person	Preservation	Nelson Loop Rd	SR 1536	SR 1536	1.56	Full Depth Patching and Double Seal	$154,000
2030	5	073-Person	Preservation	Thomas Green Rd	GRANVILLE CO	SR 1561	2.64	Full Depth Patching and Double Seal and Fog Seal	$261,000
2030	5	073-Person	Preservation	Vernon Hill Church Rd	GRANVILLE CO	SR 1561	0.66	Full Depth Patching and Double Seal and Fog Seal	$65,000
2030	5	073-Person	Preservation	Whitmore Rd	SR 1111	Cul-de-sac	0.84	Full Depth Patching and Double Seal and Fog Seal	$83,000
2030	5	091-Vance	Resurfacing	Foster Rd.	NC 39	END MAINT	1.07	1.0" S9.5B	$133,000
2030	5	091-Vance	Resurfacing	Peter Gill	SR 1115	SR 1547	0.90	Full Depth Patching and 1.5" S9.5B	$196,000
2030	5	091-Vance	Resurfacing	Peter Gill	US 1 Bus	SR 1547	1.26	Full Depth Patching and 1.5" S9.5B	$276,000
2030	5	091-Vance	Resurfacing	St Andrews Church Rd	SR 1303	NC 39	1.94	Full Depth Patching and 1.25" S9.5B	$377,000
2030	5	091-Vance	Resurfacing	William St	End Concrete	SR 1179	0.73	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$240,000
2030	5	091-Vance	Resurfacing	William St	Beg C&G/Pavement Joint	Begin Concrete	1.21	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$400,000
2030	5	091-Vance	Preservation	Morris Wilson	SR 1303	End Pavement	0.45	Full Depth Patching and 1.25" S9.5B	$79,000
2030	5	091-Vance	Preservation	North Piney Grove	End Maintenance	End Maintenance	1.49	Full Depth Patching and 1.25" S9.5B	$290,000
2030	5	091-Vance	Preservation	Wilson Brothers	Warren Co	SR 1363	1.66	Full Depth Patching and 1.25" S9.5B	$291,000
2030	5	092-Wake	Resurfacing	Alonzo Rd	SR 2701	Cul-de-sac	0.96	Full Depth Patching and 1.5" S9.5B	$209,000
2030	5	092-Wake	Resurfacing	Alston Ave	Dead End	Dead End	0.61	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$161,000
2030	5	092-Wake	Resurfacing	Apple Meadow Dr	SR 2767	Cul-de-sac	0.39	Full Depth Patching and 1.5" S9.5B	$85,000
2030	5	092-Wake	Resurfacing	Ashton Hollow Dr	SR 2725	SR 4892	0.55	Full Depth Patching and 1.5" S9.5B	$119,000
2030	5	092-Wake	Resurfacing	Automotive Way	Brookside Dr	US 401	0.24	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$79,000
2030	5	092-Wake	Resurfacing	Bayview Dr	SR 1907	Cul-de-sac	0.16	Full Depth Patching and 1.5" S9.5B	$34,000
2030	5	092-Wake	Resurfacing	Bennyfield Ct	SR 3769	Cul-de-sac	0.08	Full Depth Patching and 1.5" S9.5B	$16,000
2030	5	092-Wake	Resurfacing	Big Buck Ln	SR-5391	Cul-de-sac	0.12	Full Depth Patching and 1.5" S9.5B	$26,000
2030	5	092-Wake	Resurfacing	Blue Slate Ct	SR 5072	Cul-de-sac	0.10	Full Depth Patching and 1.5" S9.5B	$20,000
2030	5	092-Wake	Resurfacing	Bushy Branch Dr	Cul-de-sac	SR 4965	0.55	Full Depth Patching and 1.5" S9.5B	$120,000
2030	5	092-Wake	Resurfacing	Clamshell Dr	SR 4544	SR 4546	0.31	Full Depth Patching and 1.5" S9.5B	$68,000
2030	5	092-Wake	Resurfacing	Darnley St	SR-4965	Cul-de-sac	0.13	Full Depth Patching and 1.5" S9.5B	$28,000
2030	5	092-Wake	Resurfacing	Davis Drive	Durhan Couty Line	SR 1639	0.91	Full Depth Patching and 1.5" S9.5B	$407,000
2030	5	092-Wake	Resurfacing	Davis Drive	SR 1639	Durham County Line	0.90	Full Depth Patching and 1.5" S9.5B	$374,000
2030	5	092-Wake	Resurfacing	E Edenton St	SR-2911	Mcdowell St	1.28	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$535,000
2030	5	092-Wake	Resurfacing	Eagle Creek Ct	SR-1489	SR-0054	0.26	Full Depth Patching and 1.5" S9.5B	$57,000
2030	5	092-Wake	Resurfacing	Eastwood Drive	SR 1301	Cul-de-sac	0.17	Full Depth Patching and 1.5" S9.5B	$33,000
2030	5	092-Wake	Resurfacing	English Cir	SR-4858	Cul-de-sac	0.12	Full Depth Patching and 1.5" S9.5B	$24,000
2030	5	092-Wake	Resurfacing	Falcon Crest Cir	SR 2791	Cul-de-sac	0.16	Full Depth Patching and 1.5" S9.5B	$28,000
2030	5	092-Wake	Resurfacing	Farmstone Dr	SR 5070	SR 5071	0.21	Full Depth Patching and 1.5" S9.5B	$46,000
2030	5	092-Wake	Resurfacing	Fox Stone Dr	SR 5070	Cul-de-sac	0.09	Full Depth Patching and 1.5" S9.5B	$19,000
2030	5	092-Wake	Resurfacing	Foxbrook Dr	SR 1375	Cul-de-sac	0.49	Full Depth Patching and 1.5" S9.5B	$107,000
2030	5	092-Wake	Resurfacing	Freewood Ct	SR-1489	Cul-de-sac	0.07	Full Depth Patching and 1.5" S9.5B	$14,000
2030	5	092-Wake	Resurfacing	Gold Dust Ln	NC-55	Cul-de-sac	0.44	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$97,000
2030	5	092-Wake	Resurfacing	Harvey Johnson Rd	SR 2725	Cul-de-sac	0.51	Full Depth Patching and 1.5" S9.5B	$111,000
2030	5	092-Wake	Resurfacing	High Oaks Ln	SR-1489	Cul-de-sac	0.05	Full Depth Patching and 1.5" S9.5B	$10,000
2030	5	092-Wake	Resurfacing	Hodges Rd	US 401	SR 1476	0.20	Full Depth Patching and 1.5" S9.5B	$39,000
2030	5	092-Wake	Resurfacing	Holltree Ct	SR 1221	Cul-de-sac	0.08	Full Depth Patching and 1.5" S9.5B	$19,000
2030	5	092-Wake	Resurfacing	Holly Springs Rd	SR-1009	Pavement Joint	0.12	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$77,000
2030	5	092-Wake	Resurfacing	Horse Apple Ct	SR 3856	Cul-de-sac	0.03	Full Depth Patching and 1.5" S9.5B	$7,000
2030	5	092-Wake	Resurfacing	Jones Franklin Rd	I-440	Western Blvd	1.03	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$283,000
2030	5	092-Wake	Resurfacing	Jones Franklin Rd	Western Blvd	Hillsborough St	0.10	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$66,000
2030	5	092-Wake	Resurfacing	Kennebec Church Rd	NC 55	of Rawls Church Rd (Slightly into H	0.58	Full Depth Patching and 1.5" S9.5B	$126,000
2030	5	092-Wake	Resurfacing	Kennebec Rd	NC 55	Pavement Joint	0.20	Full Depth Patching and 1.5" S9.5B	$39,000
2030	5	092-Wake	Resurfacing	Kildaire Farm Rd	SR 1010	Begin Divided	1.27	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$851,000
2030	5	092-Wake	Resurfacing	Kirkhill Dr	SR 2381	END MAINT	0.19	Full Depth Patching and 1.25" S9.5B	$33,000
2030	5	092-Wake	Resurfacing	Lake Pine Dr	US 64	U-5537 Pavement Joint	0.27	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$161,000
2030	5	092-Wake	Resurfacing	Low Ground Ct	SR-3856	Cul-de-sac	0.21	Full Depth Patching and 1.5" S9.5B	$46,000
2030	5	092-Wake	Resurfacing	Mal Weathers Rd	SR 2727	SR 2737	1.55	Full Depth Patching and 1.5" S9.5B	$338,000
2030	5	092-Wake	Resurfacing	Malos	SR 3856	SR 4965	0.23	Full Depth Patching and 1.5" S9.5B	$51,000
2030	5	092-Wake	Resurfacing	Maxwell Dr	US 401	Greenbrier Rd	0.74	Full Depth Patching and 1.5" S9.5B	$161,000
2030	5	092-Wake	Resurfacing	Mayfair Wood Dr	SR 2767	SR 3768	0.33	Full Depth Patching and 1.5" S9.5B	$72,000
2030	5	092-Wake	Resurfacing	Meadowland Ln	SR 2726	Cul-de-sac	0.11	Full Depth Patching and 1.5" S9.5B	$22,000
2030	5	092-Wake	Resurfacing	Misty Lynn Ct	SR 3769	Cul-de-sac	0.04	Full Depth Patching and 1.5" S9.5B	$8,000
2030	5	092-Wake	Resurfacing	MLK Jr Blvd	SR 3670	US 401 Bridge	0.43	Mill 2.0" and 2.0" S9.5C	$215,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	5	092-Wake	Resurfacing	MLK Jr Blvd	US 401 Brg	SR 3670	0.43	Mill 2.0" and 2.0" S9.5C	$218,000
2030	5	092-Wake	Resurfacing	Morar St	SR 4695	Cul-de-sac	0.04	Full Depth Patching and 1.5" S9.5B	$9,000
2030	5	092-Wake	Resurfacing	Mystic Ct	SR-3867	Cul-de-sac	0.08	Full Depth Patching and 1.5" S9.5B	$17,000
2030	5	092-Wake	Resurfacing	N Salem St To US 64 Ramp EB	N Salem St	US 64 EB	0.16	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$46,000
2030	5	092-Wake	Resurfacing	N Salem St To US 64 Ramp WB	N Salem St	US 64 WB	0.26	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$75,000
2030	5	092-Wake	Resurfacing	NC 54	Fincastle Dr	NE Maynard Rd	0.30	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$93,000
2030	5	092-Wake	Resurfacing	NC 54	NE Maynard Rd	I-440	4.09	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,642,000
2030	5	092-Wake	Resurfacing	NC 54	I-440	Blue Ridge Rd	0.66	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$222,000
2030	5	092-Wake	Resurfacing	NC 54	Marsh Ave	prox 0.2 Miles East of Edwards Mill	0.55	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$159,000
2030	5	092-Wake	Resurfacing	NC 54	Approx 560' East of Corporate Center Dr	Approx 960' East of Trinity Drive	0.60	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$155,000
2030	5	092-Wake	Resurfacing	NC 55	Technology Dr Intersection	Pavement Joint at Apex Peakway	1.82	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,179,000
2030	5	092-Wake	Resurfacing	NC 55	NC 55	NC 55	0.34	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$137,000
2030	5	092-Wake	Resurfacing	Needle Point Cir	SR-4856	Cul-de-sac	0.23	Full Depth Patching and 1.5" S9.5B	$50,000
2030	5	092-Wake	Resurfacing	Old Milburnie Rd	BUS 64	Buffaloe Rd	4.02	Full Depth Patching and 1.5" S9.5B	$1,139,000
2030	5	092-Wake	Resurfacing	Old Raleigh Rd	SR 1435 S	SR 1435 S +1.827 Miles	1.83	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$524,000
2030	5	092-Wake	Resurfacing	Peakwood Dr	Dead End	Cul-de-sac	0.14	Full Depth Patching and 1.5" S9.5B	$31,000
2030	5	092-Wake	Resurfacing	Pine Dr	SR-1384	SR-1384	1.19	Full Depth Patching and 1.5" S9.5B	$233,000
2030	5	092-Wake	Resurfacing	Piney Plains Rd	Pavement Joint	SR 1009	0.67	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$446,000
2030	5	092-Wake	Resurfacing	Poole Rd	SR-1007	avement joint at Heritage Manor D	0.90	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$269,000
2030	5	092-Wake	Resurfacing	Poole Rd	Pavement joint at Heritage Manor Dr	SR 5233	1.09	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$325,000
2030	5	092-Wake	Resurfacing	Purfoy Rd	SR 5577 + 0.179 Miles	Pavement Joint (Harnett County)	0.46	Full Depth Patching and 1.5" S9.5B	$104,000
2030	5	092-Wake	Resurfacing	Rand Rd	NC 50	SR 5383	2.51	Full Depth Patching and 1.5" S9.5B	$601,000
2030	5	092-Wake	Resurfacing	Rockside Hills Dr	SR-2736	Cul-de-sac	0.82	Full Depth Patching and 1.5" S9.5B	$161,000
2030	5	092-Wake	Resurfacing	Rogers Rd	US 1 Alt	SR 5114	1.60	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$635,000
2030	5	092-Wake	Resurfacing	Safari Dr	SR-5391	Cul-de-sac	0.13	Full Depth Patching and 1.5" S9.5B	$31,000
2030	5	092-Wake	Resurfacing	Sanford Ave	SR 1424	Currin Dr	0.19	Full Depth Patching and 1.5" S9.5B	$41,000
2030	5	092-Wake	Resurfacing	Scott Rd	US 401	Dead End	0.17	Full Depth Patching and 1.5" S9.5B	$33,000
2030	5	092-Wake	Resurfacing	Shellrock Dr	SR 1909	Cul-de-sac	0.15	Full Depth Patching and 1.5" S9.5B	$32,000
2030	5	092-Wake	Resurfacing	Smithfield Rd	SR 1007	Johnston County	2.05	Full Depth Patching and 1.5" S9.5B	$515,000
2030	5	092-Wake	Resurfacing	Stone Crystal Dr	SR 1101	Dead End	0.41	Full Depth Patching and 1.5" S9.5B	$89,000
2030	5	092-Wake	Resurfacing	Tardiva Dr	SR 4807	MP 0.131	0.13	Full Depth Patching and 1.5" S9.5B	$28,000
2030	5	092-Wake	Resurfacing	Thistleton Ln	Dead End	Dead End	0.24	Full Depth Patching and 1.5" S9.5B	$60,000
2030	5	092-Wake	Resurfacing	Tryon Rd	US 1	Crescent Commons Dr	0.39	Mill 2.0" and 2.0" S9.5C	$210,000
2030	5	092-Wake	Resurfacing	Tryon Rd	Pavement Joint east of Jones Franklin Rd	US 1	3.23	Mill 2.0" and 2.0" S9.5C	$2,196,000
2030	5	092-Wake	Resurfacing	Umstead Rd	US 401	SR 1476	0.19	Full Depth Patching and 1.5" S9.5B	$36,000
2030	5	092-Wake	Resurfacing	US 401	I-540 Brg Approach Slab	Approx 1000' East of Jonesville Rd	5.41	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,732,000
2030	5	092-Wake	Resurfacing	US 401	Approx 1000' East of Jonesville Rd	I-540 Brg Approach Slab	5.43	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,910,000
2030	5	092-Wake	Resurfacing	US 64 To N Salem St Ramp	US 64 EB	N Salem St	0.26	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$78,000
2030	5	092-Wake	Resurfacing	US 64 To W Williams St Ramp	US 64	W Williams St	0.30	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$86,000
2030	5	092-Wake	Resurfacing	US 64 To W Williams St Ramp	US 64 WB	W Williams St	0.38	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$110,000
2030	5	092-Wake	Resurfacing	US 70	SR 1370	Pvmt Joint N of I-40	1.61	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$613,000
2030	5	092-Wake	Resurfacing	US 70	Pavement joint N of I-40	SR 1370 (Tryon Rd)	1.66	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$706,000
2030	5	092-Wake	Resurfacing	US 70	Pavement joint N of Wade Ave Bridge	Pavement Joint at RR Bridge	0.66	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$310,000
2030	5	092-Wake	Resurfacing	US 70	Pvmt Joint at RR Bridge	Pvmt Joint N of Wade Ave Bridge	0.76	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$290,000
2030	5	092-Wake	Resurfacing	US HWY 64 E	Pavement joint 0.2 miles west of NC 55	SR 1613 + 0.2 miles at RR Bridge	1.77	Full Depth Patching and 1.5" S9.5C	$741,000
2030	5	092-Wake	Resurfacing	US HWY 64 W	RR Bridge ~0.2 Miles east of SR 1613	avement joint 0.2 Miles W of NC 5	1.80	Full Depth Patching and 1.5" S9.5C	$755,000
2030	5	092-Wake	Resurfacing	Virgina Creeper Ln	SR-4857	Pvmt Joint / New Sub-division	0.31	Full Depth Patching and 1.5" S9.5B	$68,000
2030	5	092-Wake	Resurfacing	Vitex St	SR-3856	Cul-de-sac	0.72	Full Depth Patching and 1.5" S9.5B	$157,000
2030	5	092-Wake	Resurfacing	W Williams St To US 64 Ramp EB	W Williams St	US 64 EB	0.22	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$64,000
2030	5	092-Wake	Resurfacing	W Williams St To US 64 Ramp WB	W Williams St	US 64 WB	0.22	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$64,000
2030	5	092-Wake	Resurfacing	W. Young St. / Averette Rd.	Begin Curb & Gutter	US 401	0.98	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$277,000
2030	5	092-Wake	Resurfacing	W. Young St. / Averette Rd.	NC 98	Begin Curb & Gutter	1.64	Full Depth Patching and 1.5" S9.5B	$375,000
2030	5	092-Wake	Resurfacing	Walnut St	Pavement Joint Near Kingston Ridge Rd	SR 1009	1.51	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$608,000
2030	5	092-Wake	Resurfacing	Walnut St	SR 1009	vement Joint Near Kingston Ridge	1.53	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$613,000
2030	5	092-Wake	Resurfacing	Western Blvd	Begin Curb	US 401 Bridge	1.04	Mill 2.0" and 2.0" S9.5C	$421,000
2030	5	092-Wake	Resurfacing	Western Blvd	US 401 Brg	Pvmt Jt/Begin Curb	1.03	Mill 2.0" and 2.0" S9.5C	$421,000
2030	5	092-Wake	Resurfacing	Wheatland Dr	SR-3867	Cul-de-sac	0.07	Full Depth Patching and 1.5" S9.5B	$15,000
2030	5	092-Wake	Resurfacing	Wheelerbrook Ct	SR 5070	Cul-de-sac	0.47	Full Depth Patching and 1.5" S9.5B	$102,000
2030	5	092-Wake	Resurfacing	Whitley Way	US 64 Bus	SR 2382	0.38	Full Depth Patching and 1.25" S9.5B	$67,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	5	092-Wake	Resurfacing	Willow Spring St	SR-2754	NC-42	0.33	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$65,000
2030	5	092-Wake	Resurfacing	Winterton Dr	NC-42	Dead End	0.29	Full Depth Patching and 1.5" S9.5B	$63,000
2030	5	092-Wake	Resurfacing	Wrangler Ct	SR-5391	Cul-de-sac	0.12	Full Depth Patching and 1.5" S9.5B	$28,000
2030	5	092-Wake	Resurfacing	Yopon Ct	SR-5367	Cul-de-sac	0.07	Full Depth Patching and 1.5" S9.5B	$14,000
2030	5	092-Wake	Preservation	Agio Ct	Dead End	Cul-de-sac	0.12	1.0" S9.5B	$15,000
2030	5	092-Wake	Preservation	Amber Dawn Ln	SR 2755	Cul-de-sac	0.10	1.0" S9.5B	$12,000
2030	5	092-Wake	Preservation	Angleview Dr	SR 2357	SR 2357	0.49	1.0" S9.5B	$55,000
2030	5	092-Wake	Preservation	Ashton Glen Dr	SR 2350	Cul-de-sac	0.34	1.0" S9.5B	$43,000
2030	5	092-Wake	Preservation	Austin St	SR 1490	SR 1492	0.15	1.0" S9.5B	$17,000
2030	5	092-Wake	Preservation	Barrington Hills Ln	SR 2703	Cul-de-sac	0.46	1.0" S9.5B	$57,000
2030	5	092-Wake	Preservation	Bethune Dr	SR 1481	SR 1491	0.11	1.0" S9.5B	$12,000
2030	5	092-Wake	Preservation	Blue Marble Ct	SR 5369	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2030	5	092-Wake	Preservation	Bobbitt Rd	SR 6107	SR 1448	0.17	1.0" S9.5B	$26,000
2030	5	092-Wake	Preservation	Bobbitt Rd	SR 1257	Cul-de-sac	0.31	1.0" S9.5B	$35,000
2030	5	092-Wake	Preservation	Bradbury Ct	SR 3415	Cul-de-sac	0.04	1.0" S9.5B	$5,000
2030	5	092-Wake	Preservation	Breezy Branch Ln	SR 5580	Cul-de-sac	0.14	1.0" S9.5B	$19,000
2030	5	092-Wake	Preservation	Brusby Ridge Dr	SR 1390	Cul-de-sac	0.17	1.0" S9.5B	$19,000
2030	5	092-Wake	Preservation	Camley Ave	SR 1670	Cul-de-sac	0.10	1.0" S9.5B	$12,000
2030	5	092-Wake	Preservation	Charles G Dr	SR 1381	Dead End	0.21	1.0" S9.5B	$23,000
2030	5	092-Wake	Preservation	Clear Pool Ln	SR 2760	Dead End	0.24	1.0" S9.5B	$30,000
2030	5	092-Wake	Preservation	Deer Path	SR 1909	SR 1974	0.14	1.0" S9.5B	$17,000
2030	5	092-Wake	Preservation	Durango Ct	SR 3898	Cul-de-sac	0.06	1.0" S9.5B	$7,000
2030	5	092-Wake	Preservation	Fairchild Rd	SR 2339	END MAINT	0.16	1.0" S9.5B	$16,000
2030	5	092-Wake	Preservation	Falls Glen Ct	NC 98	Cul-de-sac	0.22	1.0" S9.5B	$28,000
2030	5	092-Wake	Preservation	Flat Creek Ct	SR 5580	Cul-se-sac	0.06	1.0" S9.5B	$8,000
2030	5	092-Wake	Preservation	Fox Trap Ct	SR 5319	Cul-de-sac	0.14	1.0" S9.5B	$17,000
2030	5	092-Wake	Preservation	Fox Walk Path	SR 2707	SR 5320	0.50	1.0" S9.5B	$62,000
2030	5	092-Wake	Preservation	Hazelfield Ct	SR 2318	Dead End	0.25	1.0" S9.5B	$31,000
2030	5	092-Wake	Preservation	Heritage Landing Ct	SR 2469	Cul-de-sac	0.15	1.0" S9.5B	$18,000
2030	5	092-Wake	Preservation	Hidden River Ct	SR 5156	Cul-de-sac	0.07	1.0" S9.5B	$7,000
2030	5	092-Wake	Preservation	Hillandale Ln	SR 2547	Cul-de-sac	0.74	1.0" S9.5B	$110,000
2030	5	092-Wake	Preservation	Holly Forest Rd	SR 1909	Cul-de-sac	0.30	1.0" S9.5B	$37,000
2030	5	092-Wake	Preservation	Kipskin Ct	SR 3898	Cul-de-sac	0.03	1.0" S9.5B	$3,000
2030	5	092-Wake	Preservation	Leah Ln	SR 2876	SR 5319	0.26	1.0" S9.5B	$32,000
2030	5	092-Wake	Preservation	Loblolly Pine Dr	NC 98	Cul-de-sac	0.20	1.0" S9.5B	$23,000
2030	5	092-Wake	Preservation	Maduro Ct	Cul-de-sac	Dead End	0.14	1.0" S9.5B	$17,000
2030	5	092-Wake	Preservation	Marwood Dr	SR 2951	Cul-de-sac	0.10	1.0" S9.5B	$13,000
2030	5	092-Wake	Preservation	Peakwood Dr	Dead End	Cul-de-sac	0.14	1.0" S9.5B	$18,000
2030	5	092-Wake	Preservation	Perimeter Ct	SR 1001	Cul-de-sac	0.03	1.0" S9.5B	$4,000
2030	5	092-Wake	Preservation	Pheiffer Dr	SR 1491	SR 1481	0.10	1.0" S9.5B	$11,000
2030	5	092-Wake	Preservation	Possum Trot Rd	Cul-de-sac	Cul-de-sac	0.26	1.0" S9.5B	$33,000
2030	5	092-Wake	Preservation	River Ridge Rd	SR 2368	Cul-de-sac	0.11	1.0" S9.5B	$14,000
2030	5	092-Wake	Preservation	Sadie Hopkins St	SR 1009	SR 1490	0.27	1.0" S9.5B	$30,000
2030	5	092-Wake	Preservation	Squire Ridge Dr	SR 1101	Cul-de-sac	0.30	1.0" S9.5B	$38,000
2030	5	092-Wake	Preservation	Stronwood Ct	SR 2877	Cul-de-sac	0.16	1.0" S9.5B	$20,000
2030	5	092-Wake	Preservation	Tiny Branch Ln	SR 5580	Cul-de-sac	0.07	1.0" S9.5B	$8,000
2030	5	092-Wake	Preservation	Troutman Ln	SR 3364	SR 2357	0.35	1.0" S9.5B	$43,000
2030	5	092-Wake	Preservation	Waterbrook Ct	SR 5071	Cul-de-sac	0.06	1.0" S9.5B	$8,000
2030	5	092-Wake	Preservation	Wheatstone Ln	SR 1826	Dead End	0.13	1.0" S9.5B	$16,000
2030	5	093-Warren	Resurfacing	Cole Farm	SR 1300	SR 1306	4.71	1.0" S9.5B	$584,000
2030	5	093-Warren	Resurfacing	Greentown	SR 1625	End Pavement	1.83	1.0" S9.5B	$227,000
2030	5	093-Warren	Resurfacing	Hub Quarter	SR 1335	End Maintenance	3.42	Full Depth Patching and 1.25" S9.5B	$665,000
2030	5	093-Warren	Resurfacing	Ridgeway Drewry Rd	Vance County Line	US 1	4.84	Full Depth Patching and 1.25" S9.5B	$990,000
2030	5	093-Warren	Resurfacing	Ridgeway Warrenton Rd	US 158 BUS	US 1	4.53	Full Depth Patching and 1.25" S9.5B	$927,000
2030	5	093-Warren	Resurfacing	Sulphur Springs	SR 1616	US 401	3.26	Full Depth Patching and 1.25" S9.5B	$634,000
2030	5	093-Warren	Preservation	Baltimore Church Road	SR 1600	End Pavement	0.66	Full Depth Patching and 1.25" S9.5B	$128,000
2030	5	093-Warren	Preservation	Baltimore Church Road	End Pavement	NC 58	1.89	Full Depth Patching and 1.25" S9.5B	$369,000
2030	5	093-Warren	Preservation	Powells Mill Rd	SR 1606	SR 1600	2.16	Full Depth Patching and 1.25" S9.5B	$422,000
2030	6	009-Bladen	Resurfacing	NC 131	NC 410	SR 1191	1.73	Mill 1.5" and 1.5" S9.5C	$1,224,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	6	009-Bladen	Resurfacing	NC 87	5 LANE DIVIDED	SR 1340	1.15	Mill 1.5" and 1.5" S9.5C	$460,000
2030	6	009-Bladen	Resurfacing	NC 87	NC 41	End CI&G N of Dublin	2.88	Mill 1.5" and 1.5" S9.5C	$1,151,600
2030	6	009-Bladen	Resurfacing	NC 87	5 LANE DIVIDED	SR 1340	1.27	Mill 1.5" and 1.5" S9.5C	$508,000
2030	6	009-Bladen	Resurfacing	US 701	MCDOWELL STREET	87 BUS	0.53	Mill 1.5" and 1.5" S9.5C	$212,000
2030	6	009-Bladen	Resurfacing	US 701	CLARKTON CITY LIMITS	NC 242	7.51	1.5" S9.5C	$1,351,800
2030	6	009-Bladen	Preservation	SR 1725	SR 1726	NC 87	1.07	Seal - Double	$34,000
2030	6	009-Bladen	Preservation	SR 1726	SR 1730	END OF PAVEMENT	1.98	Seal - Double	$55,000
2030	6	009-Bladen	Preservation	SR 1728	SR 1726	SR 1730	1.33	Seal - Double	$40,000
2030	6	009-Bladen	Preservation	SR 1730	COLUMBUS CO.	NC 53	11.11	Seal - Double	$360,000
2030	6	009-Bladen	Preservation	SR 1732	NC 87	SR 1730	0.92	Seal - Double	$30,000
2030	6	009-Bladen	Preservation	SR 1734	NC 87	DEAD END	0.99	Seal - Double	$30,000
2030	6	009-Bladen	Preservation	SR 1735	COLUMBUS CO.	DEAD END	0.74	Seal - Double	$20,000
2030	6	009-Bladen	Preservation	SR 1736	COLUMBUS CO.	NC 87	0.66	Seal - Double	$20,000
2030	6	009-Bladen	Preservation	SR 1737	COLUMBUS CO.	SR 1741	0.97	Seal - Double	$25,000
2030	6	009-Bladen	Preservation	SR 1739	SR 1736	SR 1741	0.66	Seal - Double	$19,000
2030	6	009-Bladen	Preservation	SR 1740	COLUMBUS CO.	SR 1741	0.99	Seal - Double	$30,000
2030	6	009-Bladen	Preservation	SR 1741	COLUMBUS CO.	NC 87	2.82	Seal - Double	$82,000
2030	6	009-Bladen	Preservation	SR 1742	SR 1741	SR 1743	1.34	Seal - Double	$35,000
2030	6	009-Bladen	Preservation	SR 1743	NC 87	SR 1741	2.80	Seal - Double	$80,000
2030	6	009-Bladen	Preservation	SR 1744	SR 1745	SR 1787	1.97	Seal - Double	$55,000
2030	6	009-Bladen	Preservation	SR 1745	SR 1730	NC 87	2.70	Seal - Double	$72,000
2030	6	009-Bladen	Preservation	SR 1746	SR 1745	DEAD END	1.19	Seal - Double	$34,000
2030	6	009-Bladen	Preservation	SR 1747	SR 1730	SR 1745	1.24	Seal - Double	$38,000
2030	6	009-Bladen	Preservation	SR 1748	SR 1730	SR 1748	3.04	Seal - Double	$90,000
2030	6	009-Bladen	Preservation	SR 1768	SR 1741	SR 1743	0.74	Seal - Double	$20,000
2030	6	009-Bladen	Preservation	SR 1772	COLUMBUS CO.	COLUMBUS CO.	0.71	Seal - Double	$20,000
2030	6	009-Bladen	Preservation	SR 1779	NC 87	DEAD END	0.54	Seal - Double	$15,000
2030	6	009-Bladen	Preservation	SR 1780	SR 1744	DEAD END	0.20	Seal - Double	$6,000
2030	6	009-Bladen	Preservation	SR 1786	SR 1730	SR 1730	0.35	Seal - Double	$11,000
2030	6	009-Bladen	Preservation	SR 1787	NC 87	END MAINT	1.41	Seal - Double	$40,000
2030	6	009-Bladen	Preservation	SR 1794	SR 1730	NC 211	0.45	Seal - Double	$13,000
2030	6	009-Bladen	Preservation	SR 1800	SR 1743	DEAD END	0.40	Seal - Double	$11,000
2030	6	024-Columbus	Resurfacing	SR 1002	US 701	NC 410	5.78	1.5" S9.5B	$1,156,000
2030	6	024-Columbus	Resurfacing	SR 1005	SC LINE	AR 1173	3.15	1.5" S9.5B	$630,000
2030	6	024-Columbus	Resurfacing	SR 1006	SR 1931	NC 905	3.59	1.5" S9.5B	$720,000
2030	6	024-Columbus	Resurfacing	SR 1108	SR 1112	SR 1103	5.68	1.5" S9.5B	$1,136,000
2030	6	024-Columbus	Resurfacing	US 701	SR 1550	Bladen County Line	10.57	1.5" S9.5C	$4,227,600
2030	6	024-Columbus	Preservation	SR 1712	NC 214	Dead End	0.16	Seal - Double	$4,500
2030	6	024-Columbus	Preservation	SR 1717	SR 1001	NC 214	0.39	Seal - Double	$11,000
2030	6	024-Columbus	Preservation	SR 1718	SR 1717	NC 214	0.14	Seal - Double	$3,500
2030	6	024-Columbus	Preservation	SR 1734	NC 214	MP 0.54	0.54	Seal - Double	$17,000
2030	6	024-Columbus	Preservation	SR 1736	SR 1735	End Pavement	0.31	Seal - Double	$8,000
2030	6	024-Columbus	Preservation	SR 1736	NC 214	SR 1001	3.12	Seal - Double	$100,000
2030	6	024-Columbus	Preservation	SR 1740	LKW Town Limits	SR 1757	1.46	Seal - Double	$40,000
2030	6	024-Columbus	Preservation	SR 1751	NC 214	SR 1752	0.13	Seal - Double	$3,500
2030	6	024-Columbus	Preservation	SR 1752	SR 1751	SR 1768	0.21	Seal - Double	$7,000
2030	6	024-Columbus	Preservation	SR 1756	NC 214	Dead End	0.09	Seal - Double	$3,000
2030	6	024-Columbus	Preservation	SR 1758	Dead End	NC 214	0.12	Seal - Double	$3,500
2030	6	024-Columbus	Preservation	SR 1759	NC 214	Dead End	1.15	Seal - Double	$32,000
2030	6	024-Columbus	Preservation	SR 1768	SR 1752	NC 214	0.12	Seal - Double	$3,000
2030	6	024-Columbus	Preservation	SR 1901	SR 1736	SR 1900	2.18	Seal - Double	$70,000
2030	6	024-Columbus	Preservation	SR 1902	SR 1736	SR 1901	1.53	Seal - Double	$45,000
2030	6	024-Columbus	Preservation	SR 1904	SR 1001	SR 1914	3.88	Seal - Double	$112,000
2030	6	024-Columbus	Preservation	SR 1905	SR 1904	SR 1906	0.61	Seal - Double	$18,000
2030	6	024-Columbus	Preservation	SR 1906	SR 1904	NC 214	1.07	Seal - Double	$31,000
2030	6	024-Columbus	Preservation	SR 1907	NC 214	SR 1001	2.05	Seal - Double	$60,000
2030	6	024-Columbus	Preservation	SR 1908	SR 1001	SR 1001	1.61	Seal - Double	$45,000
2030	6	024-Columbus	Preservation	SR 1909	SR 1908	SR 1908	1.10	Seal - Double	$30,000
2030	6	024-Columbus	Preservation	SR 1910	SR 1001	SR 1911	1.75	Seal - Double	$50,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	6	024-Columbus	Preservation	SR 1911	SR 1904	SR 1914	2.56	Seal - Double	$75,000
2030	6	024-Columbus	Preservation	SR 1912	SR 1907	SR 1914	2.02	Seal - Double	$60,000
2030	6	024-Columbus	Preservation	SR 1914	NC 214	SR 1001	6.94	Seal - Double	$200,000
2030	6	024-Columbus	Preservation	SR 1923	SR 1972	End of Pavement	0.41	Seal - Double	$10,000
2030	6	024-Columbus	Preservation	SR 1925	SR 1001	NC 130	2.95	Seal - Double	$85,000
2030	6	024-Columbus	Preservation	SR 1927	SR 1001	NC 130	2.05	Seal - Double	$60,000
2030	6	024-Columbus	Preservation	SR 1928	NC 130	Brunswick	4.79	Seal - Double	$125,000
2030	6	024-Columbus	Preservation	SR 1929	SR 1930	SR 1928	1.50	Seal - Double	$52,500
2030	6	024-Columbus	Preservation	SR 1930	SR 1928	SR 1929	2.90	Seal - Double	$75,000
2030	6	024-Columbus	Preservation	SR 1941	SR 1001	SR 1968	0.31	Seal - Double	$9,000
2030	6	024-Columbus	Preservation	SR 1948	SR 1941	Dead End	0.07	Seal - Double	$2,000
2030	6	024-Columbus	Preservation	SR 1956	NC 214	SR 1736	0.63	Seal - Double	$18,000
2030	6	024-Columbus	Preservation	SR 1957	SR 1901	SR 1900	0.93	Seal - Double	$25,000
2030	6	024-Columbus	Preservation	SR 1959	SR 1904	Dead End	0.52	Seal - Double	$15,000
2030	6	024-Columbus	Preservation	SR 1960	SR 1957	Dead End	0.33	Seal - Double	$9,000
2030	6	024-Columbus	Preservation	SR 1961	SR 1957	SR 1960	0.18	Seal - Double	$6,300
2030	6	024-Columbus	Preservation	SR 1962	SR 1957	CDS	0.19	Seal - Double	$5,000
2030	6	024-Columbus	Preservation	SR 1963	SR 1957	SR 1960	0.38	Seal - Double	$11,000
2030	6	024-Columbus	Preservation	SR 1964	SR 1963	Dead End	0.05	Seal - Double	$1,500
2030	6	024-Columbus	Preservation	SR 1965	SR 1963	Dead End	0.03	Seal - Double	$1,050
2030	6	024-Columbus	Preservation	SR 1968	NC 214	SR 1736	0.27	Seal - Double	$8,000
2030	6	024-Columbus	Preservation	SR 1969	SR 1957	Dead End	0.12	Seal - Double	$3,500
2030	6	024-Columbus	Preservation	SR 1975	NC214	SR 1976	0.17	Seal - Double	$5,000
2030	6	024-Columbus	Preservation	SR 1976	SR 1914	SR 1977	0.41	Seal - Double	$12,000
2030	6	024-Columbus	Preservation	SR 1977	SR 1914	SR 1976	0.33	Seal - Double	$10,000
2030	6	026-Cumberland	Resurfacing	NC 162	301/95	NC 59	3.74	Mill 1.5" and 1.5" S9.5B	$1,028,500
2030	6	026-Cumberland	Resurfacing	NC 162	NC 59	US 301/I-95BUS	3.72	Mill 1.5" and 1.5" S9.5B	$1,023,000
2030	6	026-Cumberland	Resurfacing	NC 295	SR 1400	US 401	2.45	Mill 1.5" and 1.5" S9.5C	$728,750
2030	6	026-Cumberland	Resurfacing	NC 295	US 401	SR 1400	2.67	Mill 1.5" and 1.5" S9.5C	$734,250
2030	6	026-Cumberland	Resurfacing	SR 1005	US 301	Sampson Co	7.12	1.5" S9.5B	$1,174,800
2030	6	026-Cumberland	Resurfacing	SR 1761	SR 1834	Dead End	0.68	1.0" S9.5B	$112,200
2030	6	026-Cumberland	Resurfacing	SR 1815	SR 1005	US 13	1.25	1.5" S9.5B	$207,900
2030	6	026-Cumberland	Resurfacing	SR 1834	SR 1835	SR 1006	2.72	1.5" S9.5B	$448,800
2030	6	026-Cumberland	Resurfacing	SR 1870	SR 1834	Dead End	0.27	1.0" S9.5B	$44,550
2030	6	026-Cumberland	Resurfacing	SR1400	SR 1403	SR 1007	3.55	Mill 1.5" and 1.5" S9.5B	$1,420,000
2030	6	043-Harnett	Resurfacing	NC 27	SR 1117	401/210	8.93	Mill 1.5" and 1.5" S9.5C	$1,946,000
2030	6	043-Harnett	Resurfacing	NC 55	NC 27	NC 210	7.45	Mill 1.5" and 1.5" S9.5C	$1,639,000
2030	6	043-Harnett	Resurfacing	SR 1117	NC 27	NC 24/87	6.44	1.5" S9.5B	$1,062,600
2030	6	043-Harnett	Resurfacing	SR 1120	End Div Section	NC 210	3.68	1.5" S9.5B	$607,200
2030	6	043-Harnett	Resurfacing	SR 1229	SR 1291	SR 1233	7.45	1.5" S9.5B	$1,229,250
2030	6	043-Harnett	Resurfacing	SR 1500	Johnston Co Line	NC 210	5.31	1.5" S9.5B	$879,450
2030	6	043-Harnett	Resurfacing	SR 3242	NC 24/87	SR 1121	3.60	1.5" S9.5B	$605,550
2030	6	078-Robeson	Resurfacing	NC 130 BUS	NC 41	NC 130	2.81	1.5" S9.5B	$562,000
2030	6	078-Robeson	Resurfacing	NC 71	NC 20	SR 1731	3.67	1.5" S9.5C	$734,000
2030	6	078-Robeson	Resurfacing	NC 904	NC 41	COLUMBUS CO	8.02	1.5" S9.5B	$1,604,000
2030	6	078-Robeson	Resurfacing	SR 1002	NC 211	SR 2115	1.23	1.5" S9.5B	$221,400
2030	6	078-Robeson	Resurfacing	SR 1349	SR 1350	DEAD END	1.92	1.75" S9.5A	$400,000
2030	6	078-Robeson	Resurfacing	SR 1350	NC 710	SR 1339	1.45	1.5" S9.5A	$300,000
2030	6	078-Robeson	Resurfacing	SR 1507	NC 211	NC 72	1.98	1.5" S9.5B	$380,000
2030	6	078-Robeson	Resurfacing	SR 1717	CUMB. CO.	NC 71	1.52	1.5" S9.5B	$300,000
2030	6	078-Robeson	Resurfacing	SR 1753	SR 1754	SR 1505	2.44	1.5" S9.5B	$400,000
2030	6	078-Robeson	Resurfacing	SR 1784	SR 1006	SR 1318	1.63	1.5" S9.5B	$326,000
2030	6	078-Robeson	Resurfacing	SR 2215	SR 2207	SR 2212	1.80	1.5" S9.5B	$324,000
2030	6	078-Robeson	Resurfacing	SR 2417	SR 2317	SR 2235	1.57	1.5" S9.5A	$282,000
2030	6	078-Robeson	Resurfacing	SR 2418	SR 2317	Dead end	0.25	1.5" S9.5A	$45,000
2030	6	078-Robeson	Resurfacing	SR 2435	NC 130 Bus.	NC 130	9.45	1.5" S9.5B	$1,710,000
2030	6	078-Robeson	Resurfacing	US 301	I 95	NC 20	10.12	1.5" S9.5C	$2,024,000
2030	6	078-Robeson	Resurfacing	US 74 ALT	NC 710	SR 2534	10.13	1.5" S9.5B	$2,026,000
2030	6	078-Robeson	Resurfacing	US 74 ALT	Begin Divided Highway	End Divided Highway	0.64	1.5" S9.5B	$132,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	6	078-Robeson	Preservation	SR 1529	I 95	SR 1947	2.43	Seal - Split	$72,000
2030	6	078-Robeson	Preservation	SR 1942	SR 1005	END MAINT	2.08	Seal - Split	$62,000
2030	6	078-Robeson	Preservation	SR 1947	SR 1945	SR 1955	4.10	Seal - Split	$146,320
2030	6	078-Robeson	Preservation	SR 1948	SR 1953	SR 1945	2.72	Seal - Split	$80,000
2030	6	078-Robeson	Preservation	SR 1953	SR 1954	SR 1945	1.87	Seal - Split	$56,000
2030	6	078-Robeson	Preservation	SR 1954	NC 41	SR 1956	3.02	Seal - Split	$91,000
2030	6	078-Robeson	Preservation	SR 1955	SR 1935	NC 41	3.88	Seal - Split	$116,000
2030	6	078-Robeson	Preservation	SR 1956	SR 1947	SR 1004	3.26	Seal - Split	$98,000
2030	6	078-Robeson	Preservation	SR 1958	SR 1005	SR 1935	2.19	Seal - Split	$66,000
2030	6	078-Robeson	Preservation	SR 1959	SR 1956	SR 1004	1.79	Seal - Split	$54,000
2030	6	078-Robeson	Preservation	SR 1981	SR 1529	DEAD END	0.25	Seal - Split	$8,000
2030	6	078-Robeson	Preservation	SR 2025	SR 1948	DEAD END	0.22	Seal - Split	$7,000
2030	6	078-Robeson	Preservation	SR 2052	SR 1947	DEAD END	0.11	Seal - Split	$3,000
2030	6	078-Robeson	Preservation	SR 2100	NC 211	SR 1002	1.76	Seal - Split	$56,320
2030	6	078-Robeson	Preservation	SR 2116	SR 2115	SR 2121	6.89	Seal - Split	$220,480
2030	6	078-Robeson	Preservation	SR 2117	SR 2115	SR 1002	1.03	Seal - Split	$32,960
2030	6	078-Robeson	Preservation	SR 2118	SR 1002	SR 2119	1.29	Seal - Split	$41,280
2030	6	078-Robeson	Preservation	SR 2118	NC 211	END PVMT	0.63	Seal - Split	$20,160
2030	6	078-Robeson	Preservation	SR 2119	SR 1002	SR 2118	1.46	Seal - Split	$46,720
2030	6	078-Robeson	Preservation	SR 2121	SR 1002	NC 72	5.75	Seal - Split	$184,000
2030	6	078-Robeson	Preservation	SR 2123	NC 72	END PVMT	0.98	Seal - Split	$31,360
2030	6	078-Robeson	Preservation	SR 2124	SR 2123	DEAD END	1.09	Seal - Split	$34,880
2030	6	078-Robeson	Preservation	SR 2127	SR 2116	SR 2115	1.21	Seal - Split	$38,720
2030	6	078-Robeson	Preservation	SR 2129	NC 211	SR 2100	0.55	Seal - Split	$17,600
2030	6	078-Robeson	Preservation	SR 2132	NC 72	DEAD END	0.25	Seal - Split	$8,000
2030	6	078-Robeson	Preservation	SR 2133	SR 2132	NC 211	0.17	Seal - Split	$5,440
2030	6	078-Robeson	Preservation	SR 2202	Lumberton CL	NC 72	1.86	Seal - Split	$59,520
2030	6	078-Robeson	Preservation	SR 2203	SR 2204	SR 2202	1.35	Seal - Split	$43,200
2030	6	078-Robeson	Preservation	SR 2204	Lumberton CL	SR 2207	2.45	Seal - Split	$78,400
2030	6	078-Robeson	Preservation	SR 2207	NC 72	SR 2289	1.62	Seal - Split	$51,840
2030	6	078-Robeson	Preservation	SR 2210	US 74	SR 2204	0.37	Seal - Split	$11,840
2030	6	078-Robeson	Preservation	SR 2211	SR 2220	SR 2212	2.12	Seal - Split	$67,840
2030	6	078-Robeson	Preservation	SR 2212	SR 2214	SR 2211	2.75	Seal - Split	$88,000
2030	6	078-Robeson	Preservation	SR 2213	SR 2212	END PVMT	0.42	Seal - Split	$13,440
2030	6	078-Robeson	Preservation	SR 2214	NC 72	NC 72	4.90	Seal - Split	$156,800
2030	6	078-Robeson	Preservation	SR 2216	NC 72	SR 2214	1.76	Seal - Split	$56,320
2030	6	078-Robeson	Preservation	SR 2217	NC 72	SR 2218	0.75	Seal - Split	$24,000
2030	6	078-Robeson	Preservation	SR 2220	US 74	NC 72	3.03	Seal - Split	$96,960
2030	6	078-Robeson	Preservation	SR 2221	SR 2214	NC 72	0.76	Seal - Split	$24,320
2030	6	078-Robeson	Preservation	SR 2222	SR 2214	SR 2220	1.34	Seal - Split	$42,880
2030	6	078-Robeson	Preservation	SR 2223	SR 2214	SR 2222	0.70	Seal - Split	$22,400
2030	6	078-Robeson	Preservation	SR 2224	SR 2220	SR 2222	1.64	Seal - Split	$52,480
2030	6	078-Robeson	Preservation	SR 2225	NC 72	US 74	1.26	Seal - Split	$40,320
2030	6	078-Robeson	Preservation	SR 2295	SR 2216	SR 2215	0.76	Seal - Split	$24,320
2030	6	078-Robeson	Preservation	SR 2305	NC 72	SR 2289	1.19	Seal - Split	$38,080
2030	6	078-Robeson	Preservation	SR 2310	DEAD END	SR 2204	0.25	Seal - Split	$8,000
2030	6	078-Robeson	Preservation	SR 2313	SR 2211	DEAD END	0.10	Seal - Split	$1,600
2030	6	078-Robeson	Preservation	SR1936	SR 1935	SR 1005	1.30	Seal - Split	$39,000
2030	7	001-Alamance	Resurfacing	Arthur Dr.	SR 2218	SR 2236	0.27	#78 Mat Seal and 1.5" S9.5B	$71,600
2030	7	001-Alamance	Resurfacing	Barrington Dr.	SR 1504	DEAD END	0.14	#78 Mat Seal and 1.5" S9.5B	$37,200
2030	7	001-Alamance	Resurfacing	Barton Ct.	SR 1674	DEAD END	0.05	#78 Mat Seal and 1.5" S9.5B	$13,300
2030	7	001-Alamance	Resurfacing	Broadrock Rd.	Bass Mtn. Rd.	Dead End	0.49	#78 Mat Seal and 1.5" S9.5B	$129,900
2030	7	001-Alamance	Resurfacing	Camelot Lane	SR 2227	SR 2236	0.21	#78 Mat Seal and 1.5" S9.5B	$55,700
2030	7	001-Alamance	Resurfacing	Christopher Dr	SR 1700	END MAINT	0.41	#78 Mat Seal and 1.5" S9.5B	$108,700
2030	7	001-Alamance	Resurfacing	Copeland Terrace	SR 2174	DEAD END	0.44	#78 Mat Seal and 1.5" S9.5B	$116,650
2030	7	001-Alamance	Resurfacing	Eli Court	SR 2365	DEAD END	0.06	#78 Mat Seal and 1.5" S9.5B	$16,000
2030	7	001-Alamance	Resurfacing	Elon Ct.	SR 1672	DEAD END	0.02	#78 Mat Seal and 1.5" S9.5B	$5,300
2030	7	001-Alamance	Resurfacing	Fire Tower Rd.	Mt. Herman R. Crk. Rd.	Sr 2440	0.16	#78 Mat Seal and 1.5" S9.5B	$42,500
2030	7	001-Alamance	Resurfacing	Garden Circle Rd.	Burch Bridge Rd.	END MAINT	0.24	#78 Mat Seal and 1.5" S9.5B	$63,700

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	7	001-Alamance	Resurfacing	Gibson Rd.	SR 1981	US 70	2.03	#78 Mat Seal and 1.5" S9.5B	$538,000
2030	7	001-Alamance	Resurfacing	Huffman Mill Rd.	GCL	SR 1213	2.94	#78 Mat Seal and 1.5" S9.5B	$779,150
2030	7	001-Alamance	Resurfacing	Ironwood Dr.	SR 2422	END MAINT	0.11	#78 Mat Seal and 1.5" S9.5B	$29,200
2030	7	001-Alamance	Resurfacing	Ivey Rd.	NC 87	NC 54	1.35	#78 Mat Seal and 1.5" S9.5B	$357,800
2030	7	001-Alamance	Resurfacing	Lancelot Lane	SR 2226	VAlley Dr.	0.17	#78 Mat Seal and 1.5" S9.5B	$45,100
2030	7	001-Alamance	Resurfacing	NC 54	NC 119	OCL	6.83	#78 Mat Seal and 1.5" S9.5B	$1,810,050
2030	7	001-Alamance	Resurfacing	Noah Rd.	SR 2107	SR 2226	0.47	#78 Mat Seal and 1.5" S9.5B	$124,600
2030	7	001-Alamance	Resurfacing	Plateau Place	SR 2228	END MAINT	0.13	#78 Mat Seal and 1.5" S9.5B	$34,500
2030	7	001-Alamance	Resurfacing	Rock Oak Rd.	Broadrock Rd.	Dead End	0.08	#78 Mat Seal and 1.5" S9.5B	$21,300
2030	7	001-Alamance	Resurfacing	Ross St.	SR 1700	SR 1537	0.36	#78 Mat Seal and 1.5" S9.5B	$95,600
2030	7	001-Alamance	Resurfacing	Spring Rd.	Burch Bridge Rd.	END MAINT	0.19	#78 Mat Seal and 1.5" S9.5B	$50,400
2030	7	001-Alamance	Resurfacing	Springfield Dr.	SR 1504	DEAD END	0.28	#78 Mat Seal and 1.5" S9.5B	$74,220
2030	7	001-Alamance	Resurfacing	Sylvan Rd.	Greensboro Ch. Hill Rd.	CCL	3.74	#78 Mat Seal and 1.5" S9.5B	$991,160
2030	7	001-Alamance	Resurfacing	Sylvan School Rd.	SR 2369	SR 1004	0.42	#78 Mat Seal and 1.5" S9.5B	$111,306
2030	7	001-Alamance	Resurfacing	Third St. Ext.	SR 1940	Holmes Lane	1.18	Mill 1.5" and 1.5" S9.5B	$444,200
2030	7	001-Alamance	Resurfacing	Valley Dr.	SR 2227	END MAINT	0.19	#78 Mat Seal and 1.5" S9.5B	$50,360
2030	7	001-Alamance	Resurfacing	W. Front St.	E. Haggard	SR 1612	0.55	Mill 1.5" and 1.5" S9.5B	$213,160
2030	7	001-Alamance	Resurfacing	W. Front St.	Sr 1446	US 70 (S. Church St.)	1.81	Mill 1.5" and 1.5" S9.5B	$701,470
2030	7	001-Alamance	Resurfacing	W. Front St.	SR 1612	SR 1446	1.36	#78 Mat Seal and 1.5" S9.5B	$360,500
2030	7	001-Alamance	Resurfacing	Whittemore Rd.	NC 54	Woody Dr.	0.54	#78 Mat Seal and 1.5" S9.5B	$143,200
2030	7	001-Alamance	Resurfacing	Wibsley Dr.	SR 1672	SR 1676	0.13	#78 Mat Seal and 1.5" S9.5B	$34,500
2030	7	001-Alamance	Resurfacing	Woody Dr.	NC 54	END MAINT	0.66	#78 Mat Seal and 1.5" S9.5B	$175,000
2030	7	001-Alamance	Preservation	Ashley Pond Ct.	SR 2119	DEAD END	0.09	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Austin Quarter Rd.	SR 2146	DEAD END	1.10	Seal - Double and Fog Seal	$49,300
2030	7	001-Alamance	Preservation	Bowlingwood Ln.	SR 2165	DEAD END	0.10	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Byers Ct.	SR 2627	DEAD END	0.06	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Carden Rd.	NC 87 (S)	DEAD END	0.40	Seal - Double and Fog Seal	$17,900
2030	7	001-Alamance	Preservation	Cedar Cliff Rd.	NC 87 (S)	SR 2116	1.60	Seal - Double and Fog Seal	$71,600
2030	7	001-Alamance	Preservation	Coggins Rd.	SR 2178	DEAD END	0.40	Seal - Double and Fog Seal	$17,900
2030	7	001-Alamance	Preservation	Cypress Dr.	SR 2601	DEAD END	0.40	Seal - Double and Fog Seal	$17,900
2030	7	001-Alamance	Preservation	Driftwood Rd.	SR 2116	DEAD END	0.40	Seal - Double and Fog Seal	$17,900
2030	7	001-Alamance	Preservation	Ellington Rd.	SR 2116	DEAD END	0.60	Seal - Double and Fog Seal	$26,900
2030	7	001-Alamance	Preservation	Fancy Loop Rd.	SR 2158	SR 2158	0.50	Seal - Double and Fog Seal	$22,400
2030	7	001-Alamance	Preservation	Forey's Ct.	SR 2641	DEAD END	0.08	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Golden Oak Rd.	Sr 2121	DEAD END	0.30	Seal - Double and Fog Seal	$13,500
2030	7	001-Alamance	Preservation	Hillside Dr.	SR 2157	DEAD END	0.17	Seal - Double and Fog Seal	$9,000
2030	7	001-Alamance	Preservation	Hopewood Ct.	SR 2181	DEAD END	0.09	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Hopewood Dr.	SR 2181	SR 1005	0.40	Seal - Double and Fog Seal	$17,900
2030	7	001-Alamance	Preservation	John Thompson Rd.	SR 2147	DEAD END	0.30	Seal - Double and Fog Seal	$13,500
2030	7	001-Alamance	Preservation	Judge Sharpe Rd.	NC 87	DEAD END	0.70	Seal - Double and Fog Seal	$31,330
2030	7	001-Alamance	Preservation	Lacie Nicole Rd.	SR 2287	DEAD END	0.20	Seal - Double and Fog Seal	$9,000
2030	7	001-Alamance	Preservation	Lambert Rd.	SR 2158	DEAD END	0.30	Seal - Double and Fog Seal	$13,500
2030	7	001-Alamance	Preservation	Lazy Lane	SR 2627	DEAD END	0.07	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Lewis Rd.	NC 87 (S)	DEAD END	0.10	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Mandale Rd.	SR 2102	SR 2182	1.90	Seal - Double and Fog Seal	$85,100
2030	7	001-Alamance	Preservation	Mattie Florence Dr.	SR 2628	DEAD END	0.30	Seal - Double and Fog Seal	$31,400
2030	7	001-Alamance	Preservation	McBane Mill Rd.	SR 2182	SR 1005	0.82	Seal - Double and Fog Seal	$85,100
2030	7	001-Alamance	Preservation	Misty Hollow Ct.	SR 2610	DEAD END	0.10	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Misty Hollow Lane	SR 2610	SR 2121	0.09	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Morrow School Rd.	SR 2147	DEAD END	0.60	Seal - Double and Fog Seal	$26,900
2030	7	001-Alamance	Preservation	Mt. Olive Church Rd.	NC 87 (S)	CCL	0.13	Seal - Double and Fog Seal	$58,200
2030	7	001-Alamance	Preservation	Payne Rd.	SR 2142	DEAD END	1.46	Seal - Double and Fog Seal	$67,150
2030	7	001-Alamance	Preservation	Perry Rd.	SR 2104	NC 87 (S)	3.00	Seal - Double and Fog Seal	$134,250
2030	7	001-Alamance	Preservation	Petty Rd.	SR 2172	SR 2178	0.70	Seal - Double and Fog Seal	$31,400
2030	7	001-Alamance	Preservation	Phillips Chapel Rd.	SR 2150	SR 2153	2.00	Seal - Double and Fog Seal	$89,500
2030	7	001-Alamance	Preservation	Pine Ave.	SR 2164	SR 2158	0.30	Seal - Double and Fog Seal	$13,500
2030	7	001-Alamance	Preservation	Pinetop Ave.	SR 2156	DEAD END	0.24	Seal - Double and Fog Seal	$13,500
2030	7	001-Alamance	Preservation	Preacher Davis Rd.	SR 2166	DEAD END	0.10	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Rumley Rd.	NC 87 (S)	SR 2176	2.70	Seal - Double and Fog Seal	$120,900

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	7	001-Alamance	Preservation	Ryan's Place	SR 2158	DEAD END	0.04	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Salem Church Rd.	SR 2150	NC 54	1.70	Seal - Double and Fog Seal	$76,100
2030	7	001-Alamance	Preservation	Salem Church Rd.	SR 2147	SR 2142	0.90	Seal - Double and Fog Seal	$40,300
2030	7	001-Alamance	Preservation	Saxapahaw-Beth. Ch. Rd	SR 2164	DEAD END	0.19	Seal - Double and Fog Seal	$9,000
2030	7	001-Alamance	Preservation	Saybrook Dr.	SR 2119	DEAD END	0.10	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Shelley Graham Rd.	SR 2116	DEAD END	0.60	Seal - Double and Fog Seal	$26,900
2030	7	001-Alamance	Preservation	Snipes Rd.	SR 2158	DEAD END	0.40	Seal - Double and Fog Seal	$17,900
2030	7	001-Alamance	Preservation	Southwick Dr.	SR 2116	DEAD END	0.20	Seal - Double and Fog Seal	$9,000
2030	7	001-Alamance	Preservation	Springe Lane	NC 87 (S)	DEAD END	0.20	Seal - Double and Fog Seal	$9,000
2030	7	001-Alamance	Preservation	SR 1931 Lee Rd	SR 1927 Brickyard Rd	EOM	0.37	Seal - Double	$15,845
2030	7	001-Alamance	Preservation	Stanton Ct.	SR 2632	DEAD END	0.10	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Steelcrest Rd.	SR 2223	DEAD END	0.26	Seal - Double and Fog Seal	$17,900
2030	7	001-Alamance	Preservation	Sweps. Meth. Ch. Rd.	SR 2158	SR 2159	0.30	Seal - Double and Fog Seal	$13,500
2030	7	001-Alamance	Preservation	Thom Rd.	SR 2146	NC 54	2.00	Seal - Double and Fog Seal	$89,500
2030	7	001-Alamance	Preservation	Varnals Ct.	SR 2632	DEAD END	0.09	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Viginia Lamm Rd.	SR 1005	DEAD END	0.40	Seal - Double and Fog Seal	$18,000
2030	7	001-Alamance	Preservation	Walter Andrews Rd.	SR 2116	DEAD END	0.20	Seal - Double and Fog Seal	$9,000
2030	7	001-Alamance	Preservation	Whitney Ln.	SR 2171	SR 2174	0.32	Seal - Double and Fog Seal	$17,900
2030	7	001-Alamance	Preservation	Whitney Rd.	NC 87 (S)	SR 2171	3.00	Seal - Double and Fog Seal	$132,300
2030	7	001-Alamance	Preservation	Will Ct.	SR 2628	DEAD END	0.10	Seal - Double and Fog Seal	$4,500
2030	7	001-Alamance	Preservation	Windsor Dr.	NC 87 (S)	DEAD END	0.23	Seal - Double and Fog Seal	$11,200
2030	7	001-Alamance	Preservation	Wlliam Newlin Dr.	SR 2627	SR 2632	0.20	Seal - Double and Fog Seal	$8,950
2030	7	001-Alamance	Preservation	Woods Ln.	NC 54	DEAD END	0.40	Seal - Double and Fog Seal	$17,900
2030	7	001-Alamance	Preservation	Wormranch Rd.	SR 2165	NC 54	0.80	Seal - Double and Fog Seal	$35,800
2030	7	017-Caswell	Resurfacing	Foster Rd.	SR 1300	US 158	5.10	#78 Mat Seal and 1.5" S9.5B	$820,000
2030	7	017-Caswell	Resurfacing	NC 49	OCL	PCL	2.61	#67 Mat Seal and 1.5" S9.5B	$705,100
2030	7	017-Caswell	Resurfacing	Park Springs Rd.	NC 86	SR 1500	2.00	#67 Mat Seal and 1.5" S9.5B	$375,000
2030	7	017-Caswell	Resurfacing	Park Springs Rd.	US 158	SR 1500	10.51	#78 Mat Seal and 1.5" S9.5B	$2,587,613
2030	7	017-Caswell	Resurfacing	Ridgeville Rd.	NC 86	US 158	9.83	#78 Mat Seal and 1.5" S9.5B	$1,600,000
2030	7	017-Caswell	Resurfacing	US 158 (W)	RCL	SR 1163 + .30 Miles	11.92	#67 Mat Seal and 1.5" S9.5B	$3,195,430
2030	7	017-Caswell	Preservation	Airport Rd.	US 158	END MAINT	0.17	Seal - Double and Fog Seal	$7,700
2030	7	017-Caswell	Preservation	Allison Grove Rd.	SR 1306	END MAINT	0.60	Seal - Double and Fog Seal	$26,900
2030	7	017-Caswell	Preservation	Big Oak Farm Rd.	SR 1300	SR 1306	1.80	Seal - Double and Fog Seal	$80,544
2030	7	017-Caswell	Preservation	Blackwell Rd.	SR 1321	END MAINT	1.16	Seal - Double and Fog Seal	$53,700
2030	7	017-Caswell	Preservation	Henderson Rd.	SR 1300	SR 1306	1.99	Seal - Double and Fog Seal	$89,500
2030	7	017-Caswell	Preservation	James Foster Rd.	SR 1311	END MAINT	0.40	Seal - Double and Fog Seal	$17,900
2030	7	017-Caswell	Preservation	Jones Rd.	SR 1306	SR 1311	1.70	Seal - Double and Fog Seal	$76,100
2030	7	017-Caswell	Preservation	Landfill Rd.	NC 86	END MAINT	0.20	Seal - Double and Fog Seal	$9,000
2030	7	017-Caswell	Preservation	Mineral Springs Rd.	SR 1306	SR 1311	1.70	Seal - Double and Fog Seal	$76,100
2030	7	017-Caswell	Preservation	Page Rd.	SR 1500	SR 1321	1.30	Seal - Double and Fog Seal	$58,171
2030	7	017-Caswell	Preservation	Pallie Watlington Rd.	SR 1311	END MAINT	1.10	Seal - Double and Fog Seal	$49,300
2030	7	017-Caswell	Preservation	Park Springs Lake Rd.	SR 1300	END MAINT	0.60	Seal - Double and Fog Seal	$26,900
2030	7	017-Caswell	Preservation	Thompson Rd.	SR 1315	END MAINT	0.44	Seal - Double and Fog Seal	$19,700
2030	7	017-Caswell	Preservation	Wild Wood Rd.	SR 1300	END MAINT	0.39	Seal - Double and Fog Seal	$17,900
2030	7	041-Guilford	Resurfacing	Alamance Rd.	SR 4193	END MAINT	0.46	#78 Mat Seal and 1.5" S9.5B	$121,400
2030	7	041-Guilford	Resurfacing	Alfred Dr.	SR 1424	SR 1427	0.29	#78 Mat Seal and 1.5" S9.5B	$75,800
2030	7	041-Guilford	Resurfacing	Anson Circle	SR 1371	CUL-DE-SAC	0.09	#78 Mat Seal and 1.5" S9.5B	$24,900
2030	7	041-Guilford	Resurfacing	Arborwood Dr.	SR 3231	DEAD END	0.11	#78 Mat Seal and 1.5" S9.5B	$28,630
2030	7	041-Guilford	Resurfacing	Aredon Dr.	DEAD END	CUL-DE-SAC	0.28	#78 Mat Seal and 1.5" S9.5B	$74,203
2030	7	041-Guilford	Resurfacing	Austin Creek Dr.	SR 4861	DEAD END	0.18	#78 Mat Seal and 1.5" S9.5B	$47,500
2030	7	041-Guilford	Resurfacing	Barden Dr.	NC 150	END MAINT	0.15	#78 Mat Seal and 1.5" S9.5B	$39,800
2030	7	041-Guilford	Resurfacing	Beaver Farm Ct.	SR 2029	CUL-DE-SAC	0.19	#78 Mat Seal and 1.5" S9.5B	$50,100
2030	7	041-Guilford	Resurfacing	Bethesda Ct.	SR 4861	CUL-DE-SAC	0.22	#78 Mat Seal and 1.5" S9.5B	$58,600
2030	7	041-Guilford	Resurfacing	Birdsong Ct.	SR 4915	CUL-DE-SAC	0.15	#78 Mat Seal and 1.5" S9.5B	$40,300
2030	7	041-Guilford	Resurfacing	Brandi Wood Circle	SR 4861	SR 4863	0.32	#78 Mat Seal and 1.5" S9.5B	$84,900
2030	7	041-Guilford	Resurfacing	Briar Rd.	SR 3999	CUL-DE-SAC	0.15	#78 Mat Seal and 1.5" S9.5B	$38,700
2030	7	041-Guilford	Resurfacing	Bridle Trail	SR 1379	SR 1376	0.10	#78 Mat Seal and 1.5" S9.5B	$25,700
2030	7	041-Guilford	Resurfacing	Brigham Rd.	SR 2133	DEAD END	0.45	#78 Mat Seal and 1.5" S9.5B	$119,600
2030	7	041-Guilford	Resurfacing	Brunswick Rd.	SR 1376	SR 1372	0.23	#78 Mat Seal and 1.5" S9.5B	$60,200

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	7	041-Guilford	Resurfacing	Buckminster Dr.	SR 5402	END MAINT	0.10	Microsurface	$3,369
2030	7	041-Guilford	Resurfacing	Cassidy Way	SR 2321	CUL-DE-SAC	0.18	#78 Mat Seal and 1.5" S9.5B	$47,200
2030	7	041-Guilford	Resurfacing	Castle Oaks Ct.	SR 1824	END MAINT	0.11	#78 Mat Seal and 1.5" S9.5B	$31,900
2030	7	041-Guilford	Resurfacing	Cattail Ct.	SR4045	CUL-DE-SAC	0.13	#78 Mat Seal and 1.5" S9.5B	$34,451
2030	7	041-Guilford	Resurfacing	Causey Lake Rd.	SR 3037	SR 1005	1.39	#78 Mat Seal and 1.5" S9.5B	$248,320
2030	7	041-Guilford	Resurfacing	Cell Rd.	SR 1426	DEAD END	0.25	#78 Mat Seal and 1.5" S9.5B	$65,500
2030	7	041-Guilford	Resurfacing	Championship Dr.	SR 5307	SR 5321	0.37	#78 Mat Seal and 1.5" S9.5B	$97,800
2030	7	041-Guilford	Resurfacing	Chelsea Acers Ct.	SR 1424	CUL-DE-SAC	0.11	#78 Mat Seal and 1.5" S9.5B	$28,700
2030	7	041-Guilford	Resurfacing	Chenault Ct.	SR 5406	CUL-DE-SAC	0.10	Microsurface	$1,872
2030	7	041-Guilford	Resurfacing	Church View Dr.	SR1001	CUL-DE-SAC	0.41	#78 Mat Seal and 1.5" S9.5B	$108,655
2030	7	041-Guilford	Resurfacing	Collonade Ct.	SR 5403	CUL-DE-SAC	0.05	Microsurface	$1,123
2030	7	041-Guilford	Resurfacing	County Line Rd.	FCL	SR 1858	1.32	#78 Mat Seal and 1.5" S9.5B	$350,100
2030	7	041-Guilford	Resurfacing	Currituck Place	SR 1373	SR 1624	0.11	#78 Mat Seal and 1.5" S9.5B	$30,200
2030	7	041-Guilford	Resurfacing	Dorchester Rd.	SR 1381	SR 1372	0.55	#78 Mat Seal and 1.5" S9.5B	$146,900
2030	7	041-Guilford	Resurfacing	E. Perquimans Rd.	CUL-DE-SAC	CUL-DE-SAC	0.20	#78 Mat Seal and 1.5" S9.5B	$53,300
2030	7	041-Guilford	Resurfacing	E. Sedgefield Dr.	SR 1381	SR 4121	0.30	#78 Mat Seal and 1.5" S9.5B	$80,100
2030	7	041-Guilford	Resurfacing	Eagle Nest Ct.	SR 4981	CUL-DE-SAC	0.05	#78 Mat Seal and 1.5" S9.5B	$143,150
2030	7	041-Guilford	Resurfacing	Eagle Nest Dr.	SR 4321	DEAD END	0.27	#78 Mat Seal and 1.5" S9.5B	$72,100
2030	7	041-Guilford	Resurfacing	Edgefield Ct.	SR 2011	END MAINT	0.08	#78 Mat Seal and 1.5" S9.5B	$21,250
2030	7	041-Guilford	Resurfacing	Forsyth Dr.	SR 1381	SR 1376	0.61	#78 Mat Seal and 1.5" S9.5B	$161,400
2030	7	041-Guilford	Resurfacing	Friendship Glen Dr.	SR 2728	CUL-DE-SAC	0.87	#78 Mat Seal and 1.5" S9.5B	$232,420
2030	7	041-Guilford	Resurfacing	Gaston Rd.	SR 1372	SR 1372	0.55	#78 Mat Seal and 1.5" S9.5B	$145,800
2030	7	041-Guilford	Resurfacing	Grenham Rd.	SR 2329	DEAD END	0.32	#78 Mat Seal and 1.5" S9.5B	$84,804
2030	7	041-Guilford	Resurfacing	Grinted Ct.	SR 4055	CUL-DE-SAC	0.22	#78 Mat Seal and 1.5" S9.5B	$58,303
2030	7	041-Guilford	Resurfacing	Gumwood Rd.	SR 2128	END MAINT	0.38	#78 Mat Seal and 1.5" S9.5B	$100,180
2030	7	041-Guilford	Resurfacing	Harvey Rd.	SR 4228	SR 1113	2.81	#78 Mat Seal and 1.5" S9.5B	$743,650
2030	7	041-Guilford	Resurfacing	Heather Ridge Ct.	SR 2329	CUL-DE-SAC	0.26	#78 Mat Seal and 1.5" S9.5B	$28,903
2030	7	041-Guilford	Resurfacing	Hedgerow Ct.	SR 1372	DEAD END	0.11	Mill 1.5" and 1.5" S9.5B	$27,900
2030	7	041-Guilford	Resurfacing	Henson Forest Dr.	DEAD END	SR 5020	2.29	#78 Mat Seal and 1.5" S9.5B	$275,900
2030	7	041-Guilford	Resurfacing	Hollow River Ct.	SR 2096	CUL-DE-SAC	0.15	#78 Mat Seal and 1.5" S9.5B	$39,800
2030	7	041-Guilford	Resurfacing	Hollow River Dr.	SR 2022	DEAD END	0.53	#78 Mat Seal and 1.5" S9.5B	$141,300
2030	7	041-Guilford	Resurfacing	Jac A. Ree Dr.	SR 4916	Adler Rd.	0.14	#78 Mat Seal and 1.5" S9.5B	$48,500
2030	7	041-Guilford	Resurfacing	Katherine Louise Dr.	SR 5017	SR 5017	0.27	#78 Mat Seal and 1.5" S9.5B	$71,100
2030	7	041-Guilford	Resurfacing	Kellam Ridge Dr.	SR 4901	DEAD END	0.10	#78 Mat Seal and 1.5" S9.5B	$26,501
2030	7	041-Guilford	Resurfacing	Kellam Ridge Dr.	SR 2329	DEAD END	0.29	#78 Mat Seal and 1.5" S9.5B	$76,854
2030	7	041-Guilford	Resurfacing	Kilt Ct.	SR 3231	CUL-DE-SAC	0.08	#78 Mat Seal and 1.5" S9.5B	$21,800
2030	7	041-Guilford	Resurfacing	Kyla Dr.	SR4372	DEAD END	0.11	#78 Mat Seal and 1.5" S9.5B	$29,151
2030	7	041-Guilford	Resurfacing	Lariat Dr.	SR 1002	CUL-DE-SAC	0.52	#78 Mat Seal and 1.5" S9.5B	$138,100
2030	7	041-Guilford	Resurfacing	Maple Tree Ct.	SR 2010	CUL-DE-SAC	0.16	#78 Mat Seal and 1.5" S9.5B	$43,200
2030	7	041-Guilford	Resurfacing	Margaret Ct.	SR 2252	CUL-DE-SAC	0.06	Mill 1.5" and 1.5" S9.5B	$14,600
2030	7	041-Guilford	Resurfacing	Matheson Ct.	SR 5017	DEAD END	0.10	#78 Mat Seal and 1.5" S9.5B	$27,100
2030	7	041-Guilford	Resurfacing	McCloud Rd.	CUL-DE-SAC	DEAD END	1.34	#78 Mat Seal and 1.5" S9.5B	$354,100
2030	7	041-Guilford	Resurfacing	McConnell Rd.	NA	NA	1.80	#78 Mat Seal and 1.5" S9.5B	$477,040
2030	7	041-Guilford	Resurfacing	Mckibbin Circle	SR 5054	SR 5054	0.27	#78 Mat Seal and 1.5" S9.5B	$70,800
2030	7	041-Guilford	Resurfacing	Mecklenburg Rd.	SR 1373	SR 1372	0.59	#78 Mat Seal and 1.5" S9.5B	$156,100
2030	7	041-Guilford	Resurfacing	Merrick Ct.	SR 4654	CUL-DE-SAC	0.10	#78 Mat Seal and 1.5" S9.5B	$27,300
2030	7	041-Guilford	Resurfacing	Milwood School Rd.	NC 68	SR 1556	0.45	#78 Mat Seal and 1.5" S9.5B	$118,500
2030	7	041-Guilford	Resurfacing	Minneola St.	Beg C&G	SR 2860	0.29	#78 Mat Seal and 1.5" S9.5B	$76,400
2030	7	041-Guilford	Resurfacing	Monnett Rd.	SR 3336	NC 22	5.13	#78 Mat Seal and 1.5" S9.5B	$1,359,530
2030	7	041-Guilford	Resurfacing	Mossyrock Rd.	SR 3549	SR 3314	1.30	#78 Mat Seal and 1.5" S9.5B	$220,000
2030	7	041-Guilford	Resurfacing	Mt. Hope Church Rd.	NA	NA	2.00	#78 Mat Seal and 1.5" S9.5B	$530,840
2030	7	041-Guilford	Resurfacing	Mt. Hope Church Rd.	NA	NA	3.35	#78 Mat Seal and 1.5" S9.5B	$887,800
2030	7	041-Guilford	Resurfacing	N. Church St.	US70	PVMT. JOINT @ 840	3.74	#78 Mat Seal and 1.5" S9.5B	$991,152
2030	7	041-Guilford	Resurfacing	N. Rockingham Rd.	SR 1371	SR 1624	1.09	#78 Mat Seal and 1.5" S9.5B	$288,900
2030	7	041-Guilford	Resurfacing	New Avedon Dr.	CUL-DE-SAC	DEAD END	0.28	#78 Mat Seal and 1.5" S9.5B	$74,203
2030	7	041-Guilford	Resurfacing	Pasquotank Rd.	SR 1372	SR 1485	0.09	#78 Mat Seal and 1.5" S9.5B	$23,900
2030	7	041-Guilford	Resurfacing	Pavalion Ct.	SR 5402	CUL-DE-SAC	0.29	Microsurface	$5,429
2030	7	041-Guilford	Resurfacing	Pearson Run Ct.	SR 4861	CUL-DE-SAC	0.15	#78 Mat Seal and 1.5" S9.5B	$40,100
2030	7	041-Guilford	Resurfacing	Pegg Rd.	SR 1556	SR 1844	1.33	Mill 1.5" and 1.5" S9.5B	$352,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	7	041-Guilford	Resurfacing	Piedmont Triad Prkwy	SR 1844	SR 1840	0.49	Mill 1.5" and 1.5" S9.5B	$260,800
2030	7	041-Guilford	Resurfacing	Pilot Circle	SR 1381	END MAINT	0.06	#78 Mat Seal and 1.5" S9.5B	$156,400
2030	7	041-Guilford	Resurfacing	Prima Ct.	SR4048	CUL-DE-SAC	0.08	#78 Mat Seal and 1.5" S9.5B	$21,201
2030	7	041-Guilford	Resurfacing	Prima Dr.	SR 4045	SR 1001	0.23	#78 Mat Seal and 1.5" S9.5B	$60,953
2030	7	041-Guilford	Resurfacing	Prudencia Dr.	SR 3219	DEAD END	0.90	#78 Mat Seal and 1.5" S9.5B	$237,720
2030	7	041-Guilford	Resurfacing	Reata Dr.	NC 150	CUL-DE-SAC	0.33	#78 Mat Seal and 1.5" S9.5B	$88,300
2030	7	041-Guilford	Resurfacing	Reserve Parkway	SR 3056	DEAD END	0.49	Microsurface	$76,000
2030	7	041-Guilford	Resurfacing	Rockingham Rd. (S)	SR 1372	SR 1478	0.71	#78 Mat Seal and 1.5" S9.5B	$189,300
2030	7	041-Guilford	Resurfacing	S. College Dr.	SR 1961	SR 1278	0.97	Mill 1.5" and 1.5" S9.5B	$258,150
2030	7	041-Guilford	Resurfacing	Saratoga Ct.	SR 4864	CUL-DE-SAC	0.11	#78 Mat Seal and 1.5" S9.5B	$29,450
2030	7	041-Guilford	Resurfacing	Scottville rd.	SR 2850	US 70	0.16	#78 Mat Seal and 1.5" S9.5B	$41,350
2030	7	041-Guilford	Resurfacing	Shimer Dr.	SR 1424	SR 1428	0.47	#78 Mat Seal and 1.5" S9.5B	$124,600
2030	7	041-Guilford	Resurfacing	Simpson Calhoun Rd.	SR 2329	PVMT JOINT	0.38	#78 Mat Seal and 1.5" S9.5B	$100,705
2030	7	041-Guilford	Resurfacing	Spencer Brook Dr.	SR 4861	CUL-DE-SAC	0.47	#78 Mat Seal and 1.5" S9.5B	$125,700
2030	7	041-Guilford	Resurfacing	Stanback Ct.	SR 5054	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$17,226
2030	7	041-Guilford	Resurfacing	Summit Ave.	NC 150	SR 2515+0.14mi	2.00	#67 Mat Seal and 1.5" S9.5B	$536,150
2030	7	041-Guilford	Resurfacing	Summit Springs Ct.	SR 4930	CUL-DE-SAC	0.09	#78 Mat Seal and 1.5" S9.5B	$23,057
2030	7	041-Guilford	Resurfacing	Suttonwood Dr.	SR 4121	SR 1372	0.32	#78 Mat Seal and 1.5" S9.5B	$85,900
2030	7	041-Guilford	Resurfacing	Sydney Ct.	SR 4861	CUL-DE-SAC	0.07	#78 Mat Seal and 1.5" S9.5B	$182,900
2030	7	041-Guilford	Resurfacing	Tartan Ct.	SR 3231	CUL-DE-SAC	0.08	#78 Mat Seal and 1.5" S9.5B	$21,200
2030	7	041-Guilford	Resurfacing	Transon Ct.	SR 5403	CUL-DE-SAC	0.04	Microsurface	$936
2030	7	041-Guilford	Resurfacing	Tynecastle Ct.	SR1001	CUL-DE-SAC	0.24	#78 Mat Seal and 1.5" S9.5B	$63,603
2030	7	041-Guilford	Resurfacing	W. Market Center Dr.	E. Kearns Ave.	SR 4053	1.13	Mill 1.5" and 1.5" S9.5B	$298,950
2030	7	041-Guilford	Resurfacing	W. Sedgefield Dr.	SR 1381	SR 4121	0.28	#78 Mat Seal and 1.5" S9.5B	$74,800
2030	7	041-Guilford	Resurfacing	Wallace Dr.	SR 1378	SR 1373	0.22	#78 Mat Seal and 1.5" S9.5B	$58,300
2030	7	041-Guilford	Resurfacing	Wayne Rd.	SR 1387	SR 4193	0.71	#78 Mat Seal and 1.5" S9.5B	$187,700
2030	7	041-Guilford	Resurfacing	Wedgewood Dr.	BEG MAINT	DEAD END	0.24	#78 Mat Seal and 1.5" S9.5B	$64,200
2030	7	041-Guilford	Resurfacing	West Whirlaway Ct.	SR 5309	CUL-De-SAC	0.11	#78 Mat Seal and 1.5" S9.5B	$29,200
2030	7	041-Guilford	Resurfacing	Westbury Dr.	SR 2074	END MAINT	0.16	#78 Mat Seal and 1.5" S9.5B	$43,000
2030	7	041-Guilford	Resurfacing	Whitestone Dr.	SR1001	SR 4047	0.48	#78 Mat Seal and 1.5" S9.5B	$127,206
2030	7	041-Guilford	Resurfacing	Wyatt Dr.	SR 2127	SR 2127	0.74	#78 Mat Seal and 1.5" S9.5B	$196,900
2030	7	041-Guilford	Preservation	Bartlett Dr.	SR 4038	END MAINT	0.09	Seal - Double and Fog Seal	$2,610
2030	7	041-Guilford	Preservation	Bashkir Way	SR 2509	SR 5240	0.07	Seal - Double and Fog Seal	$3,177
2030	7	041-Guilford	Preservation	Beckett Rd.	SR 2630	DEAD END	0.15	Seal - Double and Fog Seal	$6,800
2030	7	041-Guilford	Preservation	Bee Jay Rd.	NC 150	DEAD END	0.63	Seal - Double and Fog Seal	$28,200
2030	7	041-Guilford	Preservation	Benaja Rd.	SR 2514	RCL	1.78	Seal - Double and Fog Seal	$79,700
2030	7	041-Guilford	Preservation	Birchdale Rd.	SR 2650	SR 5247	0.35	Seal - Double and Fog Seal	$15,500
2030	7	041-Guilford	Preservation	Blagdon Ct.	SR 5241	DEAD END	0.09	Seal - Double and Fog Seal	$3,900
2030	7	041-Guilford	Preservation	Bluefield Rd.	NC 150	SR 2650	0.19	Seal - Double and Fog Seal	$8,600
2030	7	041-Guilford	Preservation	Bluefield Rd.	SR 2647	SR 2649	0.24	Seal - Double and Fog Seal	$10,700
2030	7	041-Guilford	Preservation	Bowling Green Dr.	SR 5229	DEAD END	0.17	Seal - Double and Fog Seal	$7,700
2030	7	041-Guilford	Preservation	Burguss Rd.	BEG MAINT	FCL	0.20	Seal - Double and Fog Seal	$6,000
2030	7	041-Guilford	Preservation	Burnette Dr.	SR 1130	END MAINT	0.30	Seal - Double and Fog Seal	$8,940
2030	7	041-Guilford	Preservation	Burton Farm Rd.	SR 2523	SR 1001	1.74	Seal - Double and Fog Seal	$78,000
2030	7	041-Guilford	Preservation	Bush Rd.	SR 2359	DEAD END	0.69	Seal - Double and Fog Seal	$31,000
2030	7	041-Guilford	Preservation	Byfield Rd.	SR 2614	DEAD END	0.09	Seal - Double and Fog Seal	$4,200
2030	7	041-Guilford	Preservation	Caber Rd.	NC 150	SR 2526	0.67	Seal - Double and Fog Seal	$30,200
2030	7	041-Guilford	Preservation	Candlenut Rd.	SR 2526	DEAD END	0.39	Seal - Double and Fog Seal	$17,300
2030	7	041-Guilford	Preservation	Chatsworth Ct.	SR 5241	NS-98070	0.11	Seal - Double and Fog Seal	$4,900
2030	7	041-Guilford	Preservation	Clayton Rd.	SR 2630	NC 150	0.47	Seal - Double and Fog Seal	$20,900
2030	7	041-Guilford	Preservation	Clybourn Ct.	SR 5241	DEAD END	0.06	Seal - Double and Fog Seal	$2,700
2030	7	041-Guilford	Preservation	Faulkner Rd.	NC 62	SR 1286	0.40	Seal - Double and Fog Seal	$12,500
2030	7	041-Guilford	Preservation	Ferrin Rd.	NC 150	DEAD END	1.01	Seal - Double and Fog Seal	$44,970
2030	7	041-Guilford	Preservation	Gilchrist Rd.	SR 2523	DEAD END	0.23	Seal - Double and Fog Seal	$10,300
2030	7	041-Guilford	Preservation	Gilchrist Rd.	SR 2523	DEAD END	0.20	Seal - Double and Fog Seal	$6,900
2030	7	041-Guilford	Preservation	Gorman Dr.	NC 150	DEAD END	0.11	Seal - Double and Fog Seal	$5,000
2030	7	041-Guilford	Preservation	Highlawn Dr.	SR 4178	SR 1655	0.13	Seal - Double and Fog Seal	$4,000
2030	7	041-Guilford	Preservation	Ivywood Rd.	NC 150	DEAD END	0.16	Seal - Double and Fog Seal	$7,400
2030	7	041-Guilford	Preservation	Jonquil Dr.	SR 1129	END MAINT.	1.04	Seal - Double and Fog Seal	$106,353

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	7	041-Guilford	Preservation	Joyce Circle	SR 1824	FCL	0.08	Seal - Double and Fog Seal	$4,000
2030	7	041-Guilford	Preservation	Kalon Dr.	SR 2523	END MAINT.	0.25	Seal - Double and Fog Seal	$7,500
2030	7	041-Guilford	Preservation	Kalon Dr.	SR 2523	NS-9554	0.25	Seal - Double and Fog Seal	$11,300
2030	7	041-Guilford	Preservation	Krista-Kim Dr.	SR 1556	DEAD END	0.38	Seal - Double and Fog Seal	$12,000
2030	7	041-Guilford	Preservation	Lynnoak Dr.	SR 1130	END MAINT	0.14	Seal - Double and Fog Seal	$4,080
2030	7	041-Guilford	Preservation	Mapleway Ln.	NC 150	SR 2674	0.37	Seal - Double and Fog Seal	$16,800
2030	7	041-Guilford	Preservation	Mapleway Ln.	DEAD END	SR 5247	0.06	Seal - Double and Fog Seal	$2,870
2030	7	041-Guilford	Preservation	Meadowrue Dr.	SR 2523	DEAD END	0.13	Seal - Double and Fog Seal	$5,700
2030	7	041-Guilford	Preservation	Memory Way	SR 1117	END MAINT	0.15	Seal - Double and Fog Seal	$4,560
2030	7	041-Guilford	Preservation	Middleburg Rd.	SR 1104	SR 3267	0.31	Seal - Double and Fog Seal	$9,390
2030	7	041-Guilford	Preservation	Miltonwood Rd.	BEG MAINT	SR 2359	0.78	Seal - Double and Fog Seal	$34,900
2030	7	041-Guilford	Preservation	Monrovia Dr.	SR 2501	SR 2649	0.08	Seal - Double and Fog Seal	$3,800
2030	7	041-Guilford	Preservation	Nutmeg Dr.	SR 2522	SR 2615	0.08	Seal - Double and Fog Seal	$3,500
2030	7	041-Guilford	Preservation	Oak Arbor Rd.	NC 150	DEAD END	0.50	Seal - Double and Fog Seal	$22,380
2030	7	041-Guilford	Preservation	Oakbury Ct.	DEAD END	SR 2654	0.18	Seal - Double and Fog Seal	$8,000
2030	7	041-Guilford	Preservation	Old Berkshire Dr.	DEAD END	SR 5241	0.45	Seal - Double and Fog Seal	$20,000
2030	7	041-Guilford	Preservation	Old Mine Rd.	SR 2531	END MAINT.	0.10	Seal - Double and Fog Seal	$5,100
2030	7	041-Guilford	Preservation	Pindals Rd.	SR 2526	DEAD END	0.37	Seal - Double and Fog Seal	$16,700
2030	7	041-Guilford	Preservation	Pinoak Rd.	SR 2647	SR 2659	0.59	Seal - Double and Fog Seal	$26,600
2030	7	041-Guilford	Preservation	Queen Alice Rd.	SR 4121	END MAINT.	0.10	Seal - Double and Fog Seal	$9,500
2030	7	041-Guilford	Preservation	Richardsonwood Rd.	SR 2504	RCL	0.17	Seal - Double and Fog Seal	$7,500
2030	7	041-Guilford	Preservation	Ridgecroft Rd.	SR 2523	DEAD ENd	0.10	Seal - Double and Fog Seal	$4,500
2030	7	041-Guilford	Preservation	River Ridge Rd.	SR 2509	DEAD END	0.60	Seal - Double and Fog Seal	$26,700
2030	7	041-Guilford	Preservation	Sandy Ridge Rd.	SR 1855	FCL	1.43	Seal - Double and Fog Seal	$43,000
2030	7	041-Guilford	Preservation	Service Rd.	US 29	DEAD END	0.25	Seal - Double and Fog Seal	$11,200
2030	7	041-Guilford	Preservation	Southerland Dr.	NC 150	NS-92610	0.79	Seal - Double and Fog Seal	$35,400
2030	7	041-Guilford	Preservation	Sutton Ct.	SR 1106	END MAINT	0.24	Seal - Double and Fog Seal	$7,200
2030	7	041-Guilford	Preservation	Tanglebrook Rd.	SR 1820	FCL	0.32	Seal - Double and Fog Seal	$10,000
2030	7	041-Guilford	Preservation	Teralda Pl.	SR 2504	DEAD END	0.31	Seal - Double and Fog Seal	$13,700
2030	7	041-Guilford	Preservation	Thacker Rd.	SR 2523	SR 2614	0.34	Seal - Double and Fog Seal	$15,400
2030	7	041-Guilford	Preservation	Willmatt Dr.	SR 2516	DEAD END	0.24	Seal - Double and Fog Seal	$10,900
2030	7	068-Orange	Resurfacing	Brisbane Dr.	SR 1718	CUL-DE-SAC	0.04	#78 Mat Seal and 1.5" S9.5B	$106,100
2030	7	068-Orange	Resurfacing	Casey Lane	SR 1306	CUL-DE-SAC	0.24	#78 Mat Seal and 1.5" S9.5B	$63,700
2030	7	068-Orange	Resurfacing	Creekridge Ln.	SR 2281	CUL-DE-SAC	0.40	#78 Mat Seal and 1.5" S9.5B	$106,100
2030	7	068-Orange	Resurfacing	Creekwood Dr.	SR 1731	SR 1731	0.90	#78 Mat Seal and 1.5" S9.5B	$238,520
2030	7	068-Orange	Resurfacing	E. Mill Pointe Lane	SR 1343	CUL-DE-SAC	0.49	#78 Mat Seal and 1.5" S9.5B	$129,900
2030	7	068-Orange	Resurfacing	Eubanks Rd.	NC 86	SR 1009	1.80	#78 Mat Seal and 1.5" S9.5B	$290,500
2030	7	068-Orange	Resurfacing	Hathaway Lane	SR 1718	CUL-DE-SAC	0.30	#78 Mat Seal and 1.5" S9.5B	$79,600
2030	7	068-Orange	Resurfacing	Iva Ada Drive	SR 1548	CUL-DE-SAC	0.33	#78 Mat Seal and 1.5" S9.5B	$87,500
2030	7	068-Orange	Resurfacing	Jomali Dr.	SR 1567	CUL-DE-SAC	0.72	#78 Mat Seal and 1.5" S9.5B	$99,000
2030	7	068-Orange	Resurfacing	Kerley Rd.	DCL	SR 1716	1.10	#78 Mat Seal and 1.5" S9.5B	$291,520
2030	7	068-Orange	Resurfacing	Lannie Dr.	SR 1709	SR 1711	0.97	#78 Mat Seal and 1.25" S9.5A	$135,000
2030	7	068-Orange	Resurfacing	NC 54	Anderson Prk Joint	SR 1951	3.80	#78 Mat Seal and 1.5" S9.5C	$1,007,053
2030	7	068-Orange	Resurfacing	Oak Hill Dr.	SR 1732	SR 1732	1.06	#78 Mat Seal and 1.5" S9.5B	$291,600
2030	7	068-Orange	Resurfacing	Oakdale Rd.	SR 1006	SR 1009	1.10	#78 Mat Seal and 1.5" S9.5B	$174,500
2030	7	068-Orange	Resurfacing	Old Greensboro Rd.	SR 1942	ACL	9.12	#78 Mat Seal and 1.5" S9.5B	$2,416,930
2030	7	068-Orange	Resurfacing	Rigsbee Rd. (N)	SR 1712	END PVMT	0.05	#78 Mat Seal and 1.5" S9.5B	$70,000
2030	7	068-Orange	Resurfacing	Riverside Dr.	US 70	US 70	0.84	#78 Mat Seal and 1.25" S9.5A	$120,000
2030	7	068-Orange	Resurfacing	Sawmill Rd.	NC 86	SR 1001	1.90	#78 Mat Seal and 1.5" S9.5B	$337,250
2030	7	068-Orange	Resurfacing	Wolfs Trail	SR 1939	SR 2020	0.85	#78 Mat Seal and 1.25" S9.5A	$113,560
2030	7	068-Orange	Preservation	Bivins Rd.	SR 1002	DCL	0.59	Seal - Double and Fog Seal	$26,400
2030	7	068-Orange	Preservation	Brigadoon Rd.	SR 1566	END PVMT	0.75	Seal - Double and Fog Seal	$33,600
2030	7	068-Orange	Preservation	Cabe Ford Rd.	SR 1567	END MAINT	0.63	Seal - Double and Fog Seal	$28,200
2030	7	068-Orange	Preservation	Cole Mill Rd.	SR 1567	DEAD END	0.90	Seal - Double and Fog Seal	$40,300
2030	7	068-Orange	Preservation	Deer View Tr.	NC 157	END PVMT	0.37	Seal - Double and Fog Seal	$16,600
2030	7	068-Orange	Preservation	Ebenezer Church Rd.	SR 1567	DCL	1.00	Seal - Double and Fog Seal	$44,800
2030	7	068-Orange	Preservation	Forest Ridge Place	SR 1602	CUL-DE-SAC	0.10	Seal - Double and Fog Seal	$4,500
2030	7	068-Orange	Preservation	Gibs Lane	SR 1562	CUL-DE-SAC	0.35	Seal - Double and Fog Seal	$15,700
2030	7	068-Orange	Preservation	Horse Shoe Creek Rd.	SR 1617	SR 1617	0.50	Seal - Double and Fog Seal	$23,373

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	7	068-Orange	Preservation	Howe St.	DCL	END MAINT	0.29	Seal - Double and Fog Seal	$13,000
2030	7	068-Orange	Preservation	Laurel Ridge Rd.	SR 1567	DEAD END	0.30	Seal - Double and Fog Seal	$13,500
2030	7	068-Orange	Preservation	Linden Rd.	US 70	END PAVEMENT	1.19	Seal - Double and Fog Seal	$53,250
2030	7	068-Orange	Preservation	McDermot Rd.	SR 1590	END PVMT	0.50	Seal - Double and Fog Seal	$23,400
2030	7	068-Orange	Preservation	Palmers Grove Rd.	US 70	SR 1561	1.75	Seal - Double and Fog Seal	$78,350
2030	7	068-Orange	Preservation	Pleasant Gr. Comm. Ctr.	SR 1567	DEAD END	0.14	Seal - Double and Fog Seal	$6,300
2030	7	068-Orange	Preservation	Reinfrew Rd.	SR 1590	END PAVMT	0.50	Seal - Double and Fog Seal	$23,400
2030	7	068-Orange	Preservation	Saddle Dr.	SR 1617	SR 1617	0.20	Seal - Double and Fog Seal	$23,400
2030	7	068-Orange	Preservation	Shelton Ct.	SR 1002	END PVMT	0.17	Seal - Double and Fog Seal	$7,700
2030	7	068-Orange	Preservation	Springview Trail	SR 1567	DEAD END	0.23	Seal - Double and Fog Seal	$10,300
2030	7	068-Orange	Preservation	Summer Ln.	SR 1610	END PVMT	0.23	Seal - Double and Fog Seal	$10,300
2030	7	068-Orange	Preservation	Tuscarora Dr.	US 70	END PAVEMENT	0.39	Seal - Double and Fog Seal	$17,500
2030	7	068-Orange	Preservation	Willet Dr.	SR 1567	CUL-DE-SAC	0.93	Seal - Double and Fog Seal	$41,700
2030	7	068-Orange	Preservation	Yates Rd.	SR 1562	CUL-DE-SAC	0.50	Seal - Double and Fog Seal	$22,400
2030	7	079-Rockingham	Resurfacing	Bakers Crossroad	SR 1001	NC 704	4.80	#78 Mat Seal and 1.5" S9.5B	$1,272,100
2030	7	079-Rockingham	Resurfacing	Bethany Rd.	SR 2308	NC 65	5.12	#78 Mat Seal and 1.5" S9.5B	$1,356,900
2030	7	079-Rockingham	Resurfacing	Moir Mill Rd.	SR 2023	SR 2039	4.64	#78 Mat Seal and 1.5" S9.5B	$1,229,670
2030	7	079-Rockingham	Resurfacing	NC 770	SR 1594	US 311	6.00	#67 Mat Seal and 1.5" S9.5B	$1,100,000
2030	7	079-Rockingham	Resurfacing	Oregon Hill Rd.	NC 700	US 29 Bus.	6.01	#78 Mat Seal and 1.5" S9.5B	$1,592,735
2030	7	079-Rockingham	Resurfacing	Stadium Dr.	NC 700	SR 1787	1.34	Mill 1.5" and #67 Mat Seal and 1.5" S9.5B	$303,997
2030	7	079-Rockingham	Resurfacing	Stewart Store Rd.	SR 2203	SR 2021	0.40	#78 Mat Seal and 1.5" S9.5B	$88,704
2030	7	079-Rockingham	Resurfacing	US 311	NC 14	SR 1714+.96	2.32	Mill 1.5" and 1.5" S9.5C	$1,114,282
2030	7	079-Rockingham	Preservation	Alee Rd.	SR 2571	DEAD END	0.38	Seal - Double and Fog Seal	$17,700
2030	7	079-Rockingham	Preservation	Apple Rd.	SR 2571	DEA D END	0.57	Seal - Double and Fog Seal	$26,600
2030	7	079-Rockingham	Preservation	Bayberry Rd.	SR 2579	NS-99930	0.15	Seal - Double and Fog Seal	$7,000
2030	7	079-Rockingham	Preservation	Bell Rd.	SR 2600	DEAD END	0.71	Seal - Double and Fog Seal	$33,100
2030	7	079-Rockingham	Preservation	Billingsley Rd.	SR 2633	DEAD END	0.17	Seal - Double and Fog Seal	$8,000
2030	7	079-Rockingham	Preservation	Brady Club Rd.	US 158	DEAD END	0.41	Seal - Double and Fog Seal	$19,100
2030	7	079-Rockingham	Preservation	Brann Rd.	GCL	SR 2614	1.11	Seal - Double and Fog Seal	$51,800
2030	7	079-Rockingham	Preservation	Busick Rd.	SR 2571	DEAD END	0.34	Seal - Double and Fog Seal	$15,900
2030	7	079-Rockingham	Preservation	Carriage Ln.	NC 87	Gravel Rd.	0.30	Seal - Double and Fog Seal	$14,000
2030	7	079-Rockingham	Preservation	Carrot Rd.	NC 87	SR 2817	0.11	Seal - Double and Fog Seal	$5,200
2030	7	079-Rockingham	Preservation	Chico Rd.	SR 2633	DEAD END	0.18	Seal - Double and Fog Seal	$8,400
2030	7	079-Rockingham	Preservation	City Store Rd.	SR 2631	NC 87	1.20	Seal - Double and Fog Seal	$55,600
2030	7	079-Rockingham	Preservation	Combs Rd.	NC 87	MP 0.89	0.89	Seal - Double and Fog Seal	$41,400
2030	7	079-Rockingham	Preservation	Copperhead Rd.	SR 2580	DEAD END	0.45	Seal - Double and Fog Seal	$21,000
2030	7	079-Rockingham	Preservation	Cornelius Rd.	US 29	DEAD END	0.72	Seal - Double and Fog Seal	$33,500
2030	7	079-Rockingham	Preservation	Cotton Rd.	SR 2600	DEAD END	0.51	Seal - Double and Fog Seal	$23,800
2030	7	079-Rockingham	Preservation	County Line Rd.	NC 87	SR 2692	2.58	Seal - Double and Fog Seal	$115,270
2030	7	079-Rockingham	Preservation	Deer Trail Rd.	SR 2688	DEAD END	0.12	Seal - Double and Fog Seal	$5,600
2030	7	079-Rockingham	Preservation	Elliot Rd.	SR 2817	DEAD END	0.60	Seal - Double and Fog Seal	$28,000
2030	7	079-Rockingham	Preservation	Faucette Rd.	SR 2571	MP 0.72	0.72	Seal - Double and Fog Seal	$33,500
2030	7	079-Rockingham	Preservation	First Ct.	SR 2682	DEAD END	0.17	Seal - Double and Fog Seal	$7,800
2030	7	079-Rockingham	Preservation	Frank Rd.	SR 2571	DEAD END	1.57	Seal - Double and Fog Seal	$73,100
2030	7	079-Rockingham	Preservation	Friendship Church Rd.	SR 2627	SR 2627	0.80	Seal - Double and Fog Seal	$37,300
2030	7	079-Rockingham	Preservation	Gardner Rd.	NC 150	DEAD END	0.87	Seal - Double and Fog Seal	$40,500
2030	7	079-Rockingham	Preservation	Garrison Rd.	US 158	SR 2552	2.02	Seal - Double and Fog Seal	$90,400
2030	7	079-Rockingham	Preservation	Gilliam Rd.	SR 2614	NC 150	2.13	Seal - Double and Fog Seal	$99,045
2030	7	079-Rockingham	Preservation	Grady Rd.	US 158	END PVMT	0.31	Seal - Double and Fog Seal	$14,500
2030	7	079-Rockingham	Preservation	Haw Rd.	NC 150	DEAD END	1.00	Seal - Double and Fog Seal	$46,500
2030	7	079-Rockingham	Preservation	Hearth Rd.	SR 2627	DEAD END	0.29	Seal - Double and Fog Seal	$13,500
2030	7	079-Rockingham	Preservation	Jones Lake Rd.	SR 2600	DEAD END	0.59	Seal - Double and Fog Seal	$27,500
2030	7	079-Rockingham	Preservation	Kernodle Rd.	SR 2658	SR 2614	1.87	Seal - Double and Fog Seal	$86,800
2030	7	079-Rockingham	Preservation	Kimbro Rd.	US 158	DEAD END	0.55	Seal - Double and Fog Seal	$25,600
2030	7	079-Rockingham	Preservation	Leap Rd.	US 158	SR 2552	0.13	Seal - Double and Fog Seal	$6,100
2030	7	079-Rockingham	Preservation	Lindsey Rd.	NC 87	DEAD END	0.84	Seal - Double and Fog Seal	$39,100
2030	7	079-Rockingham	Preservation	Manley Farm Rd.	SR 2579	MP 1.46	1.46	Seal - Double and Fog Seal	$67,900
2030	7	079-Rockingham	Preservation	Massey Rd.	SR 2571	DEAD END	1.21	Seal - Double and Fog Seal	$26,300
2030	7	079-Rockingham	Preservation	Mullins Rd.	US 158	DEAD END	0.57	Seal - Double and Fog Seal	$26,300

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	7	079-Rockingham	Preservation	Partridge Ct.	SR 2592	DEAD END	0.33	Seal - Double and Fog Seal	$15,400
2030	7	079-Rockingham	Preservation	Pearson Cemetary Rd.	SR 2571	DEAD END	0.41	Seal - Double and Fog Seal	$19,100
2030	7	079-Rockingham	Preservation	Penn Rd.	SR 2600	DEAD END	0.75	Seal - Double and Fog Seal	$34,900
2030	7	079-Rockingham	Preservation	Pepper Rd.	SR 2596	DEAD END	0.81	Seal - Double and Fog Seal	$37,700
2030	7	079-Rockingham	Preservation	Perkins Loop	NC 87	NC 87	0.35	Seal - Double and Fog Seal	$16,300
2030	7	079-Rockingham	Preservation	Ponderosa Acres Rd.	SR 2577	CDS	0.29	Seal - Double and Fog Seal	$13,500
2030	7	079-Rockingham	Preservation	Rockingham Lake Rd.	SR 2571	NC 150	3.36	Seal - Double and Fog Seal	$150,400
2030	7	079-Rockingham	Preservation	Rocky Ford Rd.	SR 2594	SR 2571	1.44	Seal - Double and Fog Seal	$66,900
2030	7	079-Rockingham	Preservation	Running Creek Rd.	SR 2623	GCL	0.46	Seal - Double and Fog Seal	$21,350
2030	7	079-Rockingham	Preservation	Rustic Rd.	NC 87	SR 2613	0.34	Seal - Double and Fog Seal	$15,900
2030	7	079-Rockingham	Preservation	Second Ct.	SR 2682	DEAD END	0.12	Seal - Double and Fog Seal	$5,600
2030	7	079-Rockingham	Preservation	Somers Loop	NC 150	NC 150	0.59	Seal - Double and Fog Seal	$27,500
2030	7	079-Rockingham	Preservation	Stanfield Rd.	NC 87	DEAD END	0.79	Seal - Double and Fog Seal	$26,800
2030	7	079-Rockingham	Preservation	Stockton Rd.	SR 2588	DEAD END	0.19	Seal - Double and Fog Seal	$8,900
2030	7	079-Rockingham	Preservation	Sweetgum Rd.	SR 2581	DEAD END	0.31	Seal - Double and Fog Seal	$14,500
2030	7	079-Rockingham	Preservation	Tate Rd	SR 2571	CCL	3.06	Seal - Double and Fog Seal	$137,150
2030	7	079-Rockingham	Preservation	Trails End Rd.	DEAD END	SR 2613	1.48	Seal - Double and Fog Seal	$28,800
2030	7	079-Rockingham	Preservation	Vaughn Rd.	US 158	SR 2579	1.45	Seal - Double and Fog Seal	$67,500
2030	7	079-Rockingham	Preservation	Watts Farm Rd.	SR 2552	MP 0.45	0.45	Seal - Double and Fog Seal	$20,950
2030	7	079-Rockingham	Preservation	Wildlife Lake Rd.	NC 150	END PVMT	0.82	Seal - Double and Fog Seal	$38,200
2030	7	079-Rockingham	Preservation	Zeb Rd.	SR 2617	CCL	0.48	Seal - Double and Fog Seal	$22,350
2030	8	019-Chatham	Resurfacing	NC 751	US 64	DURHAM CO	9.30	2.0" S9.5B	$1,700,000
2030	8	019-Chatham	Resurfacing	NC 87	US 64 BUS	SR 1571	2.03	2.0" S9.5B	$400,000
2030	8	019-Chatham	Resurfacing	NC 902	SR 1009	SR 1176	2.00	#78 Mat Seal and 1.5" S9.5B	$400,000
2030	8	019-Chatham	Resurfacing	SR 1006	NC 902	MOORE CO	4.23	2.0" S9.5B	$650,000
2030	8	019-Chatham	Resurfacing	SR 1011	WAKE CO	BRIDGE	1.71	2.0" S9.5B	$300,000
2030	8	019-Chatham	Resurfacing	SR 1011	HAW RIVER BRIDGE	LEE CO	2.15	2.0" S9.5B	$400,000
2030	8	019-Chatham	Resurfacing	SR 1103	SR 1107	SR 1102	1.24	1.25" SF9.5A	$221,000
2030	8	019-Chatham	Resurfacing	SR 1105	US 64	SR 1107	0.27	1.25" SF9.5A	$40,000
2030	8	019-Chatham	Resurfacing	SR 1151	SR 1005	NC 22	3.69	1.5" S9.5B	$575,000
2030	8	019-Chatham	Resurfacing	SR 1176	SR 2113	SR 1005	4.00	#67 Mat Seal and 1.5" S9.5B	$720,000
2030	8	019-Chatham	Resurfacing	SR 1506	SR 1555	SR 1549	0.82	1.5" S9.5B	$120,000
2030	8	019-Chatham	Resurfacing	SR 1529	US 501	END MAINT	0.63	1.25" S9.5B	$113,000
2030	8	019-Chatham	Resurfacing	SR 1539	SR 1536	SR 1540	1.05	1.5" S9.5B	$189,000
2030	8	019-Chatham	Resurfacing	SR 1727	SR 1008	SR 1726	0.73	1.5" S9.5B	$132,000
2030	8	019-Chatham	Resurfacing	SR 1727	SR 1726	END MAINT	1.29	1.5" S9.5B	$200,000
2030	8	019-Chatham	Resurfacing	SR 1912	SR 1011	NC 42	5.26	1.5" S9.5B	$800,000
2030	8	019-Chatham	Resurfacing	SR 1921	NC 42	ENG PVMT	0.80	1.25" S9.5B	$100,000
2030	8	019-Chatham	Resurfacing	SR 1923	SR 1916	END MAINT	0.19	1.5" S9.5B	$30,000
2030	8	019-Chatham	Resurfacing	SR 1943	BRIDGE	SR 1012	3.11	1.5" S9.5B	$450,000
2030	8	019-Chatham	Resurfacing	SR 1958	SR 2217	END PVMT	1.24	1.5" S9.5B	$200,000
2030	8	019-Chatham	Resurfacing	SR 1958	SR 1958	SR 2217	1.59	1.5" S9.5B	$250,000
2030	8	019-Chatham	Resurfacing	SR 1960	SR 1931	SR 1931	0.07	1.5" S9.5B	$10,000
2030	8	019-Chatham	Resurfacing	SR 1970	SR 1012	SR 1931	0.93	1.5" S9.5B	$133,419
2030	8	019-Chatham	Resurfacing	SR 1993	SR 1912	CUL DE SAC	0.27	1.5" S9.5B	$40,000
2030	8	019-Chatham	Resurfacing	SR 2120	US 421	SR 2170	2.50	1.5" S9.5B	$315,000
2030	8	019-Chatham	Resurfacing	SR 2176	NC 902	SR 1010	3.27	1.25" S9.5B	$490,950
2030	8	019-Chatham	Resurfacing	SR 2180	SR 2207	SR 2175	1.58	1.25" S9.5B	$237,000
2030	8	019-Chatham	Resurfacing	SR 2187	NC 902	SR 1010	3.44	1.25" S9.5B	$516,150
2030	8	019-Chatham	Resurfacing	SR 2188	SR 2142	SR 1010	2.31	1.25" SF9.5A	$320,000
2030	8	019-Chatham	Resurfacing	SR 2229	US 64	END MAINT	0.22	1.25" SF9.5A	$35,000
2030	8	019-Chatham	Resurfacing	SR 2301	SR 1176	SR 2300	1.21	Full Depth Patching and 1.25" S9.5B	$200,000
2030	8	019-Chatham	Resurfacing	US 64 BUS	US 64 WEST	US 15-501	3.49	Mill 1.5" and 1.5" S9.5B	$720,000
2030	8	019-Chatham	Resurfacing	US 64 EB	SR 2170	SR 1514	6.18	2.0" S9.5C	$1,235,000
2030	8	019-Chatham	Preservation	SR 1100	SR 1005	SR 1129	2.31	Seal - Double	$100,000
2030	8	019-Chatham	Preservation	SR 1108	BEG DIV HWY	SR 2113	0.03	Crack Seal	$1,000
2030	8	019-Chatham	Preservation	SR 1131	SR 1130	END MAINT	0.50	Crack Seal	$7,500
2030	8	019-Chatham	Preservation	SR 1168	SR 1107	DEAD END	0.38	Seal - Double	$11,000
2030	8	019-Chatham	Preservation	SR 1316	SR 1004	SR 1317	2.01	Crack Seal	$25,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	8	019-Chatham	Preservation	SR 1340	ALAM CO	SR1337	0.85	Seal - Double	$30,000
2030	8	019-Chatham	Preservation	SR 1357	END MAINT	SR 1346	0.70	Crack Seal	$10,000
2030	8	019-Chatham	Preservation	SR 1508	SR 1511	SR 1507	1.01	Seal - Double	$40,000
2030	8	019-Chatham	Preservation	SR 1941	SR 1700	END MAINT	0.88	Seal - Double	$35,000
2030	8	019-Chatham	Preservation	SR 2130	SR 2333	DEAD END	0.45	Seal - Double	$15,000
2030	8	019-Chatham	Preservation	SR 2131	SR 2213	SR 1010	0.18	Seal - Double	$5,500
2030	8	019-Chatham	Preservation	SR 2137	SR 2135	END MAINT	0.78	Seal - Double	$31,000
2030	8	019-Chatham	Preservation	SR 2145	RR XING	SR 2150	2.61	Seal - Double	$75,000
2030	8	019-Chatham	Preservation	SR 2153	SR 2142	SR 2155	1.85	Seal - Double	$80,000
2030	8	019-Chatham	Preservation	SR 2172	SR 2170	DEAD END	0.99	Seal - Double	$38,000
2030	8	019-Chatham	Preservation	SR 2180	SR 2207	SR 2175	1.58	Crack Seal	$20,000
2030	8	019-Chatham	Preservation	SR 2180	SR 2207	SR 2175	1.58	Seal - Double	$50,000
2030	8	019-Chatham	Preservation	SR 2184	SR 2187	DEAD END	0.50	Seal - Double	$15,000
2030	8	019-Chatham	Preservation	SR 2217	US 15-501	US 15-501	2.57	Seal - Double	$85,000
2030	8	019-Chatham	Preservation	SR 2231	SR 2113	DEAD END	0.84	Seal - Double	$30,000
2030	8	019-Chatham	Preservation	SR 2236	US 64	DEAD END	0.03	Seal - Double	$1,000
2030	8	019-Chatham	Preservation	SR 2303	SR 1009	NC 42	2.23	Seal - Double	$75,000
2030	8	019-Chatham	Preservation	SR 2314	SR 1009	SR 2303	1.21	Seal - Double	$40,000
2030	8	019-Chatham	Preservation	SR 2319	SR 2314	SR 2318	1.28	Seal - Double	$51,000
2030	8	019-Chatham	Preservation	SR 2319	SR 2314	SR 2318	1.28	Seal - Double	$40,000
2030	8	019-Chatham	Preservation	SR 2319	NC 42	SR 2314	1.15	Seal - Double	$45,000
2030	8	019-Chatham	Preservation	SR 2320	SR 2319	SR 2318	1.52	Seal - Double	$40,000
2030	8	019-Chatham	Preservation	SR 2330	SR 2314	END MAINT	0.42	Seal - Double	$13,000
2030	8	019-Chatham	Preservation	SR 2336	NC 42	SR 2306	1.48	Seal - Double	$40,000
2030	8	047-Hoke	Resurfacing	SR 1001	SR 1449	SR 1436	1.57	1.5" S9.5B	$244,510
2030	8	047-Hoke	Resurfacing	SR 1004	SR 1430	SR 1430	1.74	1.5" S9.5B	$268,820
2030	8	047-Hoke	Resurfacing	SR 1114	SR 1113	SR 1111	1.24	Full Depth Patching and 1.5" S9.5B	$220,000
2030	8	047-Hoke	Resurfacing	SR 1302	SR 1367	SR 1303	1.76	Full Depth Patching and 1.5" S9.5B	$301,537
2030	8	047-Hoke	Resurfacing	SR 1406	SR 1792	SR 1466 + .095	2.00	Full Depth Patching and 1.5" S9.5B	$444,000
2030	8	047-Hoke	Resurfacing	SR 1453	SR 1456	NC 20	1.36	1.5" S9.5B	$220,000
2030	8	047-Hoke	Resurfacing	US401	SR1661	US401 BUS	2.08	Mill 1.5" and 1.5" S9.5C	$505,000
2030	8	047-Hoke	Preservation	SR 1109	SR 1105	ROBESON COUNTY LINE	1.67	Full Depth Patching and Double Seal	$91,338
2030	8	047-Hoke	Preservation	SR 1113	SR 1118	SR 1116	1.40	Full Depth Patching and Double Seal	$80,200
2030	8	047-Hoke	Preservation	SR 1119	SR 1120	SR 1113	1.57	Full Depth Patching and Double Seal	$87,510
2030	8	047-Hoke	Preservation	SR 1211	SR 1212	SR 1216	0.95	Full Depth Patching and Double Seal	$63,000
2030	8	047-Hoke	Preservation	SR 1229	MOORE COUNTY	SR 1225	1.84	Full Depth Patching and Double Seal	$110,000
2030	8	047-Hoke	Preservation	SR 1416	SR 1413	SR 1415	1.34	Full Depth Patching and Double Seal	$77,620
2030	8	047-Hoke	Preservation	SR 1423	SR 1406	SR 1406	0.42	Full Depth Patching and Double Seal	$24,000
2030	8	053-Lee	Resurfacing	SR 1009	SR 1325	BEG C&G	1.56	Full Depth Patching and 1.5" S9.5A	$222,000
2030	8	053-Lee	Resurfacing	SR 1140	HARNETT CO	SR 1144	0.58	1.25" SF9.5A	$81,000
2030	8	053-Lee	Resurfacing	SR 1141	BEG PVMT	SR 1140	0.73	Full Depth Patching and 1.5" S9.5B	$143,000
2030	8	053-Lee	Resurfacing	SR 1160	SR 1144	SR 1001	1.76	1.5" S9.5B	$150,000
2030	8	053-Lee	Resurfacing	SR 1173	US 1	SR 1601	1.21	1.5" S9.5B	$285,000
2030	8	053-Lee	Resurfacing	SR 1178	SR 1144	SR 1144	0.16	1.25" SF9.5A	$22,000
2030	8	053-Lee	Resurfacing	SR 1179	SR 1144	US 1	4.47	Full Depth Patching and 1.5" S9.5B	$892,850
2030	8	053-Lee	Resurfacing	SR 1208	SR 1207	END MAINT	0.10	1.0" S9.5A	$14,750
2030	8	053-Lee	Resurfacing	SR 1225	PVMT CHG	SR 1236	0.09	1.25" SF9.5A	$14,750
2030	8	053-Lee	Resurfacing	SR 1263	SR 1131	HIWATHA TR	0.52	1.5" S9.5B	$78,000
2030	8	053-Lee	Resurfacing	SR 1288	SR 1117	MP .05	0.05	1.5" S9.5B	$7,500
2030	8	053-Lee	Resurfacing	SR 1295	SR 1144	CUL DE CAS	0.51	1.25" SF9.5A	$78,000
2030	8	053-Lee	Resurfacing	SR 1309	SR 1305	SR 1313	1.46	Full Depth Patching and 1.5" S9.5B	$250,000
2030	8	053-Lee	Resurfacing	SR 1332	SR 1334	SR 1305	2.47	Full Depth Patching and 1.5" S9.5B	$350,000
2030	8	053-Lee	Resurfacing	SR 1405	PVMT CHG	SR 1406	0.65	Full Depth Patching and 1.5" S9.5B	$165,000
2030	8	053-Lee	Resurfacing	SR 1406	SR 1466	SR 1422	1.89	1.5" S9.5B	$280,000
2030	8	053-Lee	Resurfacing	SR 1419	SR 1415	SR 1418	0.54	Full Depth Patching and 1.5" S9.5B	$92,000
2030	8	053-Lee	Resurfacing	SR 1467	US 15	DEAD END	0.11	Full Depth Patching and 1.5" S9.5A	$14,000
2030	8	053-Lee	Resurfacing	SR 1472	SR 1466	SR 1466	0.43	Full Depth Patching and 1.5" S9.5B	$56,000
2030	8	053-Lee	Resurfacing	SR 1477	SR 1476	CUL DE SAC	0.26	1.25" SF9.5A	$36,000
2030	8	053-Lee	Resurfacing	SR 1500	SR 1538	SR 1538	2.81	Full Depth Patching and 1.5" S9.5B	$375,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	8	053-Lee	Resurfacing	US 1	SR 1157 + .656 MILES	SR 1333	1.48	Mill 3.0" and 3.0" S9.5C	$416,000
2030	8	053-Lee	Resurfacing	US 1	SR 1181 + .116 MILES	US 15	1.22	Mill 1.5" and 1.5" S9.5C	$239,899
2030	8	053-Lee	Resurfacing	US 15	SR 1456	CHATHAM CO	1.78	Mill 1.5" and 1.5" S9.5C	$399,500
2030	8	053-Lee	Resurfacing	US1	MOORE COUNTY	US 1 SOUTH	1.80	Mill 1.5" and 1.5" S9.5C	$330,000
2030	8	053-Lee	Resurfacing	US1	US 1 SOUTH	US 1 BUS	1.00	Mill 1.5" and 1.5" S9.5C	$270,000
2030	8	053-Lee	Resurfacing	US1	US 1 BUS SOUTH	US 1	0.99	Mill 1.5" and 1.5" S9.5C	$268,000
2030	8	053-Lee	Resurfacing	US1	SR 1600 + .478 MILES	US 1 SOUTH	0.52	Mill 1.5" and 1.5" S9.5C	$173,000
2030	8	053-Lee	Preservation	SR 1131	SR 1	SR 1211	0.88	Seal - Double	$33,450
2030	8	053-Lee	Preservation	SR 1161	SR 1156	SR 1215	0.42	Seal - Double	$16,250
2030	8	053-Lee	Preservation	SR 1176	SR 1179	SR 1174	0.48	Seal - Double	$18,250
2030	8	053-Lee	Preservation	SR 1192	US 1 SOUTH	END MAINT	0.09	Seal - Double	$3,275
2030	8	053-Lee	Preservation	SR 1309	SR 1305	SR 1313	1.46	Seal - Double	$55,500
2030	8	053-Lee	Preservation	SR 1317	SR 1007	END MAINT	0.58	Seal - Double	$22,500
2030	8	053-Lee	Preservation	SR 1384	US 421	CUL DE SAC	0.98	Seal - Double	$38,500
2030	8	053-Lee	Preservation	SR 1474	SR 1472	DEAD END	0.04	Seal - Single	$1,500
2030	8	053-Lee	Preservation	SR 1579	LANE CHG	END C&G	3.63	Seal - Double	$231,480
2030	8	053-Lee	Preservation	SR 1589	SR 1514	SR 1590	0.11	Seal - Double	$4,025
2030	8	053-Lee	Preservation	US 1	SR 1002	SR 1420	4.79	Crack Seal	$60,020
2030	8	062-Montgomery	Resurfacing	NC 109	SR 1153 + 1.008 miles	Randolph County	4.90	1.5" S9.5B	$966,300
2030	8	062-Montgomery	Resurfacing	NC 24	SR 1554 + 1.123 mi	NC 27 South	0.04	1.5" S9.5B	$11,000
2030	8	062-Montgomery	Resurfacing	NC 24	SR 1554 + 1.123 mi	NC 27 South	0.37	1.5" S9.5B	$101,000
2030	8	062-Montgomery	Resurfacing	NC 24	SR 1554 + 1.123 mi	NC 27 South	0.08	1.5" S9.5B	$22,000
2030	8	062-Montgomery	Resurfacing	NC 73	SR 1174	NC 24/27	4.32	1.5" S9.5B	$1,000,000
2030	8	062-Montgomery	Resurfacing	SR 1134	SR 1134	SR 1310	1.02	1.5" S9.5B	$145,000
2030	8	062-Montgomery	Resurfacing	SR 1150	SR 1182	NC 24/27	2.91	1.5" S9.5B	$504,088
2030	8	062-Montgomery	Resurfacing	SR 1354	Randolph Co	SR 1349	0.51	1.5" S9.5B	$95,000
2030	8	062-Montgomery	Resurfacing	SR 1408	US 220A	END OF PVT	0.40	1.5" S9.5B	$75,000
2030	8	062-Montgomery	Resurfacing	US 220 ALT SB	US 220 ALT	US 220 ALT	0.18	Mill 1.5" and 1.5" S9.5B	$82,000
2030	8	062-Montgomery	Preservation	SR 1146	SR 1134	SR 1147	1.33	Seal - Double	$59,000
2030	8	062-Montgomery	Preservation	SR 1352	SR 1311	SR 1340	2.00	Seal - Double	$89,000
2030	8	062-Montgomery	Preservation	SR 1511	US 220 ALT	Dead End	0.96	Seal - Double and Fog Seal	$50,000
2030	8	062-Montgomery	Preservation	SR 1512	SR 1582	NS 99144	0.27	Seal - Double and Fog Seal	$12,000
2030	8	062-Montgomery	Preservation	SR 1513	SR 1512	Dead End	0.20	Seal - Double and Fog Seal	$10,000
2030	8	062-Montgomery	Preservation	SR 1537	SR 1536	Dead End	0.57	Seal - Double	$25,000
2030	8	062-Montgomery	Preservation	SR 1564	SR 1005	SR 1565	2.11	Seal - Double	$88,245
2030	8	062-Montgomery	Preservation	SR 1565	SR 1543	SR 1005	0.48	Seal - Double	$21,000
2030	8	062-Montgomery	Preservation	SR 1566	SR 1565	Dead End	1.00	Seal - Double	$44,000
2030	8	062-Montgomery	Preservation	SR 1569	SR 1568	SR 1568	0.83	Seal - Double	$36,000
2030	8	062-Montgomery	Preservation	SR 1581	SR 1511	SR 1582	0.20	Seal - Double and Fog Seal	$14,000
2030	8	062-Montgomery	Preservation	SR 1582	NC 211	SR-1581	0.69	Seal - Double and Fog Seal	$33,000
2030	8	062-Montgomery	Preservation	SR 1602	DEAD END	NS-99114	0.39	Seal - Double and Fog Seal	$23,000
2030	8	063-Moore	Resurfacing	SR 1102	US 1	BRIDGE	3.40	1.5" S9.5B	$473,470
2030	8	063-Moore	Resurfacing	SR 1122	SR 1169	BRIDGE	2.36	1.25" S4.75A	$395,172
2030	8	063-Moore	Resurfacing	SR 1125	SR 1126	NC 73	0.60	1.5" S9.5A	$74,785
2030	8	063-Moore	Resurfacing	SR 1126	SR 1137	SR 1125	3.01	1.5" S9.5A	$377,061
2030	8	063-Moore	Resurfacing	SR 1229	SR 1227	SR 1224	6.42	1.5" S9.5B	$780,000
2030	8	063-Moore	Resurfacing	SR 1234	NC 211	SR 1237	0.29	1.0" S9.5A	$21,000
2030	8	063-Moore	Resurfacing	SR 1274	SR 1304	NC 211	0.30	1.5" S9.5A	$52,000
2030	8	063-Moore	Resurfacing	SR 1275	NC 211	SR 1138	6.50	1.5" S9.5A	$488,081
2030	8	063-Moore	Resurfacing	SR 1275	SR 1278	NC 211	1.80	1.5" S9.5A	$282,000
2030	8	063-Moore	Resurfacing	SR 1322	SR 1261	DEAD END	0.47	1.0" S9.5A	$31,000
2030	8	063-Moore	Resurfacing	SR 1638	SR 1679	SR 1629	1.78	1.5" S9.5A	$262,250
2030	8	063-Moore	Resurfacing	SR 1802	NC 24	SR 1803	0.92	1.5" S9.5A	$128,000
2030	8	063-Moore	Resurfacing	SR 1805	CRAIN CRK	SR 1829	1.91	1.5" S9.5B	$296,000
2030	8	063-Moore	Resurfacing	SR 1825	PVMT CHG	US 1 BUS	0.18	1.5" S9.5A	$27,500
2030	8	063-Moore	Resurfacing	SR 1861	SR 1803	PVMT CHG	0.43	1.5" S9.5A	$80,000
2030	8	063-Moore	Resurfacing	SR 1950	SR 1840	SR 1908	0.15	1.5" S9.5A	$24,570
2030	8	063-Moore	Resurfacing	SR 2017	HARNETT CO	NC 690	2.36	1.5" S9.5A	$251,000
2030	8	063-Moore	Resurfacing	SR 2054	SR 2132	END MAINT	0.20	1.0" S9.5B	$24,700

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	8	063-Moore	Resurfacing	SR 2194	PVMT CHG	SR 2002	0.39	1.25" SF9.5A	$60,000
2030	8	063-Moore	Resurfacing	US 1 BUS	SR 1826	SR 1821 + .37	0.22	Mill 1.5" and 1.5" S9.5B	$49,725
2030	8	063-Moore	Resurfacing	US 1 BUS	SR 1821 +.37	LEE CO	0.93	Mill 1.5" and 1.5" S9.5B	$205,250
2030	8	063-Moore	Resurfacing	US 1 S	SR 2026	SR 1857	0.59	Mill 1.5" and 1.5" S9.5C	$100,000
2030	8	063-Moore	Resurfacing	US 15	NC 24	SR 1656	1.50	Mill 1.5" and 1.5" S9.5C	$383,000
2030	8	063-Moore	Resurfacing	US 15	SR 1656	LEE CO	3.87	Mill 1.5" and 1.5" S9.5C	$792,530
2030	8	063-Moore	Resurfacing	US 1NB	SR 2118	SR 1112	6.27	Mill 1.5" and 1.5" S9.5C	$1,671,900
2030	8	063-Moore	Preservation	SR 1004	SR 1113	SR 1112	4.03	Crack Seal and Double Seal	$119,520
2030	8	063-Moore	Preservation	SR 1105	SR 1104	SR 1103	2.82	Seal - Double	$93,533
2030	8	063-Moore	Preservation	SR 1105	RR	SR 1104	2.12	Seal - Double	$78,211
2030	8	063-Moore	Preservation	SR 1126	MONT CO	SR 1137	1.42	Seal - Double	$48,950
2030	8	063-Moore	Preservation	SR 1171	US 1	DEAD END	0.49	Seal - Double	$15,650
2030	8	063-Moore	Preservation	SR 1216	SR 1210	NC 211	3.86	Seal - Double	$156,382
2030	8	063-Moore	Preservation	SR 1221	SR 1209	DEAD END	0.32	Seal - Double	$9,750
2030	8	063-Moore	Preservation	SR 1245	SR 1240	SR 1246	0.66	Seal - Double	$27,060
2030	8	063-Moore	Preservation	SR 1248	SR 1252	SR 1249	0.99	Crack Seal and Double Seal	$41,950
2030	8	063-Moore	Preservation	SR 1249	SR 1248	SR 1250	0.71	Seal - Double	$28,750
2030	8	063-Moore	Preservation	SR 1250	SR 1252	SR 1251	1.37	Seal - Double	$44,500
2030	8	063-Moore	Preservation	SR 1273	END PVMT	NC 705	0.95	Seal - Double	$35,850
2030	8	063-Moore	Preservation	SR 1409	NC 705	SR 1418	4.83	Crack Seal and Double Seal	$175,235
2030	8	063-Moore	Preservation	SR 1412	SR 1414	RANDOLPH CO	3.73	Crack Seal and Double Seal	$72,350
2030	8	063-Moore	Preservation	SR 1419	SR 1459	SR 1456	5.97	Seal - Double	$219,935
2030	8	063-Moore	Preservation	SR 1432	SR 1425	SR 1002	1.29	Seal - Double	$48,500
2030	8	063-Moore	Preservation	SR 1432	SR 1002	DEAD END	0.70	Seal - Double	$25,525
2030	8	063-Moore	Preservation	SR 1458	SR 1003	SR 1419	1.23	Seal - Double	$51,000
2030	8	063-Moore	Preservation	SR 1519	SR 1405	SR 1405 + .893	0.89	Seal - Double	$32,250
2030	8	063-Moore	Preservation	SR 1605	CHATHAM CO.	SR 1600	0.93	Seal - Double	$28,500
2030	8	063-Moore	Preservation	SR 1880	NC 24	US 15	0.40	Seal - Double	$15,750
2030	8	063-Moore	Preservation	SR 2184	SR 2162	SR 2075	0.65	Crack Seal and Double Seal	$29,725
2030	8	076-Randolph	Resurfacing	I-73 NBL	SR 1138 Dawson Miller Rd.	Pavement Jt. of US 64 Bypass	1.65	1.5" S9.5C	$700,000
2030	8	076-Randolph	Resurfacing	I-73 SBL	Pavement Jt. of US 64 Bypass	SR 1138 Dawson Miller Rd.	1.67	1.5" S9.5C	$700,000
2030	8	076-Randolph	Resurfacing	NC 159	US 220 ALT	MM 2.81 @ Roundabout	2.81	#67 Mat Seal and 1.5" S9.5C	$590,000
2030	8	076-Randolph	Resurfacing	NC 49	MM 34.5	MM 38.13	3.63	Full Depth Patching and 1.5" S9.5C	$820,000
2030	8	076-Randolph	Resurfacing	SR 1003	Bridge	US 64	9.75	1.5" S9.5B	$1,552,000
2030	8	076-Randolph	Resurfacing	SR 1114	SR 1248	SR 1248+2.515 Miles	2.52	Seal - Single and 1.5" S9.5B	$325,000
2030	8	076-Randolph	Resurfacing	SR 1115	NC 134	SR 1188	1.76	1.25" S9.5B	$232,000
2030	8	076-Randolph	Resurfacing	SR 1121	US 220 ALT	SR 1118	4.87	1.5" S9.5B	$755,000
2030	8	076-Randolph	Resurfacing	SR 1123	SR 1127	DEAD END.	0.87	Seal - Single and 1.5" S9.5B	$95,000
2030	8	076-Randolph	Resurfacing	SR 1143	SR 1175	SR 1181	1.50	1.5" S9.5B	$235,000
2030	8	076-Randolph	Resurfacing	SR 1172	SR 1171	NC 49	0.97	1.25" SF9.5A	$125,000
2030	8	076-Randolph	Resurfacing	SR 1188	MONTGOMERY COUNTY	SR 1119	1.34	Seal - Single and 1.5" S9.5B	$141,000
2030	8	076-Randolph	Resurfacing	SR 1237	SR 1200	SR 1238	0.30	Full Depth Patching and 1.25" S9.5A	$35,000
2030	8	076-Randolph	Resurfacing	SR 1244	SR 1150	End Maint	0.09	Mill 1.25" and 1.25" S9.5A	$11,000
2030	8	076-Randolph	Resurfacing	SR 1313	SR 1312	CUL DE SAC	0.40	1.5" S9.5B	$61,000
2030	8	076-Randolph	Resurfacing	SR 1339	SR 1340	SR 1311	1.47	Full Depth Patching and 1.25" S9.5B	$219,900
2030	8	076-Randolph	Resurfacing	SR 1344	DAVIDSON COUNTY	US 64	3.12	1.25" SF9.5A	$247,000
2030	8	076-Randolph	Resurfacing	SR 1352	NC 49	US 64	0.51	Full Depth Patching and 1.25" S9.5A	$60,000
2030	8	076-Randolph	Resurfacing	SR 1372	PAVEMENT CHANGE	END PAVEMENT	0.26	1.5" S9.5B	$32,000
2030	8	076-Randolph	Resurfacing	SR 1410	US 64	US 64	1.67	Seal - Single and 1.5" S9.5B	$214,500
2030	8	076-Randolph	Resurfacing	SR 1463	Pvmt Change	End Maint	0.30	Full Depth Patching and 1.5" S9.5A	$34,000
2030	8	076-Randolph	Resurfacing	SR 1536	PAVEMENT CHANGE	DEAD END	0.17	1.25" SF9.5A	$15,000
2030	8	076-Randolph	Resurfacing	SR 1547	SR 1404	SR 1405	0.79	1.5" S9.5B	$118,200
2030	8	076-Randolph	Resurfacing	SR 1549	SR 1406	SR 1636	1.23	Seal - Single and 1.5" S9.5B	$135,000
2030	8	076-Randolph	Resurfacing	SR 1570	SR 1004	US 311	1.17	1.25" SF9.5A	$113,000
2030	8	076-Randolph	Resurfacing	SR 1619	BEGIN MAINTENANCE	SR 1618	0.76	1.5" S9.5C	$87,000
2030	8	076-Randolph	Resurfacing	SR 1631	SR 1619	SR 1627	0.51	1.25" SF9.5A	$45,000
2030	8	076-Randolph	Resurfacing	SR 1916	GUILFORD COUNTY	SR 1917 SUITS RD.	1.89	Full Depth Patching and 1.5" S9.5B	$359,100
2030	8	076-Randolph	Resurfacing	SR 1922	GUILFORD COUNTY	SR 1928	2.71	Crack Seal and 1.5" S9.5B	$250,000
2030	8	076-Randolph	Resurfacing	SR 1926	Guilford Co	SR 1921	1.44	1.25" SF9.5A	$111,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	8	076-Randolph	Resurfacing	SR 1944	PAVEMENT CHANGE	PAVEMENT CHANGE	0.50	1.25" SF9.5A	$52,000
2030	8	076-Randolph	Resurfacing	SR 1944	US 311	SR 1926	3.58	1.5" S9.5B	$537,000
2030	8	076-Randolph	Resurfacing	SR 1950	BEGIN MAINTENANCE	SR 1952	0.42	Crack Seal and 1.5" S9.5B	$55,000
2030	8	076-Randolph	Resurfacing	SR 1990	SR 1936	WIDTH CHANGE	0.24	1.5" S9.5B	$22,000
2030	8	076-Randolph	Resurfacing	SR 1991	DEAD END	DEAD END	0.60	1.5" S9.5B	$74,550
2030	8	076-Randolph	Resurfacing	SR 1991	DEAD END	SR 1951	0.30	Full Depth Patching and 1.25" S9.5A	$31,000
2030	8	076-Randolph	Resurfacing	SR 1996	SR 1995	SR 1995	0.31	Full Depth Patching and 1.25" S9.5A	$36,000
2030	8	076-Randolph	Resurfacing	SR 2025	SR 1944	CUL DE SAC	0.25	Full Depth Patching and 1.25" S9.5A	$29,000
2030	8	076-Randolph	Resurfacing	SR 2029	SR 2028	CUL DE SAC	0.08	Full Depth Patching and 1.25" S9.5A	$9,000
2030	8	076-Randolph	Resurfacing	SR 2049	SR 1939	CUL DE SAC	0.33	1.25" SF9.5A	$29,000
2030	8	076-Randolph	Resurfacing	SR 2057	SR 1547	SR 2058	0.09	1.25" SF9.5A	$8,000
2030	8	076-Randolph	Resurfacing	SR 2058	SR 2057	CUL DE SAC	0.17	1.25" SF9.5A	$15,000
2030	8	076-Randolph	Resurfacing	SR 2060	SR 1408	END MAINTENANCE	0.21	1.25" SF9.5A	$18,000
2030	8	076-Randolph	Resurfacing	SR 2073	CUL-DE-SAC	SR 1990	1.02	Mill 1.25" and 1.25" S9.5B	$223,000
2030	8	076-Randolph	Resurfacing	SR 2075	SR 1525	CUL DE SAC	0.09	1.25" SF9.5A	$8,000
2030	8	076-Randolph	Resurfacing	SR 2108	SR 2116 NEW SALEM RD.	SR 2106 RACCINE RD.	3.11	Full Depth Patching and 1.5" S9.5B	$590,900
2030	8	076-Randolph	Resurfacing	SR 2122	US 220 BUS	SR 2128	1.44	1.5" S9.5C	$134,000
2030	8	076-Randolph	Resurfacing	SR 2140	SR 2138	NC 22	1.60	Full Depth Patching and 1.25" S9.5B	$211,000
2030	8	076-Randolph	Resurfacing	SR 2182	US 220 BUS	SR 2184	0.40	1.25" SF9.5A	$43,000
2030	8	076-Randolph	Resurfacing	SR 2197	NC 42	US 64	0.57	Crack Seal and 1.5" S9.5B	$56,000
2030	8	076-Randolph	Resurfacing	SR 2213	US 64	US 64	0.55	1.5" S9.5B	$82,500
2030	8	076-Randolph	Resurfacing	SR 2215	SR 2218	SR 2374 + .17 MILES	1.03	1.5" S9.5B	$149,000
2030	8	076-Randolph	Resurfacing	SR 2234	SR 2236	SR 2122	0.47	1.5" S9.5B	$43,000
2030	8	076-Randolph	Resurfacing	SR 2240	SR 2138	SR 2132	1.41	1.5" S9.5B	$175,161
2030	8	076-Randolph	Resurfacing	SR 2297	SR 2114	CUL DE SAC	0.25	1.25" SF9.5A	$22,000
2030	8	076-Randolph	Resurfacing	SR 2312	SR 2150	SR 2331	0.65	1.5" S9.5B	$57,000
2030	8	076-Randolph	Resurfacing	SR 2322	SR 2106	CUL DE SAC	0.28	1.5" S9.5B	$33,000
2030	8	076-Randolph	Resurfacing	SR 2335	SR 2334	DEAD END	0.19	1.5" S9.5B	$22,000
2030	8	076-Randolph	Resurfacing	SR 2358	SR 2132	SR 2132	0.73	1.5" S9.5B	$85,000
2030	8	076-Randolph	Resurfacing	SR 2363	SR 2122	CUL DE SAC	0.37	1.5" S9.5B	$43,000
2030	8	076-Randolph	Resurfacing	SR 2364	SR 2108	CUL DE SAC	0.20	1.5" S9.5B	$18,000
2030	8	076-Randolph	Resurfacing	SR 2437	SR 2438	SR 2459	1.37	1.5" S9.5B	$171,435
2030	8	076-Randolph	Resurfacing	SR 2442	SR 2479	NC 49	1.67	1.5" S9.5B	$162,000
2030	8	076-Randolph	Resurfacing	SR 2458	SR 2459	SR 2459 +1.499 MILES	1.50	Full Depth Patching and 1.25" S9.5B	$197,000
2030	8	076-Randolph	Resurfacing	SR 2510	SR 2511	DEAD END	0.10	1.5" S9.5B	$8,000
2030	8	076-Randolph	Resurfacing	SR 2552	SR 1006	DEAD END	0.20	1.5" S9.5B	$21,000
2030	8	076-Randolph	Resurfacing	SR 2555	US 64	END PAVEMENT	0.14	1.5" S9.5B	$14,000
2030	8	076-Randolph	Resurfacing	SR 2607	SR 1003	SR 2691	1.47	1.5" S9.5B	$130,000
2030	8	076-Randolph	Resurfacing	SR 2609	SR 2610	SR 2610 + 1.032 MILES	1.03	Full Depth Patching and 1.25" S9.5B	$136,000
2030	8	076-Randolph	Resurfacing	SR 2614	SR 2611	NC 42	2.93	1.5" S9.5B	$297,000
2030	8	076-Randolph	Resurfacing	SR 2628	SR 2723	SR 2642	1.66	Full Depth Patching and 1.5" S9.5B	$197,000
2030	8	076-Randolph	Resurfacing	SR 2628	US 64	SR 2823	1.63	Full Depth Patching and 1.25" S9.5B	$215,000
2030	8	076-Randolph	Resurfacing	SR 2661	SR 2607	CUL DE SAC	0.66	1.5" S9.5B	$77,000
2030	8	076-Randolph	Resurfacing	SR 2834	SR 2830	NC 159	0.28	1.5" S9.5B	$24,331
2030	8	076-Randolph	Resurfacing	SR 2834	SR 2830	NC 159	1.29	1.5" S9.5B	$114,074
2030	8	076-Randolph	Resurfacing	SR 2845	NC 42	SR 2909	1.82	1.5" S9.5B	$203,000
2030	8	076-Randolph	Resurfacing	SR 2866	Moore County Rd	SR 1003	4.14	1.5" S9.5B	$592,020
2030	8	076-Randolph	Resurfacing	SR 2882	NC 22	SR 2876	1.34	Seal - Single and 1.5" S9.5B	$147,000
2030	8	076-Randolph	Resurfacing	SR 2903	SR 2904	PAVEMENT CHANGE	0.46	1.5" S9.5B	$47,000
2030	8	076-Randolph	Resurfacing	SR 2909	SR 2905	SR 2903	1.23	Seal - Split and 1.5" S9.5B	$135,000
2030	8	076-Randolph	Resurfacing	SR 2958	US 220 ALT	BIRDIE PL	0.60	1.5" S9.5B	$70,000
2030	8	076-Randolph	Resurfacing	SR 3106	SR 1408	SR 3129	1.34	1.5" S9.5B	$118,000
2030	8	076-Randolph	Resurfacing	SR 3161	SR 1549	DEAD END	0.60	Full Depth Patching and 1.25" S9.5B	$78,000
2030	8	076-Randolph	Resurfacing	US 220 BUS	NC 42 (Salisbury St.)	E. Beasley St.	2.26	Mill 1.5" and 1.5" S9.5C	$850,000
2030	8	076-Randolph	Preservation	SR 1102	SR-1181 New Hope Rd	SR-1103 Volunteer Rescue Rd	1.94	Full Depth Patching and Double Seal	$120,000
2030	8	076-Randolph	Preservation	SR 1111	SR 1112 Lanier Rd.	SR 1112 Abner Rd.	3.39	Full Depth Patching and Double Seal	$245,000
2030	8	076-Randolph	Preservation	SR 1113	SR 1114 Pisgah Covered Bridge Rd.	Dead End	1.00	Full Depth Patching and Double Seal and Fog Seal	$80,000
2030	8	076-Randolph	Preservation	SR 1125	SR 1119 Little River Rd.	Dead End	1.75	Full Depth Patching and Double Seal	$120,000
2030	8	076-Randolph	Preservation	SR 1160	Begin Pavement	End Maintenance	0.85	Full Depth Patching and Double Seal and Fog Seal	$65,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	8	076-Randolph	Preservation	SR 1173	SR 1174 Waynick Meadow Rd.	NC 49	0.69	Full Depth Patching and Double Seal	$55,000
2030	8	076-Randolph	Preservation	SR 1199	SR 1163 Tot Hill Farm Rd.	Dead End	0.63	Full Depth Patching and Double Seal and Fog Seal	$50,000
2030	8	076-Randolph	Preservation	SR 1210	NC 49	Dead End	0.21	Full Depth Patching and Double Seal and Fog Seal	$18,000
2030	8	076-Randolph	Preservation	SR 1231	NC 49	SR 1251 Scaleybark Ln.	0.58	Full Depth Patching and Double Seal and Fog Seal	$42,000
2030	8	076-Randolph	Preservation	SR 1236	SR 1160 Billy Walker Rd.	Dead End	0.18	Full Depth Patching and Double Seal and Fog Seal	$15,000
2030	8	076-Randolph	Preservation	SR 1238	SR 1163 Tot Hill Farm Rd.	Dead End	0.13	Full Depth Patching and Double Seal and Fog Seal	$11,000
2030	8	076-Randolph	Preservation	SR 1251	Begin Maintenance	Dead End	0.27	Full Depth Patching and Double Seal and Fog Seal	$22,000
2030	8	076-Randolph	Preservation	SR 1260	NC 49	Dead End	0.52	Full Depth Patching and Double Seal	$40,000
2030	8	076-Randolph	Preservation	SR 1261	SR 1251 Scaleybark Ln.	Dead End	0.23	Full Depth Patching and Double Seal and Fog Seal	$18,500
2030	8	076-Randolph	Preservation	SR 1271	NC 49	Dead End	0.11	Full Depth Patching and Double Seal and Fog Seal	$10,000
2030	8	076-Randolph	Preservation	SR 1272	Begin Maintenance	Ashworth View Dr.	0.52	Full Depth Patching and Triple Seal and Fog Seal	$35,000
2030	8	076-Randolph	Preservation	SR 1301	NC 47	SR 1303 Brantley Gordon Rd.	1.84	Full Depth Patching and Double Seal	$125,000
2030	8	076-Randolph	Preservation	SR 1323	US 64	NC 49	0.35	Full Depth Patching and Double Seal and Fog Seal	$25,000
2030	8	076-Randolph	Preservation	SR 1352	NC 49	US 64	0.51	Full Depth Patching and Double Seal and Fog Seal	$35,000
2030	8	076-Randolph	Preservation	SR 1353	SR 1352 Westbury Rd.	Dead End	0.05	Full Depth Patching and Double Seal and Fog Seal	$5,000
2030	8	076-Randolph	Preservation	SR 1354	SR 1352 Westbury Rd.	Dead End	0.12	Full Depth Patching and Double Seal and Fog Seal	$8,500
2030	8	076-Randolph	Preservation	SR 1355	SR 1354 Cranbrook Way	SR 1356 Cranbrook Cir.	0.13	Full Depth Patching and Double Seal and Fog Seal	$10,000
2030	8	076-Randolph	Preservation	SR 1356	SR 1352 Westbury Rd.	SR 1355 Cranbrook Cir.	0.09	Full Depth Patching and Double Seal and Fog Seal	$6,000
2030	8	076-Randolph	Preservation	SR 1367	NC 49	Dead End	0.36	Full Depth Patching and Double Seal and Fog Seal	$27,500
2030	8	076-Randolph	Preservation	SR 1368	NC 49	Dead End	0.55	Full Depth Patching and Double Seal and Fog Seal	$42,000
2030	8	076-Randolph	Preservation	SR 1373	NC 49	Dead End	0.41	Full Depth Patching and Double Seal and Fog Seal	$30,000
2030	8	076-Randolph	Preservation	SR 1377	SR 1373 McDaniel Dr.	Dead End	0.16	Full Depth Patching and Double Seal and Fog Seal	$15,000
2030	8	076-Randolph	Preservation	SR 1378	SR 1381 Woodlane Ct.	Dead End	0.51	Full Depth Patching and Double Seal and Fog Seal	$36,500
2030	8	076-Randolph	Preservation	SR 1379	SR 1368 Taylors Creek Dr.	Dead End	0.13	Full Depth Patching and Double Seal and Fog Seal	$12,000
2030	8	076-Randolph	Preservation	SR 1380	SR 1368 Taylors Creek Rd.	Dead End	0.44	Full Depth Patching and Double Seal and Fog Seal	$35,000
2030	8	076-Randolph	Preservation	SR 1381	SR 1380 Shaw St.	Dead End	0.15	Full Depth Patching and Double Seal and Fog Seal	$13,000
2030	8	076-Randolph	Preservation	SR 1388	SR 1378 CreekridgeDr.	Dead End	0.10	Full Depth Patching and Double Seal and Fog Seal	$10,000
2030	8	076-Randolph	Preservation	SR 1399	NC 49	Dead End	0.30	Full Depth Patching and Double Seal and Fog Seal	$25,000
2030	8	076-Randolph	Preservation	SR 1547 FULLER MILL RD N.	DAVIDSON COUNTY	SR 1547 FINCH FARM RD.	3.61	Seal - Double and Fog Seal	$130,000
2030	8	076-Randolph	Preservation	SR 2121	SR 2122 Worthville Rd.	Dead End	0.19	Full Depth Patching and Double Seal and Fog Seal	$15,000
2030	8	076-Randolph	Preservation	SR 2125	SR 2122 Worthville Rd.	SR 2123 Caudle Rd.	0.95	Full Depth Patching and Double Seal and Fog Seal	$70,000
2030	8	076-Randolph	Preservation	SR 2129	SR 2122 Worthville Rd.	Dead Ende	0.23	Full Depth Patching and Double Seal and Fog Seal	$15,000
2030	8	076-Randolph	Preservation	SR 2244	US 220 BUS	Blue Violet Dr.	0.46	Full Depth Patching and Double Seal and Fog Seal	$35,000
2030	8	076-Randolph	Preservation	SR 2268	SR 2244 Forest Dr.	SR 2123 Caudle Rd.	0.34	Full Depth Patching and Double Seal and Fog Seal	$26,000
2030	8	076-Randolph	Preservation	SR 2290	SR 2244 Forest Dr.	SR 2123 Caudle Rd.	0.33	Full Depth Patching and Double Seal and Fog Seal	$25,000
2030	8	076-Randolph	Preservation	SR 2299	SR 2122 Worthville Rd.	Dead End	0.36	Full Depth Patching and Double Seal and Fog Seal	$25,000
2030	8	076-Randolph	Preservation	SR 2300	Begin Maint.	Dead End	0.13	Full Depth Patching and Double Seal and Fog Seal	$10,000
2030	8	076-Randolph	Preservation	SR 2301	SR 2122 Worthville Rd.	Dead End	0.26	Full Depth Patching and Double Seal and Fog Seal	$17,500
2030	8	076-Randolph	Preservation	SR 2307	SR 2244 Forest Dr.	SR 2123 Caudle Rd.	0.33	Full Depth Patching and Double Seal and Fog Seal	$25,000
2030	8	076-Randolph	Preservation	SR 3304	SR 1373 McDaniel Dr.	Dead End	0.14	Full Depth Patching and Double Seal and Fog Seal	$15,000
2030	8	077-Richmond	Resurfacing	NC 177	SC	US 74 bus	7.60	1.5" S9.5B	$1,300,000
2030	8	077-Richmond	Resurfacing	NC 73 W	Mont Co	Us 220 bus	12.00	1.5" S9.5B	$1,900,000
2030	8	077-Richmond	Resurfacing	SR 1322	SR 1005	SR 1005	5.80	1.5" S9.5B	$650,000
2030	8	077-Richmond	Resurfacing	SR 1442	US 1	Bridge	2.20	1.5" S9.5B	$350,000
2030	8	077-Richmond	Resurfacing	SR 1452	US 220 Bus	SR1424	4.80	1.5" S9.5B	$870,000
2030	8	077-Richmond	Preservation	Sr 1125	SR 1124	US 74	0.83	Seal - Double	$30,000
2030	8	077-Richmond	Preservation	SR 1127	SR 1125	End Maint	0.06	Seal - Double	$2,000
2030	8	077-Richmond	Preservation	SR 1142	SR 1141	SR 1005	2.90	Seal - Double	$85,000
2030	8	077-Richmond	Preservation	SR 1300	SR 1005	Sr 1335	0.12	Seal - Double	$4,000
2030	8	077-Richmond	Preservation	SR 1305	Dead end	US 220	3.30	Seal - Double	$110,000
2030	8	077-Richmond	Preservation	SR 1310	SR 1309	NC 73	3.47	Seal - Double	$85,000
2030	8	077-Richmond	Preservation	SR 1443	SR 1424	SR1441	1.00	Seal - Double	$30,000
2030	8	077-Richmond	Preservation	Sr 1448	SR 1446	SR 1450	1.50	Seal - Double	$50,000
2030	8	077-Richmond	Preservation	SR 1453	Pavt change	I-74	2.90	Seal - Double	$95,000
2030	8	077-Richmond	Preservation	SR 1479	US 1	end	0.05	Seal - Double	$2,500
2030	8	077-Richmond	Preservation	SR 1544	SR 1504	SR 1545	0.40	Seal - Double	$11,000
2030	8	077-Richmond	Preservation	SR 1561	SR 1511	US 1	0.50	Seal - Double	$30,000
2030	8	077-Richmond	Preservation	SR 1604	SR1001	SR 1694	0.90	Seal - Double	$25,000
2030	8	077-Richmond	Preservation	SR 1694	SR 1001	Dead end	0.70	Seal - Double	$19,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	8	077-Richmond	Preservation	SR 1704	NC 177	SR 1614	0.44	Seal - Double	$14,000
2030	8	077-Richmond	Preservation	SR 1811	SR 1825	SR 1615	1.70	Seal - Double	$60,000
2030	8	077-Richmond	Preservation	SR 1916	SR 1903	SR 2074	0.23	Seal - Double	$8,000
2030	8	077-Richmond	Preservation	SR 1920	SR2031	SR 1922	0.13	Seal - Double	$3,000
2030	8	077-Richmond	Preservation	SR 1922	SR 1903	Dead end	0.25	Seal - Double	$6,000
2030	8	077-Richmond	Preservation	SR 2026	SR 1915	Dead end	0.19	Seal - Double	$6,500
2030	8	077-Richmond	Preservation	SR 2034	SR 2031	Dead end	0.31	Seal - Double	$9,500
2030	8	077-Richmond	Preservation	SR 2040	SR 2039	Dead end	0.18	Seal - Double	$5,500
2030	8	077-Richmond	Preservation	SR 2062	SR 1971	Dead end	0.63	Seal - Double	$27,000
2030	8	083-Scotland	Resurfacing	SR1107	US401 BUS	US74 BUS	1.31	Mill 1.5" and 1.5" S9.5B	$267,900
2030	8	083-Scotland	Resurfacing	SR1107	US74 BUS	US15BUS	1.29	Mill 1.5" and 1.5" S9.5B	$277,200
2030	8	083-Scotland	Resurfacing	SR1304	US74	SR1303	0.99	1.5" S9.5B	$173,913
2030	8	083-Scotland	Resurfacing	SR1643	SR1642	US15 BUS	0.07	1.5" S9.5B	$22,495
2030	8	083-Scotland	Preservation	SR1261	SR1100	SR1257	0.14	Seal - Double and Fog Seal	$18,000
2030	8	083-Scotland	Preservation	SR1331	BEG PAVT	SR1324	3.56	Seal - Double and Fog Seal	$173,000
2030	8	083-Scotland	Preservation	SR1412	SR1415	HOKE CO	7.36	Seal - Double	$315,000
2030	8	083-Scotland	Preservation	SR1612	ROBESON CO	US501	5.22	Seal - Double	$225,000
2030	9	029-Davidson	Resurfacing	NC 47	NC 8	SR 2248	3.76	Mill 1.5" and 1.5" S9.5C	$1,378,667
2030	9	029-Davidson	Resurfacing	SR 1232	SR 1192	SR 1230	1.16	1.5" S9.5B	$310,323
2030	9	029-Davidson	Resurfacing	SR 1299	SR 1297	CUL DE SAC	0.61	1.5" S9.5B	$135,989
2030	9	029-Davidson	Resurfacing	SR 1412	NC 8	SR 1681	0.52	#67 Mat Seal and 1.5" S9.5B	$183,040
2030	9	029-Davidson	Resurfacing	SR 1797	SR1798	US 29	1.50	Mill 1.5" and 1.5" S9.5B	$440,000
2030	9	029-Davidson	Resurfacing	SR 1837	SR 1835	SR 1813	1.33	1.5" S9.5B	$327,132
2030	9	029-Davidson	Resurfacing	SR 2012	US 64	US 64	1.42	1.5" S9.5B	$316,565
2030	9	029-Davidson	Resurfacing	SR 2013	SR 2010	SR 2012	0.76	1.5" S9.5B	$169,429
2030	9	029-Davidson	Resurfacing	SR 2023	SR 2123	US 29	0.34	1.5" S9.5B	$83,377
2030	9	029-Davidson	Resurfacing	SR 2025	SR 2020	SR 2010	1.26	1.5" S9.5B	$252,806
2030	9	029-Davidson	Resurfacing	SR 2044	SR 2123	SR 2123	0.55	Mill 1.5" and 1.5" S9.5B	$274,267
2030	9	029-Davidson	Resurfacing	SR 2053	NC 109	SR 2054	0.58	Mill 1.5" and 1.5" S9.5B	$357,280
2030	9	029-Davidson	Resurfacing	SR 2085	SR 2183	SR 2123	2.90	Mill 1.5" and 1.5" S9.5C	$1,063,333
2030	9	029-Davidson	Resurfacing	SR 2123	SR 2043	SR 2185	2.87	Mill 1.5" and 1.5" S9.5C	$968,147
2030	9	029-Davidson	Resurfacing	SR 2250	SR 2205	NC 47	3.77	#67 Mat Seal and 1.5" S9.5B	$1,327,040
2030	9	029-Davidson	Resurfacing	SR 2289	SR 1396	SR 2294	0.67	1.5" S9.5B	$179,238
2030	9	029-Davidson	Resurfacing	SR 2294	SR 2289	SR 2304	3.98	1.5" S9.5B	$976,002
2030	9	029-Davidson	Resurfacing	SR 2318	RANDOLPH CO LINE	SR 2416	3.12	1.5" S9.5B	$765,107
2030	9	029-Davidson	Resurfacing	SR 2550	MONTGOMERY CO	MONGOMERY CO	2.29	#67 Mat Seal and 1.5" S9.5B	$705,320
2030	9	029-Davidson	Resurfacing	SR 2727	SR 2013	SR 2728	0.72	1.5" S9.5B	$160,512
2030	9	029-Davidson	Resurfacing	SR 2728	SR 2016	SR 2727	0.10	1.5" S9.5B	$22,293
2030	9	029-Davidson	Resurfacing	SR 2776	SR 2085	EOM	0.09	Mill 1.5" and 1.5" S9.5B	$26,400
2030	9	029-Davidson	Resurfacing	SR 3405	SR 2085	NC 109	1.15	Mill 1.5" and 1.5" S9.5B	$337,333
2030	9	029-Davidson	Resurfacing	SR 3520	NC 47	EOM	0.97	Mill 1.5" and 1.5" S9.5C	$284,533
2030	9	029-Davidson	Preservation	SR 1194	SR 1192	US 64	0.56	Seal - Double and Fog Seal	$47,562
2030	9	029-Davidson	Preservation	SR 1195	SR 1192	US 64	1.04	Seal - Double and Fog Seal	$97,621
2030	9	029-Davidson	Preservation	SR 1415	SR 1413	NC 8	0.16	Seal - Double and Fog Seal	$13,517
2030	9	029-Davidson	Preservation	SR 1432	SR 1485	SR 1497	0.36	Seal - Double and Fog Seal	$33,792
2030	9	029-Davidson	Preservation	SR 1483	SR 3289	SR 1484	0.14	Seal - Double and Fog Seal	$13,141
2030	9	029-Davidson	Preservation	SR 1484	END	MP .31	0.31	Seal - Double and Fog Seal	$26,189
2030	9	029-Davidson	Preservation	SR 1495	SR 1485	SR 1497	1.14	Seal - Double and Fog Seal	$107,008
2030	9	029-Davidson	Preservation	SR 1589	SR 1821	SR 1590	0.36	Seal - Double and Fog Seal	$33,792
2030	9	029-Davidson	Preservation	SR 1590	SR 1589	SR 1591	0.09	Seal - Double and Fog Seal	$8,448
2030	9	029-Davidson	Preservation	SR 1591	SR1589	END	0.17	Seal - Double and Fog Seal	$15,957
2030	9	029-Davidson	Preservation	SR 1681	CITY LIMIT	CUL DE SAC	0.45	Seal - Double and Fog Seal	$42,240
2030	9	029-Davidson	Preservation	SR 1682	SR 1681	CUL DE SAC	0.06	Seal - Double and Fog Seal	$5,632
2030	9	029-Davidson	Preservation	SR 1823	SR 1821	PVMT CHANGE	0.21	Seal - Double and Fog Seal	$17,741
2030	9	029-Davidson	Preservation	SR 1848	NC 8	END	0.31	Seal - Double and Fog Seal	$26,189
2030	9	029-Davidson	Preservation	SR 1851	SR 1850	CITY LIMITS	0.14	Seal - Double and Fog Seal	$11,489
2030	9	029-Davidson	Preservation	SR 1899	SR 1827	SR 1826	0.32	Seal - Double and Fog Seal	$30,037
2030	9	029-Davidson	Preservation	SR 2200	CITY LIIMITS	END	0.07	Seal - Double and Fog Seal	$5,257
2030	9	029-Davidson	Preservation	SR 2201	CITY LIIMITS	END	0.10	Seal - Double and Fog Seal	$7,509

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	9	029-Davidson	Preservation	SR 2202	SR 2203	END	0.16	Seal - Double and Fog Seal	$12,015
2030	9	029-Davidson	Preservation	SR 2204	SR 2203	PVMT END	0.19	Seal - Double and Fog Seal	$16,051
2030	9	029-Davidson	Preservation	SR 2207	SR 1243	SR 2390	0.41	Seal - Double and Fog Seal	$38,485
2030	9	029-Davidson	Preservation	SR 2208	SR 1243	SR 2210	0.40	Seal - Double and Fog Seal	$33,792
2030	9	029-Davidson	Preservation	SR 2208	SR 2210	SR 2209	0.05	Seal - Double and Fog Seal	$4,224
2030	9	029-Davidson	Preservation	SR 2209	SR 2210	END	0.17	Seal - Double and Fog Seal	$15,206
2030	9	029-Davidson	Preservation	SR 2209	SR 1243	WIDTH CHANGE	0.15	Seal - Fog	$1,980
2030	9	029-Davidson	Preservation	SR 2209	WIDTH CHANGE	SR 2210	0.12	Seal - Fog	$1,760
2030	9	029-Davidson	Preservation	SR 2210	SR 1243	END	0.39	Seal - Double and Fog Seal	$36,608
2030	9	029-Davidson	Preservation	SR 2211	SR 2209	SR 2208	0.20	Seal - Fog	$2,640
2030	9	029-Davidson	Preservation	SR 2216	SR 1243	SR 2216	1.18	Seal - Double and Fog Seal	$138,453
2030	9	029-Davidson	Preservation	SR 2217	SR 2216	SR 2216	0.22	Seal - Double and Fog Seal	$25,227
2030	9	029-Davidson	Preservation	SR 2218	SR 2216	SR 2217	0.26	Seal - Double and Fog Seal	$30,976
2030	9	029-Davidson	Preservation	SR 2390	CUL DE SAC	END	0.40	Seal - Double and Fog Seal	$37,547
2030	9	029-Davidson	Preservation	SR 2403	US 64	SR 2404	0.30	Seal - Double and Fog Seal	$28,160
2030	9	029-Davidson	Preservation	SR 2404	SR 2403	END	0.10	Seal - Double and Fog Seal	$8,448
2030	9	029-Davidson	Preservation	SR 2405	SR 2390	SR 2390	0.32	Seal - Double and Fog Seal	$30,037
2030	9	029-Davidson	Preservation	SR 2407	SR 2390	END	0.16	Seal - Double and Fog Seal	$15,019
2030	9	029-Davidson	Preservation	SR 2407	SR 2391	CUL DE SAC	0.38	Seal - Double and Fog Seal	$35,669
2030	9	029-Davidson	Preservation	SR 2410	SR 2389	END	0.19	Seal - Fog	$2,787
2030	9	029-Davidson	Preservation	SR 2456	SR 2207	END	0.08	Seal - Fog	$1,173
2030	9	029-Davidson	Preservation	SR 2726	SR 2203	PVMT ENDS	0.25	Seal - Double and Fog Seal	$23,467
2030	9	029-Davidson	Preservation	SR 2912	SR 1464	SR 1826	0.10	Seal - Double and Fog Seal	$7,509
2030	9	029-Davidson	Preservation	SR 2975	SR 1821	END	0.09	Seal - Double and Fog Seal	$8,448
2030	9	029-Davidson	Preservation	SR 2976	SR 1848	END	0.11	Seal - Double and Fog Seal	$9,293
2030	9	029-Davidson	Preservation	SR 2978	SR 2976	END	0.07	Seal - Double and Fog Seal	$5,914
2030	9	029-Davidson	Preservation	SR 3318	SR 2203	END	0.05	Seal - Double and Fog Seal	$4,693
2030	9	029-Davidson	Preservation	SR1821	SR 3010	SR 1464	1.08	Seal - Double and Fog Seal	$91,238
2030	9	029-Davidson	Preservation	SR1826	SR 1464	SR 1464	0.33	Seal - Double and Fog Seal	$27,878
2030	9	029-Davidson	Preservation	SR1920	SR 1899	END	0.19	Seal - Double and Fog Seal	$17,835
2030	9	029-Davidson	Preservation	SR2030	SR 2208	END	0.05	Seal - Fog	$660
2030	9	029-Davidson	Preservation	SR2389	SR 2207	SR 2208	0.10	Seal - Fog	$1,467
2030	9	030-Davie	Resurfacing	NC 801	US 158	S 1410	5.56	Mill 1.5" and 1.5" S9.5C	$1,957,120
2030	9	030-Davie	Resurfacing	NC 801	SR 1410	US 601	5.75	Mill 1.5" and 1.5" S9.5C	$2,024,000
2030	9	030-Davie	Resurfacing	SR 1002	YADKIN COUNTY	SR 1343	3.63	1.5" S9.5B	$891,154
2030	9	030-Davie	Resurfacing	SR 1116	SR 1147	US 64	2.56	Mill 1.5" and 1.5" S9.5B	$902,176
2030	9	030-Davie	Resurfacing	SR 1320	IREDELL CO	SR 1002	3.77	1.5" S9.5B	$923,769
2030	9	030-Davie	Preservation	SR 1139	COOLEEMEE	SR 1147	4.75	Crack Seal	$30,679
2030	9	030-Davie	Preservation	SR 1158	IREDELL CO LINE	NC 901	1.04	Seal - Double and Fog Seal	$146,010
2030	9	030-Davie	Preservation	SR 1159	SR 1147	ROWAN CO LINE	1.08	Seal - Double and Fog Seal	$101,001
2030	9	030-Davie	Preservation	SR 1315	SR 1317	EOM	0.64	Seal - Double and Fog Seal	$60,262
2030	9	030-Davie	Preservation	SR 1316	SR 1317	SR 1313	0.98	Seal - Double and Fog Seal	$82,368
2030	9	030-Davie	Preservation	SR 1319	SR 1320	SR 1317	1.10	Seal - Double and Fog Seal	$103,159
2030	9	030-Davie	Preservation	SR 1405	US 601	US 158	3.72	Crack Seal	$24,026
2030	9	030-Davie	Preservation	SR 1632	US 158	SR 1630	1.58	Seal - Double and Fog Seal	$148,497
2030	9	030-Davie	Preservation	SR 1636	US 158	SR 1600	2.34	Seal - Double and Fog Seal	$219,648
2030	9	030-Davie	Preservation	SR 1638	SR 1636	SR 1600	0.73	Seal - Double and Fog Seal	$69,898
2030	9	030-Davie	Preservation	SR 1912	SR 1929	SR 1911	0.33	Seal - Double and Fog Seal	$30,694
2030	9	034-Forsyth	Resurfacing	NC 66	SR 2775	SR 2611	3.99	Mill 1.5" and 1.5" S9.5C	$1,404,480
2030	9	034-Forsyth	Resurfacing	SR 1101	SR 1100	US 158	4.13	Mill 1.5" and 1.5" S9.5B	$1,332,613
2030	9	034-Forsyth	Resurfacing	SR 1166	SR 1100	SR 1171	4.14	Mill 1.5" and 1.5" S9.5B	$1,214,400
2030	9	034-Forsyth	Resurfacing	SR 1175	SR 1173	SR 1001	2.75	Mill 1.5" and 1.5" S9.5B	$968,000
2030	9	034-Forsyth	Resurfacing	SR 1308	SR 1001	SR 1525	3.06	Mill 1.5" and 1.5" S9.5B	$1,032,240
2030	9	034-Forsyth	Resurfacing	SR 1433	SR1525	SR 1348	1.81	Mill 1.5" and 1.5" S9.5B	$637,120
2030	9	034-Forsyth	Resurfacing	SR 1447	SR 3210	SR 1465	3.12	Mill 1.5" and 1.5" S9.5B	$1,006,720
2030	9	034-Forsyth	Resurfacing	SR 2601	US 421	Guilford Co Line	0.88	Mill 1.5" and 1.5" S9.5B	$344,960
2030	9	034-Forsyth	Resurfacing	SR 2643	NC 109	SR 2691	3.38	Mill 1.5" and 1.5" S9.5B	$1,189,760
2030	9	034-Forsyth	Resurfacing	SR 2775	Davidson Co Line	NC 66	0.91	Mill 1.5" and 1.5" S9.5C	$320,320
2030	9	034-Forsyth	Resurfacing	SR 3000	Rail Road Tracks	SR 2999	2.01	Mill 1.5" and 1.5" S9.5B	$648,560

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	9	034-Forsyth	Resurfacing	SR 3210	NC 67	SR 1525	2.07	Mill 1.5" and 1.5" S9.5B	$667,920
2030	9	034-Forsyth	Preservation	SR 1122	SR 1001	SR 3153	0.64	Crack Seal	$9,642
2030	9	034-Forsyth	Preservation	SR 1146	SR 1152	SR 1153	0.37	Seal - Double and Fog Seal	$27,990
2030	9	034-Forsyth	Preservation	SR 1153	SR 1103	SR 1146	0.68	Seal - Double and Fog Seal	$46,812
2030	9	034-Forsyth	Preservation	SR 1316	SR 1001	EOM	0.80	Seal - Double and Fog Seal	$60,785
2030	9	034-Forsyth	Preservation	SR 1323	SR 1348	EOM	0.50	Seal - Double and Fog Seal	$38,210
2030	9	034-Forsyth	Preservation	SR 1393	SR 1348	SR 1525	2.86	Crack Seal	$18,759
2030	9	034-Forsyth	Preservation	SR 1427	SR 1430	SR 1348	0.83	Seal - Double and Fog Seal	$76,145
2030	9	034-Forsyth	Preservation	SR 1428	SR 1427	EOM	1.02	Seal - Double and Fog Seal	$78,097
2030	9	034-Forsyth	Preservation	SR 1429	SR 1428	EOM	0.32	Seal - Double and Fog Seal	$22,239
2030	9	034-Forsyth	Preservation	SR 1430	SR 1427	SR 3246	0.72	Seal - Double and Fog Seal	$54,836
2030	9	034-Forsyth	Preservation	SR 1432	SR 1433	EOM	0.49	Seal - Double and Fog Seal	$37,447
2030	9	034-Forsyth	Preservation	SR 1435	SR 1525	EOM	0.17	Seal - Double and Fog Seal	$14,262
2030	9	034-Forsyth	Preservation	SR 1552	SR 1433	EOM	0.75	Seal - Double and Fog Seal	$57,124
2030	9	034-Forsyth	Preservation	SR 1567	SR 1525	EOM	0.52	Seal - Double and Fog Seal	$35,350
2030	9	034-Forsyth	Preservation	SR 2703	SR 2705	DAVIDSON CO	1.26	Crack Seal	$7,629
2030	9	034-Forsyth	Preservation	SR 3243	SR 1567	EOM	0.13	Seal - Double and Fog Seal	$10,220
2030	9	034-Forsyth	Preservation	SR 3245	SR 3246	SR 1434	0.09	Seal - Double and Fog Seal	$6,940
2030	9	034-Forsyth	Preservation	SR 3246	EOM	SR 1430	0.12	Seal - Double and Fog Seal	$9,305
2030	9	034-Forsyth	Preservation	SR 3247	SR 1430	EOM	0.07	Seal - Double and Fog Seal	$5,644
2030	9	034-Forsyth	Preservation	SR 3268	SR 3267	EOM	0.07	Seal - Double and Fog Seal	$5,110
2030	9	034-Forsyth	Preservation	SR 3269	SR 3267	EOM	0.05	Seal - Double and Fog Seal	$3,585
2030	9	034-Forsyth	Preservation	SR 3273	SR 1552	SR 3274	0.13	Seal - Double and Fog Seal	$8,580
2030	9	034-Forsyth	Preservation	SR 3274	SR 3273	SR 1433	0.42	Seal - Double and Fog Seal	$28,966
2030	9	034-Forsyth	Preservation	SR 3276	SR 1434	EOM	0.16	Seal - Double and Fog Seal	$12,203
2030	9	034-Forsyth	Preservation	SR 3287	SR 3243	EOM	0.11	Seal - Double and Fog Seal	$8,542
2030	9	034-Forsyth	Preservation	SR 3312	SR 1567	EOM	0.21	Seal - Double and Fog Seal	$14,071
2030	9	034-Forsyth	Preservation	SR 3341	SR 1427	SR 1348	0.38	Seal - Double and Fog Seal	$43,815
2030	9	034-Forsyth	Preservation	SR 3342	SR 3341	EOM	0.16	Seal - Double and Fog Seal	$14,186
2030	9	034-Forsyth	Preservation	SR 3343	SR 3274	EOM	0.04	Seal - Double and Fog Seal	$3,051
2030	9	034-Forsyth	Preservation	SR 3355	SR 3341	SR 3341	0.26	Seal - Double and Fog Seal	$24,070
2030	9	034-Forsyth	Preservation	SR 3398	SR 3341	EOM	0.12	Seal - Double and Fog Seal	$11,059
2030	9	034-Forsyth	Preservation	SR 3399	SR 3398	EOM	0.05	Seal - Double and Fog Seal	$4,301
2030	9	034-Forsyth	Preservation	SR 3411	SR 3341	EOM	0.09	Seal - Double and Fog Seal	$8,420
2030	9	034-Forsyth	Preservation	SR 3412	SR 3411	EOM	0.08	Seal - Double and Fog Seal	$5,949
2030	9	034-Forsyth	Preservation	SR 4117	SR 1430	EOM	0.08	Seal - Double and Fog Seal	$7,040
2030	9	034-Forsyth	Preservation	SR 4278	SR 4315	NC 66	1.16	Crack Seal	$10,535
2030	9	080-Rowan	Resurfacing	SR 1002	SR 2133	Davidson Co Line	4.62	1.5" S9.5B	$1,338,938
2030	9	080-Rowan	Resurfacing	SR 1004	STANLEY CO	SR 1005	2.60	1.5" S9.5B	$637,589
2030	9	080-Rowan	Resurfacing	SR 1005	SR 1004	STANLY CO	1.01	1.5" S9.5B and Widen	$180,130
2030	9	080-Rowan	Resurfacing	SR 2151	SR 1004	STANLY CO	0.45	Full Depth Patching and 1.5" S9.5B	$70,805
2030	9	080-Rowan	Resurfacing	US 29	Pavement Jnt at SR 2740	Pavement Jnt atNC150	6.95	Mill 1.5" and 1.5" S9.5B	$5,300,533
2030	9	080-Rowan	Resurfacing	US 601	US 70	Pmvt Jnt at Laurel Valley Way	1.09	#67 Mat Seal and 1.5" S9.5B	$340,196
2030	9	080-Rowan	Preservation	SR 1360	SR 1351	SR 1353	2.35	Seal - Double and Fog Seal	$198,434
2030	9	080-Rowan	Preservation	SR 1361	SR 1369	SR 1360	1.62	Seal - Double and Fog Seal	$136,994
2030	9	080-Rowan	Preservation	SR 1382	SR 1124	EOM	0.52	Seal - Double and Fog Seal	$43,946
2030	9	080-Rowan	Preservation	SR 1386	SR 1382	SR 1392	0.32	Seal - Double and Fog Seal	$29,661
2030	9	080-Rowan	Preservation	SR 1391	SR 1414	SR 1351	0.53	Seal - Double and Fog Seal	$49,768
2030	9	080-Rowan	Preservation	SR 1392	SR 1124	SR 1361	0.83	Seal - Double and Fog Seal	$69,976
2030	9	080-Rowan	Preservation	SR 1393	SR 1460	SR 1361	0.31	Seal - Double and Fog Seal	$26,452
2030	9	080-Rowan	Preservation	SR 1395	SR 1393	EOM	0.62	Seal - Double and Fog Seal	$52,482
2030	9	080-Rowan	Preservation	SR 1397	SR 1361	SR 1351	0.15	Seal - Double and Fog Seal	$12,254
2030	9	080-Rowan	Preservation	SR 1398	SR 1361	EOM	0.37	Seal - Double and Fog Seal	$30,847
2030	9	080-Rowan	Preservation	SR 1423	SR 1424	EOM	0.46	Seal - Double and Fog Seal	$43,101
2030	9	080-Rowan	Preservation	SR 1424	SR 1382	SR 1382	0.38	Seal - Double and Fog Seal	$36,058
2030	9	080-Rowan	Preservation	SR 1460	SR 1393	EOM	0.14	Seal - Double and Fog Seal	$12,959
2030	9	080-Rowan	Preservation	SR 1481	SR 1124	SR 1351	0.16	Seal - Double and Fog Seal	$12,019
2030	9	080-Rowan	Preservation	SR 1482	SR 1355	EOM	0.81	Seal - Double and Fog Seal	$68,286
2030	9	080-Rowan	Preservation	SR 2706	SR 1395	EOM	0.08	Seal - Double and Fog Seal	$6,676

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	9	080-Rowan	Preservation	SR 2710	SR 1351	EOM	0.28	Seal - Double and Fog Seal	$23,917
2030	9	080-Rowan	Preservation	SR 2711	SR 1482	EOM	0.15	Seal - Double and Fog Seal	$13,015
2030	9	080-Rowan	Preservation	SR 2712	SR 1361	EOM	0.20	Seal - Double and Fog Seal	$19,062
2030	9	080-Rowan	Preservation	SR 2725	SR 1363	SR 2725	0.57	Seal - Double and Fog Seal	$48,087
2030	9	080-Rowan	Preservation	SR 2743	SR 1359	EOM	0.16	Seal - Double and Fog Seal	$14,837
2030	9	080-Rowan	Preservation	SR 2764	SR 1355	EOM	0.32	Seal - Double and Fog Seal	$29,767
2030	9	080-Rowan	Preservation	SR 2765	SR 1355	EOM	0.44	Seal - Double and Fog Seal	$40,849
2030	9	080-Rowan	Preservation	SR 2767	SR 2765	EOM	0.13	Seal - Double and Fog Seal	$11,832
2030	9	080-Rowan	Preservation	SR 2768	SR 2765	EOM	0.17	Seal - Double and Fog Seal	$15,588
2030	9	085-Stokes	Resurfacing	NC 772	US 311	NC 704	10.28	1.5" S9.5B	$2,520,930
2030	9	085-Stokes	Resurfacing	SR 1722	NC 772	US 311	4.03	1.5" S9.5B	$988,263
2030	9	085-Stokes	Resurfacing	SSR 1686	NC 772	Rockingham Co Line	3.63	1.5" S9.5B	$1,032,627
2030	9	085-Stokes	Preservation	SR 1759	NC 772	SR 1686	3.20	Crack Seal	$16,130
2030	9	085-Stokes	Preservation	SR 1917	SR 1918	EOM	0.60	Seal - Double and Fog Seal	$50,941
2030	9	085-Stokes	Preservation	SR 1966	SR 1973	NC 66	3.96	Seal - Double and Fog Seal	$389,805
2030	9	085-Stokes	Preservation	SR 1973	SR 1955	SR 2019	3.46	Crack Seal	$20,942
2030	9	085-Stokes	Preservation	SR 1978	SR 1935	EOM	1.24	Seal - Double and Fog Seal	$104,586
2030	9	085-Stokes	Preservation	SR 1980	SR 1937	EOM	0.78	Seal - Double and Fog Seal	$66,148
2030	9	085-Stokes	Preservation	SR 1993	SR 2019	SR 2018	3.37	Seal - Double and Fog Seal	$316,331
2030	9	085-Stokes	Preservation	SR 2037	SR 1932	SR 2038	0.11	Seal - Double and Fog Seal	$10,419
2030	9	085-Stokes	Preservation	SR 2039	SR 1932	SR 2038	0.10	Seal - Double and Fog Seal	$9,105
2030	9	085-Stokes	Preservation	SR 2063	SR 2062	EOM	0.47	Seal - Double and Fog Seal	$39,621
2030	9	085-Stokes	Preservation	SR 2070	SR 1932	EOM	0.21	Seal - Double and Fog Seal	$17,403
2030	10	004-Anson	Resurfacing	NC 145	Morven City Limits	.4 miles North of SR 1804 Hinson R	6.90	1.5" S9.5C and Widen	$1,745,700
2030	10	004-Anson	Resurfacing	SR 1002 New Home Church Rd	SR 1645 Cappadocia Church Rd	NC 218	1.98	Full Depth Patching and 1.25" S9.5C	$631,813
2030	10	004-Anson	Resurfacing	SR 1259 Anson High School Rd	US 74	SR 1205	1.35	Full Depth Patching and 1.5" S9.5C	$432,103
2030	10	004-Anson	Resurfacing	SR 1443 Tucker Rd	SR 1446	SR 1002	1.52	Crack Seal and 1.5" S9.5C	$498,153
2030	10	004-Anson	Resurfacing	SR 1703 Stanback Ferry	SR 1634 Grassy Island	SR 1711 Doc Wyatt	5.02	Full Depth Patching and 1.5" S9.5C	$1,595,493
2030	10	004-Anson	Preservation	SR 1224 Austin Road	SR 1253 Watts Road	SR 1225 Tice Road	0.58	FDR and Triple Seal	$216,750
2030	10	004-Anson	Preservation	SR 1226 Crown Road	SR 1227 Pear Orchard	SC Line	0.71	FDR and Triple Seal	$265,125
2030	10	004-Anson	Preservation	SR 1242 Webb Ingram Road	SR 1240 Mineral Springs Church Road	End Of Maintenance	1.72	FDR and Triple Seal	$645,000
2030	10	004-Anson	Preservation	SR 1662	SR 1661	SR 1663	0.08	Seal - Double and Fog Seal	$5,850
2030	10	013-Cabarrus	Resurfacing	NC 3 Concord Lake	Old Earnhardt	Dale Earnhardt Blvd NC 3	0.13	1.5" S9.5C	$40,000
2030	10	013-Cabarrus	Resurfacing	NC 49 NB	SR 1155 Zion Ch Rd	0.06 mi North of Selma Dr	0.45	2.0" S9.5C	$104,428
2030	10	013-Cabarrus	Resurfacing	NC 49 North	SR 1309 Stough Rd -.101	SR 1155 Zion Church Rd -.425	1.98	Mill 3.0" and 3.0" S9.5C	$542,000
2030	10	013-Cabarrus	Resurfacing	NC 49 South	SR 1155 Zion Church Rd +.425	SR 1309 Stough Rd +.101	2.00	Mill 3.0" and 3.0" S9.5C	$542,000
2030	10	013-Cabarrus	Resurfacing	SR 1134 Pioneer Mill Rd	SR 1136 Lower Rocky River Rd	SR 1135 Morrison Rd	1.39	1.5" S9.5C	$472,600
2030	10	013-Cabarrus	Resurfacing	SR 1153 Zion Ch Rd East	US 601	SR 1155 Zion Ch Rd	1.60	1.5" S9.5B	$320,000
2030	10	013-Cabarrus	Resurfacing	SR 1159 Mulberry Rd	Width change	dead end	0.42	Full Depth Patching and 1.25" S9.5B	$75,000
2030	10	013-Cabarrus	Resurfacing	SR 1159 Mulberry Rd	SR 1158 Pharr Mill Rd	Width Change	0.31	1.25" S4.75A	$56,950
2030	10	013-Cabarrus	Resurfacing	SR 1168 Robinson Ch Rd	Mecklenburg County line	SR 1139 Rocky River Rd	2.39	1.5" S9.5C	$500,000
2030	10	013-Cabarrus	Resurfacing	SR 1236 Dakeita Cr	SR 1235 Baptist Ln	cul-de-sac	0.88	1.25" S4.75A	$160,000
2030	10	013-Cabarrus	Resurfacing	SR 1269 Falcon Dr	jt at culvert south of SR 3010	dead end	0.47	1.25" S4.75A	$100,000
2030	10	013-Cabarrus	Resurfacing	SR 2001 S Ridge Ave	begin pavement	US 29	0.24	Mill 1.5" and 1.5" S9.5B	$62,000
2030	10	013-Cabarrus	Resurfacing	SR 2366 Kiwi Ct	dead end	dead end off SR 1270	0.38	1.25" S4.75A	$75,000
2030	10	013-Cabarrus	Resurfacing	SR 2399 Fieldstone Trace	US 601	SR 1119 Wallace Rd	0.47	1.25" S4.75A	$100,000
2030	10	013-Cabarrus	Resurfacing	SR 2400 Irish Potato Rd	SR 1002 Old Concord Salisbury	SR 2400 Barrier Rd	2.65	Full Depth Patching and 1.5" S9.5B	$530,000
2030	10	013-Cabarrus	Resurfacing	SR 2408 Gold Hill Rd	SR 2411	Bridge	1.15	Full Depth Patching and 2.0" S9.5C	$600,000
2030	10	013-Cabarrus	Resurfacing	SR 2408 Gold Hill Rd	Bridge	SR 2427 Cline School Rd	1.57	Full Depth Patching and 2.0" S9.5C	$800,000
2030	10	013-Cabarrus	Resurfacing	SR 2408 Gold Hill Rd	SR 2427 Cline School Rd	SR 1006 Mt Pleasant Rd	1.28	Full Depth Patching and 2.0" S9.5C	$650,000
2030	10	013-Cabarrus	Resurfacing	SR 2411 Cold Springs East	SR 2637 Mt Pleasant Rd West	SR 1006 Mt Pleasant Rd	1.50	Mill 1.5" and 1.5" S9.5B	$550,000
2030	10	013-Cabarrus	Resurfacing	SR 2416 Mt Olive Rd	SR 1006 Mt. Pleasant Rd	M.P. 6.5 SR 2416 Sansbury Rd	4.35	Full Depth Patching and 1.5" S9.5B	$1,088,598
2030	10	013-Cabarrus	Resurfacing	SR 2453 Lentz Harness	pvmt change	SR 2444 St Stephens Ch Rd	0.67	1.5" S9.5B	$90,000
2030	10	013-Cabarrus	Resurfacing	SR 2453 Lentz Harness	NC 49	NC 49 + 1.65	1.65	Mill 1.5" and 1.5" S9.5B	$430,000
2030	10	013-Cabarrus	Resurfacing	SR 2453 Lentz Harness	SR 2602 Bear Crk Ch Rd	NC 49	1.52	Mill 1.5" and 1.5" S9.5B	$400,000
2030	10	013-Cabarrus	Resurfacing	SR 2638 Eagle Street	NC 73	SR 2639 Pinecrest Dr	0.11	Mill 1.25" and 1.25" S9.5A	$20,000
2030	10	013-Cabarrus	Resurfacing	SR 2713 Maple Bluff Ln	SR 1105 Joyner Rd	cul-de-sac	0.43	1.25" S4.75A	$90,000
2030	10	013-Cabarrus	Resurfacing	SR 2823 Armentrout Dr	US 601	cul-de-sac	0.50	Mill 1.25" and 1.25" S9.5A	$100,000
2030	10	013-Cabarrus	Resurfacing	SR 2841 Commerce Dr	SR 1155 Zion Ch Rd	Cul-de-sac	0.15	Mill 1.5" and 1.5" S9.5C	$60,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	10	013-Cabarrus	Resurfacing	SR 2909 Oxford Ct	SR 2910 Scottland Dr	dead end	0.05	1.25" S4.75A	$15,950
2030	10	013-Cabarrus	Resurfacing	SR 3001 Haydens Way	SR 1236 Dakeita Cr	cul-de-sac	0.50	1.25" S4.75A	$90,000
2030	10	013-Cabarrus	Resurfacing	SR 3035 Piper Ct	dead end	dead end	0.36	Full Depth Patching and 1.5" S9.5B	$72,000
2030	10	013-Cabarrus	Resurfacing	SR 3036 McCamie Hill Pl	SR 3035 Piper Ct	dead end	0.35	Full Depth Patching and 1.5" S9.5B	$70,000
2030	10	013-Cabarrus	Resurfacing	US 601	US601South + 0.684 mi	SR 2631 +.067 miles	1.80	Full Depth Patching and 2.0" S9.5C	$1,000,000
2030	10	013-Cabarrus	Preservation	SR 1145	SR 1123 Jim Sossoman	SR 1143 Cal Bost	2.54	Seal - Double and Fog Seal	$168,558
2030	10	013-Cabarrus	Preservation	SR 1888 Crofton Ave	NC 3	SR 1900 Bealgray Rd	0.42	Seal - Double and Fog Seal	$27,300
2030	10	013-Cabarrus	Preservation	SR 1900 Bealgray Rd	SR 1888	cul de sac	0.45	Seal - Double and Fog Seal	$29,250
2030	10	013-Cabarrus	Preservation	SR 1930 Meadowview Dr	SR 1612	SR 1931	0.34	Seal - Double and Fog Seal	$25,000
2030	10	013-Cabarrus	Preservation	SR 1931 Autumn Cir	SR 1930	SR 1932	0.33	Seal - Double and Fog Seal	$21,450
2030	10	013-Cabarrus	Preservation	SR 1932 Harvest Ln	SR 1930	SR 1931	0.22	Seal - Double and Fog Seal	$14,300
2030	10	013-Cabarrus	Preservation	SR 2117 Mullis Rd	SR 2114 Centergrove Rd	SR 2284	0.26	Seal - Double and Fog Seal	$16,900
2030	10	013-Cabarrus	Preservation	SR 2245 Oak Trail Cir	SR 2113 Penninger Rd	SR 2113 Penninger Rd	0.72	Seal - Double and Fog Seal	$46,800
2030	10	013-Cabarrus	Preservation	SR 2281 Mockingbird Ln	SR 2114 Centergrove Rd	dead end	0.10	Seal - Double and Fog Seal	$6,500
2030	10	013-Cabarrus	Preservation	SR 2436	SR 2408	SR 2435	2.33	Seal - Double and Fog Seal	$160,000
2030	10	013-Cabarrus	Preservation	SR 2450	Rowan Co.	NC 49	3.38	Seal - Double and Fog Seal	$220,422
2030	10	013-Cabarrus	Preservation	SR 2474 Simmons St	SR 1002 Old Concord Salisbury	dead end	0.64	Seal - Double and Fog Seal	$41,600
2030	10	013-Cabarrus	Preservation	SR 2475 Whiting Ave	SR 2474	dead end	0.29	Seal - Double and Fog Seal	$18,850
2030	10	013-Cabarrus	Preservation	SR 2492 Lenhaven	SR 1002- Old Salisbury Concord	SR 2496	0.35	Seal - Double and Fog Seal	$22,042
2030	10	013-Cabarrus	Preservation	SR 2610 Bowman Barrier	Hahn Scott Rd. SR2612	Lambert Rd.SR2611	0.86	Seal - Double and Fog Seal	$58,347
2030	10	013-Cabarrus	Preservation	SR 2623 County Line Rd	SR2622 Barrier Store Rd	NC 200	3.92	Seal - Double and Fog Seal	$225,000
2030	10	013-Cabarrus	Preservation	SR 2625	NC 200	SR 2623	1.67	Crack Seal	$25,000
2030	10	060-Mecklenburg	Resurfacing	NC 160 West Blvd	SR 1255 Byrum Drive	Pavement Divide	1.30	Full Depth Patching and 1.5" S9.5C	$950,000
2030	10	060-Mecklenburg	Resurfacing	NC 49 York Rd / S Tryon St	Steele Creek Rd	Mecklenburg County line	4.33	Mill 1.5" and 1.5" S9.5D	$1,275,000
2030	10	060-Mecklenburg	Resurfacing	NC 49 York Rd / S Tryon St	Mecklenburg County line	Steele Creek Rd	1.64	Mill 1.5" and 1.5" S9.5D	$1,210,000
2030	10	060-Mecklenburg	Resurfacing	NC 51 Blair Road	NC 218 Fairview Road	I-485	1.71	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$875,000
2030	10	060-Mecklenburg	Resurfacing	SR 1148 Garrison Road	West Boulevard	EOM	1.19	Full Depth Patching and 1.5" S9.5C	$458,000
2030	10	060-Mecklenburg	Resurfacing	SR 1156 Yorkmont Rd	NC 49 S Tryon St	Beam Rd	2.53	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$710,000
2030	10	060-Mecklenburg	Resurfacing	SR 1177 Yorkmont Rd	NC 49 S Tryon St	West Tyvola Rd	0.61	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$180,000
2030	10	060-Mecklenburg	Resurfacing	SR 1177 Yorkmont Rd	NC 160 West Blvd	Pavement Divide	0.25	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$284,000
2030	10	060-Mecklenburg	Resurfacing	SR 1189 Brick Yard Rd Ext	Brick Yard Rd	dead end	0.31	Full Depth Patching and 1.25" S9.5B	$75,000
2030	10	060-Mecklenburg	Resurfacing	SR 1535 Elena Drive	Soldier Road	EOM	0.10	Full Depth Patching and 1.5" S9.5C	$30,000
2030	10	060-Mecklenburg	Resurfacing	SR 1601 Moores Chapel Rd	I 485 Roundabout	Waldon Road	0.52	Full Depth Patching and 1.5" S9.5C	$143,000
2030	10	060-Mecklenburg	Resurfacing	SR 1601 Moores Chapel Rd	Beg Divide Kendall Dr	End Divide Dilling Farm	0.19	Full Depth Patching and 1.5" S9.5C	$52,250
2030	10	060-Mecklenburg	Resurfacing	SR 1784 Mt Holly Road	SR 1785 Valleydale Road	NC 24 Freedom Drive	1.15	Full Depth Patching and 1.5" S9.5C	$479,000
2030	10	060-Mecklenburg	Resurfacing	SR 2117 Hambright Rd	End of island .09 Miles West of NC 115	SR 2458 Everett Keith Road	0.77	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$305,000
2030	10	060-Mecklenburg	Resurfacing	SR 2117 Hambright Rd	SR 2458 Everette Keith Rd	Pavement joint at Blythe school	0.80	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$660,000
2030	10	060-Mecklenburg	Resurfacing	SR 2117 Hambright Rd	US 21 Statesville Rd	SR 2120 Mccoy Road	2.44	Full Depth Patching and 1.5" S9.5C	$843,000
2030	10	060-Mecklenburg	Resurfacing	SR 2426 Hilwassee Rd	SR 2426 Huntersville Concord Rd	SR 2427 Ramah Church Rd	0.96	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$302,000
2030	10	060-Mecklenburg	Resurfacing	SR 2426 Huntersville Concord Rd	SR 2425 McAuley Rd	SR 2426 Hilwassee Rd	0.62	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$205,000
2030	10	060-Mecklenburg	Resurfacing	SR 2448 Huntersville Concord Rd	SR 2426 Huntersville Concord Rd	NC 115 Statesville Rd	2.45	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$480,000
2030	10	060-Mecklenburg	Resurfacing	SR 2468 Gene Downs Road	SR 2464 Morehead Road	EOM	0.34	Full Depth Patching and 1.5" S9.5C	$93,500
2030	10	060-Mecklenburg	Resurfacing	SR 2882 Damson Plum Lane	SR 5856 Daerwood Place	EOM	0.04	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$7,300
2030	10	060-Mecklenburg	Resurfacing	SR 3440 McKee Rd	Bridge	SR 3445 Tilley Morris	1.29	Full Depth Patching and 1.5" S9.5C	$890,000
2030	10	060-Mecklenburg	Resurfacing	SR 3457 Campus Ridge Rd	BOM	Union County Line	0.86	Mill 1.5" and 2.0" S9.5C	$350,000
2030	10	060-Mecklenburg	Resurfacing	SR 3637 Dorman Road	SR 4982 Lancaster Hwy	SC State line	0.18	Full Depth Patching and 1.5" S9.5C	$327,000
2030	10	060-Mecklenburg	Resurfacing	SR 3814 East Woodlawn Rd.	Park Road	SR 3998 South Blvd	1.48	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$1,250,000
2030	10	060-Mecklenburg	Resurfacing	SR 3998 South Blvd	Sharon Lakes	SR 3814 East Woodlawn	1.85	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$2,100,000
2030	10	060-Mecklenburg	Resurfacing	SR 3998 South Blvd	Pavement Divide	Pavement Divide	0.24	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$231,000
2030	10	060-Mecklenburg	Resurfacing	SR 3998 South Blvd	Pavement Divide	Pavement Divide	0.05	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$55,000
2030	10	060-Mecklenburg	Resurfacing	SR 3998 South Blvd	Pavement Divide	Pavement Divide	0.18	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$155,000
2030	10	060-Mecklenburg	Resurfacing	SR 3998 South Blvd	Pavement Divide	Pavement Divide	0.14	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$140,000
2030	10	060-Mecklenburg	Resurfacing	SR 4631 Marlstone Ln	SR 2810 Rocky River Church Rd	EOM	0.36	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$136,000
2030	10	060-Mecklenburg	Resurfacing	SR 4982 Polk ST/South Blvd	NC 51 Pineville Matthews Road	I-485	1.16	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$820,000
2030	10	060-Mecklenburg	Resurfacing	SR 5032 Jardin Way	SR 2804 Reedy Creek Road	EOM	0.43	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$82,110
2030	10	060-Mecklenburg	Resurfacing	SR 5067 Scarlet Runner Drive	SR 5032 Jardin Way	EOM	0.15	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$29,000
2030	10	060-Mecklenburg	Resurfacing	SR 5068 Schooner Bay Lane	SR 5067 Scarlet Runner Drive	EOM	0.11	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$19,470
2030	10	060-Mecklenburg	Resurfacing	SR 5069 Clayford Rdg	SR 2804 Reedy Creek Road	Cul de sac	0.39	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$75,000
2030	10	060-Mecklenburg	Resurfacing	SR 5070 Daerwood Pl	SR 5069 Clayford Rdg	SR 5071 Pale Hickory Lane	0.30	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$60,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	10	060-Mecklenburg	Resurfacing	SR 5072 Shipwright Ln	SR 5070 Daerwood Pl	SR 5073 Passeres Ct	0.09	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$17,000
2030	10	060-Mecklenburg	Resurfacing	SR 5073 Passeres Ct	Cul de sac	Cul de sac	0.13	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$25,000
2030	10	060-Mecklenburg	Resurfacing	SR 5074 Red Snow Ct	SR 5070 Daerwood Pl	Cul de sac	0.03	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$6,000
2030	10	060-Mecklenburg	Resurfacing	SR 5075 Scrimshaw Ln	SR 2804 Reedy Creek Road	SR 5078 Spandril Ln	0.18	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$34,000
2030	10	060-Mecklenburg	Resurfacing	SR 5077 Scuppernong Court	SR 5032 Jardin Way	EOM	0.20	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$35,400
2030	10	060-Mecklenburg	Resurfacing	SR 5078 Spandril Ln	SR 4698 English Walnut Ln	SR 5808 Peacock Ln	0.36	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$38,000
2030	10	060-Mecklenburg	Resurfacing	SR 5079 Turmeric Ct	SR 5078 Spandril Ln	Cul de sac	0.06	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$12,000
2030	10	060-Mecklenburg	Resurfacing	SR 5080 Renda Ct	SR 5078 Spandril Ln	Cul de sac	0.09	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$18,000
2030	10	060-Mecklenburg	Resurfacing	SR 5395 Sanridge Wind Lane	SR 5399 Claybrooke Drive	EOM	0.24	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$112,000
2030	10	060-Mecklenburg	Resurfacing	SR 5396 Kendan Knoll Drive	SR 5395 Sanridge Wind Lane	Galloway Drive	0.12	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$36,000
2030	10	060-Mecklenburg	Resurfacing	SR 5397 Turning Leaf Court	SR 5399 Claybrooke Drive	EOM	0.17	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$51,000
2030	10	060-Mecklenburg	Resurfacing	SR 5398 Loganberry Trail	SR 5397 Turning Leaf Court	EOM	0.07	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$21,000
2030	10	060-Mecklenburg	Resurfacing	SR 5399 Claybrooke Drive	Galloway Drive	EOM	0.18	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$54,000
2030	10	060-Mecklenburg	Resurfacing	SR 5802 Rock Maple Ct	Scuppernog Ct	Reedy Creek Rd	0.07	Full Depth Patching and 1.25" S9.5B	$13,000
2030	10	060-Mecklenburg	Resurfacing	SR 5807 Isthmust Ct	SR 5078 Spandril Ln	Cul de sac	0.12	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$29,000
2030	10	060-Mecklenburg	Resurfacing	SR 5808 Peacock Ln	SR 2809 Peach Orchard Rd	Cul de sac	0.28	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$52,640
2030	10	060-Mecklenburg	Resurfacing	SR 5809 Leghorn Ct	SR 5808 Peacock Ln	Cul de sac	0.05	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$9,712
2030	10	060-Mecklenburg	Resurfacing	SR 5854 Red Spruce Drive	SR 5855 Sugar Maple Lane	EOM	0.15	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$31,550
2030	10	060-Mecklenburg	Resurfacing	SR 5855 Sugar Maple Lane	EOM	EOM	0.18	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$37,860
2030	10	060-Mecklenburg	Resurfacing	SR 5856 Daerwood Place	SR 5854 Red Spruce Lane	SR 5069 Clayford Rdg	0.21	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$52,310
2030	10	060-Mecklenburg	Resurfacing	SR 5857 Bald Eagle Drive	SR 2804 Reedy Creek Road	EOM	0.12	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$21,240
2030	10	060-Mecklenburg	Resurfacing	SR 5858 Kingbird Court	SR 5857 Bald Eagle Drive	EOM	0.14	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$24,780
2030	10	060-Mecklenburg	Resurfacing	SR 5860 Cedar Post Lane	EOM	EOM	0.24	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$54,800
2030	10	060-Mecklenburg	Resurfacing	SR 5861 Laurel Twig Court	SR 5860 Cedar Post Lane	EOM	0.10	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$20,700
2030	10	060-Mecklenburg	Resurfacing	SR 5862 Red Holly Court	SR 5860 Cedar Post Lane	EOM	0.10	Mill 1.25" and 1.25" S9.5B and Full Depth Patching	$17,800
2030	10	060-Mecklenburg	Preservation	SR 1116 Shopton Rd West	Kirkwood Commons Dr	SR 1114 Woody Point Rd	3.32	Rejuvenator	$45,000
2030	10	060-Mecklenburg	Preservation	SR 1129 Downs Road	NC 51 Rock Hill Pineville Road	EOM past Ammon Lane	1.26	Rejuvenator	$20,400
2030	10	060-Mecklenburg	Preservation	SR 1138 West Arrowood Rd EBL	I-485	I-77	2.60	Rejuvenator	$35,000
2030	10	060-Mecklenburg	Preservation	SR 1138 West Arrowood Rd WBL	I-77	I-485	2.60	Rejuvenator	$45,000
2030	10	060-Mecklenburg	Preservation	SR 1143 West Arrowood Rd EBL	SR 1142 Sandy Porter Rd	I-485 Bridge	0.34	Rejuvenator	$7,000
2030	10	060-Mecklenburg	Preservation	SR 1143 West Arrowood Rd EBL	SR 1142 Sandy Porter Rd	EOM	0.15	Rejuvenator	$2,600
2030	10	060-Mecklenburg	Preservation	SR 1143 West Arrowood Rd WBL	SR 1142 Sandy Porter Rd	EOM	0.15	Rejuvenator	$2,000
2030	10	060-Mecklenburg	Preservation	SR 1143 West Arrowood Rd WBL	I-485 Bridge	SR 1142 Sandy Porter Rd	0.34	Rejuvenator	$7,000
2030	10	060-Mecklenburg	Preservation	SR 1149 Horton Rd	Garrison Rd	eom	0.31	Rejuvenator	$4,200
2030	10	060-Mecklenburg	Preservation	SR 1291 East Woodlawn Rd	Begin Divide at Sterling Dr	End Divide at South Blvd	0.16	Rejuvenator	$2,500
2030	10	060-Mecklenburg	Preservation	SR 1291 East Woodlawn Rd	SR 3998 South Blvd	NC 49 S Tryon S	0.80	Rejuvenator	$23,000
2030	10	060-Mecklenburg	Preservation	SR 1291 W. Woodlawn Rd	NC 49 S Tryon St	end divide at Wallingford st	0.28	Rejuvenator	$4,600
2030	10	060-Mecklenburg	Preservation	SR 1392 Harbor View Rd	Kalabash Rd	eom	0.30	Rejuvenator	$4,100
2030	10	060-Mecklenburg	Preservation	SR 1410 Westinghouse Blvd	NC 160 Steele Creek Rd	NC 49 S Tryon St	2.12	Microsurface	$130,360
2030	10	060-Mecklenburg	Preservation	SR 1410 Westinghouse Blvd	RR Crossing at EOM	NC 49 S Tryon St	2.65	Microsurface	$297,000
2030	10	060-Mecklenburg	Preservation	SR 1410 Westinghouse Blvd	SR 1116 Shopton Rd W	NC 160 Steele Creek Rd	1.22	Microsurface	$86,939
2030	10	060-Mecklenburg	Preservation	SR 1435 Sharlyn Dr	Walker Ferry Rd	dead end	0.28	Rejuvenator	$3,400
2030	10	060-Mecklenburg	Preservation	SR 1509 Four Horse Rd	SR 1116 Shopton Rd W	Waymart Ln	0.63	Rejuvenator	$7,700
2030	10	060-Mecklenburg	Preservation	SR 1813 Thomasboro Dr	Glenwood Dr	Bradford Dr	0.58	Rejuvenator	$14,100
2030	10	060-Mecklenburg	Preservation	SR 2112 Lakeview Rd	Reames Rd	Beatties Ford Rd	0.98	Rejuvenator	$16,000
2030	10	060-Mecklenburg	Preservation	SR 2147 Westmoreland Rd	SR 5544 W Catawba Ave	EOM	1.27	Rejuvenator	$22,500
2030	10	060-Mecklenburg	Preservation	SR 2151 Jetton Rd	Peninsula Point Dr	EOM	1.89	Rejuvenator	$23,000
2030	10	060-Mecklenburg	Preservation	SR 2279 Kennewick Rd	SR 2004 Mt Holly Huntersville Rd	EOM	0.42	Rejuvenator	$6,300
2030	10	060-Mecklenburg	Preservation	SR 2321 Marengo Cr	SR 2279 Kennewick Rd	SR 2279 Kennewick Rd	0.49	Rejuvenator	$6,611
2030	10	060-Mecklenburg	Preservation	SR 2344 J. T. Williams Junior High Dr	Tipton Dr	eom	0.18	Rejuvenator	$3,000
2030	10	060-Mecklenburg	Preservation	SR 2802 Rocky River Rd	Cabarrus County line	Back Creek Church Rd	1.76	Rejuvenator	$23,800
2030	10	060-Mecklenburg	Preservation	SR 2976 Grier Rd	SR 2853 Newell-Hickory Grove Rd	SR Rocky River Rd	1.12	Microsurface	$85,000
2030	10	060-Mecklenburg	Preservation	SR 3106 Brief Rd	NC 218	MP .655	0.67	Rejuvenator	$7,200
2030	10	060-Mecklenburg	Preservation	SR 3110 Arlington Church Rd	SR 3110 Arlington Church Rd	EOM	0.36	Rejuvenator	$5,900
2030	10	060-Mecklenburg	Preservation	SR 3135 Lebanon Rd	SR 3128 Lawyers Rd	SR 3156 Margaret Wallace Rd	0.45	Rejuvenator	$6,700
2030	10	060-Mecklenburg	Preservation	SR 3135 Lebanon Rd	Begin Divide	SR 3128 Lawyers Rd	0.05	Rejuvenator	$500
2030	10	060-Mecklenburg	Preservation	SR 3156 Margaret Wallace Rd	SR 3135 Lebanon Rd	SR 3143 Idlewild Rd	1.02	Rejuvenator	$15,200
2030	10	060-Mecklenburg	Preservation	SR 3624 Rea Rd	NC 51 Pineville-Matthews Rd	Piper Glenn Dr	0.16	Rejuvenator	$26,500
2030	10	060-Mecklenburg	Preservation	SR 3624 Rea Road	Piper Glenn Drive	NC 51 Pineville Matthews Road	0.16	Rejuvenator	$24,300

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	10	060-Mecklenburg	Preservation	SR 4240 Morris Pond Dr	SR 3128 Lawyers Rd	SR 4244 Milton Morris Dr	0.31	Rejuvenator	$5,000
2030	10	060-Mecklenburg	Preservation	SR 4240 Morris Pond Dr	Begin Divide	SR 3128 Lawyers Rd	0.06	Rejuvenator	$500
2030	10	060-Mecklenburg	Preservation	SR 4241 Rena Mae Ln	SR 4240 Morris Pond Dr	SR 4244 Milton Morris Dr	0.37	Rejuvenator	$5,500
2030	10	060-Mecklenburg	Preservation	SR 4262 Barn Stone Dr	SR 4244 Milton Morris Dr	EOM	0.31	Rejuvenator	$4,200
2030	10	060-Mecklenburg	Preservation	SR 4277 Verda's Path	SR 3102 Cabarrus Rd	EOM	0.18	Rejuvenator	$2,900
2030	10	060-Mecklenburg	Preservation	SR 4279 Red Setter Lane	SR 4278 Swedish Ivy Lane	EOM	0.17	Rejuvenator	$2,300
2030	10	060-Mecklenburg	Preservation	SR 4282 David Lee Ln	SR 4278 Swedish Ivy Ln	EOM	0.30	Rejuvenator	$4,000
2030	10	060-Mecklenburg	Preservation	SR 4283 Houndstooth Dr	SR 4278 Swedish Ivy Ln	EOM	0.12	Rejuvenator	$1,620
2030	10	060-Mecklenburg	Preservation	SR 5225 Morgan Glenn Drive	SR 3110 Arlington Church Rd	EOM	0.36	Rejuvenator	$6,000
2030	10	060-Mecklenburg	Preservation	SR 5226 Coral Ridge Drive	SR 5225 Morgan Glenn Dr	EOM	0.15	Rejuvenator	$2,500
2030	10	060-Mecklenburg	Preservation	SR 5227 White Cliffs Drive	SR 5225 Morgan Glenn Dr	EOM	0.07	Rejuvenator	$1,500
2030	10	060-Mecklenburg	Preservation	SR 5427 S Mint St	US 29 Graham St	W 3rd St	0.21	Rejuvenator	$8,500
2030	10	060-Mecklenburg	Preservation	SR 5428 W Martin Luther King Jr Blvd	US 29 Graham St	SR 5427 S Mint St	0.10	Rejuvenator	$3,300
2030	10	060-Mecklenburg	Preservation	SR 5469 Shopton Rd	NC 160	Pleasant Way Ln	1.15	Microsurface	$45,000
2030	10	060-Mecklenburg	Preservation	SR 5702 Wilson Dr	Davis Dr	cul de sac	0.73	Rejuvenator	$11,000
2030	10	060-Mecklenburg	Preservation	SR 5772 Bridel Trace Lane	SR 5766 Aden Creek Way	EOM	0.58	Rejuvenator	$9,400
2030	10	084-Stanly	Resurfacing	NC 205 N Main St	East 10th St	NC 24/27 E Red Cross Rd	3.06	1.5" S9.5C	$841,500
2030	10	084-Stanly	Resurfacing	NC 49	.10 miles past James St	SR 1005 High Rock Rd	0.57	1.5" S9.5C	$303,883
2030	10	084-Stanly	Resurfacing	NC 49	County Line	.10 miles past James St	3.70	1.5" S9.5C	$1,017,500
2030	10	084-Stanly	Resurfacing	NC 73	SR 1134 Millingport Rd	SR 1244 Hatley Farm rd	3.95	1.5" S9.5C	$1,097,250
2030	10	084-Stanly	Resurfacing	NC 742	Union Co Line	West Thomas Ave	3.04	1.5" S9.5C	$1,150,633
2030	10	084-Stanly	Resurfacing	SR 1227 Ridgecrest Rd	SR 1214 Austin rd	NC 24/24 E Red Cross Rd	1.97	1.5" S9.5B	$492,500
2030	10	084-Stanly	Preservation	SR 1001 Love Mill/ Love Chapel Rd	Union Co Line	SR 1145 River Rd	4.45	Seal - Double	$135,000
2030	10	084-Stanly	Preservation	SR 1117 Griffin Greene Blvd	SR 1130 Big Lick Rd	SR 1115 Oak Grove Rd	0.98	Seal - Double	$38,000
2030	10	084-Stanly	Preservation	SR 1145 River Rd	SR 1140 Renee Ford Rd	SR 1001 Love Chapel Rd	1.51	Seal - Double	$54,000
2030	10	084-Stanly	Preservation	SR 1145 River Rd	Cabarrus Co Line	.07 Miles East of Cabarrus Co line	0.07	Seal - Double	$3,000
2030	10	084-Stanly	Preservation	SR 1145 River Rd	.07 East of Cabarrus Co Line	SR 1140 Renee Ford Rd	1.14	Seal - Double	$40,000
2030	10	084-Stanly	Preservation	SR 1169 Sedgefield Circle	NC 200	EOM	0.20	Seal - Double	$8,000
2030	10	084-Stanly	Preservation	SR 1170 Sedgefield Circle	NC 200	EOM	0.19	Seal - Double	$8,000
2030	10	084-Stanly	Preservation	SR 1172 Kennel Rd	SR 1130 Big Lick rd	EOM	0.16	Seal - Double	$8,000
2030	10	084-Stanly	Preservation	SR 1734 Anderson/ Ed's Rd	NC 24/27/73	EOM	0.73	Seal - Double	$26,000
2030	10	084-Stanly	Preservation	SR 1741 Dennis Rd	SR 1740 Indian Mound Rd	US 52 Hwy	3.25	Seal - Double	$130,000
2030	10	084-Stanly	Preservation	SR 1795 Vineyard Rd	SR 1755 Berry Hill Dr	SR 1757 Brookside Dr	0.28	Seal - Double	$10,000
2030	10	084-Stanly	Preservation	SR 1796 Vincent St	SR 1755 Berry Hill Dr	EOM	0.35	Seal - Double	$13,000
2030	10	084-Stanly	Preservation	SR 1816 Woodhurst Lane	SR 1783 Henson St	Anderson Rd	0.56	Seal - Double	$28,000
2030	10	084-Stanly	Preservation	SR 1820 Sterling Drive	SR 1816 Woodhurst Lane	EOM	0.21	Seal - Double	$7,350
2030	10	084-Stanly	Preservation	SR 1826 post Rd	Anderson Rd	EOM	0.08	Seal - Double	$4,000
2030	10	084-Stanly	Preservation	SR 1839 Nicks Rd	SR 1797 Lake Shore Drive	EOM	0.25	Seal - Double	$10,000
2030	10	084-Stanly	Preservation	SR 1906 Southside Rd	NC 138	Paving joint west of US 52	0.46	Seal - Double	$16,100
2030	10	084-Stanly	Preservation	SR 1914 Cooper Rd	SR 1913 Swaringen Rd	NC 138	1.72	Seal - Double	$60,200
2030	10	084-Stanly	Preservation	SR 1917 Silver Springs Rd	SR 1919 Chapel Rd	NC 138	2.37	Seal - Double	$84,795
2030	10	084-Stanly	Preservation	SR 1919 Chapel Rd	SR 1918 Cottonville Rd	SR 1920 Ward Rd	1.11	Seal - Double	$39,000
2030	10	084-Stanly	Preservation	SR 1928 Richardson/ Dupree rd	SR 1927 Brickyard Rd	EOM	0.35	Seal - Double	$15,685
2030	10	084-Stanly	Preservation	SR 1930 Stanly Grove Ch Rd	SR 1927 Brickyard Rd	EOM	0.17	Seal - Double	$5,000
2030	10	084-Stanly	Preservation	SR 1940 Rocky River Springs Rd	SR 1935 Plank Rd	SR 1918 Cottonville Rd	2.53	Seal - Double	$95,000
2030	10	084-Stanly	Preservation	SR 1941 Eddins Poplin Rd	SR 1918 Cottonville Rd	SR 1940 Rocky River Springs rd	1.47	Seal - Double	$63,000
2030	10	084-Stanly	Preservation	SR 1942 Aldridge Rd	SR 1935 Plank Rd	SR 1943 Old Davis Rd	1.49	Seal - Double	$59,000
2030	10	084-Stanly	Preservation	SR 1957 Tyson Rd	SR 1956 Old Aquadale Rd	SR 1957 Cross Rd	2.12	Seal - Double	$74,200
2030	10	084-Stanly	Preservation	SR 1958 Tyson Rd	SR 1957 Cross Rd	NC 138	0.57	Seal - Double	$20,000
2030	10	084-Stanly	Preservation	SR 1960 Mabry Rd	SR 1984 Union Grove Rd	SR 1956 Old Aquadale Rd	0.66	Seal - Double	$28,000
2030	10	084-Stanly	Preservation	SR 1987 Old Rd	SR 1927 Brickyard Rd	EOM	0.09	Seal - Double	$6,000
2030	10	084-Stanly	Preservation	SR 2013 Halfway Rd	SR 1918 Cottonville Rd	EOM	0.51	Seal - Double	$20,000
2030	10	084-Stanly	Preservation	SR 2031 Dale Rd	SR 1927 Brickyard Rd	EOM	0.08	Seal - Double	$5,000
2030	10	084-Stanly	Preservation	SR 2047 Moose Rd	SR 1837 S Business 52	EOM	0.38	Seal - Double	$14,300
2030	10	090-Union	Resurfacing	NC 200 N	Honey Bee	Roundabout	1.82	1.5" S9.5C	$802,620
2030	10	090-Union	Resurfacing	NC 218	Anson County	Bunn Simpson	2.90	1.5" S9.5C	$1,278,900
2030	10	090-Union	Resurfacing	SR 1001 Sikes Mill Rd	US 601 N	Tom Boyd	3.46	1.5" S9.5B	$1,271,550
2030	10	090-Union	Resurfacing	SR 1004 Lawyers Rd	Stevens Mill	Mill Grove Rd	1.90	1.5" S9.5B	$837,900
2030	10	090-Union	Resurfacing	SR 1006 Olive Branch Rd	NC 218	Burnsville Rd	0.25	1.5" S9.5B	$91,875

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	10	090-Union	Resurfacing	SR 1007 Rocky River Rd	Doster Rd	Pave JT	2.64	1.5" S9.5B	$1,164,240
2030	10	090-Union	Resurfacing	SR 1009 Old Charlotte Hwy	Rocky River Rd	Wesley Chapel Stouts	2.76	Microsurface	$139,104
2030	10	090-Union	Resurfacing	SR 1316 Rea Rd	SR 3286 Tom Short Rd	SR 2948 Marvin School Rd	0.62	Microsurface	$26,784
2030	10	090-Union	Resurfacing	SR 1316 Rea Rd	SR 2948 Marvin School Rd	SR 3286 Tom Short Rd	0.62	Microsurface	$24,552
2030	10	090-Union	Resurfacing	SR 1525 Mill Grove Rd	Lawyers Rd	Crismark Dr	1.52	1.5" S9.5B	$670,320
2030	10	090-Union	Resurfacing	SR 1627 New Salem Rd	Rilla Hampton	Lawyers Rd	1.55	1.5" S9.5B	$626,588
2030	10	090-Union	Resurfacing	SR 1719 Marshville-Olive Branch Rd	Burnsville Rd	Ansonville Rd	2.70	1.5" S9.5B	$992,250
2030	10	090-Union	Resurfacing	SR 2146 Plyler Mill Rd	NC 200 S	Griffith Rd	3.12	1.5" S9.5B	$1,146,600
2030	10	090-Union	Resurfacing	SR 2156 Austin Rd	Trinity Church Rd	SC line	1.70	1.5" S9.5B	$562,275
2030	10	090-Union	Resurfacing	SR 2166 Trinity Church Rd	NC 522	Plyler Mill Rd	1.80	1.5" S9.5B	$595,350
2030	10	090-Union	Resurfacing	SR 2180 W Sunset Dr	Griffith Rd	S Hayne St	0.37	Microsurface	$13,320
2030	10	090-Union	Resurfacing	SR 2181 E Sunset Dr	S Hayne St	E Franklin St	1.65	Microsurface	$59,400
2030	10	090-Union	Resurfacing	SR 2188 Charles St	E Sunset Dr	E Franklin St	0.58	Microsurface	$18,792
2030	10	090-Union	Resurfacing	SR 3700 Campobello Dr	Stonington Dr	Stonington Dr	0.78	1.5" S9.5B	$257,985
2030	10	090-Union	Resurfacing	US 601 S	US 74	Median	1.52	1.5" S9.5C	$1,686,825
2030	10	090-Union	Rehabilitation	SR 1380 Brickyard Rd	SR 1009 Old Charlotte Hwy	eom	0.43	FDR and 1.0" S9.5A and Widen	$200,000
2030	10	090-Union	Rehabilitation	SR 1934 Camden Rd	SR 1903 Gilboa Rd	SR 1937 Old Pageland Marshville R	1.77	FDR and 1.0" S9.5A and Widen	$796,500
2030	10	090-Union	Preservation	SR 1723 S C Helms Rd	SR 1719 Marshville/Olive Branch Rd	Anson County line	1.76	Seal - Double	$100,000
2030	10	090-Union	Preservation	SR 1727 Brice Griffin Rd	SR 1719 Marsh. Olive Branch	EOM	0.70	Seal - Double	$32,900
2030	11	003-Alleghany	Resurfacing	SR 1426	US 21	NC 18	4.23	Full Depth Patching and 1.5" S9.5B	$1,488,960
2030	11	003-Alleghany	Preservation	SR 1119	US 21	SR 1426	0.39	Seal - Triple and Fog Seal	$21,960
2030	11	003-Alleghany	Preservation	SR 1130	SR 1129	EOM	1.35	Seal - Triple and Fog Seal	$114,640
2030	11	003-Alleghany	Preservation	SR 1136	NC 18	NC 18	1.03	Seal - Triple and Fog Seal	$96,680
2030	11	003-Alleghany	Preservation	SR 1137	SR 1136	SR 1136	1.35	Seal - Triple and Fog Seal	$114,050
2030	11	003-Alleghany	Preservation	SR 1199	SR 1137	EOM	0.15	Seal - Triple and Fog Seal	$11,260
2030	11	003-Alleghany	Preservation	SR 1208	SR 1131	SR 1207	0.14	Seal - Triple and Fog Seal	$11,830
2030	11	003-Alleghany	Preservation	SR 1304	SR 1303	NC 113	1.20	Seal - Triple and Fog Seal	$101,380
2030	11	003-Alleghany	Preservation	SR 1403	SR 1418	GRAYSON ST	0.89	Seal - Triple and Fog Seal	$75,190
2030	11	003-Alleghany	Preservation	SR 1507	NC 18	EOM	0.36	Seal - Triple and Fog Seal	$33,790
2030	11	003-Alleghany	Preservation	SR 1513	SR 1507	EOM	0.13	Seal - Triple and Fog Seal	$12,200
2030	11	005-Ashe	Resurfacing	SR 1134	SR 1133	US 221 Bus	0.89	1.5" S9.5B	$281,000
2030	11	005-Ashe	Resurfacing	SR 1514	SR 1501	NC 194	1.48	1.5" S9.5B	$521,000
2030	11	005-Ashe	Resurfacing	SR 1549	BEG PVMT	SR 1560	0.20	1.5" S9.5B	$70,500
2030	11	005-Ashe	Resurfacing	SR 1568	SR 1567	SR 1567	2.38	1.5" S9.5B	$754,000
2030	11	005-Ashe	Resurfacing	SR 1571	SR 1572	NC 16	0.53	1.5" S9.5B	$149,000
2030	11	005-Ashe	Resurfacing	SR 1581	US 221	EOM	0.44	1.5" S9.5B	$124,000
2030	11	005-Ashe	Resurfacing	SR 1595	SR 1593	SR 1599	2.22	1.5" S9.5B	$703,300
2030	11	005-Ashe	Resurfacing	SR 1663	SR 1581	EOM	0.24	1.5" S9.5B	$76,000
2030	11	005-Ashe	Resurfacing	SR 1670	SR 1583	AIRPORT Entrance	0.53	1.5" S9.5B	$186,500
2030	11	005-Ashe	Preservation	SR 1324	SR 1354	SR 1334	3.14	Seal - Triple and Fog Seal	$176,845
2030	11	005-Ashe	Preservation	SR 1337	SR 1352	EOM	0.91	Seal - Triple and Fog Seal	$68,335
2030	11	005-Ashe	Preservation	SR 1347	SR 1342	SR 1349	2.12	Seal - Triple and Fog Seal	$198,997
2030	11	005-Ashe	Preservation	SR 1350	SR 1347	NC 194	1.06	Seal - Triple and Fog Seal	$89,549
2030	11	005-Ashe	Preservation	SR 1371	SR 1370	SR 1358	1.72	Seal - Triple and Fog Seal	$145,306
2030	11	005-Ashe	Preservation	SR 1394	END PVMT	SR 1352	2.34	Seal - Triple and Fog Seal	$197,683
2030	11	006-Avery	Resurfacing	NC 105	MP 3.5	Watauga Co	2.11	Full Depth Patching and 1.5" S9.5C	$1,114,000
2030	11	006-Avery	Resurfacing	SR 1101	US 19E	Pavement Width Change	0.76	Full Depth Patching and 1.5" S9.5B	$280,890
2030	11	006-Avery	Resurfacing	SR 1101	Pavement Width Change	EOM	1.54	Full Depth Patching and 1.5" S9.5B	$514,980
2030	11	006-Avery	Resurfacing	SR 1120	SR 1114	EOM	1.21	1.5" S9.5B	$340,740
2030	11	006-Avery	Resurfacing	SR 1143	US 221	WCL CROSSNORE	0.96	1.5" S9.5B	$304,130
2030	11	006-Avery	Preservation	SR 1103	US 19E	EOP	1.10	Seal - Triple and Fog Seal	$103,250
2030	11	006-Avery	Preservation	SR 1110	NC 194	EOM	1.41	Seal - Triple and Fog Seal	$105,880
2030	11	006-Avery	Preservation	SR 1186	SR 1166	EOM	0.20	Seal - Triple and Fog Seal	$15,020
2030	11	014-Caldwell	Resurfacing	RMP 2279	SR 1933 NB	US 321 NB Gore	0.20	Mill 1.5" and 1.5" S9.5C	$77,440
2030	11	014-Caldwell	Resurfacing	SR 1002	ALEXANDER	SR 1734	2.35	1.5" S9.5B	$744,480
2030	11	014-Caldwell	Resurfacing	SR 1107	Br # 262	SR 1751	2.26	1.5" S9.5B	$795,520
2030	11	014-Caldwell	Resurfacing	SR 1715	SR 1712	SR 1160	0.88	1.5" S9.5B	$278,780
2030	11	014-Caldwell	Resurfacing	SR 1741	SR 1002	CO LINE	1.88	1.5" S9.5B	$595,580
2030	11	014-Caldwell	Resurfacing	SR 1756	SR 1740	Br #099 over Upper Little River	1.33	Full Depth Patching and 1.5" S9.5C	$468,160

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	11	014-Caldwell	Resurfacing	SR 1757	SR 1751	SR 1751	2.35	Full Depth Patching and 1.5" S9.5C	$827,200
2030	11	014-Caldwell	Resurfacing	SR 1850	SR 1751	CUL-DE-SAC	0.63	1.5" S9.5B	$199,580
2030	11	014-Caldwell	Resurfacing	SR 1892	SR 1850	CUL-DE-SAC	0.20	1.5" S9.5B	$63,360
2030	11	014-Caldwell	Resurfacing	SR 1933 NB	SR 1001	Ramp 2279	1.99	Mill 1.5" and 1.5" S9.5C	$1,020,800
2030	11	014-Caldwell	Resurfacing	SR 1933 SB	Ramp 2280/US 321 NB Off Ramp	SR 1001	2.05	Mill 1.5" and 1.5" S9.5C	$1,046,320
2030	11	014-Caldwell	Preservation	SR 1501	SR 1504	WILKES Co Line	1.48	Seal - Triple and Fog Seal	$138,923
2030	11	014-Caldwell	Preservation	SR 1505	NC 268	SR 1504	3.15	Seal - Triple and Fog Seal	$221,700
2030	11	014-Caldwell	Preservation	SR 1506	SR 1505	EOM	1.77	Seal - Triple and Fog Seal	$112,200
2030	11	014-Caldwell	Preservation	SR 1712	BEG 20'	US 64	1.12	Seal - Triple and Fog Seal	$131,400
2030	11	014-Caldwell	Preservation	SR 1712	SR 1718	BEG 20'	0.69	Seal - Triple and Fog Seal	$72,800
2030	11	014-Caldwell	Preservation	SR 1717	SR 1809	SR 1718	1.79	Seal - Triple and Fog Seal	$210,000
2030	11	014-Caldwell	Preservation	SR 1748	SR 1751	SR 1718	0.80	Seal - Triple and Fog Seal	$65,000
2030	11	014-Caldwell	Preservation	SR 1829	SR 1717	EOM	0.14	Seal - Triple and Fog Seal	$10,513
2030	11	086-Surry	Resurfacing	NC 103	SR 1748 WEST INT	VA STATE LINE	4.81	1.5" S9.5B	$1,861,270
2030	11	086-Surry	Resurfacing	NC 104	NC 103	Brunswick Ln (NS)	0.25	Mill 1.5" and 1.5" S9.5B	$264,000
2030	11	086-Surry	Resurfacing	NC 104	Brunswick Ln (NS)	End of Widening NE of SR 1716	1.94	Full Depth Patching and 1.5" S9.5B	$1,365,760
2030	11	086-Surry	Resurfacing	NC 104	End of Widening NE of SR 1716	Br # 34	0.59	Full Depth Patching and 1.5" S9.5B	$249,216
2030	11	086-Surry	Resurfacing	SR 1727	NC 104	NC 103	1.48	1.5" S9.5B	$573,056
2030	11	086-Surry	Resurfacing	US 52	Hickory St (NS)	Begin Auxiliary Turn Lane at SR 1701	2.15	Mill 1.5" and 1.5" S9.5C	$1,135,200
2030	11	086-Surry	Preservation	SR 1129	SR 1001	SR 1122	1.11	Seal - Triple and Fog Seal	$104,192
2030	11	086-Surry	Preservation	SR 1301	SR 1302	SR 1307	2.37	Seal - Triple and Fog Seal	$200,218
2030	11	086-Surry	Preservation	SR 1338	NC 89	SR 1331	5.10	Seal - Triple and Fog Seal	$478,720
2030	11	086-Surry	Preservation	SR 1408	NC 89	SR 1338	5.61	Seal - Triple and Fog Seal	$526,592
2030	11	086-Surry	Preservation	SR 1716	NC 104	SR 1708	0.58	Seal - Triple and Fog Seal	$48,998
2030	11	086-Surry	Preservation	SR 2057	SR 2048	SR 2080	2.94	Seal - Triple and Fog Seal	$275,968
2030	11	095-Watauga	Resurfacing	SR 1131	BRIDGE # 0140	NC 194	0.95	1.5" S9.5B	$300,960
2030	11	095-Watauga	Resurfacing	SR 1136	SR 1138	SR 1137	1.24	1.5" S9.5B	$392,832
2030	11	095-Watauga	Resurfacing	SR 1524	SR 1523	SR 1608	1.12	1.5" S9.5B	$394,240
2030	11	095-Watauga	Resurfacing	SR 1552	NC 105	SR 1557	3.82	1.5" S9.5B	$1,210,176
2030	11	095-Watauga	Resurfacing	SR 1600	SR 1511	EOM	1.21	Leveling and 1.5" S9.5B	$383,330
2030	11	095-Watauga	Resurfacing	US 321	SR 1211	SR 1238	1.77	Full Depth Patching and 1.5" S9.5C	$778,800
2030	11	095-Watauga	Preservation	SR 1110	SR 1107	US 321	0.66	Seal - Triple and Fog Seal	$55,757
2030	11	095-Watauga	Preservation	SR 1113	SR 1109	SR 1114	1.14	Seal - Triple and Fog Seal	$96,307
2030	11	095-Watauga	Preservation	SR 1122	NC 194	SR 1166	1.76	Seal - Triple and Fog Seal	$148,685
2030	11	095-Watauga	Preservation	SR 1125	SR 1128	END PVMT	2.67	Seal - Triple and Fog Seal	$225,562
2030	11	095-Watauga	Preservation	SR 1153	SR 1125	DE	0.40	Seal - Triple and Fog Seal	$30,037
2030	11	095-Watauga	Preservation	SR 1532	US 221/US 321	EOM	1.14	Seal - Triple and Fog Seal	$101,658
2030	11	097-Wilkes	Resurfacing	NC 115	IREDELL	SR 2412	1.66	1.5" S9.5B	$701,185
2030	11	097-Wilkes	Resurfacing	NC 268	SR 1137	SR 1141	3.73	1.5" S9.5B	$1,509,904
2030	11	097-Wilkes	Resurfacing	SR 1194	NC 18	NC 16/NC 18	2.33	1.5" S9.5B	$820,160
2030	11	097-Wilkes	Resurfacing	SR 1322	US 421	SR 1325	1.99	1.5" S9.5B	$630,430
2030	11	097-Wilkes	Resurfacing	SR 1346	SR 1317	SR 1304	0.73	Leveling and 1.5" S9.5B	$218,410
2030	11	097-Wilkes	Resurfacing	SR 1957	SR 1959	NC 268	2.76	1.5" S9.5B	$971,520
2030	11	097-Wilkes	Resurfacing	SR 1971	SR 2162	NC 268	1.10	1.5" S9.5B	$385,440
2030	11	097-Wilkes	Resurfacing	SR 2018	SR 1924	NC 268	2.56	Mill 1.5" and 1.5" S9.5B and Full Depth Patching	$901,120
2030	11	097-Wilkes	Preservation	SR 1001	SR 2478	SR 2494	1.98	Seal - Triple and Fog Seal	$148,685
2030	11	097-Wilkes	Preservation	SR 1102	SR 1194	EOM	0.59	Seal - Triple and Fog Seal	$55,381
2030	11	097-Wilkes	Preservation	SR 1105	SR 1103	EOM	0.49	Seal - Triple and Fog Seal	$41,395
2030	11	097-Wilkes	Preservation	SR 1108	SR 1202	2ND BRIDGE	1.24	Seal - Triple and Fog Seal	$116,395
2030	11	097-Wilkes	Preservation	SR 1110	NC 16	END PVMT	3.35	Seal - Triple and Fog Seal	$282,755
2030	11	097-Wilkes	Preservation	SR 1119	SR 1117	SR 1114	2.21	Seal - Triple and Fog Seal	$186,701
2030	11	097-Wilkes	Preservation	SR 1146	SR 1147	US 421	0.77	Seal - Triple and Fog Seal	$65,050
2030	11	097-Wilkes	Preservation	SR 1146	US 421	EOM	1.44	Seal - Triple and Fog Seal	$135,168
2030	11	097-Wilkes	Preservation	SR 1155	SR 1158	BRIDGE	3.68	Seal - Triple and Fog Seal	$310,886
2030	11	097-Wilkes	Preservation	SR 1155	SR 1168	SR 1167	2.54	Seal - Triple and Fog Seal	$238,421
2030	11	097-Wilkes	Preservation	SR 1208	SR 1148	SR 1149	0.21	Seal - Triple and Fog Seal	$17,741
2030	11	097-Wilkes	Preservation	SR 1387	SR 1337	SR 1388	0.16	Seal - Triple and Fog Seal	$13,517
2030	11	099-Yadkin	Resurfacing	SR 1103	US 21	SR 1323	1.46	1.5" S9.5B	$462,530
2030	11	099-Yadkin	Resurfacing	SR 1103	SR 1323	SR 1314	1.90	1.5" S9.5B	$668,800

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	11	099-Yadkin	Resurfacing	SR 1165	US 601	SR 1002	1.81	1.5" S9.5B	$573,400
2030	11	099-Yadkin	Resurfacing	SR 1314	US 601	End 3-Lane	0.60	1.5" S9.5B	$443,520
2030	11	099-Yadkin	Resurfacing	SR 1536	SR 1537	SR 1003 N	1.90	1.5" S9.5B	$668,800
2030	11	099-Yadkin	Resurfacing	SR 1605	SR 1634	SR 1700	0.50	Mill 1.5" and 1.5" S9.5B	$212,460
2030	11	099-Yadkin	Resurfacing	SR 1605	SR 1700	US 601	0.17	Mill 1.5" and 1.5" S9.5B	$129,320
2030	11	099-Yadkin	Resurfacing	SR 1765	SR 1146	SR 1605	0.78	1.5" S9.5B	$328,200
2030	11	099-Yadkin	Resurfacing	SR 1765	SR 1742	SR 1146	0.55	1.5" S9.5B	$348,480
2030	11	099-Yadkin	Preservation	SR 1102	SR 1126	SR 1129	1.10	Seal - Triple and Fog Seal	$103,253
2030	11	099-Yadkin	Preservation	SR 1102	SR 1129	SR 1100	2.01	Seal - Triple and Fog Seal	$127,300
2030	11	099-Yadkin	Preservation	SR 1102	SR 1100	Iredell Co. Line	0.75	Seal - Triple and Fog Seal	$52,800
2030	11	099-Yadkin	Preservation	SR 1105	Wilkes Co. Line	SR 1100	1.08	Seal - Triple and Fog Seal	$76,000
2030	11	099-Yadkin	Preservation	SR 1106	Begin Pavement	Wilkes Co Line	0.09	Seal - Triple and Fog Seal	$8,000
2030	11	099-Yadkin	Preservation	SR 1109	WILKES CO LINE	SR 1217	0.98	Seal - Triple and Fog Seal	$62,100
2030	11	099-Yadkin	Preservation	SR 1115	SR 1100	DE	1.10	Seal - Triple and Fog Seal	$73,500
2030	11	099-Yadkin	Preservation	SR 1120	SR 1119	SR 1122	1.21	Seal - Triple and Fog Seal	$85,100
2030	11	099-Yadkin	Preservation	SR 1126	SR 1102	US 21	0.56	Seal - Triple and Fog Seal	$39,400
2030	11	099-Yadkin	Preservation	SR 1364	SR 1363	END MAINT	0.88	Seal - Triple and Fog Seal	$111,500
2030	12	002-Alexander	Resurfacing	SR 1005	SR 1628	Iredell County Line	1.42	1.0" S9.5B	$156,541
2030	12	002-Alexander	Resurfacing	SR 1131	SR 1124 Church Rd	NC 16	2.33	1.5" S9.5B	$324,849
2030	12	002-Alexander	Resurfacing	SR 1137	NC 127	SR 1135 Wayside Church Rd	7.18	1.5" S9.5B	$1,051,087
2030	12	002-Alexander	Resurfacing	SR 1141	SR 1208 Shiloh Church Rd	SR 1143 Hubbard Rd	0.89	1.5" S9.5B	$124,084
2030	12	002-Alexander	Resurfacing	SR 1154	SR 1153 Devil Track Rd	SR 1153 Devil Track Rd	0.89	1.5" S9.5B	$124,641
2030	12	002-Alexander	Resurfacing	SR 1331	NC 16	SR 1332 Shew Rd	3.57	1.5" S9.5B	$522,616
2030	12	002-Alexander	Resurfacing	SR 1338	NC 16	SR 1332 Little River Church Rd	1.89	1.5" S9.5B	$250,329
2030	12	002-Alexander	Resurfacing	SR 1404	SR 1403Vashti Rd	SR 1412 Black Oak Ridge Rd	2.18	1.5" S9.5B	$303,378
2030	12	002-Alexander	Resurfacing	SR 1412	SR 1403 Vashti Rd	End Maintenance	7.12	1.5" S9.5B	$1,042,158
2030	12	002-Alexander	Resurfacing	SR 1500	SR 1498 Goble Rd	NC 90	0.79	1.5" S9.5B	$110,142
2030	12	002-Alexander	Resurfacing	SR 1628	US 64	SR 1005	0.83	1.0" S9.5B	$75,150
2030	12	002-Alexander	Resurfacing	US 64	SR 1349 Bumgarner Ln	SR 1348 Old NC 90	3.90	Mill 2.0" and 2.0" S9.5C	$931,913
2030	12	002-Alexander	Preservation	SR 1150	NC 127	SR 1124	6.07	Seal - Double	$212,450
2030	12	002-Alexander	Preservation	SR 1151	SR 1137	SR 1150	0.88	Seal - Double and Fog Seal	$29,920
2030	12	002-Alexander	Preservation	SR 1165	SR 1002	US 64	1.61	Seal - Double and Fog Seal	$54,774
2030	12	002-Alexander	Preservation	SR 1166	NC 127	NC 127	1.95	Seal - Double and Fog Seal	$66,300
2030	12	002-Alexander	Preservation	SR 1318	SR 1313	SR 1307	3.58	Seal - Double and Fog Seal	$125,160
2030	12	002-Alexander	Preservation	SR 1423	SR 1425	SR 1403	5.02	Seal - Double and Fog Seal	$170,646
2030	12	002-Alexander	Preservation	SR 1425	SR 1412	SR 1419	4.64	Seal - Double and Fog Seal	$162,330
2030	12	002-Alexander	Preservation	SR 1458	SR 1001	SR 1460	1.74	Seal - Double and Fog Seal	$60,970
2030	12	002-Alexander	Preservation	SR 1468	SR 1467	Iredell County Line	0.45	Seal - Double	$15,750
2030	12	002-Alexander	Preservation	SR 1631	SR 1631	SR 1617	2.00	Seal - Double and Fog Seal	$70,000
2030	12	018-Catawba	Resurfacing	NC 16	SR 1801	I 40	5.73	Mill 1.5" and 1.5" S9.5C	$1,117,350
2030	12	018-Catawba	Resurfacing	NC 16	I 40	SR 1801	5.20	Mill 1.5" and 1.5" S9.5C	$1,014,000
2030	12	018-Catawba	Resurfacing	SR 1003	NC 16	NC 10	6.21	Full Depth Patching and 1.5" S9.5B	$1,552,000
2030	12	018-Catawba	Resurfacing	SR 1003	NC 10	Lincoln County	4.81	Full Depth Patching and 1.5" S9.5C	$1,202,500
2030	12	018-Catawba	Resurfacing	SR 1776	SR 1734	SR 1734	0.88	Full Depth Patching and 1.5" S9.5B	$219,750
2030	12	018-Catawba	Resurfacing	SR 1783	SR 1709	END MAINT	0.23	Full Depth Patching and 1.5" S9.5B	$57,500
2030	12	018-Catawba	Resurfacing	SR 1787	SR 1732	SR 1732	0.23	Full Depth Patching and 1.5" S9.5B	$57,500
2030	12	018-Catawba	Resurfacing	SR 1799	SR 2400	END MAINT	0.11	Patching and 1.0" S9.5A	$26,500
2030	12	018-Catawba	Resurfacing	SR 1822	SR 1848	BRIDGE	2.22	Full Depth Patching and 1.5" S9.5B	$555,000
2030	12	018-Catawba	Resurfacing	SR 1899	SR 1844	END MAINT	0.50	Full Depth Patching and 1.5" S9.5B	$124,750
2030	12	018-Catawba	Resurfacing	SR 1918	SR 1849	SR 1919	0.45	Patching and 1.0" S9.5A	$112,500
2030	12	018-Catawba	Resurfacing	SR 1932	SR 1849	DEAD END	0.84	Patching and 1.0" S9.5A	$210,000
2030	12	018-Catawba	Resurfacing	SR 1974	US 321 BUS	END MAINT	0.38	Patching and 1.0" S9.5A	$95,000
2030	12	018-Catawba	Resurfacing	SR 1990	END MAINT	DEAD END	0.34	Patching and 1.0" S9.5A	$85,000
2030	12	018-Catawba	Resurfacing	SR 1991	END MAINT	DEAD END	0.33	Patching and 1.0" S9.5A	$52,800
2030	12	018-Catawba	Resurfacing	SR 1992	DEAD END	SR 1874	0.21	Patching and 1.0" S9.5A	$52,500
2030	12	018-Catawba	Resurfacing	SR 1994	SR 1731	END MAINT	0.30	Patching and 1.0" S9.5A	$74,500
2030	12	018-Catawba	Resurfacing	SR 2126	SR 1732	SR 2127	0.18	Patching and 1.0" S9.5A	$44,000
2030	12	018-Catawba	Resurfacing	SR 2127	SR 2126	DEAD END	0.09	Patching and 1.0" S9.5A	$22,500
2030	12	018-Catawba	Resurfacing	SR 2400	SR 1799	DEAD END	0.19	Patching and 1.0" S9.5A	$47,250

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	12	018-Catawba	Resurfacing	SR 2401	SR 1715	CDS	0.37	Full Depth Patching and 1.25" S9.5A	$91,250
2030	12	018-Catawba	Resurfacing	SR 2404	NC 16	DEAD END	0.23	1.25" SF9.5A	$57,000
2030	12	018-Catawba	Resurfacing	SR 2411	NC 16	SR 1711	0.24	1.25" SF9.5A	$58,750
2030	12	018-Catawba	Resurfacing	SR 2443	END MAINT	DEAD END	0.34	Patching and 1.0" S9.5A	$85,000
2030	12	018-Catawba	Resurfacing	SR 2450	SR 1702	DEAD END	0.37	Patching and 1.0" S9.5A	$92,500
2030	12	018-Catawba	Resurfacing	SR 2454	SR 1707	DEAD END	0.35	Patching and 1.0" S9.5A	$87,250
2030	12	018-Catawba	Resurfacing	SR 2459	SR 1714	SR 2420	0.17	Patching and 1.0" S9.5A	$42,500
2030	12	018-Catawba	Resurfacing	SR 2637	SR 1003	END MAINT	0.81	Patching and 1.0" S9.5A	$202,000
2030	12	018-Catawba	Resurfacing	SR 2679	SR 1731	END MAINT	0.41	Patching and 1.0" S9.5A	$101,500
2030	12	018-Catawba	Resurfacing	SR 2690	SR 2717	END MAINT	0.59	Patching and 1.0" S9.5A	$147,500
2030	12	018-Catawba	Resurfacing	SR 2730	SR 1802	SR 1805	0.21	Patching and 1.0" S9.5A	$52,500
2030	12	018-Catawba	Resurfacing	SR 2756	SR 1880	DEAD END	0.16	Patching and 1.0" S9.5A	$39,250
2030	12	018-Catawba	Resurfacing	SR 2758	SR 1806	DEAD END	0.22	Patching and 1.0" S9.5A	$55,000
2030	12	018-Catawba	Resurfacing	SR 2772	SR 1837	DEAD END	0.36	Patching and 1.0" S9.5A	$90,000
2030	12	018-Catawba	Resurfacing	SR 2787	SR 2778	DEAD END	0.10	Patching and 1.0" S9.5A	$25,000
2030	12	018-Catawba	Resurfacing	SR 3106	SR 1853	END MAINT	0.43	Patching and 1.0" S9.5A	$107,250
2030	12	018-Catawba	Resurfacing	SR 3107	SR 3105	DEAD END	0.20	Patching and 1.0" S9.5A	$49,000
2030	12	018-Catawba	Resurfacing	SR 3117	SR 1832	DEAD END	0.51	Patching and 1.0" S9.5A	$126,750
2030	12	018-Catawba	Resurfacing	SR 3125	SR 1838	DEAD END	0.79	Patching and 1.0" S9.5A	$196,250
2030	12	018-Catawba	Resurfacing	SR 3126	SR 3125	DEAD END	0.23	Patching and 1.0" S9.5A	$57,500
2030	12	018-Catawba	Preservation	SR 1226	SR 1148	SR 1245	0.25	.75" S4.75A	$28,000
2030	12	018-Catawba	Preservation	SR 1245	SR 1148	Dead End	0.55	.75" S4.75A	$61,600
2030	12	018-Catawba	Preservation	SR 1819	SR 1833	SR 1004	1.66	Microsurface	$89,225
2030	12	018-Catawba	Preservation	SR 1833	SR 1832	Dead End	4.03	Microsurface	$216,612
2030	12	018-Catawba	Preservation	SR 1885	SR 1833	Dead End	2.17	Microsurface	$116,637
2030	12	018-Catawba	Preservation	SR 1904	SR 1833	SR 1848	0.33	Microsurface	$17,737
2030	12	018-Catawba	Preservation	SR 2502	SR 1148	SR 2503	0.18	.75" S4.75A	$20,160
2030	12	018-Catawba	Preservation	SR 2503	SR 2502	SR 2504	0.05	.75" S4.75A	$5,600
2030	12	018-Catawba	Preservation	SR 2504	SR 1148	Dead End	0.56	.75" S4.75A	$62,720
2030	12	018-Catawba	Preservation	SR 2596	SR 1245	SR 2596	0.89	.75" S4.75A	$99,680
2030	12	018-Catawba	Preservation	SR 2900	SR 1144	SR 2901	0.60	.75" S4.75A	$67,200
2030	12	018-Catawba	Preservation	SR 2901	SR 2900	SR 2933	0.39	.75" S4.75A	$43,680
2030	12	018-Catawba	Preservation	SR 2919	SR 2504	Dead End	0.22	.75" S4.75A	$25,640
2030	12	018-Catawba	Preservation	SR 2922	SR 1008	Cul-de-sac	0.62	.75" S4.75A	$69,440
2030	12	018-Catawba	Preservation	SR 2923	SR 2922	SR 2922	0.41	.75" S4.75A	$45,920
2030	12	018-Catawba	Preservation	SR 2924	Cul-de-sac	Cul-de-sac	0.24	.75" S4.75A	$26,880
2030	12	018-Catawba	Preservation	SR 2925	SR 2900	SR 2924	0.10	.75" S4.75A	$11,200
2030	12	018-Catawba	Preservation	SR 2928	SR 2596	SR 2596	0.09	.75" S4.75A	$10,080
2030	12	018-Catawba	Preservation	SR 2933	SR 2901	Cul-de-sac	0.03	.75" S4.75A	$3,360
2030	12	018-Catawba	Preservation	SR 2934	SR 2901	Cul-de-sac	0.04	.75" S4.75A	$4,480
2030	12	018-Catawba	Preservation	SR 2935	SR 2901	Cul-de-sac	0.04	.75" S4.75A	$4,480
2030	12	018-Catawba	Preservation	SR 2940	SR 2924	Cul-de-sac	0.03	.75" S4.75A	$3,360
2030	12	023-Cleveland	Resurfacing	U.S. 74	N.C. 150 (Dekalb St	utherford County line (Westbound	11.27	1.5" S9.5C	$4,020,000
2030	12	023-Cleveland	Resurfacing	U.S. 74	Rutherford County Line	N.C. 150 (Dekalb St) Eastbound	11.20	1.5" S9.5C	$4,480,000
2030	12	023-Cleveland	Preservation	S.R. 1612	NC 18	Lincoln Co	1.51	Seal - Double	$104,921
2030	12	023-Cleveland	Preservation	S.R. 1651	SR 1653	SR 1652	0.28	Seal - Double	$43,421
2030	12	023-Cleveland	Preservation	S.R. 1652	SR 1612	Lincoln Co	1.04	Seal - Double	$94,421
2030	12	023-Cleveland	Preservation	S.R. 1653	SR 1651	SR 1654	1.01	Seal - Double	$80,421
2030	12	023-Cleveland	Preservation	S.R. 1657	SR 1905	NC 182	1.78	Seal - Double	$118,421
2030	12	023-Cleveland	Preservation	SR 1600	NC 10	NC 18	1.31	Seal - Double	$76,000
2030	12	023-Cleveland	Preservation	SR 1604	NC 18	NC 10	1.92	Seal - Double	$95,500
2030	12	023-Cleveland	Preservation	SR 1606	1607	Lincoln Co	0.28	Seal - Double	$43,421
2030	12	023-Cleveland	Preservation	SR 1607	1608	NC 18	1.54	Seal - Double	$106,421
2030	12	023-Cleveland	Preservation	SR 1608	1609	Lincoln Co	0.74	Seal - Double	$98,504
2030	12	023-Cleveland	Preservation	SR 1611	SR 1612	SR 1609	0.94	Seal - Double	$86,421
2030	12	023-Cleveland	Preservation	SR 2429	SR 2276	DE	0.23	.75" S4.75A	$47,938
2030	12	036-Gaston	Resurfacing	NC 16 N	LIN CL	MECK CL	4.18	1.5" S9.5B	$850,000
2030	12	036-Gaston	Resurfacing	NC 16S	LIN CL	MECK CL	4.20	1.5" S9.5B	$850,000
2030	12	036-Gaston	Resurfacing	SE 2004	SR 2000	D END	0.88	1.5" S9.5B	$120,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	12	036-Gaston	Resurfacing	SR 1002	LINC CO.	NC 150	1.39	1.5" S9.5B	$244,100
2030	12	036-Gaston	Resurfacing	SR 1624	NC 279	SR 1622	2.75	1.5" S9.5B	$485,725
2030	12	036-Gaston	Resurfacing	SR 1805	SR1804	SR1802	1.49	1.5" S9.5B	$202,800
2030	12	036-Gaston	Resurfacing	SR 2016	US 29/74	NC 7	0.48	1.5" S9.5B	$87,500
2030	12	036-Gaston	Resurfacing	SR 2032	SR 2040	SR 2033	0.52	1.5" S9.5B	$98,500
2030	12	036-Gaston	Resurfacing	SR 2275	SR 2278	NC 279	1.41	1.5" S9.5B	$200,000
2030	12	036-Gaston	Resurfacing	SR 2428	NC 274	SC	1.48	1.5" S9.5B and Widen	$350,000
2030	12	036-Gaston	Resurfacing	SR 2466	US 321	US 29	1.60	1.5" S9.5B	$650,000
2030	12	036-Gaston	Resurfacing	SR 3113	US 321	CDS	0.87	1.5" S9.5B	$104,600
2030	12	036-Gaston	Resurfacing	SR1923	BRIDGE	WOODLAWN	1.00	1.5" S9.5B	$139,000
2030	12	036-Gaston	Resurfacing	SR1923	WOODLAWN	SR2198	0.78	1.5" S9.5B	$106,600
2030	12	036-Gaston	Resurfacing	US 29/74	SR 1307	SR1136	1.83	1.5" S9.5B	$550,000
2030	12	036-Gaston	Resurfacing	us 29/74	SR1136	THOMAS ST/ BELVEDEER	3.68	1.5" S9.5B	$3,000,000
2030	12	036-Gaston	Resurfacing	US 29/74S	SR 1136	SR 1122	1.83	1.5" S9.5B	$440,100
2030	12	036-Gaston	Preservation	SR 1408	NC 274	SR 1401	1.62	Microsurface	$35,600
2030	12	036-Gaston	Preservation	SR 1441	SR 1440	SR 1474	0.82	Microsurface	$28,500
2030	12	036-Gaston	Preservation	SR 1617	LINC CO	LINC CO	2.28	Microsurface	$92,000
2030	12	036-Gaston	Preservation	SR 1699	SR 1508	CDS	0.51	Microsurface	$33,300
2030	12	036-Gaston	Preservation	SR 1716	LINC CO	ESM	0.17	Microsurface	$14,100
2030	12	036-Gaston	Preservation	SR 1754	SR 1699	D END	0.35	Microsurface	$15,100
2030	12	036-Gaston	Preservation	SR 1800	SR 1804	SR 1001	1.24	Microsurface	$65,800
2030	12	036-Gaston	Preservation	SR 1850	SR 1806	CDS	0.17	1.0" S9.5B	$12,200
2030	12	036-Gaston	Preservation	SR 1878	US 321B	D END	0.19	1.0" S9.5B	$14,500
2030	12	036-Gaston	Preservation	SR 1957	SR 1992	DE	0.89	Microsurface	$36,000
2030	12	036-Gaston	Preservation	SR 2085	SR 2197	SR 1924	0.32	1.0" S9.5B	$22,800
2030	12	036-Gaston	Preservation	SR 2105	SR 2050	SR 2107	0.46	1.0" S9.5B	$46,000
2030	12	036-Gaston	Preservation	SR 2114	SR 2196	SR 2167	0.88	1.0" S9.5B	$87,000
2030	12	036-Gaston	Preservation	SR 2118	SR 2000	D END	0.51	1.0" S9.5B	$51,000
2030	12	036-Gaston	Preservation	SR 2122	SR 2121	SR 2153	0.20	1.0" S9.5B	$21,000
2030	12	036-Gaston	Preservation	SR 2123	NC 7	END MAINT	0.10	1.0" S9.5B	$5,800
2030	12	036-Gaston	Preservation	SR 2125	SR 2003	SR 2126	0.23	1.0" S9.5B	$23,000
2030	12	036-Gaston	Preservation	SR 2126	SR 2125	SR 2127	0.14	1.0" S9.5B	$10,450
2030	12	036-Gaston	Preservation	SR 2127	SR 2128	D END	0.13	1.0" S9.5B	$13,000
2030	12	036-Gaston	Preservation	SR 2128	SR 2127	D END	0.09	1.0" S9.5B	$6,300
2030	12	036-Gaston	Preservation	SR 2131	SR 2092	SR 2092	0.24	1.0" S9.5B	$24,000
2030	12	036-Gaston	Preservation	SR 2132	SR 2000	SR 2133	0.16	1.0" S9.5B	$12,450
2030	12	036-Gaston	Preservation	SR 2147	SR 2041	CDS	0.21	1.0" S9.5B	$20,000
2030	12	036-Gaston	Preservation	SR 2148	SR 2147	DE	0.06	1.0" S9.5B	$5,000
2030	12	036-Gaston	Preservation	SR 2155	SR 2107	SR 2156	0.11	1.0" S9.5B	$10,000
2030	12	036-Gaston	Preservation	SR 2156	SR 2155	SR 2157	0.20	1.0" S9.5B	$20,000
2030	12	036-Gaston	Preservation	SR 2157	SR 2155	D END	0.35	1.0" S9.5B	$35,000
2030	12	036-Gaston	Preservation	SR 2159	SR 2050	sr SR 2188	0.28	1.0" S9.5B	$26,200
2030	12	036-Gaston	Preservation	SR 2160	SR 2000	END MAINT	0.34	1.0" S9.5B	$32,500
2030	12	036-Gaston	Preservation	SR 2164	SR 1827	D END	0.14	1.0" S9.5B	$10,500
2030	12	036-Gaston	Preservation	SR 2167	SR 2114	SR 2114	0.73	1.0" S9.5B	$73,000
2030	12	036-Gaston	Preservation	SR 2170	SR 2114	SR 2167	0.30	1.0" S9.5B	$30,000
2030	12	036-Gaston	Preservation	SR 2177	SR 2000	CDS	0.32	1.0" S9.5B	$32,100
2030	12	036-Gaston	Preservation	SR 2188	SR 2159	SR 2159	0.37	1.0" S9.5B	$23,000
2030	12	036-Gaston	Preservation	SR 2195	SR 2114	SR 2197	0.15	1.0" S9.5B	$11,500
2030	12	036-Gaston	Preservation	SR 2196	SR 1924	SR 2197	0.16	1.0" S9.5B	$12,000
2030	12	036-Gaston	Preservation	SR 2197	SR 2085	SR 2196	0.22	1.0" S9.5B	$21,000
2030	12	036-Gaston	Preservation	SR 2269	NC 279	NC 279	0.65	Microsurface	$36,200
2030	12	036-Gaston	Preservation	SR 2270	SR 2271	D END	0.14	Microsurface	$7,000
2030	12	036-Gaston	Preservation	SR 2271	SR 2269	SR 2275	0.82	Microsurface	$30,500
2030	12	036-Gaston	Preservation	SR 2440	SRV 2439	D. END	0.60	Microsurface	$29,000
2030	12	036-Gaston	Preservation	SR 2442	NC 274	D .END	0.56	Microsurface	$28,300
2030	12	036-Gaston	Preservation	SR 2531	NC 273	D. END	2.10	Microsurface	$97,000
2030	12	036-Gaston	Preservation	SR 2588	SR 2439	D END	0.50	Microsurface	$24,200
2030	12	036-Gaston	Preservation	SR 2657	SR 2656	SR 2658	0.40	1.0" S9.5B	$30,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	12	036-Gaston	Preservation	SR 2658	SR 2656	SR 2657	0.17	1.0" S9.5B	$20,000
2030	12	036-Gaston	Preservation	SR 2659	SR 2657	SR 2658	0.11	1.0" S9.5B	$10,900
2030	12	036-Gaston	Preservation	SR 2660	SR 2657	SR 2656	0.10	1.0" S9.5A	$6,000
2030	12	036-Gaston	Preservation	SR 2676	SR 2657	SR 2656	0.12	1.0" S9.5B	$12,200
2030	12	036-Gaston	Preservation	SR 2824	SR 2426	CDS	0.58	1.0" S9.5B	$29,100
2030	12	036-Gaston	Preservation	SR 2909	NC 7	DEAD END	0.25	1.0" S9.5B	$30,000
2030	12	036-Gaston	Preservation	SR 3216	SR 2000	DE	0.13	1.0" S9.5B	$14,000
2030	12	036-Gaston	Preservation	SR 3404	SR 1806	D END	0.19	1.0" S9.5B	$19,000
2030	12	036-Gaston	Preservation	SR 3405	SR 1806	D END	0.24	1.0" S9.5B	$24,400
2030	12	036-Gaston	Preservation	SR2427	SR2426	S.C.	0.86	Microsurface	$48,000
2030	12	036-Gaston	Preservation	SR2436	NC279	D.END	0.95	Microsurface	$40,000
2030	12	036-Gaston	Preservation	SR2564	SR2017	SR2563	0.25	1.0" S9.5B	$19,300
2030	12	049-Iredell	Resurfacing	NC 3	County Line	NC 150	7.47	1.5" S9.5C	$1,680,750
2030	12	049-Iredell	Resurfacing	SR 1143	NC 3	County Line	5.11	1.5" S9.5C	$1,149,750
2030	12	049-Iredell	Resurfacing	SR 1190	SR 1109	EOP	1.40	1.0" S9.5B	$351,000
2030	12	049-Iredell	Resurfacing	SR 1191	SR 1109	SR 1191	1.34	1.5" S9.5C	$301,500
2030	12	049-Iredell	Resurfacing	SR 1209	SR 1190	End of Maint.	0.89	1.0" S9.5B	$200,250
2030	12	049-Iredell	Resurfacing	SR 1210	SR 1209	SR 1209	0.13	1.0" S9.5B	$29,500
2030	12	049-Iredell	Resurfacing	SR 1234	SR 1178	End Maint.	1.38	1.0" S9.5B	$245,000
2030	12	049-Iredell	Resurfacing	SR 1235	SR 1234	End of Maint.	0.33	1.0" S9.5B	$55,000
2030	12	049-Iredell	Resurfacing	SR 1290	SR 1210	SR 1190	0.12	1.0" S9.5B	$27,000
2030	12	049-Iredell	Resurfacing	SR 1291	SR 1290	End of Maint.	0.30	1.0" S9.5B	$67,500
2030	12	049-Iredell	Resurfacing	SR 1300	SR	Cul-de-sac	5.06	1.5" S9.5C and Widen	$1,138,500
2030	12	049-Iredell	Resurfacing	SR 1432	SR 1300	SR 1300	1.42	1.0" S9.5B	$310,000
2030	12	049-Iredell	Resurfacing	SR 1452	SR 1303	DE	0.62	1.0" S9.5B	$139,500
2030	12	049-Iredell	Resurfacing	SR 1471	SR 1300	SR 1471	1.02	1.0" S9.5B	$229,500
2030	12	049-Iredell	Resurfacing	SR 1859	SR 1858	SR 1862	1.50	Seal - Double and Fog Seal	$67,500
2030	12	049-Iredell	Resurfacing	SR 2105	Yadkin County	Davie County Line	4.72	1.5" S9.5C	$1,062,000
2030	12	049-Iredell	Resurfacing	SR 2121	SR 2126	SR 2105	2.44	1.5" S9.5C	$549,000
2030	12	049-Iredell	Resurfacing	SR 2122	SR 2121	SR 2120	1.58	1.5" S9.5C	$355,500
2030	12	049-Iredell	Resurfacing	SR 2364	SR 2362	Rowan County	1.15	1.5" S9.5A	$258,750
2030	12	049-Iredell	Resurfacing	SR 2765	SR 1302	DE	0.31	1.0" S9.5B	$69,750
2030	12	049-Iredell	Resurfacing	SR 2766	SR 2765	DE	0.03	1.0" S9.5B	$6,750
2030	12	049-Iredell	Resurfacing	SR 2767	SR 2765	DE	0.03	1.0" S9.5B	$6,750
2030	12	049-Iredell	Resurfacing	SR 2768	SR 2765	DE	0.26	1.0" S9.5B	$58,500
2030	12	049-Iredell	Resurfacing	SR 2769	SR 2768	DE	0.10	1.0" S9.5B	$22,500
2030	12	049-Iredell	Resurfacing	SR 2770	SR 2768	DE	0.12	1.0" S9.5B	$27,000
2030	12	049-Iredell	Resurfacing	SR 2771	SR 2771	DE	0.13	1.0" S9.5B	$28,000
2030	12	049-Iredell	Resurfacing	SR 2772	SR 1302	DE	0.21	1.0" S9.5B	$47,250
2030	12	049-Iredell	Resurfacing	SR 2774	SR 1302	DE	0.48	1.0" S9.5B	$108,000
2030	12	049-Iredell	Resurfacing	SR 2775	SR 2774	DE	0.10	1.0" S9.5B	$22,500
2030	12	049-Iredell	Resurfacing	SR 2776	SR 2774	DE	0.12	1.0" S9.5B	$27,000
2030	12	049-Iredell	Resurfacing	SR 2777	SR 2774	DE	0.10	1.0" S9.5B	$22,500
2030	12	049-Iredell	Resurfacing	SR 2788	SR 1432	End of Maint.	0.35	1.0" S9.5B	$78,750
2030	12	049-Iredell	Resurfacing	SR 2938	SR 1113	SR 1113	1.34	1.0" S9.5B	$301,500
2030	12	049-Iredell	Resurfacing	SR 2939	SR 2938	DE	0.11	1.0" S9.5B	$27,000
2030	12	049-Iredell	Resurfacing	SR 2971	SR 2938	SR 2972	0.16	1.0" S9.5B	$36,000
2030	12	049-Iredell	Resurfacing	SR 2972	Cul-de-Sac	DE	0.24	1.0" S9.5B	$54,000
2030	12	049-Iredell	Resurfacing	SR 2973	SR 2972	DE	0.20	1.0" S9.5B	$45,000
2030	12	049-Iredell	Resurfacing	SR 2996	SR 1190	End of Maint.	0.14	1.0" S9.5B	$31,500
2030	12	049-Iredell	Resurfacing	SR 2997	SR 1100	End of Maint.	0.14	1.0" S9.5B	$31,500
2030	12	049-Iredell	Resurfacing	SR 3003	SR 2996	End of Maint.	0.10	1.0" S9.5B	$22,500
2030	12	049-Iredell	Resurfacing	SR 3007	SR 1100	SR 1100	0.60	1.0" S9.5B	$135,000
2030	12	049-Iredell	Resurfacing	SR 3022	SR 2938	DE	0.12	1.0" S9.5B	$27,000
2030	12	049-Iredell	Resurfacing	SR 3091	SR 1190	End of Maint.	0.26	1.0" S9.5B	$58,500
2030	12	049-Iredell	Resurfacing	SR 3092	SR 3187	SR 3092	0.86	1.0" S9.5B	$193,500
2030	12	049-Iredell	Resurfacing	SR 3135	SR 1303	DE	0.19	1.0" S9.5B	$42,750
2030	12	049-Iredell	Resurfacing	SR 3138	SR 1303	DE	0.13	1.0" S9.5B	$28,000
2030	12	049-Iredell	Resurfacing	SR 3139	SR 1301	DE	0.32	1.0" S9.5B	$72,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	12	049-Iredell	Resurfacing	SR 3187	SR 1190	End of Maint.	0.23	1.0" S9.5B	$51,000
2030	12	049-Iredell	Resurfacing	SR 3213	SR 1113	DE	0.17	1.0" S9.5B	$38,250
2030	12	049-Iredell	Resurfacing	SR 3214	SR 3213	DE	0.06	1.0" S9.5B	$13,500
2030	12	049-Iredell	Resurfacing	SR 3239	SR 1113	DE	0.27	1.0" S9.5B	$60,750
2030	12	049-Iredell	Resurfacing	SR 3240	SR 3239	DE	0.06	1.0" S9.5B	$13,500
2030	12	049-Iredell	Resurfacing	SR 3319	SR 3319	DE	0.08	1.0" S9.5B	$18,000
2030	12	049-Iredell	Resurfacing	SR 3320	SR 2938	DE	0.07	1.0" S9.5B	$18,000
2030	12	049-Iredell	Preservation	SR 1608	NC 115	County Line	0.95	Seal - Double and Fog Seal	$42,750
2030	12	049-Iredell	Preservation	SR 1849	NC 1845	NC 901	2.88	Seal - Double and Fog Seal	$129,600
2030	12	049-Iredell	Preservation	SR 1858	SR 1892	SR 1880	3.71	Seal - Double and Fog Seal	$166,950
2030	12	049-Iredell	Preservation	SR 1860	SR 1862	SR 1861	1.15	Seal - Double and Fog Seal	$52,200
2030	12	049-Iredell	Preservation	SR 1861	NC 115	SR 1880	4.64	Seal - Double and Fog Seal	$208,800
2030	12	049-Iredell	Preservation	SR 1861	NC 115	SR 1892	4.40	Seal - Double and Fog Seal	$198,000
2030	12	049-Iredell	Preservation	SR 1872	SR 2017	SR 1896	0.94	Seal - Double and Fog Seal	$42,300
2030	12	049-Iredell	Preservation	SR 1874	SR 1898	SR 1896	2.15	Seal - Double and Fog Seal	$96,750
2030	12	049-Iredell	Preservation	SR 1884	SR 1981	SR 1884	1.28	Seal - Double and Fog Seal	$57,600
2030	12	049-Iredell	Preservation	SR 2017	NC 115	SR 1873	2.07	Seal - Double and Fog Seal	$53,100
2030	12	049-Iredell	Preservation	SR 2128	NC 901	SR 2129	2.11	Seal - Double and Fog Seal	$94,950
2030	12	049-Iredell	Preservation	SR 2130	SR 2128	County Line	1.03	Seal - Double and Fog Seal	$46,350
2030	12	049-Iredell	Preservation	SR 2131	NC 901	County Line	1.11	Seal - Double and Fog Seal	$49,950
2030	12	055-Lincoln	Resurfacing	NC 27	NC 150	NC 73	1.67	Mill 1.5" and 1.5" S9.5C	$324,675
2030	12	055-Lincoln	Resurfacing	SR 1373	NC 16 Bus	SR 1360	2.36	Full Depth Patching and 1.5" S9.5C	$460,200
2030	12	055-Lincoln	Resurfacing	SR 1511	NC 73	NC 16	6.49	Full Depth Patching and 1.5" S9.5B	$1,265,550
2030	12	055-Lincoln	Resurfacing	SR 1603	SR 1336	SR 1581	0.15	Full Depth Patching and 1.5" S9.5C	$29,250
2030	12	055-Lincoln	Resurfacing	SR 1604	SR 1581	SR 1603	0.29	Full Depth Patching and 1.5" S9.5C	$56,550
2030	12	055-Lincoln	Resurfacing	SR 1671	SR 1366	SR 1366	0.64	Full Depth Patching and 1.5" S9.5B	$124,800
2030	12	055-Lincoln	Resurfacing	SR 1706	NC 182	Cul-de-sac	0.47	Full Depth Patching and 1.5" S9.5C	$90,675
2030	12	055-Lincoln	Resurfacing	SR 1741	SR 1342	Dead End	0.67	Full Depth Patching and 1.5" S9.5C	$130,455
2030	12	055-Lincoln	Resurfacing	SR 1749	NC 16 Bus	End Maint	0.36	Full Depth Patching and 1.5" S9.5C	$70,200
2030	12	055-Lincoln	Resurfacing	SR 1758	NC 16	E O M	0.12	Full Depth Patching and 1.5" S9.5B	$23,400
2030	12	055-Lincoln	Resurfacing	SR 1795	SR 1380	DEAD END	0.14	Full Depth Patching and 1.25" S9.5B	$26,910
2030	12	055-Lincoln	Resurfacing	SR 1806	SR 1671	END MAINT	0.08	Full Depth Patching and 1.25" S9.5B	$15,600
2030	12	055-Lincoln	Resurfacing	SR 1852	SR 1282	Cul-de-sac	0.17	Full Depth Patching and 1.5" S9.5C	$32,175
2030	12	055-Lincoln	Resurfacing	SR 1853	SR 1852	Clu-de-sac	0.10	Full Depth Patching and 1.5" S9.5C	$19,500
2030	12	055-Lincoln	Resurfacing	SR 2064	SR 1367	CUL-DE-SAC	0.32	Patching and 1.0" S9.5A	$62,400
2030	12	055-Lincoln	Resurfacing	SR 2124	NC 73	Dead End	0.60	Full Depth Patching and 1.5" S9.5C	$117,000
2030	12	055-Lincoln	Resurfacing	US 321	GASTON CO	NC 27 + .38 miles	11.07	Mill 1.5" and 1.5" S9.5B	$2,158,650
2030	12	055-Lincoln	Preservation	SR 1190	SR 1002	NC 27	1.96	Seal - Double and Fog Seal	$105,350
2030	12	055-Lincoln	Preservation	SR 1197	SR 1113	CATAWBA CO	3.70	Microsurface	$198,875
2030	12	055-Lincoln	Preservation	SR 1207	SR 1113	SR 1208	0.99	Seal - Double and Fog Seal	$53,212
2030	12	055-Lincoln	Preservation	SR 1312	NC 27	GASTON CO	1.73	Seal - Double	$92,880
2030	12	055-Lincoln	Preservation	SR 1316	SR 1314	SR 1309	0.65	Seal - Double and Fog Seal	$34,937
2030	12	055-Lincoln	Preservation	SR 1338	US 321 Bus	SR 1339	1.97	Seal - Double and Fog Seal	$105,833
2030	12	055-Lincoln	Preservation	SR 1346	SR 1343	Catawba Co	1.29	Seal - Double and Fog Seal	$69,337
2030	12	055-Lincoln	Preservation	SR 1356	SR 1355	NC 73	2.08	Seal - Double and Fog Seal	$111,638
2030	12	055-Lincoln	Preservation	SR 1363	SR 1355	SR 1362	1.71	Seal - Double and Fog Seal	$91,912
2030	12	055-Lincoln	Preservation	SR 1454	SR 1316	SR 1309	0.36	Seal - Double and Fog Seal	$19,188
2030	12	055-Lincoln	Preservation	SR 1641	SR 1001	DEAD END	0.67	Seal - Double	$35,905
2030	12	055-Lincoln	Preservation	SR 3006	SR 1362	SR 1349	0.43	Seal - Double and Fog Seal	$23,112
2030	13	011-Buncombe	Resurfacing	WOODFIN AVENUE/VINE /WASHINGTON	NC 251	END OF STATE MAINTENANCE	0.52	Full Depth Patching and 1.5" S9.5C	$125,000
2030	13	011-Buncombe	Resurfacing	(NORTH WOODFIN AVENUE/BROOKDALE	US 25	SR 1684 (ELK MOUNTAIN ROAD)	0.70	Full Depth Patching and 1.5" S9.5C	$285,000
2030	13	011-Buncombe	Resurfacing	SR 1729 (PINEBROOK ROAD)	SR 1882 (NEWSTOCK ROAD)	END OF MAINTENANCE	0.37	Full Depth Patching and 1.0" S4.75A	$68,350
2030	13	011-Buncombe	Resurfacing	SR 1740 (NEWSTOCK ROAD)	SR 1727 (MONTICELLO ROAD)	US HIGHWAY 25	1.45	Full Depth Patching and 1.5" S9.5C	$355,250
2030	13	011-Buncombe	Resurfacing	R 1741 (LOWER SHEPPARD BRANCH ROAD	SR 1742 (LOWER FLAT CREEK ROAD)	US 25/70	0.84	Full Depth Patching and 1.25" S9.5B	$243,000
2030	13	011-Buncombe	Resurfacing	SR 1741 (SHEPHARD BRANCH ROAD)	US HIGHWAY 25	SR (1740 (NEWSTOCK ROAD)	2.22	Full Depth Patching and 1.5" S9.5C	$642,000
2030	13	011-Buncombe	Resurfacing	SR 1742 (LOWER FLAT CREEK ROAD)	NC 251	SR 1756 (JUPITER ROAD)	3.09	Full Depth Patching and 1.5" S9.5C	$795,226
2030	13	011-Buncombe	Resurfacing	SR 1756 (JUPITER ROAD)	MADISON COUNTY LINE	US 26	5.86	Full Depth Patching and 1.5" S9.5C	$1,685,000
2030	13	011-Buncombe	Resurfacing	SR 1764 (FLAT CREEK CHURCH ROAD)	SR 2207 (OLD MARS HILL HIGHWAY)	SR 1740 (NEWSTOCK ROAD)	2.44	Full Depth Patching and 1.5" S9.5C	$580,632
2030	13	011-Buncombe	Resurfacing	SR 1826 (CHADWICK WADE DRIVE)	SR 1883 (AIKEN ROAD)	END OF MAINTENANCE)	0.27	Full Depth Patching and 1.0" S4.75A	$64,550

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	13	011-Buncombe	Resurfacing	SR 1833 (PERIWINKLE DRIVE)	SR 1829 (WOODY LANE)	CUL DE SAC	0.17	Full Depth Patching and 1.0" S4.75A	$49,090
2030	13	011-Buncombe	Resurfacing	SR 1870 (WOODLAND KNOLLS)	SR 1844 (WOODY LANE)	CUL DE SAC	0.09	Full Depth Patching and 1.0" S4.75A	$18,277
2030	13	011-Buncombe	Resurfacing	SR 1871 (WOODLAND RIDGE)	SR 1844 (WOODY LANE)	CUL DE SAC	0.10	Full Depth Patching and 1.0" S4.75A	$19,975
2030	13	011-Buncombe	Resurfacing	SR 1882 (NEWSTOCK ROAD)	SR 1720 (AIKEN ROAD)+.03 MILE	SR 1727 (MONTICELLO ROAD)	1.59	Full Depth Patching and 1.5" S9.5C	$380,200
2030	13	011-Buncombe	Resurfacing	SR 2110 (JUMP COVE ROAD)	SR 2109 (OX CREEK ROAD)	END OF PAVEMENT	0.26	Full Depth Patching and 1.5" S9.5C	$58,145
2030	13	011-Buncombe	Resurfacing	SR 2204 (GLENWAY DRIVE)	SR 2068 (RICE BRANCH ROAD)	END OF MAINTENANCE	0.08	Full Depth Patching and 1.0" S4.75A	$12,000
2030	13	011-Buncombe	Resurfacing	R 2207 (NORTH BUNCOMBE SCHOOL ROAI	US 19 BUSINESS	SR 1768 (OLD BURNSVILLE ROAD)	5.47	Full Depth Patching and 1.5" S9.5C	$2,000,600
2030	13	011-Buncombe	Resurfacing	SR 2208 (CHUNNS COVE ROAD)	SR 2042 (VANCE GAP ROAD)	APACHE TRAIL (PRIVATE ROAD)	0.13	Full Depth Patching and 1.25" S9.5B	$28,000
2030	13	011-Buncombe	Resurfacing	SR 2547 (COLLEGE CIRCLE)	SR 2416 (WARREN WILSON ROAD)	SR 2548 (COLLEGE PLACE)	0.14	Mill 1.5" and 1.5" S9.5C	$46,500
2030	13	011-Buncombe	Resurfacing	2587 (COVEWOOD ROAD/ COVEWOOD TR.	SR 2208 (CHUNNS COCE ROAD)	END OF MAINTENANCE	0.59	Full Depth Patching and 1.5" S9.5C	$95,567
2030	13	011-Buncombe	Resurfacing	SR 3077 (DAVIDSON ROAD)	SR 3052 (SCHOOL ROAD)	SR 3075 (ONTEORA BOULEVARD)	0.25	Full Depth Patching and 1.0" S4.75A	$57,500
2030	13	011-Buncombe	Resurfacing	SR 3228 (FOX ROAD)	SR 3141 (FOX ROAD)	DEAD END	0.30	Full Depth Patching and 1.5" S9.5C	$64,250
2030	13	011-Buncombe	Resurfacing	SR 3258 (MUIRFIELD DRIVE)	SR 3157 (WESTON ROAD)	SR 3260 (MUIRFIELD DRIVE)	0.03	Full Depth Patching and 1.5" S9.5C	$9,500
2030	13	011-Buncombe	Resurfacing	SR 3291 (MAYBURY PLACE)	SR 3160 (CHESTNUT PLACE)	CUL DE SAC	0.05	Full Depth Patching and 1.5" S9.5C	$15,700
2030	13	011-Buncombe	Preservation	3357 (SOUTH KNOLL COURT)	SR 3356 (KNOLL DRIVE)	CUL DE SAC	0.05	Full Depth Patching and 1.0" S4.75A	$7,000
2030	13	011-Buncombe	Preservation	SE 3080 (RED OAK TERRACE/FRENO DRIVE	SR 3079 (OAKVIEW PARK ROAD)	END OF MAINTENANCE	0.16	Full Depth Patching and 1.0" S4.75A	$24,000
2030	13	011-Buncombe	Preservation	SR 3076 (WENTWORTH AVENUE)	SR 3052 (SCHOOL ROAD)	ATE MAINTENANCE(WENTWORTH	0.32	Full Depth Patching and 1.0" S4.75A	$48,000
2030	13	011-Buncombe	Preservation	SR 3119 (MERRILLS COVE ROAD)	SR 3192 (BOB BARNWELL ROAD)	SR 3121 (ROSE HILL ROAD)	1.79	Full Depth Patching and Double Seal and Fog Seal	$144,090
2030	13	011-Buncombe	Preservation	SR 3212 (SIGMON ROAD)	SR 3138 (UPPER BRUSH CREEK ROAD)	END OF MAINTENANCE	0.43	Full Depth Patching and Double Seal and Fog Seal	$22,122
2030	13	011-Buncombe	Preservation	SR 3236 (SAINT ANDREWS ROAD)	SR 3157 (WESTON ROAD)	CUL DE SAC	0.42	Full Depth Patching and 1.0" S4.75A	$63,000
2030	13	011-Buncombe	Preservation	SR 3242 (FOREST RIDGE DRIVE)	SR 3226 (SAINT ANDREWS ROAD)	CUL DE SAC	0.23	Full Depth Patching and 1.0" S4.75A	$34,500
2030	13	011-Buncombe	Preservation	SR 3243 (FOREST RIDGE COURT)	SR 3242 (FOREST RIDGE DRIVE)	CUL DE SAC	0.04	Full Depth Patching and 1.0" S4.75A	$10,000
2030	13	011-Buncombe	Preservation	SR 3244 (CRESTBROOK DRIVE)	SR 3242 (FOREST RIDGE DRIVE)	CUL DE SAC	0.12	Full Depth Patching and 1.0" S4.75A	$18,000
2030	13	011-Buncombe	Preservation	SR 3245 (PALATKA STREET)	SR 3187 (PENSACOLA AVENUE)	END OF STATE MAINTENANCE	0.16	Full Depth Patching and 1.0" S4.75A	$25,000
2030	13	011-Buncombe	Preservation	SR 3264 (TURNBERRY DRIVE)	SR 3157 (WESTON ROAD)	DEAD END	0.36	Full Depth Patching and 1.0" S4.75A	$54,000
2030	13	011-Buncombe	Preservation	SR 3265 (CANTERBURY DRIVE)	SR 3264 (TURNBERRY DRIVE)	CUL DE SAC	0.14	Full Depth Patching and 1.0" S4.75A	$21,000
2030	13	011-Buncombe	Preservation	SR 3266 (CANTERBURY PLACE)	SR 3265 (CANTERBURY DRIVE)	DEAD END	0.12	Full Depth Patching and 1.0" S4.75A	$14,160
2030	13	011-Buncombe	Preservation	SR 3267 (CRESTBROOK COURT)	SR 3244 (CRESTBROOK DRIVE)	CUL DE SAC	0.05	Full Depth Patching and 1.0" S4.75A	$10,000
2030	13	011-Buncombe	Preservation	SR 3283 (TURNBERRY PLACE)	SR 3264 (TURNBERRY PLACE)	CUL DE SAC	0.07	Full Depth Patching and 1.0" S4.75A	$10,500
2030	13	011-Buncombe	Preservation	SR 3285 (OCALA STREET)	SR 3187 (PENSACOLA AVENUE)	CUL DE SAC	0.23	Full Depth Patching and 1.0" S4.75A	$35,000
2030	13	011-Buncombe	Preservation	SR 3303 (ASHCROFT ROAD)	SR 3187 (PENSACOLA AVENUE)	END OF MAINTENANCE	0.14	Full Depth Patching and 1.0" S4.75A	$30,000
2030	13	011-Buncombe	Preservation	SR 3304 (HICKORY HILLS DRIVE)	SR 3157 (WESTON ROAD)	CUL DE SAC	0.14	Full Depth Patching and 1.0" S4.75A	$21,000
2030	13	011-Buncombe	Preservation	SR 3306 (ASHECROFT PLACE)	SR 3303 (ASHCROFT ROAD)	CUL DE SAC	0.05	Full Depth Patching and 1.0" S4.75A	$6,224
2030	13	011-Buncombe	Preservation	SR 3324 (RAVENWOOD DRIVE)	SR 3149 (OLD CONCORD ROAD)	CUL DE SAC	0.56	Full Depth Patching and Double Seal and Fog Seal	$24,000
2030	13	012-Burke	Resurfacing	NC 18	SR 1712 (DREXEL ROAD)+.05 MI	US 70+.09MI	2.29	Mill 1.5" and 1.5" S9.5C	$2,399,425
2030	13	012-Burke	Resurfacing	SR 1002 (HENRY RIVER ROAD)	SR 1834 (DIETZ AVENUE)	I 40 ACCESS ROAD	0.20	Full Depth Patching and 1.5" S9.5C	$40,990
2030	13	012-Burke	Resurfacing	SR 1007 1ST AVE SW/US 70A E	COUNTY LINE	US 70	1.64	Full Depth Patching and 1.5" S9.5C	$475,750
2030	13	012-Burke	Resurfacing	SR 1547(GARDOIL AVENUE NORTH EAST)	PAVEMENT JOINT AT BRIGE	R 1547 (REFOUR ROAD NORTH EAS	0.27	Full Depth Patching and 1.25" S9.5B	$65,300
2030	13	012-Burke	Resurfacing	SR 1580 (OLD SEACREST AVENUE)	SR 1535 (OAKLAND AVENUE)	DEAD END	0.22	Full Depth Patching and 1.5" S9.5C	$45,599
2030	13	012-Burke	Resurfacing	SR 1581 (BERRYTOWN STREET)	SR 1542 (BERRYTOWN AVENUE)	DEAD END	0.08	Full Depth Patching and 1.5" S9.5C	$15,000
2030	13	012-Burke	Resurfacing	SR 1602 (WOODLAWN DRIVE)	US 70	US 70 + 0.17 MILES	0.17	Full Depth Patching and 1.0" S4.75A	$36,799
2030	13	012-Burke	Resurfacing	SR 1605 (HILDERS STREET)	US 70	US 70 + 0.09 MILES	0.09	Full Depth Patching and 1.0" S4.75A	$15,599
2030	13	012-Burke	Resurfacing	SR 1611 (RHODHISS ROAD)	US 70	CALDWELL COUNTY LINE	5.24	Full Depth Patching and 1.5" S9.5C	$1,650,300
2030	13	012-Burke	Resurfacing	SR 1625 (9TH AVE DRIVE NORTH WEST)	CATAWBA COUNTY	330 (CLEMENT BLVD NW)+ 0.35 M	0.41	Full Depth Patching and 1.5" S9.5C	$100,900
2030	13	012-Burke	Resurfacing	SR 1633 (THIRD STREET NORTH EAST)	SR 1632 (FIRST AVENUE NORTH EAST)	DEAD END	0.49	Full Depth Patching and 1.0" S4.75A	$115,000
2030	13	012-Burke	Resurfacing	SR 1641 (36TH STREET NORTH WEST)	SR 1630 (MAIN AVENUE DRIVE NORTH WEST)	END OF MAINTENANCE	0.15	Full Depth Patching and 1.25" S9.5B	$33,000
2030	13	012-Burke	Resurfacing	SR 1642 (34TH STREET NW)	COUNTY LINE	R 1653 (2ND AVENUE NORTH WES	0.40	Full Depth Patching and 1.25" S9.5B	$170,000
2030	13	012-Burke	Resurfacing	SR 1647 (CAPE HICKORY ROAD)	SR 1007 (1ST AVE SOUTH WEST)	SR 1611 (BURKE STREET)	3.67	Full Depth Patching and 1.25" S9.5B	$1,290,000
2030	13	012-Burke	Resurfacing	SR 1656 (WEST VIEW ACRES AVENUE)	SR 1653 (HICKORY AIRPORT ROAD)	END OF MAINTENANCE	0.65	Full Depth Patching and 1.0" S4.75A	$141,000
2030	13	012-Burke	Resurfacing	SR 1681 (FIRST STREET NORTH WEST)	SR 1680 (2ND AVENUE NORTH WEST)	DEAD END	0.18	Full Depth Patching and 1.0" S4.75A	$47,090
2030	13	012-Burke	Resurfacing	33 (INDIAN HILLS AVENUE/INDIAN HILLS ST	SR 1647 (CAPE HICKORY ROAD)	ENSD OF MAINTENANCE	0.89	Full Depth Patching and 1.0" S4.75A	$215,000
2030	13	012-Burke	Resurfacing	SR 1684 (HARMONY STREET)	SR 1624 (DOC PUGH ROAD)	SR 1623 (MOUNT HARMONY ROAD	0.44	Full Depth Patching and 1.25" S9.5B	$100,000
2030	13	012-Burke	Resurfacing	SR 1691 (INDIAN HILLS CIRCLE)	SR 1683 (INDIAN HILLS STREET)	SR 1683 (INDIAN HILLS STREET)	0.42	Full Depth Patching and 1.0" S4.75A	$98,600
2030	13	012-Burke	Resurfacing	SR 1698 (ISLAND CREEK AVENUE)	SR 1607 (ISRAEL CHAPEL ROAD)	END OF MAINTENANCE	0.15	Full Depth Patching and 1.0" S4.75A	$32,455
2030	13	012-Burke	Resurfacing	RED STREET SE / MINERAL SPRINGS MOUI	40 PROJECT PAVEMENT CHANGE	US70	0.95	Full Depth Patching and 1.5" S9.5C	$329,900
2030	13	012-Burke	Resurfacing	1744 (MINERAL SPRINGS MOUNTAIN ROA	SR 1001 (RUTHERFORD COLLEGE ROAD)	40 PROJECT PAVEMENT CHANGE	0.39	Full Depth Patching and 1.5" S9.5C	$135,000
2030	13	012-Burke	Resurfacing	SR 1756 (COTTON MILL STREET)	SR 1755 (COLDWATER STREET)	END OF PAVEMENT	0.18	Full Depth Patching and 1.5" S9.5C	$21,990
2030	13	012-Burke	Resurfacing	SR 1763 (JOHN WILLIAMS ROAD)	US 70	DEAD END	0.26	Full Depth Patching and 1.0" S4.75A	$42,779
2030	13	012-Burke	Resurfacing	SR 1773 (4TH AVENUE SOUTH WEST)	SR 1761 (MAIN AVENUE)	SR 1002 (SOUTH CENTER STREET)	0.34	Full Depth Patching and 1.25" S9.5B	$69,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	13	012-Burke	Resurfacing	SR 1795 (WARLICK CHAPEL ROAD)	SR 1786 (MILLER BRIDGE ROAD)	)1 (MINERAL SPRINGS MOUNTAIN	1.46	Full Depth Patching and 1.0" S4.75A	$295,000
2030	13	012-Burke	Resurfacing	SR 1802 (CLAUDE BRITTAIN ROAD)	SR 1796 (OLD LAUREL ROAD)	1736 (WILKIES GROVE CHURCH RO.	1.70	Full Depth Patching and 1.0" S4.75A	$431,000
2030	13	012-Burke	Resurfacing	SR 1803 (JOHNSON BRIDGE ROAD)	SR 1784 (OLD BRITTAIN ROAD)	SR 1761 (OLD NC 10)	0.46	Full Depth Patching and 1.5" S9.5C	$75,000
2030	13	012-Burke	Resurfacing	SR 1823 (ICARD CHURCH OF GOD ROAD)	US 70	SR 1761 (OLD NC 10)	0.51	Full Depth Patching and 1.0" S4.75A	$99,777
2030	13	012-Burke	Resurfacing	SR 1924 (OLD NC 18)	PAVEMENT CHANGE	913 (SUGAR LOAF ROAD)+ 2.033 M	1.56	Full Depth Patching and 1.0" S4.75A	$395,000
2030	13	012-Burke	Resurfacing	SR 1924 (OLD NC 18)	BRIDGE 307 ABUTMENT	SR 1917 (OLD CREEK ROAD)	3.15	Full Depth Patching and 1.25" S9.5B	$710,000
2030	13	012-Burke	Resurfacing	SR 1935 (SUNNYSIDE DRIVE)	SR 1924 (OLD NC 18)	SR 1933 (SKYLAND DRIVE)	0.29	Full Depth Patching and 1.5" S9.5C	$60,177
2030	13	012-Burke	Resurfacing	SR 1938 (OAKTREE ROAD)	MP 35	DEAD END	0.02	Full Depth Patching and 1.5" S9.5C	$4,800
2030	13	012-Burke	Resurfacing	SR 2306 (RAINTREE STREET)	SR 1621 (ICARD RHODHISS ROAD)	DEAD END	0.44	Full Depth Patching and 1.0" S4.75A	$105,000
2030	13	012-Burke	Resurfacing	SR 2317 (KNOB MOUNTAIN DRIVE)	SR 1620 (KNOBS LANDING ROAD)	END OF MANTENANCE	0.32	Full Depth Patching and 1.0" S4.75A	$77,000
2030	13	012-Burke	Resurfacing	SR 2321 (WEST VIEW TRAIL)	SR 1656 (WEST VIEW ACRES AVENUE)	SR 2324 (ACRES STREET)	0.40	Full Depth Patching and 1.0" S4.75A	$65,055
2030	13	012-Burke	Resurfacing	SR 2322 (ETHEL STREET)	SR 1621 (ICARD RHODHISS ROAD)	DEAD END	0.17	Full Depth Patching and 1.0" S4.75A	$38,779
2030	13	012-Burke	Resurfacing	SR 2323 (VIEW DRIVE)	SR 1656 (WEST VIEW ACRES AVENUE)	DEAD END	0.11	Full Depth Patching and 1.0" S4.75A	$19,999
2030	13	012-Burke	Resurfacing	SR 2324 (ACRES STREET)	SR 1656 (WEST VIEW ACRES AVENUE)	END OF MAINTENANCE	0.09	Full Depth Patching and 1.0" S4.75A	$19,877
2030	13	012-Burke	Resurfacing	SR 2339 (HIDDEN POINT DRIVE)	CUL DE SAC	CUL DE SAC	0.16	Full Depth Patching and 1.0" S4.75A	$34,500
2030	13	012-Burke	Resurfacing	SR 2340 (HIDDEN POINT DRIVE)	SR 2338 (LAKE ACRES DRIVE)	SR 2339 (HIDDEN POINT DRIVE	0.11	Full Depth Patching and 1.0" S4.75A	$24,000
2030	13	012-Burke	Resurfacing	SR 2503 (NEUVILLE AVENUE)	SR 1890 (I 40 ACCESS ROAD SOUTH EAST)	CATAWBA COUNTY LINE	0.29	Full Depth Patching and 1.25" S9.5C	$73,500
2030	13	012-Burke	Preservation	SR 1136 (BEE TREE AVENUE)	SR 1129 (DYSARTSVILLE ROAD)	END OF MAINTENANCE	0.77	Full Depth Patching and Double Seal and Fog Seal	$57,600
2030	13	012-Burke	Preservation	SR 1143 (SUNDOWN ROAD)	US 70	SR 1138 (KATHY ROAD)	1.75	Full Depth Patching and Double Seal and Fog Seal	$131,025
2030	13	012-Burke	Preservation	SR 1144 (JEWEL STREET)	US 70	END OF MAINTENANCE	0.16	Full Depth Patching and Double Seal and Fog Seal	$9,855
2030	13	012-Burke	Preservation	SR 1148 (MESSER AVENUE)	SR 1147 (CAUSBY ROAD)	END OF MAINTENANCE)	0.32	Full Depth Patching and Double Seal and Fog Seal	$25,925
2030	13	012-Burke	Preservation	SR 1198 (WEST PINE HILL AVENUE)	SR 1129 (DYSARTSVILLE ROAD)	END OF MAINTENANCE	0.22	Full Depth Patching and Double Seal and Fog Seal	$22,000
2030	13	012-Burke	Preservation	SR 1203 (CHAMBERS CHAPEL CIRCLE)	US 70	US 70	0.52	Full Depth Patching and Double Seal and Fog Seal	$30,000
2030	13	012-Burke	Preservation	SR 1204 (PERRY POWELL ROAD)	SR 1203 (CHAMBERS CHAPEL CIRCLE)	END OF MAINTENANCE	0.10	Full Depth Patching and Double Seal and Fog Seal	$6,599
2030	13	012-Burke	Preservation	SR 1208 (POLLARD AVENE)	SR 1225 (LAIL ROAD)	END OF MAINTENANCE	0.85	Full Depth Patching and Double Seal and Fog Seal	$55,655
2030	13	012-Burke	Preservation	SR 1222 (SWAN POND DRIVE)	NC 126	END OF PAVEMENT	0.09	Full Depth Patching and Double Seal and Fog Seal	$6,535
2030	13	012-Burke	Preservation	SR 1232 (CORPENING CHAPEL ROAD)	SR 1233 (NORTH POWERHOUSE ROAD)	END OF MAINTENANCE	0.78	Full Depth Patching and Double Seal and Fog Seal	$56,555
2030	13	012-Burke	Preservation	SR 1239 (PARKS DRIVE)	NC 126	END OF MAINTENANCE	0.57	Full Depth Patching and Double Seal and Fog Seal	$34,320
2030	13	012-Burke	Preservation	SR 1241 (ADVENTIST CIRCLE)	BEGIN PAVEMENT	END PAVEMENT	0.35	Full Depth Patching and Double Seal and Fog Seal	$24,550
2030	13	012-Burke	Preservation	SR 1255 (LONNIE SHUFFLER STREET)	SR 1254 (PEA RIDGE)	END OF MAINTENANCE	0.73	Full Depth Patching and Double Seal and Fog Seal	$56,500
2030	13	012-Burke	Preservation	SR 1268 (BUCKEYE HOLLOW ROAD)	NC 183	NC 181	1.32	Full Depth Patching and Double Seal and Fog Seal	$98,000
2030	13	012-Burke	Preservation	SR 1269 (JOE BOWMAN AVENUE)	SR 1267 (DOGWOOD KNOB ROAD)	END OF PAVEMENT	0.30	Full Depth Patching and Double Seal and Fog Seal	$19,320
2030	13	012-Burke	Preservation	SR 1272 (DONALD BARRIER STREET)	NC 183	BLUE RIDGE PARKWAY	0.16	Full Depth Patching and Double Seal and Fog Seal	$10,000
2030	13	012-Burke	Preservation	SR 1281 (ROCK HILL STREET)	NC 126	END OF MAINTENANCE	0.31	Full Depth Patching and Double Seal and Fog Seal	$22,000
2030	13	012-Burke	Preservation	SR 1282 (BARRIER AVENUE)	NC 181	END OF MAINTENANCE	0.16	Full Depth Patching and Double Seal and Fog Seal	$9,000
2030	13	012-Burke	Preservation	SR 1288 (CHAMBERS AVENUE)	SR 1203 (CHAMBERS CHAPEL CIRCLE)	END OF MAINTENANCE	0.10	Full Depth Patching and Double Seal and Fog Seal	$7,000
2030	13	012-Burke	Preservation	SR 1294 (BAILEY STREET)	US 70	CUL DE SAC	0.34	Full Depth Patching and Double Seal and Fog Seal	$28,000
2030	13	012-Burke	Preservation	SR 1301 (ORDERS DRIVE)	SR 1208 (POLLARD AVENUE)	END OF MAINTENANCE	0.12	Full Depth Patching and 1.0" S4.75A	$17,000
2030	13	012-Burke	Preservation	SR 1302 (SOUTH LAIL AVENUE)	SR 1225 (LAIL ROAD)	DEAD END	0.14	Full Depth Patching and 1.0" S4.75A	$33,000
2030	13	012-Burke	Preservation	SR 1303 (NORTH LAIL AVENUE)	SR 1225 (LAIL ROAD)	END OF MAINTENANCE	0.17	Full Depth Patching and 1.0" S4.75A	$34,000
2030	13	012-Burke	Preservation	SR 1313 (LA FORET DRIVE)	NC 126	END OF STATE MAINTENANCE	0.49	Full Depth Patching and 1.0" S4.75A	$65,000
2030	13	012-Burke	Preservation	SR 1314 (LA BELLEVUE STREET)	SR 1313 (LAFORET DRIVE)	CUL DE SAC	0.29	Full Depth Patching and 1.0" S4.75A	$35,000
2030	13	012-Burke	Preservation	SR 1338 (DUMONT DRIVE)	SR 1313 (LA FORET DRIVE)	SR 1314 (LA BELLEVUE STREET)	0.13	Full Depth Patching and 1.0" S4.75A	$22,500
2030	13	012-Burke	Preservation	1342 (CAMBRIDGE DRIVE/COVENTRY DRI	SR 12148 (FRANK WHISNANT ROAD)	END OF MAINTENANCE)	0.29	Full Depth Patching and 1.0" S4.75A	$35,625
2030	13	012-Burke	Preservation	SR 1358 (STEVENSON ROAD)	SR 1216 (MULL LANE)	END OF MAINTENANCE	0.06	Full Depth Patching and Double Seal and Fog Seal	$2,234
2030	13	012-Burke	Preservation	SR 1401 (MORTIMER ROAD)	NC 181	AVERY COUNTY LINE	1.57	Full Depth Patching and Double Seal and Fog Seal	$135,000
2030	13	012-Burke	Preservation	SR 1403 (BEAM AVENUE)	NC 181	END OF MAINTENANCE	0.36	Full Depth Patching and Double Seal and Fog Seal	$26,700
2030	13	012-Burke	Preservation	SR 1410 (GOODMAN LAKE ROAD)	SR 1439(HENDERSON MILL ROAD)	NC 181	1.65	Full Depth Patching and 1.0" S4.75A	$247,500
2030	13	012-Burke	Preservation	SR 1411 (ROY CALDWELL STREET)	SR 1412 (WILLOW CHURCH AVENUE)	END OF MAINTENANCE	0.50	Full Depth Patching and Double Seal and Fog Seal	$17,845
2030	13	012-Burke	Preservation	SR 1441 (BARRIER LOOP ROAD)	NC 181	NC 181	0.39	Full Depth Patching and Double Seal and Fog Seal	$23,400
2030	13	012-Burke	Preservation	SR 1481 (TIMBERLINE DRIVE)	SR 1414 (ST MARY'S CHURCH ROAD)	CUL DE SAC	0.44	Full Depth Patching and 1.0" S4.75A	$55,000
2030	13	012-Burke	Preservation	SR 1483 (WILDWOOD DRIVE)	SR 1481 (TIMBERLINE DRIVE)	SR 1485 (HORSE SHOE LANE)	0.22	Full Depth Patching and 1.0" S4.75A	$41,503
2030	13	012-Burke	Preservation	SR 1484 (APPLE BLOSSOM DRIVE)	SR 1481 (TIMBERLINE DRIVE)	SR 1418 (WA HARRIS ROAD)	0.28	Full Depth Patching and 1.0" S4.75A	$36,250
2030	13	012-Burke	Preservation	SR 1485 (HORSE SHOE LANE)	SR 1484 (APPLE BLOSSOM DRIVE)	CUL DE SAC	0.34	Full Depth Patching and 1.0" S4.75A	$42,500
2030	13	012-Burke	Preservation	SR 1486 (TIMBER TRACE)	PAVEMENT CHANGE	CUL DE SAC	0.22	Full Depth Patching and 1.0" S4.75A	$28,875
2030	13	012-Burke	Preservation	SR 1494 (CAM DRIVE)	SR 1410 (GOODMAN LAKE ROAD)	CUL DE SAC	0.36	Full Depth Patching and 1.0" S4.75A	$75,000
2030	13	012-Burke	Preservation	SR 1495 GOODMAN DRIVE)	SR 1494 (CAM DRIVE)	CUL DE SAC	0.07	Full Depth Patching and 1.0" S4.75A	$10,000
2030	13	012-Burke	Preservation	SR 1556 (MILL / GIDEON STREET)	SR 1001 (MALCOLM BOULEVARD)	SR 1557 (BENFIELD DRIVE)	0.17	Full Depth Patching and Double Seal and Fog Seal	$8,595
2030	13	012-Burke	Preservation	SR 1797 (ST JOHN CHURCH AVENUE)	NC 18 SOUTH	NC 18 SOUTH	0.94	Full Depth Patching and Double Seal and Fog Seal	$75,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	13	012-Burke	Preservation	SR 2117 (FRANCIS ROAD)	SR 1142 (JAMESTOWN ROAD)	142 (JAMESTOWN ROAD)+ 0.098 M	0.10	Full Depth Patching and 1.0" S4.75A	$20,000
2030	13	012-Burke	Preservation	SR 2136 (BRADLEY ROAD)	SR 1142 (JAMESTOWN ROAD)	CUL DE SAC	0.55	Full Depth Patching and Double Seal and Fog Seal	$35,000
2030	13	012-Burke	Preservation	SR1218 (STEPHENS ROAD)	NC 181	NC 126	0.76	Full Depth Patching and Double Seal and Fog Seal	$56,455
2030	13	012-Burke	Preservation	SR1482 (MORNING GLORY LANE)	SR 1481 (TIMBERLINE DRIVE)	CUL DE SAC	0.10	Full Depth Patching and 1.0" S4.75A	$16,250
2030	13	057-Madison	Resurfacing	l319 (LONESOME MOUNTAIN /REVERE RO	SR 1318 (GUNTERTOWN)	US 25/70	4.05	Full Depth Patching and 1.5" S9.5C	$720,500
2030	13	057-Madison	Preservation	SR 1163 (HOWARD MOORE ROAD)	NC 209	END OD PAVEMENT	1.71	Full Depth Patching and Double Seal and Fog Seal	$128,000
2030	13	057-Madison	Preservation	SR 1173 (GORENFLO GAP ROAD)	NC 209	END OF PAVEMENT	1.35	Full Depth Patching and Double Seal and Fog Seal	$82,250
2030	13	057-Madison	Preservation	SR 1174 (BLUFF MOUNTAIN ROAD)	SR 1173 (GORENFLO GAP ROAD)	END OF PAVEMENT	1.17	Full Depth Patching and Double Seal and Fog Seal	$68,500
2030	13	057-Madison	Preservation	SR 1175 (MEADOW FORK ROAD)	SR 1165 (CALDWELL MOUNTAIN ROAD)	NC 209	7.07	Full Depth Patching and Double Seal and Fog Seal	$337,434
2030	13	057-Madison	Preservation	SR 1177 (ROARING FORK ROAD)	SR 1175 (MEADOW FORK ROAD)	END OF PAVEMENT	2.00	Full Depth Patching and Double Seal and Fog Seal	$125,250
2030	13	057-Madison	Preservation	SR 1178 (PANTHER BRANCH ROAD)	SR 1175 (MEADOW FORK ROAD)	END OF PAVEMENT	1.21	Full Depth Patching and Double Seal and Fog Seal	$90,750
2030	13	059-McDowell	Resurfacing	)1 (MONTFORD COVE ROAD/SUGAR HILL F	CROSSMAN DRIVE + .19 MI.	SR 1162 (CHARLIE DRIVE)	5.71	Full Depth Patching and 1.5" S9.5C	$2,127,000
2030	13	059-McDowell	Resurfacing	1 (SUGAR HILL ROAD/WEST HENDERSON S	SR 1183 (STROUD STREET)	LD WEST HENDERSON STREET (CIT	1.22	Full Depth Patching and 1.5" S9.5C	$801,250
2030	13	059-McDowell	Resurfacing	SR 1001 (WEST HENDERSON STREET)	OLD WEST HENDERSON STREET (CITY)	US 221 BUISNESS	0.68	Full Depth Patching and 1.5" S9.5C	$389,000
2030	13	059-McDowell	Resurfacing	SR 1100 (MOUNT HEBRON ROAD)	BUNCOMBE COUNTY LINE	SR 1101 (HEBRON HILL ROAD)	2.70	Full Depth Patching and 1.5" S9.5C	$520,980
2030	13	059-McDowell	Resurfacing	SR 1104 (ROY MOORE ROAD)	SR 1103 (BAT CAVE ROAD)	SR 1105 (CHERRY SPRINGS ROAD)	0.32	Full Depth Patching and 1.25" S9.5B	$67,770
2030	13	059-McDowell	Resurfacing	SR 1191 (VETERANS DRIVE)	SR 1001 (SUGAR HILL ROAD)	SR 1195 (NIX CREEK ROAD)	0.94	Full Depth Patching and 1.5" S9.5C	$210,770
2030	13	059-McDowell	Resurfacing	SR 1299 (VETERANS DRIVE)	SR 1195 (NIX CREEK)	END OF MAINTENANCE	0.38	Full Depth Patching and 1.5" S9.5C	$81,500
2030	13	059-McDowell	Resurfacing	SR 1338 (HIDDEN VIEW LOOP ROAD)	SR 1214 (OLD GREENLEE ROAD)	SR 1214 (OLD GREENLEE ROAD)	1.17	Full Depth Patching and 1.5" S9.5C	$245,000
2030	13	059-McDowell	Resurfacing	SR 1446 (BEAR WALLOW ROAD)	MITCHELL C/L	NC 226 ALT	0.87	Full Depth Patching and 1.5" S9.5C	$185,950
2030	13	059-McDowell	Resurfacing	SR 1569 (NORTH COVE SCHOOL ROAD)	SR 1560 (OLD LINVILLE ROAD)	US 221	0.40	Full Depth Patching and 1.5" S9.5C	$85,995
2030	13	059-McDowell	Resurfacing	SR 1573 (PITTS STATION)	SR 1560 (OLD LINVILLE ROAD)	US 221	0.29	Full Depth Patching and 1.5" S9.5C	$83,270
2030	13	059-McDowell	Preservation	1309 (WINDSWEPT DRIVE)	SR 1153 (GOOSE CREEK ROAD)	END OF MAINTENANCE	0.17	Full Depth Patching and Double Seal and Fog Seal	$15,000
2030	13	059-McDowell	Preservation	COXES CREEK CHURCH ROAD	NC 226	END OF MAINT	0.46	Full Depth Patching and Double Seal and Fog Seal	$35,569
2030	13	059-McDowell	Preservation	SR 1163 (DINK CANNON ROAD)	SR 1351 (MUDCUT ROAD)	SR 1001 (SUGAR HILL ROAD)	1.36	Full Depth Patching and Double Seal and Fog Seal	$99,400
2030	13	059-McDowell	Preservation	SR 1276 (INDUSTRIAL DRIVE)	END OF MAINTENANCE	SR 1168 (ASHWORTH ROAD)	0.12	Full Depth Patching and Double Seal and Fog Seal	$9,360
2030	13	059-McDowell	Preservation	SR 1357 (STONE CREEK DRIVE)	SR 1191 (NIX CREEK ROAD)	CUL-DE-SAC	0.18	Full Depth Patching and 1.0" S4.75A	$22,500
2030	13	059-McDowell	Preservation	SR 1452 (OSBORNE KNOB ROAD)	SR 1446 (BEAR WALLOW ROAD)	MITCHELL C/L	0.48	Full Depth Patching and Double Seal and Fog Seal	$36,000
2030	13	059-McDowell	Preservation	SR 1456 (STOCKTON ROAD)	NC 226 ALT	END OF MAINTENANCE	0.35	Full Depth Patching and Double Seal and Fog Seal	$25,875
2030	13	059-McDowell	Preservation	SR 1552 (LAKE JAMES ROAD)	SR 1501 (HANKINS ROAD)	DALES CREEK BRIDGE (#73)	4.19	Full Depth Patching and Double Seal and Fog Seal	$304,000
2030	13	059-McDowell	Preservation	SR 1603 (LINVILLE FALLS CHURCH ROAD)	NC 183	NC 183	0.24	Full Depth Patching and Double Seal and Fog Seal	$20,000
2030	13	059-McDowell	Preservation	SR 1776 (PIERCE ROAD)	SR 1775 (WALKER ROAD)	SR 1777 (LANDIS LANE)	0.70	Full Depth Patching and Double Seal and Fog Seal	$52,500
2030	13	059-McDowell	Preservation	SR 1802 (VEIN MOUNTAIN)	SR 1783 (MACEDONIA CHURCH LOOP ROAD)	SR 1781 POLLY SPROUT ROAD)	3.54	Full Depth Patching and Double Seal and Fog Seal	$265,500
2030	13	061-Mitchell	Resurfacing	00 (CHESTNUT GROVE/MCKINNEY MINE R	MCDOWELL COUNTY LINE	MP 2.45 (PAVEMENT CHANGE)	2.45	Full Depth Patching and 1.5" S9.5C	$489,000
2030	13	061-Mitchell	Resurfacing	. (NORTH MITCHELL AVENUE/ CANE CREEK	NC 221	217 (GREEN YOUNG CEMETERY RC	2.00	Full Depth Patching and 1.5" S9.5C	$479,000
2030	13	061-Mitchell	Resurfacing	SR 1250 (SNOW CREEK ROAD)	SR 1250 (ORCHARD ROAD)	NC 226	0.49	Full Depth Patching and 1.5" S9.5C	$105,250
2030	13	061-Mitchell	Resurfacing	SR 1361 (LONGVIEW DRIVE)	NC 261	END OF PAVEMENT	0.31	Full Depth Patching and 1.25" S9.5B	$67,500
2030	13	061-Mitchell	Resurfacing	SR 1405 (HOSPITAL DRIVE)	SR 1121 (ALTAPASS HIGHWAY)	END OF MAINTENANCE	0.47	Full Depth Patching and 1.25" S9.5B	$103,999
2030	13	061-Mitchell	Preservation	SR 1189 (MINNIE LANE)	NC 226	END OF PAVEMENT	0.44	Full Depth Patching and Double Seal and Fog Seal	$34,000
2030	13	061-Mitchell	Preservation	SR 1205 (GREENE COVE ROAD)	SR 1211 (CANE CREEK ROAD)	END OF PAVEMENT	1.81	Full Depth Patching and Double Seal and Fog Seal	$133,750
2030	13	061-Mitchell	Preservation	SR 1231 (JARRETT ROAD)	226 S HIGHWAY	END OF MAINTENANCE	0.30	Full Depth Patching and 1.0" S4.75A	$37,500
2030	13	061-Mitchell	Preservation	SR 1250 (WING ROAD)	NC 226 SOUTH	SR 1167(WING ROAD)	0.39	Full Depth Patching and Double Seal and Fog Seal	$29,250
2030	13	061-Mitchell	Preservation	SR 1316 (BRUMMETT CREEK ROAD)	SR 1312 (GRIFFITH ROAD)	END OF MAINTENANCE	1.39	Full Depth Patching and Double Seal and Fog Seal	$82,500
2030	13	061-Mitchell	Preservation	SR 1328 (BATTLE BRANCH ROAD)	SR 1325 (BEANS CREEK ROAD)	END OF MAINTENANCE	0.90	Full Depth Patching and Double Seal and Fog Seal	$70,000
2030	13	061-Mitchell	Preservation	SR 1332 (ODOMS CHAPEL ROAD)	SR 1330 (HUGHES GAP ROAD)	END OF MAINTENANCE	0.91	Full Depth Patching and Double Seal and Fog Seal	$74,000
2030	13	061-Mitchell	Preservation	SR 1350 (FLAT BRANCH ROAD)	NC 197	END OF MAINTENANCE	1.12	Full Depth Patching and Double Seal and Fog Seal	$82,550
2030	13	081-Rutherford	Resurfacing	BABER ROAD)	SR 1005 (COX ROAD)	SR 1153 (UNION ROAD)	0.81	Full Depth Patching and 1.25" S9.5B	$196,000
2030	13	081-Rutherford	Resurfacing	SR 1005 (COXE ROAD)	SR 1141 (GRAYS CREEK CHURCH ROAD)	US 221	5.25	Full Depth Patching and 1.25" S9.5B	$1,255,000
2030	13	081-Rutherford	Resurfacing	SR 1116 (HOGAN ROAD)	RAIL ROAD	US 221	3.66	Full Depth Patching and 1.5" S9.5C	$795,500
2030	13	081-Rutherford	Resurfacing	SR 1148 (CLEGHORN MILL ROAD)	SR 1004 (POORES FORD ROAD)	US 74	1.81	Full Depth Patching and 1.25" S9.5B	$401,500
2030	13	081-Rutherford	Resurfacing	SR 1192 (GRAYS CHAPEL CHURCH ROAD)	SR 1155 (GRAYS ROAD)	END OF MAINTENANCE	0.22	Full Depth Patching and 1.25" S9.5B	$45,500
2030	13	081-Rutherford	Resurfacing	SR 2125 (HARRIS HENRIETTA ROAD)	US 221	SR 1116 (HOGAN ROAD)	0.67	Full Depth Patching and 1.25" S9.5B	$178,090
2030	13	081-Rutherford	Resurfacing	SR 2125 (HARRIS HENRIETTA ROAD)	SR 2210 (CHAISE HIGH ROAD)	US 221	1.06	Full Depth Patching and 1.25" S9.5B	$238,550
2030	13	081-Rutherford	Resurfacing	SR 2148 (MORROW MOTORS ROAD)	SR 2210 (CHASE HIGH ROAD)	SR 2149 (DOGGETT GROVE ROAD)	1.34	Full Depth Patching and 1.25" S9.5B	$308,010
2030	13	081-Rutherford	Resurfacing	SR 2150 (BRIDGES FARM ROAD)	SR 2152 (MORNINGSTAR LAKE ROAD)	US 22221	1.32	Full Depth Patching and 1.25" S9.5B	$350,050
2030	13	081-Rutherford	Resurfacing	SR 2163 (NEWTON ROAD)	SR 2159 (DOGGETT ROAD)	SR 2164 (TANNERS GROVE ROAD)	0.56	Full Depth Patching and 1.25" S9.5B	$121,500
2030	13	081-Rutherford	Resurfacing	SR 2169 (OAKLAND ROAD)	US 221	US 221 ALTERNATE	4.58	Full Depth Patching and 1.25" S9.5B	$1,009,225
2030	13	081-Rutherford	Resurfacing	SR 2177 (BRACKETT ROAD)	SR 2173 (WASHINGTON STREET)	SR 2213 (SOUTH CHURCH STREET)	0.54	Full Depth Patching and 1.25" S9.5B	$129,000
2030	13	081-Rutherford	Resurfacing	SR 2184 (DANIEL ROAD)	US 74 ALTERNATE	SR 2159 (PINEY RIDGE ROAD)	0.53	Full Depth Patching and 1.25" S9.5B	$129,970

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	13	081-Rutherford	Resurfacing	SR 2185 (WITHROW ROAD)	US 74 BUS	SR 2184 (DANIEL ROAD)	0.98	Full Depth Patching and 1.25" S9.5B	$255,500
2030	13	081-Rutherford	Resurfacing	SR 2185 (WITHROW ROAD)	SR 2184 (DANIEL ROAD)	SR 2169 (OAKLAND ROAD)	1.18	Full Depth Patching and 1.25" S9.5B	$280,990
2030	13	081-Rutherford	Resurfacing	SR 2193 (OLD STONECUTTER ROAD)	SR 2292 (CC HOYLE ROAD)	SR 2201 (THUNDER ROAD)	1.73	Full Depth Patching and 1.5" S9.5C	$400,025
2030	13	081-Rutherford	Resurfacing	SR 2193 (OLD STONECUTTER ROAD)	SR 2194 (POORS FORD ROAD)	SR 2292 (CC HOYLE ROAD)	0.40	Full Depth Patching and 1.5" S9.5C	$85,000
2030	13	081-Rutherford	Resurfacing	SR 2198 (GRIFFIN ROAD)	SR 2179 (SUNSET MEMORIAL ROAD)	SR 2214 (MCDADE ROAD)	0.73	Full Depth Patching and 1.25" S9.5B	$176,500
2030	13	081-Rutherford	Resurfacing	SR 2200 (DAVENPORT ROAD)	SR 2194 (POORS FORD ROAD)	END OF PAVEMENT	0.73	Full Depth Patching and 1.0" S4.75A	$179,980
2030	13	081-Rutherford	Resurfacing	SR 2203 (LAUREL HILL DRIVE)	US 221 ALTERNATE	END OF MAINTENANCE	1.20	Full Depth Patching and 1.25" S9.5B	$290,000
2030	13	081-Rutherford	Resurfacing	SR 2214 (MCDADE ROAD)	SR 2159 (PINEY RIDGE ROAD)	SR 2169 (OAKLAND ROAD)	1.39	Full Depth Patching and 1.5" S9.5C	$335,000
2030	13	081-Rutherford	Resurfacing	SR 2215 (HENSON ROAD)	NC 221	BRIDGE 144 ABUTMENT	1.17	Full Depth Patching and 1.25" S9.5B	$280,000
2030	13	081-Rutherford	Resurfacing	SR 2261 (LANCASTER DRIVE)	SR 2162 (POPLAR STREET)	SR 2160 (POINTER ROAD)	0.46	Full Depth Patching and 1.25" S9.5B	$89,000
2030	13	081-Rutherford	Resurfacing	SR 2263 (CHURCH DRIVE)	US 221 ALTERNATE	END OF MAINTENANCE	0.17	Full Depth Patching and 1.0" S4.75A	$34,000
2030	13	081-Rutherford	Resurfacing	SR 2278 (OAKWOOD DRIVE)	SR 2179 (SUNSET MEMORIAL ROAD)	R 2179 (SUNSET MEMORIAL ROAD	0.35	Full Depth Patching and 1.0" S4.75A	$65,000
2030	13	081-Rutherford	Resurfacing	SR 2296 (MORROW ROAD)	SR 2169 (OAKLAND ROAD)	END OF MAINTENANCE	0.23	Full Depth Patching and 1.25" S9.5B	$54,000
2030	13	081-Rutherford	Resurfacing	SR 2306 (BABBIT LANE)	SR 2215 (HENSON ROAD)	END OF MAINTENANCE	0.10	Full Depth Patching and 1.0" S4.75A	$21,500
2030	13	081-Rutherford	Preservation	SR 1159 (JAY WHITE ROAD)	SR 1167 (RIVER ROAD)	END OF PAVEMENT	0.92	Full Depth Patching and Double Seal and Fog Seal	$69,000
2030	13	081-Rutherford	Preservation	SR 1170 (FLYNN DRIVE)	US 64	SR 1178 (MAPLE CREEK ROAD)	1.20	Full Depth Patching and Double Seal and Fog Seal	$90,000
2030	13	081-Rutherford	Preservation	SR 1171 (DAVE SIMS ROAD)	SR 1172 (COOPERS GAP ROAD)	SR 1178 (MAPLE CREEK ROAD)	1.24	Full Depth Patching and Double Seal and Fog Seal	$93,000
2030	13	081-Rutherford	Preservation	SR 1175 (CC LOVELACE ROAD)	SR 1172 (COOPERS GAP ROAD)	SR 1178 (MAPLE CREEK ROAD)	1.10	Full Depth Patching and Double Seal and Fog Seal	$82,500
2030	13	081-Rutherford	Preservation	SR 1176 (SID SIMS ROAD)	SR 1177 (MOSS ROAD)	END OF MAINTENANCE	0.55	Full Depth Patching and Double Seal and Fog Seal	$41,250
2030	13	081-Rutherford	Preservation	SR 1211 (STARVIEW DRIVE)	SR 1178 (MAPLE CREEK ROAD)	CUL DE SAC	0.56	Full Depth Patching and Double Seal and Fog Seal	$45,750
2030	13	081-Rutherford	Preservation	SR 1329 (BROOKS LAKE ROAD)	SR 1328 (PAINTERS GAP ROAD)	SR 1351 (DARLINGTON ROAD)	1.59	Full Depth Patching and Double Seal and Fog Seal	$119,250
2030	13	081-Rutherford	Preservation	SR 1342 (CAMBY ROAD)	SR 1341 (MCENTIRE ROAD	END OF MAINTENANCE	0.47	Full Depth Patching and Double Seal and Fog Seal	$35,250
2030	13	081-Rutherford	Preservation	SR 1352 (HAMPTON ROAD)	SR 1351 (DARLINGTON ROAD)	SR 1001 (COVE ROAD)	1.42	Full Depth Patching and Double Seal and Fog Seal	$106,500
2030	13	081-Rutherford	Preservation	SR 1354 (C FOWLER ROAD)	SR 1001 (COVE ROAD)	END OF PAVEMENT	0.25	Full Depth Patching and Double Seal and Fog Seal	$18,750
2030	13	081-Rutherford	Preservation	SR 1357 (HIPP ROAD)	SR 1351 (DARLINGTON ROAD)	END OF PAVEMENT	0.46	Full Depth Patching and Double Seal and Fog Seal	$34,500
2030	13	081-Rutherford	Preservation	SR 1364 (CASH ROAD)	SR 1355 (MOUNTAIN CREEK ROAD)	END OF MAINTENANCE	0.54	Full Depth Patching and Double Seal and Fog Seal	$40,500
2030	13	081-Rutherford	Preservation	R 1369 (FRADY STREET / HIGHLAND DRIVE	US 64	END OF MAINTENANCE	0.57	Full Depth Patching and Double Seal and Fog Seal	$42,750
2030	13	081-Rutherford	Preservation	SR 1382 (NIX ROAD)	SR 1328 (PAINTERS GAP ROAD)	END OF PAVEMENT	0.27	Full Depth Patching and Double Seal and Fog Seal	$20,250
2030	13	081-Rutherford	Preservation	SR 1383 (FLEMING DRIVE)	SR 1367 (THOMPSON ROAD)	END OF MAINTENANCE	0.37	Full Depth Patching and Double Seal and Fog Seal	$27,750
2030	13	081-Rutherford	Preservation	SR 1386 (WILKERSON ROAD)	SR 1372 (HOWELL ROAD)	END OF MAINTENANCE	0.12	Full Depth Patching and Double Seal and Fog Seal	$9,000
2030	13	081-Rutherford	Preservation	SR 1387 (CANDY ROCK ROAD)	SR 1321 (THERMAL CITY ROAD)	END OF MAINTENANCE	0.43	Full Depth Patching and Double Seal and Fog Seal	$32,250
2030	13	081-Rutherford	Preservation	SR 1390 (FOREST RIDGE ROAD)	SR 1351 (DARLINGTON ROAD)	CUL DE SAC	0.24	Full Depth Patching and 1.0" S4.75A	$30,000
2030	13	081-Rutherford	Preservation	SR 1393 (BENT TREE DRIVE)	US 64	CUL DE SAC	0.54	Full Depth Patching and 1.0" S4.75A	$81,000
2030	13	100-Yancey	Resurfacing	SR 1395 (BALD MOUNTAIN ROAD)	SR 1411 (LITTLE CREEK ROAD)	BRIDGE 126	4.46	Full Depth Patching and 1.5" S9.5C	$1,078,580
2030	13	100-Yancey	Preservation	SR 1348 (SAMPSON BRANCH ROAD)	SR 1349 (SWEETWATER ROAD)	END OF PAVEMENT	1.12	Full Depth Patching and Double Seal and Fog Seal	$84,000
2030	13	100-Yancey	Preservation	SR 1353 (SAM J BYRD ROAD)	SR 1336 (JACKS CREEK ROAD)	END OF PAVEMENT	0.64	Full Depth Patching and Double Seal and Fog Seal	$48,000
2030	13	100-Yancey	Preservation	SR 1355 (BAILEY BRANCH ROAD	SR 1336 (JACKS CREEK ROAD)	END OF PAVEMENT)	1.92	Full Depth Patching and Double Seal and Fog Seal	$144,000
2030	13	100-Yancey	Preservation	SR 1356 (BYRD BRANCH ROAD)	SR 1336 (JACKS CREEK ROAD)	1.63 + .13 MILE IS END OF PAVEMI	1.63	Full Depth Patching and Double Seal and Fog Seal	$125,000
2030	13	100-Yancey	Preservation	SR 1360 (STAR BRANCH ROAD)	SR 1336 (JACKS CREEK ROAD)	ND OF MAINTENANCE / CUL DE SA	0.92	Full Depth Patching and Double Seal and Fog Seal	$65,000
2030	13	100-Yancey	Preservation	SR 1361 (MOSES BRANCH ROAD)	SR 1336 (JACKS CREEK ROAD)	END OF PAVEMENT	1.12	Full Depth Patching and Double Seal and Fog Seal	$76,250
2030	13	100-Yancey	Preservation	SR 1362 (CARL FOX / EVANS ROAD)	SR 1336 (JACKS CREEK ROAD)	CUL DE SAC	0.58	Full Depth Patching and Double Seal and Fog Seal	$43,500
2030	13	100-Yancey	Preservation	SR 1363 (CARL FOX ROAD)	SR 1362 (CARL FOX/ EVANS ROAD)	END OF PAVEMENT	0.11	Full Depth Patching and Double Seal and Fog Seal	$8,250
2030	14	020-Cherokee	Resurfacing	NC 60	US 64	Cherokee Co Line	5.06	Mill 1.5" and 1.5" S9.5C	$4,000,000
2030	14	020-Cherokee	Resurfacing	SR 1331	Pavement @ Beaverdam Rd	SR 1326	5.39	Full Depth Patching and 1.5" S9.5B	$1,482,250
2030	14	020-Cherokee	Preservation	SR 1104	BRIDGE	SR 1101	0.30	Seal - Double and Fog Seal	$21,000
2030	14	020-Cherokee	Preservation	SR 1104	GA LINE	BRIDGE	1.85	Seal - Double and Fog Seal	$129,500
2030	14	020-Cherokee	Preservation	SR 1153	NC 294	END PVMT	0.19	Seal - Double and Fog Seal	$13,580
2030	14	020-Cherokee	Preservation	SR 1158	SR 1150	SR 1143	2.81	Seal - Double and Fog Seal	$196,910
2030	14	020-Cherokee	Preservation	SR 1381	SR 1379	Bridge	1.07	Seal - Double and Fog Seal	$74,900
2030	14	020-Cherokee	Preservation	SR 1531	SR 1670	SR 1687	1.38	Seal - Double and Fog Seal	$96,600
2030	14	020-Cherokee	Preservation	SR 1558	Pvmt Chng	SR 1564	2.23	Seal - Double and Fog Seal	$156,100
2030	14	022-Clay	Resurfacing	SR 1116	NC 69	NC 69	1.70	1.5" S9.5B	$467,500
2030	14	022-Clay	Resurfacing	SR 1118	NC 69	SR 1100 (Old Hwy 64)	1.79	1.5" S9.5B	$492,250
2030	14	022-Clay	Preservation	SR 1302	Cherokee CL	SR 1300	1.65	Seal - Double and Fog Seal	$115,500
2030	14	022-Clay	Preservation	SR 1303	US 64	EOP	1.11	Seal - Double and Fog Seal	$77,700
2030	14	022-Clay	Preservation	SR 1359	SR 1372	EOP	0.08	Seal - Double and Fog Seal	$5,600
2030	14	022-Clay	Preservation	SR 1372	SR 1300	EOP	0.48	Seal - Double and Fog Seal	$33,600
2030	14	038-Graham	Resurfacing	NC 28	US 143	SR 1287	6.18	Full Depth Patching and 1.5" S9.5C	$2,000,000
2030	14	038-Graham	Resurfacing	SR 1202	US 129	EOM	1.02	Full Depth Patching and 1.25" S9.5B	$275,000

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	14	038-Graham	Resurfacing	SR 1255	US 129	EOM	0.31	Full Depth Patching and 1.25" S9.5B	$77,500
2030	14	038-Graham	Preservation	SR 1111	SR 1110	EOP	0.65	Seal - Double and Fog Seal	$45,500
2030	14	038-Graham	Preservation	SR 1214	NC 143	EOP	4.54	Seal - Double and Fog Seal	$317,870
2030	14	044-Haywood	Resurfacing	SR 1585	NC 215	SR 1613	1.42	Full Depth Patching and 1.5" S9.5B	$390,500
2030	14	044-Haywood	Resurfacing	SR 1589	NC 215	SR 1585	0.73	Full Depth Patching and 1.5" S9.5B	$115,500
2030	14	044-Haywood	Resurfacing	SR 1613	SR 1001	County Line	5.79	Full Depth Patching and 1.25" S9.5B	$1,592,250
2030	14	044-Haywood	Preservation	1625	NC 209	MP0.210	0.19	Seal - Double and Fog Seal	$13,510
2030	14	044-Haywood	Preservation	SR 1130	276	deaf end	0.66	Seal - Double and Fog Seal	$46,340
2030	14	044-Haywood	Preservation	SR 1240	SR 1129	DEAD END	0.23	Seal - Double and Fog Seal	$15,890
2030	14	044-Haywood	Preservation	SR 1256	SR 1255	DEAD END	0.05	Seal - Double and Fog Seal	$3,500
2030	14	044-Haywood	Preservation	SR 1259	SR 1258	EOM	0.14	Seal - Double and Fog Seal	$9,800
2030	14	044-Haywood	Preservation	SR 1357	SR 1355	NC 209	1.04	Seal - Double and Fog Seal	$72,800
2030	14	044-Haywood	Preservation	SR 1518	SR 1654	MP 0.409	0.41	Seal - Double and Fog Seal	$28,630
2030	14	044-Haywood	Preservation	SR 1662	NC 209	DEAD END	0.20	Seal - Double and Fog Seal	$13,650
2030	14	044-Haywood	Preservation	SR 1852	SR 1849	EOM	0.25	Seal - Double and Fog Seal	$17,640
2030	14	044-Haywood	Preservation	SR 1854	SR 1850	SR 1849	1.38	Seal - Double and Fog Seal	$96,600
2030	14	044-Haywood	Preservation	SR 1854	END C&G	SR 1850	1.13	Seal - Double and Fog Seal	$79,100
2030	14	044-Haywood	Preservation	SR 1858	SR 1847	EOM	1.27	Seal - Double and Fog Seal	$88,900
2030	14	044-Haywood	Preservation	SR 1864	SR 1847	SR 1863	0.83	Seal - Double and Fog Seal	$58,100
2030	14	044-Haywood	Preservation	SR 1867	NC 110	SR 1871	1.26	Seal - Double and Fog Seal	$88,410
2030	14	044-Haywood	Preservation	SR 1885	US 276	US 276	0.93	Seal - Double and Fog Seal	$65,310
2030	14	044-Haywood	Preservation	SR 1895	US 276	DEAD END	0.18	Seal - Double and Fog Seal	$12,530
2030	14	044-Haywood	Preservation	SR 1917	SR 1871	DEAD END	0.26	Seal - Double and Fog Seal	$18,060
2030	14	044-Haywood	Preservation	SR 1936	NC 110	NS 99291	0.23	Seal - Double and Fog Seal	$16,100
2030	14	044-Haywood	Preservation	SR 1947	SR 1922	DEAD END	0.04	Seal - Double and Fog Seal	$2,800
2030	14	045-Henderson	Resurfacing	SR 1188	Laurel Park	SR 1171	3.80	1.25" S9.5B	$1,046,100
2030	14	045-Henderson	Resurfacing	SR 1602	SR 1973	Pvmt Change	4.75	Full Depth Patching and 1.5" S9.5B	$1,306,250
2030	14	045-Henderson	Resurfacing	SR 1710	SR 1602	SR 1602	2.94	1.25" S9.5B	$588,000
2030	14	045-Henderson	Resurfacing	SR 2233	NC 280	SR 2228	0.07	1.5" S9.5B	$18,975
2030	14	045-Henderson	Resurfacing	US 25	US 64	Bridge #169	3.66	Mill 1.5" and 1.5" S9.5C and Full Depth Patching	$5,000,000
2030	14	045-Henderson	Preservation	SR 1171	SR 1210	SR 2155	2.79	Seal - Double and Fog Seal	$195,300
2030	14	045-Henderson	Preservation	SR 1316	SR 1317	NC 280	2.68	Seal - Double and Fog Seal	$187,600
2030	14	045-Henderson	Preservation	SR 1322	SR 1323	SR 1325	1.15	Seal - Double and Fog Seal	$80,500
2030	14	045-Henderson	Preservation	SR 1381	NC 191	Bus 25	1.62	Seal - Double and Fog Seal	$113,330
2030	14	045-Henderson	Preservation	SR 1463	NC 191	NC 191	0.52	Seal - Double and Fog Seal	$36,400
2030	14	045-Henderson	Preservation	SR 1464	SR 1463	EOP	0.06	Seal - Double and Fog Seal	$4,200
2030	14	045-Henderson	Preservation	SR 1465	SR 1463	EOP	0.09	Seal - Double and Fog Seal	$6,300
2030	14	045-Henderson	Preservation	SR 1468	SR 1463	EOP	0.16	Seal - Double and Fog Seal	$11,200
2030	14	045-Henderson	Preservation	SR 1846	SCL	PCL	3.02	Seal - Double and Fog Seal	$211,400
2030	14	045-Henderson	Preservation	SR 1847	SR 1838	SR 1846	1.34	Seal - Double and Fog Seal	$93,520
2030	14	045-Henderson	Preservation	SR 1980	NC 191	SR 1381	0.43	Seal - Double and Fog Seal	$30,100
2030	14	045-Henderson	Preservation	SR 1982	SR 1980	EOP	0.09	Seal - Double and Fog Seal	$6,300
2030	14	045-Henderson	Preservation	SR 1983	SR 1980	EOP	0.07	Seal - Double and Fog Seal	$4,830
2030	14	045-Henderson	Preservation	SR 1984	SR 1980	EOP	0.08	Seal - Double and Fog Seal	$5,460
2030	14	045-Henderson	Preservation	SR 2007	SR 1463	EOP	0.04	Seal - Double and Fog Seal	$2,800
2030	14	045-Henderson	Preservation	SR 2417	SR 2416	SR 2406	0.33	Seal - Double and Fog Seal	$23,100
2030	14	050-Jackson	Resurfacing	SR 1001	SR 1330	NC 107	0.85	Full Depth Patching and 1.5" S9.5A	$233,750
2030	14	050-Jackson	Resurfacing	SR 1120	PVMT CHNG	US 64	1.83	Seal - Double and Fog Seal	$502,975
2030	14	050-Jackson	Resurfacing	SR 1149	SR 1188	SR 1145	3.96	Full Depth Patching and 1.5" S9.5B	$1,089,000
2030	14	050-Jackson	Resurfacing	SR 1443	SR 1522	EOP	1.38	#78 Mat Seal and 1.25" S9.5A	$379,500
2030	14	050-Jackson	Resurfacing	SR 1731	SR 1730	EOP	1.82	Full Depth Patching and 1.25" S9.5A	$500,500
2030	14	050-Jackson	Preservation	SR 1110	SR 1111	EOP	0.38	Seal - Double and Fog Seal	$26,600
2030	14	050-Jackson	Preservation	SR 1111	SR 1112	SR 1110	0.22	Seal - Double and Fog Seal	$15,400
2030	14	050-Jackson	Preservation	SR 1131	NC 107	EOP	0.21	Seal - Double and Fog Seal	$14,700
2030	14	050-Jackson	Preservation	SR 1141	NC 107	US 64	0.64	Seal - Double and Fog Seal	$44,590
2030	14	050-Jackson	Preservation	SR 1176	NC 107	SR 1182	0.30	Seal - Double and Fog Seal	$21,000
2030	14	050-Jackson	Preservation	SR 1186	NC 107	SR 1176	0.20	Seal - Double and Fog Seal	$14,000
2030	14	050-Jackson	Preservation	SR 1301	SR 1300	EOM	0.73	Seal - Double and Fog Seal	$51,100
2030	14	050-Jackson	Preservation	SR 1304	SR 1300	EOP	0.35	Seal - Double and Fog Seal	$24,500

Plan Year	Division	County	Budget Group	Route	Begin Description	End Description	Length	Treatment	Estimated Cost
2030	14	050-Jackson	Preservation	SR 1507	SR 1330	EOM	0.98	Seal - Double and Fog Seal	$68,600
2030	14	050-Jackson	Preservation	SR 1757	SR 1756	NC 281	2.62	Seal - Double and Fog Seal	$183,400
2030	14	056-Macon	Resurfacing	NC-28	SR-1710	SR-1613	2.10	Full Depth Patching and 1.5" S9.5B	$577,500
2030	14	056-Macon	Resurfacing	SR-1148	SR-1442	US-64	0.15	Full Depth Patching and 1.5" S9.5B	$41,500
2030	14	056-Macon	Resurfacing	SR-1148	US-64	SR-1148	1.30	Full Depth Patching and 1.5" S9.5B	$415,250
2030	14	056-Macon	Resurfacing	SR-1313	SR-1442	EOM	0.74	Full Depth Patching and 1.5" S9.5B	$203,500
2030	14	056-Macon	Resurfacing	SR-1331	US-23	US-23	1.70	Full Depth Patching and 1.5" S9.5B	$467,500
2030	14	056-Macon	Resurfacing	SR-1630	US-441S	US-441S	0.62	Full Depth Patching and 1.5" S9.5B	$170,500
2030	14	056-Macon	Preservation	SR 1514	NC 28	SR 1568	0.68	Seal - Double and Fog Seal	$47,600
2030	14	056-Macon	Preservation	SR -1684	SR-1634	SR-1636	0.99	Seal - Double and Fog Seal	$60,090
2030	14	056-Macon	Preservation	SR-1397	SR-1475	EOM on Sam Walters Rd	1.43	Seal - Double and Fog Seal	$100,100
2030	14	056-Macon	Preservation	SR-1412	SR 1412	SR 1414	0.87	Seal - Double and Fog Seal	$60,900
2030	14	056-Macon	Preservation	SR-1611	NC-28	SR-1613	1.34	Seal - Double and Fog Seal	$93,800
2030	14	056-Macon	Preservation	SR-1613	SR-1618	NC-28	3.40	Seal - Double and Fog Seal	$237,790
2030	14	056-Macon	Preservation	SR-1618	NC-28	EOP	0.53	Seal - Double and Fog Seal	$37,100
2030	14	075-Polk	Resurfacing	SR 1137	NC 108	NC 108	3.37	Full Depth Patching and 1.5" S9.5B	$1,011,000
2030	14	075-Polk	Resurfacing	US 74E	NC 9 Overpass	Polk Co Line	6.02	Mill 1.5" and 1.5" S9.5B and .75" OGFC	$4,000,000
2030	14	075-Polk	Resurfacing	US 74W	Polk Co Line	NC 9 Overpass	6.03	Mill 1.5" and 1.5" S9.5B and .75" OGFC	$4,000,000
2030	14	075-Polk	Preservation	SR 1115	SR 1116	EOSM	0.61	Seal - Double and Fog Seal	$42,350
2030	14	075-Polk	Preservation	SR 1116	SR 1116	SR 1115	1.57	Seal - Double and Fog Seal	$109,900
2030	14	075-Polk	Preservation	SR 1116	SR 1116	EOP	2.75	Seal - Double and Fog Seal	$192,500
2030	14	075-Polk	Preservation	SR 1174	SR 1116	EOP	0.97	Seal - Double and Fog Seal	$67,900
2030	14	075-Polk	Preservation	SR 1176	SR 1174	EOSM	0.67	Seal - Double and Fog Seal	$46,900
2030	14	087-Swain	Resurfacing	1133	SR 1131	EOM	2.25	Full Depth Patching and 1.5" S9.5B	$652,780
2030	14	087-Swain	Preservation	SR 1171	SR 1195	DEAD END	0.19	Seal - Double and Fog Seal	$13,090
2030	14	087-Swain	Preservation	SR 1184	SR 1195	EOM	0.20	Seal - Double	$13,650
2030	14	087-Swain	Preservation	SR 1301	NC 28	END MAINT	1.18	Seal - Double and Fog Seal	$82,460
2030	14	087-Swain	Preservation	SR 1320	US 19	US 19	0.19	Seal - Double	$13,370
2030	14	087-Swain	Preservation	SR 1332	SR 1333	DEAD END	0.30	Seal - Double and Fog Seal	$20,930
2030	14	087-Swain	Preservation	SR 1340	SR 1337	SR 1339	0.20	Seal - Double and Fog Seal	$14,000
2030	14	087-Swain	Preservation	SR 1352	SR 1351	EOM	0.78	Seal - Double and Fog Seal	$54,600
2030	14	087-Swain	Preservation	SR 1367	US 19	EOM	0.33	Seal - Double and Fog Seal	$23,100
2030	14	087-Swain	Preservation	SR 1372	US 19	EOM	0.49	Seal - Double and Fog Seal	$34,300
2030	14	087-Swain	Preservation	SR 1382	SR 1352	SR 1352	0.30	Seal - Double and Fog Seal	$21,000
2030	14	088-Transylvania	Resurfacing	SR 1314	SR 1313	MP 1.634	0.41	Mill 1.25" and 1.25" S9.5B	$111,375
2030	14	088-Transylvania	Resurfacing	SR 1326	NC 215	BRIDGE	2.10	1.25" S9.5B	$576,950
2030	14	088-Transylvania	Resurfacing	SR 1326	BRIDGE	SR 1310	0.96	1.25" S9.5B	$264,000
2030	14	088-Transylvania	Resurfacing	SR 1388	US 178	US 64	2.84	1.25" SF9.5A	$780,450
2030	14	088-Transylvania	Resurfacing	SR 1504	US 64	SR 1528	0.79	1.25" S9.5B	$217,250
2030	14	088-Transylvania	Resurfacing	SR 1505	SR 1506	EOM	0.59	1.25" S9.5B	$162,800
2030	14	088-Transylvania	Resurfacing	SR 1527	SR 1577	SR 1528	0.98	1.25" S9.5B	$269,775
2030	14	088-Transylvania	Preservation	SR 1108	SR 1103	EOM	0.56	Seal - Double and Fog Seal	$38,990
2030	14	088-Transylvania	Preservation	SR 1113	SR 1110	SR 1114	1.66	Seal - Double and Fog Seal	$115,990
2030	14	088-Transylvania	Preservation	SR 1140	US 178	US 178	0.49	Seal - Double and Fog Seal	$34,160
2030	14	088-Transylvania	Preservation	SR 1160	US 64	EOM	0.23	Seal - Double and Fog Seal	$16,100
2030	14	088-Transylvania	Preservation	SR 1332	SR 1392	EOM	0.61	Seal - Double and Fog Seal	$42,490
2030	14	088-Transylvania	Preservation	SR 1333	SR 1393	EOM	0.11	Seal - Double and Fog Seal	$7,490
2030	14	088-Transylvania	Preservation	SR 1335	SR 1334	EOM	0.51	Seal - Double and Fog Seal	$35,700
2030	14	088-Transylvania	Preservation	SR 1336	SR 1334	EOM	0.21	Seal - Double and Fog Seal	$14,700
2030	14	088-Transylvania	Preservation	SR 1371	US 178	EOM	0.48	Seal - Double and Fog Seal	$33,530
2030	14	088-Transylvania	Preservation	SR 1387	SR 1337	EOM	0.16	Seal - Double and Fog Seal	$11,200
2030	14	088-Transylvania	Preservation	SR 1393	SR 1394	EOM	0.15	Seal - Double and Fog Seal	$10,500

Highway Maintenance Improvement Program Needs Assessment Report

Pursuant to N.C.G.S. 136-44.3A.(g) the North Carolina Department of Transportation (NCDOT) submits the following report on the Highway Maintenance Improvement Program (HMIP) Needs Assessment.

Background and Methodology

The needs-based assessment is a five-year pavement analysis of investment needed to meet the level of service (LOS) targets at the end of the fifth year. The goal of this analysis is to minimize the cost to reach the LOS targets. Five years is used in the analysis to minimize budgetary impacts. The average of the five-year analysis facilitates a consistent paving program and provides a projected budget that will result in reaching target service levels.

2024 pavement conditions for the primary (NC and US routes) and secondary systems are:

System	% Good	% Fair	% Poor
Primary (NC and US Routes)	59.33	22.47	18.02
Secondary	68.22	26.95	4.82

LOS goals by system are:

System	% Good (Minimum)	% Poor (Maximum)
Primary (NC and US Routes)	80	7.5
Secondary	70	10

For example, if a division has a current primary system score of 60% good and 15% poor. Instead of setting the analysis to meet targets in year one, the targets in the analysis are set as shown below. This gradual increase of LOS minimizes budgetary swings in any given year.

Year	% Good	% Poor
1	64	13
2	68	11
3	72	9
4	76	8
5	80	7.5

As a second example, if a division is at target or slightly above target with a primary system score of 82% good and 8% poor, the targets in the analysis are set to maintain current LOS as shown below.

Year	% Good	% Poor
1	82	7.5
2	82	7.5
3	82	7.5
4	82	7.5
5	82	7.5

The analysis consists of an automated and iterative process which applies preservation, resurfacing and rehabilitation treatments to achieve target LOS over the five-year period. Preservation treatments, such as crack sealing and chip seals, are applied to roads in high-fair to good condition in order to extend their service life. Resurfacing treatments include single and double layer overlays and mill and fill operations. Rehabilitation is done to correct existing deficiencies and to increase the structural capacity (thickness) of a pavement to meet future traffic needs.

The analysis provides results in the budget categories for preservation, resurfacing, and rehabilitation. This report includes the estimated cost for each budget category for each division. The average cost over the five-year period is calculated for each division and each budget category. The rehabilitation and resurfacing categories are then combined as they are both funded from the contract resurfacing appropriation.

Budgeting and Allocations

The needs assessment, along with the inventory of roads in each division, provides the basis to calculate the allocations for each funding category. A division's needs-based portion of their allocation in a funding category is the ratio of the division's need in that category divided by the statewide total need in that category, unless otherwise stated in legislation. Similarly, a division's inventory-based portion of their allocation in a funding category is the ratio of the division's inventory of roads divided by the statewide total inventory of roads.

These allocations are used as inputs to the budget-based analysis, generating the starting point for the 5-year HMIP plan. The goal of a budget-based analysis is to maximize the benefit to the system when constrained by the budget. The benefit can be expressed in terms of pavement condition over time. By simulating a five-year needs assessment, an agency will deplete less expensive treatment projects and will begin treating roads requiring more extensive work, such as, patching or thicker overlays. Over time, more of the system is in good condition, but must have preservation and resurfacing treatments to maintain this condition.

Division Needs

The HMIP needs assessment indicates the following monetary needs per year to meet LOS:

- $115,342,380 in pavement preservation funding
- $815,992,496 in contract resurfacing funding

The estimated lanes miles needed to be treated per year are approximately:

- 13,088 in pavement preservation
- 7,395 in contract resurfacing

The planned lane miles in the FY 2026 – FY 2030 HMIP plan per year are approximately:

- 2,925 in preservation
- 5,083 in resurfacing

Per N.C.G.S. 136-44.3A.(c) the current HMIP plan is based on previous FY allocations and will be adjusted according to the Department's needs-based allocation process during the current budget cycle.

System Needs Analysis						
Division	**Pavement Preservation Per Year**			**Contract Resurfacing Per Year**		
	Needed Cost	**Needed Lane Miles**	**Planned Lane Miles**	**Needed Cost**	**Needed Lane Miles**	**Planned Lane Miles**
1	$5,616,809	567	167	$64,119,015	582	952
2	$7,426,019	836	128	$57,624,573	460	328
3	$7,319,560	737	147	$66,334,825	553	386
4	$8,377,479	964	264	$78,133,764	633	1,429
5	$6,724,453	796	103	$79,405,038	683	444
6	$12,909,771	1,634	341	$50,764,540	760	1.057
7	$6,116,304	789	279	$57,029,685	553	932
8	$10,476,663	1,186	350	$66,921,970	598	1,509
9	$7,084,237	890	189	$51,462,227	506	732
10	$6,945,407	909	215	$68,868,115	610	307
11	$12,213,690	1,150	165	$33,817,741	306	167
12	$8,413,791	1,016	250	$55,141,682	593	1,169
13	$8,549,090	933	160	$41,770,220	411	741
14	$7,169,107	682	166	$44,599,101	372	548
Totals	**$115,342,380**	**13,088**	**2,925**	**$815,992,496**	**7,395**	**5,083**
FY 2025 Allocation	**$85,800,267**			**$626,919,880**		

Table 1: Pavement Preservation and Contract Resurfacing needed dollars and needed lane miles.

ROUTINE MAINTENANCE - RMIP

Statewide - Estimated Costs for Planned Work Functions

Asset Category	Work Code	Description	FY 2026	FY 2027	FY 2028	FY2029	FY 2030	5-Year-Total
Bridge Maintenance	3309	Replacement of Bridge Expansion Joints	$5,349,016	$5,451,166	$5,451,166	$5,451,166	$5,451,166	$27,153,679
	3310	Maintenance / Repair Bridge Expansion Joints	$ 310,680	$ 310,680	$ 310,680	$ 310,680	$ 310,680	$ 1,553,400
	3314	Maintain / Repair Steel Superstructure Components	$ 2,786,627	$ 2,809,935	$ 2,809,935	$ 2,809,935	$ 2,809,935	$ 14,026,367
	3316	Maintenance of Timber Rail	$ 2,249,685	$ 2,297,299	$ 2,297,299	$ 2,297,299	$ 2,297,299	$ 11,438,882
	3326	Maintain Concrete Deck	$ 153,790	$ 155,201	$ 155,201	$ 155,201	$ 155,201	$ 774,592
	3328		$ 616,654	$ 618,709	$ 618,709	$ 618,709	$ 618,709	$ 3,091,491
	3342	Clean and Paint Structural Steel	$ 792,081	$ 793,221	$ 793,221	$ 793,221	$ 793,221	$ 3,964,965
	3352	Maint Slope Protection	$ 1,791,250	$ 1,810,791	$ 1,810,791	$ 1,810,791	$ 1,810,791	$ 9,034,415
	3366	Drift and Debris Removal	$ 975,899	$ 991,691	$ 991,691	$ 991,691	$ 991,691	$ 4,942,664
	3376	Clean / Wash Bridge Decks	$ 4,799,546	$ 4,839,491	$ 4,839,491	$ 4,839,491	$ 4,839,491	$ 24,157,511
Pipe	3126	Install Pipes (48” or Less)	$ 43,174,298	$ 45,432,760	$ 45,432,760	$ 45,432,760	$ 45,432,760	$ 224,905,337
	3128	Maint / Repair Pipes (48” or less)	$ 6,684,971	$ 7,200,562	$ 7,200,562	$ 7,200,562	$ 7,200,562	$ 35,487,220
	3300	Install Non NBIS >48” Up To NBIS Structures	$ 24,377,668	$ 25,669,646	$ 25,669,646	$ 25,669,646	$ 25,669,646	$ 127,056,254
	3302	Repair Non NBIS >48” Up To NBIS Structures	$ 5,331,541	$ 5,596,358	$ 5,596,358	$ 5,596,358	$ 5,596,358	$ 27,716,974
	3368	Installation of NBIS Pipes and Culverts	$ 3,334,010	$ 3,510,679	$ 3,510,679	$ 3,510,679	$ 3,510,679	$ 17,376,725
	3370	Repair of NBIS Pipes and Culverts	$ 115,142	$ 121,292	$ 121,292	$ 121,292	$ 121,292	$ 600,309
Shoulder and Ditch	3108	Drainage Ditch Maintenance	$ 13,251,328	$ 13,971,071	$ 13,971,071	$ 13,971,071	$ 13,971,071	$ 69,135,614
	3109	Maintenance of Shoulders AND Ditches	$ 29,236,478	$ 30,714,762	$ 30,714,762	$ 30,714,762	$ 30,714,762	$ 152,095,527
	3112	Shoulder Maintenance / Reconstruction	$ 32,682,090	$ 34,414,615	$ 34,414,615	$ 34,414,615	$ 34,414,615	$ 170,340,550
Specialty Services & Operations	2920	Rest Areas & Welcome Centers Operations	$ 14,309,711	$ 14,319,448	$ 14,319,448	$ 14,319,448	$ 14,319,448	$ 71,587,501
	3104	Litter Removal	$ 16,270,856	$ 16,652,372	$ 16,652,372	$ 16,652,372	$ 16,652,372	$ 82,880,346
Traffic Devices/Safety	3200		$ 6,086,702	$ 6,400,307	$ 6,400,307	$ 6,400,307	$ 6,400,307	$ 31,687,928
	3222	Long Line Painted Pavement Markings	$ 7,896,796	$ 8,149,723	$ 8,149,723	$ 8,149,723	$ 8,149,723	$ 40,495,689
	3226	Long Line Specialty Material Pavement Markings	$ 21,403,075	$ 20,362,681	$ 20,362,681	$ 20,362,681	$ 20,362,681	$ 102,853,798
	3236	Traffic Signal Routine Maintenance	$ 10,927,388	$ 11,512,812	$ 11,512,812	$ 11,512,812	$ 11,512,812	$ 56,978,636
	3250	Installation of Ground Mounted Signs	$ 15,728,126	$ 18,866,949	$ 18,866,949	$ 18,866,949	$ 18,866,949	$ 91,195,922
Vegetation Management	2900	Grass Mowing	$ 38,230,598	$ 38,359,378	$ 38,359,378	$ 38,359,378	$ 38,359,378	$ 191,668,109
	2908	Brush and Tree Control /Herbicides	$ 3,219,300	$ 3,248,442	$ 3,248,442	$ 3,248,442	$ 3,248,442	$ 16,213,069
	2912	Mechanical Brush and Tree Control	$ 18,131,564	$ 18,711,018	$ 18,711,018	$ 18,711,018	$ 18,711,018	$ 92,975,635

Statewide Totals	FY 2026	FY 2027	FY 2028	FY2029	FY 2030	5-Year-Total
	$ 330,216,869	$ 343,293,060	$ 343,293,060	$ 343,293,060	$ 343,293,060	$ 1,703,389,110

Statewide - Estimated Costs in 5 Year RMIP

Division	Budget Group	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	5-Year Total
1	Bridge Pres	$ 2,498,500	$ 2,498,500	$ 2,498,500	$ 2,498,500	$ 2,498,500	$ 12,492,500
	GMR	$ 47,550,552	$ 50,233,570	$ 50,233,570	$ 50,233,570	$ 50,233,570	$ 248,484,831
	Roadside	$ 7,276,539	$ 7,276,539	$ 7,276,539	$ 7,276,539	$ 7,276,539	$ 36,382,693
2	Bridge Pres	$ 2,118,250	$ 2,118,250	$ 2,118,250	$ 2,118,250	$ 2,118,250	$ 10,591,250
	GMR	$ 46,434,139	$ 48,920,703	$ 48,920,703	$ 48,920,703	$ 48,920,703	$ 242,116,952
	Roadside	$ 6,676,740	$ 6,676,740	$ 6,676,740	$ 6,676,740	$ 6,676,740	$ 33,383,700
3	Bridge Pres	$ 2,481,121	$ 2,481,121	$ 2,481,121	$ 2,481,121	$ 2,481,121	$ 12,405,607
	GMR	$ 52,050,545	$ 54,820,705	$ 54,820,705	$ 54,820,705	$ 54,820,705	$ 271,333,366
	Roadside	$ 7,393,287	$ 7,393,287	$ 7,393,287	$ 7,393,287	$ 7,393,287	$ 36,966,434
4	Bridge Pres	$ 2,364,000	$ 2,364,000	$ 2,364,000	$ 2,364,000	$ 2,364,000	$ 11,820,000
	GMR	$ 55,437,580	$ 58,446,816	$ 58,446,816	$ 58,446,816	$ 58,446,816	$ 289,224,844
	Roadside	$ 9,455,000	$ 9,455,000	$ 9,455,000	$ 9,455,000	$ 9,455,000	$ 47,275,000
5	Bridge Pres	$ 2,994,098	$ 2,994,098	$ 2,994,098	$ 2,994,098	$ 2,994,098	$ 14,970,491
	GMR	$ 67,839,298	$ 71,303,633	$ 71,303,633	$ 71,303,633	$ 71,303,633	$ 353,053,832
	Roadside	$ 8,906,470	$ 8,906,470	$ 8,906,470	$ 8,906,470	$ 8,906,470	$ 44,532,349
6	Bridge Pres	$ 1,989,385	$ 1,989,385	$ 1,989,385	$ 1,989,385	$ 1,989,385	$ 9,946,925
	GMR	$ 51,686,840	$ 54,550,809	$ 54,550,809	$ 54,550,809	$ 54,550,809	$ 269,890,075
	Roadside	$ 8,255,000	$ 8,255,000	$ 8,255,000	$ 8,255,000	$ 8,255,000	$ 41,275,000
7	Bridge Pres	$ 2,662,819	$ 2,662,819	$ 2,662,819	$ 2,662,819	$ 2,662,819	$ 13,314,094
	GMR	$ 55,686,413	$ 58,548,386	$ 58,548,386	$ 58,548,386	$ 58,548,386	$ 289,879,959
	Roadside	$ 7,510,825	$ 7,510,825	$ 7,510,825	$ 7,510,825	$ 7,510,825	$ 37,554,123
8	Bridge Pres	$ 2,046,000	$ 2,046,000	$ 2,046,000	$ 2,046,000	$ 2,046,000	$ 10,230,000
	GMR	$ 53,581,401	$ 56,589,181	$ 56,589,181	$ 56,589,181	$ 56,589,181	$ 279,938,127
	Roadside	$ 9,484,860	$ 9,484,860	$ 9,484,860	$ 9,484,860	$ 9,484,860	$ 47,424,299
9	Bridge Pres	$ 2,072,380	$ 2,072,380	$ 2,072,380	$ 2,072,380	$ 2,072,380	$ 10,361,900
	GMR	$ 45,979,902	$ 48,458,906	$ 48,458,906	$ 48,458,906	$ 48,458,906	$ 239,815,526
	Roadside	$ 7,569,600	$ 7,569,600	$ 7,569,600	$ 7,569,600	$ 7,569,600	$ 37,848,000

Statewide - Estimated Costs in 5 Year RMIP

Division	Budget Group	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	5-Year Total
10	Bridge Pres	$ 2,712,913	$ 2,712,913	$ 2,712,913	$ 2,712,913	$ 2,712,913	$ 13,564,564
	GMR	$ 53,909,823	$ 56,652,300	$ 56,652,300	$ 56,652,300	$ 56,652,300	$ 280,519,022
	Roadside	$ 8,076,024	$ 8,076,024	$ 8,076,024	$ 8,076,024	$ 8,076,024	$ 40,380,119
11	Bridge Pres	$ 2,202,850	$ 2,202,850	$ 2,202,850	$ 2,202,850	$ 2,202,850	$ 11,014,250
	GMR	$ 48,147,095	$ 50,632,401	$ 50,632,401	$ 50,632,401	$ 50,632,401	$ 250,676,699
	Roadside	$ 7,397,442	$ 7,397,442	$ 7,397,442	$ 7,397,442	$ 7,397,442	$ 36,987,210
12	Bridge Pres	$ 2,226,273	$ 2,226,793	$ 2,226,793	$ 2,226,793	$ 2,226,793	$ 11,133,443
	GMR	$ 52,546,074	$ 55,343,764	$ 55,343,764	$ 55,343,764	$ 55,343,764	$ 273,921,131
	Roadside	$ 8,500,210	$ 8,500,210	$ 8,500,210	$ 8,500,210	$ 8,500,210	$ 42,501,052
13	Bridge Pres	$ 2,915,603	$ 2,915,603	$ 2,915,603	$ 2,915,603	$ 2,915,603	$ 14,578,015
	GMR	$ 48,783,495	$ 51,176,370	$ 51,176,370	$ 51,176,370	$ 51,176,370	$ 253,488,974
	Roadside	$ 8,137,001	$ 8,137,001	$ 8,137,001	$ 8,137,001	$ 8,137,001	$ 40,685,005
14	Bridge Pres	$ 2,642,138	$ 2,642,138	$ 2,642,138	$ 2,642,138	$ 2,642,138	$ 13,210,688
	GMR	$ 44,683,336	$ 46,898,977	$ 46,898,977	$ 46,898,977	$ 46,898,977	$ 232,279,243
	Roadside	$ 8,776,150	$ 8,776,150	$ 8,776,150	$ 8,776,150	$ 8,776,150	$ 43,880,752
Statewide Totals	Bridge Pres	$ 33,926,329	$ 33,926,849	$ 33,926,849	$ 33,926,849	$ 33,926,849	$ 169,633,726
	GMR	$ 724,316,494	$ 762,576,522	$ 762,576,522	$ 762,576,522	$ 762,576,522	$ 3,774,622,582
	Roadside	$ 113,415,147	$ 113,415,147	$ 113,415,147	$ 113,415,147	$ 113,415,147	$ 567,075,735

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2026	1	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	20.00	LFT	$ 10,000.00
2026	1	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	20.00	LFT	$ 6,000.00
2026	1	Bridge Pres	3336	RMIP	Moveable Bridges (Maintenance)	90.00	HR	$ 9,000.00
2026	1	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	100.00	SFT	$ 4,000.00
2026	1	Bridge Pres	3352	RMIP	Maint Slope Protection	200.00	SFT	$ 30,000.00
2026	1	Bridge Pres	3366	RMIP	Drift and Debris Removal	40.00	HR	$ 6,000.00
2026	1	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	1800.00	LFT	$ 810,000.00
2026	1	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	625000.00	SFT	$ 125,000.00
2027	1	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	20.00	LFT	$ 10,000.00
2027	1	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	20.00	LFT	$ 6,000.00
2027	1	Bridge Pres	3336	RMIP	Moveable Bridges (Maintenance)	90.00	HR	$ 9,000.00
2027	1	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	100.00	SFT	$ 4,000.00
2027	1	Bridge Pres	3352	RMIP	Maint Slope Protection	200.00	SFT	$ 30,000.00
2027	1	Bridge Pres	3366	RMIP	Drift and Debris Removal	40.00	HR	$ 6,000.00
2027	1	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	1800.00	LFT	$ 810,000.00
2027	1	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	625000.00	SFT	$ 125,000.00
2028	1	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	20.00	LFT	$ 10,000.00
2028	1	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	20.00	LFT	$ 6,000.00
2028	1	Bridge Pres	3336	RMIP	Moveable Bridges (Maintenance)	90.00	HR	$ 9,000.00
2028	1	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	100.00	SFT	$ 4,000.00
2028	1	Bridge Pres	3352	RMIP	Maint Slope Protection	200.00	SFT	$ 30,000.00
2028	1	Bridge Pres	3366	RMIP	Drift and Debris Removal	40.00	HR	$ 6,000.00
2028	1	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	1800.00	LFT	$ 810,000.00
2028	1	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	625000.00	SFT	$ 125,000.00
2029	1	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	20.00	LFT	$ 10,000.00
2029	1	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	20.00	LFT	$ 6,000.00
2029	1	Bridge Pres	3336	RMIP	Moveable Bridges (Maintenance)	90.00	HR	$ 9,000.00
2029	1	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	100.00	SFT	$ 4,000.00
2029	1	Bridge Pres	3352	RMIP	Maint Slope Protection	200.00	SFT	$ 30,000.00
2029	1	Bridge Pres	3366	RMIP	Drift and Debris Removal	40.00	HR	$ 6,000.00
2029	1	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	1800.00	LFT	$ 810,000.00
2029	1	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	625000.00	SFT	$ 125,000.00
2030	1	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	20.00	LFT	$ 10,000.00
2030	1	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	20.00	LFT	$ 6,000.00
2030	1	Bridge Pres	3336	RMIP	Moveable Bridges (Maintenance)	90.00	HR	$ 9,000.00
2030	1	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	100.00	SFT	$ 4,000.00
2030	1	Bridge Pres	3352	RMIP	Maint Slope Protection	200.00	SFT	$ 30,000.00
2030	1	Bridge Pres	3366	RMIP	Drift and Debris Removal	40.00	HR	$ 6,000.00
2030	1	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	1800.00	LFT	$ 810,000.00
2030	1	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	625000.00	SFT	$ 125,000.00
2026	1	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 38,500.00
2026	1	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 10,000.00
2026	1	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 100,000.00
2026	1	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 10,000.00
2026	1	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 20,000.00
2026	1	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 25,000.00
2026	1	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 10,000.00
2026	1	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 5,000.00
2026	1	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 50,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2026	1	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 5,000.00
2026	1	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 110,000.00
2026	1	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 1,040,000.00
2026	1	Bridge Pres	3334C	Budgeted	Bridge Bearings	-	EA	$ 5,000.00
2026	1	Bridge Pres	3353C	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 70,000.00
2027	1	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 38,500.00
2027	1	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 10,000.00
2027	1	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 100,000.00
2027	1	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 10,000.00
2027	1	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 20,000.00
2027	1	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 25,000.00
2027	1	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 10,000.00
2027	1	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 5,000.00
2027	1	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 50,000.00
2027	1	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 5,000.00
2027	1	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 110,000.00
2027	1	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 1,040,000.00
2027	1	Bridge Pres	3334C	Budgeted	Bridge Bearings	-	EA	$ 5,000.00
2027	1	Bridge Pres	3353C	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 70,000.00
2028	1	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 38,500.00
2028	1	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 10,000.00
2028	1	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 100,000.00
2028	1	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 10,000.00
2028	1	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 20,000.00
2028	1	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 25,000.00
2028	1	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 10,000.00
2028	1	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 5,000.00
2028	1	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 50,000.00
2028	1	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 5,000.00
2028	1	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 110,000.00
2028	1	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 1,040,000.00
2028	1	Bridge Pres	3334C	Budgeted	Bridge Bearings	-	EA	$ 5,000.00
2028	1	Bridge Pres	3353C	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 70,000.00
2029	1	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 38,500.00
2029	1	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 10,000.00
2029	1	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 100,000.00
2029	1	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 10,000.00
2029	1	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 20,000.00
2029	1	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 25,000.00
2029	1	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 10,000.00
2029	1	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 5,000.00
2029	1	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 50,000.00
2029	1	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 5,000.00
2029	1	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 110,000.00
2029	1	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 1,040,000.00
2029	1	Bridge Pres	3334C	Budgeted	Bridge Bearings	-	EA	$ 5,000.00
2029	1	Bridge Pres	3353C	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 70,000.00
2030	1	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 38,500.00
2030	1	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 10,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2030	1	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 100,000.00
2030	1	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 10,000.00
2030	1	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 20,000.00
2030	1	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 25,000.00
2030	1	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 10,000.00
2030	1	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 5,000.00
2030	1	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 50,000.00
2030	1	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 5,000.00
2030	1	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 110,000.00
2030	1	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 1,040,000.00
2030	1	Bridge Pres	3334C	Budgeted	Bridge Bearings	-	EA	$ 5,000.00
2030	1	Bridge Pres	3353C	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 70,000.00
2026	2	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	98.00	LFT	$ 73,500.00
2026	2	Bridge Pres	3336	RMIP	Moveable Bridges (Maintenance)	925.00	HR	$ 78,625.00
2026	2	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	625.00	SFT	$ 175,000.00
2026	2	Bridge Pres	3352	RMIP	Maint Slope Protection	3075.00	SFT	$ 123,000.00
2026	2	Bridge Pres	3366	RMIP	Drift and Debris Removal	1600.00	HR	$ 96,000.00
2026	2	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	2380250.00	SFT	$ 1,190,125.00
2027	2	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	98.00	LFT	$ 73,500.00
2027	2	Bridge Pres	3336	RMIP	Moveable Bridges (Maintenance)	925.00	HR	$ 78,625.00
2027	2	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	625.00	SFT	$ 175,000.00
2027	2	Bridge Pres	3352	RMIP	Maint Slope Protection	3075.00	SFT	$ 123,000.00
2027	2	Bridge Pres	3366	RMIP	Drift and Debris Removal	1600.00	HR	$ 96,000.00
2027	2	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	2380250.00	SFT	$ 1,190,125.00
2028	2	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	98.00	LFT	$ 73,500.00
2028	2	Bridge Pres	3336	RMIP	Moveable Bridges (Maintenance)	925.00	HR	$ 78,625.00
2028	2	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	625.00	SFT	$ 175,000.00
2028	2	Bridge Pres	3352	RMIP	Maint Slope Protection	3075.00	SFT	$ 123,000.00
2028	2	Bridge Pres	3366	RMIP	Drift and Debris Removal	1600.00	HR	$ 96,000.00
2028	2	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	2380250.00	SFT	$ 1,190,125.00
2029	2	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	98.00	LFT	$ 73,500.00
2029	2	Bridge Pres	3336	RMIP	Moveable Bridges (Maintenance)	925.00	HR	$ 78,625.00
2029	2	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	625.00	SFT	$ 175,000.00
2029	2	Bridge Pres	3352	RMIP	Maint Slope Protection	3075.00	SFT	$ 123,000.00
2029	2	Bridge Pres	3366	RMIP	Drift and Debris Removal	1600.00	HR	$ 96,000.00
2029	2	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	2380250.00	SFT	$ 1,190,125.00
2030	2	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	98.00	LFT	$ 73,500.00
2030	2	Bridge Pres	3336	RMIP	Moveable Bridges (Maintenance)	925.00	HR	$ 78,625.00
2030	2	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	625.00	SFT	$ 175,000.00
2030	2	Bridge Pres	3352	RMIP	Maint Slope Protection	3075.00	SFT	$ 123,000.00
2030	2	Bridge Pres	3366	RMIP	Drift and Debris Removal	1600.00	HR	$ 96,000.00
2030	2	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	2380250.00	SFT	$ 1,190,125.00
2026	2	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 25,000.00
2026	2	Bridge Pres	2714	Budgeted	Assessments and Inspections	-	HR	$ 25,000.00
2026	2	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 40,000.00
2026	2	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 1,000.00
2026	2	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 150,000.00
2026	2	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 25,000.00
2026	2	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 40,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2026	2	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 75,000.00
2026	2	Bridge Pres	6040	Budgeted	CONSTR/MAINT OF FACILITY	-	HR	$ 1,000.00
2027	2	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 25,000.00
2027	2	Bridge Pres	2714	Budgeted	Assessments and Inspections	-	HR	$ 25,000.00
2027	2	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 40,000.00
2027	2	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 1,000.00
2027	2	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 150,000.00
2027	2	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 25,000.00
2027	2	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 40,000.00
2027	2	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 75,000.00
2027	2	Bridge Pres	6040	Budgeted	CONSTR/MAINT OF FACILITY	-	HR	$ 1,000.00
2028	2	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 25,000.00
2028	2	Bridge Pres	2714	Budgeted	Assessments and Inspections	-	HR	$ 25,000.00
2028	2	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 40,000.00
2028	2	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 1,000.00
2028	2	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 150,000.00
2028	2	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 25,000.00
2028	2	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 40,000.00
2028	2	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 75,000.00
2028	2	Bridge Pres	6040	Budgeted	CONSTR/MAINT OF FACILITY	-	HR	$ 1,000.00
2029	2	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 25,000.00
2029	2	Bridge Pres	2714	Budgeted	Assessments and Inspections	-	HR	$ 25,000.00
2029	2	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 40,000.00
2029	2	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 1,000.00
2029	2	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 150,000.00
2029	2	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 25,000.00
2029	2	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 40,000.00
2029	2	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 75,000.00
2029	2	Bridge Pres	6040	Budgeted	CONSTR/MAINT OF FACILITY	-	HR	$ 1,000.00
2030	2	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 25,000.00
2030	2	Bridge Pres	2714	Budgeted	Assessments and Inspections	-	HR	$ 25,000.00
2030	2	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 40,000.00
2030	2	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 1,000.00
2030	2	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 150,000.00
2030	2	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 25,000.00
2030	2	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 40,000.00
2030	2	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 75,000.00
2030	2	Bridge Pres	6040	Budgeted	CONSTR/MAINT OF FACILITY	-	HR	$ 1,000.00
2026	3	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	420000.00	SFT	$ 630,000.00
2027	3	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	420000.00	SFT	$ 630,000.00
2028	3	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	420000.00	SFT	$ 630,000.00
2029	3	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	420000.00	SFT	$ 630,000.00
2030	3	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	420000.00	SFT	$ 630,000.00
2026	3	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 250,000.00
2026	3	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 701,121.34
2026	3	Bridge Pres	1P08	Budgeted	Proj Scoping Prep & Mtg	-		$ 300,000.00
2026	3	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 600,000.00
2027	3	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 250,000.00
2027	3	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 701,121.34

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2027	3	Bridge Pres	1P08	Budgeted	Proj Scoping Prep & Mtg	-		$ 300,000.00
2027	3	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 600,000.00
2028	3	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 250,000.00
2028	3	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 701,121.34
2028	3	Bridge Pres	1P08	Budgeted	Proj Scoping Prep & Mtg	-		$ 300,000.00
2028	3	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 600,000.00
2029	3	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 250,000.00
2029	3	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 701,121.34
2029	3	Bridge Pres	1P08	Budgeted	Proj Scoping Prep & Mtg	-		$ 300,000.00
2029	3	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 600,000.00
2030	3	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 250,000.00
2030	3	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 701,121.34
2030	3	Bridge Pres	1P08	Budgeted	Proj Scoping Prep & Mtg	-		$ 300,000.00
2030	3	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 600,000.00
2026	4	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	1500.00	LFT	$ 600,000.00
2027	4	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	1500.00	LFT	$ 600,000.00
2028	4	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	1500.00	LFT	$ 600,000.00
2029	4	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	1500.00	LFT	$ 600,000.00
2030	4	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	1500.00	LFT	$ 600,000.00
2026	4	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 500,000.00
2026	4	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 45,000.00
2026	4	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 54,000.00
2026	4	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 100,000.00
2026	4	Bridge Pres	3332	Budgeted	Maintenance Drainage System - Bridge	-	LFT	$ 10,000.00
2026	4	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 80,000.00
2026	4	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 50,000.00
2026	4	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 125,000.00
2026	4	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 100,000.00
2026	4	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 500,000.00
2026	4	Bridge Pres	2PB1	Budgeted	- Eastern Mussel PBO	-		$ 200,000.00
2027	4	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 500,000.00
2027	4	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 45,000.00
2027	4	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 54,000.00
2027	4	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 100,000.00
2027	4	Bridge Pres	3332	Budgeted	Maintenance Drainage System - Bridge	-	LFT	$ 10,000.00
2027	4	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 80,000.00
2027	4	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 50,000.00
2027	4	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 125,000.00
2027	4	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 100,000.00
2027	4	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 500,000.00
2027	4	Bridge Pres	2PB1	Budgeted	- Eastern Mussel PBO	-		$ 200,000.00
2028	4	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 500,000.00
2028	4	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 45,000.00
2028	4	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 54,000.00
2028	4	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 100,000.00
2028	4	Bridge Pres	3332	Budgeted	Maintenance Drainage System - Bridge	-	LFT	$ 10,000.00
2028	4	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 80,000.00
2028	4	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 50,000.00
2028	4	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 125,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2028	4	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 100,000.00
2028	4	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 500,000.00
2028	4	Bridge Pres	2PB1	Budgeted	- Eastern Mussel PBO	-		$ 200,000.00
2029	4	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 500,000.00
2029	4	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 45,000.00
2029	4	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 54,000.00
2029	4	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 100,000.00
2029	4	Bridge Pres	3332	Budgeted	Maintenance Drainage System - Bridge	-	LFT	$ 10,000.00
2029	4	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 80,000.00
2029	4	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 50,000.00
2029	4	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 125,000.00
2029	4	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 100,000.00
2029	4	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 500,000.00
2029	4	Bridge Pres	2PB1	Budgeted	- Eastern Mussel PBO	-		$ 200,000.00
2030	4	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 500,000.00
2030	4	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 45,000.00
2030	4	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 54,000.00
2030	4	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 100,000.00
2030	4	Bridge Pres	3332	Budgeted	Maintenance Drainage System - Bridge	-	LFT	$ 10,000.00
2030	4	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 80,000.00
2030	4	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 50,000.00
2030	4	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 125,000.00
2030	4	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 100,000.00
2030	4	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 500,000.00
2030	4	Bridge Pres	2PB1	Budgeted	- Eastern Mussel PBO	-		$ 200,000.00
2026	5	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	808.00	LFT	$ 145,440.00
2026	5	Bridge Pres	3352	RMIP	Maint Slope Protection	2000.50	SFT	$ 400,100.00
2026	5	Bridge Pres	3366	RMIP	Drift and Debris Removal	2801.90	HR	$ 173,717.80
2026	5	Bridge Pres	3314C	RMIP	Maintain / Repair Steel Superstructure Components	300.00	LFT	$ 360,000.00
2026	5	Bridge Pres	3342C	RMIP	Clean and Paint Structural Steel	2164.00	SFT	$ 162,300.00
2026	5	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	20000.12	SFT	$ 200,001.20
2027	5	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	808.00	LFT	$ 145,440.00
2027	5	Bridge Pres	3352	RMIP	Maint Slope Protection	2000.50	SFT	$ 400,100.00
2027	5	Bridge Pres	3366	RMIP	Drift and Debris Removal	2801.90	HR	$ 173,717.80
2027	5	Bridge Pres	3314C	RMIP	Maintain / Repair Steel Superstructure Components	300.00	LFT	$ 360,000.00
2027	5	Bridge Pres	3342C	RMIP	Clean and Paint Structural Steel	2164.00	SFT	$ 162,300.00
2027	5	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	20000.12	SFT	$ 200,001.20
2028	5	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	808.00	LFT	$ 145,440.00
2028	5	Bridge Pres	3352	RMIP	Maint Slope Protection	2000.50	SFT	$ 400,100.00
2028	5	Bridge Pres	3366	RMIP	Drift and Debris Removal	2801.90	HR	$ 173,717.80
2028	5	Bridge Pres	3314C	RMIP	Maintain / Repair Steel Superstructure Components	300.00	LFT	$ 360,000.00
2028	5	Bridge Pres	3342C	RMIP	Clean and Paint Structural Steel	2164.00	SFT	$ 162,300.00
2028	5	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	20000.12	SFT	$ 200,001.20
2029	5	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	808.00	LFT	$ 145,440.00
2029	5	Bridge Pres	3352	RMIP	Maint Slope Protection	2000.50	SFT	$ 400,100.00
2029	5	Bridge Pres	3366	RMIP	Drift and Debris Removal	2801.90	HR	$ 173,717.80
2029	5	Bridge Pres	3314C	RMIP	Maintain / Repair Steel Superstructure Components	300.00	LFT	$ 360,000.00
2029	5	Bridge Pres	3342C	RMIP	Clean and Paint Structural Steel	2164.00	SFT	$ 162,300.00
2029	5	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	20000.12	SFT	$ 200,001.20

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2030	5	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	808.00	LFT	$ 145,440.00
2030	5	Bridge Pres	3352	RMIP	Maint Slope Protection	2000.50	SFT	$ 400,100.00
2030	5	Bridge Pres	3366	RMIP	Drift and Debris Removal	2801.90	HR	$ 173,717.80
2030	5	Bridge Pres	3314C	RMIP	Maintain / Repair Steel Superstructure Components	300.00	LFT	$ 360,000.00
2030	5	Bridge Pres	3342C	RMIP	Clean and Paint Structural Steel	2164.00	SFT	$ 162,300.00
2030	5	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	20000.12	SFT	$ 200,001.20
2026	5	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 35,000.00
2026	5	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 5,000.00
2026	5	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 55,000.00
2026	5	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 37,539.17
2026	5	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 12,000.00
2026	5	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 15,000.00
2026	5	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 138,000.00
2026	5	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 20,000.00
2026	5	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 175,000.00
2026	5	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 920,000.00
2026	5	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 140,000.00
2027	5	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 35,000.00
2027	5	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 5,000.00
2027	5	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 55,000.00
2027	5	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 37,539.17
2027	5	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 12,000.00
2027	5	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 15,000.00
2027	5	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 138,000.00
2027	5	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 20,000.00
2027	5	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 175,000.00
2027	5	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 920,000.00
2027	5	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 140,000.00
2028	5	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 35,000.00
2028	5	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 5,000.00
2028	5	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 55,000.00
2028	5	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 37,539.17
2028	5	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 12,000.00
2028	5	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 15,000.00
2028	5	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 138,000.00
2028	5	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 20,000.00
2028	5	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 175,000.00
2028	5	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 920,000.00
2028	5	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 140,000.00
2029	5	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 35,000.00
2029	5	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 5,000.00
2029	5	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 55,000.00
2029	5	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 37,539.17
2029	5	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 12,000.00
2029	5	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 15,000.00
2029	5	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 138,000.00
2029	5	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 20,000.00
2029	5	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 175,000.00
2029	5	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 920,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2029	5	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 140,000.00
2030	5	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 35,000.00
2030	5	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 5,000.00
2030	5	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 55,000.00
2030	5	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 37,539.17
2030	5	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 12,000.00
2030	5	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 15,000.00
2030	5	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 138,000.00
2030	5	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 20,000.00
2030	5	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 175,000.00
2030	5	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 920,000.00
2030	5	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 140,000.00
2026	6	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	400.00	LFT	$ 140,000.00
2026	6	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	10.00	LFT	$ 120.00
2026	6	Bridge Pres	3352	RMIP	Maint Slope Protection	1800.00	SFT	$ 261,000.00
2026	6	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	2170.00	LFT	$ 759,500.00
2026	6	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	398700.00	SFT	$ 378,765.00
2027	6	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	400.00	LFT	$ 140,000.00
2027	6	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	10.00	LFT	$ 120.00
2027	6	Bridge Pres	3352	RMIP	Maint Slope Protection	1800.00	SFT	$ 261,000.00
2027	6	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	2170.00	LFT	$ 759,500.00
2027	6	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	398700.00	SFT	$ 378,765.00
2028	6	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	400.00	LFT	$ 140,000.00
2028	6	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	10.00	LFT	$ 120.00
2028	6	Bridge Pres	3352	RMIP	Maint Slope Protection	1800.00	SFT	$ 261,000.00
2028	6	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	2170.00	LFT	$ 759,500.00
2028	6	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	398700.00	SFT	$ 378,765.00
2029	6	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	400.00	LFT	$ 140,000.00
2029	6	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	10.00	LFT	$ 120.00
2029	6	Bridge Pres	3352	RMIP	Maint Slope Protection	1800.00	SFT	$ 261,000.00
2029	6	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	2170.00	LFT	$ 759,500.00
2029	6	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	398700.00	SFT	$ 378,765.00
2030	6	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	400.00	LFT	$ 140,000.00
2030	6	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	10.00	LFT	$ 120.00
2030	6	Bridge Pres	3352	RMIP	Maint Slope Protection	1800.00	SFT	$ 261,000.00
2030	6	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	2170.00	LFT	$ 759,500.00
2030	6	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	398700.00	SFT	$ 378,765.00
2026	6	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 210,000.00
2026	6	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 40,000.00
2026	6	Bridge Pres	3107	Budgeted	Graffiti Removal	-	SFT	$ 10,000.00
2026	6	Bridge Pres	3244	Budgeted	Scheduled Temporary Traffic Control	-	HR	$ 10,000.00
2026	6	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 30,000.00
2026	6	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 100,000.00
2026	6	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 20,000.00
2026	6	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 30,000.00
2027	6	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 210,000.00
2027	6	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 40,000.00
2027	6	Bridge Pres	3107	Budgeted	Graffiti Removal	-	SFT	$ 10,000.00
2027	6	Bridge Pres	3244	Budgeted	Scheduled Temporary Traffic Control	-	HR	$ 10,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2027	6	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 30,000.00
2027	6	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 100,000.00
2027	6	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 20,000.00
2027	6	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 30,000.00
2028	6	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 210,000.00
2028	6	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 40,000.00
2028	6	Bridge Pres	3107	Budgeted	Graffiti Removal	-	SFT	$ 10,000.00
2028	6	Bridge Pres	3244	Budgeted	Scheduled Temporary Traffic Control	-	HR	$ 10,000.00
2028	6	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 30,000.00
2028	6	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 100,000.00
2028	6	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 20,000.00
2028	6	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 30,000.00
2029	6	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 210,000.00
2029	6	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 40,000.00
2029	6	Bridge Pres	3107	Budgeted	Graffiti Removal	-	SFT	$ 10,000.00
2029	6	Bridge Pres	3244	Budgeted	Scheduled Temporary Traffic Control	-	HR	$ 10,000.00
2029	6	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 30,000.00
2029	6	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 100,000.00
2029	6	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 20,000.00
2029	6	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 30,000.00
2030	6	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 210,000.00
2030	6	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 40,000.00
2030	6	Bridge Pres	3107	Budgeted	Graffiti Removal	-	SFT	$ 10,000.00
2030	6	Bridge Pres	3244	Budgeted	Scheduled Temporary Traffic Control	-	HR	$ 10,000.00
2030	6	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 30,000.00
2030	6	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 100,000.00
2030	6	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 20,000.00
2030	6	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 30,000.00
2026	7	Bridge Pres	3310	RMIP	Maintenance / Repair Bridge Expansion Joints	100.00	LFT	$ 15,000.00
2026	7	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	140.06	LFT	$ 180,005.11
2026	7	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	51.81	LFT	$ 6,000.00
2026	7	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	4711.06	SFT	$ 89,981.16
2026	7	Bridge Pres	3352	RMIP	Maint Slope Protection	10526.32	SFT	$ 240,000.00
2026	7	Bridge Pres	3366	RMIP	Drift and Debris Removal	1200.00	HR	$ 72,000.00
2026	7	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	25000.00	SFT	$ 60,000.00
2026	7	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	2335.40	LFT	$ 612,715.73
2026	7	Bridge Pres	3310C	RMIP	Maintenance / Repair Bridge Expansion Joints	300.00	LFT	$ 116,280.00
2027	7	Bridge Pres	3310	RMIP	Maintenance / Repair Bridge Expansion Joints	100.00	LFT	$ 15,000.00
2027	7	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	140.06	LFT	$ 180,005.11
2027	7	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	51.81	LFT	$ 6,000.00
2027	7	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	4711.06	SFT	$ 89,981.16
2027	7	Bridge Pres	3352	RMIP	Maint Slope Protection	10526.32	SFT	$ 240,000.00
2027	7	Bridge Pres	3366	RMIP	Drift and Debris Removal	1200.00	HR	$ 72,000.00
2027	7	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	25000.00	SFT	$ 60,000.00
2027	7	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	2335.40	LFT	$ 612,715.73
2027	7	Bridge Pres	3310C	RMIP	Maintenance / Repair Bridge Expansion Joints	300.00	LFT	$ 116,280.00
2028	7	Bridge Pres	3310	RMIP	Maintenance / Repair Bridge Expansion Joints	100.00	LFT	$ 15,000.00
2028	7	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	140.06	LFT	$ 180,005.11
2028	7	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	51.81	LFT	$ 6,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2028	7	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	4711.06	SFT	$ 89,981.16
2028	7	Bridge Pres	3352	RMIP	Maint Slope Protection	10526.32	SFT	$ 240,000.00
2028	7	Bridge Pres	3366	RMIP	Drift and Debris Removal	1200.00	HR	$ 72,000.00
2028	7	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	25000.00	SFT	$ 60,000.00
2028	7	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	2335.40	LFT	$ 612,715.73
2028	7	Bridge Pres	3310C	RMIP	Maintenance / Repair Bridge Expansion Joints	300.00	LFT	$ 116,280.00
2029	7	Bridge Pres	3310	RMIP	Maintenance / Repair Bridge Expansion Joints	100.00	LFT	$ 15,000.00
2029	7	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	140.06	LFT	$ 180,005.11
2029	7	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	51.81	LFT	$ 6,000.00
2029	7	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	4711.06	SFT	$ 89,981.16
2029	7	Bridge Pres	3352	RMIP	Maint Slope Protection	10526.32	SFT	$ 240,000.00
2029	7	Bridge Pres	3366	RMIP	Drift and Debris Removal	1200.00	HR	$ 72,000.00
2029	7	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	25000.00	SFT	$ 60,000.00
2029	7	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	2335.40	LFT	$ 612,715.73
2029	7	Bridge Pres	3310C	RMIP	Maintenance / Repair Bridge Expansion Joints	300.00	LFT	$ 116,280.00
2030	7	Bridge Pres	3310	RMIP	Maintenance / Repair Bridge Expansion Joints	100.00	LFT	$ 15,000.00
2030	7	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	140.06	LFT	$ 180,005.11
2030	7	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	51.81	LFT	$ 6,000.00
2030	7	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	4711.06	SFT	$ 89,981.16
2030	7	Bridge Pres	3352	RMIP	Maint Slope Protection	10526.32	SFT	$ 240,000.00
2030	7	Bridge Pres	3366	RMIP	Drift and Debris Removal	1200.00	HR	$ 72,000.00
2030	7	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	25000.00	SFT	$ 60,000.00
2030	7	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	2335.40	LFT	$ 612,715.73
2030	7	Bridge Pres	3310C	RMIP	Maintenance / Repair Bridge Expansion Joints	300.00	LFT	$ 116,280.00
2026	7	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 598,836.75
2026	7	Bridge Pres	7640C	Budgeted	Payment to Contractor	-	DOL	$ 672,000.00
2027	7	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 598,836.75
2027	7	Bridge Pres	7640C	Budgeted	Payment to Contractor	-	DOL	$ 672,000.00
2028	7	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 598,836.75
2028	7	Bridge Pres	7640C	Budgeted	Payment to Contractor	-	DOL	$ 672,000.00
2029	7	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 598,836.75
2029	7	Bridge Pres	7640C	Budgeted	Payment to Contractor	-	DOL	$ 672,000.00
2030	7	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 598,836.75
2030	7	Bridge Pres	7640C	Budgeted	Payment to Contractor	-	DOL	$ 672,000.00
2026	8	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	160.00	LFT	$ 56,000.00
2026	8	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	40.00	LFT	$ 6,400.00
2026	8	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	320.00	SFT	$ 28,800.00
2026	8	Bridge Pres	3352	RMIP	Maint Slope Protection	1600.00	SFT	$ 126,400.00
2026	8	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	32000.00	SFT	$ 192,000.00
2026	8	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	240.00	LFT	$ 96,000.00
2026	8	Bridge Pres	3310C	RMIP	Maintenance / Repair Bridge Expansion Joints	897.00	LFT	$ 179,400.00
2027	8	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	160.00	LFT	$ 56,000.00
2027	8	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	40.00	LFT	$ 6,400.00
2027	8	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	320.00	SFT	$ 28,800.00
2027	8	Bridge Pres	3352	RMIP	Maint Slope Protection	1600.00	SFT	$ 126,400.00
2027	8	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	32000.00	SFT	$ 192,000.00
2027	8	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	240.00	LFT	$ 96,000.00
2027	8	Bridge Pres	3310C	RMIP	Maintenance / Repair Bridge Expansion Joints	897.00	LFT	$ 179,400.00
2028	8	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	160.00	LFT	$ 56,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2028	8	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	40.00	LFT	$ 6,400.00
2028	8	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	320.00	SFT	$ 28,800.00
2028	8	Bridge Pres	3352	RMIP	Maint Slope Protection	1600.00	SFT	$ 126,400.00
2028	8	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	32000.00	SFT	$ 192,000.00
2028	8	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	240.00	LFT	$ 96,000.00
2028	8	Bridge Pres	3310C	RMIP	Maintenance / Repair Bridge Expansion Joints	897.00	LFT	$ 179,400.00
2029	8	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	160.00	LFT	$ 56,000.00
2029	8	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	40.00	LFT	$ 6,400.00
2029	8	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	320.00	SFT	$ 28,800.00
2029	8	Bridge Pres	3352	RMIP	Maint Slope Protection	1600.00	SFT	$ 126,400.00
2029	8	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	32000.00	SFT	$ 192,000.00
2029	8	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	240.00	LFT	$ 96,000.00
2029	8	Bridge Pres	3310C	RMIP	Maintenance / Repair Bridge Expansion Joints	897.00	LFT	$ 179,400.00
2030	8	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	160.00	LFT	$ 56,000.00
2030	8	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	40.00	LFT	$ 6,400.00
2030	8	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	320.00	SFT	$ 28,800.00
2030	8	Bridge Pres	3352	RMIP	Maint Slope Protection	1600.00	SFT	$ 126,400.00
2030	8	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	32000.00	SFT	$ 192,000.00
2030	8	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	240.00	LFT	$ 96,000.00
2030	8	Bridge Pres	3310C	RMIP	Maintenance / Repair Bridge Expansion Joints	897.00	LFT	$ 179,400.00
2026	8	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 10,000.00
2026	8	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 60,000.00
2026	8	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 40,000.00
2026	8	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 100,000.00
2026	8	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 25,000.00
2026	8	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 20,000.00
2026	8	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 100,000.00
2026	8	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 30,000.00
2026	8	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 40,000.00
2026	8	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 300,000.00
2026	8	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 50,000.00
2026	8	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 80,000.00
2026	8	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 260,000.00
2026	8	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 40,000.00
2026	8	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 190,000.00
2026	8	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 16,000.00
2027	8	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 10,000.00
2027	8	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 60,000.00
2027	8	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 40,000.00
2027	8	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 100,000.00
2027	8	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 25,000.00
2027	8	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 20,000.00
2027	8	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 100,000.00
2027	8	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 30,000.00
2027	8	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 40,000.00
2027	8	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 300,000.00
2027	8	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 50,000.00
2027	8	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 80,000.00
2027	8	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 260,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2027	8	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 40,000.00
2027	8	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 190,000.00
2027	8	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 16,000.00
2028	8	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 10,000.00
2028	8	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 60,000.00
2028	8	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 40,000.00
2028	8	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 100,000.00
2028	8	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 25,000.00
2028	8	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 20,000.00
2028	8	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 100,000.00
2028	8	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 30,000.00
2028	8	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 40,000.00
2028	8	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 300,000.00
2028	8	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 50,000.00
2028	8	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 80,000.00
2028	8	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 260,000.00
2028	8	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 40,000.00
2028	8	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 190,000.00
2028	8	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 16,000.00
2029	8	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 10,000.00
2029	8	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 60,000.00
2029	8	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 40,000.00
2029	8	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 100,000.00
2029	8	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 25,000.00
2029	8	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 20,000.00
2029	8	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 100,000.00
2029	8	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 30,000.00
2029	8	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 40,000.00
2029	8	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 300,000.00
2029	8	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 50,000.00
2029	8	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 80,000.00
2029	8	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 260,000.00
2029	8	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 40,000.00
2029	8	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 190,000.00
2029	8	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 16,000.00
2030	8	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 10,000.00
2030	8	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 60,000.00
2030	8	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 40,000.00
2030	8	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 100,000.00
2030	8	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 25,000.00
2030	8	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 20,000.00
2030	8	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 100,000.00
2030	8	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 30,000.00
2030	8	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 40,000.00
2030	8	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 300,000.00
2030	8	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 50,000.00
2030	8	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 80,000.00
2030	8	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 260,000.00
2030	8	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 40,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2030	8	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 190,000.00
2030	8	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 16,000.00
2026	9	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	474.75	LFT	$ 308,590.02
2026	9	Bridge Pres	3326	RMIP	Maintain Concrete Deck	3219.75	SFT	$ 128,790.00
2026	9	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	2600.00	SFT	$ 195,000.00
2026	9	Bridge Pres	3352	RMIP	Maint Slope Protection	1822.22	SFT	$ 82,000.00
2026	9	Bridge Pres	3366	RMIP	Drift and Debris Removal	1907.69	HR	$ 124,000.00
2026	9	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	38000.00	SFT	$ 114,000.00
2027	9	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	474.75	LFT	$ 308,590.02
2027	9	Bridge Pres	3326	RMIP	Maintain Concrete Deck	3219.75	SFT	$ 128,790.00
2027	9	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	2600.00	SFT	$ 195,000.00
2027	9	Bridge Pres	3352	RMIP	Maint Slope Protection	1822.22	SFT	$ 82,000.00
2027	9	Bridge Pres	3366	RMIP	Drift and Debris Removal	1907.69	HR	$ 124,000.00
2027	9	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	38000.00	SFT	$ 114,000.00
2028	9	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	474.75	LFT	$ 308,590.02
2028	9	Bridge Pres	3326	RMIP	Maintain Concrete Deck	3219.75	SFT	$ 128,790.00
2028	9	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	2600.00	SFT	$ 195,000.00
2028	9	Bridge Pres	3352	RMIP	Maint Slope Protection	1822.22	SFT	$ 82,000.00
2028	9	Bridge Pres	3366	RMIP	Drift and Debris Removal	1907.69	HR	$ 124,000.00
2028	9	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	38000.00	SFT	$ 114,000.00
2029	9	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	474.75	LFT	$ 308,590.02
2029	9	Bridge Pres	3326	RMIP	Maintain Concrete Deck	3219.75	SFT	$ 128,790.00
2029	9	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	2600.00	SFT	$ 195,000.00
2029	9	Bridge Pres	3352	RMIP	Maint Slope Protection	1822.22	SFT	$ 82,000.00
2029	9	Bridge Pres	3366	RMIP	Drift and Debris Removal	1907.69	HR	$ 124,000.00
2029	9	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	38000.00	SFT	$ 114,000.00
2030	9	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	474.75	LFT	$ 308,590.02
2030	9	Bridge Pres	3326	RMIP	Maintain Concrete Deck	3219.75	SFT	$ 128,790.00
2030	9	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	2600.00	SFT	$ 195,000.00
2030	9	Bridge Pres	3352	RMIP	Maint Slope Protection	1822.22	SFT	$ 82,000.00
2030	9	Bridge Pres	3366	RMIP	Drift and Debris Removal	1907.69	HR	$ 124,000.00
2030	9	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	38000.00	SFT	$ 114,000.00
2026	9	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 30,000.00
2026	9	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 125,000.00
2026	9	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 610,000.00
2026	9	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 130,000.00
2026	9	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 70,000.00
2026	9	Bridge Pres	9900	Budgeted	Administrative Functions	-	HR	$ 155,000.00
2027	9	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 30,000.00
2027	9	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 125,000.00
2027	9	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 610,000.00
2027	9	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 130,000.00
2027	9	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 70,000.00
2027	9	Bridge Pres	9900	Budgeted	Administrative Functions	-	HR	$ 155,000.00
2028	9	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 30,000.00
2028	9	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 125,000.00
2028	9	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 610,000.00
2028	9	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 130,000.00
2028	9	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 70,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2028	9	Bridge Pres	9900	Budgeted	Administrative Functions	-	HR	$ 155,000.00
2029	9	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 30,000.00
2029	9	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 125,000.00
2029	9	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 610,000.00
2029	9	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 130,000.00
2029	9	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 70,000.00
2029	9	Bridge Pres	9900	Budgeted	Administrative Functions	-	HR	$ 155,000.00
2030	9	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 30,000.00
2030	9	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 125,000.00
2030	9	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 610,000.00
2030	9	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 130,000.00
2030	9	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 70,000.00
2030	9	Bridge Pres	9900	Budgeted	Administrative Functions	-	HR	$ 155,000.00
2026	10	Bridge Pres	3309	RMIP	Replacement of Bridge Expansion Joints	199.00	LFT	$ 199,000.00
2026	10	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	263.80	LFT	$ 263,800.00
2026	10	Bridge Pres	3314C	RMIP	Maintain / Repair Steel Superstructure Components	21.54	LFT	$ 215,400.00
2027	10	Bridge Pres	3309	RMIP	Replacement of Bridge Expansion Joints	199.00	LFT	$ 199,000.00
2027	10	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	263.80	LFT	$ 263,800.00
2027	10	Bridge Pres	3314C	RMIP	Maintain / Repair Steel Superstructure Components	21.54	LFT	$ 215,400.00
2028	10	Bridge Pres	3309	RMIP	Replacement of Bridge Expansion Joints	199.00	LFT	$ 199,000.00
2028	10	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	263.80	LFT	$ 263,800.00
2028	10	Bridge Pres	3314C	RMIP	Maintain / Repair Steel Superstructure Components	21.54	LFT	$ 215,400.00
2029	10	Bridge Pres	3309	RMIP	Replacement of Bridge Expansion Joints	199.00	LFT	$ 199,000.00
2029	10	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	263.80	LFT	$ 263,800.00
2029	10	Bridge Pres	3314C	RMIP	Maintain / Repair Steel Superstructure Components	21.54	LFT	$ 215,400.00
2030	10	Bridge Pres	3309	RMIP	Replacement of Bridge Expansion Joints	199.00	LFT	$ 199,000.00
2030	10	Bridge Pres	3309C	RMIP	Replacement of Bridge Expansion Joints	263.80	LFT	$ 263,800.00
2030	10	Bridge Pres	3314C	RMIP	Maintain / Repair Steel Superstructure Components	21.54	LFT	$ 215,400.00
2026	10	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 17,011.65
2026	10	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 285,178.98
2026	10	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 100,941.20
2026	10	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 19,362.45
2026	10	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 40,566.48
2026	10	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 52,136.77
2026	10	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 408,391.66
2026	10	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 230,370.61
2026	10	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 8,456.51
2026	10	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 78,462.05
2026	10	Bridge Pres	3320C	Budgeted	Maintain Metal Rail	-	LFT	$ 388,579.23
2026	10	Bridge Pres	3324C	Budgeted	Replace Timber Deck Components	-	SFT	$ 47,442.51
2026	10	Bridge Pres	3328C	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 20,261.84
2026	10	Bridge Pres	3348C	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 31,178.55
2026	10	Bridge Pres	3353C	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 306,372.22
2027	10	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 17,011.65
2027	10	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 285,178.98
2027	10	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 100,941.20
2027	10	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 19,362.45
2027	10	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 40,566.48
2027	10	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 52,136.77

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2027	10	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 408,391.66
2027	10	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 230,370.61
2027	10	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 8,456.51
2027	10	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 78,462.05
2027	10	Bridge Pres	3320C	Budgeted	Maintain Metal Rail	-	LFT	$ 388,579.23
2027	10	Bridge Pres	3324C	Budgeted	Replace Timber Deck Components	-	SFT	$ 47,442.51
2027	10	Bridge Pres	3328C	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 20,261.84
2027	10	Bridge Pres	3348C	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 31,178.55
2027	10	Bridge Pres	3353C	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 306,372.22
2028	10	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 17,011.65
2028	10	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 285,178.98
2028	10	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 100,941.20
2028	10	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 19,362.45
2028	10	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 40,566.48
2028	10	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 52,136.77
2028	10	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 408,391.66
2028	10	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 230,370.61
2028	10	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 8,456.51
2028	10	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 78,462.05
2028	10	Bridge Pres	3320C	Budgeted	Maintain Metal Rail	-	LFT	$ 388,579.23
2028	10	Bridge Pres	3324C	Budgeted	Replace Timber Deck Components	-	SFT	$ 47,442.51
2028	10	Bridge Pres	3328C	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 20,261.84
2028	10	Bridge Pres	3348C	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 31,178.55
2028	10	Bridge Pres	3353C	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 306,372.22
2029	10	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 17,011.65
2029	10	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 285,178.98
2029	10	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 100,941.20
2029	10	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 19,362.45
2029	10	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 40,566.48
2029	10	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 52,136.77
2029	10	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 408,391.66
2029	10	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 230,370.61
2029	10	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 8,456.51
2029	10	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 78,462.05
2029	10	Bridge Pres	3320C	Budgeted	Maintain Metal Rail	-	LFT	$ 388,579.23
2029	10	Bridge Pres	3324C	Budgeted	Replace Timber Deck Components	-	SFT	$ 47,442.51
2029	10	Bridge Pres	3328C	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 20,261.84
2029	10	Bridge Pres	3348C	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 31,178.55
2029	10	Bridge Pres	3353C	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 306,372.22
2030	10	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 17,011.65
2030	10	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 285,178.98
2030	10	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 100,941.20
2030	10	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 19,362.45
2030	10	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 40,566.48
2030	10	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 52,136.77
2030	10	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 408,391.66
2030	10	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 230,370.61
2030	10	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 8,456.51
2030	10	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 78,462.05

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2030	10	Bridge Pres	3320C	Budgeted	Maintain Metal Rail	-	LFT	$ 388,579.23
2030	10	Bridge Pres	3324C	Budgeted	Replace Timber Deck Components	-	SFT	$ 47,442.51
2030	10	Bridge Pres	3328C	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 20,261.84
2030	10	Bridge Pres	3348C	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 31,178.55
2030	10	Bridge Pres	3353C	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 306,372.22
2026	11	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	2890.00	LFT	$ 433,500.00
2026	11	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	1550.00	LFT	$ 119,350.00
2027	11	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	2890.00	LFT	$ 433,500.00
2027	11	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	1550.00	LFT	$ 119,350.00
2028	11	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	2890.00	LFT	$ 433,500.00
2028	11	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	1550.00	LFT	$ 119,350.00
2029	11	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	2890.00	LFT	$ 433,500.00
2029	11	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	1550.00	LFT	$ 119,350.00
2030	11	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	2890.00	LFT	$ 433,500.00
2030	11	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	1550.00	LFT	$ 119,350.00
2026	11	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 300,000.00
2026	11	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 150,000.00
2026	11	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 400,000.00
2026	11	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 200,000.00
2026	11	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 400,000.00
2026	11	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 200,000.00
2027	11	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 300,000.00
2027	11	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 150,000.00
2027	11	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 400,000.00
2027	11	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 200,000.00
2027	11	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 400,000.00
2027	11	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 200,000.00
2028	11	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 300,000.00
2028	11	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 150,000.00
2028	11	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 400,000.00
2028	11	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 200,000.00
2028	11	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 400,000.00
2028	11	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 200,000.00
2029	11	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 300,000.00
2029	11	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 150,000.00
2029	11	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 400,000.00
2029	11	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 200,000.00
2029	11	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 400,000.00
2029	11	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 200,000.00
2030	11	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 300,000.00
2030	11	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 150,000.00
2030	11	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 400,000.00
2030	11	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 200,000.00
2030	11	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 400,000.00
2030	11	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 200,000.00
2026	12	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	5237163.00	SFT	$ 1,047,432.60
2027	12	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	5239763.45	SFT	$ 1,047,952.69
2028	12	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	5239763.45	SFT	$ 1,047,952.69
2029	12	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	5239763.45	SFT	$ 1,047,952.69

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2030	12	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	5239763.45	SFT	$ 1,047,952.69
2026	12	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 125,000.00
2026	12	Bridge Pres	2714	Budgeted	Assessments and Inspections	-	HR	$ 615.00
2026	12	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 35,000.00
2026	12	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 10,000.00
2026	12	Bridge Pres	2911	Budgeted	Manual Brush and Tree Control	-	SQF	$ 380.00
2026	12	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 48,000.00
2026	12	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 5,000.00
2026	12	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 15,000.00
2026	12	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 90,000.00
2026	12	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 18,000.00
2026	12	Bridge Pres	3330	Budgeted	Maintenance/Repair Grid Steel Floor	-	SFT	$ 9,000.00
2026	12	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 445.00
2026	12	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 35,000.00
2026	12	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 35,000.00
2026	12	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 22,000.00
2026	12	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 14,900.00
2026	12	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 100,000.00
2026	12	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 330,000.00
2026	12	Bridge Pres	6355	Budgeted	Maint Order Settlement	-	DOL	$ 500.00
2026	12	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 150,000.00
2026	12	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 135,000.00
2027	12	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 125,000.00
2027	12	Bridge Pres	2714	Budgeted	Assessments and Inspections	-	HR	$ 615.00
2027	12	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 35,000.00
2027	12	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 10,000.00
2027	12	Bridge Pres	2911	Budgeted	Manual Brush and Tree Control	-	SQF	$ 380.00
2027	12	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 48,000.00
2027	12	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 5,000.00
2027	12	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 15,000.00
2027	12	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 90,000.00
2027	12	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 18,000.00
2027	12	Bridge Pres	3330	Budgeted	Maintenance/Repair Grid Steel Floor	-	SFT	$ 9,000.00
2027	12	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 445.00
2027	12	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 35,000.00
2027	12	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 35,000.00
2027	12	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 22,000.00
2027	12	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 14,900.00
2027	12	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 100,000.00
2027	12	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 330,000.00
2027	12	Bridge Pres	6355	Budgeted	Maint Order Settlement	-	DOL	$ 500.00
2027	12	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 150,000.00
2027	12	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 135,000.00
2028	12	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 125,000.00
2028	12	Bridge Pres	2714	Budgeted	Assessments and Inspections	-	HR	$ 615.00
2028	12	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 35,000.00
2028	12	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 10,000.00
2028	12	Bridge Pres	2911	Budgeted	Manual Brush and Tree Control	-	SQF	$ 380.00
2028	12	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 48,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2028	12	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 5,000.00
2028	12	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 15,000.00
2028	12	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 90,000.00
2028	12	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 18,000.00
2028	12	Bridge Pres	3330	Budgeted	Maintenance/Repair Grid Steel Floor	-	SFT	$ 9,000.00
2028	12	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 445.00
2028	12	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 35,000.00
2028	12	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 35,000.00
2028	12	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 22,000.00
2028	12	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 14,900.00
2028	12	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 100,000.00
2028	12	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 330,000.00
2028	12	Bridge Pres	6355	Budgeted	Maint Order Settlement	-	DOL	$ 500.00
2028	12	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 150,000.00
2028	12	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 135,000.00
2029	12	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 125,000.00
2029	12	Bridge Pres	2714	Budgeted	Assessments and Inspections	-	HR	$ 615.00
2029	12	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 35,000.00
2029	12	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 10,000.00
2029	12	Bridge Pres	2911	Budgeted	Manual Brush and Tree Control	-	SQF	$ 380.00
2029	12	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 48,000.00
2029	12	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 5,000.00
2029	12	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 15,000.00
2029	12	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 90,000.00
2029	12	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 18,000.00
2029	12	Bridge Pres	3330	Budgeted	Maintenance/Repair Grid Steel Floor	-	SFT	$ 9,000.00
2029	12	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 445.00
2029	12	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 35,000.00
2029	12	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 35,000.00
2029	12	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 22,000.00
2029	12	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 14,900.00
2029	12	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 100,000.00
2029	12	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 330,000.00
2029	12	Bridge Pres	6355	Budgeted	Maint Order Settlement	-	DOL	$ 500.00
2029	12	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 150,000.00
2029	12	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 135,000.00
2030	12	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 125,000.00
2030	12	Bridge Pres	2714	Budgeted	Assessments and Inspections	-	HR	$ 615.00
2030	12	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 35,000.00
2030	12	Bridge Pres	2728	Budgeted	External Customer Service	-	HR	$ 10,000.00
2030	12	Bridge Pres	2911	Budgeted	Manual Brush and Tree Control	-	SQF	$ 380.00
2030	12	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 48,000.00
2030	12	Bridge Pres	3318	Budgeted	Maintenance of Concrete Barrier Rail	-	LFT	$ 5,000.00
2030	12	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 15,000.00
2030	12	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 90,000.00
2030	12	Bridge Pres	3328	Budgeted	Maintenance/Repair/ Replace Steel Plank Bridge Floor	-	SFT	$ 18,000.00
2030	12	Bridge Pres	3330	Budgeted	Maintenance/Repair Grid Steel Floor	-	SFT	$ 9,000.00
2030	12	Bridge Pres	3334	Budgeted	Bridge Bearings	-	EA	$ 445.00
2030	12	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 35,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2030	12	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 35,000.00
2030	12	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 22,000.00
2030	12	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 14,900.00
2030	12	Bridge Pres	3354	Budgeted	Maintain / Repair Steel Substructure Components	-	LFT	$ 100,000.00
2030	12	Bridge Pres	6080	Budgeted	MISC SERV OR OPERATIONS	-	HR	$ 330,000.00
2030	12	Bridge Pres	6355	Budgeted	Maint Order Settlement	-	DOL	$ 500.00
2030	12	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 150,000.00
2030	12	Bridge Pres	2724C	Budgeted	Construction Inspection	-	HR	$ 135,000.00
2026	13	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	1865.44	LFT	$ 559,631.55
2026	13	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	1957.73	LFT	$ 225,139.12
2026	13	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	23200.00	SFT	$ 116,000.00
2026	13	Bridge Pres	3352	RMIP	Maint Slope Protection	4821.43	SFT	$ 168,750.00
2026	13	Bridge Pres	3366	RMIP	Drift and Debris Removal	3153.85	HR	$ 164,000.00
2026	13	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	18780.22	SFT	$ 78,501.33
2027	13	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	1865.44	LFT	$ 559,631.55
2027	13	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	1957.73	LFT	$ 225,139.12
2027	13	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	23200.00	SFT	$ 116,000.00
2027	13	Bridge Pres	3352	RMIP	Maint Slope Protection	4821.43	SFT	$ 168,750.00
2027	13	Bridge Pres	3366	RMIP	Drift and Debris Removal	3153.85	HR	$ 164,000.00
2027	13	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	18780.22	SFT	$ 78,501.33
2028	13	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	1865.44	LFT	$ 559,631.55
2028	13	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	1957.73	LFT	$ 225,139.12
2028	13	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	23200.00	SFT	$ 116,000.00
2028	13	Bridge Pres	3352	RMIP	Maint Slope Protection	4821.43	SFT	$ 168,750.00
2028	13	Bridge Pres	3366	RMIP	Drift and Debris Removal	3153.85	HR	$ 164,000.00
2028	13	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	18780.22	SFT	$ 78,501.33
2029	13	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	1865.44	LFT	$ 559,631.55
2029	13	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	1957.73	LFT	$ 225,139.12
2029	13	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	23200.00	SFT	$ 116,000.00
2029	13	Bridge Pres	3352	RMIP	Maint Slope Protection	4821.43	SFT	$ 168,750.00
2029	13	Bridge Pres	3366	RMIP	Drift and Debris Removal	3153.85	HR	$ 164,000.00
2029	13	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	18780.22	SFT	$ 78,501.33
2030	13	Bridge Pres	3314	RMIP	Maintain / Repair Steel Superstructure Components	1865.44	LFT	$ 559,631.55
2030	13	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	1957.73	LFT	$ 225,139.12
2030	13	Bridge Pres	3342	RMIP	Clean and Paint Structural Steel	23200.00	SFT	$ 116,000.00
2030	13	Bridge Pres	3352	RMIP	Maint Slope Protection	4821.43	SFT	$ 168,750.00
2030	13	Bridge Pres	3366	RMIP	Drift and Debris Removal	3153.85	HR	$ 164,000.00
2030	13	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	18780.22	SFT	$ 78,501.33
2026	13	Bridge Pres	2080	Budgeted	Construction Plan Preparation	-	HR	$ 175,000.00
2026	13	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 82,947.48
2026	13	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 210,000.00
2026	13	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 65,117.43
2026	13	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 72,068.04
2026	13	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 49,191.78
2026	13	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 83,324.00
2026	13	Bridge Pres	6350	Budgeted	Internal Order Settlement	-	DOL	$ 106.26
2026	13	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 865,825.95
2027	13	Bridge Pres	2080	Budgeted	Construction Plan Preparation	-	HR	$ 175,000.00
2027	13	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 82,947.48

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2027	13	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 210,000.00
2027	13	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 65,117.43
2027	13	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 72,068.04
2027	13	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 49,191.78
2027	13	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 83,324.00
2027	13	Bridge Pres	6350	Budgeted	Internal Order Settlement	-	DOL	$ 106.26
2027	13	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 865,825.95
2028	13	Bridge Pres	2080	Budgeted	Construction Plan Preparation	-	HR	$ 175,000.00
2028	13	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 82,947.48
2028	13	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 210,000.00
2028	13	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 65,117.43
2028	13	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 72,068.04
2028	13	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 49,191.78
2028	13	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 83,324.00
2028	13	Bridge Pres	6350	Budgeted	Internal Order Settlement	-	DOL	$ 106.26
2028	13	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 865,825.95
2029	13	Bridge Pres	2080	Budgeted	Construction Plan Preparation	-	HR	$ 175,000.00
2029	13	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 82,947.48
2029	13	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 210,000.00
2029	13	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 65,117.43
2029	13	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 72,068.04
2029	13	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 49,191.78
2029	13	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 83,324.00
2029	13	Bridge Pres	6350	Budgeted	Internal Order Settlement	-	DOL	$ 106.26
2029	13	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 865,825.95
2030	13	Bridge Pres	2080	Budgeted	Construction Plan Preparation	-	HR	$ 175,000.00
2030	13	Bridge Pres	2640	Budgeted	Project Management	-	HR	$ 82,947.48
2030	13	Bridge Pres	2724	Budgeted	Construction Inspection	-	HR	$ 210,000.00
2030	13	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 65,117.43
2030	13	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 72,068.04
2030	13	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 49,191.78
2030	13	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 83,324.00
2030	13	Bridge Pres	6350	Budgeted	Internal Order Settlement	-	DOL	$ 106.26
2030	13	Bridge Pres	7640	Budgeted	Payment to Contractor	-	DOL	$ 865,825.95
2026	14	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	832.00	LFT	$ 99,840.00
2026	14	Bridge Pres	3366	RMIP	Drift and Debris Removal	564.00	HR	$ 42,864.00
2026	14	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	110443.00	SFT	$ 13,253.16
2026	14	Bridge Pres	3316C	RMIP	Maintenance of Timber Rail	464.00	LFT	$ 681,152.00
2026	14	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	96889.00	SFT	$ 31,973.37
2027	14	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	832.00	LFT	$ 99,840.00
2027	14	Bridge Pres	3366	RMIP	Drift and Debris Removal	564.00	HR	$ 42,864.00
2027	14	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	110443.00	SFT	$ 13,253.16
2027	14	Bridge Pres	3316C	RMIP	Maintenance of Timber Rail	464.00	LFT	$ 681,152.00
2027	14	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	96889.00	SFT	$ 31,973.37
2028	14	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	832.00	LFT	$ 99,840.00
2028	14	Bridge Pres	3366	RMIP	Drift and Debris Removal	564.00	HR	$ 42,864.00
2028	14	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	110443.00	SFT	$ 13,253.16
2028	14	Bridge Pres	3316C	RMIP	Maintenance of Timber Rail	464.00	LFT	$ 681,152.00
2028	14	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	96889.00	SFT	$ 31,973.37

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2029	14	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	832.00	LFT	$ 99,840.00
2029	14	Bridge Pres	3366	RMIP	Drift and Debris Removal	564.00	HR	$ 42,864.00
2029	14	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	110443.00	SFT	$ 13,253.16
2029	14	Bridge Pres	3316C	RMIP	Maintenance of Timber Rail	464.00	LFT	$ 681,152.00
2029	14	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	96889.00	SFT	$ 31,973.37
2030	14	Bridge Pres	3316	RMIP	Maintenance of Timber Rail	832.00	LFT	$ 99,840.00
2030	14	Bridge Pres	3366	RMIP	Drift and Debris Removal	564.00	HR	$ 42,864.00
2030	14	Bridge Pres	3376	RMIP	Clean / Wash Bridge Decks	110443.00	SFT	$ 13,253.16
2030	14	Bridge Pres	3316C	RMIP	Maintenance of Timber Rail	464.00	LFT	$ 681,152.00
2030	14	Bridge Pres	3376C	RMIP	Clean / Wash Bridge Decks	96889.00	SFT	$ 31,973.37
2026	14	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 31,505.00
2026	14	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 30,500.00
2026	14	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 122,000.00
2026	14	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 244,000.00
2026	14	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 30,500.00
2026	14	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 427,000.00
2026	14	Bridge Pres	3332	Budgeted	Maintenance Drainage System - Bridge	-	LFT	$ 61,000.00
2026	14	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 183,000.00
2026	14	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 427,000.00
2026	14	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 183,000.00
2026	14	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 24,400.00
2026	14	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 9,150.00
2027	14	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 31,505.00
2027	14	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 30,500.00
2027	14	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 122,000.00
2027	14	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 244,000.00
2027	14	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 30,500.00
2027	14	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 427,000.00
2027	14	Bridge Pres	3332	Budgeted	Maintenance Drainage System - Bridge	-	LFT	$ 61,000.00
2027	14	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 183,000.00
2027	14	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 427,000.00
2027	14	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 183,000.00
2027	14	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 24,400.00
2027	14	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 9,150.00
2028	14	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 31,505.00
2028	14	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 30,500.00
2028	14	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 122,000.00
2028	14	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 244,000.00
2028	14	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 30,500.00
2028	14	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 427,000.00
2028	14	Bridge Pres	3332	Budgeted	Maintenance Drainage System - Bridge	-	LFT	$ 61,000.00
2028	14	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 183,000.00
2028	14	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 427,000.00
2028	14	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 183,000.00
2028	14	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 24,400.00
2028	14	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 9,150.00
2029	14	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 31,505.00
2029	14	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 30,500.00
2029	14	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 122,000.00

Plan Year	Division	Budget Group	Function Code	Plan Level	Description	Plan Work	UOM	Estimated Cost
2029	14	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 244,000.00
2029	14	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 30,500.00
2029	14	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 427,000.00
2029	14	Bridge Pres	3332	Budgeted	Maintenance Drainage System - Bridge	-	LFT	$ 61,000.00
2029	14	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 183,000.00
2029	14	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 427,000.00
2029	14	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 183,000.00
2029	14	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 24,400.00
2029	14	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 9,150.00
2030	14	Bridge Pres	2712	Budgeted	Office Engineering	-	HR	$ 31,505.00
2030	14	Bridge Pres	2726	Budgeted	Office Administration	-	HR	$ 30,500.00
2030	14	Bridge Pres	3304	Budgeted	Replace Timber Superstructure Components	-	LFT	$ 122,000.00
2030	14	Bridge Pres	3306	Budgeted	Maintain Concrete Superstructure Components	-	SFT	$ 244,000.00
2030	14	Bridge Pres	3320	Budgeted	Maintain Metal Rail	-	LFT	$ 30,500.00
2030	14	Bridge Pres	3324	Budgeted	Replace Timber Deck Components	-	SFT	$ 427,000.00
2030	14	Bridge Pres	3332	Budgeted	Maintenance Drainage System - Bridge	-	LFT	$ 61,000.00
2030	14	Bridge Pres	3344	Budgeted	Repair / Replace Timber Substructure Components	-	LFT	$ 183,000.00
2030	14	Bridge Pres	3346	Budgeted	Repair / Maintain and Replacement of Timber Wings & Bulkheads	-	SFT	$ 427,000.00
2030	14	Bridge Pres	3348	Budgeted	Maintain Concrete Substructure Components	-	SFT	$ 183,000.00
2030	14	Bridge Pres	3350	Budgeted	Repair Concrete Wings and Walls	-	SFT	$ 24,400.00
2030	14	Bridge Pres	3353	Budgeted	Maintenance or Repair of Concrete Bridge Approach Slab	-	CYD	$ 9,150.00

BRIDGES - BMIP

Statewide - Estimated Costs in 5 Year BMIP

Division	Budget Group	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	5-Year Total
1	HFBD	$7,394,000	$4,888,000	$4,530,000	$3,990,000	$1,008,500	$21,810,500
	HFBSW	$6,130,000	$7,400,000	$14,800,000	$975,000		$29,305,000
	O		$26,500,000				$26,500,000
2	BGOFF	$24,119,000				$2,503,000	$26,622,000
	HFBD	$7,660,000	$5,620,000	$5,540,000	$2,469,000	$4,740,000	$26,029,000
	HFBSW	$56,103,700			$33,355,000		$89,458,700
	NHPB			$7,391,000	$15,200,000		$22,591,000
3	HFBD		$10,365,000	$9,515,000	$4,505,000	$3,740,000	$28,125,000
	HFBSW	$8,900,000	$15,950,000	$17,105,000			$41,955,000
	NHPB				$10,290,000	$32,900,000	$43,190,000
4	BGOFF		$6,580,000				$6,580,000
	HFBD	$5,695,000	$10,890,000	$8,990,000		$7,980,000	$33,555,000
	HFBSW	$24,750,803	$52,497,324		$2,750,000		$79,998,127
	NHPB			$16,780,000	$153,810,000		$170,590,000
5	BGOFF	$4,451,000			$2,200,000	$3,940,000	$10,591,000
	HFBD	$5,725,000	$5,760,000	$8,325,000	$12,800,000		$32,610,000
	HFBSW		$8,100,000	$2,870,000	$27,725,000	$30,000,000	$68,695,000
	NHPB				$86,376,000		$86,376,000
6	BGOFF			$3,130,000		$3,290,000	$6,420,000
	HFBD	$2,210,000	$2,140,000	$5,100,000			$9,450,000
	O	$9,000,000					$9,000,000
7	BGOFF	$15,725,000	$15,310,000				$31,035,000
	HFBD	$12,035,000	$4,370,000	$6,012,800	$4,787,800	$3,311,400	$30,517,000
	HFBSW	$34,510,000	$84,477,000	$22,850,000	$19,460,000		$161,297,000
	NHPB		$14,080,000	$12,308,000	$11,880,000		$38,268,000
8	BGOFF	$820,000			$12,220,000		$13,040,000
	HFBD	$7,832,000	$5,930,000	$1,225,000	$1,240,000		$16,227,000
9	BGOFF	$6,630,000		$15,120,000	$12,800,000		$34,550,000
	HFBD	$7,550,000	$6,165,000	$10,235,000			$23,950,000
	HFBSW	$32,910,000	$20,720,000	$65,690,000	$3,250,000	$20,000,000	$142,570,000
	NHPB		$12,400,000		$18,860,000		$31,260,000
10	BGOFF	$3,100,000	$4,453,000	$3,255,000		$615,000	$11,423,000
	HFBD	$6,790,745	$8,807,400	$6,456,271	$4,281,060	$6,803,320	$33,138,796
	HFBSW	$22,877,055		$23,152,800	$13,100,000		$59,129,855
	NHPB			$5,520,000	$4,348,000		$9,868,000

Statewide - Estimated Costs in 5 Year BMIP

Division	Budget Group	FY 2026	FY 2027	FY 2028	FY 2029	FY 2030	5-Year Total
11	BGOFF	$9,100,000				$4,250,000	$13,350,000
	HFBD	$22,200,000	$12,625,000	$2,700,000			$37,525,000
	HFBSW		$36,840,000	$17,150,000	$8,200,000		$62,190,000
	HFBSW / O	$5,740,000	$55,855,000				$61,595,000
	NHPB	$45,220,000					$45,220,000
	O			$26,100,000			$26,100,000
12	BGOFF			$23,900,000		$4,187,000	$28,087,000
	HFBD	$6,215,800	$14,764,200	$8,696,100	$9,239,900	$10,045,800	$48,961,800
	HFBSW	$41,421,560	$42,570,000	$81,910,000		$16,400,000	$182,301,560
	NHPB	$82,400,000			$76,600,000	$38,890,000	$197,890,000
13	BGOFF	$3,210,000		$25,400,000			$28,610,000
	HFBD	$39,455,000	$15,040,500	$17,550,000	$13,175,000	$4,800,000	$90,020,500
	HFBSW	$67,380,000	$25,740,000	$8,720,000	$31,880,000	$20,000,000	$153,720,000
	NHPB				$51,450,000	$11,800,000	$63,250,000
14	BGOFF	$14,140,000	$3,195,000	$6,810,000	$13,130,000		$37,275,000
	HFBD	$10,955,000	$13,375,000	$8,429,000	$10,560,000	$9,260,000	$52,579,000
	HFBSW	$16,629,020	$88,448,020	$5,650,000	$6,460,000		$117,187,040
	NHPB	$7,480,000					$7,480,000
Statewide Totals	BGOFF	$81,295,000	$29,538,000	$77,615,000	$40,350,000	$18,785,000	$247,583,000
	HFBD	$141,717,545	$120,740,100	$103,304,171	$67,047,760	$51,689,020	$484,498,596
	HFBSW	$311,612,138	$382,742,344	$259,897,800	$147,155,000	$86,400,000	$1,187,807,282
	HFBSW / O	$5,740,000	$55,855,000	$0	$0	$0	$61,595,000
	NHPB	$135,100,000	$26,480,000	$41,999,000	$428,814,000	$83,590,000	$715,983,000
	O	$9,000,000	$26,500,000	$26,100,000	$0	$0	$61,600,000

Budget Group Descriptions	
BGOFF	Surface Transportation Block Grant Program (Off System)
BPR	Central Bridge Preservation
HFBD	Highway Fund Bridge Replacement Program (Division Funds)
HFBSW	Highway Fund Bridge Replacement Program (Statewide Funds)
NHPB	National Highway Performance Program (Bridge)
O	Local, Non Federal or State Funds

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2026	1	BERTIE	BR-0153	HFBSW	Replacement	NC11, NC42	CASHIE RIVER	070024	$6,130,000
2026	1	HYDE	BP1-R033	HFBD	Replacement	SR1362	CANAL	Non-NBIS Pipe	$2,050,000
2026	1	TYRRELL	BP1-R014	HFBD	Replacement	SR1105	SECOND CREEK	880018	$1,657,000
2026	1	HERTFORD	BP1-R012	HFBD	Replacement	SR1155	CUTAWHISKIE SWAMP	450064	$1,050,000
2026	1	MARTIN	BP1-R013	HFBD	Replacement	SR1106	SMITHWICK CREEK	570022	$1,050,000
2026	1	NORTHAMPTON	BP1-R018	HFBD	Replacement	SR1508	DOOLITTLE MILL POND	650017	$980,000
2026	1	PASQUOTANK	BP1-R011	HFBD	Replacement	SR1367(CLOSED)	CANAL SHEPHARD'S DITCH	690041	$607,000
2026	2	PAMLICO	B-5995	BGOFF	Replacement	SR1302	DAWSON CREEK	680057	$5,950,000
2026	2	CRAVEN	BR-0074	HFBSW	Replacement	US70E US70W	SLOCUM CREEK S. PR. SLOCUM CREEK	240091 240092	$10,452,200
2026	2	PAMLICO	BR-0173	HFBSW	Replacement	NC306 FERRY	NEUSE RIVER	680078	$9,700,000
2026	2	BEAUFORT	B-5614	BGOFF	Replacement	SR1112	BLOUNTS CREEK	060009	$18,169,000
2026	2	BEAUFORT	BR-0004	HFBSW	Replacement	US264	PUNGO RIVER	060066	$19,220,000
2026	2	BEAUFORT	BR-0005	HFBSW	Replacement	NC33	CHOCOWINITY CREEK	060075	$16,731,500
2026	2	BEAUFORT	BP2-R017	HFBD	Replacement	SR1334	UPPER GOOSE CREEK	060115	$1,810,000
2026	2	BEAUFORT	BP2-R008	HFBD	Replacement	SR1110	HERRING RUN	060010	$1,330,000
2026	2	BEAUFORT	BP2-R015	HFBD	Replacement	SR1718	OLD MILL CREEK	060131	$1,330,000
2026	2	CRAVEN	BP2-R022	HFBD	Replacement	SR1465	SWIFT CREEK	240043	$1,310,000
2026	2	BEAUFORT	BP2-R010	HFBD	Replacement	SR1100	HERRING RUN	060011	$1,280,000
2026	2	CARTERET	17BP.2.C.13	HFBD	Replacement	OFF SR1170/US70	UNNAMED BRANCH	Non-NBIS Pipe	$600,000
2026	3	PENDER	BR-0174	HFBSW	Replacement	NC53	ANGOLA CREEK	700037	$8,900,000
2026	4	JOHNSTON	BP4-R007	HFBD	Replacement	SR1701	BUFFALO CREEK	500169	$2,690,000
2026	4	NASH	BR-0090	HFBSW	Replacement	NC561	FISHING CREEK	630036	$7,490,000
2026	4	WAYNE	B-4838	HFBSW	Replacement	US70 BUS.	SCL RAILROAD	950020	$8,227,303
2026	4	NASH	BR-0147	HFBSW	Replacement	US64BUS	TAR RIVER OVERFLOW	630205	$9,033,500
2026	4	WAYNE	BP4-R027	HFBD	Replacement	SR1505	AYCOCK SWAMP	950219	$1,700,000
2026	4	EDGECOMBE	BP4-R020	HFBD	Replacement	SR1120	BYNUM MILL CREEK	320010	$1,305,000
2026	5	GRANVILLE	HB-0072	BGOFF	Replacement	SR1629	FORK CREEK	380199	$4,451,000
2026	5	WAKE	BP5-C001	HFBD	Replacement	SR1160	BEAVER CREEK	910358	$1,925,000
2026	5	WARREN	BP5-R075	HFBD	Replacement	SR1509	BENS CREEK	920016	$1,900,000
2026	5	GRANVILLE	BP5-R103	HFBD	Replacement	SR1303	N FORK TAR RIVER	380107	$1,900,000
2026	6	ROBESON	B-5985B	O	Replacement	SR1600	LUMBER RIVER	770175	$9,000,000
2026	6	COLUMBUS	BP6-R008	HFBD	Replacement	SR1818	MILL CREEK	230271	$1,180,000
2026	6	ROBESON	BP6-R007	HFBD	Replacement	SR1515	RICHLAND SWAMP	770369	$1,030,000
2026	7	GUILFORD	17BP.7.R.114	HFBD	Replacement	SR1332	BRANCH OF DEEP RIVER	400052	$6,300,000
2026	7	ROCKINGHAM	BP7-C001	HFBD	Replacement	SR2147	TACKETT BRANCH	Non-NBIS Pipe	$2,510,000
2026	7	ROCKINGHAM	BR-0096	BGOFF	Replacement	SR1700	NC14, NC87	780176	$2,910,000
2026	7	ROCKINGHAM	BR-0141	BGOFF	Replacement	SR2150	US220, US311	780123	$4,510,000
2026	7	ORANGE	BR-0092	HFBSW	Replacement	NC86	NEW HOPE CREEK	670037	$6,400,000
2026	7	ROCKINGHAM	BR-0155	HFBSW	Replacement	US158	HOGAN'S CREEK	780163	$9,550,000
2026	7	GUILFORD	BR-0080	BGOFF	Replacement	SULLIVAN STREET	US29, US70, US220	400331	$8,305,000
2026	7	ROCKINGHAM	BR-0098	HFBSW	Replacement	US29BUS	US29 BYP.	780183	$7,510,000
2026	7	ALAMANCE	BR-0060	HFBSW	Replacement	NC87	CANE CREEK	000014	$11,050,000
2026	7	ROCKINGHAM	BP7-R001	HFBD	Replacement	US29BUS.RAMP	US29	780023	$1,625,000
2026	7	ROCKINGHAM	17BP.7.R.139	HFBD	Replacement	SR1002	HAW RIVER	780018	$1,600,000
2026	8	RANDOLPH	HB-0071	BGOFF	Replacement	SR2207	CREEK OFF DEEP RIVER	750176	$820,000
2026	8	RANDOLPH	BP8-R025	HFBD	Replacement	SR2453	SANDY CREEK	750151	$1,240,000
2026	8	RICHMOND	BP8-R006	HFBD	Replacement	SR1148	COLEMAN'S CREEK	760091	$1,120,000
2026	8	MOORE	BP8-R024	HFBD	Replacement	SR1947	BEAVER CREEK	620006	$1,030,000

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2026	8	RANDOLPH	BP8-R019	HFBD	Replacement	SR1005	BRUSH CREEK	750162	$952,000
2026	8	MOORE	BP8-R022	HFBD	Replacement	SR2018	CRANE CREEK	620198	$930,000
2026	8	HOKE	BP8-R012	HFBD	Replacement	SR1300	ROCKFISH CREEK	460066	$920,000
2026	8	RANDOLPH	BP8-R027	HFBD	Replacement	SR2863	MEADOW CREEK	750305	$820,000
2026	8	RANDOLPH	BP8-R028	HFBD	Replacement	SR1400	BR. OF BRIER CREEK	750330	$820,000
2026	9	ROWAN	BP9-R012	HFBD	Replacement	SR1004	RILES CRK ROYALS CRK	790108	$4,000,000
2026	9	ROWAN	17BP.9.R.96	HFBD	Replacement	SR1547	KERR CREEK	790254	$2,200,000
2026	9	STOKES	BR-0102	HFBSW	Replacement	NC268	BIG CREEK	840037	$4,320,000
2026	9	FORSYTH	B-5007	BGOFF	Replacement	WEST FIRST ST.	NORFOLK S. RAILROAD (ABA	330296	$6,630,000
2026	9	FORSYTH	BR-0168	HFBSW	Replacement	SR4000	US52	330289	$13,580,000
2026	9	DAVIDSON	BR-0140	HFBSW	Replacement	I85N.BUS,US29,US70 I85BUSS,US29,US70	WSSB RAILROAD WSSB RR	280087 280089	$15,010,000
2026	9	DAVIE	BP9-R007	HFBD	Replacement	SR1621	BAILEY CREEK	290025	$1,350,000
2026	10	CABARRUS	BP10-C012	HFBD	Replacement	SR3628	FLAT BRANCH	Non-NBIS Pipe	NA
2026	10	CABARRUS	BP10-R047	HFBD	Replacement	SR2408	DUTCH BUFFALO CREEK	120083	$2,560,600
2026	10	UNION	BP10-R046	HFBD	Replacement	SR1004	SOUTH FORK CROOKED CREEK	890269	$2,370,000
2026	10	MECKLENBURG	BP10-R012	HFBSW	Replacement	SR2442	S.PRONG OF CLARK'S CREEK	590090	$2,746,000
2026	10	MECKLENBURG	B-5931	BGOFF	Replacement	MORRIS FIELD DRIVE	SOUTHERN RAILROAD	590443	$3,100,000
2026	10	MECKLENBURG	BP10-R013	HFBSW	Replacement	SR5469	COFFEY CREEK	590165	$8,611,055
2026	10	UNION	BR-0049	HFBSW	Replacement	CONCORD AVE	US74, NC200	890034	$11,520,000
2026	10	CABARRUS	BP10-C011	HFBD	Replacement	SR1524	UNNAMED BRANCH	Non-NBIS Pipe	$1,280,000
2026	10	CABARRUS	BP10-R055	HFBD	Replacement	SR2625	LITTLE MEADOW CREEK	120292	$580,145
2026	11	SURRY	BP11-R026	HFBD	Replacement	SR1624	PAULS CREEK	850092	$2,750,000
2026	11	SURRY	BP11-R019	HFBD	Replacement	SR2018	FLAT SHOAL CREEK	850131	$2,250,000
2026	11	ASHE	17BP.11.R.160	HFBD	Replacement	US221	DOG CREEK	040029	$1,700,000
2026	11	WILKES	BP11-R047	HFBD	Replacement	SR1939 (CLOSED)	SPARKS CREEK	960221	$1,575,000
2026	11	WILKES	BP11-R051	HFBD	Replacement	SR2419 SR2012 SR2425	LITTLE HUNTING CREEK LITTLE BUGABOO CREEK UT TO HUNTING CREEK	960018 960296 960344	$1,500,000
2026	11	ASHE	BP11-R046	HFBD	Replacement	SR1169	W. FORK PINE SWAMP CREEK	040156	$1,450,000
2026	11	WILKES	BP11-R030	HFBD	Replacement	SR1363	N.PRONG LEWIS FORK CREEK	960110	$1,400,000
2026	11	YADKIN	B-5833	NHPB	Replacement	US21BUS	I-77	980029	$20,900,000
2026	11	SURRY	B-5831	NHPB	Replacement	I-77 NBL	NC268,SOU.RR,YADKIN RVR.	850006	$24,320,000
2026	11	ASHE	HB-0051	HFBSW / O	Replacement	SR1159	SOUTH FORK NEW RIVER	040466	$2,420,000
2026	11	ASHE	HB-0068	HFBSW / O	Replacement	SR1527	HELTON CREEK	040048	$1,550,000
2026	11	ASHE	HB-0043	HFBSW / O	Replacement	SR1523	HELTON CREEK	040047	$1,770,000
2026	11	WILKES	B-4676A	BGOFF	Replacement	SR1001	CUB CREEK	960029	$9,100,000
2026	11	ASHE	BP11-R029	HFBD	Replacement	SR1118	NORTH FORK NEW RIVER	040118	$1,250,000
2026	11	ASHE	BP11-R012	HFBD	Replacement	SR1193	BUFFALO CREEK	040474	$1,075,000
2026	11	ASHE	BP11-R016	HFBD	Replacement	SR1100	GAP CREEK	040171	$1,050,000
2026	11	ASHE	BP11-R028	HFBD	Replacement	SR1592	DOG CREEK	040153	$1,050,000
2026	11	CALDWELL	BP11-R008	HFBD	Replacement	SR1545	ZACKS FORK CREEK	130011	$925,000
2026	11	ASHE	BP11-R009	HFBD	Replacement	SR1308	CABBAGE CREEK	040137	$925,000
2026	11	YADKIN	BP11-R020	HFBD	Replacement	SR1581	UT TO LOGAN CREEK	980147	$900,000
2026	11	CALDWELL	BP11-R040	HFBD	Replacement	SR1719	UPPER LITTLE RIVER	130048	$875,000
2026	11	YADKIN	BP11-R021	HFBD	Replacement	SR1591	FORBUSH CREEK	980087	$775,000
2026	11	WATAUGA	BP11-R034	HFBD	Replacement	SR1311	VANDERPOOL CREEK	940090	$750,000
2026	12	IREDELL	17BP.12.R.78	HFBD	Replacement	SR1512	THIRD CREEK	480254	$2,400,000
2026	12	IREDELL	BP12-R029	HFBD	Replacement	SR1150	CODDLE CREEK	480032	$1,875,800
2026	12	CLEVELAND	BP12-C003	HFBD	Replacement	SR2017	LITTLE PERSIMMON CREEK	220043	$1,140,000

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2026	12	IREDELL	B-5394	HFBSW	Replacement	SR1832	HUNTING CREEK	480279	$4,940,000
2026	12	CLEVELAND	BP12-R002	HFBSW	Replacement	NC226	HINTON CREEK	220075	$10,050,000
2026	12	GASTON	B-5857	HFBSW	Replacement	US29 & US74	SOUTH FORK CATAWBA RIVER	350082	$11,950,000
2026	12	GASTON	BR-0019	HFBSW	Replacement	NC275	S. FORK CATAWBA RIVER	350056	$14,481,560
2026	12	GASTON	B-6051	NHPB	Replacement	US29,US74	CATAWBA RIVER	350091	$82,400,000
2026	12	GASTON	BP12-C004	HFBD	Replacement	SR1446	UT TO LONG CREEK	350312	$800,000
2026	13	BUNCOMBE	BP13-T027	HFBD	Replacement	SR2426	SHOPE CREEK	100307	NA
2026	13	BUNCOMBE	BP13-T028	HFBD	Replacement	SR2115	REEMS CREEK	100506	NA
2026	13	MADISON	BP13-T029	HFBD	Replacement	SR1378	WEST FORK BULL CREEK	560082	NA
2026	13	MADISON	BP13-T030	HFBD	Replacement	SR1127	ROBERTS BRANCH	560312	NA
2026	13	MITCHELL	BP13-R016	HFBD	Replacement	SR1211	CANE CREEK	600046	$4,350,000
2026	13	RUTHERFORD	BP13-R004	HFBD	Replacement	SR1576	PUZZLE CREEK	800076	$3,300,000
2026	13	MADISON	BP13-R022	HFBD	Replacement	SR1395	WALNUT CREEK	560063	$3,200,000
2026	13	MCDOWELL	BP13-R048	HFBD	Replacement	SR1560	NORTH FORK CATAWBA RIVER	580108	$2,955,000
2026	13	MITCHELL	17BP.13.R.184	HFBD	Replacement	SR1002	BIG CRABTREE CREEK	600101	$2,600,000
2026	13	MADISON	BP13-R024	HFBD	Replacement	SR1318	SPILLCORN CREEK	560152	$2,550,000
2026	13	MADISON	BP13-R010	HFBD	Replacement	9901	BIG LAUREL CREEK	560552	$2,375,000
2026	13	MADISON	BP13-R020	HFBD	Replacement	SR1515	MIDDLE FORK CREEK	560036	$2,350,000
2026	13	MADISON	BP13-R014	HFBD	Replacement	SR1318	BIG LAUREL CREEK	560090	$2,000,000
2026	13	MADISON	BP13-R023	HFBD	Replacement	SR1347	CHANDLER CREEK	560087	$1,950,000
2026	13	BUNCOMBE	BP13-R006	HFBD	Replacement	SR1733	FLAT CREEK	100065	$1,875,000
2026	13	MCDOWELL	BP13-R026	HFBD	Replacement	SR1559	LIMEKILN CREEK	580194	$1,825,000
2026	13	BURKE	BP13-R033	HFBD	Replacement	SR1116	DOUBLE BRANCH	110254	$1,825,000
2026	13	MADISON	BP13-R021	HFBD	Replacement	SR1395	WALNUT CREEK	560061	$1,675,000
2026	13	MADISON	BP13-R015	HFBD	Replacement	SR1370	WEST FORK BULL CREEK	560098	$1,650,000
2026	13	MADISON	BR-0251	HFBD	Replacement	SR1341 SR1341 SR1339 SR1336	FOSTER CREEK FOSTER CREEK BIG LAUREL CREEK BIG LAUREL CREEK	560072 560074 560381 560500	$1,550,000
2026	13	BUNCOMBE	BP13-R013	HFBD	Replacement	SR1768	ADKINS BRANCH	100692	$1,425,000
2026	13	MADISON	BR-0145	HFBSW	Replacement	NC208	SHELTON LAUREL CREEK	560033	$2,750,000
2026	13	RUTHERFORD	B-6047	BGOFF	Replacement	SR2125	FLOYDS CREEK	800145	$3,210,000
2026	13	MCDOWELL	B-6040	HFBSW	Replacement	US70	SOUTHERN RR	580127	$4,620,000
2026	13	RUTHERFORD	BR-0101	HFBSW	Replacement	US64	COVE CREEK	800104	$7,990,000
2026	13	BURKE	BR-0010	HFBSW	Replacement	US64,NC18	JOHNS RIVER	110105	$13,020,000
2026	13	BURKE	BR-0151	HFBSW	Replacement	SR1002	I-40	110173	$18,000,000
2026	13	BUNCOMBE	B-5953	HFBSW	Replacement	SR1002	FRENCH BROAD RVR,SO.RR	100649	$21,000,000
2026	14	HAYWOOD	BP14-R002	HFBD	Replacement	SR1129 SR1129	LITTLE E. FORK PIGEON RV LITTLE E.FORK PIGEON RVR	430087 430090	$5,375,000
2026	14	POLK	BP14-R038	HFBD	Replacement	SR1102	NORTH PACOLET RIVER	740009	$4,060,000
2026	14	POLK	BP14-R006	HFBD	Replacement	SR1138	PANTHER CREEK	740143	$1,520,000
2026	14	JACKSON	B-6034	BGOFF	Replacement	SR1300	SAVANNAH CREEK	490065	$1,570,000
2026	14	MACON	B-6029	BGOFF	Replacement	SR1001	NORTH PRONG ELLIJAY CREE	550009	$2,000,000
2026	14	HENDERSON	B-5929	BGOFF	Replacement	OLD DANA ROAD	DEVILS FORK CREEK	440350	$2,150,000
2026	14	JACKSON	B-5921	BGOFF	Replacement	SR1120	CEDAR CREEK	490008	$2,910,000
2026	14	MACON	BR-0031	HFBSW	Replacement	SR1310	NANTAHALA RIVER	550226	$3,367,520
2026	14	MACON	BR-0052	HFBSW	Replacement	SR1310	NANTAHALA RIVER	550227	$3,438,500
2026	14	MACON	BR-0053	HFBSW	Replacement	SR1310	NANTAHALA RIVER	550228	$3,793,000
2026	14	POLK	BR-0040	HFBSW	Replacement	NC9	GREEN RIVER	740037	$6,030,000
2026	14	HAYWOOD	B-5920	BGOFF	Replacement	SR1216	WEST FORK PIGEON RIVER	430246	$1,970,000

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2026	14	CHEROKEE	B-5925	NHPB	Replacement	SR1548	HIWASSEE RIVER	190223	$7,480,000
2026	14	MACON	HB-0030	BGOFF	Replacement	SR1679	CULLASAJA RIVER	550055	$3,540,000
2027	1	MARTIN	BP1-R021	HFBD	Replacement	SR1538	BR HARDISON MILL CREEK	570025	$712,000
2027	1	MARTIN	BP1-R019	HFBD	Replacement	SR1510	LANIER SWAMP	570048	$862,000
2027	1	HERTFORD	BP1-R015	HFBD	Replacement	SR1112	AHOSKIE CREEK	450060	$1,214,000
2027	1	GATES	BP1-R016	HFBD	Replacement	SR1116	COLE CREEK	360007	$2,100,000
2027	1	CHOWAN	BR-0183	HFBSW	Replacement	US17BUS	PEMBROKE CREEK	200002	$7,400,000
2027	1	TYRRELL	HB-0001A	O	Replacement	US64	ALLIGATOR RIVER	880007	$26,500,000
2027	2	BEAUFORT	BP2-R033	HFBD	Replacement	SR1126	MORRIS RUN	060073	$80,000
2027	2	PITT	BP2-C010	HFBD	Replacement	OFF SR1116	UNNAMED BRANCH	Non-NBIS Pipe	$300,000
2027	2	PITT	BP2-C017	HFBD	Replacement	OFF SR1507	UNNAMED BRANCH	Non-NBIS Pipe	$300,000
2027	2	LENOIR	BP2-C008	HFBD	Replacement	OFF SR1588	UNNAMED BRANCH	Non-NBIS Pipe	$350,000
2027	2	CRAVEN	BP2-R025	HFBD	Replacement	SR1224	ROLLOVER CREEK	240047	$1,230,000
2027	2	CRAVEN	BP2-R024	HFBD	Replacement	SR1213	WILSON CREEK	240160	$1,730,000
2027	2	CARTERET	BP2-R030	HFBD	Replacement	SR1331	GILLIKIN CREEK	150017	$1,380,000
2027	2	JONES	BP2-C020	HFBD	Replacement	OFF SR1157	UNNAMED BRANCH	Non-NBIS Pipe	$250,000
2027	3	ONSLOW	17BP.3.R.63	HFBD	Replacement	SR1310	JENKINS SWAMP	660144	$560,000
2027	3	BRUNSWICK	BP3-R004	HFBD	Replacement	SR1437	STURGEON CREEK	090181	$2,650,000
2027	3	ONSLOW	BR-0194	HFBSW	Replacement	US17	CHANEY CREEK	660029	$5,600,000
2027	3	ONSLOW	BR-0193	HFBSW	Replacement	NC24W	NORTHEAST CREEK	660007	$10,350,000
2027	3	ONSLOW	BP3-R010	HFBD	Replacement	SR1109 SR1509	HARRIS CREEK QUEENS CREEK	660071 660077	$1,740,000
2027	3	PENDER	BP3-R011	HFBD	Replacement	SR1306	SILLS CREEK	700068	$2,190,000
2027	3	ONSLOW	BP3-R013	HFBD	Replacement	SR1333	WHITE OAK RIVER	660010	$3,225,000
2027	4	HALIFAX	BP4-R033	HFBD	Replacement	SR1210	MARTIN SWAMP	410021	$800,000
2027	4	EDGECOMBE	BP4-R034	HFBD	Replacement	US258	BR. OF DEEP CREEK	320094	$900,000
2027	4	NASH	BP4-R036	HFBD	Replacement	SR1417	TRIB OF PIG BASKET CR.	630155	$900,000
2027	4	WILSON	BP4-R029	HFBD	Replacement	SR1428	TRIB. OF WHITE SWAMP	970148	$1,300,000
2027	4	HALIFAX	BP4-R024	HFBD	Replacement	SR1338	LITTLE FISHING CREEK	410109	$2,190,000
2027	4	NASH	BP4-R035	HFBD	Replacement	SR1544	STONEY CREEK	630116	$2,300,000
2027	4	HALIFAX	BP4-R031	HFBD	Replacement	SR1627 SR1627	QUANKEY CREEK QUANKEY CREEK OVERFLOW	410152 410154	$2,500,000
2027	4	JOHNSTON	HB-0042	HFBSW	Replacement	US301,NC96	BLACK CREEK	500056	$5,650,000
2027	4	NASH	HB-0038	BGOFF	Replacement	SR1745	TAR RIVER	630110	$6,580,000
2027	4	NASH	BR-0192	HFBSW	Replacement	NC43BUS,NC48	TAR RIVER	630038	$8,610,000
2027	4	HALIFAX	BR-0021	HFBSW	Replacement	NC48	ROANOKE RIVER	410051	$38,237,324
2027	5	DURHAM	BP5-C002	HFBD	Replacement	SR1103	CROOKED CREEK	310267	NA
2027	5	WAKE	BP5-R105	HFBD	Replacement	SR2720	UT TO SWIFT CREEK	910496	$1,750,000
2027	5	WAKE	BP5-R090	HFBD	Replacement	SR1911	NEW LIGHT CREEK	910114	$2,000,000
2027	5	WAKE	BP5-R091	HFBD	Replacement	SR1912	NEW LIGHT CREEK	910119	$2,010,000
2027	5	WAKE	B-5681	HFBSW	Replacement	SR2713	US70, NC50	910258	$3,500,000
2027	5	FRANKLIN	BR-0169	HFBSW	Replacement	NC561	SANDY CREEK	340024	$4,600,000
2027	6	CUMBERLAND	BP6-R010	HFBD	Replacement	SR1850	BUCK CREEK	250029	$900,000
2027	6	ROBESON	BP6-R012	HFBD	Replacement	SR2204	JACOB SWAMP WATERSHED	770444	$1,240,000
2027	7	GUILFORD	BP7-C002	HFBD	Replacement	SR3098	UNNAMED BRANCH	Non-NBIS Pipe	$460,000
2027	7	ROCKINGHAM	BP7-R021	HFBD	Replacement	SR1964 (CLOSED)	DAN RIVER	780233	$810,000
2027	7	ORANGE	BP7-R009	HFBD	Replacement	SR1336	ENO RIVER	670011	$1,200,000
2027	7	ROCKINGHAM	17BP.7.R.141	HFBD	Replacement	SR2670	LITTLE TROUBLESOME CREEK	780280	$1,900,000
2027	7	GUILFORD	BR-0186	HFBSW	Replacement	BENJAMIN PARKWAY	W WENDOVER AVE/US70/220	400469	$9,250,000

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2027	7	GUILFORD	BR-0081	HFBSW	Replacement	SR2526N.RAMP PHILLIPS AVENUE	US29 US29,SR2526N.	400283 400342	$15,000,000
2027	7	GUILFORD	BR-0078	HFBSW	Replacement	US70,US220 US70	US220S, SR1452 SOUTHERN RAILROAD	400292 400467	$36,600,000
2027	7	ROCKINGHAM	HB-0035	BGOFF	Replacement	SR1535	MATRIMONY CREEK	780177	$5,210,000
2027	7	GUILFORD	BR-0077	HFBSW	Replacement	SR2770	US70	400131	$23,627,000
2027	7	ORANGE	B-6037	NHPB	Replacement	NC86	SOUTHERN RAILWAY	670049	$14,080,000
2027	7	GUILFORD	BR-0079	BGOFF	Replacement	TUSCALOOSA STREET	US29, US70, US220	400302	$10,100,000
2027	8	MOORE	BP8-R031	HFBD	Replacement	SR1401	MILL CREEK	620144	$1,240,000
2027	8	RANDOLPH	BP8-R030	HFBD	Replacement	SR2613	MILL CREEK	750354	$1,390,000
2027	8	RANDOLPH	BP8-R032	HFBD	Replacement	SR2403	SANDY CREEK	750126	$1,240,000
2027	8	RANDOLPH	BP8-R029	HFBD	Replacement	SR1402	BRIER CREEK	750294	$820,000
2027	8	MONTGOMERY	BP8-R033	HFBD	Replacement	SR1306	BARNES CREEK	610145	$1,240,000
2027	9	DAVIE	BP9-C001	HFBD	Replacement	OFF SR1316	UNNAMED BRANCH	Non-NBIS Pipe	$600,000
2027	9	DAVIE	BP9-C002	HFBD	Replacement	OFF SR1436	UNNAMED BRANCH	Non-NBIS Pipe	$650,000
2027	9	DAVIE	BP9-R008	HFBD	Replacement	SR1313	UT TO BEAR CREEK	290065	$1,555,000
2027	9	FORSYTH	BP9-R002	HFBD	Replacement	SR1525	MILL CREEK	330261	$3,360,000
2027	9	FORSYTH	BR-0018	HFBSW	Replacement	NC8	US52	330048	$20,720,000
2027	9	FORSYTH	B-5950	NHPB	Replacement	NC67 NBL	SALEM CREEK	330007	$12,400,000
2027	10	UNION	BP10-R023	HFBD	Replacement	SR1714	WATER BRANCH	890048	$819,700
2027	10	ANSON	BP10-R057	HFBD	Replacement	SR1122	N. FORK JONES CREEK	030273	$850,000
2027	10	STANLY	BP10-R021	HFBD	Replacement	SR1954	LITTLE CREEK	830095	$921,400
2027	10	CABARRUS	BP10-R034	HFBD	Replacement	SR2416	BR.OF DUTCH BUFFALO CRK.	120073	$2,280,000
2027	10	UNION	BP10-R017	HFBD	Replacement	SR1301	TWELVEMILE CREEK	890224	$3,936,300
2027	10	ANSON	B-6048	BGOFF	Replacement	SR1812	JONES CREEK	030039	$4,453,000
2027	11	ASHE	BP11-R036	HFBD	Replacement	SR1166	EAST FORK PINE SWAMP CRK	040006	$650,000
2027	11	ASHE	BP11-R037	HFBD	Replacement	SR1317	RICH HILL CREEK	040262	$650,000
2027	11	WILKES	BP11-R039	HFBD	Replacement	SR2035	BRANCH ELKIN RIVER	960236	$700,000
2027	11	ALLEGHANY	BP11-R031	HFBD	Replacement	SR1403	UT TO NEW RIVER	020024	$750,000
2027	11	ASHE	BP11-R023	HFBD	Replacement	SR1192	OBIDS CREEK	040475	$900,000
2027	11	CALDWELL	BP11-R042	HFBD	Replacement	SR1328	ESTES MILL CREEK	130322	$950,000
2027	11	CALDWELL	BP11-R048	HFBD	Replacement	SR1571	KINGS CREEK	130342	$1,300,000
2027	11	YADKIN	BP11-R050	HFBD	Replacement	SR1320	DOBBIN CREEK	980042	$1,400,000
2027	11	CALDWELL	BP11-R025	HFBD	Replacement	SR1927	ABINGDON CREEK	130332	$1,475,000
2027	11	ASHE	BP11-R052	HFBD	Replacement	SR1120	NORTH FORK NEW RIVER	040439	$1,500,000
2027	11	WILKES	BP11-R049	HFBD	Replacement	SR2044	ELKIN CREEK	960239	$2,100,000
2027	11	ASHE	HB-0050	HFBSW / O	Replacement	SR1563	N.FORK NEW RIVER	040463	$5,410,000
2027	11	ASHE	HB-0046	HFBSW / O	Replacement	SR1105	SOUTH FORK NEW RIVER	040226	$2,530,000
2027	11	ASHE	HB-0044	HFBSW / O	Replacement	SR1644	NORTH FORK NEW RIVER	040093	$2,500,000
2027	11	AVERY	HB-0055	HFBSW / O	Replacement	SR1326	ELK RIVER	050091	$2,080,000
2027	11	ALLEGHANY	HB-0067	HFBSW / O	Replacement	SR1433	BRUSH CREEK	020082	$1,910,000
2027	11	CALDWELL	HB-0057	HFBSW / O	Replacement	SR1356	JOHNS RIVER	130185	$2,900,000
2027	11	ASHE	HB-0052	HFBSW / O	Replacement	SR1104	S.FORK NEW RIVER	040477	$2,625,000
2027	11	WILKES	HB-0065	HFBSW / O	Replacement	SR1170	STONY FORK CREEK	960691	$2,200,000
2027	11	ASHE	HB-0048	HFBSW / O	Replacement	SR1606	CRANBERRY CREEK	040343	$2,020,000
2027	11	ASHE	HB-0047	HFBSW / O	Replacement	SR1528	HELTON CREEK	040304	$1,830,000
2027	11	WILKES	HB-0063	HFBSW / O	Replacement	SR1559	MID. FORK REDDIES RIVER	960341	$1,690,000
2027	11	ASHE	HB-0054	HFBSW / O	Replacement	SR1222	SOUTH FORK NEW RIVER	040509	$3,880,000
2027	11	ASHE	HB-0045	HFBSW / O	Replacement	SR1609	CRANBERRY CREEK	040183	$1,910,000

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2027	11	CALDWELL	HB-0061	HFBSW / O	Replacement	SR1574	JONES CREEK	130349	$1,680,000
2027	11	WILKES	HB-0064	HFBSW / O	Replacement	SR1567	WINGLER CREEK	960655	$1,570,000
2027	11	ASHE	HB-0053	HFBSW / O	Replacement	SR1126	NORTH FORK NEW RIVER	040480	$2,020,000
2027	11	CALDWELL	HB-0059	HFBSW / O	Replacement	SR1356	JOHNS RIVER	130275	$2,360,000
2027	11	ASHE	HB-0049	HFBSW / O	Replacement	SR1602	SOUTH FORK NEW RIVER	040351	$2,490,000
2027	11	CALDWELL	HB-0060	HFBSW / O	Replacement	SR1356	JOHNS RIVER	130317	$2,730,000
2027	11	WILKES	HB-0066	HFBSW / O	Replacement	SR1355	S.FORK REDDIES RIVER	960340	$2,290,000
2027	11	CALDWELL	HB-0058	HFBSW / O	Replacement	SR1356	JOHNS RIVER	130186	$2,520,000
2027	11	WATAUGA	HB-0062	HFBSW / O	Replacement	SR1594	WATAUGA RIVER	940319	$2,560,000
2027	11	CALDWELL	HB-0056	HFBSW / O	Replacement	SR1514	YADKIN RIVER	130130	$2,150,000
2027	11	WILKES	HB-0020	HFBSW	Replacement	SR1185	YADKIN RIVER	960730	$14,840,000
2027	11	YADKIN	BR-0177	HFBSW	Replacement	SR1605	YADKIN RIVER	980186	$22,000,000
2027	11	WATAUGA	BP11-R032	HFBD	Replacement	SR1339	MEAT CAMP CREEK	940187	$250,000
2027	12	ALEXANDER	BP12-C001	HFBD	Replacement	SR1419	ROCKY FACE BRANCH	010304	$1,030,000
2027	12	CATAWBA	BP12-C002	HFBD	Replacement	SR1196	LONGVIEW CREEK	170298	$1,070,000
2027	12	CLEVELAND	BP12-R034	HFBD	Replacement	SR1337	UT TO FIRST BROAD RIVER	220012	$2,050,000
2027	12	CATAWBA	BP12-R005	HFBD	Replacement	SR1544	HERMAN CREEK	170277	$3,155,000
2027	12	IREDELL	BP12-R012	HFBD	Replacement	SR1892	ROCKY CREEK	480263	$3,529,200
2027	12	CATAWBA	BR-0182	HFBSW	Replacement	NC150	SEABOARD COASTLINE RR	170099	$3,780,000
2027	12	LINCOLN	BP12-R010	HFBD	Replacement	SR1360	ANDERSON CREEK	540014	$3,930,000
2027	12	IREDELL	BR-0023	HFBSW	Replacement	SR1005	I40	480090	$4,800,000
2027	12	CLEVELAND	B-5531	HFBSW	Replacement	NC150	BUFFALO CREEK	220076	$10,100,000
2027	12	GASTON	B-5926	HFBSW	Replacement	NC273	DUKE POWER FEEDER	350022	$12,400,000
2027	12	LINCOLN	BR-0087	HFBSW	Replacement	NC150	S.FORK CATAWBA RIVER	540035	$11,490,000
2027	13	YANCEY	BP13-R044	HFBD	Replacement	SR1158	COLBERT CREEK	990156	$1,550,000
2027	13	MADISON	BP13-C007	HFBD	Replacement	SR1501	WOLF LAUREL BRANCH	560546	NA
2027	13	MCDOWELL	BP13-T031	HFBD	Replacement	SR1409	MILL CREEK	580141	NA
2027	13	YANCEY	BP13-T032	HFBD	Replacement	SR1153	AYLES CREEK	990062	NA
2027	13	YANCEY	BP13-T033	HFBD	Replacement	SR1333	PIGPEN CREEK	990192	NA
2027	13	YANCEY	BP13-T034	HFBD	Replacement	SR1401	BALD MTN CREEK	990202	NA
2027	13	BURKE	BP13-R018	HFBD	Replacement	SR1962	UT TO DOUBLE BRANCH	110316	$855,000
2027	13	MADISON	BP13-C005	HFBD	Replacement	NC212 #N/A	MILL CREEK #N/A	560123 569999	$1,110,000
2027	13	MITCHELL	BP13-R036	HFBD	Replacement	SR1325	BEANS CREEK	600156	$1,250,000
2027	13	MADISON	BP13-C003	HFBD	Replacement	SR1501	WOLF LAUREL BRANCH CREEK	560544	$1,350,000
2027	13	MADISON	BP13-C004	HFBD	Replacement	SR1501	WOLF LAUREL CREEK	560545	$1,350,000
2027	13	MCDOWELL	BP13-R025	HFBD	Replacement	SR1560	STILLHOUSE BRANCH	580122	$1,475,500
2027	13	BUNCOMBE	BP13-R003	HFBD	Replacement	SR2713(CLOSED)	SWANNANOA RIVER	100785	$1,975,000
2027	13	MITCHELL	BP13-R027	HFBD	Replacement	SR1140	BEAVER CREEK	600063	$2,050,000
2027	13	MADISON	BP13-R009	HFBD	Replacement	SR1355	GABRIEL CREEK	560184	$2,075,000
2027	13	RUTHERFORD	B-5876	HFBSW	Replacement	US74 BYP. EBL US74 BYP. WBL	SECOND BROAD RIVER SECOND BROAD RIVER	800083 800084	$15,040,000
2027	13	MCDOWELL	BR-0171	HFBSW	Replacement	US70	CATAWBA RIVER OVER FLOW	580096	$10,700,000
2027	14	HAYWOOD	BR-0022	HFBSW	Replacement	US19,23,74 SBL	NC209 CONNECTOR	430122	$11,034,000
2027	14	HAYWOOD	BR-0154	HFBSW	Replacement	NC209	COVE CREEK	430128	$1,760,000
2027	14	CLAY	BP14-R010	HFBD	Replacement	SR1171	THUMPING CREEK	210079	$1,775,000
2027	14	CHEROKEE	B-4069	BGOFF	Replacement	SR1326	HANGING DOG CREEK	190159	$2,095,000
2027	14	SWAIN	BP14-R014	HFBD	Replacement	SR1185	ALARKA CREEK	860152	$3,075,000
2027	14	SWAIN	BP14-R009	HFBD	Replacement	SR1307	ALARKA CREEK	860058	$3,425,000
2027	14	MACON	BR-0030	HFBSW	Replacement	NC28	COWEE CREEK	550085	$4,960,000

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2027	14	JACKSON	BP14-R040	HFBD	Replacement	SR1300 SR1300 SR1300	SAVANNAH CREEK SAVANNAH CREEK SAVANNAH CREEK	490068 490345 490346	$5,100,000
2027	14	MACON	BR-0028	HFBSW	Replacement	US64	NANTAHALA RIVER	550023	$9,010,000
2027	14	MACON	BR-0088	HFBSW	Replacement	US64	CULLASAJA RIVER	550104	$18,000,000
2027	14	GRAHAM	BR-0076	HFBSW	Replacement	NC28	LITTLE TENNESSEE RIVER	370009	$21,650,000
2027	14	MACON	HB-0037	BGOFF	Replacement	SR1679	CULLASAJA RIVER	550056	$1,100,000
2027	14	HENDERSON	BR-0083	HFBSW	Replacement	US64 US64	FRENCH BROAD RVR.OVERFLO FRENCH BROAD RIVER	440057 440115	$22,034,020
2028	1	BERTIE	BP1-R024	HFBD	Replacement	SR1246	EASON SWAMP	070018	$775,000
2028	1	BERTIE	BP1-R025	HFBD	Replacement	SR1246	EASON SWAMP	070065	$775,000
2028	1	CAMDEN	BP1-R001	HFBD	Replacement	SR1235	JOYCE CREEK	140019	$1,300,000
2028	1	MARTIN	BP1-R020	HFBD	Replacement	SR1505	BR. OF PETER SWAMP	570194	$1,680,000
2028	1	CURRITUCK	BP1-R032	HFBSW	Replacement	NC615	CREEK OFF BACK BAY	260007	$14,800,000
2028	2	PITT	BP2-C009	HFBD	Replacement	OFF SR1588	BRIERY SWAMP	Non-NBIS Pipe	$350,000
2028	2	PITT	BP2-C018	HFBD	Replacement	OFF SR1402	UNNAMED BRANCH	Non-NBIS Pipe	$350,000
2028	2	GREENE	BP2-C019	HFBD	Replacement	OFF SR1101	UNNAMED BRANCH	Non-NBIS Pipe	$500,000
2028	2	PITT	BP2-R032	HFBD	Replacement	SR1404	BRANCH OF CONETOE CREEK	730198	$1,330,000
2028	2	PAMLICO	BP2-R023	HFBD	Replacement	SR1204	SOUTH PRONG BAY RIVER	680067	$1,380,000
2028	2	BEAUFORT	BP2-R028	HFBD	Replacement	SR1932	DURHAM CREEK	060057	$1,380,000
2028	2	LENOIR	B-4566	NHPB	Replacement	NC903	NEUSE RIVER	530045	$7,391,000
2028	2	LENOIR	BP2-C007	HFBD	Replacement	OFF SR1300	UNNAMED BRANCH	Non-NBIS Pipe	$250,000
2028	3	DUPLIN	BR-0167	HFBSW	Replacement	NC241	LIMESTONE CREEK	300027	$1,200,000
2028	3	DUPLIN	BP3-R007	HFBD	Replacement	SR1704	PANTHER CREEK	300144	$2,315,000
2028	3	BRUNSWICK	17BP.3.R.62	HFBD	Replacement	NC906	SARAH HOLE	090023	$2,200,000
2028	3	PENDER	B-5653	HFBSW	Replacement	NC133	TURKEY CREEK	700014	$3,200,000
2028	3	BRUNSWICK	B-5627	HFBSW	Replacement	NC87	ORTON CREEK	090011	$3,330,000
2028	3	BRUNSWICK	BP3-R012	HFBD	Replacement	SR1472	STURGEON CREEK	090208	$5,000,000
2028	3	BRUNSWICK	BR-0008	HFBSW	Replacement	US17	US76	090007	$9,375,000
2028	4	HALIFAX	BP4-R032	HFBD	Replacement	SR1615	TRIB.OF MARSH SWAMP	410019	$800,000
2028	4	NASH	BP4-R038	HFBD	Replacement	SR1909	TRIB.OF LITTLE SAPONY	630243	$800,000
2028	4	WAYNE	BP4-R026	HFBD	Replacement	SR1324	BUCK SWAMP	950210	$1,190,000
2028	4	WILSON	BP4-R030	HFBD	Replacement	NC58	BRANCH OF TOISNOT SWAMP	970038	$2,000,000
2028	4	WAYNE	BP4-R037	HFBD	Replacement	SR1008	NEUSE RIVER	950072	$4,200,000
2028	4	EDGECOMBE	B-4933	NHPB	Replacement	NC33 NC33	TAR RIVER OVERFLOW TAR RIVER	320049 320080	$16,780,000
2028	5	GRANVILLE	BP5-R115	HFBD	Replacement	CLOSED (SR1443)	JOHNHKERR RESERVOIR	380144	$8,325,000
2028	5	WAKE	BR-0198	HFBSW	Replacement	SR2224	WAKE CROSSROADS LAKE	910152	$2,870,000
2028	6	HARNETT	BP6-R019	HFBD	Replacement	SR2045	LOWER LITTLE RIVER	420074	$2,440,000
2028	6	COLUMBUS	BP6-R013	HFBD	Replacement	SR1158	BEAVER DAM SWAMP	230324	$2,660,000
2028	6	HARNETT	HB-0008	BGOFF	Replacement	SR1214	UPPER LITTLE RIVER	420034	$3,130,000
2028	7	ORANGE	BR-0247	HFBSW	Replacement	US70BUS,NC86	CATES CREEK	670029	$400,000
2028	7	ROCKINGHAM	BP7-R014	HFBD	Replacement	SR2308	HOGANS CREEK	780197	$820,000
2028	7	ROCKINGHAM	BP7-R010	HFBD	Replacement	SR2371	BRANCH	780024	$875,000
2028	7	GUILFORD	BP7-R012	HFBD	Replacement	SR2347	HAW RIVER	400124	$1,020,000
2028	7	ROCKINGHAM	BP7-R011	HFBD	Replacement	SR2582	HOGAN'S CREEK	780247	$1,077,800
2028	7	ORANGE	BP7-R013	HFBD	Replacement	SR1940	PRITCHARD MILL CREEK	670090	$2,220,000
2028	7	ALAMANCE	B-6052	HFBSW	Replacement	SR1928	SOUTHERN R.R.	000068	$3,000,000
2028	7	GUILFORD	B-5718	NHPB	Replacement	PATTON AVE	I40, I85 BUS, US29/70/22	400329	$3,568,000
2028	7	CASWELL	BR-0165	HFBSW	Replacement	NC119	REEDY FORK CREEK	160013	$6,160,000

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2028	7	ROCKINGHAM	B-5729	HFBSW	Replacement	NC700	DAN RIVER	780134	$13,290,000
2028	7	ROCKINGHAM	B-6038	NHPB	Replacement	NC14,NC87	NORFOLK SOUTHERN RR	780155	$8,740,000
2028	8	RANDOLPH	BP8-R003	HFBD	Replacement	SR1002	BRANCH OF LITTLE CREEK	750384	$1,225,000
2028	9	DAVIE	B-5768	HFBSW	Replacement	NC801	CEDAR CREEK	290038	$865,000
2028	9	FORSYTH	BP9-R010	HFBD	Replacement	SR2662	SALEM CREEK	330210	$1,500,000
2028	9	STOKES	BP9-R005	HFBD	Replacement	SR1432	DAN RIVER	840076	$2,750,000
2028	9	FORSYTH	B-5148	HFBSW	Replacement	SR1001	NC67	330276	$4,375,000
2028	9	DAVIDSON	BR-0016	HFBSW	Replacement	US29N,US70N.BUS	US29,US70S.BUS.RAMP	280150	$5,700,000
2028	9	FORSYTH	BP9-R011	HFBD	Replacement	SR1301	US421	330110	$5,985,000
2028	9	DAVIDSON	B-5787	HFBSW	Replacement	NC49	NC109	280029	$6,600,000
2028	9	DAVIDSON	B-5785	HFBSW	Replacement	I85N.BUS,US29,U70 I85SBUS,US29,US70	LEONARD CREEK LEONARD CREEK	280121 280122	$12,000,000
2028	9	FORSYTH	HB-0031	BGOFF	Replacement	3RD STREET 4TH STREET FIFTH STREET	US52, US311 & NC8 US52, US311 & NC8 US52, US311 & NC8	330185 330191 330203	$10,500,000
2028	9	FORSYTH	HB-0036	BGOFF	Replacement	SIXTEENTH STREET	NORFOLK&WESTERN RAILROAD	330390	$4,620,000
2028	9	FORSYTH	BR-0184	HFBSW	Replacement	SR2747	US52,I285	330060	$18,500,000
2028	9	FORSYTH	B-5775	HFBSW	Replacement	ROBINHOOD ROAD	NC67	330275	$17,650,000
2028	10	MECKLENBURG	BP10-R032	HFBD	Replacement	SR2138	TORRENCE CREEK	590109	NA
2028	10	UNION	BP10-R002	HFBD	Replacement	SR1147	TWELVE MILE CREEK	890198	$707,200
2028	10	CABARRUS	BR-0244	HFBSW	Replacement	SR1625	IRISH BUFFALO CREEK	120033	$1,500,000
2028	10	UNION	BP10-R005	HFBD	Replacement	SR1126	UT TO WAXHAW CREEK	890376	$1,770,000
2028	10	UNION	B-5376	BGOFF	Replacement	SR1681	STEWART'S CREEK	890021	$3,255,000
2028	10	CABARRUS	BP10-R015	HFBD	Replacement	SR2635	COLD WATER CREEK	120129	$3,979,071
2028	10	ANSON	BR-0163	HFBSW	Replacement	NC742	LANES CREEK	030084	$4,892,800
2028	10	UNION	B-5949	NHPB	Replacement	NC200	STEWARTS CREEK	890053	$5,520,000
2028	10	CABARRUS	BR-0181	HFBSW	Replacement	SR2180	LAKE FISHER	120062	$6,750,000
2028	10	MECKLENBURG	B-5983	HFBSW	Replacement	NC160	SOUTHERN RAILROAD	590054	$10,010,000
2028	11	ASHE	BP11-R038	HFBD	Replacement	SR1592	DOG CREEK	040152	$850,000
2028	11	ASHE	BP11-R044	HFBD	Replacement	SR1379	LITTLE HELTON CREEK	040341	$900,000
2028	11	WATAUGA	BP11-R033	HFBD	Replacement	SR1324	COBB CREEK	940041	$950,000
2028	11	SURRY	BR-0197	HFBSW	Replacement	US52 SBL	SOU. RR,HEATHERLY CREEK	850100	$5,150,000
2028	11	ASHE	BR-0178	HFBSW	Replacement	SR1340	NORTH FORK NEW RIVER	040056	$12,000,000
2028	11	WILKES	HB-0069	O	Replacement	US421B	REDDIES RIVER	960012	$26,100,000
2028	12	CLEVELAND	BP12-R043	HFBD	Replacement	SR1913	SUCK CREEK	220271	$1,140,000
2028	12	IREDELL	BP12-R030	HFBD	Replacement	SR1143	CODDLE CREEK	480034	$1,524,500
2028	12	ALEXANDER	BR-0061	HFBSW	Replacement	NC127	DUCK CREEK	010005	$1,650,000
2028	12	IREDELL	BP12-R031	HFBD	Replacement	SR1153	CODDLE CREEK	480031	$1,871,800
2028	12	CLEVELAND	BP12-R032	HFBD	Replacement	SR1001	POTTS CREEK	220040	$2,053,500
2028	12	IREDELL	BP12-R027	HFBD	Replacement	SR1930	FOURTH CREEK	480179	$2,106,300
2028	12	ALEXANDER	B-5954	HFBSW	Replacement	NC127	DUCK CREEK	010001	$5,090,000
2028	12	IREDELL	BR-0084	HFBSW	Replacement	SR2342	I-77	480126	$6,160,000
2028	12	CATAWBA	BR-0071	HFBSW	Replacement	NC127	US70,US321 BUS	170063	$6,270,000
2028	12	LINCOLN	B-6042	HFBSW	Replacement	NC150	S.A.L. RAILROAD	540026	$9,400,000
2028	12	CLEVELAND	B-5855	HFBSW	Replacement	US74 BUS	SEABOARD COAST LINE RR	220009	$10,800,000
2028	12	IREDELL	BR-0024	HFBSW	Replacement	I40 WBL	THIRD CREEK	480102	$32,200,000
2028	12	CATAWBA	BR-0143	HFBSW	Replacement	US321 BUS	SMYRE CREEK	170081	$10,340,000
2028	12	IREDELL	HB-0032	BGOFF	Replacement	SR1004	CATAWBA RIVER	480081	$23,900,000
2028	13	BUNCOMBE	BP13-C001	HFBD	Replacement	SR2002	BULL CREEK	100306	$1,350,000
2028	13	MITCHELL	BP13-R028	HFBD	Replacement	SR1349	PIGEONROOST CREEK	600080	$1,500,000

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2028	13	MITCHELL	BP13-R030	HFBD	Replacement	SR1349	PIGEON ROOST CREEK	600081	$1,500,000
2028	13	MITCHELL	BP13-R029	HFBD	Replacement	SR1349	PIGEONROOST CREEK	600082	$1,550,000
2028	13	BUNCOMBE	BP13-R008	HFBD	Replacement	SR2791	LAUREL CREEK	100515	$1,600,000
2028	13	MADISON	BP13-R041	HFBD	Replacement	US74 BYP. EBL	SECOND BROAD RIVER	800083	$1,600,000
2028	13	BUNCOMBE	BP13-R031	HFBD	Replacement	SR2791	LAUREL CREEK	100514	$1,650,000
2028	13	BUNCOMBE	BP13-R011	HFBD	Replacement	SR3116	ROBINSON CREEK	100173	$2,100,000
2028	13	BUNCOMBE	BP13-R049	HFBD	Replacement	SR1003	IVY CREEK	100154	$2,300,000
2028	13	MITCHELL	BP13-R034	HFBD	Replacement	SR1211	CANE CREEK	600044	$2,400,000
2028	13	BURKE	BR-0180	HFBSW	Replacement	SR1002	HENRY FORK CREEK	110346	$7,000,000
2028	13	RUTHERFORD	B-5871	BGOFF	Replacement	SR1306	BROAD RIVER	800628	$25,400,000
2028	13	YANCEY	BR-0162	HFBSW	Replacement	US19W	BALD CREEK	990012	$1,720,000
2028	14	GRAHAM	BP14-R003	HFBD	Replacement	SR1105	MILL CREEK	370119	$80,000
2028	14	MACON	B-6026	BGOFF	Replacement	SR1500	WATAUGA CREEK	550214	$500,000
2028	14	HENDERSON	BP14-R019	HFBD	Replacement	SR1109	CABIN CREEK	440208	$1,360,000
2028	14	POLK	BP14-R013	HFBD	Replacement	SR1501	UT TO WOLFE CREEK	740022	$1,500,000
2028	14	JACKSON	BP14-R001	HFBD	Replacement	SR1447	FISHER CREEK	490099	$1,710,000
2028	14	TRANSYLVANIA	BP14-R022	HFBD	Replacement	SR1559	WALKER CREEK	870011	$1,714,000
2028	14	JACKSON	B-6036	BGOFF	Replacement	SR1737	JOHNS CREEK	490081	$1,910,000
2028	14	HAYWOOD	BP14-R005	HFBD	Replacement	SR1148	ALLEN CREEK	430386	$2,065,000
2028	14	MACON	BR-0055	HFBSW	Replacement	SR1310	NANTAHALA RIVER	550230	$2,650,000
2028	14	MACON	BR-0054	HFBSW	Replacement	SR1310	NANTAHALA RIVER	550229	$3,000,000
2028	14	TRANSYLVANIA	HB-0026	BGOFF	Replacement	SR1533	FRENCH BROAD RIVER	870030	$4,400,000
2029	1	WASHINGTON	BP1-R026	HFBD	Replacement	SR1114	CONABY CREEK	930017	$960,000
2029	1	CHOWAN	BR-0245	HFBSW	Replacement	US17BUS	BRANCH	200017	$975,000
2029	1	NORTHAMPTON	BP1-R028	HFBD	Replacement	SR1356	BR. OF KIRBY'S CREEK	650044	$1,010,000
2029	1	PASQUOTANK	BP1-R029	HFBD	Replacement	SR1140	BR. OF LITTLE RIVER	690031	$1,010,000
2029	1	MARTIN	BP1-R030	HFBD	Replacement	SR1113	CREEK	570066	$1,010,000
2029	2	CARTERET	BP2-R026	HFBD	Replacement	SR1176	CALICO CREEK	150034	$210,000
2029	2	BEAUFORT	BP2-C023	HFBD	Replacement	OFF SR1516	UNNAMED BRANCH	Non-NBIS Pipe	$250,000
2029	2	PITT	BP2-R004	HFBD	Replacement	SR1756	COW SWAMP	730006	$2,009,000
2029	2	PAMLICO	B-5616	HFBSW	Replacement	NC55	ALLIGATOR CREEK	680037	$2,630,000
2029	2	PAMLICO	BR-0172	HFBSW	Replacement	NC55	TRENT CREEK	680043	$4,475,000
2029	2	PAMLICO	B-5613	HFBSW	Replacement	NC55	SO. PRONG BAY RIVER	680036	$5,650,000
2029	2	PITT	B-5612	NHPB	Replacement	NC222	TAR RIVER	730024	$15,200,000
2029	2	BEAUFORT	BR-0006	HFBSW	Replacement	NC306 FERRY NC306 FERRY	PAMLICO SOUND PAMLICO RIVER	060321 060322	$20,600,000
2029	3	DUPLIN	BP3-R014	HFBD	Replacement	SR1307	NAHUNGA SWAMP	300107	$1,615,000
2029	3	DUPLIN	BP3-R005	HFBD	Replacement	SR1301	GROVE CREEK	300230	$2,890,000
2029	3	SAMPSON	B-4636	NHPB	Replacement	NC24	SIX RUNS CREEK	810056	$10,290,000
2029	4	WILSON	BR-0150	HFBSW	Replacement	US117	GREAT SWAMP	970023	$2,750,000
2029	4	JOHNSTON	B-6044	NHPB	Replacement	I95N I95 SBL I95N I95 SBL	BLACK CREEK BLACK CREEK NEUSE RIVER NEUSE RIVER	500082 500085 500100 500101	$54,010,000
2029	4	JOHNSTON	B-6050	NHPB	Replacement	SR2137 SR2130 SR2339	I95 I95 I95	500109 500110 500112	$99,800,000
2029	5	WAKE	B-5680	HFBSW	Replacement	SR1633	CSX R.R.	910449	$1,150,000
2029	5	VANCE	B-5685	HFBSW	Replacement	SR1308	JOHN H. KERR RESERVOIR	900089	$3,400,000
2029	5	GRANVILLE	BP5-R102	HFBD	Replacement	SR1133	TAR RIVER	380074	$5,600,000

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2029	5	WAKE	B-5675	HFBSW	Replacement	PULLEN ROAD	SR1012	910533	$5,800,000
2029	5	WAKE	BP5-R041	HFBD	Replacement	SR1630	KIT CREEK	910061	$7,200,000
2029	5	WAKE	BR-0050	HFBSW	Replacement	US401S US401	ATLANTIC AVE. ATLANTIC AVE.	910172 910175	$7,575,000
2029	5	WAKE	B-5130	NHPB	Replacement	SR1321	LAKE JOHNSON	910318	$8,000,000
2029	5	WAKE	B-5683	HFBSW	Replacement	SR1371	YATES POND SPILLWAY	910302	$9,800,000
2029	5	DURHAM	B-5674	NHPB	Replacement	US15/US501NBL	SR1308	310080	$45,200,000
2029	5	WAKE	HB-0029	BGOFF	Replacement	SR1179	NORFOLK SOUTHERN RAILWAY	910497	$2,200,000
2029	5	WAKE	B-5986	NHPB	Replacement	NC231	CAROLINA COASTAL	910034	$6,756,000
2029	5	WAKE	B-5987	NHPB	Replacement	US401 N US401S	SOUTHERN RR, CREEK SOUTHERN RR, CREEK	910115 910117	$26,420,000
2029	7	GUILFORD	B-5356	NHPB	Replacement	I40,85,US29,70,220	SOUTH BUFFALO CREEK	400299	$11,880,000
2029	7	ORANGE	BP7-R017	HFBD	Replacement	SR1548	SOUTH FORK LITTLE RIVER	670114	$850,000
2029	7	ROCKINGHAM	BP7-R022	HFBD	Replacement	SR2039	DAN RIVER BACK WATER	780257	$1,020,000
2029	7	ALAMANCE	BP7-R016	HFBD	Replacement	SR1003	CANE CREEK	000113	$1,240,000
2029	7	GUILFORD	BP7-R020	HFBD	Replacement	SR2035	KINGS CREEK	400376	$1,677,800
2029	7	CASWELL	B-5734	HFBSW	Replacement	NC86	MOON CREEK	160060	$8,460,000
2029	7	ORANGE	BR-0091	HFBSW	Replacement	US70 NC54	ENO RIVER MORGAN CREEK	670032 670036	$11,000,000
2029	8	RANDOLPH	BP8-R005	HFBD	Replacement	SR1312	JACKSON CREEK	750043	$1,240,000
2029	8	LEE	B-5976	BGOFF	Replacement	SR1400 SR1400	NORFOLK SOUTHERN RR SOUTHERN RR	520069 520070	$12,220,000
2029	9	DAVIDSON	B-5773	HFBSW	Replacement	SR3346	WINSTON SALEM S.B. RR	280025	$3,250,000
2029	9	FORSYTH	BR-0075	BGOFF	Replacement	SR1109	I40	330135	$12,800,000
2029	9	FORSYTH	HB-0033	NHPB	Replacement	POLO ROAD	SR4000	330284	$6,600,000
2029	9	DAVIDSON	B-5779	NHPB	Replacement	I85NBUS,US29,US70	SR3346	280118	$12,260,000
2029	10	ANSON	BP10-R024	HFBD	Replacement	SR1714	WATER BRANCH	890048	$707,200
2029	10	MECKLENBURG	BP10-R007	HFBD	Replacement	SR2426	RAMAH CREEK	590096	$740,000
2029	10	STANLY	BP10-R037	HFBD	Replacement	SR1522	LITTLE MOUNTAIN CREEK	830012	$905,380
2029	10	UNION	BP10-R029	HFBD	Replacement	SR1328	EAST FORK TWELVE MILE CR	890313	$964,240
2029	10	UNION	BP10-R059	HFBD	Replacement	SR1929	BARKER'S BRANCH	890098	$964,240
2029	10	MECKLENBURG	B-5990	NHPB	Replacement	SR1138 WBL	SUGAR CREEK	590001	$4,348,000
2029	10	MECKLENBURG	B-5984	HFBSW	Replacement	NC49	SOUTHERN RAILROAD	590088	$13,100,000
2029	11	ALLEGHANY	BR-0001	HFBSW	Replacement	US21	LITTLE RIVER	020030	$8,200,000
2029	12	GASTON	BP12-R044	HFBD	Replacement	SR2040	FITES CREEK	350191	NA
2029	12	GASTON	BP12-R036	HFBD	Replacement	SR1108	CROWDERS CREEK	350063	$1,123,600
2029	12	IREDELL	BP12-R004	HFBD	Replacement	SR1006	BUFFALO SHOALS CREEK	480108	$1,432,400
2029	12	GASTON	BP12-R035	HFBD	Replacement	SR1607	SULPHUR BRANCH	350145	$1,513,200
2029	12	CATAWBA	BP12-R025	HFBD	Replacement	SR1712	UT TO LYLE CREEK	170007	$1,568,500
2029	12	GASTON	BP12-R037	HFBD	Replacement	SR1627	BEAVERDAM CREEK	350116	$1,617,500
2029	12	IREDELL	BP12-R026	HFBD	Replacement	SR1142	DYE CREEK	480037	$1,984,700
2029	12	IREDELL	BR-0025	NHPB	Replacement	SR1639	I40	480118	$4,300,000
2029	12	IREDELL	HB-0041	NHPB	Replacement	I-77 SBL	THIRD CREEK	480133	$11,000,000
2029	12	IREDELL	HB-0018	NHPB	Replacement	I40 EBL I-40 WBL	CATAWBA RIVER CATAWBA RIVER	480006 480007	$61,300,000
2029	13	MITCHELL	BP13-R046	HFBD	Replacement	SR1002	E.FORK BIG CRABTREE CR	600112	$1,525,000
2029	13	BUNCOMBE	BP13-R012	HFBD	Replacement	SR1389	NORTH TURKEY CREEK	100183	$1,550,000
2029	13	RUTHERFORD	BP13-R038	HFBD	Replacement	SR2102	BIG HORSE CREEK	800153	$1,550,000
2029	13	BUNCOMBE	BP13-C002	HFBD	Replacement	SR1389	UNNAMED BRANCH	Non-NBIS Pipe	$1,600,000
2029	13	RUTHERFORD	BP13-R035	HFBD	Replacement	SR1526	UT TO CATHEYS CREEK	800216	$1,600,000

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2029	13	RUTHERFORD	BP13-R045	HFBD	Replacement	SR1700	LITTLE FIRST BROAD RIVER	800199	$1,600,000
2029	13	RUTHERFORD	BP13-R037	HFBD	Replacement	SR1359	EAST BRANCH MOUNTAIN CRK	800380	$1,800,000
2029	13	BUNCOMBE	BP13-R047	HFBD	Replacement	SR2776	ROCKY CREEK	100105	$1,950,000
2029	13	BURKE	BR-0068	HFBSW	Replacement	NC126	CANOE CREEK	110103	$3,990,000
2029	13	BURKE	BR-0149	HFBSW	Replacement	NC181	IRISH CREEK	110063	$4,040,000
2029	13	MITCHELL	BR-0191	HFBSW	Replacement	SR1121	NORTH TOE RIVER	600068	$10,650,000
2029	13	MITCHELL	BR-0190	HFBSW	Replacement	SR1403	N.TOE RIVER,N&S RR.	600008	$13,200,000
2029	13	BUNCOMBE	B-4443	NHPB	Replacement	US19,23 NB US19,23 SB,FUTURE	SR1839 SR1839	100345 100346	$51,450,000
2029	14	HENDERSON	BP14-R018	HFBD	Replacement	SR1328	SWEET WATER BRANCH	440182	$1,070,000
2029	14	MACON	B-6030	BGOFF	Replacement	SR1351	MATLOCK CREEK	550220	$1,300,000
2029	14	HAYWOOD	BP14-R011	HFBD	Replacement	SR1302	JONATHANS CREEK	430256	$1,300,000
2029	14	JACKSON	BP14-R025	HFBD	Replacement	SR1756	GAGE CREEK	490294	$1,410,000
2029	14	TRANSYLVANIA	BP14-R012	HFBD	Replacement	SR1324	DOUBLE BRANCH	870142	$1,545,000
2029	14	HENDERSON	BP14-R029	HFBD	Replacement	SR1893	DEVILS FORK CREEK	440058	$2,175,000
2029	14	JACKSON	B-6031	BGOFF	Replacement	SR1300	SAVANNAH CREEK	490069	$2,310,000
2029	14	JACKSON	B-6033	BGOFF	Replacement	SR1445	SCOTT CREEK	490129	$2,700,000
2029	14	HAYWOOD	BP14-R030	HFBD	Replacement	SR1364	JONATHAN CREEK	430046	$3,060,000
2029	14	HAYWOOD	HB-0027	BGOFF	Replacement	SR1355	FINES CREEK	430206	$1,100,000
2029	14	POLK	HB-0025	BGOFF	Replacement	SR1004	BROAD RIVER	740087	$5,720,000
2029	14	HENDERSON	B-5922	HFBSW	Replacement	SR1545	SOUTHERN RAILROAD	440237	$6,460,000
2030	1	CHOWAN	BP1-R031	HFBD	Replacement	SR1305	INDIAN CREEK	200023	$1,008,500
2030	2	PITT	BR-0254	HFBSW	Replacement	US13	LITTLE CONTENTNEA CREEK	730016	NA
2030	2	LENOIR	BP2-C021	HFBD	Replacement	OFF SR1700	UNNAMED BRANCH	Non-NBIS Pipe	$250,000
2030	2	BEAUFORT	BP2-C015	HFBD	Replacement	OFF SR1456	UNNAMED BRANCH	Non-NBIS Pipe	$330,000
2030	2	PITT	17BP.2.R.102	HFBD	Replacement	SR1780	CHICOD CREEK	730017	$1,300,000
2030	2	JONES	BP2-R013	HFBD	Replacement	SR1153	TRENT RIVER	510031	$1,430,000
2030	2	BEAUFORT	BP2-R016	HFBD	Replacement	SR1159	CHICOD CREEK	060062	$1,430,000
2030	2	PITT	HB-0022	BGOFF	Replacement	ROCK SPRING ROAD	GREEN MILL RUN	730096	$2,503,000
2030	3	ONSLOW	BP3-R001	HFBD	Replacement	SR1534	KINGS CREEK	660143	$1,670,000
2030	3	BRUNSWICK	BP3-R015	HFBD	Replacement	SR1112	MERCERS MILL POND	090022	$2,070,000
2030	3	ONSLOW	B-5944	NHPB	Replacement	SR1509	QUEENS CREEK	660077	$32,900,000
2030	4	HALIFAX	BP4-R025	HFBD	Replacement	SR1003	BRANCH DEEP CREEK	410120	$790,000
2030	4	WILSON	BP4-R016	HFBD	Replacement	NC42	CONTENTNEA CREEK	970031	$7,190,000
2030	5	DURHAM	BR-0253	HFBSW	Replacement	I85NBL,US15N I85S,US15S	NEUSE RIVER/FALLS LAKE NEUSE RIVER/FALLS LAKE	310226 310227	$20,000,000
2030	5	VANCE	BR-0255	HFBSW	Replacement	US1N.BYP	CSX RAILROAD	900038	$10,000,000
2030	5	FRANKLIN	HB-0024	BGOFF	Replacement	US401	SANDY CREEK	340056	$3,940,000
2030	6	CUMBERLAND	HB-0010	BGOFF	Replacement	SR1850 SR1716	BUCK CREEK WADE CANAL	250029 250091	$1,420,000
2030	6	COLUMBUS	HB-0009	BGOFF	Replacement	SR1800	RICEFIELD BRANCH	230250	$1,870,000
2030	7	ROCKINGHAM	BP7-R024	HFBD	Replacement	SR1509	BUFFALO CREEK	780172	$710,000
2030	7	GUILFORD	BP7-R026	HFBD	Replacement	SR1372	PRONG REDDICKS CREEK	400403	$871,400
2030	7	ORANGE	BP7-R015	HFBD	Replacement	SR1005	MORGAN CREEK	670086	$1,730,000
2030	9	FORSYTH	BR-0256	HFBSW	Replacement	I40 BUS I40 BUS	BRUSHY FORK CREEK LOWERY STREET	330354 330355	$20,000,000
2030	10	STANLY	B-5811	BGOFF	Replacement	SR1434	BIG BEAR CREEK	830042	$615,000
2030	10	CABARRUS	BP10-C003	HFBD	Replacement	SR2113	UT TO COLD WATER CREEK	120050	$770,000
2030	10	UNION	BP10-R036	HFBD	Replacement	SR1627	WATSON CREEK	890031	$894,670
2030	10	MECKLENBURG	BP10-R039	HFBD	Replacement	SR2822	UT TO REEDY CREEK	590060	$1,690,000

Plan Year	Division	County	Project ID	Budget Group	Improvement Type	Facility Carried	Feature Intersected	Structure	Estimated Project Cost
2030	10	UNION	BP10-R053	HFBD	Replacement	SR1504	SOUTH FORK CROOKED CREEK	890270	$3,448,650
2030	11	SURRY	B-5832	BGOFF	Replacement	SR2080	ARARAT RIVER	850152	$4,250,000
2030	12	CATAWBA	BR-0258	HFBSW	Replacement	NC16 BUS	US70	170019	$10,000,000
2030	12	IREDELL	B-5843	BGOFF	Replacement	SR2402	I-L CREEK	480020	$742,000
2030	12	IREDELL	BP12-R003	HFBD	Replacement	SR1505	GOBLE CREEK	480464	$1,434,700
2030	12	GASTON	BP12-R021	HFBD	Replacement	SR1909	JOHNSTON CREEK	350198	$2,011,100
2030	12	CLEVELAND	BR-0072	HFBSW	Replacement	NC182	BUFFALO CREEK	220038	$6,400,000
2030	12	CLEVELAND	BP12-R047	HFBD	Replacement	SR2017	LITTLE PERSIMMON CREEK	220043	$6,600,000
2030	12	CATAWBA	B-5847	NHPB	Replacement	SR1709	I40	170173	$11,700,000
2030	12	CATAWBA	B-6041	NHPB	Replacement	I40 EBL I40 WBL	LYLE CREEK LYLE CREEK	170177 170178	$27,190,000
2030	12	CLEVELAND	B-5858	BGOFF	Replacement	SR1607	BUFFALO CREEK	220392	$3,445,000
2030	13	BURKE	BR-0259	HFBSW	Replacement	US70	SOUTHERN RR	110128	$10,000,000
2030	13	MCDOWELL	BR-0260	HFBSW	Replacement	NC226	US64	580026	$10,000,000
2030	13	MITCHELL	BP13-R042	HFBD	Replacement	SR1223 SR1931	GREENE CREEK HILLS CREEK	600113 800113	$1,450,000
2030	13	RUTHERFORD	BP13-R039	HFBD	Replacement	SR1778	UT TO W. FORK SANDY RUN	800106	$1,550,000
2030	13	RUTHERFORD	BP13-R040	HFBD	Replacement	SR1314	BUFFALO CREEK	800343	$1,800,000
2030	13	BURKE	BR-0130	NHPB	Replacement	I-40 EBL I-40 WBL	SILVER CREEK SILVER CREEK	110114 110120	$11,800,000
2030	14	HAYWOOD	BP14-R023	HFBD	Replacement	SR1856	DUTCH COVE CREEK	430375	$1,450,000
2030	14	MACON	BP14-R027	HFBD	Replacement	SR1618	EAST FORK OVERFLOW CREEK	550315	$1,565,000
2030	14	GRAHAM	BP14-R026	HFBD	Replacement	SR1275	TULULA CREEK	370020	$1,820,000
2030	14	HENDERSON	BP14-R015	HFBD	Replacement	SR1108	ROCK CREEK	440100	$2,175,000
2030	14	HENDERSON	BP14-R028	HFBD	Replacement	SR1006	DEVILS FORK CREEK	440048	$2,250,000