

**CONSTRUCTED RIFFLE:**

**Description**

This work consists of the construction and maintenance of physical barriers placed in and along the stream at locations designated on the plans to provide grade control.

The quantity of constructed riffles to be installed will be affected by the actual conditions that occur during the construction of the project. The quantity of constructed riffles may be increased, decreased, or eliminated entirely as directed. Such variations in quantity will not be considered as alterations in the details of construction or a change in the character of the work.

**Materials**

<b>Item</b>	<b>Section</b>
No. ___ Stone	Section ___
Plain Riprap, Class ___	Section 1042

**Construction Methods**

Constructed riffles shall be constructed according to the Constructed Riffle Detail shown on the plans or as directed.

**Measurement and Payment**

No. \_\_\_ Stone will be measured and paid as the actual number of tons that have been incorporated into the work, or have been delivered to and stockpiled on the project as directed. No. \_\_\_ stone that has been stockpiled will not be measured a second time.

Riprap, Class \_\_\_ will be measured and paid for in accordance with Subarticles 876-5(B) and 876-6(B) of the *Standard Specifications*.

Such price and payment will be full compensation for all work covered by this section, including, but not limited to, furnishing all materials, labor, equipment and incidentals necessary to construct the constructed riffles.

Payment will be made under:

<b>Pay Item</b>	<b>Pay Unit</b>
No. ___ Stone	Ton (Metric Ton)