

**CONSTRUCTED RIFFLE:**

**Description**

This work consists of the construction and maintenance of physical barriers placed in and along the stream at locations designated on the plans to provide grade control.

The quantity of constructed riffles to be installed will be affected by the actual conditions that occur during the construction of the project. The quantity of constructed riffles may be increased, decreased, or eliminated entirely as directed. Such variations in quantity will not be considered as alterations in the details of construction or a change in the character of the work.

**Materials**

Refer to Division 10 of NCDOT 2018 Standard Specifications for Roads and Structures

<b>Item</b>	<b>Section</b>
No. [ ] Stone	Section 1005
Riprap, Class [ ]	Section 1042

**Construction Methods**

Constructed riffles shall be constructed according to the Constructed Riffle Detail shown on the plans or as directed.

**Measurement and Payment**

No. [ ] *Stone* will be measured and paid for as provided in the Structure Stone Special Provision.

*Riprap, Class [ ]* will be measured and paid for as provided in the Structure Stone Special Provision.

Such price and payment will be full compensation for all work covered by this section, including, but not limited to, furnishing all materials, labor, equipment and incidentals necessary to construct the constructed riffles.