

# ANNUAL REPORT FOR 2003



**Roanoke Island Mitigation Site**  
**Dare County**  
**Project No. 8.1052501**  
**TIP No. K-4003**



Prepared By:  
Office of Natural Environment & Roadside Environmental Unit  
North Carolina Department of Transportation  
December 2003

# TABLE OF CONTENTS

<b>SUMMARY.....</b>	<b>1</b>
<b>1.0 INTRODUCTION.....</b>	<b>2</b>
1.1 Project Description.....	2
1.2 Purpose.....	2
1.3 Project History.....	3
1.4 Debit Ledger.....	3
<b>2.0 HYDROLOGY.....</b>	<b>5</b>
2.1 Success Criteria.....	5
2.2 Hydrologic Description.....	5
2.3 Results of Hydrologic Monitoring.....	8
2.3.1 Site Data.....	8
2.3.2 Climatic Data.....	11
2.4 Conclusions.....	11
<b>3.0 VEGETATION.....</b>	<b>13</b>
3.1 Success Criteria.....	13
3.2 Description of Species.....	13
3.3 Results of Vegetation Monitoring.....	13
3.4 Conclusions.....	14
<b>4.0 OVERALL CONCLUSIONS/ RECOMMENDATIONS.....</b>	<b>14</b>

## **TABLES**

TABLE 1 – 2003 HYDROLOGIC MONITORING RESULTS.....	8
TABLE 2 – 2003 VEGETATIVE MONITORING RESULTS .....	13

## **FIGURES**

FIGURE 1 – SITE LOCATION MAP.....	4
FIGURE 2 – MONITORING GAUGE LOCATION MAP- NORTH TRACT.....	6
FIGURE 3 – MONITORING GAUGE LOCATION MAP- SOUTH TRACT.....	7
FIGURE 4 – 2003 HYDROLOGIC MONITORING RESULTS- NORTH .....	9
FIGURE 5 – 2003 HYDROLOGIC MONITORING RESULTS- SOUTH.....	10
FIGURE 6 – 30-70 PERCENTILE GRAPH.....	12

## **APPENDICES**

APPENDIX A – GAUGE DATA GRAPHS

APPENDIX B – SITE PHOTOS/ PHOTO AND VEGETATION PLOT  
LOCATIONS

## **SUMMARY**

The following report summarizes the monitoring activities that have occurred in the past year at the Roanoke Island Mitigation Site. The site was constructed to serve as mitigation for the Roanoke Island Visitor Center/ Rest Area; approximately 1.77 acres of impacts are mitigated for onsite and the remaining 1.36 acres of preservation were debited from the Mashoes Road Mitigation Site. The Roanoke Island Site was constructed in 2002 and this report details the second year of monitoring activities following construction.

Data from the second year of hydrologic monitoring indicates that the site is, at minimum, meeting jurisdictional success by showing saturation within 12 inches of the surface for at least 12.5% of the growing season. However, the gauges in the constructed areas on the south tract are within 20% of the saturation period for only half of their respective reference gauges. The saturation period is longer in the constructed zone (not less than 87% of the growing season) than at two of the four reference area gauges. Both of the gauges on the north tract are within 20% of the saturation period for the reference gauge in that area.

Vegetation monitoring yielded only 168 trees per acre, which is below the minimum requirement (320 trees per acre for three years). NCDOT will replant the site and continue to monitor for vegetation in 2004.

NCDOT will continue to monitor vegetation and hydrology at the Roanoke Island Mitigation Site.

## **1.0 INTRODUCTION**

### **1.1 Project Description**

The Roanoke Island Site serves as onsite mitigation for the Roanoke Island Visitor Center/Rest Area, located adjacent to the new US 64-264 Manteo Bypass. The site is divided into two tracts; the “south” tract is on the same property as the Visitor Center and the “north” tract is located approximately 600 feet north of the Visitor Center (Figure 1). The mitigation is associated with Project 8.1052501, TIP Numbers K-4003 and R-2551.

The site is designed to provide 0.11 acres of restoration (1:1) and 1.66 acres of creation (1:1) of Estuarine Fringe wetlands. The site also includes 1.29 acres (5:1) of estuarine preservation. In addition, approximately 1,004 feet of riparian buffer was planted with the same vegetation mix as that used in the wetland zones. The width of the buffer zones varies between 9 and 65 feet based on NCDOT property limits. The construction plan for the wetland sites involved grading the former borrow pit areas to meet the elevations of adjacent jurisdictional wetlands.

### **1.2 Purpose**

In order to demonstrate successful mitigation, hydrologic and vegetative monitoring must be conducted for a minimum of five years or until success criteria are fulfilled. Success criteria are based on federal guidelines for wetland mitigation and are stipulated in the “Roanoke Island Visitor Center/ Rest Area Mitigation Plan” dated May 2001 (revised July 2001). These guidelines stipulate criteria for both hydrologic conditions and vegetation survival. The following report details the results of hydrologic and vegetative monitoring during 2003 at the Roanoke Island Mitigation Site.

Activities in 2003 reflect the second year of monitoring at the mitigation site. Included in this report are analyses of both hydrologic and vegetative monitoring results, as well as local climate conditions throughout the growing season.

### 1.3 Project History

March 2002	Construction Completed
March 2002	Monitoring Gauges Installed
March 2002	Site Planted
March- November 2002	Hydrologic Monitoring (Year 1)
June 2002	Vegetation Monitoring (Year 1)
March- November 2003	Hydrologic Monitoring (Year 2)
September 2003	Vegetation Monitoring (Year 2)

### 1.4 Debit Ledger

The Roanoke Island Mitigation Site serves entirely as mitigation for the Roanoke Island Visitor Center/ Rest Area. Approximately 1.36 acres of additional preservation area has been debited from the Mashoes Road Mitigation Site to account for all of the wetland impacts caused by construction.



## **2.0 HYDROLOGY**

### **2.1 Success Criteria**

While a constructed site must typically meet jurisdictional criteria of inundation or saturation within 12 inches of the surface for at least 12.5% of the growing season, NCDOT and consulting agencies agreed that other criteria may be the best indicator of hydrologic success on this particular site. In accordance with the guidelines set forth by the approved mitigation plans, hydrologic success is dictated by the hydrologic condition of the reference wetlands adjacent to the sites. Monitoring gauges are located in both the constructed and reference areas. The site is considered a hydrologic success if the hydrologic frequency, duration and depth are within 20% of its respective reference wetland.

The growing season in Dare County begins March 13 and ends November 25. The dates correspond to a 50% probability that temperatures will drop to 28° F or lower after March 13 and before November 25.<sup>1</sup> The growing season is 258 days; therefore the optimum duration for wetland hydrology is 32 days. While the monitoring gauges record ground/surface water levels throughout the year, special attention is placed on water levels during the 258-day growing season. In addition, local rainfall totals are monitored to ensure that the site is functioning in normal climatic conditions.

### **2.2 Hydrologic Description**

The site was constructed by grading existing fill material down to meet the elevations of the existing reference wetlands. The removed fill material is associated with borrow pit/spoil basins that were previously onsite. Eleven monitoring gauges were installed on the site in order to monitor the new hydrologic conditions. Three gauges are located on the north tract and eight gauges are located on the south tract. Of these, one gauge is located within the north tract reference wetland, while four gauges are located within reference areas in the south tract. The success of the site is determined by comparing the groundwater levels in the reference areas with those in the constructed zones.

Site rainfall is monitored with a rainfall gauge located onsite. In addition, the recorded data is compared to rainfall data at the Manteo Airport gauge in order to check the accuracy of the measured data. The Manteo data was provided by the NC State Climate Office. Figures 2 and 3 are monitoring gauge maps of the north and south tracts, respectively.

---

<sup>1</sup> Natural Resources Conservation Service, Soil Survey of Dare County, North Carolina, p.69.

Roanoke Island  
Mitigation Site  
North Tract





Figure 2. Monitoring Gauge Location Map- North Tract



**Figure 3.** Monitoring Gauge Location Map – South Tract

## 2.3 Results of Hydrologic Monitoring

### 2.3.1 Site Data

Table 1 is a summary of the hydrologic monitoring results for both the north and south tracts.

The mitigation plan states that the hydrologic conditions of the constructed areas must be within 20% of those in the reference areas.

**Table 1. 2003 Hydrologic Monitoring Results (March 13 – November 25)**

Monitoring Gauge	< 5%	5 - 8%	8 – 12.5%	> 12.5%	Actual Consecutive %	Dates Meeting Success
<b>NORTH TRACT</b>						
RINT-1+				×	100	March 13-Nov 25
RINT-2+				×	92.2	April 2-Nov 25
RINT-3 (ref)+				×	87.2	March 13-Oct 23
<b>SOUTH TRACT</b>						
RIST-1+				×	100	March 13-Nov 25
RIST-2 (ref)+				×	38.0	March 17-May 17 May 19-Aug 24
RIST-3 (ref)+				×	100	March 13-Nov 25
RIST-4+				×	87.2	March 13-Oct 23
RIST-5 (ref)+				×	100	March 13-Nov 25
RIST-6+				×	92.2	April 2-Nov 25
RIST-7 (ref)+				×	41.5	March 13-June 27 June 29-Aug 24
RIST-8+				×	86.0	March 13-Oct 20

Notes: "RINT" denotes gauges on the northern tract.


"RIST" denotes gauges on the southern tract.

"ref" denotes gauges in preservation areas of the site, used as reference wetlands.

+ Gauge met the success criterion during an average rainfall month (March, June, August, and October)

Figures 4 and 5 are representations of the hydrologic monitoring results. Each gauge is highlighted in blue, as each indicated saturation for more than 12.5% of the growing season.

Appendix A contains a plot of the groundwater depth for each monitoring gauge. While success of the site is based on reference wetlands and not the percentage of the growing season that the groundwater is within 12 inches of the surface, the 12-inch line is provided as a comparison. The number of days that the water level was above this line is also provided on each graph. Precipitation events, as recorded by the onsite rain gauge, are included on each graph as bars. A comparison of the rainfall data collected onsite with that recorded at the Manteo Airport gauge revealed that the onsite gauge collected accurate data.



**North Tract**


**Figure 4. 2003 Hydrologic Monitoring Results**




Hydrology Results

- < 5%
- 5 - 8%
- 8 - 12%
- >12.5%

- ⊕ Rain Gauge
- Surface Gauge





**Figure 5. 2003 Hydrologic Monitoring Results**



### **2.3.2 Climatic Data**

Figure 6 represents an evaluation of the local climate in comparison with historical data in order to determine whether 2003 was “average” in terms of climate conditions. The two lines represent the 30<sup>th</sup> and 70<sup>th</sup> percentiles of monthly precipitation for Manteo, NC. The bars are monthly rainfall totals for 2002 and 2003. The onsite rain gauge at Roanoke Island was used for the 30-70 percentile graph for the months of September-November. The historical data was collected from the State Climate Office of North Carolina.


For the 2003-year, January and November experienced below average rainfall. The months of December (02’), March, June, August, and October all recorded average rainfall for the site. November (02’), February, April, May, July, and September experienced above average rainfall. The rainfall data from the onsite rain gauge was used for the months of September-November. Overall, 2003 experienced an average to above average rainfall year.

### **2.4 Conclusions**

The 2003-year represents the second complete year of monitoring for the Roanoke Island Mitigation Site. The hydrologic data indicates that the site is, at minimum, meeting jurisdictional success by showing saturation within 12 inches of the surface for at least 12.5% of the growing season. However, the gauges in the constructed areas on the south tract are within 20% of the saturation period for only half of their respective reference gauges. The saturation period is longer in the constructed zone (not less than 87% of the growing season) than at two of the four reference area gauges. Both of the gauges on the north tract are within 20% of the saturation period for the reference gauge in that area.

NCDOT recommends that hydrologic monitoring continue on the Roanoke Island Mitigation Site.

**Figure 6. 30-70 Percentile Graph: Manteo, NC**



### 3.0 VEGETATION: ROANOKE ISLAND VISITOR CENTER (YEAR 2 MONITORING)

#### 3.1 Success Criteria

Success criteria states that there must be a minimum of 320 trees per acre living for at least three consecutive years. A minimum of 290 trees per acre must be living at year 4 and a minimum of 260 trees per acre living at year 5.

#### 3.2 Description of Species

The following tree species were planted in the Wetland Restoration Area:

*Taxodium distichum*, Baldcypress

*Myrica cerifera*, Wax Myrtle

*Persea palustris*, Swamp Redbay

*Nyssa sylvatica* var. *biflora*, Swamp Blackgum

*Gordonia lasianthus*, Loblolly Bay

#### 3.3 Results of Vegetation Monitoring

TABLE 2 : 2003 VEGETATIVE MONITORING RESULTS

Plot #	Baldcypress	Wax Myrtle	Swamp Redbay	Loblolly Bay	Swamp Blackgum	Total (2 year)	Total (at planting)	Density (Trees/Acre)
1	14					14	39	244
2	2	2	1			5	40	85
3	6	13				19	42	308
4	1	1				2	40	34
<b>Average Tree Density</b>								<b>168</b>

**Site Notes:** Other species noted: *Juncus* sp., cattail, *Scripus* sp., *Pluchea* sp., and *Baccharis halimifolia*. Standing water was noted throughout site.

### **3.4 Conclusions**

Approximately 1.8 acres of this site (wetland restoration and creation areas) were planted in March 2002. The 2003 vegetation monitoring revealed an average density of 168 trees per acre, which is below the 320 trees per acre minimum requirement.

NCDOT will replant the site and continue vegetation monitoring at the Roanoke Island Mitigation Site.

## **4.0 OVERALL CONCLUSIONS/ RECOMMENDATIONS**

The 2003-year represents the second year of hydrologic and vegetation monitoring following construction. The hydrologic data indicates that the site is, at minimum, meeting jurisdictional success by showing saturation within 12 inches of the surface for at least 12.5% of the growing season. However, the gauges in the constructed areas on the south tract are within 20% of the saturation period for only half of their respective reference gauges. The saturation period is longer in the constructed zone (not less than 87% of the growing season) than at two of the four reference area gauges. Both of the gauges on the north tract are within 20% of the saturation period for the reference gauge in that area.

Vegetation monitoring yielded an average tree density of 168 trees per acre over the four plots. The site did not meet vegetation criteria for the 2003-year. NCDOT will replant the site and continue to monitor vegetation success.

NCDOT will continue to monitor the Roanoke Island Mitigation Site for hydrology and vegetation.

**APPENDIX A**

**GAUGE DATA GRAPHS**

## **APPENDIX B**

### **SITE PHOTOS/ PHOTO AND VEGETATION PLOT LOCATIONS**

# Roanoke Island Visitor Center



Photo 1



Photo 2



Photo 3



Photo 4



Photo 5



Photo 6



Photo 7

# ROANOKE ISLAND VISITOR CENTER

## PHOTO AND VEGETATION PLOT LOCATIONS

