



Something Doesn't Look Quite Right!



Mid Atlantic

What's Up With *That*?



Hitting the Life Alert button is not going to work!

Background

- ▶ Building ~50% complete
- ▶ Has my crane been moved?
- ▶ One side of the structure settling



The Players!

- ▶ Owner
- ▶ Attorneys
- ▶ Lenders
- ▶ Investors
- ▶ Insurance Cos.
- ▶ NC Brownfields Program
- ▶ Underground Injection Control Program
- ▶ Hazardous Waste Program
- ▶ Geotechnical Engineers
- ▶ City of Raleigh
- ▶ Mid-Atlantic



The Solution

- ▶ Install over 1,200 micro-piles to shore up the structure
- ▶ Conduct the work concurrently with on-going construction
- ▶ Efficiently manage the environmental media



Environmental Challenges

- ▶ Drilling through VIMs system
- ▶ Generation of hazardous waste?
 - ▶ Drilling water
 - ▶ Drilling mud/sludge
- ▶ Disposal of IDW
- ▶ Repair of VIMs system
- ▶ \$\$\$\$\$\$\$\$\$\$\$\$\$\$\$\$\$



Environmental Solutions

- ▶ Can IDW be classified as non-hazardous?
- ▶ Find ways to minimize waste generation
- ▶ Find cheaper disposal options for IDW
- ▶ Minimize disruption to construction

Waste Minimization

- ▶ Identify 12 adjacent borings (one shift, one rig)
- ▶ Reuse/recycle the mud/water from this set of borings does not constitute cross contamination or introducing contamination
- ▶ Received NCBP and NCDEQ approval



The Process

- ▶ Drilling mud pumped through flocculent system or silt bag system.
- ▶ Water was then pumped to a 5,000-gallon tank.
- ▶ Driller pumped water from tank to rig to complete the recycling loop.



The Process

- ▶ Silt bags and mud were characterized and transported off site for disposal
- ▶ Water was disposed of via a POTW permit and off-site



What About the VI Issue?

- ▶ How do we ensure the system is salvageable?
 - ▶ Smoke tests
 - ▶ Pressure testing
 - ▶ Resized blowers
- ▶ Post-construction & Pre-occupancy testing



Post Occupancy

- ▶ Sampling plans approved by NCBP
- ▶ Sub-slab and indoor air (canisters and radiellos)
- ▶ Flow and pressure differential readings



Results

- ▶ Amount of IDW required disposal reduced by ~75%
- ▶ Significant reduction in costs for disposing of water
- ▶ Minimal disruption of micro-pile installation and construction process

Secrets to Success

- ▶ Effective Communication
- ▶ Think outside the box (innovation)
- ▶ Help regulators find a way to say “yes”



Questions

