



## Deep Foundation Installation Standard of Practice

#### > Typical construction technique

 Preinstall the pilling or sleeves to drive piles through and then construct the wall by placing reinforcement and fill around the piles / sleeves







## Uncased Drilled Shafts close to MSE Wall Face After Wall Construction

#### Advantages

- Speed of wall construction fill and reinforcement around piles / sleeves
- Proper compaction around the piles / sleeve
- Eliminate controls and construction techniques to hold sleeves in a vertical position during fill placement and compaction

















Drilling Operation



	Detailing at Modular Block Face							
Bore Hole Location	Face Block Treatment	Geogrid Details						
1	Core fill, #3 horizontal rebar in all block courses. Masonry glue on top 5 block courses	Geogrid Precut around drilled shaft						
2	Grout, #3 horizontal and vertical rebar on all block courses	Geogrid Precut around drilled shaft						
3	Core fill and #3 horizontal rebar in all block courses except grout and #3 horizontal rebar on top 5 courses.	Geogrid Precut around drilled shaft						
4	Core fill and #3 horizontal rebar in all block courses except grout and #3 horizontal rebar on top 5 courses.	Geogrid Precut around drilled shaft						
5	Core fill, #3 horizontal rebar in all block courses. Masonry glue on top 5 block courses	Geogrid Precut around drilled shaft						
6	Core fill and #3 horizontal rebar in all block courses except grout and #3 horizontal rebar on top 5 courses.	No Geogrid Precut						
7	Core fill, #3 horizontal rebar and masonry glue on top 5 block courses only	No Geogrid Precut						



# Detailing at Modular Block Face





# **Observation and Measurements**

Offset from MSE Leveling Pad								
Bore Hole Location	Block Course above Leveling Pad Pre-Drilling			Block Course above Leveling Pad Post Drilling				
	1	7	12	1	7	12		
1	4"	5-4/8"	6-1/8"	4"	5-4/8"	6-1/8"		
2	4"	4-6/8"	5-3/8"					
3	4"	4-7/8"	5-4/8"					
4	4"	5-3/8"	7"	4"	5-3/8"	7"		
5	4"	4-1/2"	5-4/8"	4"	4-3/4"	5-3/8"		
6	4"	6"	7-4/8"	4"	6"	7-4/8"		
7	4"	4-2/8"	7-4/8"	4"	4-2/8"	7-4/8"		

### **Observation and Measurements**

- No measurable or very small movement even with the least combination of facing treatment and geogrid detailing (No grout, no geogrid precut)
- Geogrid layers at all bore hole locations cleanly sheared and no evidence of being pulled by auger
- Drilled hole remains open with no sign of collapse in Sandy backfill – Effect of Soil-Geogrid Composite



## SUMMARY / CONCLUSION

- Feasible to perform drilled shaft installation without casing at close proximity to the wall facing after geogrid reinforced MSE wall construction
- Drilling operations can be performed as close as 18 inches from the MSE wall facing with minimal remedial block facing treatments at the core
- This method of construction allows proper compaction of the backfill in the tight space between drilled shaft and wall facing, and reduces the impact of downdrag and therefore cost of the deep foundation structure
- It is acceptable to drill through the HDPE geogrid at close proximity to the wall facing without precutting the geogrid
- The compacted composite mass of the planar geogrid reinforced zone allowed the drilled hole to stay open and geogrid to be drilled through without measurable movement to the wall facing

