

2013 Geo<sup>3</sup>T<sup>2</sup> Conference

# Crosshole Sonic Logging: A 10 Year Perspective


**Kyle Murrell, PE**

**S&ME, Inc.**


**Charleston, SC**



# Survey of State DOT Practice: Use of NDE for Drilled Shafts



# CSL Equipment & Procedure




# Procedure – cont.

Pull  
Probes  
From  
Bottom  
To Top

Put probes  
in bottom  
of tubes.

Top view of pile with  
4 access tubes



Fill Tubes  
with water

*Transmit*


*Receive*

**Stress Waves, emitted  
in one tube are received  
in another one if concrete  
quality is satisfactory**

Slide courtesy of PDI



# Data Processing




# Limitations

- Cannot Evaluate Integrity Outside of the Reinforcing Cage
- Cannot be performed soon after concrete placement (typically test no sooner than 3 days)




Testing Coverage



— GGL Shaft Tested — GGL Cover Tested — CSL Shaft Tested —■— CSL Cover Tested

# SCDOT Experience - Background

- SCDOT On-call Foundation Testing Contract
- CSL Since 2000
- Responsible for  $\approx \frac{1}{2}$  testing





# On-Call Consultant Directive

1. Perform CSL on all SCDOT Shafts
2. Identify Anomalies

# Anomaly Identification

- **Good:**
  - Velocity decrease of ~~10%~~<sup>20%</sup> or less
  - Constant energy
- ~~**Questionable:**
  - Velocity decrease of 10% to 20%~~
- **Poor/Defect:**
  - Velocity decrease  $>20\%$
  - Drop in energy or loss of signal

# On-Call Consultant Directive – cont.


1. Perform CSL on all SCDOT Shafts
2. Identify Anomalies
3. Review Drilled Shaft Inspection Reports
4. Provide Recommendation
  - “Good” Shaft – Accept
  - “Poor/Defective” Shaft – Additional Evaluation Required

# Additional Evaluation

- Re-evaluate design requirements (wrt anomaly size, location, magnitude, etc.)
  - Individual Shaft Loading
  - End Bearing Requirement
  - Lateral Loading/Response
- Chipping/Sounding
- Coring




# Example – Hellers Creek (2005)



- Dry Construction
- Concrete Placed by Tremie
- CSL Performed 9 Days After Concrete Placement
- First of Four Shafts

# Hellers Creek – Cont.




# Hellers Creek – Cont.

- Classification – “Poor/Defective”
- Recommendation - Coring

TUBE PAIR	PRESENCE OF ANOMALIES?	ANOMALY DEPTH (ft)	MAXIMUM FIRST ARRIVAL TIME DELAY (%)	INCREMENT RATING
1-2	YES	54 – 57½	>100	P/D
2-3	YES	54 – 57½	>100	P/D
3-4	YES	55 – 57½	75	P/D
4-5	YES	56 – 57½	>100	P/D
1-5	YES	54½ - 57½	>100	P/D
1-4	YES	54½ - 57½	41	P/D
1-3	YES	54 – 57½	>100	P/D
2-4	YES	54½ - 57½	>100	P/D
2-5	YES	55 -57½	>100	P/D
3-5	YES	55 – 57½	>100	P/D

# Hellers Creek – cont.

- Cores from 54' to 60'  
(signal loss from 54' to 58'  
– no CSL below 58')
- No Irregularities Found






# SCDOT CSL Testing Statistics (2000 – 2011)


- Number of Projects 66
- Number of Shafts 850
- Number of Contractors 12
  
- Number of “Wet” Shafts 658
- Number of “Dry” Shafts 192
  
- Projects in Soil 24 (469 shafts)
- Projects in Rock 42 (381 shafts)

# Project Size Distribution




**More than ½ have 8 shafts or less**

# Diameter Distribution



# Distribution by Length






# CSL Testing Statistics - Anomalies

- Number of Projects 66
- Number of Shafts 850
- Shafts with Anomalies 316 (37%)
- Projects with Anomalies 56 (85%)
- Projects with No Anomalies 10 (15%)
- No. of Shafts on No-Anomaly Projects 43 (5%)



# Anomaly Locations




# Comparison with Other Studies

Jones & Wu, Geotechnology, Inc. Missouri and Kansas

“Experiences with Cross-hole Sonic Logging and Concrete Coring for Verification of Drilled Shaft Integrity”, ADSC GEO<sup>3</sup> Construction Quality Assurance/Quality Control Technical Conference, Dallas Nov 2005



# Contractor Performance




# CSL Testing Statistics – Cont.

- Number of “Good” Shafts 730
- Percentage of “Good” Shafts **86%**
  
- Number of “Poor/Defective Shafts 120
- Percentage of “Poor/Defective” Shafts **14%**
- Projects with coring 12+
  - Core Findings
    - Bleed water features
    - Minor to significant segregation
    - Lumber (missing 4x4)
- **Shafts Requiring Remediation** **2**

# Case Histories & Examples


- Top Anomalies
  - 6-ft Diam Shaft in River
  - Mudline is 12 to 18 ft below top of shaft
  - Casing is 30 ft below top of shaft
  - Anomalies in the top of every shaft

# Edge Finder





# Aggressive Manual Picks



# Explanations?

- De-bonding (SCDOT access tubes are steel)
- Flowing water created large thermal gradients leading to micro-cracking during curing
- Bleed water causing flow paths through concrete
  - Supported by coring



# Subsequent Information

- Different Project – Same Problem













Vertical features

03/02/2005

# Consequences of Bleed Water Features



Wavespeed at 97.39 ft = 13,351 fps




Possible interpretations at 99.55  
and 99.88 ft:


*No signal or*

1) Wavespeed of 8,564 (36%  
reduction)

2) Wavespeed of 4,647 (65%  
reduction)



# Top Anomaly





# Top Anomaly – continued




# Case Histories & Examples


## Bottom Anomalies

- From the inspector's logs
  - 4.5 ft diameter, 30 ft long shaft (approx 18 cy vol)
  - Permanent casing with rock socket below
  - No drilling fluid
  - Concrete placed via pump line
  - No problems noted



Bent 3 Shaft 2 -- Tubes 1 - 2



Bent 3 Shaft 2 -- Tubes 2 - 3



Bent 3 Shaft 2 -- Tubes 3 - 4




Tube Spacing :	26.00	inches
Signal Gain :	1	
Threshold :	1.50	
At Depth of	29.48	ft
Velocity	15600	ft/sec
First Arrival Time	202	us
Signal Energy	84.81	V-us






**20' to 25': Gravel or No Recovery**

Bent 3 Shaft 2 -- Tubes 1 - 2




Water level in shaft excavation

Bent 3 Shaft 2 -- Tubes 2 - 3





Bent 3 Shaft 2 -- Tubes 3 - 4



"Tremie" Positions

# Middle Anomaly







# Middle Anomaly – cont.



# Middle Anomaly – cont.





# Summary – Major Delay/No Signal

BAD  
↑



↓  
OK



# Summary – SCDOT Experience

- Concrete quality, not necking or soil intrusion, is the cause of anomalies
  - Bleed water, segregation, contamination?
- Vast majority of anomalies  $\neq$  defect
- $\approx 90\%$  of anomalies are found near the top or the bottom
- An anomaly free project is very rare
- Research should address concrete issues