

**STANDARD ROADWAY PAY ITEMS & EARTHWORK QUANTITY ADJUSTMENTS**

(For 2012 Standard Specifications – 8/19/16)

<b>Pay Item No.</b>	<b>Pay Item/Quantity Adjustment</b>	<b>Pay Unit/ %</b>	<b>Section No./ Special Provision (SP)</b>	<b>Section/Provision Title</b>
0015000000-N	Sealing Abandoned Wells	EA	205	Sealing Abandoned Wells
0084000000-E	Wick Drains	LF	SP	Wick Drains
0091000000-E	Augering for Wick Drains	LF	SP	Wick Drains
0241000000-E	Geotextile for Wick Drains	SY	SP	Wick Drains
0255000000-E	Select Material for Wick Drains	TON	SP	Wick Drains
0098000000-E	Pre-splitting of Rock	SY	SP	Blasting
0022000000-E	Unclassified Excavation	CY	SP	Surcharges and Waiting Periods, Embankment Settlement Gauges
0036000000-E	Undercut Excavation	CY	225	Roadway Excavation
0106000000-E	Borrow Excavation	CY	SP	Surcharges and Waiting Periods, Embankment Settlement Gauges
0127000000-N	Embankment Settlement Gauges	EA	SP	Embankment Settlement Gauges
0194000000-E	Select Granular Material, Class III	CY	SP	Select Granular Material
0195000000-E	Select Granular Material	CY	265	Select Granular Material
0196000000-E	Geotextile for Soil Stabilization	SY	270	Geotextile for Soil Stabilization
0220000000-E	Rock Embankments	TON	SP	Rock Embankments
0222000000-E	Geotextile for Rock Embankments	SY	SP	Rock Embankments
1077000000-E	#57 Stone	TON	SP	Rock Embankments
0223000000-E	Rock Plating	SY	275	Rock Plating
0225000000-E	Reinforced Soil Slopes	SY	SP	Reinforced Soil Slopes
6036000000-E	Matting for Erosion Control	SY	1631	Rolled Erosion Control Products
6037000000-E	Coir Fiber Mat	SY	SP	Coir Fiber Mat
6141000000-E	Geocells	SY	SP	Cellular Confinement Systems
6135000000-E	Compost Blanket	Acre	SP	Compost Blanket
0570000000-E	6" CS Pipe Culverts, 0.064" Thick (Spring Box)	LF	SP	Springs and Seeps
2187000000-E	Seeps	SY	SP	Springs and Seeps
1099500000-E	Shallow Undercut	CY	505	Aggregate Subgrade
1099700000-E	Class IV Subgrade Stabilization	TON	505	Aggregate Subgrade
1110000000-E	Stabilizer Aggregate	TON	510	Aggregate Stabilization
0255000000-E	Class IV Aggregate Stabilization	TON	SP	Class IV Aggregate Stabilization
1115000000-E	Geotextile for Pavement Stabilization	SY	SP	Geotextile for Pavement Stabilization

**STANDARD ROADWAY PAY ITEMS & EARTHWORK QUANTITY ADJUSTMENTS**

(For 2012 Standard Specifications – 8/19/16)

<b>Pay Item No.</b>	<b>Pay Item/Quantity Adjustment</b>	<b>Pay Unit/ %</b>	<b>Section No./ Special Provision (SP)</b>	<b>Section/Provision Title</b>
2044000000-E	6" Perforated Subdrain Pipe	LF	815	Subsurface Drainage
2143000000-E	Blotting Sand	TON	818	Blotting Sand
3628000000-E	Rip Rap, Class I	TON	876	Rip Rap
3635000000-E	Rip Rap, Class II	TON	876	Rip Rap
3642000000-E	Rip Rap, Class A	TON	SP, 876	Rock Embankments, Rip Rap
3649000000-E	Rip Rap, Class B	TON	SP, 876	Rock Embankments, Rip Rap
3656000000-E	Geotextile for Drainage	SY	876	Rip Rap
0000950000-E	Slab Jacking at _____	SF	SP	Slab Jacking
N/A	Loss Due to Clearing & Grubbing	CY	200	Clearing and Grubbing
N/A	Unclassified Excavation - Unsuitable Waste	CY / %	225	Roadway Excavation
N/A	Unclassified Excavation - Acceptable Degradable Rock	CY / %	225	Roadway Excavation
N/A	Unclassified Excavation - Acceptable, but not to be used in top 3 ft of embankment or backfill	CY / %	225	Roadway Excavation
N/A	Rock Swell Factor	%	235	Embankments
N/A	Shrinkage Factor	%	235	Embankments
N/A	Lime-Treated Soil	%	501	Lime-Treated Soil
N/A	Soil-Cement Base	%	542	Soil-Cement Base

**STANDARD STRUCTURE PAY ITEMS**  
(For 2012 Standard Specifications – 4/29/13)

<b>Pay Item No.</b>	<b>Pay Item</b>	<b>Pay Unit/ %</b>	<b>Section No./ Special Provision (SP)</b>	<b>Section/Provision Title</b>
Varies	___ Dia. Drilled Piers Not in Soil	LF	411	Drilled Piers
8113000000-N	SID Inspections	EA	411	Drilled Piers
8114000000-N	SPT Testing	EA	411	Drilled Piers
8115000000-N	CSL Testing	EA	411	Drilled Piers
8096000000-E	Pile Excavation in Soil	LF	450	Piles
8097000000-E	Pile Excavation Not in Soil	LF	450	Piles
8112730000-N	PDA Testing	EA	450	Piles
Varies	___ Prestressed Concrete Piles	LF	450	Piles
Varies	___ Steel Piles	LF	450	Piles
Varies	___ Galvanized Steel Piles	LF	450	Piles
8392500000-E	Predrilling for Piles	LF	450	Piles
8393000000-N	Pile Redrives	EA	450	Piles
8801000000-E	MSE Retaining Wall No. ****	SF	SP	Mechanically Stabilized Earth Retaining Walls
8802010000-E	Soil Nail Retaining Walls	SF	SP	Soil Nail Retaining Walls
8802015100-N	Soil Nail Verification Tests	EA	SP	Soil Nail Retaining Walls
8802015110-N	Soil Nail Proof Tests	EA	SP	Soil Nail Retaining Walls
8802014000-E	Soldier Pile Retaining Walls	SF	SP	Soldier Pile Retaining Walls
8802016000-E	Anchored Retaining Walls	SF	SP	Anchored Retaining Walls
8802030000-E	Segmental Gravity Retaining Walls	SF	SP	Segmental Gravity Retaining Walls
8802031000-E	Precast Gravity Retaining Walls	SF	SP	Precast Gravity Retaining Walls
8802040000-E	CIP Gravity Retaining Walls	SF	SP	Cast-In-Place Gravity Retaining Walls
8839000000-E	Concrete Barrier Rail with Moment Slab	LF	SP	Concrete Barrier Rail with Moment Slab