

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION

REBAR INDIRECT BUTT JOINT WITH SPLICE ANGLE

WELDING PROCEDURE SPECIFICATION (WPS) AWS D1.4

Specifications, Codes & Supporting Document:

NCDOT Standard Specifications/AASHTO/AWS D1.4, PQR-030

Material Specifications:

ASTM A615 Grades 75, 60 & 40, ASTM A706 Grade 60; Bar size 4 to 18 Inclusive

Welding Process:

SMAW

Manual or Semi- Automatic or Automatic:

Manual

Filler Metal Specification:

AWS A5.1

Classification:

E-7018

Manufacturer:

NCDOT Approved Electrodes

Single or Multiple Pass

both

Position of Weld

Flat

Welding Current:

DC

Polarity:

Positive

Progression:

N/A

Root Treatment:

N/A

Preheat Temp:

Refer to preheat table below

Interpass:

1100° maximum

Post Heat:

N/A

Pass Num.	Electrode Size	Welding Current		Travel Speed	Position	Joint Details	
		Amperes	Volts				
All	1/8"	90-150	20-23	6-9 ipm	All	SEE ATTACHMENT	

PREHEAT TABLE	
Rebar Size	Min. Temp.
#6 or less	300°
#7 or larger	500°

COMMENTS:

Remove all coating, rust, dirt and mill scale within one inch of the area to be welded.

Pre-heat shall extend 6" in each direction beyond the joint.

Remove all slag, spatter and weld discontinuities between passes.

Check interpass temperature prior to the application of each pass.

Clean the completed weld of all debris, slag and spatter.


WPS Description

**REBAR Indirect
Butt Joint
With Splice Angle**

Written By:

Randy Dempsey, CWI/CWE, TT IV

Signature:



WPS #:

062111030


Authorized By:

Steve Walton, Metals Engineer

Revision #:

1

Signature:



Workmanship (AWS D1.4)

4.4 Quality of Welds

4.4.2 Any crack shall be unacceptable, regardless of size or location.

4.4.3 There shall be complete fusion between weld metal and base metal and between successive passes of weld.


4.4.4 All weld craters shall be filled to a cross section that meets the minimum specified weld size.

4.4.5 Welds shall be free from overlap.

4.4.6 Undercut depth greater than 1/32" in the solid section of the bar or structural member shall not be allowed.


4.4.10 The weld size shall be equal to or greater than the weld size specified. The length of weld containing this weld size shall be equal to or greater than the weld length specified. Any portion of the length, including starts or stops, that contain a smaller weld size shall not be measured in the weld length.

WPS REBAR Indirect Butt Joint with Splice Angle 062111030R1
JOINT DETAIL ATTACHMENT



weld size = 40 percent of the bar radius (min), or as directed by the plans


weld length = 2 times the bar diameter (min), or as directed by the plans




40% of Bar Radius Min

REBAR Indirect Butt Joint with Splice Angle
JOINT DETAILS

Weld Symbol definitions per AWS A2.4:2007



FIELD
WELD
SYMBOL



Flare Bevel, Both Sides
with Groove Depth, Weld
Size and Length of Weld


Illustrations for a rebar indirect butt joint with splice angle.



Joint fit-up.



Completed weld (3 passes).



A cross section was tested to verify that a 5/16" weld can be achieved with 3 passes using 1/8" E7018.



A tensile test was performed to verify that the integrity of the material was not compromised (a 500°F preheat and interpass temperature was maintained).

NCDOT MATERIALS & TESTS UNIT (STEEL SECTION)

**North Carolina Department of Transportation
Materials Tests Unit (Steel Section)
Rebar Indirect Butt Joint with Splice Angle PQR
Procedure Qualification Record No. PQR-030**

Contractor NCDOT Materials & Tests (Steel Section)
 Authorized By Steve Walton Revision No. 1
 Welder Randy Dempsey, CWI/CWE Test Date Monday, June 27, 2011

Welding Process: FCAW-G FCAW-S GMAW SMAW

PQR Joint Type Direct Butt Indirect Butt T-Joint

Test Assembly: Figure 6.5 A Figure 6.5 B Figure 6.5 C Figure 6.5 D

Position flat Groove Type flare bevel single bevel

Joint Opening 3/4" max Root Face n/a double bevel

Backing: yes no Backing Type n/a

Backgouging: yes no Backgouging Method n/a

Technique: stringers weave Groove Angle n/a

Electrical Characteristics

Current: AC DCEP DCEN

Transfer Mode (GMAW): Short-circuiting Globular Spray

Base Metal Material Specification ASTM A615 Grade 60

welded to: Material Specification ASTM A36-08/A529-05 Grade 60

Carbon Equivalent (Bar) not available Bar Size #6

Coated Bar: yes no Type of Coating n/a

Filler Metal

AWS Specification AWS A5.1 AWS Classification E-7018

Shielding

Gas: single mixture Composition n/a Flow Rate n/a

Preheat/Interpass

Preheat/Interpass Temperature (min) 300° F

Interpass Temperature (max) 1100° F

Welding Parameters

Pass Number	Electrode Diameter					Joint Detail
		Type	Amperage	IPM	Volts	
1	1/8"	E7018	115	7	29	see attachment
2-3	1/8"	E7018	110	8	29	

**North Carolina Department of Transportation
Materials Tests Unit (Steel Section)
Rebar Indirect Butt Joint with Splice Angle PQR
Procedure Qualification Record No. PQR-030 (continued)**

TEST RESULTS

Visual Examination

Test Assembly Number One

pass fail (AWS) D1.4, Clause 4.4

Comments Within tolerance of specifications.

Test Assembly Number Two

pass fail (AWS) D1.4, Clause 4.4

Comments Within tolerance of specifications.

Tensile Test

Test Assembly Number One

pass fail (AWS) D1.4, Clause 6.3.7.2

Test Assembly Number Two

pass fail (AWS) D1.4, Clause 6.3.7.2

Specimen No.	bar size	Area	Ultimate Tensile Load (lbs)	Ultimate Unit Stress (psi)	Character of Failure and Location
1	#6	0.44	47,954	108,986	approx. 3" outside the heat affected zone (see photo)

Macroetch Test

Test Assembly Number One

pass fail (AWS) D1.4, Clause 6.3.7.3

Test Assembly Number Two

pass fail (AWS) D1.4, Clause 6.3.7.3

Specimen No.	Results	Remarks
2	pass	A 5/16" weld was achieved with the application of 3 passes.

Welder's Name Randy Dempsey, CWI/CWE Welder ID No. 2659 SCW

Visual Test Conducted By Richard Maxon, CWI

Tensile Test Conducted By Dan Miller HiCams No. 543029

Macroetch Test Conducted By Richard Maxon, CWI

We certify that the statements in this record are correct and that the welds were prepared and tested in accordance with the requirements of AWS D1.4, Structural Welding Code-Reinforcing Steel.

Contractor NCDOT Materials & Tests (Steel Section)
Authorized by Steve Walton

Date Monday, June 27, 2011

Sample Status: Meets Specs

NORTH CAROLINA DEPARTMENT OF TRANSPORTATION
MATERIALS AND TESTS UNIT
1801 BLUE RIDGE RD. RALEIGH, N.C. 27607
06/28/2011
Reinforcing Steel Test

Hicams No.: 543029
Contract No.:
County: Forsyth
Date Sampled: 06/28/2011
Sampled By: Dempsey, Randy
Sampled From: Project
Contractor:
Prod./Suppl.:
Facility:
Material: Reinforcing Steel, Plain

T.I.P. No.:
Field ID: 1
Engineer:
Received: 06/28/2011

Work Order No.:
P.O./Other No.:
Reported: 06/28/2011
Test Category: Informational
Represented Qty.: 20.000 LB

Lab No.: P367530

Test No.: ASTM A615

TENSILE TESTING	
METRIC	Results
Bar Size:	6
Nominal Area, sq. in.:	0.44
Wt. Actual % of Theoretical:	
Yield Strength, P.S.I.:	65718
Total Load, lbs.:	47954
Tensile Strength, P.S.I.:	109000
Elongation (8 in.), %:	


Comments:

V. O. Cordle

V. OWEN CORDLE
PHYSICAL TEST ENGINEER

cc:

0.44
6
ASTM A615



Test Summary

Counter: 33967
Elapsed Time: 00:01:29
Heat Number:
Lab:
Procedure Name: Rebar
Start Date: 6/28/2011
Start Time: 10:57:13 AM
End Date: 6/28/2011
End Time: 10:58:42 AM
Workstation: N.C. DOT
Tested By: owen

Test Results

Area: 0.4400 in²
Peak Load: 47954 lbf
Tensile Strength: 108986 psi
Halt of Force Yield: 65718.1800 psi