



STATE OF NORTH CAROLINA
DEPARTMENT OF TRANSPORTATION

BEVERLY EAVES PERDUE
GOVERNOR

EUGENE A. CONTI, JR.
SECRETARY

DISTRIBUTION DATE November 27, 2012

MEMORANDUM TO: All Project Special Provisions Holders

FROM: Brian C. Hanks, P. E.

SUBJECT: REVISIONS TO PROJECT SPECIAL PROVISIONS

Seven Project Special Provisions (PSPs) have been moved from the Design PSP lineup to the Preservation, Rehabilitation and Repair PSP lineup and four PSPs have been added to the Design PSP lineup. The Structures Management Homepage has been updated and the Design PSPs are available at the following URL:

<https://connect.ncdot.gov/resources/Structures/Pages/Project-Special-Provisions.aspx>

The Preservation, Rehabilitation and Repair PSPs will be available online at a later date.

The following table provides information on the PSPs that were moved or added. The PSP updates are effective with the March 2013 letting.

	<u>SPECIAL PROVISION</u>	<u>EXPLANATION OF REVISION</u>
8	Repair of Bridge Decks and Approach Pavement with Latex Modified Concrete	Moved to Preservation, Rehabilitation and Repair PSP lineup.
9	Latex Modified Concrete	Moved to Preservation, Rehabilitation and Repair PSP lineup.
10	Epoxy Resin Injection	Moved to Preservation, Rehabilitation and Repair PSP lineup.
11	Epoxy Mortar Repairs	Moved to Preservation, Rehabilitation and Repair PSP lineup.
12	Shotcrete Repairs	Moved to Preservation, Rehabilitation and Repair PSP lineup.

MAILING ADDRESS:
NC DEPARTMENT OF TRANSPORTATION
STRUCTURE MANAGEMENT
1581 MAIL SERVICE CENTER
RALEIGH NC 27699-1581

TELEPHONE: 919-707-6400
FAX: 919-250-4082

WEBSITE: WWW.NCDOT.ORG

LOCATION:
CENTURY CENTER COMPLEX
BUILDING A
1000 BIRCH RIDGE DRIVE
RALEIGH NC 27610

13	Concrete Repairs	Moved to Preservation, Rehabilitation and Repair PSP lineup.
14	Cleaning and Painting Existing Bearing Plates	Moved to Preservation, Rehabilitation and Repair PSP lineup.
8	3'-0" x 2'-6" Prestressed Concrete Bent Caps	Added to lineup. Describes method of payment for standard precast prestressed bent caps.
9	3'-8" x 2'-6" Prestressed Concrete Bent Caps	Added to lineup. Describes method of payment for standard precast prestressed bent caps.
10	Placing Load on Structure Members	Added to lineup. Revised the required number of curing days in the Standard Specifications from fourteen to seven.
14	Steel Reinforced Elastomeric Bearings	Added to lineup. Requires shim plates to be held in place by internal holding pins when bearings are located in corrosive environments. Requires external holding pin repairs to be vulcanized.

BCH