



STATE OF NORTH CAROLINA  
DEPARTMENT OF TRANSPORTATION

PAT MCCRORY  
GOVERNOR

ANTHONY J. TATA  
SECRETARY

DISTRIBUTION DATE      December 12, 2013

MEMORANDUM TO:      All Project Special Provisions Holders

FROM:      Brian C. Hanks, P. E.

SUBJECT:      REVISIONS TO PROJECT SPECIAL PROVISIONS

Five Project Special Provisions (PSPs) have been revised, two have been added and one renumbered in the Design PSP lineup. Three PSPs have been added to the Preservation, Rehabilitation and Repair PSP lineup. The Structures Management Homepage has been updated and the Project Special Provisions are available at the following URL:

<https://connect.ncdot.gov/resources/Structures/Pages/Project-Special-Provisions.aspx>

The following table provides information on the PSPs that were added, revised or renumbered. The PSP updates are effective with the March 2013 letting.

	<u>DESIGN SPECIAL PROVISION</u>	<u>EXPLANATION OF REVISION</u>
4	Construction, Maintenance and Removal of Temporary Access at Station _____	Revised wording to clarify the contractor's options.
5	Construction, Maintenance and Removal of Temporary Access at Station _____	Revised wording to clarify the contractor's options.
13	Electrical Conduit System for Signals	Renumbered PSP 28.
26	Precast Reinforced Concrete Box Culvert at Station _____	Revised to require load rating as part of the design and submittal process.
27	Optional Precast Reinforced Concrete Box Culvert at Station _____	Revised to require load rating as part of the design and submittal process.

**MAILING ADDRESS:**  
NC DEPARTMENT OF TRANSPORTATION  
STRUCTURES MANAGEMENT UNIT  
1581 MAIL SERVICE CENTER  
RALEIGH NC 27699-1581

TELEPHONE: 919-707-6400  
FAX: 919-250-4082  
  
WEBSITE: [WWW.NCDOT.ORG](http://WWW.NCDOT.ORG)

**LOCATION:**  
CENTURY CENTER COMPLEX  
BUILDING A  
1000 BIRCH RIDGE DRIVE  
RALEIGH NC 27610

28	Precast Reinforced Concrete Three Sided Culvert at Station _____	New Special Provision
31	Sound Barrier Wall	Revised to allow 20' pile spacing. Maximum standard precast concrete panel length remains 15'.
36	Steel Sheet Piles	New Special Provision revising the material requirements. ASTM A572 and A690 are allowed and require galvanizing or metallizing with a seal coat. The type of coating will be specified on the contract plans.

**PRR SPECIAL PROVISION**

**EXPLANATION OF REVISION**

26	Concrete Deck Repair for Epoxy Overlay	New Special Provision
27	Epoxy Overlay System	New Special Provision
28	Epoxy Overlay System	New Special Provision

BCH